



A&J Caulking Company, Inc.

222 Main Street, Suite 121 Farmington, CT 06032 860-404-5551 Fax 800-859-9297

PROPOSAL

October 5, 2020

John Mercier
Director of Operations, RSD 17

Re: Haddam-Killingworth High School
Higganum, CT

We propose to furnish and install materials as described below for the sum of \$ **33,500.00**
Thirty Three Thousand Five Hundred Dollars and .00/100.

To remove existing sealant/glazing material and recaulk the following items at Upper
gymnasium windows of South, West, North and East elevation:

1. Perimeter of glass to metal.
2. Metal sill joints.
3. Vertical and horizontal metal splice joints with Dow 123 silicone seal.

Materials: Perimeter sealant – Dowsil 795
Metal splices – Dowsil 123 silicone seal

The above price includes labor, materials and boom lift.

Note: All existing sealants have been tested for hazardous materials and been determined to be
Non- Hazardous as per report by others.

A&J Caulking Company, Inc. is a SBE Contractor

Accepted

Signed _____

Date _____

By  _____
John Scerrato, President