

REQUEST FOR QUOTATION	TROY SCHOOL DISTRICT 1140 RANKIN, TROY, MICHIGAN 48083 248-823-4052 FAX: 248-823-4077	REQUISITION
No. 9395		
DUE DATE 2-15-07 NO LATER THAN 3 p.m.		DATE 2-2-07

REQUEST FOR QUOTE – NOT AN ORDER

THIS FORM MUST BE UTILIZED WHEN RESPONDING TO THIS REQUEST
 BID ENVELOPE ENCLOSED

THE RFQ NUMBER MUST APPEAR ON ALL QUOTATIONS AND RELATED CORRESPONDENCE, THIS IS NOT AN ORDER

Quantity	DESCRIPTION	UNIT PRICE	AMOUNT
	<p>Please supply us with your bid to furnish the Troy School District with an UPGRADE TO ATHENS HIGH SCHOOL THEATRE SOUND SYSTEM per the attached specifications.</p> <p style="text-align: center;">Copies of the bid are available at: www.troy.k12.mi.us/purchasing/items_out_for_bid.htm</p> <p style="text-align: center;">Bid recaps will be available at: troy.k12.mi.us/purchasing/index.htm</p> <p style="text-align: center;"><u>FACSIMILE BID IS NOT ACCEPTABLE</u></p> <p>Bids will not be accepted if submitted after the deadline specified (local time) in the advertisement to bid or in the information to bidders. The late submission of a bid makes the bid nonrepsonsive and is a material defect which shall not be waived by the Board of Education. Delays in the mail will not be considered. All Late bids in the mail will be returned to the bidder unopened.</p> <p>Proposal for the submission of alternatives by vendors will be accepted and reviewed. However, if any substitution or departure is not clearly noted and described, it will be understood that the bid intends to exactly meet the specifications.</p> <p>The Board of Education shall be the sole judge as to whether the proposed goods are "equal" or "approved". Quotations must be mailed or delivered to the Purchasing Office, 1140 Rankin, Troy, MI 48083 no later than 3 p.m. on the date shown above. Michigan State Sales and Use Taxes and Federal Excise Taxes do not apply unless otherwise indicated. Exemption certificates will be furnished when necessary. This request imposes no obligations on the buyer. The Board of Education reserves the right to accept or reject any or all bids or to split awards by items or to accept bids, which will best serve the Board of Education.</p>		

THIS AREA MUST BE FILLED IN

DELIVERY TIME	PRICES FIRM FOR	NAME OF COMPANY	TELEPHONE NO.
TERMS		NO. & STREET	FAX #
FOB DELIVERED	ALL DELIVERY CHARGES MUST BE INCLUDED IN PRICES SHOWN	CITY, STATE & ZIP CODE	E-MAIL
CONTACT PERSON (PLEASE PRINT)		SIGNATURE	DATE

AFFIDAVIT OF BIDDER

The undersigned, the owner or authorized officer of _____ (the “Bidder), pursuant to the familial disclosure requirement provided in the _____ (the “School District”) advertisement for construction bids, hereby represent and warrant except as provided below, that no familial relationships exist between the over(s) or any employee of _____ and any member of the Board of Education of the School District or the Superintendent of the School District.

List any Familial Relationships:

BIDDER:

By: _____

Its: _____

STATE OF MICHIGAN)
)ss.
COUNTY OF _____)

This instrument was acknowledged before me on the _____ day of _____, 2006, by
_____.

, Notary Public

_____ County, Michigan

My Commission Expires: _____

Acting in the County of: _____

**TROY SCHOOL DISTRICT
 BID 9395 UPGRADE TO Athens THEATRE SOUND SYSTEM**

ALTERNATE 1 – DIGITAL SOLUTION

Qty.	Item/Description	Unit Price	Total Cost
2	ALS GK – Roland RSS S-4000S-3208 Modular Rack configured 32 x 8 (stage)		
1	ALS GK – Roland RSS S-4000H Fixed 8 x 32 Unit (front of house)		
1	ALS GK – Roland RSS SC-Pack complete single run cable kit		
1	ALS GK – Roland RSS 100M Cat-5e Reac Cable		
1	ALS GK – odyssey FRP04 4SPC. ATA Rack Case w/17" rackable depth		
1	Install – F.O.H. 2 SPC. Patch Panel F/2Stage Boxes & F.O.H. Box		
1	Labor/Install – Stage Box in Rack		
1	Labor/Install – Stage Box in Control room / reconnect all House Mic Lines to new box / run new cats cable from control room to F.O.H. & connect to panel		
1	Labor/Install – Verify all connections, retune main P.A. system (BSS Soundweb – File available from owner)		
1	Misc. Installation Materials		
	ANY OTHER CHARGES		
	SHIPPING		
	TOTAL		

ALTERNATE 2 – ANALOG SOLUTION

- Change the splitter so that the direct out is to the new FOH and the ISO out is in the booth
- Install new snake to FOH: 24 mic line, 8 returns and main (center w/1 spare)
- Terminate snake cable to proper length with heat shrink, right angle connectors and labels
- Test all Mic Jacks in theater approximately 50 and repair any that are not functioning
- Rebalance the sound system due to the new seating and changes to the room (access to the controller)
- Install remote power up/down module for Amps and FOH sound (moving current power module from soundboards previous location)

Qty.	Description	Unit Price	Total Cost
1	48 channel multi-pair cable		
26	XLR right angle connectors		
8	¼" TRS Right angle connectors		
1	Power button for sound system		
1	Misc. supplies ex heat-shrink, labeling tape		
	SHIPPING		
	LABOR /INSTALLATION		
	ANY OTHER CHARGES		
	TOTAL		

TROY SCHOOL DISTRICT Bid 9395 Upgrade to Athens High School Theatre System		Co. Marshall Music Terms: Net 30 Firms: 30 Days	
Qty	Description	Qty	
2	ALS GK – Roland RSS S-4000S-3208 Modular Rack configured 32 x 8 (stage)		5,565.00 11,130.00
1	ALS GK – Roland RSS S-4000H Fixed 8 x 32 Unit (front of house)		2,415.00 2,415.00
1	ALS GK – Roland RSS SC-Pack complete single run cable kit		820.20 820.20
1	ALS GK – Roland RSS 100M Cat-5e Reac Cable	SC-W100X	119.40 119.40
1	ALS GK – odyssey FRP04 4SPC. ATA Rack Case w/17" rackable depth		157.90 157.90
1	Install – F.O.H. 2 SPC. Patch Panel F/2Stage Boxes & F.O.H. Box	6	40.00 240.00
1	Labor/Install – Stage Box in Rack	2	40.00 80.00
1	Labor/Install – Stage Box in Control room / reconnect all House Mic Lines to new box / run new cats cable from control room to F.O.H. & connect to panel	16	40.00 640.00
1	Labor/Install – Verify all connections, retune main P.A. system (BSS Soundweb – File available from owner)	3	60.00 180.00
1	Misc. Installation Materials		141.90
	ANY OTHER CHARGES	open as to scaff or lift available at site	200.00
	SHIPPING		186.10
	TOTAL		16,310.50
<u>ALTERNATE 2 – ANALOG SOLUTION</u>			
Change the splitter so that the direct out is to the new FOH and the ISO out is in the booth			
Install new snake to FOH: 24 mic line, 8 returns and main (center w/1 spare)			
Terminate snake cable to proper length with heat shrink, right angle connectors and labels			
Test all Mic Jacks in theater approximately 50 and repair any that are not function			
Rebalance the sound system due to the new seating and changes to the room (access to the controller) Install remote power up/down module for Amps and FOH sound (moving current power module from soundboards previous location)			
1	48 channel multi-pair cable	200 ft Ropo IJIS per foot	7.32 1,464.00
26	XLR right angle connectors	26 male 7.70 female 8.19	8.19 212.94
8	¼" TRS Right angle connectors	8	2.98 23.84
1	Power button for sound system		836.90 836.90
1	Misc. supplies ex heat-shrink, labeling tape		217.70 217.70
	SHIPPING		190.00
	LABOR/INSTALLATION		3,300.00
	ANY OTHER CHARGES		200.00
	TOTAL		6,445.38

Genesis Technologies - Late
Monroe Sound Co. - No Response
Pegasus Theatrical, Inc. - No Response
Sound Eng. - No Response

TROY SCHOOL DISTRICT Bid 9395 Upgrade to Athens High School Theatre System		Co. Advanced Lighting & Sound Terms: Net 30 Firms: 30 Days	
Qty	Description		
2	ALS GK – Roland RSS S-4000S-3208 Modular Rack configured 32 x 8 (stage)	4,823.00	9,646.00
1	ALS GK – Roland RSS S-4000H Fixed 8 x 32 Unit (front of house)	2,093.00	2,093.00
1	ALS GK – Roland RSS SC-Pack complete single run cable kit	715.00	715.00
1	ALS GK – Roland RSS 100M Cat-5e Reac Cable	110.00	110.00
1	ALS GK – odyssey FRP04 4SPC. ATA Rack Case w/17" rackable depth	179.95	179.95
1	Install – F.O.H. 2 SPC. Patch Panel F/2Stage Boxes & F.O.H. Box	125.00	125.00
1	Labor/Install – Stage Box in Rack	50.00	50.00
1	Labor/Install – Stage Box in Control room / reconnect all House Mic Lines to new box / run new cats cable from control room to F.O.H. & connect to panel	680.00	680.00
1	Labor/Install – Verify all connections, retune main P.A. system (BSS Soundweb – File available from owner)		750.00
1	Misc. Installation Materials		350.00
	ANY OTHER CHARGES		Roland RSS-S-4000 System remote control (front of house) Operational requirement F/Digital Snake 364.00
	SHIPPING		N/C
	TOTAL		15,062.95
	<u>ALTERNATE 2 – ANALOG SOLUTION</u>		
	Change the splitter so that the direct out is to the new FOH and the ISO out is in the booth		
	Install new snake to FOH: 24 mic line, 8 returns and main (center w/1 spare)		
	Terminate snake cable to proper length with heat shrink, right angle connectors and labels		
	Test all Mic Jacks in theater approximately 50 and repair any that are not function		
	Rebalance the sound system due to the new seating and changes to the room (access to the controller) Install remote power up/down module for Amps and FOH sound (moving current power module from soundboards previous location)		
1	48 channel multi-pair cable	1,075.00	1,075.00
26	XLR right angle connectors	9.25	240.50
8	¼" TRS Right angle connectors	12.50	100.00
1	Power button for sound system	125.00	125.00
1	Misc. supplies ex heat-shrink, labeling tape	250.00	250.00
	SHIPPING		100.00
	LABOR/INSTALLATION		1,200.00
	ANY OTHER CHARGES		
	TOTAL		3,090.50

TROY SCHOOL DISTRICT Bid 9395 Upgrade to Athens High School Theatre System		Co.Thalner Electronic Labs, Inc. Terms: Net 30 Days Firm:			
Qty	Description	Qty			
2	ALS GK – Roland RSS S-4000S-3208 Modular Rack configured 32 x 8 (stage)	1	Roland - Modular 32 Channel Digital Snake System Includes Addl' Stage Box 32x8	7,560.00	7,560.00
1	ALS GK – Roland RSS S-4000H Fixed 8 x 32 Unit (front of house)	1	Fixed Line Level Unit	1,782.00	1,782.00
1	ALS GK – Roland RSS SC-Pack complete single run cable kit	1	Complete Kit for S-4000	594.00	594.00
1	ALS GK – Roland RSS 100M Cat-5e Reac Cable	1	100M REAC CAT-5 cable	85.32	85.32
1	ALS GK – odyssey FRP04 4SPC. ATA Rack Case w/17" rackable depth	1	ATA Rack Case 4 Space	178.49	178.49
1	Install – F.O.H. 2 SPC. Patch Panel F/2Stage Boxes & F.O.H. Box				
1	Labor/Install – Stage Box in Rack				
1	Labor/Install – Stage Box in Control room / reconnect all House Mic Lines to new box / run new cats cable from control room to F.O.H. & connect to panel				
1	Labor/Install – Verify all connections, retune main P.A. system (BSS Soundweb – File available from owner)		Labor		7,904.00
1	Misc. Installation Materials				3,542.50
	ANY OTHER CHARGES				
	SHIPPING				104.50
	TOTAL				21,750.81
	<u>ALTERNATE 2 – ANALOG SOLUTION</u>				
	Change the splitter so that the direct out is to the new FOH and the ISO out is in the booth				
	Install new snake to FOH: 24 mic line, 8 returns and main (center w/1 spare)				
	Terminate snake cable to proper length with heat shrink, right angle connectors and labels				
	Test all Mic Jacks in theater approximately 50 and repair any that are not function				
	Rebalance the sound system due to the new seating and changes to the room (access to the controller) Install remote power up/down module for Amps and FOH sound (moving current power module from soundboards previous location)				
1	48 channel multi-pair cable	300	48 Channel Snake Cable 100'	5.06	1,518.00
26	XLR right angle connectors	26	RT Angle XLR connector	4.97	129.27
8	¼" TRS Right angle connectors	8	1/4" TRS Connector	2.94	23.52
1	Power button for sound system	1	Power Sequencer	271.57	271.57
		3	Power Module	74.59	223.77
		1	Remote Switch for Sequencer	27.50	27.50
1	Misc. supplies ex heat-shrink, labeling tape	32		3.30	105.60
	SHIPPING				120.00
	LABOR/INSTALLATION				10,946.00
	ANY OTHER CHARGES		Materials	3,490.50	3,490.50
	TOTAL				16,855.73

TROY SCHOOL DISTRICT Bid 9395 Upgrade to Athens High School Theatre System		Co. JWR Computers & Entertainment	
Qty	Description	Qty	
2	ALS GK – Roland RSS S-4000S-3208 Modular Rack configured 32 x 8 (stage)	1	Roland RSS S-4000 System Stage box, FOH Box, Remote, and PC Software
		9,500.00	9,500.00
1	ALS GK – Roland RSS S-4000H Fixed 8 x 32 Unit (front of house)	4	5M DB25 to XLR M
		90.00	360.00
1	ALS GK – Roland RSS SC-Pack complete single run cable kit	1	5M DB25 to XLR F or 1/4"
		95.00	95.00
1	ALS GK – Roland RSS 100M Cat-5e Reac Cable	2	Boxes Cat 5 Cable
		175.00	350.00
1	ALS GK – odyssey FRP04 4SPC. ATA Rack Case w/17" rackable depth	1	Port Patch Panel
		130.00	130.00
1	Install – F.O.H. 2 SPC. Patch Panel F/2Stage Boxes & F.O.H. Box	2	16 Port 10/100/1000 switches
		180.00	360.00
1	Labor/Install – Stage Box in Rack	1	4 Space Rack
		175.00	175.00
1	Labor/Install – Stage Box in Control room / reconnect all House Mic Lines to new box / run new cats cable from control room to F.O.H. & connect to panel	1	Connectors and conduit supplies Misc.
		500.00	500.00
1	Labor/Install – Verify all connections, retune main P.A. system (BSS Soundweb – File available from owner)	1	Retune PA
		1,000.00	1,000.00
1	Misc. Installation Materials	1	Labor
		3,000.00	3,000.00
	ANY OTHER CHARGES		15,470.00
	SHIPPING		-
	TOTAL		-
	<u>ALTERNATE 2 – ANALOG SOLUTION</u>		
	Change the splitter so that the direct out is to the new FOH and the ISO out is in the booth		
	Install new snake to FOH: 24 mic line, 8 returns and main (center w/1 spare)		
	Terminate snake cable to proper length with heat shrink, right angle connectors and labels		
	Test all Mic Jacks in theater approximately 50 and repair any that are not function		
	Rebalance the sound system due to the new seating and changes to the room (access to the controller) Install remote power up/down module for Amps and FOH sound (moving current power module from soundboards previous location)		
1	48 channel multi-pair cable		1,250.00
		1,250.00	1,250.00
26	XLR right angle connectors		10.50
		267.00	273.00
8	¼" TRS Right angle connectors		12.50
		100.00	100.00
1	Power button for sound system		200.00
		200.00	200.00
1	Misc. supplies ex heat-shrink, labeling tape		402.00
		402.00	402.00
	SHIPPING		
	LABOR/INSTALLATION		1,400.00
	ANY OTHER CHARGES		
	TOTAL		3,625.00