

QUOTE

February 25, 2020

Regional School District #14
5 Minortown Road
PO Box 469
Woodbury, CT 06790

NONNEWAUG HIGH SCHOOL
DPH PROJECT #2020-0012

DPH OCCT TREATMENT SYSTEM INSTALLATION

We propose to furnish and install the OCCT treatment system per DPH approval dated 2-21-2020 to include:

- (1) Flexcon 80 gallon composite mixing/retention tank
- (1) Pulsa Feeder XP014 chemical metering pump
- (1) Pulsa Feeder MTR302 proportional meter
- (1) Flow safety switch
- (1) 62 gallon double wall solution tank
- (1) Hach SAC200 continuous pH monitor w/SIM card
- (1) Hach digital pH electrode
- (1) Spare Pulsa Feeder metering pump

Total Project cost including all necessary materials and labor: \$19,600