



**ROCKFORD BOARD OF EDUCATION
INVITATION FOR BID ON SUPPLIES, MATERIALS, EQUIPMENT OR SERVICES
FOR SCHOOL DISTRICT NO. 205
ROCKFORD, ILLINOIS**

IFB No. 17-37 RESA Middle School Pool Repair - REBID

DATE: Friday, April 7, 2017

RE: ADDENDUM NO. 4

To All Bidders:

Attached are modifications, clarifications and/or corrections for the Project Manual and are hereby made a part of the contract documents. Please attach this addendum to the Project Manual(s) in your possession. Please note the receipt of this addendum on the bid form. Bidders shall review changes to all portions of this work as changes to one portion may affect the work of another.

If you plan to hand deliver your IFB submission on the due date, please note you must check in on the 3rd floor prior to coming to the bid opening. Please allow time for this as late submission will not be accepted.

Refer all questions relative to the business aspect, Instructions to Bidders, Special Conditions, and questions concerning the technical aspect of the documents to Vicki Musa by email at musav@rps205.com.

ADDENDUM NO. 4

ROCKFORD PUBLIC SCHOOLS
17-37 RESA Middle School Pool Repair - REBID

The following questions have been received and responses are provided below:

1. Note 5 of Sheet 5 of 10 indicates that the new rebar is to be bonded to the existing per 2008 Electrical Code. The existing pool was constructed in 1998. Please confirm that the existing rebar being tied into is bonded per 2008 Electrical Code. If not, please provide direction.
 - a. All that is required is that the new rebar be bonded to the existing rebar per the referenced electrical code.

2. Please confirm that the existing ladders being replaced are bonded per 2008 Electrical Code. If not, please provide direction.
 - a. The replacement of the ladder should not require new deck fittings so no action is required. If new fittings are required, they should be bonded to the deck rebar per code.

3. Section 1 on Sheet 5 Of 10 indicated new concrete around the drain area to be 4' wide, the Section 6 of Sheet 9 of 10 indicates the new concrete area to be 5' wide. Which is correct?
 - a. The new sections should be in accordance with the detail on sheet 9.