

July 7, 2020

#### SOLICITATION ADDENDUM NO. 2 ITB 19-0060 Barnes Elementary HVAC Replacement

#### THE FOLLOWING CHANGES/ADDITIONS TO THE ABOVE CITED SOLICITATION ARE ANNOUNCED:

This Addendum modifies the Invitation to Bid (ITB) document(s) only to the extent indicated herein. Allother areas not changed or otherwise modified by this Addendum shall remain in full force and effect. This Addendum is hereby made an integral part of the ITB document. Bidder must be responsive to any requirements of this Addendum as if the requirements were set forth in the ITB. Failure to do so may result in Bid rejection. See the ITB regarding requests for clarification or change and protests of this Addendum, and the deadlines for the foregoing.

This addendum is to be acknowledged in the space provided on the Bidder Certification form supplied in the solicitation document. Failure to acknowledge receipt of this addendum may be cause to reject your offer.

#### The closing date REMAINS UNCHANGED: July 14, 2020 at 2:00 PM Pacific Time

#### CHANGES:

- 1) The Attached Specification Revisions hereby amend Attachment J Specifications. These amendments superceded any amendments include in Addendum 1.
- 2) The Attached Drawing Revisions hereby amend Attachment K Drawings. These amendments supercede any amendments found in Addendum 1.

#### **CLARIFICATIONS:**

Question: The two units on the roof that are being lifted, are they doing the condensers? Answer: The Condensors are part of the unit.

Question: Is there any asbestos? Can you provide a report? Answer: Per attached Testing Report, no asbestos was detected.

Question: Do we need CO2 for the unit ventilators? Answer: Refer to the drawings and specifications.

Question: Is the UI continuous? Answer: Yes

Question: Are all the Pneumatics gone? Answer: Yes Question: Are there controls in the scope?

Answer: Yes through any of our approved Johnson Controls contractors, Northwest Controls, Branch and Controls Contractors is Seattle who have a branch in Vancouver. These are listed in the Specs.

Question: The mandatory site walk is just for General Contractors? Answer: Yes

Question: Are the pneumatics on the wall? Answer: Yes, surface mount conduit.

Question: Do the controls need to be disconnected and reconnected for the two rooftop condensers?

Answer: This will need to be coordinated with the roof contractor during the project as the control connection/disconnection needs are undetermined at this time.

# **CONSTRUCTION DOCUMENT SET BEAVERTON SCHOOL DISTRICT MARCH 2020 MECHANICAL UPGRADE: BARNES ELEMENTARY SCHOOL** 13730 SW WALKER RD. BEAVERTON, OREGON 97006

#### CONTACTS

OWNER

**BEAVERTON SCHOOL DISTRICT** 16550 SW MERLO ROAD **BEAVERTON, OREGON 97006** 503.591.4575 FAX: 503.591.4469

MECHANICAL

SYSTEM DESIGN CONSUTANTS, INC 333 SE SECOND AVENUE, SUTIE 100 PORTLAND. OREGON 97214 503,248,0227 FAX: 503,248,0240 CONTACT: GARY BARNES

ELECTRICAL

SYSTEM DESIGN CONSUTANTS, INC 333 SE SECOND AVENUE, SUTIE 100 PORTLAND, OREGON 97214 503.248.0227 FAX: 503.248.0240 CONTACT: JEFFREY DAVIS

# **Drawing Revisions**



- E1.10 ELECTRICAL DEMO FLOOR PLANS
- E1.11 ELECTRICAL NEW FLOOR PLANS

#### GENERAL NOTES

- COORDINATE ALL WORK WITH THE DRAWINGS AND SPECIFICATIONS.
- DO NOT SCALE FROM DRAWINGS.
- CONTRACTOR AND SUB-CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH EXISTING CONDITIONS, LOCATIONS, AND PROJECT REQUIREMENTS PRIOR TO SUBMITTING A BID.
- CONTRACTOR AND SUB-CONTRACTORS SHALL FIELD VERIFY DIMENSIONS, AND FAMILIARIZE THEMSELVES WITH PROJECT REQUIREMENTS PRIOR TO COMMENCING WITH THE WORK. CONTRACTOR SHALL REPORT ANY DISCREPANCIES TO ARCHITECT.
- WORK SHALL INCLUDE ALL REQUIRED TRADE PERMITS, LABOR, MATERIALS, AND EQUIPMENT TO COMPLETE ALL WORK INDICATED ON DRAWINGS AND SPECIFICATIONS.
- PROVIDE TEMPORARY DUST-PROOF PARTITIONS AS REQUIRED TO PROTECT ALL EXISTING AREAS AND EQUIPMENT FROM DAMAGE DUE TO DEMOLITION OR NEW CONSTRUCTION ACTIVITIES. COORDINATE LOCATIONS AND REQUIREMENTS WITH OWNER.
- GENERAL CONTRACTOR TO PATCH, REPAIR AND PAINT (REFINISH) SURFACES AND BUILDING ELEMENTS DAMAGED BY MECHANICAL, ELECTRICAL, AND PLUMBING WORK AND WHERE ITEMS ARE REMOVED, RELOCATED OR ADDED.
- REPAIR FLOORS WHERE DAMAGED BY THE WORK OF THIS PROJECT. PATCH AND REPAIR ALL SURFACES TO MATCH EXISTING WHERE ITEMS ARE

REMOVED OR ALTERED - FIELD VERIFY EXTENT REQUIRED.

- CONTRACTOR IS RESPONSIBLE FOR FINAL CLEANUP OF WORK AREA AND ALL 10. EXPOSED BUILDING SURFACES AT SUBSTANTIAL COMPLETION.
- ALL TRASH AND TOOLS SHALL BE REMOVED FROM PREMISES EACH DAY AND 11. THE AREA LEFT CLEAN WHENEVER UNATTENDED. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANUP. COORDINATE WITH OWNER IF SECURE STORAGE IS NEEDED ONSITE.
- CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE TO FINISHED SURFACES, 12. EQUIPMENT, FURNITURE, EXISTING MATERIALS OR FINISHES, CAUSED AS A RESULT OF HIS WORK. REPAIR OR REPLACE DAMAGED ITEMS AS DIRECTED BY BEAVERTON SCHOOL DISTRICT
- ALL WORK SHALL BE DONE IN ACCORDANCE WITH APPLICABLE CODES AND 13. STANDARDS.
- WORK SHALL BE DONE BY THOSE SKILLED AND EXPERIENCED IN THEIR 14 RESPECTIVE TRADES. WORK SHALL BE OF THE HIGHEST QUALITY WORKMANSHIP.

DEFERRED SUBMITTAL

1. SEISMIC EQUIPMENT DETAILS AND CALCULATIONS BY MECHANICAL CONTRACTOR













	$\frown$	$\sim$	$\sim$
IPMENT S	CHEDULE		
	AREA SERVED	CONTROL	ELECTRICAL
SUPPLY AIR, 895 " HIGH, CHANGEOVER ZED RA / OSA R TEMPERATURE.	LIBRARY CLASSROOMS (TYP)	DDC	6.3 MCA 15 MOCP 120 V, 1 PH
IL 1/M1.00			
0000 CFM AT 20 CFM OSA, TSIDE AIR - SEE 5/M1.00 WB ENTERING / ITS	LIBRARY, HALLWAY	DDC	1.5 HP 240 V, 3 PH
R 375 CEM	OFFICES	DDC	15 MOCP
R, SOURM , CONNECTION TO ATING / COOLING S - VERIFY COIL R TEMPERATURE, IL 1/M1.00	OFFICES		120 V, 1 PH
EGRAL SING UNIT	STORAGE	PACKAGE	21 WATTS
ERING TOTAL DR			12.1 MCA 15 FUSE/BRKR 208 V, 1 PH
TOR			

TANICAL	STATE ENERGY O	ODE	$\bigcirc$		DESIGN CAS	EFOR	
ATHING		ZONE	TABLE 6-3	MINIMUM	ZONE	SYSTEM	
NE OSA	ZONE AIR DISTR	OUTDOOR	SYSTEM	OUTDOOR AIR	PRIMARY	OSA CFM	EXHAUST
WRATE	<b>EFFECTIVENESS</b>	AIR ZONE	VENT	INTAKE FLOW	AIRFLOW	SUPPLIED	RATE
p+Az*Ra)		Voz (CFM)	EFFICIENCY	(CFM)			CFM
z (CFM)	(Ez)	Vbz/Ez	Ev	Vot= Vbz/Ez	Vpz/(CFM)		
225	0.8	281	0.8	352	1000	355	
		281		352	1000	355	0
225	0.8	281	0.8	352	1000	355	
		281		352	1000	355	0
225	0.8	281	0.8	352	1000	355	
		281		352	1000	355	0
225	0.8	281	0.8	352	1000	355	
		281		352	1000	355	0
225	0.8	281	0.8	352	1000	355	
		281		352	1000	355	0
459	0.8	574	0.8	717	2000	720	
		574		717	2000	720	0

ADDITION TO THOSE NOT	FED TO AC	COMPLISH THE SEQUEN
ERMOSTAT	SF	SUPPLY FAN
	RF	RETURN FAN
ATURE SENSOR	EF	EXHAUST FAN
_VE	SMK	DUCT MOUNTED SMOKE DETECTOR
DAMPER	C02	CARBON DIOXIDE SENSOR

MIC D	ESIGN CRITER	IA
/ NC	SEISMIC DESIGN CATAGORY	COMPONENT IMPORTANCE FACTOR (Ip)
	D	1.5

#### MECHANICAL LEGEND

R=W

	HCS	HEATING / CHILLED WATER SUPPLY
	HCR	HEATING / CHILLED WATER RETURN
	С	COOLING CONDENSATE
<b>6</b>		BALL VALVE
X	BAL	BALANCING FITTING (CIRCUIT SETTER)
		UNION
		CAP OR PLUG
<b>&gt;</b> DV		HOSE END DRAIN VALVE
r		SUPPLY AIR RISER
		RETURN, EXHAUST AIR RISER
= 30° MAX.		TRANSITION
- 15° MAX.		TRANSITION
		SQUARE TO ROUND TRANSITION
T		WALL MOUNTED THERMOSTAT
		NECK SIZE 8x8-4W 150 CFM
RADIUS ELBOW		<b>GRILLE/DIFFUSER DESIGNATION</b>
		45°
MITER ELBOW		BRANCH TAP

MANUAL VOLUME DAMPER

MOTORIZED DAMPER NOTE: ACTUATOR SYMBOL IS DIAGRAMMATIC ONLY - EXACT LOCATION OF ACTUATOR TO BE FIELD COORDINATED FOR PROPER SERVICE ACCESS

#### ABBREVIATIONS

8Ø	ROUND DUCT DIAMETER, INCHES	OSA	OUTSIDE AIR
12X8	RECTANGULAR DUCT SIZE, INCHES	PLEN	PLENUM
М	MOTORIZED DAMPER	RA	RETURN AIR
DN	DOWN	SA	SUPPLY AIR
EA	EXHAUST AIR	TYP	TYPICAL
N.C.	NORMALLY CLOSED	W.C.	WATER COLUMN
N.O.	NORMALLY OPEN	MAV	MANUAL AIR VENT
OBD	OPPOSED BLADE DAMPER		

#### SYMBOLS

<	A ABANDON	TO EXISTING	(P) (X)	CAF REM	P OR F MOVE	PLUG EXIST	ING	
<				$\sim$				
		TROI FUNCTIONS				$\checkmark$		
			BSD					
•	EQUIPMENT	CONTROL FUNCTION	SYMBOL	DI	DO	AI	AO	ALARM
•	UNIT VENTILATOR	SPACE TEMPERATURE HIGH SPACE TEMPERATURE	ZN-T			x		x
•		LOW SPACE TEMPERATURE	CO2-LVL			х		x
,		DISCHARGE AIR TEMPERATURE	DA-T SF-S	x		х		~
•		RUN STATUS SUPPLY FAN START / STOP	SF-C	Χ	х			х
•		DRAIN PAN OVERFLOW SWITCH HEAT / COOL VALVE POSITION	HTG-O COOL-O	Х			х	Х
,		MIXED AIR LOW LIMIT (FREEZE) LOW TEMPERATURE RETURN AIR DAMPER POSITION	MA-LL DPR-O	Х			x	х
•	FAN COIL	SPACE TEMPERATURE	ZN-T			x	^	
		HIGH SPACE TEMPERATURE LOW SPACE TEMPERATURE DISCHARGE AIR TEMPERATURE	DA-T	×		x		x x
		RUN STATUS SUPPLY FAN START / STOP	SF-S	~	х			x
		HEAT / COOL VALVE POSITION	HTG-O COOL-O	~			х	~
>		LOW TEMPERATURE OUTSIDE AIR DAMPER POSITION	DPR-0	X	х			х
>	AIR HANDLING UNIT	SPACE TEMPERATURE HIGH SPACE TEMPERATURE	ZN-T			х		x
>		LOW SPACE TEMPERATURE DISCHARGE AIR TEMPERATURE SUPPLY FAN STATUS RUN STATUS	DA-T SF-S	x		х		x
>		SUPPLY FAN START / STOP CHANGEOVER VALVE POSITION	SF-C HTG-O COOL-O		х		х	
>		MIXED AIR LOW LIMIT (FREEZE) LOW TEMPERATURE CO2 SENSOR - LIBRARY ONLY	MA-LL CO2-LVL	х		х		х
>		HIGH CO2 LEVEL SMOKE DETECTOR ALARM SMOKE DETECTOR ACTIVATED	RA-SMK	x				x x
	L	RETURN AIR DAMPER POSITION OUTSIDE AIR DAMPER POSITION RELIEF AIR POSITION	DPR-O DPR-O DPR-O				x x x	
,	SPLIT SYSTEM	SYSTEM STATUS RUN STATUS	SF-S	х				х
>		SUPPLY FAN START / STOP SPACE TEMPERATURE HIGH SPACE TEMPERATURE	SF-C ZN-T		х	х		X x
		DRAIN PAN OVERFLOW SWITCH		Х	<u> </u>			X









 $2 \frac{\text{MECHANICAL MEZZANINE DEMOLITION FLOOR PLAN}}{1/4" = 1'-0"}$ 

- SHEET NOTES (1) REMOVE EXISTING HOT WATER COIL, VALVES AND 3/4-INCH CONNECTION PIPING - REMOVE RUNOUT PIPING AND CAP AS NOTED
- 2 REMOVE EXISTING HOT WATER COIL, VALVES AND 1-INCH CONNECTION PIPING REMOVE RUNOUT PIPING AND CAP AS NOTED
- (3) EXISTING RUNOUT SUPPLY AND RETURN PIPING PROTECT WATER PIPING FOR CONNECTION OF NEW UNIT VENTILATOR / FAN COIL
- REMOVE EXISTING UNIT VENTILATOR / FAN COIL PROTECT WALL SLEEVE AND EXTERIOR LOUVER FOR USE WITH NEW UNIT VENTILATOR INSTALLATION
- 5 REMOVE OUTSIDE AIR DUCT, RETURN AIR DUCT AND CONDENSER INTAKE DUCT PROTECT LOUVER AND SLEEVE FOR REUSE
- EXISTING AIR HANDLING UNIT HAS INTEGRAL COMPRESSOR / CONDENSER / REFRIGERATION SYSTEM BEAVERTON SCHOOL DISTRICT WILL EVACUATE THE REFRIGERANT INCLUDE COST IN THE BID PRICE FOR VERIFICATION THAT REFRIGERANT IS REMOVED IN COMPLIANCE WITH CURRENT CODES AND DISPOSAL OF OIL AND REMAINING REFRIGERATION COMPONENTS FROM THE EQUIPMENT AND REMOVAL FROM SITE
- (7) REMOVE EXISTING COIL TRANSITION DUCTWORK AND PROTECT DOWNSTREAM DUCTWORK IN THE MECHANICAL ROOM FOR FUTURE CONNECTIONS





 $2 \frac{\text{MECHANICAL MEZZANINE NEW FLOOR PLAN}}{1/4" = 1'-0"}$ 









#### **Specification Revisions**

#### **Barnes Elementary School HVAC Revisions**

#### TESTING, ADJUSTING AND BALANCING FOR HVAC (Addendum #1)

#### PART 1 - GENERAL

#### 1.1 SUMMARY

- A Work Included: Providing system balance work as specified.
- 1.2 OPERATION AND MAINTENANCE DATA
  - A. Provide O&M data in accordance with Section 23 00 00.
  - B. O&M data shall include copies of system balance data.

#### 1.3 QUALITY ASSURANCE

- A. Conduct the systems balance work in accordance with standard procedures and recognized practices outlined by ASH RAE and SMACNA. Record all actual equipment nameplate and operating data at the site. Test and balance to be performed by an independent air balance company certified by NEBB or AABC.
- B. Contract with Pacific Coast Air Balancing, Neudorfer Engineers Inc., Accurate Balancing Agency Inc., Air Balancing Specialty Inc., Precision Test and Balance Inc., Northwest Engineering Service, Inc. or approved equal to perform the system balance work on this project.

#### **PART 2 - PRODUCTS**

Not Used

#### **PART 3 - EXECUTION**

#### 3.1 GENERAL

- A. Install new air filters in the units before the start of testing and balancing.
- B. Provide ladders, scaffolding, and access to each system for proper testing and balancing.
- C. Confirm in writing that all wiring and controls for mechanical equipment have been installed, completed and tested.
- D. Preparation: Prior to test run, Contractor shall have performed a rough balance and the following:
  - 1. Verify correct rotation of all fans.
  - 2. Check for excessive vibration and noise.
  - 3. Verify filter installation in filter assembly.
  - 4. Check proper calibration and settings of controls.
  - 5. Confirm that ductwork has been sealed.
- E Air handling Unit / **Duct Coils**:
  - 1. Assure that air filters are clean, if not new, prior to beginning air balance work.
  - 2. Adjust the fan drive to obtain fan speed required for air volumes. Speed shall be set to the minimum to provide required air volume at furthest run without excessive static pressure.
  - 3. Adjust minimum outside air volume to that shown on the plans.
  - 4. Include the following in the logs:
    - a. Supply, return and outside air volumes.
      - b. Static pressure drops across the air handling unit.
    - c. Total pressure drops for supply and return system.

#### TESTING, ADJUSTING AND BALANCING FOR HVAC (Addendum #1)

- d. Fan speed or RPM.
- e. Actual motor voltage, amperage, RPM and overload heater sizes.
- F. Air Distribution System:
  - 1. Adjust air volumes at diffusers and grilles to within plus or minus 5% of the values shown on the plans.
  - 2. Adjust diffusers and grilles for proper direction and throw.
  - 3. Log all readings taken.
  - 4. Mark final position of all balancing dampers.
- G. Hydronic Systems (Air Handling Unit, Duct Coils, Unit Ventilators, Fan Coils): Adjust circuit setters / balancing valves to obtain flows noted on drawings and note the flows and pressure drops in the balancing log.
- H Controls and Sequence Commissioning
  - 1. Cycle the air handling unit, **duct coils,** unit ventilators and fan coil units control systems through the entire range of functions and verify proper operation and sequencing of heating, cooling, thermostat operation, etc.
  - 2. Coordinate with the DDC controls contractor for scheduling and system operation support.
  - 3. Provide the following as a separate portion of the test and balance log:
    - a. Type and characteristics of the individual controls serving each unique system in the building.
      - b. Written verification that the equipment controls and sequencing appears to be correct and functioning properly at the time of performance of the system test and balance work.

#### **END OF SECTION**

#### PART 1 - GENERAL

#### 1.1 SCOPE DESCRIPTION

- A. Furnishing and installing all control hardware and software necessary for a complete DDC control system revision as specified.
- B. Furnish all modules, temperature sensors, flow sensors, control valves, control valve actuators, damper actuators and any other items necessary for a complete system and sequence of control
- C. Final installation will allow all school control components to be monitored / controlled at a single point by district personnel through the existing district interface.
  - 1. Final graphics for the completed project must be consistent with the graphics for the areas of the school not in the project scope.
  - 2. Final user interface spaces tree for the completed project must be consistent with the areas of the school not in the project scope.
  - 3. Final control graphics and user interface spaces tree for the project areas and school areas not in scope should be identical in construction and appearance. Navigation of the control system throughout the entire school by school district personnel should be seamless with no distinction between the new project areas and the school areas outside the project scope.
- D. Coordinate the installation of temperature sensors, dampers and actuators with the mechanical contractor to assure all work required for a complete system is included in the base bid.
- E. Establish communication to the new equipment through BACnet IP protocol via the existing MSTP controllers in the **janitor** / **storage** classroom area as noted on the drawing. Do not establish communication through the existing N2 controller(s) in the boiler room. Bring the system DDC points into the district server and integrate the system graphics to match Beaverton School District (BSD) standards.
- F. Commissioning Support.
  - 1. Furnish a time allowance for a controls technician familiar with the system operations to operate the DDC controls while the air balance contractor visually observes the system components are functioning / sequencing as appropriate.
  - 2. Coordinate scheduling with the air balance contractor to perform the controls commissioning.

#### 1.2 QUALITY ASSURANCE

- A. Provide control work by a single company with licensed journeymen specialists in the type of work required, so that only one supplier is responsible for all control work for the project.
- B. Provide coordination with other contractors and subcontractors for work required by other trades for control work accomplishment.

#### 1.3 SUBMITTALS

- A. In diagrams, show complete piping or ductwork system schematics with DDC, electrical and pneumatic control devices, tubing and wiring superimposed.
- B. Completely identify all control devices with manufacturer's type, number, and functional description.
- C. Show all electric and hydronic connections of the control system to equipment furnished by others, complete to terminal points specifically identified with manufacturer's terminal designation.

- D. Provide a bill of material and catalog data on all control device types, including control operation description, technical parameters and connection identifications. Describe the complete sequence of operation containing all information necessary for clarity and understanding of device function and system sequence of operation.
- E. Furnish a list of connected data points, including connected control unit and input device.
- F. Include a spreadsheet for the user interface showing relationships between spaces and equipment. This should document the final room numbers and names used in the building. Equipment names should match tags on units in the field as installed and be consistent with the remaining areas of the building.

#### 1.4 OPERATING AND MAINTENANCE DATA:

- A. O&M Manuals in PDF format.
- B. Include a complete set of control Shop Drawings indicating as built and operating changes.
- C. Include operating and maintenance data on all equipment requiring periodic or incidental services or adjustment. Include a summary schedule for all maintenance tasks. Describe troubleshooting procedures for anticipated problems.
- D. Controls Systems Commissioning:
  - 1. Submit a complete, dated, and initialed record of all system adjustment for components of the control system.
  - 2. Indicate deviations from the specified temperatures, pressures, flows, setpoints, etc.
  - 3. Include a copy of the completed commissioning worksheets in each copy of the Operating and Maintenance Data.

#### PART 2 - PRODUCTS

#### 2.1 ACCEPTABLE MANUFACTURERS AND SYSTEMS

- A. Johnson controls by the local factory branch, Northwest Controls Company (NCC), or Automated Controls (Kirkland / Redmond, Washington).
- 2.2 CONTROL WIRING / COORDINATION WITH LINE VOLTAGE CONTROL
  - A. Provide control wiring to all control modules, sensors and actuators required to provide the project sequences of operation.
  - B. Provide control interface air handling units, unit ventilators and accessory equipment as required.
  - C. All control wiring exposed in occupied areas to be in conduit. Coordinate exposed control wiring in normally occupied spaces with the school district project manager
  - D. Provide all control system related conduit within mechanical room or at equipment locations unless specifically shown to be in other divisions work.
  - E. Control wiring in non-accessible ceilings, walls or floors shall be in conduit.
  - F. All wiring not in conduit or control cabinets shall be rated for plenum installation.
  - G. Provide conduit where required between the zone temperature sensor locations and the zone equipment. Provide all wiring / conduit in the base bid necessary for a complete operating control system.

#### 2.3 AUTOMATION SYSTEM / DDC CONTROL DEVICES

- A. All control devices to be standard products of the specified control system and accessory devices utilized by the controls installer consistent with Beaverton School District standards.
- B. Zone sensors:
  - 1. Include set point adjustments subject to a programmable range.
  - 2. Sensors to also include a timed local override to allow the occupant to override the schedule for an adjustable period of time (programmable from the global school control). At the expiration of the time, control of the unit will automatically return to the default schedule.

#### **PART 3 - EXECUTION**

#### 3.1 INSTALLATION

- A. Single source responsibility of supplier shall be the complete installation and proper operation of the building automation system and control system and shall include debugging and proper calibration of each component in the entire system.
- B. Provide all controllers to accomplish the control sequences specified herein.
- C. Provide / coordinate the installation of; sensors, pipe wells, relays and any other devices and materials required to accomplish the functions described herein.
- D. Establish communication to the new equipment through BACnet IP protocol via the existing MSTP controllers in the classroom area as noted on the drawing. Do not establish communication through the existing N2 controller(s) in the boiler room. Bring the system DDC points into the district server and integrate the system graphics to match Beaverton School District (BSD) standards.
- E. Furnish all software, device installation, programming, technical assistance to the school district and product licenses required for complete operating control systems throughout the entire facility.
- F. All control identification points and HVAC systems graphics to conform to Beaverton School district naming standards Verify with BSD project manager prior to initiation of programming and graphics development.
- G. Provide all temperature sensors, flow sensors, humidity sensors, IAQ sensors, control valves, control valve actuators, dampers, damper actuators, programming and other items necessary for a complete system and sequence of control for new equipment as identified in the contract drawings.
- H. All new equipment to have points as noted on Contract Drawing M1.00.
- I. Program all control diagrams and sequences of operation into the system graphics to allow visual review of diagrams / sequence when viewing system programming.
- J. Furnishing and installing all control hardware and software necessary for a complete DDC control system as specified.
- K. Final installation will allow all school control components to be monitored / controlled at a single point by district personnel through a single user interface.
- L. Coordinate the installation of automatic control valves, dry wells for fluid temperature sensors, dampers and actuators with the mechanical contractor to assure all work required for a complete system is included in the base bid.

- M. The Controls Contractor shall be responsible for field verification of site conditions and for gathering all necessary field data for all items to be provided under this contract prior to submitting his or her bid.
- N. Where work specified under other Sections of this Specification connects to equipment or systems that are listed and described in this Section, the Controls Contractor shall coordinate with other trades to provide proper connection(s) to such equipment.
- O. Identification Provide nameplates identifying all switches, lights and starters, and each control device where the control function is not readily apparent.

#### 3.2 SEQUENCES OF OPERATION

- A. Energy Management System Point Schedule: Provide monitoring and control functions as listed herein for each piece of equipment listed below. Provide a point list that includes each hard wired, calculated and/or resettable point. Minimum control points and alarms are listed on Drawing Sheet M1.00 and in Specification Section 23 09 00, Paragraph 3.7. Additional points are to be included as required to perform the sequence of operation noted herein.
- B. Distributed Control The control system shall observe the concept of distributed control. Modules shall be located at each operating equipment location such that individual systems or zones shall remain functional without communication to other systems on the network.
- C. All general control points noted, software PID algorithms and setpoints to be per Beaverton School District standards. Sequences noted below should be generally followed If conflicts arise between the sequences below and Beaverton School District standard operating sequences, notify the district project manager.
- D. Setpoints and values noted below are to be capable of user adjustment within generally accepted industry value ranges.
- E. Energy Compliance:
  - 1. Provide 365 day, 24 hour occupancy scheduling.
  - 2. When controlling both heating and cooling (mechanical), provide a 5-degree deadband in which the heating energy provided to the zone is reduced to a minimum.
  - 3. Provide optimum start controls to enable a morning warm-up cycle capable of varying the unit start time to meet occupied setpoint at scheduled time of occupancy.
  - 4. Close outside air dampers as appropriate to the equipment when the units are off and during the warm-up period.
- F. Air Handling Unit / Duct Coils.
  - 1. System to have independent schedule capability from global, group or local schedule.
  - 2. Unoccupied Mode:
    - a. Fans off, **duct**-coil hydronic valves closed, outside air and return air dampers indexed to full recirculation.
    - b. Relief damper closed.
    - c. Unoccupied Low Limit: When the space temperature drops below the night low limit set point (district standard adjustable), enable boiler / pump operation, start the air handling unit and open the **duet** coil valves to full heating. Heat to continue until the space is 5-degrees above night low limit set point.
    - d. Subject to the boiler outside air lockout temperature (65). When the supply fan is operational in unoccupied low limit and there is a call for heating the boiler system will be enabled.

- 3. Warm-up Mode:
  - a. At optimum warm up start period, start fan to run continuously. Index outside air and return air **indexed** to full recirculation. Relief damper remains closed. Open the **duct** coil valve to full heating.
  - b. Based on the space temperature, the optimum start/stop function starts the air handling system in warm-up mode so that the space temperature will reach set point at the scheduled occupancy time.
  - c. During warm-up the dampers will remain in full circulation and will cycle to appropriate ventilation mode control at occupancy time regardless of average zone temperature.
- 4. Occupied Mode:

e.

- a. The occupied sequence of operations for the units shall consist of four separate control modes: heating, economizer cooling, chilled water cooling and ventilation.
- b. The Fan runs continuously.
- c. Heating Mode (Heating Hot Water):
  - 1) On a call for heat, mixed air shall modulate to the minimum position allowed by outside air setting and CO2 level.
  - 2) If heating water is available the **duct**-coil valves shall modulate open until the heating setpoint is attained.
- d. Cooling Mode (Economizer cycle):
  - 1) Actuators shall operate outside air and return dampers in accordance with system operating status, supply air, zone air temperatures, and outside air temperatures.
  - 2) Modulate between minimum outside air position and 100% open to meet the cooling requirements.
  - 3) Coil valve is closed. Duct coil valves are closed.
  - Cooling Mode (Chilled Water):
    - 1) On a continued call for cooling, mixed air shall modulate to the minimum position allowed by outside air setting and CO2 level.
    - 2) If chilled water is available, the **duet** coil valves shall modulate open until the cooling setpoint is attained.
- 5. Demand Control Ventilation Mode: The mixed air control shall modulate to control the following in the priority listed:
  - a. Mixed air low limit set point (45 deg F)
  - b. CO2 high limit set point: Reset the outside air according to the following adjustable setpoints -
    - 1) 800-ppm CO2 and below OSA at 5% maximum supply air volume.
    - 2) 1200-ppm CO2 maximum OSA at 50% maximum supply air volume.
  - c. The mixed air set point shall be reset from (55) deg F at (70) deg F outside air to (65) deg F at (50) deg F based on an outside air temperature reset. If the outside air temperature is above the return air temperature the mixed air should be at minimum position as allowed by the minimum outside air setting and CO2 level.
- 6. Night Purge Mode.
  - a. Cooling setpoint 69-degrees F (adjustable).
  - b. If a night purge mode is broadcast to the system and the following conditions are present-
    - 1) Zone is 5 hours (adjustable) prior to occupancy.
    - 2) Zone is 1-degree F over night purge setpoint.
    - 3) Outside air temperature is above 45 degrees F and more than 10 degrees F below the zone temperature.

The fan will start and the outside air damper will index to full open / return air damper will close and the relief damper will open.

- c. Control valves will remain closed.
- d. Purge mode will end one hour prior to occupancy.
- 7. Alarms:
  - a. Individual alarms generated will be setup for the following actions. Each alarm is unique and will have the following options per the district representative.
    - 1) Alarm popup at district DDC central station.
    - 2) Send email Request list of emails from the district representative.
    - 3) Send text Request list of telephone numbers from the district representative.
  - b. Alarms are set with district standard messages Custom messages may be sent without program change or memory download.
  - c. System alarms.
    - 1) Air handling unit run status fault.
    - 2) High zone CO2 level Library only.
    - 3) Smoke detector activation.
    - 4) High space temperature (2 zones).
    - 5) Low space temperature (2 zones).
    - 6) Mixed air low limit Freeze.
      - a) In addition to the alarms generated above The air handling unit will stop and the outside air and return air dampers shall index to full recirculation.
- G. Classroom Unit Ventilators.
  - 1. Unit ventilators to have independent schedule capability from global, group or local schedule.
  - 2. Unoccupied Mode:
    - a. Fans off, coil hydronic valves closed, outside air and return air dampers indexed to full recirculation.
    - b. Unoccupied Low Limit: When the space temperature drops below the night low limit set point (district standard adjustable), enable boiler / pump operation, start the unit ventilator and open the coil valves to full heating. Heat to continue until the space is 5-degrees above night low limit set point.
    - c. Subject to the boiler outside air lockout temperature (65). When the unit ventilator is operational in unoccupied low limit and there is a call for heating the boiler system will be enabled.
  - 3. Warm-up Mode:
    - a. At optimum warm up start period, start fan to run continuously. Index outside air and return air indexed to full recirculation.
    - b. Based on the space temperature, the optimum start/stop function starts the unit ventilator in warm-up mode so that the space temperature will reach set point at the scheduled occupancy time.
    - c. During warm-up the dampers will remain in full circulation and will cycle to appropriate ventilation mode control at occupancy time regardless of average zone temperature.
  - 4. Occupied Mode:
    - a. The occupied sequence of operations for the units shall consist of four separate control modes: heating, economizer cooling, chilled water cooling and ventilation.
    - b. The Fan runs continuously.
    - c. Heating Mode (Heating Hot Water):
      - 1) On a call for heat, mixed air shall modulate to the minimum position allowed by outside air setting and CO2 level.

d.

e.

#### INSTRUMENTATION AND CONTROL FOR HVAC (Addendum #1)

- 2) If heating water is available the coil valves shall modulate open until the heating setpoint is attained.
- Cooling Mode (Economizer cycle):
  - 1) Actuators shall operate outside air and return dampers in accordance with system operating status, supply air, zone air temperatures, and outside air temperatures.
  - 2) Modulate between minimum outside air position and 100% open (adjustable) to meet the cooling requirements.
  - 3) Duct coil valves are closed.
- Cooling Mode (Chilled Water):
  - 1) On a continued call for cooling, mixed air shall modulate to the minimum position allowed by outside air setting and CO2 level.
  - 2) If chilled water is available, the coil valves shall modulate open until the cooling setpoint is attained.
- 5. Demand Control Ventilation Mode: The mixed air control shall modulate to control the following in the priority listed:
  - a. Mixed air low limit set point (45 deg F)
  - b. CO2 high limit set point: Reset the outside air according to the following adjustable setpoints -
    - 1) 800-ppm CO2 and below OSA at 5% maximum supply air volume.
    - 2) 1200-ppm CO2 maximum OSA at 50% maximum supply air volume.
  - c. The mixed air set point shall be reset from (55) deg F at (70) deg F outside air to (65) deg F at (50) deg F based on an outside air temperature reset. If the outside air temperature is above the return air temperature the mixed air should be at minimum position as allowed by the minimum outside air setting and CO2 level.
- 6. Night Purge Mode.
  - a. Cooling setpoint 69-degrees F (adjustable).
  - b. If a night purge mode is broadcast to the system and the following conditions are present-
    - 1) Zone is 5 hours (adjustable) prior to occupancy.
    - 2) Zone is 1-degree F over night purge setpoint.
    - 3) Outside air temperature is above 45 degrees F and more than 10 degrees F below the zone temperature.

The fan will start and the outside air damper will index to full open / return air damper will close and the relief damper will open.

- c. Control valves will remain closed.
- d. Purge mode will end one hour prior to occupancy.
- 7. Alarms:
  - a. Individual alarms generated will be setup for the following actions. Each alarm is unique and will have the following options per the district representative.
    - 1) Alarm popup at district DDC central station.
    - 2) Send email Request list of emails from the district representative.
    - 3) Send text Request list of telephone numbers from the district representative.
  - b. Alarms are set with district standard messages Custom messages may be sent without program change or memory download.
  - c. System alarms.
    - 1) High space temperature.
    - 2) Low space temperature.
    - 3) High space CO2 level.
    - 4) Unit ventilator fan run status fault.
    - 5) Drain pan overflow switch activated.

- 6) Mixed air low limit Freeze.
  - a) In addition to the alarms generated above The unit ventilator will stop and the outside air and return air dampers shall index to full recirculation.
- H. Fan Coils.
  - 1. Fan coil Units to have independent schedule capability from global, group or local schedule.
  - 2. Unoccupied Mode:
    - a. Fans off, coil hydronic valves closed, outside air damper closed.
    - b. Unoccupied Low Limit: When the space temperature drops below the night low limit set point (district standard adjustable), enable boiler / pump operation, start fan coil and open the coil valves to full heating. Heat to continue until the space is 5-degrees above night low limit set point.
    - c. Subject to the boiler outside air lockout temperature (65). When the unit ventilator is operational in unoccupied low limit and there is a call for heating the boiler system will be enabled.
  - 3. Warm-up Mode:
    - a. At optimum warm up start period, start fan to run continuously. Outside air damper remains close.
    - b. Based on the space temperature, the optimum start/stop function starts the fan coil in warm-up mode so that the space temperature will reach set point at the scheduled occupancy time.
    - c. During warm-up the outside air damper will remain closed and will cycle to preset position at occupancy time regardless of average zone temperature.
  - 4. Occupied Mode:
    - a. The occupied sequence of operations for the units shall consist of two separate control modes: heating and chilled water cooling.
    - b. The Fan runs continuously.
    - c. Heating Mode (Heating Hot Water): On a call for heat, if heating water is available the coil valves shall modulate open until the heating setpoint is attained.
    - d. Cooling Mode (Chilled Water): On a continued call for cooling, if chilled water is available, the coil valves shall modulate open until the cooling setpoint is attained.
  - 5. Alarms:
    - a. Individual alarms generated will be setup for the following actions. Each alarm is unique and will have the following options per the district representative.
      - 1) Alarm popup at district DDC central station.
      - 2) Send email Request list of emails from the district representative.
      - 3) Send text Request list of telephone numbers from the district representative.
    - b. Alarms are set with district standard messages Custom messages may be sent without program change or memory download.
    - c. System alarms.
      - 1) High space temperature.
      - 2) Low space temperature.
      - 3) Unit ventilator fan run status fault.
      - 4) Drain pan overflow switch activated.
      - 5) Mixed air low limit Freeze.
        - a) In addition to the alarms generated above The unit ventilator will stop and the outside air damper will close.

- I. Split System Heat Pump.
  - 1. Provide a space temperature sensor and calibrate to the split system thermostat setpoints.
  - 2. Enable / disable the split system on a time schedule (adjustable) The system will control space temperature with its package controls when in occupied and night setback modes.
  - 3. Program remote setpoint adjustment capability from the district server.
  - 4. Provide an alarm point from the drain pan overflow switch.
  - 5. Alarms:
    - a. Individual alarms generated will be setup for the following actions. Each alarm is unique and will have the following options per the district representative.
      - 1) Alarm popup at district DDC central station.
      - 2) Send email Request list of emails from the district representative.
      - 3) Send text Request list of telephone numbers from the district representative.
    - b. Alarms are set with district standard messages Custom messages may be sent without program change or memory download.
    - c. System alarms.
      - 1) High space temperature.
      - 2) Low space temperature.
      - 3) Run status fault.
      - 4) Drain pan overflow switch activated.

#### 3.3 FIELD QUALITY CONTROL

- A. Startup: Implement a logical step-by-step startup and checkout of the control system. In addition, startup assistance and coordination shall be provided during startup of the mechanical equipment. Startup shall be considered complete after the entire system is operating properly.
- B. Self-commission all hardware and software provided for the project.
- C. Completed field commissioning sheets shall be included with the final "as-built" O&M manuals. These sheets shall include validation check fields for all physical and LAN inputs and outputs and graphics for each operating unit or system within the facility. Each system and point shall be listed, using logical names for future reference by the owner.
- D. Commissioning shall include calibration and verification of operation of each I/O and graphic field. Functional commissioning of software programming to meet sequences of operation as submitted and approved shall be verified on the field commissioning sheets.
- E. At the completion of the job, in the presence of an Owner's representative, thoroughly check out the entire control system by simulating each control function and determine that the system performs in accordance with the Contract Specifications.

#### 3.4 INSTRUCTION OF OWNER PERSONNEL

- A. Provide complete list of system generated messages for system operation, including alarm messages.
- B. Modify error message wording as required by the Owner's personnel.
- C. Locate all control components for Operating Engineer.

#### 3.5 RECORD DRAWINGS

A. Provide complete and accurate record drawings noting all deviations from the information furnished in the original submittals.

#### 3.6 COMMISSIONING

- The equipment and systems referenced in this section are to be commissioned. A.
- Β. The contractor has specific responsibilities for scheduling, coordination, startup, test development, testing and documentation. Include time allowance in the base bid to coordinate and participate in all commissioning activities with the designated commissioning contractor.

3.7 EQUIPMENT C	UNIKUL FUNCTIONS						
		BSD					5
EQUIPMENT	CONTROL FUNCTION	SYMBO L	DI	DO	AI	AO	ALARN
		7N_T			x		
	HIGH SPACE TEMPERATURE	211-1			~		x
	LOW SPACE TEMPERATURE						x
	CO2 SENSOR	CO2-LVL			х		
	HIGH CO2 LEVEL						Х
	DISCHARGE AIR TEMPERATURE	DA-T			х		
	SUPPLY FAN STATUS	SF-S	Х				
	RUN STATUS						Х
	SUPPLY FAN START / STOP	SF-C		X			
	DRAIN PAN OVERFLOW		Х				Х
	HEAT / COOL VALVE POSITION	HTG-O				х	
		COOL-O					
	MIXED AIR LOW LIMIT (FREEZE)	MA-LL	Х				
	LOW TEMPERATURE						Х
		DPR-O				х	
	OUTSIDE AIR DAMPER						
	POSITION	DPR-0				X	
FAN COIL	SPACE TEMPERATURE	ZN-T			х		
	HIGH SPACE TEMPERATURE						Х
	LOW SPACE TEMPERATURE						Х
		DA-T			х		
	IEMPERATURE SUPPLY FAN STATUS	SF-S	x				
	RUN STATUS		~				x
	SUPPLY FAN START / STOP	SF-C		x			
	DRAIN PAN OVERFLOW		y				Y
	SWITCH		~			v	
	HEAT / COOL VALVE POSITION	HIG-O				X	

#### EQUIPMENT CONTROL FUNCTIONS 3.7

<b>INSTRUMENTATION AND</b>	<b>CONTROL FOR</b>	R HVAC (Addendum #1)	,
----------------------------	--------------------	----------------------	---

	MIXED AIR LOW LIMIT (FREEZE) LOW TEMPERATURE OUTSIDE AIR DAMPER POSITION	COOL-O MA-LL DPR-0	х	x			x
AIR HANDLING UNIT	SPACE TEMPERATURE HIGH SPACE TEMPERATURE	ZN-T			x		x
	LOW SPACE TEMPERATURE DISCHARGE AIR TEMPERATURE	DA-T			x		X
	SUPPLY FAN STATUS RUN STATUS	SF-S	X				x
	SUPPLY FAN START / STOP	SF-C		х			
	CHANGEOVER VALVE	HTG-O				Х	
		COOL-O					
	MIXED AIR LOW LIMIT (FREEZE) LOW TEMPERATURE	MA-LL	X				x
	CO2 SENSOR - LIBRARY ONLY HIGH CO2 LEVEL	CO2-LVL			x		x
	SMOKE DETECTOR ALARM SMOKE DETECTOR ACTIVATED	RA-SMK	X				x
	RETURN AIR DAMPER POSITION	DPR-O				x	
	OUTSIDE AIR DAMPER POSITION	DPR-O				x	
	RELIEF AIR POSITION	DPR-O				X	
SPLIT SYSTEM	SYSTEM STATUS RUN STATUS	SF-S	Х				x
	SUPPLY FAN START / STOP	SF-C		X			
	SPACE TEMPERATURE	ZN-T			X		
	HIGH SPACE TEMPERATURE						X
	LOW SPACE TEMPERATURE DRAIN PAN OVERFLOW SWITCH		x				X X

#### **END OF SECTION**

#### **Testing Report**

#### Limited Asbestos Survey Report

Barnes Elementary School 13730 Walker Road Beaverton, OR

Prepared for:

Beaverton School District 48J

General Information	1.1
Inspection Summary	1.2
Sample Inventories	2.1
Laboratory Data	Not Numbered
AHERA Certificates	Not Numbered



January 2020 Project No.: 23816.018 Phase No.: 0001

4412 SW Corbett Avenue, Portland, OR 97239 503.248.1939 Main 866.727.0140 Fax 888.248.1939 Toll-Free

PBSUSA.COM

#### **GENERAL INFORMATION**

#### **BUILDING DATA**

Barnes Elementary School 13730 Walker Road Beaverton, OR

#### **CLIENT DATA**

Beaverton School District 48J 16550 SW Merlo Rd. Beaverton, OR 97003 (503) 591-4560

#### BACKGROUND INFORMATION

Two story elementary school with modern south addition and original construction north building.

#### SURVEY SCOPE

PBS Engineering and Environmental Inc. (PBS) has performed a limited general asbestos survey of roofing areas in accordance with OSHA in 29 CFR 1910.1001 and compiled a report with the following information:

- The type, location, and approximate quantity of suspect asbestos-containing materials
- Bulk sampling of selected suspect building materials
- Inspection summary
- · Laboratory analytical data of bulk material sampled

With regard to asbestos, PBS endeavored to locate all the suspect asbestos-containing materials in the roof inspection area; however, suspect asbestos-containing materials may be present and concealed. If suspect materials are uncovered during demolition activities that are not identified in this report, testing should be performed prior to impact. Asbestos-containing materials are known to exist within the building outside of the scope of this inspection.

PBS has conducted a physical inspection of the building, compiled this report consistent with the survey scope, and certifies that the information is correct and accurate within the standards of professional quality and contractual obligations.

James Mastanduno Project Manager/Prime Inspector Accreditation #: IMR-20-4993B

Signature

Date

 $\ensuremath{\mathbb{C}}$  2020 PBS Engineering and Environmental Inc.



#### INSPECTION SUMMARY

DATES	SURVEYED BY	ΑCΤΙVΙΤΥ			
1/9/2020	James Mastanduno	Roofing Survey			

PBS has investigated accessible areas within the scope of inspection to locate suspect asbestoscontaining building materials (ACBM). Suspect materials may be present in concealed areas (e.g., behind walls and under carpet). The findings are listed below.

#### **ASBESTOS MATERIALS**

The following materials either tested positive, or, based on the experience of PBS field personnel, were not tested and should be considered asbestos-containing. Materials that had mixed results are considered positive. Materials not sampled may contain asbestos and should be tested to verify asbestos content prior to impact through demolition, renovation, etc. (+) Tested Positive, (M) Mixed Results, (P) Presumed Positive, (T) Previously Tested Positive.

See sample inventory for specific results.

#### No asbestos-containing building materials were identified within the scope of this survey.

#### MATERIALS THAT TESTED NEGATIVE FOR ASBESTOS

The following materials tested negative based on ASHARA sampling minimums and testing by NVLAP participating laboratories. Although no asbestos was detected, it is possible that further sampling could indicate asbestos content. It may be prudent to test prior to impact through demolition, renovation, etc.

<u>Material (type)</u>	Location
Gravel built-up roofing field layers on wood decking	Roof areas B, C, G, and H
Flashing caulk	Throughout roofing scope of inspection
Silver paint and built up roofing field layers on wood decking	Roof area F
Silver paint and roof penetration sealants	Throughout roofing scope of inspection

#### **INSPECTION SUMMARY**

#### BACKGROUND

On January 9, 2020, PBS performed a limited pre-renovation asbestos survey of portions of Barnes Elementary School in Beaverton, Oregon. The survey was requested by Beaverton School District in anticipation of roof replacement or rehabilitation of the north portions of the building. This survey was limited to roofing materials in those locations.

The purpose of the survey was to locate, identify, and quantify accessible friable and non-friable asbestoscontaining building materials for removal prior to roof work.

The survey is also intended to satisfy Occupational Safety and Health Administration (OSHA) hazard communication requirements as well as requirements by the Department of Environmental Quality (DEQ) to perform an asbestos inspection prior to renovation or demolition activities under Oregon Administrative Rule (OAR) 340-248-0270.

#### **ASBESTOS SUMMARY**

The roof areas were inspected by a PBS Asbestos Hazard Emergency Response Act (AHERA) accredited inspector to determine the presence, location, and approximate quantity of asbestos-containing materials (ACM). Eleven bulk samples of building materials, suspected of containing asbestos, were collected and submitted under chain of custody to Lab/Cor Portland Inc. of Portland, Oregon, for polarized light microscopy (PLM) analysis.

No materials were found to contain asbestos within the scope of inspection. Asbestos-containing materials are known to exist in the building outside the scope of this survey.

Please refer to the asbestos bulk sample inventory for more sample details.

#### **Asbestos Regulations**

Oregon DEQ, Environmental Protection Agency (EPA), and OSHA regulations require proper removal and handling of ACM by licensed and trained asbestos abatement contractors prior to building renovations or demolition.

The EPA, DEQ, and OSHA all define ACM as any material containing more than 1% asbestos. Although materials equal to or less than 1% are not considered by regulatory agencies to be an ACM, they still have some asbestos content, and Oregon OSHA has specific requirements for situations in which workers may encounter, disturb, or remove materials containing any level of asbestos. For the sake of hazard communication, these materials are included in the asbestos-containing materials section of this report.

In 1995, Oregon OSHA adopted 29 Code of Federal Regulations (CFR) Part 1926.1101 governing asbestos under OAR 437-003-1926.1101. The regulation has made significant changes in work procedures and how asbestos materials are managed. OSHA believes that the single biggest risk of asbestos exposure is to workers who unknowingly or improperly disturb ACM. Hazard communication, training, personal protection, work practices, exposure monitoring, and recordkeeping are all major components of the regulation.

DEQ's OAR 340, Division 248 also covers asbestos abatement requirements, removal notifications, licensing, and certifications for contractors.

For more information regarding the removal of asbestos-containing materials, please refer to the following:

1. Oregon Occupational Safety and Health Administration, OAR 437-003-1926.1101



#### **INSPECTION SUMMARY**

2. Department of Environmental Quality, OAR-340, Division 248

This report is not suitable as a bid document or an asbestos abatement design. The purpose of this report is risk hazard communication only.



Code	Material		<u>Location</u>	<u>Results</u>	<u>Lab</u>
23816.018-0001	Built-up Roofing (	01)	Area B; east, built-up roofing		Lab Cor
		Layer:	Description:	Analysis:	
		Layer 01	rocky fibrous tar, black/gray	No Asbestos Detected	
		Layer 02	woven fibers, white with tar, black	No Asbestos Detected	
		Layer 03	woven fibers, white with tar, black	No Asbestos Detected	
		Layer 04	woven fibers, white with tar, black	No Asbestos Detected	
		Layer 05	woven fibers, white with tar, black	No Asbestos Detected	
		Layer 06	woven fibers, white with tar, black	No Asbestos Detected	
		Layer 07	compressed fibers, dark brown	No Asbestos Detected	
		Layer 08	compressed fibers, light brown	No Asbestos Detected	
		Layer 09	foam material, yellow	No Asbestos Detected	
		Layer 10	fibrous backing, black	No Asbestos Detected	
		Layer 11	compressed fibers, black	No Asbestos Detected	
		Layer 12	thick tar, black	No Asbestos Detected	
23816.018-0002	Built-up Roofing (	01)	Area B; west, built-up roofing		Lab Cor
		Layer:	Description:	Analysis:	
		Layer 01	fibrous tar, black	No Asbestos Detected	
		Layer 02	fibrous tar, black	No Asbestos Detected	
		Layer 03	fibrous tar, black	No Asbestos Detected	
		Layer 04	fibrous tar, black	No Asbestos Detected	
		Layer 05	fibrous material, brown/black, with tar	No Asbestos Detected	
		Layer 06	fibrous material, light brown	No Asbestos Detected	
		Layer 07	foam material, yellow, with paper	No Asbestos Detected	
		Layer 08	rocky fibrous tar, black	No Asbestos Detected	
		Layer 09	fibrous tar, black	No Asbestos Detected	
		Layer 10	fibrous tar, black	No Asbestos Detected	
		Layer 11	fibrous tar, black	No Asbestos Detected	
		Layer 12	fibrous tar, black	No Asbestos Detected	
23816.018-0003	Roof Penetration S	Sealant (01)	Area B; south, silver paint and bla	ack sealant on penetrations	Lab Cor
		Layer:	Description:	Analysis:	
		Layer 1	paint, silver	No Asbestos Detected	
		Laver 2	tar, dark brown	No Asbestos Detected	

<u>Code</u>	<u>Material</u>		Location	<u>Results</u>	<u>Lab</u>
23816.018-0004	Built-up Roofing (01)		Area B; north upper section, built	-up roofing	Lab Cor
	Lay	ver:	Description:	Analysis:	
	Lay	er 01	fibrous tar, black	No Asbestos Detected	
	Laye	er 02	fibrous tar, black	No Asbestos Detected	
	Laye	er 03	fibrous tar, black	No Asbestos Detected	
	Laye	er 04	compressed fibers, brown	No Asbestos Detected	
	Laye	er 05	fibrous backing, dark gray	No Asbestos Detected	
	Laye	er 06	foam, yellow	No Asbestos Detected	
	Laye	er 07	rocky fibrous tar, black	No Asbestos Detected	
	Laye	er 08	fibrous tar, black	No Asbestos Detected	
	Laye	er 09	fibrous tar, black	No Asbestos Detected	
	Laye	er 10	fibrous tar, black	No Asbestos Detected	
23816.018-0005	Built-up Roofing (01)		Area C; south, built-up roofing		Lab Cor
	Lay	er:	Description:	Analysis:	
	Laye	er 01	fibrous tar, black	No Asbestos Detected	
	Laye	er 02	fibrous tar, black	No Asbestos Detected	
	Laye	er 03	fibrous tar, black	No Asbestos Detected	
	Laye	er 04	fibrous tar, black	No Asbestos Detected	
	Laye	er 05	fibrous tar, black	No Asbestos Detected	
	Laye	er 06	compressed fibers, black	No Asbestos Detected	
	Laye	er 07	compressed fibers, brown	No Asbestos Detected	
	Laye	er 08	fibrous backing, dark gray	No Asbestos Detected	
	Laye	er 09	foam, yellow	No Asbestos Detected	
	Laye	er 10	rocky fibrous tar, black	No Asbestos Detected	
	Laye	er 11	fibrous tar, black	No Asbestos Detected	
	Laye	er 12	fibrous tar, black	No Asbestos Detected	
	Laye	er 13	fibrous tar, black	No Asbestos Detected	
	Laye	er 14	fibrous tar, black	No Asbestos Detected	

<u>Code</u>	Material		Location	<u>Results</u>	<u>Lab</u>
23816.018-0006	Built-up Roofing (	01)	Area C; north, built-up roofing		Lab Cor
		Layer:	Description:	Analysis:	
		Layer 01	fibrous tar, black	No Asbestos Detected	
		Layer 02	fibrous tar, black	No Asbestos Detected	
		Layer 03	fibrous tar, black	No Asbestos Detected	
		Layer 04	fibrous tar, black	No Asbestos Detected	
		Layer 05	fibrous tar, black	No Asbestos Detected	
		Layer 06	fibrous material, light brown/black	No Asbestos Detected	
		Layer 07	foam material, yellow, with fibrous backing, black	No Asbestos Detected	
		Layer 08	rocky fibrous tar, black	No Asbestos Detected	
		Layer 09	fibrous tar, black	No Asbestos Detected	
		Layer 10	fibrous tar, black	No Asbestos Detected	
		Layer 11	fibrous tar, black	No Asbestos Detected	
		Layer 12	fibrous tar, black	No Asbestos Detected	
		Layer 13	fibrous tar, black	No Asbestos Detected	
23816.018-0007	Roof Penetration Sealant (01) Layer:		Area C; north, silver paint and bla <b>Description:</b>	Lab Cor	
		Layer 1	paint, silver	No Asbestos Detected	
		Layer 2	rubbery material, black with woven fibers, white	No Asbestos Detected	
23816.018-0008	Built-up Roofing (	02)	Area F; east, built-up roofing		Lab Cor
		Layer:	Description:	Analysis:	
		Layer 01	coating, silver	No Asbestos Detected	
		Layer 02	fibrous tar, black	No Asbestos Detected	
		Layer 03	tar, black	No Asbestos Detected	
		Layer 04	fibrous tar, black	No Asbestos Detected	
		Layer 05	tar, black	No Asbestos Detected	
		Layer 06	fibrous tar, black, with tar, black	No Asbestos Detected	
		Layer 07	compressed fibers, black	No Asbestos Detected	
		Layer 08	compressed fibers, brown	No Asbestos Detected	
		Layer 09	foam, off-white	No Asbestos Detected	
		Layer 10	fibrous material, gray/black	No Asbestos Detected	



<u>Code</u>	<u>Material</u>		Location	<u>Results</u>	<u>Lab</u>
23816.018-0009	Built-up Roofing (	02)	Area F; west, built-up roofing		Lab Cor
		Layer:	Description:	Analysis:	
		Layer 01	coating, silver	No Asbestos Detected	
		Layer 02	fibrous tar, black	No Asbestos Detected	
		Layer 03	tar, black	No Asbestos Detected	
		Layer 04	tar, black	No Asbestos Detected	
		Layer 05	tar, black	No Asbestos Detected	
		Layer 06	fibrous tar, black	No Asbestos Detected	
		Layer 07	compressed fibers, black	No Asbestos Detected	
		Layer 08	compressed fibers, brown	No Asbestos Detected	
		Layer 09	foam, off-white	No Asbestos Detected	
		Layer 10	fibrous material, gray/black	No Asbestos Detected	
23816.018-0010	Built-up Roofing (	03)	Area H; built-up roofing		Lab Cor
		Layer:	Description:	Analysis:	
		Layer 01	tar, black with woven fibers, white	No Asbestos Detected	
		Layer 02	tar, black with woven fibers, white	No Asbestos Detected	
		Layer 03	tar, black with woven fibers, white	No Asbestos Detected	
		Layer 04	tar, black with woven fibers, white	No Asbestos Detected	
		Layer 05	tar, black with woven fibers, white	No Asbestos Detected	
		Layer 06	compressed fibers, black	No Asbestos Detected	
		Layer 07	compressed fibers, brown	No Asbestos Detected	
		Layer 08	rocky fibrous tar, black/gray	No Asbestos Detected	
		Layer 09	tar, black with woven fibers, white	No Asbestos Detected	
		Layer 10	tar, black with woven fibers, white	No Asbestos Detected	
		Layer 11	tar, black with woven fibers, white	No Asbestos Detected	
23816.018-0011	Roof Penetration S	Sealant (02)	Area H; flashing caulk	Analysis	Lab Cor
		Layer:	Description:	Analysis:	
		Layer 1	rubbery material, gray/tan	No Asbestos Detected	



LabCor Portland 4321 SW Corb	<b>Portl</b> bett Ave., S	and, Inc	BULK	SAMPLE ASE	BESTOS ANALYSIS	Phone: (503) 2 http://www.labo	224-5055 orpdx.net
Portland, OR	97239		Asbest	tos and Envira	nmental Analysis		
Client: PBS Engineering 4412 SW Corbett Portland, OR 972	and Enviro Avenue 39	nmental			~	Report Number: 20 Report Date: 01	0134R01 /16/2020
Job Number: 20013 Project Name: Project Number: 23816. Project Notes:	9 <b>4</b> 018 Phase	9 0001				<b>P.O. No:</b> n/a	1
Client Sample ID: 23816	6.018-0001		Sample ID:	S1	Date Analyze	ed: 01/15/2020	
Client Sample Description	<b>1</b> :				Analy	st: Danielle de Mo	ontigny
Asbestos Mineral Fibers	Layer Percer	nt: Chrysotile	Amosite	Crocidolite			Percent Asbestos:
Layer 01							
compressed fibers, blac	sk 4 %	- %	-	-			NAD
Layer 02							
woven fibers, white with tar, black	ı 5%	% -	-	-			NAD
Layer 03	-						
woven fibers, white with tar, black	ı 5%	~ -	-	-			NAD
Layer 04	-						
woven fibers, white with tar, black	ı 5%	~ -	-	-			NAD
Layer 05		,					
tar, black	1 57	′o -	-	-			NAD
Layer Ub		1					
tar, black	1 57	′o -	-	-			NAD
Layer U/	< 10 °	/					
brown	× 107	o -	-	-			NAD
compressed fibers, light	t 15 %		-	-			NAD
Layer 09							
foam material, yellow	20 %	- 6	-	-			NAD
Layer 10							
fibrous backing, black	1 %	- 6	-	-			NAD
Layer 11							
rocky fibrous tar, black/gray	5 %	6 -	-	-			NAD
Layer 12							
thick tar, black	20 %	- 6	-	-			NAD
Other Fibers Fib	orous lass Cell	Mineral ulose Wool	Synthetic		Other	Ν	<i>l</i> atrix
Layer 01	- 60	% -	-				40 %
Layer 02	-		15 %				85 %
Layer 03 2	% Tra	ace -	15 %				83 %

Page 1 of 13

#### **BULK SAMPLE ASBESTOS ANALYSIS**

Phone: (503) 224-5055 http://www.labcorpdx.net

Client: PBS Engi 4412 SW Portland,	ineering and E Corbett Aven OR 97239	nvironmenta ue	.1			Report Number: Report Date:			
Job Number: Project Name: Project Number:	<b>200134</b> 23816.018 F	hase 0001				P.O. N	<b>o:</b> n/a		
Project Notes:									
Layer 04	10 %	Trace	-	5 %	-	-	85 %		
Layer 05	10 %	Trace	-	8 %	-	-	82 %		
Layer 06	10 %	-	-	10 %	-	-	80 %		
Layer 07	-	80 %	-	-	-	-	20 %		
Layer 08	-	95 %	-	-	-	-	5 %		
Layer 09	-	-	-	-	-	-	100 %		
Layer 10	10 %	85 %	-	-	-	-	5 %		
Layer 11	5 %	Trace	-	-	-	-	95 %		
Layer 12	3 %	-	-	-	-	-	97 %		



Phone: (503) 224-5055 http://www.labcorpdx.net

Client:	PBS Engir	eering and Environmental	Report Number: 200134R01
	4412 SW ( Portland, C	Corbett Avenue IR 97239	<b>Report Date: </b> 01/16/2020
Job Number: 200134		200134	<b>P.O. No:</b> n/a
Proje	ct Name:		
Project N Proje	lumber: ct Notes:	23816.018 Phase 0001	

Client Sample ID: 23	3816.018	-0002		Sample ID:	S2		Date Analyzed:	01/15/2020	
<b>Client Sample Descrip</b>	otion:						Analyst:	Mia Gaines	
Asbestos Mineral Fib	ers	Layer	Olan a stille						Percent
	F	ercent:	Chrysotile	Amosite	Crocidolite				Asbestos:
Layer 01									
fibrous tar, black		5 %	-	-	-				NAD
Layer 02									
fibrous tar, black		6 %	-	-	-				NAD
Layer 03									
fibrous tar, black		10 %	-	-	-				NAD
Layer 04									
fibrous tar, black		6 %	-	-	-				NAD
Layer 05									
fibrous material, brown/black, with ta	ar	10 %	-	-	-				NAD
Layer 06									
fibrous material, ligl brown	ht	20 %	-	-	-				NAD
Layer 07									
foam material, yello with paper	ow,	10 %	-	-	-				NAD
Layer 08									
rocky fibrous tar, bl	ack	10 %	-	-	-				NAD
Layer 09									
fibrous tar, black		5 %	-	-	-				NAD
Layer 10									
fibrous tar, black		5 %	-	-	-				NAD
Layer 11									
fibrous tar, black		7 %	-	-	-				NAD
Layer 12									
fibrous tar, black		6 %	-	-	-				NAD
Other Fibers	Fibrous Glass	Cellulos	Mineral e Wool	Synthetic		Other		٨	<i>N</i> atrix
Laver 01	10 %	-	-	10 %		-	-	, in the second s	80 %
Laver 02	10 %	-	-	10 %		-	-		80 %
Layer 03	10 %	5 %	-	10 %		-	-		75 %
Layer 04	-	20 %	-	-		-	-		80 %
Layer 05	-	80 %	-	-		-	-		20 %
Layer 06	2 %	70 %	-	-		-	-		28 %



#### **BULK SAMPLE ASBESTOS ANALYSIS**

Phone: (503) 224-5055 http://www.labcorpdx.net

Client: PBS 4412 Portla	Engineer SW Cortand, OR	ing and bett Ave 97239	Environme	ental	Report Number: 200134R01 Report Date: 01/16/2020					
Job Numb	ber: 20	0134							<b>P.O. No:</b> n/a	
Project Nai	me:									
Project Numbe Project Not	er: 233 tes:	816.018	Phase 00	01						
Layer 07		-	8 %	-	2 %		-	-	90 %	
Layer 08		6 %	-	-	2 %		-	-	92 %	
Layer 09		6 %	2 %	-	-		-	-	92 %	
Layer 10		8 %	-	-	-		-	-	92 %	
Layer 11		8 %	-	-	-		-	-	92 %	
Layer 12		10 %	10 %	-	-		-	-	80 %	
Client Sample	e ID: 23	3816.018	8-0003		Sample ID:	S3		Date Analyzed:	01/16/2020	
Client Sample	e Descrip	otion:						Analyst:	Danielle de Montigny	
Asbestos Mir	neral Fib	ers	Layer Percent:	Chrysotile	Amosite	Crocidolite			Percent Asbestos:	
Layer 01										
paint, silve	er		1 %	-	-	-			NAD	
Layer 02										
tar, dark bi	rown		99 %	-	-	-			NAD	
Other Fibers		Fibrous Glass	s Cellulos	Mineral e Wool	Synthetic		Other		Matrix	
Layer 01		-	1 %	-	-		-	-	99 %	
Layer 02		-	2 %	-	-		-	-	98 %	



Phone: (503) 224-5055 http://www.labcorpdx.net

<u>Client:</u>	PBS Engir 4412 SW (	eering and Environmental Corbett Avenue	Report Number: Report Date:	200134R01 01/16/2020
Job I Projec	Number:	200134	P.O. No:	n/a
Project N Projec	lumber: ct Notes:	23816.018 Phase 0001		

Client Sample ID: 23	3816.018	-0004		Sample ID:	S4		Date Analyzed:	01/16/2020	
Client Sample Descrip	otion:						Analyst:	Ryan Brown	
Asbestos Mineral Fib	<u>ers</u> □	Layer	Chrysotile	Amosito	Crocidolite				Percent
Laver 01		croont. c	JinySourc	Amosite	Crocidolite				ASDESIUS.
fibrous tar black		8%	_	_	_				NAD
		0 /0							NAD
fibrous tar black		8%		_					NAD
		0 /0							NAD
fibrous tar black		8%	-	_	_				ΝΔΟ
l aver 04		0 /0							NAD
compressed fibers, brown		32 %	-	-	-				NAD
Layer 05									
fibrous backing, da gray	rk	4 %	-	-	-				NAD
Layer 06									
foam, yellow		6 %	-	-	-				NAD
Layer 07									
rocky fibrous tar, bl	ack	9 %	-	-	-				NAD
Layer 08									
fibrous tar, black		9 %	-	-	-				NAD
Layer 09									
fibrous tar, black		9 %	-	-	-				NAD
Layer 10									
fibrous tar, black		7 %	-	-	-				NAD
Other Fibers	Fibrous		Mineral			Other			
	Glass	Cellulose	VV00I	Synthetic		Other		Μ	latrix
Layer 01	4%	-	-	5%		-	-		91 %
Layer 02	8%	-	-	5 %		-	-		87%
Layer 03	3%	-	-	-		-	-		97%
Layer 04	-	100 %	-	-		-	-		0%
Layer 05	15 %	15 %	-	-		-	-		10 %
Layer 00	- 5 %	-	-	-		-	-		00 % 05 %
Layer 08	5%	-	-	-		-	-		95 %
Layer 09	5%	-	-	-		-	-		95 %
Layer 10	5%	-	-	-		-	_		95 %
	0 /0								





Phone: (503) 224-5055 http://www.labcorpdx.net

Asbestos and Environmental Analysis

Client:	PBS Engir	eering and Environmental	Report Number:	200134R01
	4412 SW ( Portland, (	Corbett Avenue DR 97239	Report Date:	01/16/2020
Job Number: 200134			P.O. No:	n/a
Proje	Project Name:			
Project Number: 23816.018 Phase 0001		23816.018 Phase 0001		
Proje	ct Notes:			

Client Sample ID: 2	3816.018	-0005		Sample ID:	S5		Date Analyzed:	01/16/2020	
Client Sample Descri	ption:						Analyst:	Ryan Brown	
Asbestos Mineral Fib	ers	Layer	Chrysotile	Amosito	Crocidalite				Percent
Laver 01	•	croont.	of it you the	Amosito	Orocidonic				ASDESIUS.
fibrous tar black		5%	_	-	_				ΝΔΟ
l aver 02		0 /0							10.12
fibrous tar. black		5%	-	-	-				NAD
Laver 03		-							
fibrous tar, black		5 %	-	-	-				NAD
Layer 04									
fibrous tar, black		5 %	-	-	-				NAD
Layer 05									
fibrous tar, black		5 %	-	-	-				NAD
Layer 06									
compressed fibers,	black	21 %	-	-	-				NAD
Layer 07									
compressed fibers, brown		21 %	-	-	-				NAD
Layer 08									
fibrous backing, da gray	rk	2 %	-	-	-				NAD
Layer 09									
foam, yellow		6 %	-	-	-				NAD
Layer 10									
rocky fibrous tar, bl	ack	5 %	-	-	-				NAD
Layer 11									
fibrous tar, black		5 %	-	-	-				NAD
Layer 12		<b>F</b> 6/							
TIDrous tar, Diack		5 %	-	-	-				NAD
Layer 13		E 0/							NAD
		5 %	-	-	-				NAD
fibrous tar black		5%	_		_				ΝΑΠ
Other Eibers	Fibrous	0 /0	Minoral						NAD
	Glass	Cellulos	se Wool	Synthetic		Other		M	atrix
Layer 01	5 %	-	-	8 %		-	-	;	87 %
Layer 02	5 %	8 %	-	5 %		-	-	:	82 %
Layer 03	5 %	8 %	-	5 %		-	-	;	82 %

Page 6 of 13



#### **BULK SAMPLE ASBESTOS ANALYSIS**

Phone: (503) 224-5055 http://www.labcorpdx.net

<u>Client:</u>	PBS Engi 4412 SW Portland,	gineering and EnvironmentalReport Number: 200V Corbett AvenueReport Date: 01/-I, OR 97239In the second se										
Job	Number:	200134					P.O. No	n/a				
Proje	ct Name:											
Project N	lumber:	23816.018 F	hase 0001									
Projec	ct Notes:											
Layer 04	4	8 %	5 %	-	-	-	-	87 %				
Layer 08	5	5 %	-	-	8 %	-	-	87 %				
Layer 06	6	-	85 %	-	-	-	-	15 %				
Layer 07	7	-	100 %	-	-	-	-	0 %				
Layer 08	В	15 %	15 %	-	-	-	-	70 %				
Layer 09	9	-	-	-	-	-	-	100 %				
Layer 10	D	8 %	-	-	-	-	-	92 %				
Layer 11	1	8 %	-	-	-	-	-	92 %				
Layer 12	2	8 %	-	-	-	-	-	92 %				
Layer 13	3	8 %	-	-	-	-	-	92 %				
Layer 14	4	8 %	-	-	-	-	-	92 %				





Phone: (503) 224-5055 http://www.labcorpdx.net

<u>Client:</u>	PBS Engir 4412 SW ( Portland, (	neering and Environmental Corbett Avenue DR 97239	Report Number: Report Date:	200134R01 01/16/2020
Job Number: 200134			P.O. No:	n/a
Proje	ct Name:			
Project Number: Project Notes:		23816.018 Phase 0001		

Client Sample ID: 23	816.018-	0006		Sample ID:	S6		Date Analyzed:	01/16/2020	
Client Sample Descript	tion:	lovor					Analyst:	Mia Gaines	Doroont
Aspestos Mineral Fibe	P	ercent:	Chrysotile	Amosite	Crocidolite				Asbestos:
Layer 01									
fibrous tar, black		5 %	-	-	-				NAD
Layer 02									
fibrous tar, black		5 %	-	-	-				NAD
Layer 03									
fibrous tar, black		5 %	-	-	-				NAD
Layer 04									
fibrous tar, black		5 %	-	-	-				NAD
Layer 05									
fibrous tar, black		5 %	-	-	-				NAD
Layer 06									
fibrous material, ligh brown/black	t	30 %	-	-	-				NAD
Layer 07									
foam material, yellov with fibrous backing, black	Ν,	15 %	-	-	-				NAD
Layer 08									
rocky fibrous tar, bla	.ck	5 %	-	-	-				NAD
Layer 09									
fibrous tar, black		5 %	-	-	-				NAD
Layer 10									
fibrous tar, black		5 %	-	-	-				NAD
Layer 11									
fibrous tar, black		5 %	-	-	-				NAD
Layer 12									
fibrous tar, black		5 %	-	-	-				NAD
Layer 13									
fibrous tar, black		5 %	-	-	-				NAD
Other Fibers	Fibrous Glass	Cellulos	Mineral e Wool	Synthetic		Other		Mat	rix
Layer 01	10 %	-	-	8 %		-	-	82	2 %
Layer 02	10 %	4 %	-	8 %		-	-	78	3 %
Layer 03	14 %	-	-	10 %		-	-	76	5 %
Layer 04	-	20 %	-	-		-	-	80	)%



#### **BULK SAMPLE ASBESTOS ANALYSIS**

Phone: (503) 224-5055 http://www.labcorpdx.net

<u>Client:</u>	PBS Engi 4412 SW Portland,	neering and E Corbett Aven OR 97239	Environmen ue	tal				Repo	ort Number: Report Date:	200134R01 01/16/2020
Job	Number:	200134							P.O. No:	n/a
Proje	ect Name:									
Project Proje	Number: ect Notes:	23816.018	Phase 0001							
Layer (	)5	6 %	14 %	-	-		-	-		80 %
Layer (	06	-	90 %	-	-		-	-		10 %
Layer (	)7	-	6 %	-	-		-	-		94 %
Layer (	8	8 %	-	-	-		-	-		92 %
Layer (	)9	4 %	-	-	-		-	-		96 %
Layer 1	10	6 %	2 %	-	-		-	-		92 %
Layer <sup>-</sup>	11	8 %	-	-	-		-	-		92 %
Layer <sup>-</sup>	12	8 %	-	-	-		-	-		92 %
Layer <sup>-</sup>	13	8 %	2 %	-	-		-	-		90 %
Client S Client S <u>Asbest</u>	Sample ID: Sample Des Sos Mineral	23816.018 scription: <u>Fibers</u> F	<b>-0007</b> Layer Percent: C	hrysotile	Sample ID: Amosite	S7 Crocidolite		Date Analyzed: Analyst:	01/16/2020 Danielle de	Montigny Percent Asbestos:
Layer (	)1									
pair	nt, silver		40 %	-	-	-				NAD
Layer (	)2									
rubl with	pery materia woven fibe	al, black rs, white	60 %	-	-	-				NAD
Other I	-ibers	Fibrous Glass	Cellulose	Mineral Wool	Synthetic		Other			Matrix
Layer (	)1	-	2 %	-	-		-	-		98 %
Layer (	)2	-	-	-	3 %		-	-		97 %





Phone: (503) 224-5055 http://www.labcorpdx.net

Layer 10

90 %

Asbestos and Environmental Analysis

Client:	PBS Engir	eering and Environmental	Report Number:	200134R01
	4412 SW ( Portland, (	Corbett Avenue DR 97239	Report Date:	01/16/2020
Job Number: 200134			P.O. No:	n/a
Proje	Project Name:			
Project Number: 23816.018 Phase 0001		23816.018 Phase 0001		
Proje	ct Notes:			

Client Sample ID: 2	23816.018	-0008		Sample ID:	S8		Date Analyzed:	01/16/2020	
<b>Client Sample Descri</b>	iption:						Analyst:	Tim Cammann	
Asbestos Mineral Fit	bers	Layer		• •					Percent
	F	Percent: C	Inrysotile	Amosite	Crocidolite				Asbestos:
Layer 01									
coating, silver		5%	-	-	-				NAD
Layer 02									
fibrous tar, black		5 %	-	-	-				NAD
Layer 03									
tar, black		8 %	-	-	-				NAD
Layer 04									
fibrous tar, black		9 %	-	-	-				NAD
Layer 05									
tar, black		9 %	-	-	-				NAD
Layer 06									
fibrous tar, black, v tar, black	with	10 %	-	-	-				NAD
Layer 07									
compressed fibers	, black	5 %	-	-	-				NAD
Layer 08									
compressed fibers brown	,	20 %	-	-	-				NAD
Layer 09									
foam, off-white		20 %	-	-	-				NAD
Layer 10									
fibrous material, gray/black		9 %	-	-	-				NAD
Other Fibers	Fibrous Glass	Cellulose	Mineral Wool	Synthetic		Other		Mat	rix
Layer 01	-	Trace	-	-		-	-	10	0 %
Layer 02	10 %	-	-	10 %		-	-	80	)%
Layer 03	-	-	-	-		-	-	10	0 %
Layer 04	10 %	-	-	15 %		-	-	75	5%
Layer 05	-	25 %	-	-		-	-	75	5 %
Layer 06	10 %	10 %	-	10 %		-	-	70	)%
Layer 07	-	75 %	-	-		-	-	25	5 %
Layer 08	-	100 %	-	-		-	-	0	%
Layer 09	-	-	-	-		-	-	10	0 %

TESTING NVLAP Lab Code: 200741-

10 %

Page 10 of 13

# LabCor Portland Inc 4321 SW Corbett Ave., Ste A Portland, OR 97239



Phone: (503) 224-5055 http://www.labcorpdx.net

Client:	PBS Engir	eering and Environmental	Report Number:	200134R01
	4412 SW ( Portland, C	Corbett Avenue IR 97239	Report Date:	01/16/2020
Job Number: 200134		200134	P.O. No:	n/a
Proje	ct Name:			
Project Number:		23816.018 Phase 0001		
Proje	ct Notes:			

Client Sample ID: 2	23816.018	3-0009		Sample ID:	S9		Date Analyzed:	01/16/2020	
<b>Client Sample Descri</b>	iption:						Analyst:	Tim Cammann	
Asbestos Mineral Fil	bers	Layer Percent:	Chrysotile	Amosite	Crocidolite				Percent Asbestos:
Layer 01									
coating, silver		5 %	-	-	-				NAD
Layer 02									
fibrous tar, black		5 %	-	-	-				NAD
Layer 03									
tar, black		5 %	-	-	-				NAD
Layer 04									
tar, black		5 %	-	-	-				NAD
Layer 05									
tar, black		5 %	-	-	-				NAD
Layer 06									
fibrous tar, black		5 %	-	-	-				NAD
Layer 07									
compressed fibers	, black	25 %	-	-	-				NAD
Layer 08									
compressed fibers brown	,	15 %	-	-	-				NAD
Layer 09									
foam, off-white		25 %	-	-	-				NAD
Layer 10									
fibrous material, gray/black		5 %	-	-	-				NAD
Other Fibers	Fibrous	6	Mineral						
	Glass	Cellulos	e Wool	Synthetic		Other		Mat	trix
Layer 01	-	-	-	-		-	-	10	0 %
Layer 02	10 %	-	-	15 %		-	-	75	5 %
Layer 03	-	Trace	-	-		-	-	10	0 %

Layer US	-	TIACE	-	-	-	-	100 /8
Layer 04	-	Trace	-	-	-	-	100 %
Layer 05	-	3 %	-	-	-	-	97 %
Layer 06	15 %	-	-	20 %	-	-	65 %
Layer 07	-	95 %	-	-	-	-	5 %
Layer 08	-	100 %	-	-	-	-	0 %
Layer 09	-	-	-	-	-	-	100 %
Layer 10	5 %	75 %	-	-	-	-	20 %

Phone: (503) 224-5055 http://www.labcorpdx.net

Asbestos and Environmental Analysis

<u>Client:</u>	PBS Engir 4412 SW ( Portland, (	eering and Environmental Corbett Avenue DR 97239	Report Number: Report Date:	200134R01 01/16/2020
Job Number: 200134		200134	P.O. No:	n/a
Proje	ct Name:			
Project Number: Project Notes:		23816.018 Phase 0001		

Client Sample ID:	23816.018	8-0010		Sample ID:	S10		Date Analyzed:	01/16/2020	
Client Sample Desc	ription:						Analyst:	Danielle de Montigny	
Asbestos Mineral F	ibers	Layer	Olean a tilla					Percent	
		Percent:	Chrysotile	Amosite	Crocidolite			Asbestos	6 I
Layer 01									_
tar, black with wo fibers, white	ven	5 %	-	-	-			NA	D
Layer 02									
tar, black with wo fibers, white	ven	5 %	-	-	-			NA	D
Layer 03									
tar, black with wo fibers, white	ven	5 %	-	-	-			NA	D
Layer 04									
tar, black with wo fibers, white	ven	5 %	-	-	-			NA	D
Layer 05									
tar, black with wo fibers, white	ven	5 %	-	-	-			NA	D
Layer 06									
compressed fiber	s, black	15 %	-	-	-			NA	D
Layer 07									
compressed fiber brown	s,	40 %	-	-	-			NA	D
Layer 08									
rocky fibrous tar, black/gray		5 %	-	-	-			NA	D
Layer 09									
tar, black with wo fibers, white	ven	5 %	-	-	-			NA	D
Layer 10									
tar, black with wo fibers, white	ven	5 %	-	-	-			NA	D
Layer 11									
tar, black with wo fibers, white	ven	5 %	-	-	-			NA	D
Other Fibers	Fibrous	5	Mineral						
	Glass	Cellulos	se Wool	Synthetic		Other		Matrix	
Layer 01	5 %	8 %	-	10 %		-	-	77 %	
Layer 02	8 %	3 %	-	4 %		-	-	85 %	
Layer 03	5 %	2 %	-	10 %		-	-	83 %	

Page 12 of 13



#### LabCor Lab/Cor Portland, Inc.

#### **BULK SAMPLE ASBESTOS ANALYSIS**

Phone: (503) 224-5055 http://www.labcorpdx.net

Inc

4321 SW Corbett Ave., Ste A Portland, OR 97239

Asbestos and Environmental Analysis

<u>Client:</u>	PBS Engineering and Environmental 4412 SW Corbett Avenue Portland, OR 97239							Repo R	ort Number: 200134R01 eport Date: 01/16/2020
Job Number: 200134							<b>P.O. No:</b> n/a		
Proje	ect Name:								
Project Proje	Number: ect Notes:	23816.018 Phase 0001							
Layer (	04	5 %	-	-	15 %		-	-	80 %
Layer (	05	8 %	Trace	-	15 %		-	-	77 %
Layer (	06	-	60 %	-	-		-	-	40 %
Layer (	07	-	95 %	-	-		-	-	5 %
Layer (	08	20 %	-	-	-		-	-	80 %
Layer (	09	10 %	Trace	-	-		-	-	90 %
Layer 1	10	10 %	Trace	-	-		-	-	90 %
Layer 1	11	10 %	-	-	-		-	-	90 %
<u>Client Sample ID:</u> 23816.018-0011 Client Sample Description:			Sample ID:	S11		Date Analyzed: Analyst:	01/16/2020 Danielle de Montigny		
<u>Asbest</u>	tos Mineral	<u>Fibers</u>	Layer Percent:	Chrysotile	Amosite	Crocidolite			Percent Asbestos:
Homog rubb gray	<b>geneous</b> pery materia y/tan	l,	100 %	-	-	-			NAD
<u>Other I</u>	Fibers	Fibrous Glass -	s Cellulos -	Mineral Se Wool	Synthetic -		Other -	-	Matrix 100 %

This laboratory participates in the National Voluntary Laboratory Accreditation Program (NVLAP). Testing method is per 40 CFR 763 Subpart E, Appendix E, PLM. This report and the data contained therein cannot be used to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the U.S. Government.

• "NAD" is No Asbestos Detected.

· Asbestos consists of the following minerals: chrysotile, amosite, crocidolite, tremolite, actinolite, anthophyllite.

• Material binders, such as those found in vinyl floor tiles, may prevent the detection of small diameter asbestos fibers. A gravimetric preparation and point-count is recommended for such samples.

• Quantitative analysis by PLM point count or TEM may be recommended for samples testing at < or = to 1% asbestos.

• The following estimate of error for this method by visual estimation of asbestos percent are as follows:

1% asbestos: >0-3% error, 5% asbestos: 1-9% error, 10% asbestos: 5-15% error, 20% asbestos: 10-30% error.

• This report pertains only to the samples listed on the report. Report considered valid only when signed by analyst.

**Reviewed by:** 

Danielle de Montigny TEM Technical Manager

Page 13 of 13



# BS 200134 1/2

#### TRANSMITTAL AND CHAIN OF CUSTODY FOR ASBESTOS BULK SAMPLES

**Project No.:** 23816.018 Phase 0001

Individuals signing this form warrant that the information provided is correct and complete. The Sender should keep a copy and send the original. The Receiver should complete the form, keep a copy and return the original to the Sender. Receiver shall report damage of package immediately to Sender.

#### SENDER

Sender's ID No.

Date Sent: January 10, 2020

**PBS Engineering and Environmental Inc.** 4412 SW Corbett Avenue Portland, OR 97239 503.248.1939, Fax: 866.727.0140

RECEIVER

1/10/2020 Date Received:

Company: Lab Cor Address:

4321 SW Corbett Ave Ste A Portland, OR 97239

503-224-5055

hu HZName

ed Signature Author

am

Receiver's ID No.

SUNC Name 10.2 Authorized Signature Time Date

**Brief Description** 

23816.018-0001	
23816.018-0002	
23816.018-0003	
23816.018-0004	
23816.018-0005	
23816.018-0006	
23816.018-0007	
23816.018-0008	
23816.018-0009	
23816.018-0010	
23816.018-0011	

.

### 200134 2/2 **NPBS**

#### TRANSMITTAL AND CHAIN OF CUSTODY FOR ASBESTOS BULK SAMPLES

\_\_\_\_\_

Please analyze the enclosed 11 sample(s) for asbestos content using PLM with dispersion staining. PBS requests prior notification if samples will be disposed.

\_\_\_\_\_

.....

Request verbal results by: \_\_\_\_\_ AM/PM \_\_\_\_\_Date.

\_\_\_\_\_.

Please fax and mail the results to the above address.

TURNAROUND DESIRED: 72 Hour \_ .\_\_\_\_

SPECIAL INSTRUCTIONS:

THIS IS TO CERTIFY THAT

N.M.

# JAMES MASTANDUNO

# HAS SUCCESSFULLY COMPLETED THE TRAINING COURSE

1/ W

for

# **ASBESTOS INSPECTOR / MANAGEMENT** PLANNER REFRESHER

 $m \propto$ 

In accordance with TSCA Title II, Part 763, Subpart E, Appendix C of 40 CFR

Certificate: Course Location: Course Date: IMR-20-4993B Portland, OR 01/10/2020



of Toxic Substance Control Act (TSCA) Emergency Response Act enacting Title II AHERA is the Asbestos Hazard

**Expiration Date:** 01/10/2021

4412 SW Corbett Avenue PBS Environmental certificate contact:

Portland, OR 97239

503) 248-1939

For verification of the authenticity of this

Andy Fridley, Instructor

-END of Addendum Peter Madaus Contract Specialist