



Wayne RESA

Wayne RESA Education Center Transformer Replacement

Wayne, Michigan



List of Drawings
COVER

ELECTRICAL

E0.1	ELECTRICAL REFERENCE INFORMATION
E0.2	FIRST FLOOR COMPOSITE PLAN
E0.3	PENTHOUSE COMPOSITE PLAN
E3.1	FIRST FLOOR POWER PLAN - UNIT A
E3.2	PENTHOUSE POWER PLAN - UNIT A
E5.1	ONE LINE DIAGRAM - EXISTING WORK
E5.2	ONE LINE DIAGRAM - DEMOLITION WORK
E5.3	ONE LINE DIAGRAM - NEW WORK

WAYNE RESA SERVER ROOM CONSTRUCTION NOTE

SERVER ROOM A158A CONTAINS CRITICAL EQUIPMENT VITAL TO SERVER ROOM OPERATIONS. THIS ROOM SHALL REMAIN ACTIVE AND OCCUPIED BY THE OWNER THROUGHOUT CONSTRUCTION. CONTRACTORS SHALL COMPLETE ALL WORK IN THIS ROOM WITH THE UTMOST CARE. AT NO TIME SHALL THE CONTRACTOR'S ACTIVITIES IMPEDE SERVER ROOM OPERATIONS. THE FOLLOWING SHALL BE OBSERVED:


- EXISTING EQUIPMENT MAY NOT BE USED TO SUPPORT CONTRACTORS, TOOLS, MATERIALS, TEMPORARY WALLS, DRAWINGS, LADDERS, ETC.
- CONTAIN ALL DUST AND DEBRIS BY ENCLOSING WORK WITH A 1-HOUR FIRE-RESISTANCE-RATED POLYETHYLENE SHEET.
- MAINTAIN AIR FLOW TO/FROM ALL EQUIPMENT.
- CLEAN ALL WORK AREAS REGULARLY TO LIMIT COLLECTION AND SPREAD OF DUST AND DEBRIS.
- WET SAWS SHALL NOT BE USED IN THE SERVER ROOM.
- GENERATING DUST IN THE SERVER ROOM IS PROHIBITED.
- COORDINATE AND SCHEDULE ALL WORK WITH OWNER.

NO SHUTDOWNS, DISCONNECTS, REMOVAL OF POWER OR ANY SIMILAR ACTIONS TOWARD AND EXISTING SERVER ROOM EQUIPMENT SHALL BE ALLOWED, BY ANY MEANS AND AT ANY TIME WITHOUT PRIOR EXPRESS CONSENT, COORDINATION AND DIRECTION BY THE OWNER.

APPLICABLE CONSTRUCTION CODES AND STANDARDS

BUILDING:	MICHIGAN DEPARTMENT OF LICENSING AND REGULATORY AFFAIRS, BUREAU OF CONSTRUCTION CODES, 2015 MICHIGAN REHABILITATION CODE FOR EXISTING BUILDINGS, INCORPORATING THE 2016 EDITION OF THE INTERNATIONAL EXISTING BUILDING CODE
ELECTRICAL:	MICHIGAN DEPARTMENT OF LICENSING AND REGULATORY AFFAIRS, 2017 MICHIGAN ELECTRICAL CODE, INCORPORATING THE 2017 EDITION OF THE NATIONAL ELECTRICAL CODE

Site Map



Code Information

© 2019 INTEGRATED design SOLUTIONS, LLC

Issued for Issue Date

95% Owner Review	10-09-2020
Bids	10-16-2020

Registration Seal

IDS Project Number

18243-1000

Signature

Date

Signature

Date

Signature

Date

ABBREVIATIONS

[illegible]

SYMBOLS

[illegible]

SYMBOL LEGEND

The diagram illustrates four types of callouts used in architectural drawings:

- DETAIL:** A circle with a diagonal line through it. The top part contains the number '2' and the bottom part contains 'E2.1'. Labels point to the circle as 'DETAIL IDENTIFICATION' and to the text 'DETAIL SCALE' below it. A note states: 'DRAWING WHERE DETAIL IS REFERENCED OR CUT'.
- ELEVATION SYMBOL:** A diamond with a diagonal line through it. The top part contains the number '2' and the bottom part contains 'E3.1'. Labels point to the diamond as 'ELEVATION NUMBER' and to the text 'COLUMN CENTERLINE' below it. A note states: 'DRAWING WHERE ELEVATION IS DRAWN'.
- SECTION LOCATOR:** A circle with a diagonal line through it. The top part contains the number '2' and the bottom part contains 'E9.1'. A label points to the circle as 'PLAN OR DETAIL IDENTIFICATION'. A note states: 'DRAWING WHERE PLAN OR DETAILS IS DRAWN'.
- ROOM NAME AND NUMBER:** A rectangle with a diagonal line through it. The top part contains the text 'ROOM NAME' and the bottom part contains 'A101'. Labels point to the rectangle as 'EXISTING' and 'NEW'. A note states: 'DRAWING WHERE ROOM IS DRAWN'.

MOUNTING HEIGHTS

Figure 1: Mounting Heights. This diagram illustrates the recommended mounting heights for various electrical and communication devices. The heights are specified in feet and inches.

- BATTERY OPERATED PULL STATION: 7'-8"
- CLOCKS: 7'-8"
- SPEAKERS: 7'-8"
- EXIT LIGHTS: 7'-8"
- ALL TYPES OF SWITCHES: 7'-8"
- FIRE ALARM PULL STATION: 7'-8"
- VOLUME CONTROLS: 7'-8"
- CARD ACCESS SYSTEMS: 7'-8"
- READER: 7'-8"
- KEY SWITCH: 7'-8"
- RECEPTACLE OUTLET FOR TV MONITOR: 7'-6"
- TELEVISION OUTLET FOR TV MONITOR: 7'-6"
- RECEPTACLE OUTLET: 7'-6"
- COMMUNICATIONS OUTLET: 7'-6"
- MICROPHONE OUTLET: 7'-6"
- AUDIO FIRE ALARM INDICATING DEVICE: 7'-6"
- AUDIO VISUAL FIRE ALARM INDICATING DEVICE: 6'-10"
- VISUAL FIRE ALARM INDICATING DEVICE: 6'-10"
- TELEPHONE OUTLET: 4'-0"
- INTERCOM CALL BUTTON: 4'-0"

ELECTRICAL DRAWING INDEX

E0.1	ELECTRICAL REFERENCE INFORMATION
E0.2	FIRST FLOOR COMPOSITE PLAN
E0.3	PENTHOUSE COMPOSITE PLAN
E3.1	FIRST FLOOR POWER PLAN - UNIT A
E3.2	PENTHOUSE POWER PLAN - UNIT A
E5.1	ONE LINE DIAGRAM - EXISTING WORK
E5.2	ONE LINE DIAGRAM - DEMOLITION WORK
E5.3	ONE LINE DIAGRAM - NEW WORK

U
UH
UL
UON
UPS
USB
UV

V
VCR
VFC
VIF
VP
VTS

W
WAN
WAP
WG
WP

X
XP

Misc

3R
4X
Z
OR CL
C
C
+
+
+

C
PH
W

UNIT HEATER
UNDERWRITERS LABORATORIES INC.
UNLESS OTHERWISE NOTED
UNINTERRUPTED POWER SUPPLY
UNIVERSAL SERIAL BUS
UNIT VENTILATOR

V
VIDEO CASSETTE RECORDER
VARIABLE FREQUENCY CONTROLLER
VERIFY IN FIELD
VAPORPROOF
VIDEO TAPE STORAGE

W
WIDE AREA NETWORK
WIRELESS ACCESS POINT
WIRE GUARD
WEATHERPROOF

X
EXPLOSION PROOF

GENERAL NOTES

1. LIGHT LINE WEIGHT OR THE LETTER (E) INDICATES EXISTING EQUIPMENT. HEAVY LINE WEIGHT INDICATES NEW EQUIPMENT. THE LETTER (R) INDICATES RELOCATED EXISTING EQUIPMENT TO BE RELOCATED, DISCONNECT, REMOVE, AND STORE ITEMS BEING RELOCATED FOR NEW CONSTRUCTION. THE LETTER (S) INDICATES NEW WORK PLANS; SLASH MARKS INDICATE EQUIPMENT TO BE DISCONNECTED AND REMOVED.
2. PROVIDE AN OVERALL GROUNDING CONDUCTOR FOR ALL FEEDERS AND BRANCH CIRCUITS. PROVIDE A SEPARATE DEDICATED NEUTRAL CONDUCTOR FOR EACH BRANCH CIRCUIT PHASE CONDUCTOR.
3. WHERE CONDUTS PENETRATE FIRE WALLS/BARRIERS, FIRE SEAL THE PENETRATION TO A FIRE RATING EQUAL TO OR GREATER THAN THE ORIGINAL FIRE RATING OF THE WALL/BARRIER.
4. FURNISH ALL LABOR, MATERIALS, EQUIPMENT, AND SUPERVISION REQUIRED TO COMPLETE ALL DEMOLITION OF EXISTING ELECTRICAL SYSTEMS SPECIFIC TO THE PROJECT. THE CONTRACTOR SHALL RELOCATE ALL ITEMS AS REQUIRED TO FACILITATE THE NEW CONSTRUCTION, COORDINATE THE DEMOLITION REQUIREMENTS WITH THE ARCHITECT.
5. CARE SHALL BE TAKEN NOT TO DISRUPT ANY ELECTRICAL SYSTEMS REMAIN DURING DEMOLITION. WHERE REMOVAL OF CONDUIT AND WIRING AFFECTS THE OPERATION OF "UPSTREAM" AND/OR "DOWNSTREAM" ELECTRICAL SYSTEMS, THE CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE ADDITIONAL CONDUIT AND WIRING TO RESTORE THE "UPSTREAM" AND "DOWNSTREAM" UTILIZATION EQUIPMENT TO ITS ORIGINAL FUNCTION.
6. ALL CONSTRUCTION IN THE BUILDING AND ITS ELECTRICAL SYSTEMS SHALL BE COMPLETED IN CLOSELY COORDINATED PHASES TO MINIMIZE SHUTDOWNS AND USER DISRUPTIONS.
7. ALL WORK AND EQUIPMENT SHALL CONFORM TO NEC, THE NATIONAL ELECTRICAL SAFETY CODE, AND THE CITY OF SEATTLE SECTION 110-3 (c) AND (d).
8. PROVIDE LABELING / W/ NAMEPLATES FOR NEW EQUIPMENT / DEVICES CALLED AS REQUIRED PER OWNER'S LABELING STANDARDS.

Project Title

WAYNE RESA

Leading...Learning for All

Wayne RESA Education Center Transformer Replacement

Wayne, Michigan

Key Plan

	Project Administrator
	M. Nowicki
	Project Designer
	E. Young
	Project Architect / Engineer
	E. Young
	Drawing Board
	E. Young
	Q.M. Review
	M. Barden
	Approver
	M. Nowicki
	Drawing Scale
	N.T.S

Issued for	Issue Date
95% Owner Review	10-09-2021
Bids	10-16-2021



© 2019 INTEGRATED design SOLUTIONS, LLC
Drawing Title


Electrical Reference Information

IDS Project Number Drawing Number

20110-1000

E0.1



1 FIRST FLOOR POWER PLAN - AREA A
E0.2 1/8" = 1'-0"MOBILE AIR, INC.
Corporate Office
800 E. Mandoline Ave.
Madison Heights, MI 48071**Specifications****RT-PAC6034**

- 60,050 Btu/h
- 480 volt, 3 phase
- 12.4 amp power consumption
- 30 amp recommended fuse size
- 7765-C Non-NEMA plug type (Hubbelle-HBL7765C)
- Electronic thermostat
- Evaporator CFM 1950
- Evaporator maximum external static pressure 0.50" WC
- Condenser CFM 2900
- Condenser static pressure 0.50" WC
- Power cord 6 AWG 4 ft.
- Auto condensate pump
- Operating range 65-95 degrees F
- Dimensions: 28 1/4"W x 46"D x 52 1/2"H
- Net weight 460lbs / shipping weight 500lbs
- Sound level 78dB

With Local Offices to Serve you in: Indiana - Illinois - Kentucky - Michigan - Ohio - Pennsylvania - Wisconsin - Missouri

800-596-0800


GENERAL NOTES

1. CONTRACTORS SHALL PUT THE SERVER ROOM FIRE PROTECTION SYSTEM (HALON) IN BY-PASS MODE PRIOR TO ANY WORK IN THE SERVER ROOM. RESTORE THE FIRE PROTECTION SYSTEM BACK TO NORMAL MODE AFTER THE COMPLETION OF THE WORK. COORDINATE WITH OWNER REPRESENTATIVE ON THE LOCATION OF THE FIRE PROTECTION SYSTEM.
2. THERE SHALL NOT BE A COMPLETE SHUT DOWN OF THE DATA CENTER AT NO TIME DURING CONSTRUCTION.
3. EXISTING PANEL PP-EM WILL PROVIDE POWER TO THE TEMPORARY COOLING UNITS VIA A TEMPORARY PORTABLE GENERATOR (SEE KEYNOTE 2). CAM-LOCK CABLES WILL BE PROVIDED FOR THE GENERATOR CONNECTION.
4. CONTRACTOR SHALL PROVIDE DUST AND DEBRIS PROTECTION IN THE DATA CENTER DURING CONSTRUCTION IN THE DATA CENTER.
5. CONTRACTOR SHALL COMPLETE AS MUCH WORK AS POSSIBLE BEFORE SWITCHING THE POWER TO GENERATOR POWER TO MINIMIZE THE SHUTDOWN TIME OF THE UPS AND THE RUN TIME ON THE GENERATORS.
6. CONTRACTOR SHALL REPAIR OR REPLACE LANDSCAPE DAMAGE DURING CONSTRUCTION.
6. ALL CONSTRUCTION PREP WORK SHALL BE DONE THE FRIDAY BEFORE THE TRANSFORMER REPLACEMENT AND POWER SHUT DOWN. TRANSFORMER REPLACEMENT SHALL BE COMPLETED THE FOLLOWING SATURDAY. COORDINATE SHUT DOWN WITH OWNER REPRESENTATIVE AND WAYNE RESA IT DEPARTMENT MANAGER.

KEYNOTES

1. CONTRACTOR SHALL PROVIDE A SHEET OF PLYWOOD TO TEMPORARILY COVER THE WEST DOOR OPENING TO SERVER ROOM A158A. THE PLYWOOD SHALL BE SEALED TO PREVENT COOLING LOSS. THE PLYWOOD SHALL HAVE (17) HOLES FOR THE EXHAUST DUCTS FROM THE TEMPORARY COOLING UNITS. COORDINATE THE SIZE OF THE OPENING WITH THE TEMPORARY COOLING UNIT SUPPLIER.
2. CONTRACTOR SHALL PROVIDE A TEMPORARY PORTABLE GENERATOR FOR TEMPORARY POWER TO TEMPORARY PORTABLE COOLING UNITS.
3. PROVIDE 4" CONDUIT SLEEVE IN DATA CENTER WALL FOR TEMPORARY CABLES TO THE FDC AND PORTABLE GENERATOR. PROVIDE HINGED BOXES ON THE INTERIOR AND EXTERIOR WALL OF THE DATA CENTER.
4. CONTRACTOR SHALL PROVIDE A SECOND TEMPORARY GENERATOR FOR POWER TO THE FDC "A" SIDE OF THE PANEL. CONTRACTOR TO PROVIDE ALL CABLES (50FT) AND CONNECTORS REQUIRED TO CONNECT THE GENERATOR TO THE EXISTING FDC.
5. EXISTING SIMPLEX RECEPTACLES MOUNTED TO THE BOTTOM OF THE EXISTING CABLE TRAY FOR TEMPORARY COOLING UNITS. RECEPTACLES ARE FEED FROM EXISTING PP-EM.

PANELBOARD SCHEDULE							PP-EM (Existing)	
250 AMP/5 MLO								
CKT.	LOAD	CB	A	B	C	CB	LOAD	CKT.
1		100	3436					2
3	Spare			3436		30	Server Room A158A Overhead	4
5					3436		Receptacle for Portable Cooling Unit	6
7	Server Room A158A Overhead	30	3436	3436		30	Server Room A158A Overhead	8
9	Receptacle for Portable Cooling Unit			3436	3436		Receptacle for Portable Cooling Unit	10
11					3436	3436		12
13	Server Room A158A Overhead	30	3436	3436		30	Server Room A158A Overhead	14
15	Receptacle for Portable Cooling Unit			3436	3436		Receptacle for Portable Cooling Unit	16
17					3436	3436		18
19	Server Room A158A Overhead	30	3436			30	Server Room A158A Overhead	20
21	Receptacle for Portable Cooling Unit			3436		30	Receptacle for Portable Cooling Unit	22
23					3436			24
25	Space						Space	26
27	Space						Space	28
29	Space						Space	30
Panel Information			Symbols			Load Classification Total Connected Load		
Volts: 480/277 Wye			Note: All Symbols May Not Be Used			Receptacle 0 VA		
Mounting: Flush			* PROVIDE LOCK ON ATTACHMENT			Equipment 61848 VA		
A.I.C. (RMS Symmetrical): 22000			# PROVIDE SWD RATED BREAKER			Lighting 0 VA		
Phase: 3			@ PROVIDE GFCI TYPE BREAKER			Kitchen 0 VA		
Wire: 4			+ PROVIDE AFCI TYPE BREAKER					
Hertz: 60								
PHASE A CONNECTED LOAD:						20,616 VA		
PHASE B CONNECTED LOAD:						20,616 VA		
PHASE C CONNECTED LOAD:						20,616 VA		
TOTAL CONNECTED LOAD:						61,848 VA		
TOTAL ESTIMATED DEMAND LOAD:						61,848 VA		
TOTAL ESTIMATED DEMAND AMPS:						74.4 A		

Wayne, Michigan
Key Plan

Project Administrator

M. Nowicki

Project Designer

E. Young

Project Architect / Engineer

E. Young

Drawn By

E. Young

G.M. Review

M. Barden

Approved

M. Nowicki

Drawing Scale

1/8" = 1'-0"

Issued for

Issue Date

95% Owner Review

10-09-2020

Bids

10-16-2020

© 2019 INTEGRATED design SOLUTIONS, LLC

Drawing Title

First Floor Power Plan - Unit A



1. PROVIDE ALLOWANCE TO REPLACE THE EXISTING WIRE TROUGH AND FEEDER CABLES TO THE DISCONNECT SWITCH AND MAINTENANCE BY-PASS SWITCHBOARD IF THE NEW TRANSFORMER IS DEEPER THEN THE EXISTING TRANSFORMER.

- 1 CONNECT TEMPORARY FEEDER CABLES TO EXISTING PANEL PP-EM TO THE TEMPORARY GENERATOR FOR POWER TO THE TEMPORARY COOLING UNITS IN THE DATA CENTER.
- 2 INSTALL TEMPORARY COOLING UNITS IN THE DATA CENTER AND CONNECT THEM TO THE TEMPORARY RECEPTS LOCATED AT THE BOTTOM OF THE EXISTING CABLE TRAY IN THE DATA CENTER.
- 3 START THE GENERATOR FOR THE TEMPORARY COOLING UNITS AND TURN ON THE COOLING UNITS.
- 4 TURN OFF ONE OF THE DATA CENTER COOLING UNITS MAKE SURE TEMPORARY COOLING UNITS ARE HOLDING THE DATA CENTER TEMPERATURE AND THE RECEPTS COOLING UNITS ARE MAINTAINING THE TEMPERATURE THEN TURN OFF THE SECOND DATA CENTER COOLING UNIT.
- 5 TURN OFF THE CIRCUIT BREAKER IN EXISTING DP-UPS FOR THE "A" SIDE OF THE FDC.
- 6 DISCONNECT THE CABLES TO THE "A" SIDE OF THE FDC AND COIL INSIDE THE FDC FOR RECONNECTION.
- 7 CONNECT THE TEMPORARY CABLES AND ASSOCIATED CONNECTORS FROM THE GENERATOR TO THE "A" SIDE LOGS INSIDE THE FDC.
- 8 START THE GENERATOR FOR THE TEMPORARY FEEDER TO THE DATA CENTER.
- 9 ONCE GENERATOR IS RUNNING, TURN OFF THE CIRCUIT BREAKER TO THE "B" SIDE OF THE FDC IN DP-UPS.
- 10 COORDINATE WITH THE DATA REPRESENTATIVE ON THE SHUT DOWN OF THE DATA CENTER DRY COOLERS, PUMPS, PNL-UPS-1, DP-UPS-1, DP-UPS-2 BEFORE SHUTTING DOWN THE UPS AND TRANSFORMER.
- 11 TURN OFF THE FUSIBLE SWITCH IN SWITCHBOARD M2 TO THE UPS MAINTENANCE BY-PASS SWITCHBOARD.
- 12 DISCONNECT THE EXISTING FEEDER WIRES FROM THE TRANSFORMER AND THE TRANSFORMER FEEDER WIRES FROM THE TRANSFORMER. GROUND WIRES SHALL REMAIN AND BE RECONNECTED TO THE NEW TRANSFORMER.
- 13 REMOVE THE EXISTING TRANSFORMER AND INSTALL THE NEW TRANSFORMER IN THE EXACT SAME LOCATION.
- 14 RECONNECT THE EXISTING FEEDER AND GROUND WIRES TO THE NEW TRANSFORMER.
- 15 CONTRACTOR SHALL DO ANY FIELD TESTING AS REQUIRED PER SPECIFICATIONS.
- 16 CONTRACTOR SHALL TURN ON THE FUSIBLE SWITCH IN SWITCHBOARD M2 TO RE-ENERGIZE THE UPS AND TRANSFORMER.
- 17 CONTRACTOR SHALL COORDINATE WITH OWNER AND DATA CENTER REPRESENTATIVE TO TURN OFF TEMPORARY COOLING UNITS, DRY COOLERS, PUMPS, PNL-UPS-1, DP-UPS-1, DP-UPS-2.
- 18 CONTRACTOR SHALL TURN ON THE CIRCUIT BREAKER TO THE "B" SIDE OF THE FDC IN DP-UPS.
- 19 CONTRACTOR SHALL DISCONNECT AND REMOVE THE TEMPORARY FEEDER CABLES TO THE "A" SIDE OF THE FDC AND RECONNECT THE FEEDER CABLES TO THE "B" SIDE OF THE FDC.
- 20 CONTRACTOR SHALL TURN ON THE CIRCUIT BREAKER TO THE "A" SIDE OF THE FDC IN DP-UPS.
- 21 CONTRACTOR SHALL REMOVE THE TEMPORARY FEEDER CABLES AND COIL INSIDE THE DATA COOLING UNITS ARE RUNNING AND DATA CENTER IS MAINTAINING IT DESIRE TEMPERATURE.
- 22 CONTRACTOR SHALL REMOVE ALL TEMPORARY CABLES, REMOVE GENERATORS AND CLEAN UP OF THE INSTALLATION AREA.



