

**NOTICE:** These documents are instruments of professional service, and information contained therein is incomplete unless used in conjunction with DLR Group's interpretations, decisions, observations and administrations. Use or reproduction of these documents in whole or in part without DLR Group's consent is in violation of common law, copyrights, statutory and other reserved rights, which preempts state and local public records act. Portions of these specifications were created with the MasterSpec® specification writing system, are subject to the copyright of the American Institute of Architects, and require a current MasterSpec® license for editing or use on other projects.



## SECTION 000110 - TABLE OF CONTENTS

## **DIVISION 00 - CONDITIONS OF THE CONTRACT (IN FUTURE ISSUANCE)**

## **DIVISION 01 – GENERAL REQUIREMENTS**

- 011000 SUMMARY
- 012300 ALTERNATES
- 012500 SUBSTITUTION PROCEDURES
- 012500A SUBSTITUTION REQUEST FORMS
- 012600 CONTRACT MODIFICATION PROCEDURES
- 012900 PAYMENT PROCEDURES
- 013100 PROJECT MANAGEMENT AND COORDINATION
- 013200 CONSTRUCTION PROGRESS DOCUMENTATION
- 013300 SUBMITTAL PROCEDURES
- 013516 ALTERATION PROJECT PROCEDURES
- 014000 QUALITY REQUIREMENTS
- 014200 REFERENCES
- 016000 PRODUCT REQUIREMENTS
- 016116 DELEGATED DESIGN REQUIREMENTS
- 017300 EXECUTION
- 017419 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
- 017700 CLOSEOUT PROCEDURES
- 017823 OPERATION AND MAINTENANCE DATA
- 017839 PROJECT RECORD DOCUMENTS
- 017900 DEMONSTRATION AND TRAINING

## **DIVISION 02 – EXISTING CONDITIONS**

024119 SELECTIVE DEMOLITION

## **DIVISION 03 – CONCRETE**

033000 CAST-IN-PLACE CONCRETE

## DIVISION 04 – MASONRY (NOT USED)

## DIVISION 05 – METALS (NOT USED)

## **DIVISION 06 – WOOD, PLASTICS, AND COMPOSITES**

066400 PLASTIC PANELING

## **DIVISION 07 – THERMAL AND MOISTURE PROTECTION**

077200	ROOF ACCESSORIES
078413	PENETRATION FIRESTOPPING
079513.13	INTERIOR EXPANSION JOINT COVER ASSEMBLIES

## **DIVISION 08 – OPENINGS (NOT USED)**

## **DIVISION 09 – FINISHES**

092216	NON-STRUCTURAL METAL FRAMING
092900	GYPSUM BOARD
095113	ACOUSTICAL PANEL CEILINGS
096513	<b>RESILIENT BASE AND ACCESSORIES</b>
096516	<b>RESILIENT SHEET FLOORING</b>
096519	<b>RESILIENT TILE FLOORING</b>

099123 INTERIOR PAINTING

## **DIVISION 10 – SPECIALTIES**

101100	VISUAL DISPLAY UNITS
102600	WALL AND DOOR PROTECTION
102800	TOILET AND CUSTODIAL ACCESSORIES

## **DIVISION 11 – EQUIPMENT**

114000	FOOD SERVICE EQUIPMENT
115200	AUDIO VISUAL EQUIPMENT

## **DIVISION 12 – FURNISHINGS**

122413 ROLLER WINDOW SHADES

## **DIVISION 13 – SPECIAL CONSTRUCTION (NOT USED)**

## **DIVISION 14 – CONVEYING EQUIPMENT (NOT USED)**

## **DIVISION 21 – FIRE SUPPRESSION**

- 210523 GENERAL-DUTY VALVES FOR FIRE PROTECTION PIPING
- 210529 HANGERS AND SUPPORTS FOR FIRE SUPPRESSION PIPING AND EQUIPMENT
- 210553 IDENTIFICATION FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT
- 211313 WET-PIPE SPRINKLER SYSTEMS

## **DIVISION 22 – PLUMBING**

- 220518 ESCUTCHEONS FOR PLUMBING PIPING
- 220523.12 BALL VALVES FOR PLUMBING PIPING
- 220523.14 CHECK VALVES FOR PLUMBING PIPING
- 220529 HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT
- 220548 VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT

WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

220552	IDENTIFICATION FOD DI UNADING DIDING AND FOUIDMENT
220333	
<b>11</b> 00000	

- 220719 PLUMBING PIPING INSULATION
- 221116 DOMESTIC WATER PIPING
- 221119 DOMESTIC WATER PIPING SPECIALTIES
- 221316 SANITARY WASTE AND VENT PIPING
- 221319 SANITARY WASTE PIPING SPECIALTIES
- 221319.13 SANITARY DRAINS
- 221323 SANITARY WASTE INTERCEPTORS

## DIVISION 23 – HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

- 230529 HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT
- 230548 VIBRATION AND SEISMIC CONTROLS FOR HVAC
- 230553 IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT
- 230593 TESTING, ADJUSTING, AND BALANCING FOR HVAC
- 230713 DUCT INSULATION
- 230800 HVAC COMMISSIONING REQUIREMENTS
- 230923 DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC
- 231123 FACILITY NATURAL-GAS PIPING
- 233113 METAL DUCTS
- 233300 AIR DUCT ACCESSORIES
- 233423 HVAC POWER VENTILATORS
- 233533 LISTED KITCHEN VENTILATION SYSTEM EXHAUST DUCTS
- 237423.16 PACKAGED, INDIRECT-FIRED, OUTDOOR, MAKEUP-AIR UNITS

# **DIVISION 26 – ELECTRICAL**

260500	COMMON WORK RESULTS FOR ELECTRICAL
260519	LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES
260529	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
260533	RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS
260553	IDENTIFICATION FOR ELECTRICAL SYSTEMS
262726	WIRING DEVICES

## **DIVISION 27 – COMMUNICATIONS**

270000	COMMUNICATIONS
270500	COMMON WORK RESULTS FOR COMMUNICATIONS
270528	PATHWAYS FOR COMMUNICATIONS SYSTEMS
270528.29	HANGERS AND SUPPORTS FOR COMMUNICATIONS SYSTEMS
270553	IDENTIFICATION FOR COMMUNICATIONS SYSTEMS
271513	COMMUNICATIONS COPPER HORIZONTAL CABLING
274100	AUDIO-VIDEO SYSTEMS
274123	AUDIO-VIDEO ACCESSORIES

# DIVISION 28 – ELECTRONIC SAFETY AND SECURITY (NOT USED)

# **DIVISION 31 – EARTHWORK (NOT USED)**

## **DIVISION 32 – EXTERIOR IMPROVEMENTS (NOT USED)**

# **DIVISION 33 – UTILITIES (NOT USED)**

## SECTION 011000 - SUMMARY

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Project information.
  - 2. Work covered by Contract Documents.
  - 3. Work by Owner.
  - 4. Owner-furnished products.
  - 5. Access to site.
  - 6. Work restrictions.
  - 7. Specification and Drawing conventions.

#### 1.3 PROJECT INFORMATION

- A. Project Identification:
  - 1. Culinary Classroom at Westview High School
  - 2. Project Location: 4200 NW 185<sup>th</sup> Ave, Portland, OR 97229
- B. Owner: Beaverton School District. Owner's Representative: Kurt Meeuwsen Construction Project Manager Facilities Development Department 16550 SW Merlo Road Beaverton, OR 97003 (503) 964-2091
- C. Architect: DLR Group.
- D. Web-Based Project Software: Project software administered by Owner will be used for purposes of managing communication and documents during the construction stage.
  - 1. See Beaverton School District standards for requirements for using web-based Project software.

#### SUMMARY

011000 - 1

## 1.4 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of Project is defined by the Contract Documents and consists of the following:
  - 1. Upgrade an existing culinary classroom with new food service equipment, plumbing fixtures, and interior finishes. Replace kitchen exhaust hoods and add make-up air system to accommodate current code requirements.
  - 2. Construction will include demolition of the existing casework and residential hoods, ranges, and plumbing fixtures.
- B. Type of Contract:
  - 1. Project will be constructed under a single prime contract (per AIA documents A101-2007 and A201-2007).
- C. Project Considerations:
  - 1. The school will be vacated by the end of June 2021 and the upgraded classroom must be operational at the beginning of the 2021 fall school year.
  - 2. The existing school was built in 1993 and no hazardous materials are expected. If encountered, abatement will be done by the District (BSD) under separate contract. General Contractor shall coordinate scheduling, demolition, and building locations with abatement subcontractor, District Representative, and District Consultant. New construction shall not commence until completion of hazardous material abatement.
- D. Services to Provide:
  - 1. Once through the two-step solicitation process, the awarded Contractor is responsible for providing a complete project per the Construction Documents including materials, labor, equipment and coordination with the District and the design team.
- E. Specific Construction Services Description:
  - 1. Coordinate weekly construction meetings with the District and the design team.
  - 2. Prepare site and building logistics plans to encompass all proposed activities and impacts to the site, adjacent properties, and neighboring streets.
  - 3. Fully coordinate the work of subcontractors and suppliers. Provide regular and on-going quality inspection and assistance to the design team in ensuring that the Work meets the Specifications and applicable codes.
  - 4. Coordinate inspections with the authority have jurisdiction (AHJ) and third-party special inspections (provided by the District).
  - 5. Review and expedite Change Order requests and maintain logs.
  - 6. Coordinate with BSD FF&E efforts.
  - 7. Monitor compliance with payment of prevailing wages on all contracts and subcontracts, per ORS 279C.
  - 8. Maintain in a current condition Project Records including, but not necessarily limited to permits, Construction Documents, as-built records, meeting records, submittals, inspection reports, invoices, delivery receipts, daily activity logs, Requests for Information (RFI); RFI logs; Submittals; Submittal Logs; Inspection Reports; Change Order Proposals (COP);

#### SUMMARY

COP logs; Change Orders (CO); CO logs; Construction Change Directives (CCD); CCD logs; Architect's Supplemental Instructions (ASI); ASI logs; Permits; Project Allowance(s) Reconciliation; Project Contingency status reports; and Project Schedule updates.

- 9. Transmit copies of MWESB Contact Logs, Career Learning Reports and Apprenticeship Program Logs monthly via eBuilder (as required).
- 10. Intelligent and selective use of Building Information Modeling (BIM), where applicable.
- 11. Use of the district's internet-based e-builder project management system for coordination of efforts, approvals, and expedited communication is required.
- F. Solicitation and Selection Process Schedule:

Process Milestones	Dates	
ITB		
Advertise	February 11, 2021	
Release ITB	February 16, 2021	
Pre-Bid Conference	February 23, 2021 at 3:00 p.m. at Westview High School	
Deadline for Questions	February 26, 2021	
Issue Addendum	March 2, 2021	
Bids Due	March 9, 2021 by 2:00 p.m.	
Notice of Intent to Award	March 11, 2021	
School Board Approval	March 15, 2021	
Award Contract	On or about March 17, 2021	

G. Construction Schedule Milestones:

Milestones	Dates
Last Teacher day/Move out furnishings	June 18 / June 21, 2021
Mobilization on site & Demolition	On or about June 22, 2021
Construction Substantial Completion	August 1, 2021

#### SUMMARY

011000 - 3

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

Final Completion	August 15, 2021; Owner must be able
	to place FF&E

\*The dates under ITB and Construction Schedule Milestones are for reference only. The District may modify as needed.

## 1.5 WORK BY OWNER

Г

A. General: Cooperate fully with Owner so work may be carried out smoothly, without interfering with or delaying work under this Contract or work by Owner. Coordinate the Work of this Contract with work performed by Owner.

### 1.6 OWNER-FURNISHED PRODUCTS

- A. Owner will furnish products indicated. The Work includes receiving, unloading, handling, storing, protecting, and installing Owner-furnished products and making building services connections.
- B. Owner-Furnished Products:
  - 1. As noted in Owner Furnished Material and Equipment Schedule in drawing set.

#### 1.7 ACCESS TO SITE

A. General: Contractor shall have access to the Project site during the construction period according to AIA201 3.13.

#### 1.8 WORK RESTRICTIONS

- A. Work Restrictions, General: Comply with restrictions on construction operations.
  - 1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.
- B. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:
  - 1. Notify Owner not less than two days in advance of proposed utility interruptions.
  - 2. Obtain Owner's written permission before proceeding with utility interruptions.
- C. Restricted Substances: Use of tobacco products and other controlled substances on Project site is not permitted.

#### SUMMARY

011000 - 4

- D. Employee Identification: Provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.
- E. Employee Screening: Comply with Owner's requirements for screening of Contractor personnel working on Project site.
  - 1. Maintain list of approved screened personnel with Owner's representative.
  - 2. Badging to be provided by contractor.

## 1.9 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
  - 1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
  - 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:
  - 1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
  - 2. Abbreviations: Materials and products are identified by abbreviations published as part of the U.S. National CAD Standard and scheduled on Drawings.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

#### SUMMARY

SECTION 012300 - ALTERNATES

### PART 1 - GENERAL

## 1.1 SECTION INCLUDES

- A. Description of Alternates.
- B. Procedures for pricing Alternates.

## 1.2 ACCEPTANCE OF ALTERNATES

- A. Alternates quoted on Bid Forms will be reviewed and accepted or rejected at Owner's option. Accepted Alternates will be identified in the Owner-Contractor Agreement.
- B. Coordinate related work and modify surrounding work to integrate the Work of each Alternate.

## 1.3 SCHEDULE OF ALTERNATES

- A. Alternate No. 1, Resilient Sheet Flooring:
  - 1. Base Bid: Provide vinyl composition tile (VCT) patching at areas where casework is removed and saw cutting occurs, to match existing. See Section 096519 "Resilient Tile Flooring. Provide new 6" Rubber Base throughout classroom. See Section 096513 "Resilient Base and Accessories"
  - 2. Additive Alternate: Provide Resilient Sheet Flooring and integral base as specified in 096516 "Resilient Sheet Flooring".

PART 2 - PRODUCTS (Not Used)

## PART 3 - EXECUTION (Not Used)

END OF SECTION 012300

#### ALTERNATES

## SECTION 012500 - SUBSTITUTION PROCEDURES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Requirements:
  - 1. Section 012300 "Alternates" for products selected under an alternate.
  - 2. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

### 1.3 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
  - 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
  - 2. Substitutions for Convenience: Changes proposed by Contractor that are not required in order to meet other Project requirements but may offer advantage to Contractor.

#### 1.4 ACTION SUBMITTALS

- A. Substitution Requests: Refer to AIA Document A201 in the Supplementary Conditions for consideration of requests received after Contract award. Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
  - 1. Substitution Request Form: Use facsimile of form provided in Project Manual.
  - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
    - a. Statement indicating why specified product or fabrication, or installation method cannot be provided, if applicable.

#### SUBSTITUTION PROCEDURES

- b. Coordination of information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.
- c. Detailed comparison of significant qualities of proposed substitutions with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes, such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
- d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
- e. Samples, where applicable or requested.
- f. Certificates and qualification data, where applicable or requested.
- g. List of similar installations for completed projects, with project names and addresses as well as names and addresses of architects and owners.
- h. Material test reports from a qualified testing agency, indicating and interpreting test results for compliance with requirements indicated.
- i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
- j. Detailed comparison of Contractor's construction schedule using proposed substitutions with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
- k. Cost information, including a proposal of change, if any, in the Contract Sum.
- 1. Contractor's certification that proposed substitution complies with requirements in the Contract Documents, except as indicated in substitution request, is compatible with related materials and is appropriate for applications indicated.
- m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
- 3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 14 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
  - a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
  - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

## 1.5 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

#### 1.6 **PROCEDURES**

A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

### 1.7 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 14 days prior to time required for preparation and review of related submittals.
  - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
    - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
    - b. Substitution request is fully documented and properly submitted.
    - c. Requested substitution will not adversely affect Contractor's construction schedule.
    - d. Requested substitution has received necessary approvals of authorities having jurisdiction.
    - e. Requested substitution is compatible with other portions of the Work.
    - f. Requested substitution has been coordinated with other portions of the Work.
    - g. Requested substitution provides specified warranty.
    - h. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

#### SUBSTITUTION PROCEDURES

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

74-21106-00 21 JANUARY 2021 50% CONSTRUCTION DOCUMENTS

# SUBSTITUTION REQUEST

(After the Bidding Phase)

Project:	Substitution Request Number:
	From:
То:	Date:
	A/E Project Number:
Re:	Contract For:
Specification Title:	Description:
Section:Page:	Article/Paragraph:
Proposed Substitution:	
Manufacturer Address:Phone:	
Trade Name:	Model No.:
Installer:Address:	Phone
History: New product 2-5 years old 5-	-10 years old
Differences between proposed substitution and specified	aroduct:
Reason for not providing specified item:	
Project:	Architect:
Address:	Owner:
	Date Installed:
Proposed substitution affects other parts of Work:	o 🗌 Yes; explain
Savings to Owner for accepting substitution:	(\$).
Proposed substitution changes Contract Time:	Yes [Add] [Deduct]days.
Supporting Data Attached: Drawings Prod	duct Data Samples Tests Reports
© Copyright 1996, Construction Specification Institute, 99 Canal Center Plaza, Suite 300 Alexandria, VA 22314	Page of September 1996 CSI Form 13.1A

# SUBSTITUTION REQUEST (Continued)

The	Und	ersigned	certifies:
-----	-----	----------	------------

- Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.
- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule.
- Cost data as stated above is complete. Claims for additional costs related to accepted substitution which may subsequently become apparent are to be waived.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.
- Coordination, installation, and changes in the Work as necessary for accepted substitution will be complete in all respects.

Submitted by:							
Signed by:							
Firm:							
Address:							
Telephone:							
Attachments:							
A/E's DEVIEW AND AC	TION						
A/E S KEVIEW AND AC	TION						
<ul> <li>Substitution approved - Make submittals in accordance with Specification Section 01330.</li> <li>Substitution approved as noted - Make submittals in accordance with Specification Section 01330.</li> <li>Substitution rejected - Use specified materials.</li> <li>Substitution Request received too late - Use specified materials.</li> </ul>							
Signed by:					Date:		
Additional Comments:	Contractor	Subcontractor	Supplier	Manufacturer	A/E		

Copyright 1996, Construction Specification Institute, 99 Canal Center Plaza, Suite 300 Alexandria, VA 22314 September 1996 CSI Form 13.1A

### WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

74-21106-00 21 JANUARY 2021 50% CONSTRUCTION DOCUMENTS

# SUBSTITUTION REQUEST

(During the Bidding Phase)

Project:		Substitution Request Number:	
		From:	
То:		Date:	
		A/E Project Number:	
Re:		Contract For:	
Specification Title:		Description:	
Section:	Page:	Article/Paragraph:	
Proposed Substitution:			
Manufacturer:	Address:	Phone:	
Trade Name:		Model No.:	

Attached data includes product description, specifications, drawings, photographs, and performance and test data adequate for evaluation of the request; applicable portions of the data are clearly identified.

Attached data also includes a description of changes to the Contract Documents that the proposed substitution will require for its proper installation.

The Undersigned certifies:

- Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.
- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.

Submitted by: Signed by: Firm: Address:	
Telephone:	

#### A/E's REVIEW AND ACTION

Substitution approved - Make submittals in accordan Substitution approved as noted - Make submittals in a Substitution rejected - Use specified materials. Substitution Request received too late - Use specified	ce with Specification Section 01330. accordance with Specification Section 01330. I materials.	
Signed by:		Date:
Supporting Data Attached: Drawings P	ProductData Samples Tests	Reports
© Copyright 1996, Construction Specifications Institute, 99 Canal Center Plaza, Suite 300 Alexandria, VA 22314	Page of	September 1996 CSI Form 1.5C

SUBSTITUTION REQUEST FORMS

## SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract (AIA 201), including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.
- B. Related Requirements:
  - 1. Section 012500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.

#### 1.3 MINOR CHANGES IN THE WORK

A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710 and eBuilder.

### 1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
  - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
  - 2. Within 10 days after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
    - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    - c. Include costs of labor and supervision directly attributable to the change.

#### CONTRACT MODIFICATION PROCEDURES

- d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- e. Quotation Form: Use forms acceptable to Architect.
- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
  - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
  - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
  - 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
  - 4. Include costs of labor and supervision directly attributable to the change.
  - 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
  - 6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
  - 7. Proposal Request Form: Use form acceptable to Architect.

## 1.5 CHANGE ORDER PROCEDURES

- A. A Change Order is a written instrument prepared by the Architect, Owner or Contractor and signed by the Owner, Contractor and (at Owner's election) Architect stating their agreement upon all of the following:
  - 1. The change in the Work;
  - 2. The amount of the adjustment, if any, in the Contract Sum; and
  - 3. The extent of the adjustment, if any, in the Contract Time.
- B. Methods used in determining adjustments to the Contract Sum may include those listed in Section 7.3.3.
- C. Agreement on any Amendment shall constitute a final settlement of all matters relating to the change in the Work that is the subject of the Change Order, including, but not limited to, all direct and indirect costs associated with such change and any and all adjustments to the Contract Sum, the construction schedule, and the Contract Time.

### 1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. A Construction Change Directive is a written order signed by the Owner (and at Owner's election, prepared and/or signed by Architect), directing a change in the Work prior to agreement on adjustment, if any, in the Contract Sum or Contract Time, or both. The Owner may by Construction Change Directive, without invalidating the Contract, order changes in the Work within the general scope of the Contract consisting of additions, deletions or other revisions, the Contract Sum and Contract Time being adjusted accordingly.
- B. A Construction Change Directive shall be executed in accordance with the General Conditions of the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

## SECTION 012900 - PAYMENT PROCEDURES

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Requirements:
  - 1. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
  - 2. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

## 1.3 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

## 1.4 SCHEDULE OF VALUES

- A. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
  - 1. Identification: Include the following Project identification on the schedule of values:
    - a. Project name and location.
    - b. Name of Architect.
    - c. Architect's Project number.
    - d. Contractor's name and address.
    - e. Date of submittal.
  - 2. Arrange the schedule of values in tabular form, with separate columns to indicate the following for each item listed:
    - a. Related Specification Section or Division.

#### PAYMENT PROCEDURES

- b. Description of the Work.
- c. Name of subcontractor.
- d. Name of manufacturer or fabricator.
- e. Name of supplier.
- f. Change Orders (numbers) that affect value.
- g. Dollar value of the following, as a percentage of the Contract Sum to nearest onehundredth percent, adjusted to total 100 percent. Round dollar amounts to whole dollars, with total equal to Contract Sum.
  - 1) Labor.
  - 2) Materials.
  - 3) Equipment.
- 3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
- 4. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
  - a. Differentiate between items stored on-site and items stored off-site.
- 5. Overhead Costs: Include total cost and proportionate share of general overhead and profit for each line item.
- 6. Closeout Costs. Include separate line items under Contractor and principal subcontracts for Project closeout requirements in an amount totaling five percent of the Contract Sum and subcontract amount.
- 7. Schedule of Values Revisions: Revise the schedule of values when Change Orders or Construction Change Directives result in a change in the Contract Sum. Include at least one separate line item for each Change Order and Construction Change Directive.

## 1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
  - 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.

- 2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
- 3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
- 4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.
- D. Transmittal: Submit signed and notarized original copies of each Application for Payment to Architect through Owner's web-based program (eBuilder).
- E. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
  - 1. List of subcontractors.
  - 2. Schedule of values.
  - 3. Contractor's construction schedule (preliminary if not final).
  - 4. Products list (preliminary if not final).
  - 5. Sustainable design action plans, including preliminary project materials cost data.
  - 6. Schedule of unit prices.
  - 7. Submittal schedule (preliminary if not final).
  - 8. List of Contractor's staff assignments.
  - 9. List of Contractor's principal consultants.
  - 10. Copies of building permits.
  - 11. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
  - 12. Initial progress report.
  - 13. Report of preconstruction conference.
- F. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
  - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
  - 2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
  - 3. Contractor shall provide all requirements of documents AIA 201 Section 9.10.2.
- G. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
  - 1. Evidence of completion of Project closeout requirements.
  - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
  - 3. Updated final statement, accounting for final changes to the Contract Sum.
  - 4. All listed items in AIA Document A201 Section 9.10.2.

#### PAYMENT PROCEDURES

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

PAYMENT PROCEDURES

## SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
  - 1. General coordination procedures.
  - 2. Coordination drawings.
  - 3. RFIs.
  - 4. Digital project management procedures.
  - 5. Project meetings.
- B. Related Requirements:
  - 1. Section 013200 "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
  - 2. Section 017700 "Closeout Procedures" for coordinating closeout of the Contract.
  - 3. Section 019113 "General Commissioning Requirements" for coordinating the Work with Owner's Commissioning Authority.

### 1.3 DEFINITIONS

- A. BIM: Building Information Modeling.
- B. RFI: Request for Information. Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

### 1.4 INFORMATIONAL SUBMITTALS

- A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
  - 1. Name, address, telephone number, and email address of entity performing subcontract or supplying products.
  - 2. Number and title of related Specification Section(s) covered by subcontract.

#### PROJECT MANAGEMENT AND COORDINATION

013100 - 1

- 3. Drawing number and detail references, as appropriate, covered by subcontract.
- B. Key Personnel Names: Submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site in accordance with the General Conditions of the Contract.

#### 1.5 GENERAL COORDINATION PROCEDURES

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations included in different Sections that depend on each other for proper installation, connection, and operation.
  - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
  - 2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
  - 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
  - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
  - 1. Preparation of Contractor's construction schedule.
  - 2. Preparation of the schedule of values.
  - 3. Installation and removal of temporary facilities and controls.
  - 4. Delivery and processing of submittals.
  - 5. Progress meetings.
  - 6. Pre-installation conferences.
  - 7. Project closeout activities.
  - 8. Startup and adjustment of systems.

#### 1.6 COORDINATION DRAWINGS

A. Coordination Drawings, General: Prepare coordination drawings according to requirements in individual Sections, and additionally where installation is not completely indicated on Shop Drawings, where limited space availability necessitates coordination, or if coordination is

required to facilitate integration of products and materials fabricated or installed by more than one entity.

- 1. Content: Project-specific information, drawn accurately to a scale large enough to indicate and resolve conflicts. Do not base coordination drawings on standard printed data. Include the following information, as applicable:
  - a. Use applicable Drawings as a basis for preparation of coordination drawings. Prepare sections, elevations, and details as needed to describe relationship of various systems and components.
  - b. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
  - c. Indicate space requirements for routine maintenance and for anticipated replacement of components during the life of the installation.
  - d. Show location and size of access doors required for access to concealed dampers, valves, and other controls.
  - e. Indicate required installation sequences.
  - f. Indicate dimensions shown on Drawings. Specifically note dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternative sketches to Architect indicating proposed resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.
- B. Coordination Drawing Organization: Organize coordination drawings as follows:
  - 1. Floor Plans and Reflected Ceiling Plans: Show architectural and structural elements, and mechanical, plumbing, fire-protection, fire-alarm, and electrical Work. Show locations of visible ceiling-mounted devices relative to acoustical ceiling grid. Supplement plan drawings with section drawings where required to adequately represent the Work.
  - 2. Plenum Space: Indicate sub-framing for support of ceiling and wall systems, mechanical and electrical equipment, and related Work. Locate components within plenums to accommodate layout of light fixtures and other components indicated on Drawings. Indicate areas of conflict between light fixtures and other components.
  - 3. Structural Penetrations: Indicate penetrations and openings required for all disciplines.
  - 4. Mechanical and Plumbing Work: Show the following:
    - a. Sizes and bottom elevations of ductwork, piping, and conduit runs, including insulation, bracing, flanges, and support systems.
    - b. Dimensions of major components, such as dampers, valves, diffusers, access doors, cleanouts and electrical distribution equipment.
    - c. Fire-rated enclosures around ductwork.
  - 5. Electrical Work: Show the following:
    - a. Runs of vertical and horizontal conduit 1-1/4 inches (32 mm) in diameter and larger.
    - b. Light fixture, exit light, emergency battery pack, smoke detector, and other firealarm locations.
    - c. Panel board, switch board, switchgear, transformer, busway, generator, and motorcontrol center locations.

- d. Location of pull boxes and junction boxes, dimensioned from column center lines.
- 6. Fire-Protection System: Show the following:
  - a. Locations of standpipes, mains piping, branch lines, pipe drops, and sprinkler heads.
- 7. Review: Architect will review coordination drawings to confirm that in general the Work is being coordinated, but not for the details of the coordination, which are Contractor's responsibility. If Architect determines that coordination drawings are not being prepared in sufficient scope or detail, or are otherwise deficient, Architect will so inform Contractor, who shall make suitable modifications and resubmit.
- 8. Coordination Drawing Prints: Prepare coordination drawing prints according to requirements in Section 013300 "Submittal Procedures."
- C. Coordination Digital Data Files: Prepare coordination digital data files according to the following requirements:
  - 1. File Preparation Format: Same digital data software program, version, and operating system as original Drawings.
  - 2. File Preparation Format: DWG, Version, operating in Microsoft Windows operating system.
  - 3. File Submittal Format: Submit or post coordination drawing files using PDF format.
  - 4. BIM File Incorporation: Develop and incorporate coordination drawing files into BIM established for Project.
    - a. Perform three-dimensional component conflict analysis as part of preparation of coordination drawings. Resolve component conflicts prior to submittal. Indicate where conflict resolution requires modification of design requirements by Architect.
  - 5. Architect will furnish Contractor one set of digital data files of Drawings for use in preparing coordination digital data files.
    - a. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to Drawings.
    - b. Digital Data Software Program: Drawings are available in BIM.
    - c. Contractor shall execute a data licensing agreement in the form of Agreement form acceptable to Owner and Architect.
  - 6. Allow up to 14 working days for review by Owner and Architect.

## 1.7 REQUEST FOR INFORMATION (RFI)

- A. General: Immediately on discovery of the need for additional information, clarification, or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
  - 1. Architect will return without response those RFIs submitted to Architect by other entities controlled by Contractor.

- 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
  - 1. Project name.
  - 2. Project number.
  - 3. Date.
  - 4. Name of Contractor.
  - 5. Name of Architect.
  - 6. RFI number, numbered sequentially.
  - 7. RFI subject.
  - 8. Specification Section number and title and related paragraphs, as appropriate.
  - 9. Drawing number and detail references, as appropriate.
  - 10. Field dimensions and conditions, as appropriate.
  - 11. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
  - 12. Contractor's signature.
  - 13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
    - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- C. RFI Forms: Software-generated form with substantially the same content as indicated above, acceptable to Architect.
  - 1. Attachments shall be electronic files in PDF format.
  - 2. RFIs will be submitted through owner provided web-based program (eBuilder).
- D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven working days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.
  - 1. The following Contractor-generated RFIs will be returned without action:
    - a. Requests for approval of submittals.
    - b. Requests for approval of substitutions.
    - c. Requests for approval of Contractor's means and methods.
    - d. Requests for coordination information already indicated in the Contract Documents.
    - e. Requests for adjustments in the Contract Time or the Contract Sum.
    - f. Requests for interpretation of Architect's actions on submittals.
    - g. Incomplete RFIs or inaccurately prepared RFIs.

- 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt by Architect of additional information.
- 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
  - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Use software log that is part of web-based Project software. Software log with not less than the following:
  - 1. Project name.
  - 2. Name and address of Contractor.
  - 3. Name and address of Architect.
  - 4. RFI number including RFIs that were returned without action or withdrawn.
  - 5. RFI description.
  - 6. Date the RFI was submitted.
  - 7. Date Architect's response was received.
  - 8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
- F. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.

## 1.8 DIGITAL PROJECT MANAGEMENT PROCEDURES

- A. Use of Architect's Digital Data Files: Digital data files of Architect's BIM model will be provided by Architect for Contractor's use during construction.
  - 1. Digital data files may be used by Contractor in preparing coordination drawings, Shop Drawings, and Project record Drawings.
  - 2. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to Contract Drawings.
  - 3. Digital Drawing Software Program: Contract Drawings are available in BIM (Revit).
  - 4. Contractor shall execute a data licensing agreement in the form of AIA Document C106 Digital Data Licensing Agreement.
    - a. Sub-contractors, and other parties granted access by Contractor to Architect's digital data files shall execute a data licensing agreement in the form of AIA Document C106.
- B. Web-Based Project Software: Use Owner's web-based Project software site for purposes of hosting and managing Project communication and documentation until Final Completion.

#### PROJECT MANAGEMENT AND COORDINATION

013100 - 6

- C. PDF Document Preparation: Where PDFs are required to be submitted to Architect, prepare as follows:
  - 1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
  - 2. Name file with submittal number or other unique identifier, including revision identifier.
  - 3. Certifications: Where digitally submitted certificates and certifications are required, provide a digital signature with digital certificate on where indicated.

### 1.9 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.
  - 1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times a minimum of 10 working days prior to meeting.
  - 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
  - 3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days of the meeting.
- B. Preconstruction Conference: Schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.
  - 1. Attendees: Authorized representatives of Owner, Owner's Commissioning Authority, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
  - 2. Agenda: Discuss items of significance that could affect progress, including the following:
    - a. Responsibilities and personnel assignments.
    - b. Tentative construction schedule.
    - c. Phasing.
    - d. Critical work sequencing and long lead items.
    - e. Designation of key personnel and their duties.
    - f. Lines of communications.
    - g. Use of web-based Project software.
    - h. Procedures for processing field decisions and Change Orders.
    - i. Procedures for RFIs.
    - j. Procedures for testing and inspecting.
    - k. Procedures for processing Applications for Payment.
    - 1. Distribution of the Contract Documents.
    - m. Submittal procedures.
    - n. Preparation of Record Documents.

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- o. Use of the premises.
- p. Work restrictions.
- q. Working hours.
- r. Owner's occupancy requirements.
- s. Responsibility for temporary facilities and controls.
- t. Procedures for moisture and mold control.
- u. Procedures for disruptions and shutdowns.
- v. Construction waste management and recycling.
- w. Parking availability.
- x. Office, work, and storage areas.
- y. Equipment deliveries and priorities.
- z. First aid.
- aa. Security.
- 3. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.
- C. Pre-installation Conferences: Conduct a pre-installation conference at Project site before each construction activity when required by other sections and when required for coordination with other construction.
  - 1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect and Owner's Commissioning Authority of scheduled meeting dates.
  - 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
    - a. Contract Documents.
    - b. Options.
    - c. Related RFIs.
    - d. Related Change Orders.
    - e. Purchases.
    - f. Deliveries.
    - g. Submittals.
    - h. Sustainable design requirements.
    - i. Review of mockups.
    - j. Possible conflicts.
    - k. Compatibility requirements.
    - l. Time schedules.
    - m. Weather limitations.
    - n. Manufacturer's written instructions.
    - o. Warranty requirements.
    - p. Compatibility of materials.
    - q. Acceptability of substrates.
    - r. Temporary facilities and controls.
    - s. Space and access limitations.
    - t. Regulations of authorities having jurisdiction.
    - u. Testing and inspecting requirements.

- v. Installation procedures.
- w. Coordination with other work.
- x. Required performance results.
- y. Protection of adjacent work.
- z. Protection of construction and personnel.
- 3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
- 4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
- 5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Project Closeout Conference: Schedule and conduct a project closeout conference, at a time convenient to Owner and Architect, but no later than 90 days prior to the scheduled date of Substantial Completion.
  - 1. Conduct the conference to review requirements and responsibilities related to Project closeout.
  - 2. Attendees: Authorized representatives of Owner, Owner's Commissioning Authority, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the meeting. Participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
  - 3. Agenda: Discuss items of significance that could affect or delay Project closeout, including the following:
    - a. Preparation of Record Documents.
    - b. Procedures required prior to inspection for Substantial Completion and for final inspection for acceptance.
    - c. Procedures for completing and archiving web-based Project software site data files.
    - d. Submittal of written warranties.
    - e. Requirements for preparing operations and maintenance data.
    - f. Requirements for delivery of material samples, attic stock, and spare parts.
    - g. Requirements for demonstration and training.
    - h. Preparation of Contractor's punch list.
    - i. Procedures for processing Applications for Payment at Substantial Completion and for final payment.
    - j. Submittal procedures.
    - k. Owner's partial occupancy requirements.
    - 1. Installation of Owner's furniture, fixtures, and equipment.
    - m. Responsibility for removing temporary facilities and controls.
  - 4. Minutes: Entity conducting meeting will record and distribute meeting minutes.
- E. Progress Meetings: Conduct progress meetings at weekly intervals.
  - 1. Coordinate dates of meetings with preparation of payment requests.

- 2. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
- 3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
  - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
    - 1) Review schedule for next period.
  - b. Review present and future needs of each entity present, including the following:
    - 1) Interface requirements.
    - 2) Sequence of operations.
    - 3) Status of submittals.
    - 4) Deliveries.
    - 5) Off-site fabrication.
    - 6) Access.
    - 7) Site use.
    - 8) Temporary facilities and controls.
    - 9) Progress cleaning.
    - 10) Quality and work standards.
    - 11) Status of correction of deficient items.
    - 12) Field observations.
    - 13) Status of RFIs.
    - 14) Status of Proposal Requests.
    - 15) Pending changes.
    - 16) Status of Change Orders.
    - 17) Pending claims and disputes.
    - 18) Documentation of information for payment requests.
- 4. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
  - a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100
# SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

## PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.
- B. AIA Document A201, Section 3.10

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
  - 1. Startup construction schedule.
  - 2. Contractor's Construction Schedule.
  - 3. Construction schedule updating reports.
  - 4. Daily construction reports.
  - 5. Material location reports.
  - 6. Site condition reports.
  - 7. Unusual event reports.
  - 8. Construction Document Updates

#### 1.3 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction Project. Activities included in a construction schedule consume time and resources.
  - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
  - 2. Predecessor Activity: An activity that precedes another activity in the network.
  - 3. Successor Activity: An activity that follows another activity in the network.
- B. Float: The measure of leeway in starting and completing an activity.
  - 1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
  - 2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
  - 3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.

#### CONSTRUCTION PROGRESS DOCUMENTATION

C. Resource Loading: The allocation of manpower and equipment necessary for completing an activity as scheduled.

# 1.4 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
  - 1. Working electronic copy of schedule file, where indicated.
  - 2. PDF file.
- B. Startup construction schedule.
  - 1. Submittal of cost-loaded, startup construction schedule will not constitute approval of schedule of values for cost-loaded activities.
- C. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
  - 1. Submit a working digital copy of schedule, using software indicated, and labeled to comply with requirements for submittals.
- D. Construction Schedule Updating Reports: Submit with Applications for Payment.
- E. Daily Construction Reports: Submit at monthly intervals.
- F. Material Location Reports: Submit at monthly intervals.
- G. Site Condition Reports: Submit at time of discovery of differing conditions.
- H. Unusual Event Reports: Submit at time of unusual event.
- I. Qualification Data: For scheduling consultant.

## 1.5 QUALITY ASSURANCE

- A. Prescheduling Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to the preliminary construction schedule and Contractor's Construction Schedule, including, but not limited to, the following:
  - 1. Review software limitations and content and format for reports.
  - 2. Verify availability of qualified personnel needed to develop and update schedule.
  - 3. Discuss constraints, including phasing work stages area separations and interim milestones.
  - 4. Review delivery dates for Owner-furnished products.
  - 5. Review submittal requirements and procedures.
  - 6. Review time required for review of submittals and resubmittals.
  - 7. Review requirements for tests and inspections by independent testing and inspecting agencies.

#### CONSTRUCTION PROGRESS DOCUMENTATION

- 8. Review time required for Project closeout and Owner startup procedures, including commissioning activities.
- 9. Review and finalize list of construction activities to be included in schedule.
- 10. Review procedures for updating schedule.

# 1.6 COORDINATION

- A. Coordinate Contractor's Construction Schedule with the submittal schedule, progress reports, payment requests, and other required schedules and reports.
  - 1. Secure time commitments for performing critical elements of the Work from entities involved.
  - 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

## 1.7 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.
  - 1. Use Scheduling component of Project website software specified in Section 013100 "Project Management and Coordination," or other approved software available to owner and architect for current Windows operating system.
- B. Time Frame: Extend schedule from date established for the Notice to Proceed to date of final completion.
  - 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- C. Activities: Treat each floor or separate area as a separate numbered activity for each main element of the Work. Comply with the following:
  - 1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
  - 2. Procurement Activities: Include procurement process activities for long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
  - 3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with submittal schedule.
  - 4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
  - 5. Commissioning Time: Include no fewer than 15 days for commissioning.
  - 6. Substantial Completion: Indicate completion in advance of date established for Substantial Completion and, allow time for Architect's administrative procedures necessary for certification of Substantial Completion.

### CONSTRUCTION PROGRESS DOCUMENTATION

- 7. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.
- D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule and, show how the sequence of the Work is affected.
  - 1. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
  - 2. Products Ordered in Advance: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
  - 3. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
  - 4. Work Restrictions: Show the effect of the following items on the schedule:
    - a. Coordination with existing construction.
    - b. Uninterruptible services.
    - c. Use-of-premises restrictions.
    - d. Provisions for future construction.
    - e. Seasonal variations.
    - f. Environmental control.
- E. Cost Correlation: Superimpose a cost correlation timeline, indicating planned and actual costs. On the line, show planned and actual dollar volume of the Work performed as of planned and actual dates used for preparation of payment requests.
  - 1. See Section 012900 "Payment Procedures" for cost reporting and payment procedures.
- F. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
  - 1. Unresolved issues.
  - 2. Unanswered Requests for Information.
  - 3. Rejected or unreturned submittals.
  - 4. Notations on returned submittals.
  - 5. Pending modifications affecting the Work and the Contract Time.
- G. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.
  - 1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
  - 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
  - 3. As the Work progresses, indicate final completion percentage for each activity.

#### CONSTRUCTION PROGRESS DOCUMENTATION

- H. Distribution: Distribute copies of approved schedule to Architect Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
  - 1. Post copies in Project meeting rooms and temporary field offices.
  - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

# 1.8 STARTUP CONSTRUCTION SCHEDULE

- A. Gantt-Chart Schedule: Submit startup, horizontal, Gantt-chart-type construction schedule within seven days of date established for the Notice to Proceed.
- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line. Outline significant construction activities for first 90 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.

# 1.9 GANTT-CHART SCHEDULE REQUIREMENTS

- A. Gantt-Chart Schedule: Submit a comprehensive, fully developed, horizontal, Gantt-chart-type, Contractor's Construction Schedule within 30 days of date established for commencement of the Work.
  - 1. Base schedule on the startup construction schedule and additional information received since the start of Project.
- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line.
  - 1. For construction activities that require three months or longer to complete, indicate an estimated completion percentage in 10 percent increments within time bar.

## 1.10 REPORTS

- A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:
  - 1. List of subcontractors at Project site.
  - 2. List of separate contractors at Project site.
  - 3. Approximate count of personnel at Project site.
  - 4. Equipment at Project site.
  - 5. Material deliveries.
  - 6. High and low temperatures and general weather conditions, including presence of rain or snow.
  - 7. Testing and inspection.

## CONSTRUCTION PROGRESS DOCUMENTATION

- 8. Accidents.
- 9. Meetings and significant decisions.
- 10. Unusual events.
- 11. Stoppages, delays, shortages, and losses.
- 12. Meter readings and similar recordings.
- 13. Emergency procedures.
- 14. Orders and requests of authorities having jurisdiction.
- 15. Change Orders received and implemented.
- 16. Construction Change Directives received and implemented.
- 17. Services connected and disconnected.
- 18. Equipment or system tests and startups.
- 19. Partial completions and occupancies.
- 20. Substantial Completions authorized.
- B. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.
- C. Unusual Event Reports: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, responses by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.
  - 1. Submit unusual event reports directly to Owner within one day(s) of an occurrence. Distribute copies of report to parties affected by the occurrence.

## 1.11 CONSTRUCTION DOCUMENT UPDATES

- A. Project documents shall be updated regularly electronically and available to the owner/architect/subcontractors.
- B. Updated documents are to be made available via construction management software, such as Procore or some similar document control platform.
- C. Document tracking to include Contract document updates:
  - 1. Issued via ASI, CCD, PR, or similar form.
  - 2. RFI's
  - 3. Submittals

#### CONSTRUCTION PROGRESS DOCUMENTATION

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013200

CONSTRUCTION PROGRESS DOCUMENTATION

### SECTION 013300 - SUBMITTAL PROCEDURES

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.
- B. AIA Document A201, Section 3.12

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Submittal schedule requirements.
  - 2. Administrative and procedural requirements for submittals.
- B. Related Requirements:
  - 1. Section 012900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.
  - 2. Section 013100 "Project Management and Coordination" for submitting coordination drawings and subcontract list and for requirements for web-based Project software.
  - 3. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
  - 4. Section 014000 "Quality Requirements" for submitting test and inspection reports, and schedule of tests and inspections.
  - 5. Section 017700 "Closeout Procedures" for submitting closeout submittals and maintenance material submittals.
  - 6. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
  - 7. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
  - 8. Section 017900 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.

#### 1.3 DEFINITIONS

A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."

B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."

# 1.4 SUBMITTAL SCHEDULE

- A. Submittal Schedule: Submit, as an action submittal, a list of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.
  - 1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
  - 2. Initial Submittal: Include submittals required during the first 60 days of construction. List those submittals required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
  - 3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's construction schedule.
    - a. Submit revised submittal schedule to reflect changes in current status and timing for submittals.
  - 4. Format: Arrange the following information in a tabular format:
    - a. Scheduled date for first submittal.
    - b. Specification Section number and title.
    - c. Submittal Category: Action; informational.
    - d. Name of subcontractor.
    - e. Description of the Work covered.
    - f. Scheduled date for Architect's final release or approval.

# 1.5 SUBMITTAL FORMATS

- A. Submittal Information: Include the following information in each submittal:
  - 1. Project name.
  - 2. Date.
  - 3. Name of Architect.
  - 4. Name of Contractor.
  - 5. Name of firm or entity that prepared submittal.
  - 6. Names of subcontractor, manufacturer, and supplier.
  - 7. Include Specification Section number with sequential alphanumeric identifier; and alphanumeric suffix for resubmittals.
  - 8. Category and type of submittal.
  - 9. Submittal purpose and description.

- 10. Number and title of Specification Section, with paragraph number and generic name for each of multiple items.
- 11. Drawing number and detail references, as appropriate.
- 12. Location(s) where product is to be installed, as appropriate.
- 13. Other necessary identification.
- 14. Remarks.
- 15. Signature of transmitter.
- B. Options: Identify options requiring selection by Architect.
- C. Deviations and Additional Information: On each submittal, clearly indicate deviations from requirements in the Contract Documents, including minor variations and limitations; include relevant additional information and revisions, other than those requested by Architect on previous submittals. Indicate by highlighting on each submittal or noting on attached separate sheet.
- D. PDF Submittals: Prepare submittals as PDF package, incorporating complete information into each PDF file. Name PDF file with submittal number.
- E. Submittals for Web-Based Project Software: Prepare submittals as PDF files, or other format indicated by Project software website.

- A. Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.
  - 1. Email: Prepare submittals as PDF package and, transmit to Architect by sending via email. Include PDF transmittal form. Include information in email subject line as requested by Architect.
    - a. Architect will return annotated file. Annotate and retain one copy of file as a digital Project Record Document file.
  - 2. Web-Based Project Software: Prepare submittals in PDF form, and upload to web-based Project software website. Enter required data in web-based software site to fully identify submittal.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
  - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
  - 2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
  - 3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.

- 4. Coordinate transmittal of submittals for related parts of the Work specified in different Sections so processing will not be delayed because of need to review submittals concurrently for coordination.
  - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
  - 1. Initial Review: Allow 14 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
  - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
  - 3. Resubmittal Review: Allow 14 days for review of each resubmittal.
  - 4. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 14 days for initial review of each submittal.
  - 5. Concurrent Consultant Review: Where the Contract Documents indicate that submittals may be transmitted simultaneously to Architect and to Architect's consultants, allow 14 days for review of each submittal. Submittal will be returned to Architect before being returned to Contractor.
    - a. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect and Construction Manager.
- D. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
  - 1. Note date and content of previous submittal.
  - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
  - 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- E. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- F. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

# 1.7 SUBMITTAL REQUIREMENTS

A. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.

- 1. If information must be specially prepared for submittal because standard published data are unsuitable for use, submit as Shop Drawings, not as Product Data.
- 2. Mark each copy of each submittal to show which products and options are applicable.
- 3. Include the following information, as applicable:
  - a. Manufacturer's catalog cuts.
  - b. Manufacturer's product specifications.
  - c. Standard color charts.
  - d. Statement of compliance with specified referenced standards.
  - e. Testing by recognized testing agency.
  - f. Application of testing agency labels and seals.
  - g. Notation of coordination requirements.
  - h. Availability and delivery time information.
- 4. For equipment, include the following in addition to the above, as applicable:
  - a. Wiring diagrams that show factory-installed wiring.
  - b. Printed performance curves.
  - c. Operational range diagrams.
  - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
- 5. Submit Product Data before Shop Drawings, and before or concurrent with Samples.
- B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
  - 1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
    - a. Identification of products.
    - b. Schedules.
    - c. Compliance with specified standards.
    - d. Notation of coordination requirements.
    - e. Notation of dimensions established by field measurement.
    - f. Relationship and attachment to adjoining construction clearly indicated.
    - g. Seal and signature of professional engineer if specified.
- C. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other materials.
  - 1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
  - 2. Identification: Permanently attach label on unexposed side of Samples that includes the following:
    - a. Project name and submittal number.
    - b. Generic description of Sample.
    - c. Product name and name of manufacturer.

- d. Sample source.
- e. Number and title of applicable Specification Section.
- f. Specification paragraph number and generic name of each item.
- 3. Web-Based Project Software: Prepare submittals in PDF form, and upload to web-based Project software website. Enter required data in web-based software site to fully identify submittal.
- 4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
  - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
  - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
- 5. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
  - a. Number of Samples: Submit three sets of Samples. Architect will retain two Sample sets; remainder will be returned. Mark up and retain one returned Sample set as a project record Sample.
    - 1) Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
    - 2) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.
- D. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
  - 1. Type of product. Include unique identifier for each product indicated in the Contract Documents or assigned by Contractor if none is indicated.
  - 2. Manufacturer and product name, and model number if applicable.
  - 3. Number and name of room or space.
  - 4. Location within room or space.

- E. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- F. Design Data: Prepare and submit written and graphic information indicating compliance with indicated performance and design criteria in individual Specification Sections. Include list of assumptions and summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Number each page of submittal.
- G. Certificates:
  - 1. Certificates and Certifications Submittals: Submit a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity. Provide a notarized signature where indicated.
  - 2. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
  - 3. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
  - 4. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
  - 5. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
  - 6. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.
- H. Test and Research Reports:
  - 1. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
  - 2. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
  - 3. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
  - 4. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.

- 5. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- 6. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
  - a. Name of evaluation organization.
  - b. Date of evaluation.
  - c. Time period when report is in effect.
  - d. Product and manufacturers' names.
  - e. Description of product.
  - f. Test procedures and results.
  - g. Limitations of use.

#### 1.8 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
  - 1. If criteria indicated are insufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF file and three paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
  - 1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

#### 1.9 CONTRACTOR'S REVIEW

- A. Action Submittals and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Contractor's Approval: Indicate Contractor's approval for each submittal with indication in webbased Project software. Include name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.
  - 1. Architect will not review submittals received from Contractor that do not have Contractor's review and approval.

#### 1.10 ARCHITECT'S REVIEW

- A. Action Submittals: Architect will review each submittal, indicate corrections or revisions required.
  - 1. PDF Submittals: Architect will indicate, via markup on each submittal, the appropriate action.
  - 2. Submittals by Web-Based Project Software: Architect will indicate, on Project software website, the appropriate action.
- B. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- C. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- D. Architect will return without review submittals received from sources other than Contractor.
- E. Submittals not required by the Contract Documents will be returned by Architect without action.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013300

# SECTION 013516 - ALTERATION PROJECT PROCEDURES

#### 1.1 SUMMARY

A. Section includes special procedures for alteration work.

### 1.2 DEFINITIONS

- A. Alteration Work: This term includes remodeling, renovation, repair, and maintenance work performed within existing spaces or on existing surfaces as part of the Project.
- B. Consolidate: To strengthen loose or deteriorated materials in place.
- C. Design Reference Sample: A sample that represents the Architect's prebid selection of work to be matched; it may be existing work or work specially produced for the Project.
- D. Dismantle: To remove by disassembling or detaching an item from a surface, using gentle methods and equipment to prevent damage to the item and surfaces; disposing of items unless indicated to be salvaged or reinstalled.
- E. Match: To blend with adjacent construction and manifest no apparent difference in material type, species, cut, form, detail, color, grain, texture, or finish; as approved by Architect.
- F. Refinish: To remove existing finishes to base material and apply new finish to match original, or as otherwise indicated.
- G. Repair: To correct damage and defects, retaining existing materials, features, and finishes. This includes patching, piecing-in, splicing, consolidating, or otherwise reinforcing or upgrading materials.
- H. Replace: To remove, duplicate, and reinstall entire item with new material. The original item is the pattern for creating duplicates unless otherwise indicated.
- I. Replicate: To reproduce in exact detail, materials, and finish unless otherwise indicated.
- J. Reproduce: To fabricate a new item, accurate in detail to the original, and from either the same or a similar material as the original, unless otherwise indicated.
- K. Retain: To keep an element or detail secure and intact.
- L. Strip: To remove existing finish down to base material unless otherwise indicated.

# 1.3 STORAGE AND HANDLING OF SALVAGED MATERIALS

A. Salvaged Materials:

# ALTERATION PROJECT PROCEDURES

- 1. Clean loose dirt and debris from salvaged items unless more extensive cleaning is indicated.
- 2. Pack or crate items after cleaning; cushion against damage during handling. Label contents of containers.
- 3. Store items in a secure area until delivery to Owner.
- 4. Transport items to Owner's storage area designated by Owner.
- 5. Protect items from damage during transport and storage.
- B. Salvaged Materials for Reinstallation:
  - 1. Repair and clean items for reuse as indicated.
  - 2. Pack or crate items after cleaning and repairing; cushion against damage during handling. Label contents of containers.
  - 3. Protect items from damage during transport and storage.
  - 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment unless otherwise indicated. Provide connections, supports, and miscellaneous materials to make items functional for use indicated.
- C. Existing Materials to Remain: Protect construction indicated to remain against damage and soiling from construction work. Where permitted by Architect, items may be dismantled and taken to a suitable, protected storage location during construction work and reinstalled in their original locations after alteration and other construction work in the vicinity is complete.
- D. Storage: Catalog and store items within a weathertight enclosure where they are protected from moisture, weather, condensation, and freezing temperatures.
  - 1. Identify each item for reinstallation with a nonpermanent mark to document its original location. Indicate original locations on plans, elevations, sections, or photographs by annotating the identifying marks.
  - 2. Secure stored materials to protect from theft.
  - 3. Control humidity so that it does not exceed 85 percent. Maintain temperatures 5 deg F (3 deg C) or more above the dew point.

# 1.4 FIELD CONDITIONS

- A. Survey of Existing Conditions: Record existing conditions that affect the Work by use of preconstruction photographs.
- B. Discrepancies: Notify Architect of discrepancies between existing conditions and Drawings before proceeding with removal and dismantling work.
- C. Owner's Removals: Before beginning alteration work, verify in correspondence with Owner that the items identified in Section 024119 "Selective Demolition" and/or listed on drawings have been removed.

PART 2 - PRODUCTS - (Not Used)

# PART 3 - EXECUTION

## 3.1 **PROTECTION**

- A. Protect persons, motor vehicles, surrounding surfaces of building, building site, plants, and surrounding buildings from harm resulting from alteration work.
  - 1. Use only proven protection methods, appropriate to each area and surface being protected.
  - 2. Provide temporary barricades, barriers, and directional signage to exclude the public from areas where alteration work is being performed.
  - 3. Erect temporary barriers to form and maintain fire-egress routes.
  - 4. Erect temporary protective covers over walkways and at points of pedestrian and vehicular entrance and exit that must remain in service during alteration work.
  - 5. Contain dust and debris generated by alteration work, and prevent it from reaching the public or adjacent surfaces.
  - 6. Provide shoring, bracing, and supports as necessary. Do not overload structural elements.
  - 7. Protect floors and other surfaces along hauling routes from damage, wear, and staining.
- B. Temporary Protection of Materials to Remain:
  - 1. Protect existing materials with temporary protections and construction. Do not remove existing materials unless otherwise indicated.
  - 2. Do not attach temporary protection to existing surfaces except as indicated as part of the alteration work program.
- C. Comply with each product manufacturer's written instructions for protections and precautions. Protect against adverse effects of products and procedures on people and adjacent materials, components, and vegetation.
- D. Utility and Communications Services:
  - 1. Notify Owner, Architect, authorities having jurisdiction, and entities owning or controlling wires, conduits, pipes, and other services affected by alteration work before commencing operations.
  - 2. Disconnect and cap pipes and services as required by authorities having jurisdiction, as required for alteration work.
  - 3. Maintain existing services unless otherwise indicated; keep in service, and protect against damage during operations. Provide temporary services during interruptions to existing utilities.
- E. Existing Drains: Prior to the start of work in an area, test drainage system to ensure that it is functioning properly. Notify Architect immediately of inadequate drainage or blockage. Do not begin work in an area until the drainage system is functioning properly.

## ALTERATION PROJECT PROCEDURES

- 1. Prevent solids such as adhesive or mortar residue or other debris from entering the drainage system. Clean out drains and drain lines that become sluggish or blocked by sand or other materials resulting from alteration work.
- 2. Protect drains from pollutants. Block drains or filter out sediments, allowing only clean water to pass.
- F. Existing Roofing: Prior to the start of work in an area, install roofing protection.

## 3.2 **PROTECTION FROM FIRE**

- A. General: Follow fire-prevention plan and the following:
  - 1. Comply with NFPA 241 requirements unless otherwise indicated.
  - 2. Remove and keep area free of combustibles, including rubbish, paper, waste, and chemicals, unless necessary for the immediate work.
    - a. If combustible material cannot be removed, provide fire blankets to cover such materials.
- B. Heat-Generating Equipment and Combustible Materials: Comply with the following procedures while performing work with heat-generating equipment or combustible materials, including welding, torch-cutting, soldering, brazing, removing paint with heat, or other operations where open flames or implements using high heat or combustible solvents and chemicals are anticipated:
  - 1. As far as practicable, restrict heat-generating equipment to shop areas or outside the building.
  - 2. Do not perform work with heat-generating equipment in or near rooms or in areas where flammable liquids or explosive vapors are present or thought to be present. Use a combustible gas indicator test to ensure that the area is safe.
  - 3. Use fireproof baffles to prevent flames, sparks, hot gases, or other high-temperature material from reaching surrounding combustible material.
  - 4. Prevent the spread of sparks and particles of hot metal through open windows, doors, holes, and cracks in floors, walls, ceilings, roofs, and other openings.
- C. Fire-Control Devices: Provide and maintain fire extinguishers, fire blankets, and rag buckets for disposal of rags with combustible liquids. Maintain each as suitable for the type of fire risk in each work area. Ensure that nearby personnel and the fire-watch personnel are trained in fire-extinguisher and blanket use.
- D. Sprinklers: Where sprinkler protection exists and is functional, maintain it without interruption while operations are being performed. If operations are performed close to sprinklers, shield them temporarily with guards.
  - 1. Remove temporary guards at the end of work shifts, whenever operations are paused, and when nearby work is complete.

## ALTERATION PROJECT PROCEDURES

### 3.3 PROTECTION DURING APPLICATION OF CHEMICALS

- A. Protect surrounding surfaces of building and building site from harm or spillage resulting from applications of chemicals and adhesives.
- B. Cover adjacent surfaces with protective materials that are proven to resist chemicals selected for Project unless chemicals being used will not damage adjacent surfaces as indicated in alteration work program. Use covering materials and masking agents that are waterproof and UV resistant and that will not stain or leave residue on surfaces to which they are applied. Apply protective materials according to manufacturer's written instructions. Do not apply liquid masking agents or adhesives to painted or porous surfaces. When no longer needed, promptly remove protective materials.
- C. Do not apply chemicals during winds of sufficient force to spread them to unprotected surfaces.
- D. Neutralize alkaline and acid wastes and legally dispose of off Owner's property.
- E. Collect and dispose of runoff from chemical operations by legal means and in a manner that prevents soil contamination, soil erosion, undermining of paving and foundations, damage to landscaping, or water penetration into building interior.

END OF SECTION 013516

## SECTION 014000 - QUALITY REQUIREMENTS

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspection services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
  - 1. Specific quality-assurance and quality-control requirements for individual work results are specified in their respective Specification Sections. Requirements in individual Sections may also cover production of standard products.
  - 2. Specified tests, inspections, and related actions do not limit Contractor's other qualityassurance and quality-control procedures that facilitate compliance with the Contract Document requirements.
  - 3. Requirements for Contractor to provide quality-assurance and quality-control services required by Architect, Owner, Commissioning Authority, or authorities having jurisdiction are not limited by provisions of this Section.
  - 4. Specific test and inspection requirements are not specified in this Section.

#### 1.3 DEFINITIONS

- A. Experienced: When used with an entity or individual, "experienced" unless otherwise further described means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.
- B. Field Quality-Control Tests: Tests and inspections that are performed on-site for installation of the Work and for completed Work.

- C. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, assembly, and similar operations.
  - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.
- E. Product Tests: Tests and inspections that are performed by a nationally recognized testing laboratory (NRTL) according to 29 CFR 1910.7, by a testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program (NVLAP), or by a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- F. Source Quality-Control Tests: Tests and inspections that are performed at the source; for example, plant, mill, factory, or shop.
- G. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- H. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- I. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Contractor's quality-control services do not include contract administration activities performed by Architect or Construction Manager.

# 1.4 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
  - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.

## 1.5 CONFLICTING REQUIREMENTS

A. Conflicting Standards and Other Requirements: If compliance with two or more standards or requirements are specified and the standards or requirements establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent

requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for direction before proceeding.

B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

#### 1.6 ACTION SUBMITTALS

A. Delegated-Design Services Submittal: In addition to Shop Drawings, Product Data, and other required submittals, submit a statement signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional, indicating that the products and systems are in compliance with performance and design criteria indicated. Include list of codes, loads, and other factors used in performing these services.

## 1.7 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Qualification Data: For Contractor's quality-control personnel.
- C. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility submitted to authorities having jurisdiction before starting work on the following systems:
  - 1. Seismic-force-resisting system, designated seismic system, or component listed in the Statement of Special Inspections.
  - 2. Main wind-force-resisting system or a wind-resisting component listed in the Statement of Special Inspections.
- D. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- E. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
  - 1. Specification Section number and title.
  - 2. Entity responsible for performing tests and inspections.
  - 3. Description of test and inspection.
  - 4. Identification of applicable standards.
  - 5. Identification of test and inspection methods.
  - 6. Number of tests and inspections required.

- 7. Time schedule or time span for tests and inspections.
- 8. Requirements for obtaining samples.
- 9. Unique characteristics of each quality-control service.
- F. Reports: Prepare and submit certified written reports and documents as specified.
- G. Permits, Licenses, and Certificates: For Owner's record, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents established for compliance with standards and regulations bearing on performance of the Work.

#### 1.8 CONTRACTOR'S QUALITY-CONTROL PLAN

- A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice to Proceed, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities. Coordinate with Contractor's Construction Schedule.
- B. Quality-Control Personnel Qualifications: Engage qualified personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.
  - 1. Project quality-control manager may also serve as Project superintendent.
- C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.
- D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:
  - 1. Contractor-performed tests and inspections including Subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections. Distinguish source quality-control tests and inspections from field quality-control tests and inspections.
  - 2. Special inspections required by authorities having jurisdiction and indicated on the Statement of Special Inspections will be conducted by Owner.
  - 3. Owner-performed tests and inspections indicated in the Contract Documents, including tests and inspections indicated to be performed by Commissioning Authority.
- E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring work into compliance with standards of workmanship established by Contract requirements and approved mockups.

F. Monitoring and Documentation: Maintain testing and inspection reports including log of approved and rejected results. Include work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

# 1.9 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
  - 1. Date of issue.
  - 2. Project title and number.
  - 3. Name, address, telephone number, and email address of testing agency.
  - 4. Dates and locations of samples and tests or inspections.
  - 5. Names of individuals making tests and inspections.
  - 6. Description of the Work and test and inspection method.
  - 7. Identification of product and Specification Section.
  - 8. Complete test or inspection data.
  - 9. Test and inspection results and an interpretation of test results.
  - 10. Record of temperature and weather conditions at time of sample taking and testing and inspection.
  - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
  - 12. Name and signature of laboratory inspector.
  - 13. Recommendations on retesting and re-inspecting.
- B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, telephone number, and email address of technical representative making report.
  - 2. Statement on condition of substrates and their acceptability for installation of product.
  - 3. Statement that products at Project site comply with requirements.
  - 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
  - 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
  - 6. Statement whether conditions, products, and installation will affect warranty.
  - 7. Other required items indicated in individual Specification Sections.
- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, telephone number, and email address of factory-authorized service representative making report.
  - 2. Statement that equipment complies with requirements.

- 3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
- 4. Statement whether conditions, products, and installation will affect warranty.
- 5. Other required items indicated in individual Specification Sections.

# 1.10 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units. As applicable, procure products from manufacturers able to meet qualification requirements, warranty requirements, and technical or factory-authorized service representative requirements.
- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, applying, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or products which are similar in material, design, and extent to those indicated for this Project.
- F. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspection indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.
- G. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- H. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:

- 1. Contractor responsibilities include the following:
  - a. Provide test specimens representative of proposed products and construction.
  - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
  - c. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
  - d. Build site-assembled test assemblies and mockups using installers who will perform same tasks for Project.
  - e. Build laboratory mockups at testing facility using personnel, products, and methods of construction indicated for the completed Work.
  - f. When testing is complete, remove test specimens and test assemblies, and mockups; do not reuse products on Project.
- 2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect and Commissioning Authority, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.

## 1.11 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
  - 1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspection they are engaged to perform.
  - 2. Payment for these services will be made from testing and inspection allowances, as authorized by Change Orders.
  - 3. Costs for retesting and re-inspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities, whether specified or not, to verify and document that the Work complies with requirements.
  - 1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
  - 2. Engage a qualified testing agency to perform quality-control services.
    - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
  - 3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspection will be performed.

- 4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
- 5. Testing and inspection requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
- 6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Retesting/Re-inspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and re-inspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- D. Testing Agency Responsibilities: Cooperate with Architect, Commissioning Authority and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
  - 1. Notify Architect, Commissioning Authority, and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
  - 2. Determine the locations from which test samples will be taken and in which in-situ tests are conducted.
  - 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
  - 4. Submit a certified written report, in duplicate, of each test, inspection, and similar qualitycontrol service through Contractor.
  - 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
  - 6. Do not perform duties of Contractor.
- E. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."
- F. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in pre-installation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.
- G. Associated Contractor Services: Cooperate with agencies and representatives performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
  - 1. Access to the Work.
  - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
  - 3. Adequate quantities of representative samples of materials that require testing and inspection. Assist agency in obtaining samples.
  - 4. Facilities for storage and field curing of test samples.
  - 5. Delivery of samples to testing agencies.

- 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
- 7. Security and protection for samples and for testing and inspection equipment at Project site.
- H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and quality-control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspection.
  - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.

# 1.12 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Conducted by a qualified testing agency or special inspector as required by authorities having jurisdiction, as indicated in individual Specification Sections, and as follows:
  - 1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviewing the completeness and adequacy of those procedures to perform the Work.
  - 2. Notifying Architect, Commissioning Authority, and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
  - 3. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect and Commissioning Authority with copy to Contractor and to authorities having jurisdiction.
  - 4. Submitting a final report of special tests and inspections at Substantial Completion, that includes a list of unresolved deficiencies.
  - 5. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.
  - 6. Retesting and re-inspecting corrected work.

## PART 2 - PRODUCTS (Not Used)

# PART 3 - EXECUTION

# 3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
  - 1. Date test or inspection was conducted.
  - 2. Description of the Work tested or inspected.
  - 3. Date test or inspection results were transmitted to Architect.
  - 4. Identification of testing agency or special inspector conducting test or inspection.

- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's, Commissioning Authority's, reference during normal working hours.
  - 1. Submit log at Project closeout as part of Project Record Documents.

END OF SECTION 014000

SECTION 014200 - REFERENCES

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

#### 1.3 INDUSTRY STANDARDS

A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied

#### REFERENCES

directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.

B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.

## 1.4 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.
  - 1. AABC Associated Air Balance Council; <u>www.aabc.com</u>.
  - 2. AAMA American Architectural Manufacturers Association; <u>www.aamanet.org</u>.
  - 3. AAPFCO Association of American Plant Food Control Officials; <u>www.aapfco.org</u>.
  - 4. AASHTO American Association of State Highway and Transportation Officials; <u>www.transportation.org</u>.
  - 5. AATCC American Association of Textile Chemists and Colorists; <u>www.aatcc.org</u>.
  - 6. ABMA American Bearing Manufacturers Association; <u>www.americanbearings.org</u>.
  - 7. ABMA American Boiler Manufacturers Association; <u>www.abma.com</u>.
  - 8. ACI American Concrete Institute; (Formerly: ACI International); <u>www.abma.com</u>.
  - 9. ACPA American Concrete Pipe Association; <u>www.concrete-pipe.org</u>.
  - 10. AEIC Association of Edison Illuminating Companies, Inc. (The); <u>www.aeic.org</u>.
  - 11. AF&PA American Forest & Paper Association; www.afandpa.org.
  - 12. AGA American Gas Association; <u>www.aga.org</u>.
  - 13. AHAM Association of Home Appliance Manufacturers; www.aham.org.
  - 14. AHRI Air-Conditioning, Heating, and Refrigeration Institute (The); www.ahrinet.org.
  - 15. AI Asphalt Institute; www.asphaltinstitute.org.
  - 16. AIA American Institute of Architects (The); www.aia.org.
  - 17. AISC American Institute of Steel Construction; www.aisc.org.
  - 18. AISI American Iron and Steel Institute; <u>www.steel.org</u>.
  - 19. AITC American Institute of Timber Construction; <u>www.aitc-glulam.org</u>.
  - 20. AMCA Air Movement and Control Association International, Inc.; www.amca.org.
  - 21. ANSI American National Standards Institute; <u>www.ansi.org</u>.
  - 22. AOSA Association of Official Seed Analysts, Inc.; www.aosaseed.com.
  - 23. APA APA The Engineered Wood Association; <u>www.apawood.org</u>.
  - 24. APA Architectural Precast Association; <u>www.archprecast.org</u>.
  - 25. API American Petroleum Institute; <u>www.api.org</u>.
  - 26. ARI Air-Conditioning & Refrigeration Institute; (See AHRI).
  - 27. ARI American Refrigeration Institute; (See AHRI).
  - 28. ARMA Asphalt Roofing Manufacturers Association; www.asphaltroofing.org.
  - 29. ASCE American Society of Civil Engineers; <u>www.asce.org</u>.
  - 30. ASCE/SEI American Society of Civil Engineers/Structural Engineering Institute; (See ASCE).
  - 31. ASHRAE American Society of Heating, Refrigerating and Air-Conditioning Engineers; <u>www.ashrae.org</u>.

#### REFERENCES

- 32. ASME ASME International; (American Society of Mechanical Engineers); www.asme.org.
- 33. ASSE American Society of Safety Engineers (The); www.asse.org.
- 34. ASSE American Society of Sanitary Engineering; www.asse-plumbing.org.
- 35. ASTM ASTM International; www.astm.org.
- 36. ATIS Alliance for Telecommunications Industry Solutions; <u>www.atis.org</u>.
- 37. AWEA American Wind Energy Association; www.awea.org.
- 38. AWI Architectural Woodwork Institute; <u>www.awinet.org</u>.
- 39. AWMAC Architectural Woodwork Manufacturers Association of Canada; <u>www.awmac.com</u>.
- 40. AWPA American Wood Protection Association; <u>www.awpa.com</u>.
- 41. AWS American Welding Society; <u>www.aws.org</u>.
- 42. AWWA American Water Works Association; www.awwa.org.
- 43. BHMA Builders Hardware Manufacturers Association; www.buildershardware.com.
- 44. BIA Brick Industry Association (The); www.gobrick.com.
- 45. BICSI BICSI, Inc.; <u>www.bicsi.org</u>.
- 46. BIFMA BIFMA International; (Business and Institutional Furniture Manufacturer's Association); <u>www.bifma.org</u>.
- 47. BISSC Baking Industry Sanitation Standards Committee; www.bissc.org.
- 48. BWF Badminton World Federation; (Formerly: International Badminton Federation); www.bissc.org.
- 49. CDA Copper Development Association; <u>www.copper.org</u>.
- 50. CEA Canadian Electricity Association; www.electricity.ca.
- 51. CEA Consumer Electronics Association; www.ce.org.
- 52. CFFA Chemical Fabrics and Film Association, Inc.; <u>www.chemicalfabricsandfilm.com</u>.
- 53. CFSEI Cold-Formed Steel Engineers Institute; <u>www.cfsei.org</u>.
- 54. CGA Compressed Gas Association; <u>www.cganet.com</u>.
- 55. CIMA Cellulose Insulation Manufacturers Association; www.cellulose.org.
- 56. CISCA Ceilings & Interior Systems Construction Association; www.cisca.org.
- 57. CISPI Cast Iron Soil Pipe Institute; www.cispi.org.
- 58. CLFMI Chain Link Fence Manufacturers Institute; www.chainlinkinfo.org.
- 59. CPA Composite Panel Association; www.pbmdf.com.
- 60. CRI Carpet and Rug Institute (The); <u>www.carpet-rug.org</u>.
- 61. CRRC Cool Roof Rating Council; <u>www.coolroofs.org</u>.
- 62. CRSI Concrete Reinforcing Steel Institute; www.crsi.org.
- 63. CSA Canadian Standards Association; <u>www.csa.ca</u>.
- 64. CSA CSA International; (Formerly: IAS International Approval Services); <u>www.csa-international.org</u>.
- 65. CSI Construction Specifications Institute (The); www.csinet.org.
- 66. CSSB Cedar Shake & Shingle Bureau; <u>www.cedarbureau.org</u>.
- 67. CTI Cooling Technology Institute; (Formerly: Cooling Tower Institute); www.cti.org.
- 68. CWC Composite Wood Council; (See CPA).
- 69. DASMA Door and Access Systems Manufacturers Association; www.dasma.com.
- 70. DHI Door and Hardware Institute; <u>www.dhi.org</u>.
- 71. ECA Electronic Components Association; (See ECIA).
- 72. ECAMA Electronic Components Assemblies & Materials Association; (See ECIA).
- 73. ECIA Electronic Components Industry Association; <u>www.eciaonline.org</u>.
- 74. EIA Electronic Industries Alliance; (See TIA).
- 75. EIMA EIFS Industry Members Association; <u>www.eima.com</u>.

## REFERENCES

- 76. EJMA Expansion Joint Manufacturers Association, Inc.; <u>www.ejma.org</u>.
- 77. ESD ESD Association; (Electrostatic Discharge Association); www.esda.org.
- 78. ESTA Entertainment Services and Technology Association; (See PLASA).
- 79. EVO Efficiency Valuation Organization; <u>www.evo-world.org</u>.
- 80. FCI Fluid Controls Institute; www.fluidcontrolsinstitute.org.
- 81. FIBA Federation Internationale de Basketball; (The International Basketball Federation); www.fiba.com.
- 82. FIVB Federation Internationale de Volleyball; (The International Volleyball Federation); www.fivb.org.
- 83. FM Approvals FM Approvals LLC; www.fmglobal.com.
- 84. FM Global FM Global; (Formerly: FMG FM Global); www.fmglobal.com.
- 85. FRSA Florida Roofing, Sheet Metal & Air Conditioning Contractors Association, Inc.; www.floridaroof.com.
- 86. FSA Fluid Sealing Association; www.fluidsealing.com.
- 87. FSC Forest Stewardship Council U.S.; <u>www.fscus.org</u>.
- 88. GA Gypsum Association; <u>www.gypsum.org</u>.
- 89. GANA Glass Association of North America; <u>www.glasswebsite.com</u>.
- 90. GS Green Seal; www.greenseal.org.
- 91. HI Hydraulic Institute; <u>www.pumps.org</u>.
- 92. HI/GAMA Hydronics Institute/Gas Appliance Manufacturers Association; (See AHRI).
- 93. HMMA Hollow Metal Manufacturers Association; (See NAAMM).
- 94. HPVA Hardwood Plywood & Veneer Association; www.hpva.org.
- 95. HPW H. P. White Laboratory, Inc.; www.hpwhite.com.
- 96. IAPSC International Association of Professional Security Consultants; <u>www.iapsc.org</u>.
- 97. IAS International Accreditation Service; www.iasonline.org.
- 98. IAS International Approval Services; (See CSA).
- 99. ICBO International Conference of Building Officials; (See ICC).
- 100. ICC International Code Council; www.iccsafe.org.
- 101. ICEA Insulated Cable Engineers Association, Inc.; www.icea.net.
- 102. ICPA International Cast Polymer Alliance; www.icpa-hq.org.
- 103. ICRI International Concrete Repair Institute, Inc.; www.icri.org.
- 104. IEC International Electrotechnical Commission; http://www.iec.ch.
- 105. IEEE Institute of Electrical and Electronics Engineers, Inc. (The); www.ieee.org.
- 106. IES Illuminating Engineering Society; (Formerly: Illuminating Engineering Society of North America); www.ies.org.
- 107. IESNA Illuminating Engineering Society of North America; (See IES).
- 108. IEST Institute of Environmental Sciences and Technology; www.iest.org.
- 109. IGMA Insulating Glass Manufacturers Alliance; www.igmaonline.org.
- 110. IGSHPA International Ground Source Heat Pump Association; www.igshpa.okstate.edu.
- 111. ILI Indiana Limestone Institute of America, Inc.; www.iliai.com.
- 112. Intertek Intertek Group; (Formerly: ETL SEMCO; Intertek Testing Service NA); www.intertek.com.
- 113. ISA International Society of Automation (The); (Formerly: Instrumentation, Systems, and Automation Society); <u>www.isa.org</u>.
- 114. ISAS Instrumentation, Systems, and Automation Society (The); (See ISA).
- 115. ISFA International Surface Fabricators Association; (Formerly: International Solid Surface Fabricators Association); <u>www.isfanow.org</u>.
- 116. ISO International Organization for Standardization; <u>www.iso.org</u>.
- 117. ISSFA International Solid Surface Fabricators Association; (See ISFA).

#### REFERENCES

- 118. ITU International Telecommunication Union; www.itu.int/home.
- 119. KCMA Kitchen Cabinet Manufacturers Association; www.kcma.org.
- 120. LMA Laminating Materials Association; (See CPA).
- 121. LPI Lightning Protection Institute; www.lightning.org.
- 122. MBMA Metal Building Manufacturers Association; www.mbma.com.
- 123. MCA Metal Construction Association; www.metalconstruction.org.
- 124. MFMA Maple Flooring Manufacturers Association, Inc.; www.maplefloor.org.
- 125. MFMA Metal Framing Manufacturers Association, Inc.; www.metalframingmfg.org.
- 126. MHIA Material Handling Industry of America; www.mhia.org.
- 127. MIA Marble Institute of America; www.marble-institute.com.
- 128. MMPA Moulding & Millwork Producers Association; www.wmmpa.com.
- 129. MPI Master Painters Institute; www.paintinfo.com.
- 130. MSS Manufacturers Standardization Society of The Valve and Fittings Industry Inc.; <u>www.mss-hq.org</u>.
- 131. NAAMM National Association of Architectural Metal Manufacturers; www.naamm.org.
- 132. NACE NACE International; (National Association of Corrosion Engineers International); www.nace.org.
- 133. NADCA National Air Duct Cleaners Association; www.nadca.com.
- 134. NAIMA North American Insulation Manufacturers Association; www.naima.org.
- 135. NBGQA National Building Granite Quarries Association, Inc.; www.nbgqa.com.
- 136. NBI New Buildings Institute; www.newbuildings.org.
- 137. NCAA National Collegiate Athletic Association (The); www.ncaa.org.
- 138. NCMA National Concrete Masonry Association; www.ncma.org.
- 139. NEBB National Environmental Balancing Bureau; www.nebb.org.
- 140. NECA National Electrical Contractors Association; www.necanet.org.
- 141. NeLMA Northeastern Lumber Manufacturers Association; www.nelma.org.
- 142. NEMA National Electrical Manufacturers Association; www.nema.org.
- 143. NETA InterNational Electrical Testing Association; www.netaworld.org.
- 144. NFHS National Federation of State High School Associations; www.nfhs.org.
- 145. NFPA National Fire Protection Association; <u>www.nfpa.org</u>.
- 146. NFPA NFPA International; (See NFPA).
- 147. NFRC National Fenestration Rating Council; www.nfrc.org.
- 148. NHLA National Hardwood Lumber Association; www.nhla.com.
- 149. NLGA National Lumber Grades Authority; www.nlga.org.
- 150. NOFMA National Oak Flooring Manufacturers Association; (See NWFA).
- 151. NOMMA National Ornamental & Miscellaneous Metals Association; www.nomma.org.
- 152. NRCA National Roofing Contractors Association; www.nrca.net.
- 153. NRMCA National Ready Mixed Concrete Association; www.nrmca.org.
- 154. NSF NSF International; www.nsf.org.
- 155. NSPE National Society of Professional Engineers; www.nspe.org.
- 156. NSSGA National Stone, Sand & Gravel Association; www.nssga.org.
- 157. NTMA National Terrazzo & Mosaic Association, Inc. (The); www.ntma.com.
- 158. NWFA National Wood Flooring Association; www.nwfa.org.
- 159. PCI Precast/Prestressed Concrete Institute; www.pci.org.
- 160. PDI Plumbing & Drainage Institute; www.pdionline.org.
- 161. PLASA PLASA; (Formerly: ESTA Entertainment Services and Technology Association); www.plasa.org.
- 162. RCSC Research Council on Structural Connections; www.boltcouncil.org.
- 163. RFCI Resilient Floor Covering Institute; www.rfci.com.

#### REFERENCES
# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 164. RIS Redwood Inspection Service; www.redwoodinspection.com.
- 165. SAE SAE International; <u>www.sae.org</u>.
- 166. SCTE Society of Cable Telecommunications Engineers; <u>www.scte.org</u>.
- 167. SDI Steel Deck Institute; www.sdi.org.
- 168. SDI Steel Door Institute; www.steeldoor.org.
- 169. SEFA Scientific Equipment and Furniture Association (The); www.sefalabs.com.
- 170. SEI/ASCE Structural Engineering Institute/American Society of Civil Engineers; (See ASCE).
- 171. SIA Security Industry Association; www.siaonline.org.
- 172. SJI Steel Joist Institute; www.steeljoist.org.
- 173. SMA Screen Manufacturers Association; www.smainfo.org.
- 174. SMACNA Sheet Metal and Air Conditioning Contractors' National Association; www.smacna.org.
- 175. SMPTE Society of Motion Picture and Television Engineers; www.smpte.org.
- 176. SPFA Spray Polyurethane Foam Alliance; www.sprayfoam.org.
- 177. SPIB Southern Pine Inspection Bureau; www.spib.org.
- 178. SPRI Single Ply Roofing Industry; <u>www.spri.org</u>.
- 179. SRCC Solar Rating & Certification Corporation; www.solar-rating.org.
- 180. SSINA Specialty Steel Industry of North America; www.ssina.com.
- 181. SSPC SSPC: The Society for Protective Coatings; <u>www.sspc.org</u>.
- 182. STI Steel Tank Institute; www.steeltank.com.
- 183. SWI Steel Window Institute; <u>www.steelwindows.com</u>.
- 184. SWPA Submersible Wastewater Pump Association; www.swpa.org.
- 185. TCA Tilt-Up Concrete Association; www.tilt-up.org.
- 186. TCNA Tile Council of North America, Inc.; www.tileusa.com.
- 187. TEMA Tubular Exchanger Manufacturers Association, Inc.; www.tema.org.
- 188. TIA Telecommunications Industry Association (The); (Formerly: TIA/EIA -Telecommunications Industry Association/Electronic Industries Alliance); www.tiaonline.org.
- 189. TIA/EIA Telecommunications Industry Association/Electronic Industries Alliance; (See TIA).
- 190. TMS The Masonry Society; www.masonrysociety.org.
- 191. TPI Truss Plate Institute; www.tpinst.org.
- 192. TPI Turfgrass Producers International; www.turfgrasssod.org.
- 193. TRI Tile Roofing Institute; www.tileroofing.org.
- 194. UL Underwriters Laboratories Inc.; www.ul.com.
- 195. UNI Uni-Bell PVC Pipe Association; www.uni-bell.org.
- 196. USAV USA Volleyball; www.usavolleyball.org.
- 197. USGBC U.S. Green Building Council; www.usgbc.org.
- 198. USITT United States Institute for Theatre Technology, Inc.; www.usitt.org.
- 199. WASTEC Waste Equipment Technology Association; www.wastec.org.
- 200. WCLIB West Coast Lumber Inspection Bureau; www.wclib.org.
- 201. WCMA Window Covering Manufacturers Association; www.wcmanet.org.
- 202. WDMA Window & Door Manufacturers Association; www.wdma.com.
- 203. WI Woodwork Institute; www.wicnet.org.
- 204. WSRCA Western States Roofing Contractors Association; www.wsrca.com.
- 205. WWPA Western Wood Products Association; <u>www.wwpa.org</u>.

REFERENCES

- B. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is believed to be accurate as of the date of the Contract Documents.
  - 1. DIN Deutsches Institut fur Normung e.V.; www.din.de.
  - 2. IAPMO International Association of Plumbing and Mechanical Officials; <u>www.iapmo.org</u>.
  - 3. ICC International Code Council; <u>www.iccsafe.org</u>.
  - 4. ICC-ES ICC Evaluation Service, LLC; <u>www.icc-es.org</u>.
- C. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. Information is subject to change and is up to date as of the date of the Contract Documents.
  - 1. COE Army Corps of Engineers; <u>www.usace.army.mil</u>.
  - 2. CPSC Consumer Product Safety Commission; <u>www.cpsc.gov</u>.
  - 3. DOC Department of Commerce; National Institute of Standards and Technology; <u>www.nist.gov</u>.
  - 4. DOD Department of Defense; <u>www.quicksearch.dla.mil</u>.
  - 5. DOE Department of Energy; <u>www.energy.gov</u>.
  - 6. EPA Environmental Protection Agency; <u>www.epa.gov</u>.
  - 7. FAA Federal Aviation Administration; <u>www.faa.gov</u>.
  - 8. FG Federal Government Publications; <u>www.gpo.gov/fdsys</u>.
  - 9. GSA General Services Administration; <u>www.gsa.gov</u>.
  - 10. HUD Department of Housing and Urban Development; <u>www.hud.gov</u>.
  - 11. LBL Lawrence Berkeley National Laboratory; Environmental Energy Technologies Division; <u>www.eetd.lbl.gov</u>.
  - 12. OSHA Occupational Safety & Health Administration; www.osha.gov.
  - 13. SD Department of State; <u>www.state.gov</u>.
  - 14. TRB Transportation Research Board; National Cooperative Highway Research Program; The National Academies; <u>www.trb.org</u>.
  - 15. USDA Department of Agriculture; Agriculture Research Service; U.S. Salinity Laboratory; <u>www.ars.usda.gov</u>.
  - 16. USDA Department of Agriculture; Rural Utilities Service; <u>www.usda.gov</u>.
  - 17. USDOJ Department of Justice; Office of Justice Programs; National Institute of Justice; <u>www.ojp.usdoj.gov</u>.
  - 18. USP U.S. Pharmacopeial Convention; <u>www.usp.org</u>.
  - 19. USPS United States Postal Service; <u>www.usps.com</u>.
- D. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.
  - 1. CFR Code of Federal Regulations; Available from Government Printing Office; <u>www.gpo.gov/fdsys</u>.
  - 2. DOD Department of Defense; Military Specifications and Standards; Available from DLA Document Services; <u>www.quicksearch.dla.mil</u>.
  - 3. DSCC Defense Supply Center Columbus; (See FS).

# REFERENCES

- 4. FED-STD Federal Standard; (See FS).
- 5. FS Federal Specification; Available from DLA Document Services; <u>www.quicksearch.dla.mil</u>.
  - a. Available from Defense Standardization Program; <u>www.dsp.dla.mil</u>.
  - b. Available from General Services Administration; <u>www.gsa.gov</u>.
  - c. Available from National Institute of Building Sciences/Whole Building Design Guide; <u>www.wbdg.org/ccb</u>.
- 6. MILSPEC Military Specification and Standards; (See DOD).
- 7. USAB United States Access Board; <u>www.access-board.gov</u>.
- 8. USATBCB U.S. Architectural & Transportation Barriers Compliance Board; (See USAB).

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 014200

# SECTION 016000 - PRODUCT REQUIREMENTS

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.
- B. Related Requirements:
  - 1. Section 012300 "Alternates" for products selected under an alternate.
  - 2. Section 012500 "Substitution Procedures" for requests for substitutions.
  - 3. Section 014200 "References" for applicable industry standards for products specified.

### 1.3 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
  - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
  - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
  - 3. Comparable Product: Product that is demonstrated and approved by Architect through submittal process to have the indicated qualities related to type, function, dimension, inservice performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a single manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation. In addition to the basis-of-design product description, product attributes and characteristics may be listed to establish the significant qualities related to type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other special features and requirements for purposes of evaluating comparable products of additional manufacturers named in the specification.

#### PRODUCT REQUIREMENTS

C. Subject to Compliance with Requirements: Where the phrase "Subject to compliance with requirements" introduces a product selection procedure in an individual Specification Section, provide products qualified under the specified product procedure. In the event that a named product or product by a named manufacturer does not meet the other requirements of the specifications, select another named product or product from another named manufacturer that does meet the requirements of the specifications. Submit a comparable product request, if applicable.

# 1.4 ACTION SUBMITTALS

- A. Comparable Product Request Submittal: Submit request for consideration of each comparable product. Identify basis-of-design product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
  - 1. Include data to indicate compliance with the requirements specified in "Comparable Products" Article.
  - 2. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
    - a. Form of Architect's Approval of Submittal: As specified in Section 013300 "Submittal Procedures."
    - b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 013300 "Submittal Procedures." Show compliance with requirements.

# 1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.
- B. Identification of Products: Except for required labels and operating data, do not attach or imprint manufacturer or product names or trademarks on exposed surfaces of products or equipment that will be exposed to view in occupied spaces or on the exterior.
  - 1. Labels: Locate required product labels and stamps on a concealed surface, or, where required for observation following installation, on a visually accessible surface that is not conspicuous.
  - 2. Equipment Nameplates: Provide a permanent nameplate on each item of service-connected or power-operated equipment. Locate on a visually accessible but inconspicuous surface. Include information essential for operation, including the following:

- a. Name of product and manufacturer.
- b. Model and serial number.
- c. Capacity.
- d. Speed.
- e. Ratings.
- 3. See individual identification sections in Divisions 21, 22, 23, and 26 for additional identification requirements.

## 1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.
- B. Delivery and Handling:
  - 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
  - 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
  - 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
  - 4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.
- C. Storage:
  - 1. Store products to allow for inspection and measurement of quantity or counting of units.
  - 2. Store materials in a manner that will not endanger Project structure.
  - 3. Store products that are subject to damage by the elements, under cover in a weather-tight enclosure above ground, with ventilation adequate to prevent condensation.
  - 4. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
  - 5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
  - 6. Protect stored products from damage and liquids from freezing.
  - 7. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

# 1.7 PRODUCT WARRANTIES

A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on

product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

- 1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
- 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
  - 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
  - 2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
  - 3. See other Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

# PART 2 - PRODUCTS

# 2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
  - 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
  - 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
  - 3. Owner reserves the right to limit selection to products with warranties meeting requirements of the Contract Documents.
  - 4. Where products are accompanied by the term "as selected," Architect will make selection.
  - 5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
- B. Product Selection Procedures:
  - 1. Sole Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
    - a. Sole product may be indicated by the phrase: "Subject to compliance with requirements, provide the following: ..."

- 2. Sole Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
  - a. Sole manufacturer/source may be indicated by the phrase: "Subject to compliance with requirements, provide products by the following: ..."
- 3. Limited List of Products: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will be considered unless otherwise indicated.
  - a. Limited list of products may be indicated by the phrase: "Subject to compliance with requirements, provide one of the following: ..."
- 4. Non-Limited List of Products: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, which complies with requirements.
  - a. Non-limited list of products is indicated by the phrase: "Subject to compliance with requirements, available products that may be incorporated in the Work include, but are not limited to, the following: ..."
- 5. Limited List of Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated.
  - a. Limited list of manufacturers is indicated by the phrase: "Subject to compliance with requirements, provide products by one of the following: ..."
- 6. Non-Limited List of Manufacturers: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed, or a product by an unnamed manufacturer, which complies with requirements.
  - a. Non-limited list of manufacturers is indicated by the phrase: "Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following: ..."
- 7. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
  - a. For approval of products by unnamed manufacturers, comply with requirements in Section 012500 "Substitution Procedures" for substitutions for convenience.

- C. Visual Matching Specification: Where Specifications require "match Architect's sample," provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.
  - 1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 012500 "Substitution Procedures" for proposal of product.
- D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

## 2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration of Comparable Products: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:
  - 1. Evidence that proposed product does not require revisions to the Contract Documents, is consistent with the Contract Documents, will produce the indicated results, and is compatible with other portions of the Work. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant product qualities include attributes such as type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other specific features and requirements.
  - 2. Evidence that proposed product provides specified warranty.
  - 3. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
  - 4. Samples, if requested.
- B. Submittal Requirements: Approval by the Architect of Contractor's request for use of comparable product is not intended to satisfy other submittal requirements. Comply with specified submittal requirements.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

#### PRODUCT REQUIREMENTS

# SECTION 016116 - DELEGATED DESIGN REQUIREMENTS

# PART 1 - GENERAL

## 1.1 SUMMARY

- A. General: This Section specifies administrative and procedural requirements for delegated design indicated in the various Sections of these Specifications.
- B. Section Includes: Structural and other design requirements for delegated design components, otherwise known as fabricator-designed, Contractor-designed or Contractor design-build components.
- C. This Section applies to Technical Specification Sections, and supplements requirements indicated in the General and Supplementary Conditions.
- D. Delegated design items may require deferred submittals. Deferred submittals are required for delegated design items that require authority having jurisdiction (AHJ) permit review. Deferred submittals are required for:
  - 1. Section 077200 "Roof Accessories", attachment of rooftop mechanical units to supporting curbs.
  - 2. Section 078413 "Penetration Firestopping", special inspection required.
  - 3. Section 095113 "Acoustical Panel Ceilings", acoustical ceiling suspension systems.
  - 4. Fire Protection.
  - 5. Fire sprinkler system.
  - 6. Fire Alarm Systems.
  - 7. Seismic bracing for permanently installed plumbing equipment.
  - 8. Product data and installation instructions for HVAC systems, components, and equipment.
  - 9. Kitchen Exhaust Hood, Type 1 Fire Suppression System.
  - 10. Hangers and Support for all equipment.
  - 11. Seismic bracing for permanently installed electrical equipment.

#### 1.2 DEFINITIONS

- A. Contractor Design Requirements: Where occurs, same meaning as Delegated Design Requirements.
- B. Delegated Design Work: Design services and certifications provided by a Professional Engineer registered as such in the State where the Project is located related to systems, materials or equipment required for the Work to satisfy design and performance criteria established by the Contract Documents. Delegated Design does not include professional services the Contractor needs to fulfill their responsibilities under the Contract including but not limited to construction means, methods and sequence.

#### DELEGATED DESIGN REQUIREMENTS

- C. Seal: Certification that builder design plans, computations and specifications were designed and prepared under the direct supervision of the Architect or Engineer whose name appears thereon.
- D. Approval Stamp: Certification obtained by the Contractor that the Building Official has reviewed a submittal, and finds it acceptable with respect to applicable regulatory requirements.
- E. Contractor-Design: Design services provided by an installer or manufacturer complying with quality assurance, performance requirements and design requirements indicated and established by the Contract Documents. Contractor-design does not include Professional Engineering unless indicated otherwise.

# 1.3 DELEGATED DESIGN SERVICES

- A. Where referenced in these specifications, Delegated Design components and their attachments to the structure shall comply with the currently adopted edition of applicable state and local ordinances, with parameters as specified in the individual Sections.
- B. Where referenced in these specifications, Contractor-Design components and installation shall comply with the currently adopted edition of all applicable state and local ordinates, with parameters specified in this and individual sections.
- C. Permitting Agency Requirements: Follow the requirements for permits current at the time of submission. The Contractor is responsible to coordinate and submit material required, so the permitting agency's review will not adversely affect the construction schedule. At or near time of application, the Contractor shall meet with the permitting agency to identify Deferred Submittal components and how they are to be submitted and processed for permits.
- D. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
  - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.

# 1.4 SUBMITTALS

- A. General: Submit complete Deferred Submittals to meet permitting agency requirements for permits. Include drawings and calculations for that portion of the Work signed and sealed by a State of Oregon registered engineer. Incomplete submittals or submittals not previously reviewed and so stamped by Contractor will not be accepted for review by the Architect or Engineer of Record.
- B. These submittal requirements are in addition to other submittal requirements stated elsewhere in the contract documents.

# 1.5 QUALITY ASSURANCE

- A. Where referenced in these specifications, Delegated Design components and their attachments to the structure shall comply with the currently adopted edition of applicable state and local ordinances, with parameters as specified in this Section.
- B. Permitting Agency Requirements: Follow the requirements for permits current at the time of submission. The General Contractor is responsible to coordinate and submit all material required, so the permitting agency's review will not adversely affect the construction schedule. At or near time of application, the Contractor shall meet with the permitting agency to identify Deferred submittal components and how they are to be submitted and processed for permits.

# 1.6 INSURANCES

A. Refer to General Conditions for Insurance and Bonds.

# PART 2 - PRODUCTS (Not Used)

# PART 3 - EXECUTION

# 3.1 WORK INCLUDED

- A. General: Certain of the components of the Work under this project are Delegated Design. It is the General Contractor's responsibility to coordinate and assume or assign to subcontractors the complete responsibility for the design, calculations, submittals, fabrication, transportation and installation of the Delegated Design portions or components as required in this Section.
- B. The General Contractor is responsible to submit all documents required by the permitting agency for the separate approval and permit for each Delegated Design item. Delegated Design components of this Work are defined as complete, operational systems, provided for their intended use.
- C. All permit plan review and permit fees for Delegated Design items are the responsibility of the submitting General Contractor.

# 3.2 DOCUMENTS REQUIRED

- A. General: Delegated Design documents and related permits issuance must be completed prior to fabrication. The General Contractor must complete and submit a Contractor Design Summary Sheet listing Delegated Design Subcontractors and their registered engineer's names and phone numbers prior to submission of the Delegated Design documents for review.
- B. Scope of Documents: Delegated Design components are shown in the Contract Documents for design intent. The purpose is to have the General Contractor responsible to provide, coordinate and install each Delegated Design component.

#### DELEGATED DESIGN REQUIREMENTS

- 1. Delegated Design components attached to the structural frame or supplemental to the structural frame shall be designed for the anticipated loads as outlined in the Contract Documents. These Delegated Design components are all to be coordinated with appropriate subcontractors.
- 2. Load reactions at the interface between the Delegated Design components and the structural frame shall be clearly defined to allow for a review by the Architect and Engineer of Record.
- C. Component Certification: Certify that mechanical and electrical components comply with the structural provisions of all applicable codes.
  - 1. Shop Drawings: Submit shop drawings for all attachments to the structure for all elements requiring structural design per these specifications. These attachments include, but are not limited to, structural bracing for equipment, conveyances, and architectural components; seismic restraints of vibration isolation systems; and details of lateral bracing and attachment systems designed to accommodate differential movement between building levels.
  - 2. Shop Drawings shall be sealed by the structural engineer responsible for their design.
- D. Quality Assurance Plan: Submit a quality assurance plan for the designated structural system of all elements requiring structural design per these specifications. Quality assurance plan shall comply with Owner's requirements and all applicable codes.

END OF SECTION 016116

# SECTION 017300 - EXECUTION

# PART 1 - GENERAL

## 1.1 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work, including, but not limited to, the following:
  - 1. Construction layout.
  - 2. Field engineering and surveying.
  - 3. Installation of the Work.
  - 4. Cutting and patching.
  - 5. Coordination of Owner's portion of the Work.
  - 6. Coordination of Owner-installed products.
  - 7. Progress cleaning.
  - 8. Starting and adjusting.
  - 9. Protection of installed construction.
  - 10. Correction of the Work.
- B. Related Requirements:
  - 1. Section 011000 "Summary" for coordination of Owner-furnished products, Ownerperformed work, and limits on use of Project site.
  - 2. Section 013300 "Submittal Procedures" for submitting surveys.
  - 3. Section 024119 "Selective Demolition" for demolition and removal of selected portions of the building.
  - 4. Section 078413 "Penetration Firestopping" for patching penetrations in fire-rated construction.

#### 1.2 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of subsequent work.
- B. Patching: Fitting and repair work required to restore construction to original conditions after installation of subsequent work.

# 1.3 QUALITY ASSURANCE

A. Professional Engineer Qualifications: Refer to Section 014000 "Quality Requirements."

- B. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
  - 1. Structural Elements: When cutting and patching structural elements, or when encountering the need for cutting and patching of elements whose structural function is not known, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection.
  - 2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety. Operational elements include the following:
    - a. Primary operational systems and equipment.
    - b. Fire separation assemblies.
    - c. Air or smoke barriers.
    - d. Fire-suppression systems.
    - e. Plumbing piping systems.
    - f. Mechanical systems piping and ducts.
    - g. Control systems.
    - h. Communication systems.
    - i. Fire-detection and -alarm systems.
    - j. Conveying systems.
    - k. Electrical wiring systems.
    - 1. Operating systems of special construction.
  - 3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety. Other construction elements include but are not limited to the following:
    - a. Water, moisture, or vapor barriers.
    - b. Membranes and flashings.
    - c. Sprayed fire-resistive material.
    - d. Equipment supports.
    - e. Piping, ductwork, vessels, and equipment.
    - f. Noise- and vibration-control elements and systems.
  - 4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- C. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of specified products and equipment.

# PART 2 - PRODUCTS

#### 2.1 MATERIALS

- A. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
  - 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials. Use materials that are not considered hazardous.
- B. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, mechanical and electrical systems, and other construction affecting the Work.
  - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, gas service piping, and water-service piping; underground electrical services; and other utilities.
  - 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
  - 1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
  - 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
  - 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

#### 3.2 PREPARATION

- A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Architect in accordance with requirements in Section 013100 "Project Management and Coordination."

## 3.3 CONSTRUCTION LAYOUT

A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks and existing conditions. If discrepancies are discovered, notify Architect promptly.

## 3.4 INSTALLATION

- A. Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
  - 1. Make vertical work plumb, and make horizontal work level.
  - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
  - 3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.
  - 4. Maintain minimum headroom clearance of 96 inches (2440 mm) in occupied spaces and [90 inches (2300 mm)] in unoccupied spaces, unless otherwise indicated on Drawings.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure satisfactory results as judged by Architect. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations, so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy of type expected for Project.
- E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on-site and placement in permanent locations.

- F. Tools and Equipment: Select tools or equipment that minimize production of excessive noise levels.
- G. Templates: Obtain and distribute to the parties involved templates for Work specified to be factory prepared and field installed. Check Shop Drawings of other portions of the Work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions with manufacturer.
  - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
  - 2. Allow for building movement, including thermal expansion and contraction.
  - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- I. Joints: Make joints of uniform width. Where joint locations in exposed Work are not indicated, arrange joints for the best visual effect, as judged by Architect. Fit exposed connections together to form hairline joints.

# 3.5 CUTTING AND PATCHING

- A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
  - 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.
- C. Temporary Support: Provide temporary support of Work to be cut.
- D. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- E. Adjacent Occupied Areas: Where interference with use of adjoining areas or interruption of free passage to adjoining areas is unavoidable, coordinate cutting and patching in accordance with requirements in Section 011000 "Summary."

- F. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to prevent interruption to occupied areas.
- G. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
  - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
  - 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
  - 3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
  - 4. Excavating and Backfilling: Comply with requirements in applicable Sections where required by cutting and patching operations.
  - 5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
- H. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as practicable, as judged by Architect. Provide materials and comply with installation requirements specified in other Sections, where applicable.
  - 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
  - 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.
    - a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
    - b. Restore damaged pipe covering to its original condition.
  - 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.
    - a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch, corner to corner of wall and edge to edge of ceiling. Provide additional coats until patch blends with adjacent surfaces.
  - 4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance.

EXECUTION

017300 - 6

I. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

# 3.6 COORDINATION OF OWNER'S PORTION OF THE WORK

- A. Coordination: Coordinate construction and operations of the Work with work performed by Owner's construction personnel.
  - 1. Construction Schedule: Inform Owner of Contractor's preferred construction schedule for Owner's portion of the Work. Adjust construction schedule based on a mutually agreeable timetable. Notify Owner if changes to schedule are required due to differences in actual construction progress.
  - 2. Preinstallation Conferences: Include Owner's construction personnel at preinstallation conferences covering portions of the Work that are to receive Owner's work. Attend preinstallation conferences conducted by Owner's construction personnel if portions of the Work depend on Owner's construction.

# 3.7 PROGRESS CLEANING

- A. Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
  - 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
  - 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F (27 deg C).
  - 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
    - a. Use containers intended for holding waste materials of type to be stored.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where Work is in progress to the level of cleanliness necessary for proper execution of the Work.
  - 1. Remove liquid spills promptly.
  - 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.

- F. Exposed Surfaces: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Comply with waste disposal requirements in Section 017419 "Construction Waste Management and Disposal."
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- J. Limiting Exposures: Supervise construction operations to ensure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

## 3.8 STARTING AND ADJUSTING

- A. Coordinate startup and adjusting of equipment and operating components with requirements in Section 019113 "General Commissioning Requirements."
- B. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- C. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.
- D. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- E. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements."

# 3.9 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Protection of Existing Items: Provide protection and ensure that existing items to remain undisturbed by construction are maintained in condition that existed at commencement of the Work.
- C. Comply with manufacturer's written instructions for temperature and relative humidity.

## 3.10 CORRECTION OF THE WORK

- A. Repair or remove and replace damaged, defective, or nonconforming Work. Restore damaged substrates and finishes.
  - 1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- B. Repair Work previously completed and subsequently damaged during construction period. Repair to like-new condition.
- C. Restore permanent facilities used during construction to their specified condition.
- D. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.
- E. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.
- F. Remove and replace chipped, scratched, and broken glass or reflective surfaces.

END OF SECTION 017300

# SECTION 017419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for the following:
  - 1. Recycling nonhazardous demolition and construction waste.
  - 2. Disposing of nonhazardous demolition and construction waste.

#### 1.3 DEFINITIONS

- A. Construction Waste: Building and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.
- B. Demolition Waste: Building and site improvement materials resulting from demolition or selective demolition operations.
- C. Disposal: Removal off-site of demolition and construction waste and subsequent sale, recycling, reuse, or deposit in landfill or incinerator acceptable to authorities having jurisdiction.
- D. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.

### 1.4 ACTION SUBMITTALS

A. Waste Management Plan: Submit plan within 30 days of date established for commencement of the Work.

### 1.5 QUALITY ASSURANCE

A. Regulatory Requirements: Comply with hauling and disposal regulations of authorities having jurisdiction.

#### CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

## 1.6 WASTE MANAGEMENT PLAN

- A. Waste Management Plan: Include the following information
  - 1. Analysis of the trash and waste projected to be generated during the entire project construction cycle, including types and quantities.
  - 2. Landfill Options: The name, address, and telephone number of the landfill(s) where trash/waste will be disposed of, the applicable landfill tipping fee(s), and the projected cost of disposing of all project trash/waste in the landfill(s).
  - 3. Materials Handling Procedures: Describe the means by which materials to be diverted from landfills will be protected from contamination and prepared for acceptance by designated facilities; include separation procedures for recyclables, storage, and packaging.
  - 4. Transportation: Identify the destination and means of transportation of materials to be recycled; i.e. whether materials will be site-separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler.

# PART 2 - PRODUCTS (Not Used)

# PART 3 - EXECUTION

# 3.1 PLAN IMPLEMENTATION

- A. General: Implement approved waste management plan. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.
  - 1. Comply with operation, termination, and removal requirements in Section 015000 "Temporary Facilities and Controls."
- B. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
  - 1. Designate and label specific areas on Project site necessary for separating materials that are to be salvaged, recycled, reused, donated, and sold.
  - 2. Comply with Section 015000 "Temporary Facilities and Controls" for controlling dust and dirt, environmental protection, and noise control.

#### 3.2 RECYCLING

- A. Use Source Separation Method or Co-Mingling Method suitable to sorting and processing method of selected recycling center. Dispose non-recyclable trash separately into landfill.
  - 1. Source Separation Method: Recyclable materials separated from trash and sorted into bins or containers prior to transportation to recycling center.

#### CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

- 2. Co-Mingling Method: Recyclable materials separated from trash and placed in unsorted bins or container for sorting at recycling center.
- B. Materials suggested for recycling include:
  - 1. Packing materials including paper, cardboard, foam plastic, and sheeting.
  - 2. Recyclable plastics.
  - 3. Organic plant debris.
  - 4. Earth materials.
  - 5. Native stone and granular fill.
  - 6. Asphalt and paving.
  - 7. Wood.
  - 8. Glass.
  - 9. Metals.
  - 10. Gypsum products.
  - 11. Acoustical ceiling tile.
  - 12. Carpet.
  - 13. Equipment oil.

## 3.3 DISPOSAL OF WASTE

- A. General: Except for items or materials to be salvaged, recycled, or otherwise reused, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.
  - 1. Contractor will be responsible for disposing of any equipment in the existing buildings not scheduled to be salvaged to the owner.
  - 2. Contractor will be responsible for disposing of remaining school portable units if present.
  - 3. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
  - 4. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
- B. Burning: Do not burn waste materials.
- C. Burying: Do not bury waste materials.
- D. Disposal: Remove waste materials and dispose of at designated spoil areas on Owner's property.
- E. Disposal: Remove waste materials from Owner's property and legally dispose of them.

END OF SECTION 017419

#### CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

# SECTION 017700 - CLOSEOUT PROCEDURES

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
  - 1. Substantial Completion procedures.
  - 2. Final completion procedures.
  - 3. Warranties.
  - 4. Final cleaning.
  - 5. Repair of the Work.
- B. Related Requirements:
  - 1. Section 017823 "Operation and Maintenance Data" for additional operation and maintenance manual requirements.
  - 2. Section 017839 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
  - 3. Section 017900 "Demonstration and Training" for requirements to train the Owner's maintenance personnel to adjust, operate, and maintain products, equipment, and systems.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of cleaning agent.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at final completion.

## 1.4 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.

#### CLOSEOUT PROCEDURES

## 1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Schedule of Maintenance Material Items: For maintenance material submittal items specified in other Sections.

## 1.6 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
- B. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.
  - 1. Request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected.
  - 2. Results of completed inspection will form the basis of requirements for final completion.

#### 1.7 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete the following:
  - 1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
  - 2. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, damage or settlement surveys, property surveys, and similar final record information.
  - 3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
  - 4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number.
    - a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Owner's signature for receipt of submittals.
  - 5. Submit testing, adjusting, and balancing records.

#### CLOSEOUT PROCEDURES

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 6. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
- 7. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
- 8. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
- 9. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements. Submit final completion photographic documentation.
- B. Procedures Prior to Final Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
  - 1. Advise Owner of pending insurance changeover requirements.
  - 2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
  - 3. Complete startup and testing of systems and equipment.
  - 4. Perform preventive maintenance on equipment used prior to Substantial Completion.
  - 5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training video recordings specified in Section 017900 "Demonstration and Training."
  - 6. Advise Owner of changeover in utility services.
  - 7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
  - 8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
  - 9. Complete final cleaning requirements.
  - 10. Touch up paint and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- C. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
  - 1. Request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected.

# 1.8 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.

- 1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor.
- 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
- 3. Include the following information at the top of each page:
  - a. Project name.
  - b. Date.
  - c. Name of Architect.
  - d. Name of Contractor.
  - e. Page number.
- 4. Submit list of incomplete items in the following format:
  - a. MS Excel electronic file. Architect will return annotated file.
  - b. Web-based project software upload. Utilize software feature for creating and updating list of incomplete items (punch list).

# 1.9 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where warranties are indicated to commence on dates other than date of Substantial Completion, or when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.
- C. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.
- D. Warranty Electronic File: Provide warranties and bonds in PDF format. Assemble complete warranty and bond submittal package into an individual electronic PDF files corresponding to specification section numbers.
  - 1. Submit by uploading to web-based project software site.
- E. Warranties in Paper Form:
  - 1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
  - 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
  - 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.

#### CLOSEOUT PROCEDURES

F. Provide additional copies of each warranty to include in operation and maintenance manuals.

## PART 2 - PRODUCTS

# 2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

## PART 3 - EXECUTION

## 3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
  - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
    - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
    - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
    - c. Rake grounds that are not planted, mulched, or paved to a smooth, even-textured surface.
    - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
    - e. Remove snow and ice to provide safe access to building.
    - f. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
    - g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
    - h. Sweep concrete floors broom clean in unoccupied spaces.
    - i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean according to manufacturer's recommendations if visible soil or stains remain.

- j. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
- k. Remove labels that are not permanent.
- 1. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
- m. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
- n. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
- o. Clean ducts, blowers, and coils if units were operated without filters during construction or that display contamination with particulate matter on inspection.
- p. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency.
- q. Leave Project clean and ready for occupancy.
- C. Construction Waste Disposal: Comply with Owner waste disposal.

## 3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair, or remove and replace, defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.
  - 1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
  - 2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that that already show evidence of repair or restoration.
    - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.
  - 3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
  - 4. Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

#### END OF SECTION 017700

#### CLOSEOUT PROCEDURES

# SECTION 017823 - OPERATION AND MAINTENANCE DATA

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
  - 1. Operations Maintenance Manual:
    - a. Emergency manuals.
    - b. Systems and equipment operation manuals.
    - c. Systems and equipment maintenance manuals.
    - d. Product maintenance manuals.
- B. Related Requirements:
  - 1. Section 013300 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.
  - 2. Section 019113 "General Commissioning Requirements" for verification and compilation of data into operation and maintenance manuals.

# 1.3 DEFINITIONS

- A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.
- B. Subsystem: A portion of a system with characteristics similar to a system.

#### 1.4 CLOSEOUT SUBMITTALS

- A. Submit operation and maintenance manuals indicated. Provide content for each manual as specified in individual Specification Sections, and as reviewed and approved at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
  - 1. Submit a closeout submittal log listing all required closeout submittals, listed by Specifications section numbers.

- 2. Architect, BSD, and Commissioning Authority will comment on whether content of operation and maintenance submittals is acceptable.
- 3. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.
- B. Format: Submit operation and maintenance manuals in the following format:
  - 1. Initial Electronic Submittal Review: Submit by uploading to web-based project software site, eBuilder process called "CLOP." Enable reviewer comments on draft submittals.
  - 2. BSD will not accept any hardcopy documents until initial electronic review has been completed.
- C. Initial Manual Submittal: Submit draft copy of each manual at least 10 days before commencing demonstration and training. Architect, BSD and Commissioning Authority will comment on whether general scope and content of manual are acceptable.
- D. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion Prior to final completion.
  - 1. Correct or revise each manual to comply with Architect's, BSD's and Commissioning Authority's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's, BSD's and Commissioning Authority's comments and prior to commencing demonstration and training.
- E. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

# 1.5 FORMAT OF OPERATION AND MAINTENANCE MANUALS

- A. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic keyword searchable PDF file for each manual type required.
  - 1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
  - 2. For each specification section, provide 1 PDF containing all Product Data and 1 PDF containing the Warranty. Place PDFs into files named according to CSI format
  - 3. Submit all documents by uploading to web-based project software site.
- B. Manuals, Paper Copy: Submit manuals in the form of hard-copy, bound and labeled volumes.
  - 1. Binders: Heavy-duty, three-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.

- a. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name, and subject matter of contents, and indicate Specification Section number on bottom of spine. Indicate volume number for multiple-volume sets.
- b. Submit 1 copy of the Operation and Maintenance Manual and 1 copy of the Warranty Binder.
- 2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section of the manual. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
- 3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software storage media for computerized electronic equipment. Enclose title pages and directories in clear plastic sleeves.
- 4. Supplementary Text: Prepared on 8-1/2-by-11-inch white bond paper.
- 5. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.
  - a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
  - b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

# 1.6 REQUIREMENTS FOR OPERATION, AND MAINTENANCE MANUALS

- A. Organization of Manual: Unless otherwise indicated, organize single manual. The manual shall contain the following materials, in the order listed:
  - 1. Title page.
  - 2. Table of contents.
  - 3. Manual contents.
    - a. Contact list.
    - b. Certificate of Substantial Completion (AIA G704-2000).
    - c. Contractor's Statement of Warranty.
    - d. Lead & Asbestos Free Certification Letter.
    - e. Certificate of Occupancy.
    - f. Final Permit Inspection Approvals.
    - g. Operation & Maintenance Data (including shop drawings, where applicable) and Warranties organized by specification sections chronological order and named according to CSI Format.
- B. Title Page: Include the following information:
  - 1. Subject matter included in manual.
  - 2. Name and address of Project.
  - 3. Name and address of Owner.

- 4. Date of submittal.
- 5. Name and contact information for Contractor.
- 6. Name and contact information for Construction Manager.
- 7. Name and contact information for Architect.
- 8. Name and contact information for Commissioning Authority.
- 9. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
- 10. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
- D. Manual Contents: Arrange contents by specification sections chronological order. If possible, assemble instructions for subsystems, equipment, and components of one system into a single file.

## 1.7 SYSTEMS AND EQUIPMENT OPERATION MANUALS

- A. Systems and Equipment Operation Manual: Assemble a complete set of data indicating operation of each system, subsystem, and piece of equipment not part of a system. Include information required for daily operation and management, operating standards, and routine and special operating procedures.
  - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
  - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- B. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
  - 1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
  - 2. Performance and design criteria if Contractor has delegated design responsibility.
  - 3. Operating standards.
  - 4. Operating procedures.
  - 5. Operating logs.
  - 6. Wiring diagrams.
  - 7. Control diagrams.
  - 8. Piped system diagrams.
  - 9. Precautions against improper use.
  - 10. License requirements including inspection and renewal dates.
- C. Descriptions: Include the following:
  - 1. Product name and model number. Use designations for products indicated on Contract Documents.

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 2. Manufacturer's name.
- 3. Equipment identification with serial number of each component.
- 4. Equipment function.
- 5. Operating characteristics.
- 6. Limiting conditions.
- 7. Performance curves.
- 8. Engineering data and tests.
- 9. Complete nomenclature and number of replacement parts.
- D. Operating Procedures: Include the following, as applicable:
  - 1. Startup procedures.
  - 2. Equipment or system break-in procedures.
  - 3. Routine and normal operating instructions.
  - 4. Regulation and control procedures.
  - 5. Instructions on stopping.
  - 6. Normal shutdown instructions.
  - 7. Seasonal and weekend operating instructions.
  - 8. Required sequences for electric or electronic systems.
  - 9. Special operating instructions and procedures.
- E. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.
- F. Piped Systems: Diagram piping as installed and, identify color coding where required for identification.

#### 1.8 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

- A. Systems and Equipment Maintenance Manuals: Assemble a complete set of data indicating maintenance of each system, subsystem, and piece of equipment not part of a system. Include manufacturers' maintenance documentation, preventive maintenance procedures and frequency, repair procedures, wiring and systems diagrams, lists of spare parts, and warranty information.
  - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
  - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- B. Content: For each system, sub-system, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranties and bonds as described below.
- C. Source Information: List each system, sub-system, and piece of equipment included in the manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service
agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

- D. Manufacturers' Maintenance Documentation: Include the following information for each component part or piece of equipment:
  - 1. Standard maintenance instructions and bulletins; include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
    - a. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
  - 2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
  - 3. Identification and nomenclature of parts and components.
  - 4. List of items recommended to be stocked as spare parts.
- E. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:
  - 1. Test and inspection instructions.
  - 2. Troubleshooting guide.
  - 3. Precautions against improper maintenance.
  - 4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
  - 5. Aligning, adjusting, and checking instructions.
  - 6. Demonstration and training video recording, if available.
- F. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.
  - 1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
  - 2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.
- G. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.
- H. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
  - 1. Include procedures to follow and required notifications for warranty claims.

#### OPERATION AND MAINTENANCE DATA

- I. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.
  - 1. Do not use original project record documents as part of maintenance manuals.

# 1.9 PRODUCT MAINTENANCE MANUALS

- A. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
- B. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- C. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- D. Product Information: Include the following, as applicable:
  - 1. Product name and model number.
  - 2. Manufacturer's name.
  - 3. Color, pattern, and texture.
  - 4. Material and chemical composition.
  - 5. Reordering information for specially manufactured products.
- E. Maintenance Procedures: Include manufacturer's written recommendations and the following:
  - 1. Inspection procedures.
  - 2. Types of cleaning agents to be used and methods of cleaning.
  - 3. List of cleaning agents and methods of cleaning detrimental to product.
  - 4. Schedule for routine cleaning and maintenance.
  - 5. Repair instructions.
- F. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
  - 1. Include procedures to follow and required notifications for warranty claims.

#### OPERATION AND MAINTENANCE DATA

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 017823

OPERATION AND MAINTENANCE DATA

# SECTION 017839 - PROJECT RECORD DOCUMENTS

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
  - 1. Record Drawings.
  - 2. Record Specifications.
  - 3. Record Product Data.
  - 4. Miscellaneous record submittals.
- B. Related Requirements:
  - 1. Section 017700 "Closeout Procedures" for general closeout procedures.
  - 2. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

### 1.3 CLOSEOUT SUBMITTALS

- A. Upload to owner web-based program: O&M Manual; Specs; Revit model; DWG files; pdfs of Record Drawings, Redline Drawings (scanned if necessary) and Permit Drawings (scanned) also submit by uploading to web-based project software site.
- B. Permit Drawing Set (original stamp, signature, & date).
- C. One (1) hard copy of Record Drawings.
- D. One (1) copy O&M Manual 3-Ring Binders including:
  - 1. Table of Contents.
  - 2. Contact list.
  - 3. Certificate of Substantial Completion (AIA G704-2000).
  - 4. Lead & Asbestos Free Certification Letter.
  - 5. Certificate of Occupancy.
  - 6. Final Permit Inspection Approvals.
  - 7. Operation & Maintenance Data (including shop drawings, where applicable) and Warranties organized logically by CSI division.

### PROJECT RECORD DOCUMENTS

- 8. Warranties.
- E. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous recordkeeping requirements and submittals in connection with various construction activities. Submit annotated PDF electronic files and directories of each submittal.

### 1.4 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.
  - 1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
    - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
    - b. Accurately record information in an acceptable drawing technique.
    - c. Record data as soon as possible after obtaining it.
    - d. Record and check the markup before enclosing concealed installations.
    - e. Cross-reference record prints to corresponding photographic documentation.
  - 2. Content: Types of items requiring marking include, but are not limited to, the following:
    - a. Dimensional changes to Drawings.
    - b. Revisions to details shown on Drawings.
    - c. Depths of foundations.
    - d. Locations and depths of underground utilities.
    - e. Revisions to routing of piping and conduits.
    - f. Revisions to electrical circuitry.
    - g. Actual equipment locations.
    - h. Duct size and routing.
    - i. Locations of concealed internal utilities.
    - j. Changes made by Change Order or Construction Change Directive.
    - k. Changes made following Architect's written orders.
    - 1. Details not on the original Contract Drawings.
    - m. Field records for variable and concealed conditions.
    - n. Record information on the Work that is shown only schematically.
  - 3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
  - 4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
  - 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
  - 6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

### PROJECT RECORD DOCUMENTS

- B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Architect. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:
  - 1. Format: Annotated PDF electronic file with comment function enabled Via USB Drive.
  - 2. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
  - 3. Refer instances of uncertainty to Architect for resolution.
  - 4. Architect will furnish Contractor with one set of digital data files of the Contract Drawings for use in recording information.
    - a. See Section 013100 "Project Management and Coordination" for requirements related to use of Architect's digital data files.
    - b. Architect will provide data file layer information. Record markups in separate layers.
- C. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
  - 1. Record Prints: Organize record prints into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
  - 2. Format: Annotated PDF electronic file with comment function enabled via USB Drive.
  - 3. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.
  - 4. Identification: As follows:
    - a. Project name.
    - b. Date.
    - c. Designation "PROJECT RECORD DRAWINGS."
    - d. Name of Architect.
    - e. Name of Contractor.

#### 1.5 RECORD SPECIFICATIONS

- A. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
  - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
  - 2. Note related Change Orders and record Drawings where applicable.
- B. Format: Submit record Specifications as annotated PDF electronic file via USB drive and upload to web-based project software site.

## 1.6 RECORD PRODUCT DATA

- A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- B. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.
  - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
  - 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
  - 3. Note related Change Orders, record Specifications, and record Drawings where applicable.
- C. Format: Submit record Product Data as annotated PDF electronic file via USB Drive.
  - 1. Include record Product Data directory organized by Specification Section number and title, electronically linked to each item of record Product Data.

### 1.7 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.
- B. Format: Submit miscellaneous record submittals as PDF electronic file via USB Drive.
  - 1. Include miscellaneous record submittals directory organized by Specification Section number and title, electronically linked to each item of miscellaneous record submittals.

### 1.8 MAINTENANCE OF RECORD DOCUMENTS

A. Maintenance of Record Documents: Store record documents in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

#### PART 2 - PRODUCTS (Not Used)

#### PART 3 - EXECUTION (Not Used)

#### END OF SECTION 017839

#### PROJECT RECORD DOCUMENTS

# SECTION 017900 - DEMONSTRATION AND TRAINING

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
  - 1. Instruction in operation and maintenance of systems, subsystems, and equipment.
  - 2. Demonstration and training video recordings.

# 1.3 INFORMATIONAL SUBMITTALS

- A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.
  - 1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.
- B. Qualification Data: For facilitator.
- C. Attendance Record: For each training module, submit list of participants and length of instruction time.

#### 1.4 CLOSEOUT SUBMITTALS

- A. Demonstration and Training Video Recordings: Upload to web-based software website or on USB within seven days of end of each training module.
  - 1. Identification: On each copy, provide an applied label with the following information:
    - a. Name of Project.
    - b. Name and address of videographer.
    - c. Name of Architect.
    - d. Name of Construction Manager.

# DEMONSTRATION AND TRAINING

017900 - 1

- e. Name of Contractor.
- f. Date of video recording.
- 2. At completion of training, submit complete training manual(s) for Owner's use prepared in same paper and PDF file format required for operation and maintenance manuals specified in Section 017823 "Operation and Maintenance Data."

## 1.5 QUALITY ASSURANCE

- A. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.
- B. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Section 014000 "Quality Requirements," experienced in operation and maintenance procedures and training.
- C. Videographer Qualifications: A professional videographer who is experienced photographing demonstration and training events similar to those required.
- D. Preinstruction Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to demonstration and training including, but not limited to, the following:
  - 1. Inspect and discuss locations and other facilities required for instruction.
  - 2. Review and finalize instruction schedule and verify availability of educational materials, instructors' personnel, audiovisual equipment, and facilities needed to avoid delays.
  - 3. Review required content of instruction.
  - 4. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.

### 1.6 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.
- C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data have been reviewed and approved by Architect.

- D. In addition to general building training the subcontractors to provide trade specific training for Mechanical and Electrical systems. This training shall be conducted during commissioning of the building, 3 months after building competition and prior to 1 year warranty expiration.
  - 1. Each training sessions to last a maximum of 8 hours.
  - 2. Controls specific training to be four to five days training for multiple Owner's operation team members.

# 1.7 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:
  - 1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
    - a. System, subsystem, and equipment descriptions.
    - b. Performance and design criteria if Contractor is delegated design responsibility.
    - c. Operating standards.
    - d. Regulatory requirements.
    - e. Equipment function.
    - f. Operating characteristics.
    - g. Limiting conditions.
    - h. Performance curves.
  - 2. Documentation: Review the following items in detail:
    - a. Emergency manuals.
    - b. Operation and Maintenance Manual.
    - c. Project Record Documents.
    - d. Identification systems.
    - e. Warranties and bonds.
    - f. Maintenance service agreements and similar continuing commitments.
  - 3. Emergencies: Include the following, as applicable:
    - a. Instructions on meaning of warnings, trouble indications, and error messages.
    - b. Instructions on stopping.
    - c. Shutdown instructions for each type of emergency.
    - d. Operating instructions for conditions outside of normal operating limits.
    - e. Sequences for electric or electronic systems.
    - f. Special operating instructions and procedures.

# DEMONSTRATION AND TRAINING

- 4. Operations: Include the following, as applicable:
  - a. Startup procedures.
  - b. Equipment or system break-in procedures.
  - c. Routine and normal operating instructions.
  - d. Regulation and control procedures.
  - e. Control sequences.
  - f. Safety procedures.
  - g. Instructions on stopping.
  - h. Normal shutdown instructions.
  - i. Operating procedures for emergencies.
  - j. Operating procedures for system, subsystem, or equipment failure.
  - k. Seasonal and weekend operating instructions.
  - 1. Required sequences for electric or electronic systems.
  - m. Special operating instructions and procedures.
- 5. Adjustments: Include the following:
  - a. Alignments.
  - b. Checking adjustments.
  - c. Noise and vibration adjustments.
  - d. Economy and efficiency adjustments.
- 6. Troubleshooting: Include the following:
  - a. Diagnostic instructions.
  - b. Test and inspection procedures.
- 7. Maintenance: Include the following:
  - a. Inspection procedures.
  - b. Types of cleaning agents to be used and methods of cleaning.
  - c. List of cleaning agents and methods of cleaning detrimental to product.
  - d. Procedures for routine cleaning.
  - e. Procedures for preventive maintenance.
  - f. Procedures for routine maintenance.
  - g. Instruction on use of special tools.
- 8. Repairs: Include the following:
  - a. Diagnosis instructions.
  - b. Repair instructions.
  - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
  - d. Instructions for identifying parts and components.
  - e. Review of spare parts needed for operation and maintenance.

### 1.8 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."
- B. Set up instructional equipment at instruction location.

#### 1.9 INSTRUCTION

- A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.
- B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
  - 1. Owner will furnish an instructor to describe Owner's operational philosophy.
  - 2. Owner will furnish Contractor with names and positions of participants.
- C. Scheduling: Provide instruction at mutually agreed-on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.
  - 1. Schedule training with Owner with at least seven days' advance notice.
- D. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.
- E. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

# PART 2 - PRODUCTS

PART 3 - EXECUTION

END OF SECTION 017900

#### DEMONSTRATION AND TRAINING

# SECTION 024119 - SELECTIVE DEMOLITION

# PART 1 - GENERAL

### 1.1 SUMMARY

### A. Section Includes:

- 1. Demolition and removal of selected portions of building or structure.
- 2. Demolition and removal of selected site elements.
- 3. Salvage of existing items to be reused or recycled.

### B. Related Requirements:

- 1. Section 011000 "Summary" for restrictions on use of the premises, Owner-occupancy requirements, and phasing requirements.
- 2. Section 017300 "Execution" for cutting and patching procedures.
- 3. Section 013516 "Alteration Project Procedures" for general protection and work procedures for alteration projects.

#### 1.2 DEFINITIONS

- A. Remove: Detach items from existing construction and dispose of them off-site unless indicated to be salvaged or reinstalled.
- B. Remove and Salvage: Detach items from existing construction, in a manner to prevent damage, and store.
- C. Remove and Reinstall: Detach items from existing construction, in a manner to prevent damage, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Leave existing items that are not to be removed and that are not otherwise indicated to be salvaged or reinstalled.

#### 1.3 MATERIALS OWNERSHIP

A. Unless otherwise indicated, demolition waste becomes property of Contractor.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Schedule of Selective Demolition Activities: Indicate the following:
  - 1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's school staff's on-site operations are uninterrupted.

- 2. Interruption of utility services. Indicate how long utility services will be interrupted.
- 3. Coordination for shutoff, capping, and continuation of utility services.
- B. Refrigerant Recovery by Owner, if required.

# 1.5 CLOSEOUT SUBMITTALS

A. Inventory: Submit a list of items that have been removed and salvaged.

# 1.6 FIELD CONDITIONS

- A. Owner may occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.
- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
  - 1. Before selective demolition, Owner will remove the following items:
    - a. Classroom will be emptied of all loose furnishings, furniture and equipment prior to Contractor mobilization.
- C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
  - 1. If suspected hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials will be removed by Owner under a separate contract.

# 1.7 COORDINATION

A. Arrange selective demolition schedule so as not to interfere with Owner's operations.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI/ASSP A10.6 and NFPA 241.

PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Review Project Record Documents of existing construction or other existing condition and hazardous material information provided by Owner. Owner does not guarantee that existing conditions are same as those indicated in Project Record Documents.
- C. Perform an engineering survey of condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective building demolition operations.
  - 1. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.
- D. Verify that hazardous materials have been remediated before proceeding with building demolition operations.

### 3.2 PREPARATION

A. Refrigerant: Before starting demolition, notify Owner to remove refrigerant from mechanical equipment, if applicable.

# 3.3 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.
- B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off utility services and mechanical/electrical systems serving areas to be selectively demolished.
  - 1. Arrange to shut off utilities with utility companies.
  - 2. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
  - 3. Disconnect, demolish, and remove fire-suppression systems, plumbing, and HVAC systems, equipment, and components indicated on Drawings to be removed.
    - a. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
    - b. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material and leave in place.
    - c. Equipment to Be Removed: Disconnect and cap services and remove equipment.

# SELECTIVE DEMOLITION

024119 - 3

- d. Equipment to Be Removed and Reinstalled: Disconnect and cap services and remove, clean, and store equipment; when appropriate, reinstall, reconnect, and make equipment operational.
- e. Equipment to Be Removed and Salvaged: Disconnect and cap services and remove equipment and deliver to Owner.
- f. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.
- g. Ducts to Be Abandoned in Place: Cap or plug ducts with same or compatible ductwork material and leave in place.

# 3.4 **PROTECTION**

- A. Temporary Protection: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
  - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
  - 2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
  - 3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
  - 4. Cover and protect furniture, furnishings, and equipment that have not been removed.
- B. Remove temporary barricades and protections where hazards no longer exist.

# 3.5 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
  - 1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
  - 2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping. Temporarily cover openings to remain.
  - 3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
  - 4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
  - 5. Maintain fire watch during and for at least 2 hours after flame-cutting operations.
  - 6. Maintain adequate ventilation when using cutting torches.

- 7. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
- 8. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
- 9. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
- 10. Dispose of demolished items and materials promptly. Comply with requirements in Section 017419 "Construction Waste Management and Disposal."
- B. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
- C. Removed and Salvaged Items:
  - 1. Clean salvaged items.
  - 2. Pack or crate items after cleaning. Identify contents of containers.
  - 3. Store items in a secure area until delivery to Owner.
  - 4. Transport items to Owner's storage area as designated by Owner.
  - 5. Protect items from damage during transport and storage.
- D. Removed and Reinstalled Items:
  - 1. Clean and repair items to functional condition adequate for intended reuse.
  - 2. Pack or crate items after cleaning and repairing. Identify contents of containers.
  - 3. Protect items from damage during transport and storage.
  - 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

# 3.6 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

- A. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, and then break up and remove.
- B. Resilient Floor Coverings: Remove floor coverings and adhesive according to recommendations in RFCI's "Recommended Work Practices for the Removal of Resilient Floor Coverings"

# 3.7 DISPOSAL OF DEMOLISHED MATERIALS

- A. Remove demolition waste materials from Project site and dispose of them in an EPA-approved construction and demolition waste landfill acceptable to authorities having jurisdiction.
  - 1. Do not allow demolished materials to accumulate on-site.
  - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
  - 3. Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."

- B. Burning: Do not burn demolished materials.
- 3.8 CLEANING
  - A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 024119

### SECTION 033000 - CAST-IN-PLACE CONCRETE

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes cast-in-place concrete, including formwork, reinforcement, concrete materials, mixture design, placement procedures, and finishes for patch work.
- B. Related Requirements:
  - 1. Division 21 Division 27 for coordination of MEP penetrations.

#### 1.3 DEFINITIONS

- A. Cementitious Materials: Portland cement alone or in combination with one or more of the following: blended hydraulic cement, fly ash, slag cement, other pozzolans, and silica fume; materials subject to compliance with requirements.
- B. W/C Ratio: The ratio by weight of water to cementitious materials.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Design Mixtures: For each concrete mixture. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.
  - 1. Indicate amounts of mixing water to be withheld for later addition at Project site.
- C. Steel Reinforcement Shop Drawings: Placing Drawings that detail fabrication, bending, and placement. Include bar sizes, lengths, material, grade, bar schedules, stirrup spacing, bent bar diagrams, bar arrangement, splices and laps, mechanical connections, tie spacing, hoop spacing, and supports for concrete reinforcement.

D. Construction Joint Layout: Indicate proposed construction joints required to construct the structure.

# 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For installer.
- B. Welding certificates.
- C. Material Certificates: For each of the following, signed by manufacturers:
  - 1. Cementitious materials.
  - 2. Admixtures.
  - 3. Form materials and form-release agents.
  - 4. Steel reinforcement and accessories.
  - 5. Fiber reinforcement
  - 6. Curing compounds.
  - 7. Floor and slab treatments.
  - 8. Vapor barrier.
  - 9. Semirigid joint filler.
  - 10. Joint-filler strips.
- D. Material Test Reports: For the following, from a qualified testing agency:
  - 1. Aggregates: Include service record data indicating absence of deleterious expansion of concrete due to alkali aggregate reactivity.
- E. Floor surface flatness and levelness measurements indicating compliance with specified tolerances.
- F. Field quality-control reports.

# 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs on Project personnel qualified as ACIcertified Flatwork Technician and Finisher and a supervisor who is an ACI-certified Concrete Flatwork Technician.
- B. Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C 94/C 94M requirements for production facilities and equipment.
  - 1. Manufacturer certified according to NRMCA's "Certification of Ready Mixed Concrete Production Facilities."
- C. Testing Agency Qualifications: An independent agency acceptable to authorities having jurisdiction and qualified according to ASTM C 1077 and ASTM E 329 for testing indicated.

D. Welding Qualifications: Qualify procedures and personnel according to AWS D1.4/D 1.4M.

### 1.7 DELIVERY, STORAGE, AND HANDLING

A. Steel Reinforcement: Deliver, store, and handle steel reinforcement to prevent bending and damage.

#### 1.8 FIELD CONDITIONS

- A. Cold-Weather Placement: Comply with ACI 306.1 and as follows. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
  - 1. When average high and low temperature is expected to fall below 40 deg F for three successive days, maintain delivered concrete mixture temperature within the temperature range required by ACI 301.
  - 2. Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials.
  - 3. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in mixture designs.
- B. Hot-Weather Placement: Comply with ACI 301 and as follows:
  - 1. Maintain concrete temperature below 90 deg F at time of placement. Chilled mixing water or chopped ice may be used to control temperature, provided water equivalent of ice is calculated to total amount of mixing water. Using liquid nitrogen to cool concrete is Contractor's option.
  - 2. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade uniformly moist without standing water, soft spots, or dry areas.

### PART 2 - PRODUCTS

### 2.1 FORM-FACING MATERIALS

- A. Smooth-Formed Finished Concrete: Form-facing panels that provide continuous, true, and smooth concrete surfaces. Furnish in largest practicable sizes to minimize number of joints.
  - 1. Plywood, metal, or other approved panel materials.
- B. Rough-Formed Finished Concrete: Plywood, lumber, metal, or another approved material. Provide lumber dressed on at least two edges and one side for tight fit.
- C. Chamfer Strips: Wood, metal, PVC, or rubber strips, 3/4 by 3/4 inch (19 by 19 mm), minimum.

- D. Form-Release Agent: Commercially formulated form-release agent that does not bond with, stain, or adversely affect concrete surfaces and does not impair subsequent treatments of concrete surfaces.
  - 1. Formulate form-release agent with rust inhibitor for steel form-facing materials.
- E. Form Ties: Factory-fabricated, removable or snap-off glass-fiber-reinforced plastic or metal form ties designed to resist lateral pressure of fresh concrete on forms and to prevent spalling of concrete on removal.
  - 1. Furnish units that leave no corrodible metal closer than 1 inch (25 mm) to the plane of exposed concrete surface.
  - 2. Furnish ties that, when removed, leave holes no larger than 1 inch (25 mm) in diameter in concrete surface.
  - 3. Furnish ties with integral water-barrier plates to walls indicated to receive dampproofing or waterproofing.

### 2.2 STEEL REINFORCEMENT

- A. Reinforcing Bars: ASTM A 615/A 615M, Grade 60, deformed.
- B. Low-Alloy-Steel Reinforcing Bars: ASTM A 706/A 706M, deformed.
- C. Plain-Steel Welded-Wire Reinforcement: ASTM A 1064/A 1064M, plain, fabricated from asdrawn steel wire into flat sheets.

# 2.3 REINFORCEMENT ACCESSORIES

- A. Joint Dowel Bars: ASTM A 615/A 615M, Grade 60 (Grade 420), plain-steel bars, cut true to length with ends square and free of burrs.
- B. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded-wire reinforcement in place. Manufacture bar supports from steel wire, plastic, or precast concrete according to CRSI's "Manual of Standard Practice," of greater compressive strength than concrete and as follows:
  - 1. For concrete surfaces exposed to view, where legs of wire bar supports contact forms, use CRSI Class 1 plastic-protected steel wire or CRSI Class 2 stainless-steel bar supports.

### 2.4 CONCRETE MATERIALS

A. Source Limitations: Obtain each type or class of cementitious material of the same brand from the same manufacturer's plant, obtain aggregate from single source, and obtain admixtures from single source from single manufacturer.

# B. Cementitious Materials:

- 1. Portland Cement: ASTM C 150/C 150M, Type I/II, gray or white.
- 2. Fly Ash: ASTM C 618, Class F or C.
- C. Normal-Weight Aggregates: ASTM C 33/C 33M, Class 3M coarse aggregate or better, graded. Provide aggregates from a single source with documented service record data of at least 10 years' satisfactory service in similar applications and service conditions using similar aggregates and cementitious materials.
  - 1. Maximum Coarse-Aggregate Size: 3/4-inch (25 mm) nominal.
- D. Air-Entraining Admixture: ASTM C 260/C 260M.
- E. Chemical Admixtures: Certified by manufacturer to be compatible with other admixtures and that do not contribute water-soluble chloride ions exceeding those permitted in hardened concrete. Do not use calcium chloride or admixtures containing calcium chloride.
  - 1. Water-Reducing Admixture: ASTM C 494/C 494M, Type A.
  - 2. Retarding Admixture: ASTM C 494/C 494M, Type B.
  - 3. Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type D.
  - 4. High-Range, Water-Reducing Admixture: ASTM C 494/C 494M, Type F.
  - 5. High-Range, Water-Reducing and Retarding Admixture: ASTM C 494/C 494M, Type G.
  - 6. Plasticizing and Retarding Admixture: ASTM C 1017/C 1017M, Type II.
- F. Water: ASTM C 94/C 94M and potable.

# 2.5 FIBER REINFORCEMENT

- A. Synthetic Micro-Fiber: Monofilament polypropylene micro-fibers engineered and designed for use in concrete, complying with ASTM C 1116/C 1116M, Type III.
  - 1. ABC Polymer Industries, LLC; FiberForce 300 (aka, Fibril-Tuf).

# 2.6 VAPOR AND RADON BARRIER

- A. Sheet Vapor Barrier and Radon Barrier, at Slab-on-Grade: ASTM E 1745 Class A, with a minimum thickness of 20 mils. Include manufacturer's recommended adhesive or pressure-sensitive tape (minimum 2-inch width).
  - 1. Basis-of-Design Product: Raven Industries, Inc.; Vapor Block Plus VBP20.
  - 2. Other Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. GCP Applied Technologies (formerly Grace Construction Products).
    - b. Raven Industries, Inc.
    - c. Stego Industries, LLC.
    - d. W. R. Meadows, Inc.

# 2.7 LIQUID FLOOR TREATMENTS

- A. Penetrating Liquid Hardener: Clear, chemically reactive, waterborne solution of inorganic silicate or siliconate materials and proprietary components; odorless; that penetrates, hardens, and densifies concrete surfaces.
  - 1. Basis-of-Design Product: Curecrete Distribution Inc.; Ashford Formula.
  - 2. Other Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. ChemMasters, Inc.
    - b. ChemTec Int'l.
    - c. Dayton Superior.
    - d. Euclid Chemical Company (The); an RPM company.
    - e. Kaufman Products, Inc.
    - f. L&M Construction Chemicals, Inc.
    - g. Metalcrete Industries.
    - h. Nox-Crete Products Group.
- B. Clear, Waterborne, Membrane-Forming, Curing and Sealing Compound (S CONC): ASTM C 1315, Type 1, Class A.
  - 1. Basis-of-Design Product: W.R. Meadows; Vocomp 30.
- C. Penetrating Moisture Vapor Barrier: Spray-applied clear liquid to seal slabs against vapor transmission ASTM C 1315, for concrete slabs-on-grade scheduled to receive adhered flooring materials. Confirm compatibility of sealer with flooring material and adhesives.
  - 1. Basis-of-Design Product: Spray-Lock SCP 327, Time of Placement by Spray-Lock Concrete Protection; www.concreteprotection.com.
  - 2. Application: Use on concrete floors where other finish floor materials are installed over concrete.

# 2.8 CURING MATERIALS

- A. Absorptive Cover: AASHTO M 182, Class 2, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. (305 g/sq. m) when dry.
- B. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.
- C. Water: Potable.

#### 2.9 RELATED MATERIALS

A. Expansion- and Isolation-Joint-Filler Strips: ASTM D 1751, asphalt-saturated cellulosic fiber.

- B. Semirigid Joint Filler: Two-component, semirigid, 100 percent solids, epoxy resin with a Type A shore durometer hardness of 80 according to ASTM D 2240.
- C. Bonding Agent: ASTM C 1059/C 1059M, Type II, nonredispersible, acrylic emulsion or styrene butadiene.
- D. Epoxy Bonding Adhesive: ASTM C 881, two-component epoxy resin, capable of humid curing and bonding to damp surfaces, of class suitable for application temperature and of grade to suit requirements, and as follows:
  - 1. Types I and II, nonload bearing for bonding hardened or freshly mixed concrete to hardened concrete.

# 2.10 REPAIR MATERIALS

- A. Repair Underlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/8 inch (3.2 mm) and that can be feathered at edges to match adjacent floor elevations.
  - 1. Cement Binder: ASTM C 150/C 150M, portland cement or hydraulic or blended hydraulic cement as defined in ASTM C 219.
  - 2. Primer: Product of underlayment manufacturer recommended for substrate, conditions, and application.
  - 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch (3.2 to 6 mm) or coarse sand as recommended by underlayment manufacturer.
  - 4. Compressive Strength: Not less than 4100 psi (29 MPa) at 28 days when tested according to ASTM C 109/C 109M.
- B. Repair Overlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/4 inch (6.4 mm) and that can be filled in over a scarified surface to match adjacent floor elevations.
  - 1. Cement Binder: ASTM C 150/C 150M, portland cement or hydraulic or blended hydraulic cement as defined in ASTM C 219.
  - 2. Primer: Product of topping manufacturer recommended for substrate, conditions, and application.
  - 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch (3.2 to 6 mm) or coarse sand as recommended by topping manufacturer.
  - 4. Compressive Strength: Not less than 5000 psi (34.5 MPa) at 28 days when tested according to ASTM C 109/C 109M.

# 2.11 CONCRETE MIXTURES, GENERAL

A. Prepare design mixtures for each type and strength of concrete, proportioned on the basis of laboratory trial mixture or field test data, or both, according to ACI 301 (ACI 301M).

- 1. Use a qualified independent testing agency for preparing and reporting proposed mixture designs based on laboratory trial mixtures.
- B. Cementitious Materials: Use fly ash, pozzolan, slag cement, and silica fume as needed to reduce the total amount of portland cement, which would otherwise be used, by not less than 40 percent. Limit percentage, by weight, of cementitious materials other than portland cement in concrete as follows:
  - 1. Fly Ash: 25 percent.
  - 2. Combined Fly Ash and Pozzolan: 25 percent.
  - 3. Slag Cement: 50 percent.
  - 4. Combined Fly Ash or Pozzolan and Slag Cement: 50 percent portland cement minimum, with fly ash or pozzolan not exceeding 25 percent.
  - 5. Silica Fume: 10 percent.
  - 6. Combined Fly Ash, Pozzolans, and Silica Fume: 35 percent with fly ash or pozzolans not exceeding 25 percent and silica fume not exceeding 10 percent.
  - 7. Combined Fly Ash or Pozzolans, Slag Cement, and Silica Fume: 50 percent with fly ash or pozzolans not exceeding 25 percent and silica fume not exceeding 10 percent.
- C. Limit water-soluble, chloride-ion content in hardened concrete to 0.3 percent by weight of cement.
- D. Admixtures: Use admixtures according to manufacturer's written instructions.
  - 1. Use water-reducing, high-range water-reducing, or plasticizing admixture in concrete, as required, for placement and workability.
  - 2. Use water-reducing and -retarding admixture when required by high temperatures, low humidity, or other adverse placement conditions.
  - 3. Use water-reducing admixture in pumped concrete, concrete for heavy-use industrial slabs and parking structure slabs, concrete required to be watertight, and concrete with a w/c ratio below 0.50.
  - 4. Use corrosion-inhibiting admixture in concrete mixtures where indicated.

# 2.12 CONCRETE MIXTURES FOR BUILDING ELEMENTS

A. Provide mixtures for building elements as indicated on the Structural Drawings.

# 2.13 FABRICATING REINFORCEMENT

A. Fabricate steel reinforcement according to CRSI's "Manual of Standard Practice."

# 2.14 CONCRETE MIXING

A. Ready-Mixed Concrete: Measure, batch, mix, and deliver concrete according to ASTM C 94/C 94M and furnish batch ticket information.

- 1. When air temperature is between 85 and 90 deg F (30 and 32 deg C), reduce mixing and delivery time from 1-1/2 hours to 75 minutes; when air temperature is above 90 deg F (32 deg C), reduce mixing and delivery time to 60 minutes.
- B. Project-Site Mixing: Measure, batch, and mix concrete materials and concrete according to ASTM C 94/C 94M. Mix concrete materials in appropriate drum-type batch machine mixer.
  - 1. For mixer capacity of 1 cu. yd. (0.76 cu. m) or smaller, continue mixing at least 1-1/2 minutes, but not more than 5 minutes after ingredients are in mixer, before any part of batch is released.
  - 2. For mixer capacity larger than 1 cu. yd. (0.76 cu. m), increase mixing time by 15 seconds for each additional 1 cu. yd. (0.76 cu. m).
  - 3. Provide batch ticket for each batch discharged and used in the Work, indicating Project identification name and number, date, mixture type, mixture time, quantity, and amount of water added. Record approximate location of final deposit in structure.

# PART 3 - EXECUTION

# 3.1 FORMWORK INSTALLATION

- A. Design, erect, shore, brace, and maintain formwork, according to ACI 301 (ACI 301M), to support vertical, lateral, static, and dynamic loads, and construction loads that might be applied, until structure can support such loads.
- B. Construct formwork so concrete members and structures are of size, shape, alignment, elevation, and position indicated, within tolerance limits of ACI 117 (ACI 117M).
- C. Limit concrete surface irregularities, designated by ACI 347 as abrupt or gradual, as follows:
  - 1. Class A, 1/8 inch (3.2 mm) for smooth-formed finished surfaces.
  - 2. Class B, 1/4 inch (6 mm) for rough-formed finished surfaces.
- D. Construct forms tight enough to prevent loss of concrete mortar.
- E. Construct forms for easy removal without hammering or prying against concrete surfaces. Provide crush or wrecking plates where stripping may damage cast-concrete surfaces. Provide top forms for inclined surfaces steeper than 1.5 horizontal to 1 vertical.
  - 1. Install keyways, reglets, recesses, and the like, for easy removal.
  - 2. Do not use rust-stained steel form-facing material.
- F. Set edge forms, bulkheads, and intermediate screed strips for slabs to achieve required elevations and slopes in finished concrete surfaces. Provide and secure units to support screed strips; use strike-off templates or compacting-type screeds.
- G. Provide temporary openings for cleanouts and inspection ports where interior area of formwork is inaccessible. Close openings with panels tightly fitted to forms and securely braced to prevent loss of concrete mortar. Locate temporary openings in forms at inconspicuous locations.

- H. Chamfer exterior corners and edges of permanently exposed concrete.
- I. Form openings, chases, offsets, sinkages, keyways, reglets, blocking, screeds, and bulkheads required in the Work. Determine sizes and locations from trades providing such items.
- J. Clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, and other debris just before placing concrete.
- K. Retighten forms and bracing before placing concrete, as required, to prevent mortar leaks and maintain proper alignment.
- L. Coat contact surfaces of forms with form-release agent, according to manufacturer's written instructions, before placing reinforcement.

### 3.2 EMBEDDED ITEM INSTALLATION

- A. Place and secure anchorage devices and other embedded items required for adjoining work that is attached to or supported by cast-in-place concrete. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
  - 1. Install anchor rods, accurately located, to elevations required and complying with tolerances in Section 7.5 of AISC 303.

#### 3.3 REMOVING AND REUSING FORMS

- A. General: Formwork for sides of beams, walls, columns, and similar parts of the Work that does not support weight of concrete may be removed after cumulatively curing at not less than 50 deg F (10 deg C) for 24 hours after placing concrete. Concrete has to be hard enough to not be damaged by form-removal operations, and curing and protection operations need to be maintained.
  - 1. Leave formwork for beam soffits, joists, slabs, and other structural elements that support weight of concrete in place until concrete has achieved at least 70 percent of its 28-day design compressive strength.
  - 2. Remove forms only if shores have been arranged to permit removal of forms without loosening or disturbing shores.
- B. Clean and repair surfaces of forms to be reused in the Work. Split, frayed, delaminated, or otherwise damaged form-facing material are not acceptable for exposed surfaces. Apply new form-release agent.
- C. When forms are reused, clean surfaces, remove fins and laitance, and tighten to close joints. Align and secure joints to avoid offsets. Do not use patched forms for exposed concrete surfaces unless approved by Architect.

### 3.4 SHORING AND RESHORING INSTALLATION

- A. Comply with ACI 318 (ACI 318M) and ACI 301 (ACI 301M) for design, installation, and removal of shoring and reshoring.
  - 1. Do not remove shoring or reshoring until measurement of slab tolerances is complete.

### 3.5 VAPOR BARRIER INSTALLATION

- A. Sheet Vapor Barrier: Place, protect, and repair sheet vapor barrier according to ASTM E 1643 and manufacturer's written instructions.
  - 1. Lap joints 12 inches (300 mm) and seal with manufacturer's recommended tape.

### 3.6 STEEL REINFORCEMENT INSTALLATION

- A. General: Comply with CRSI's "Manual of Standard Practice" for fabricating, placing, and supporting reinforcement.
  - 1. Do not cut or puncture vapor barrier. Repair damage and reseal vapor barrier before placing concrete.
- B. Clean reinforcement of loose rust and mill scale, earth, ice, and other foreign materials that reduce bond to concrete.
- C. Accurately position, support, and secure reinforcement against displacement. Locate and support reinforcement with bar supports to maintain minimum concrete cover. Do not tack weld crossing reinforcing bars.
  - 1. Weld reinforcing bars according to AWS D1.4/D 1.4M, where indicated.
- D. Set wire ties with ends directed into concrete, not toward exposed concrete surfaces.
- E. Install welded-wire reinforcement in longest practicable lengths on bar supports spaced to minimize sagging. Lap edges and ends of adjoining sheets at least one mesh spacing. Offset laps of adjoining sheet widths to prevent continuous laps in either direction. Lace overlaps with wire.

#### 3.7 JOINTS

- A. General: Construct joints true to line with faces perpendicular to surface plane of concrete.
- B. Construction Joints: Install so strength and appearance of concrete are not impaired, at locations indicated or as approved by Architect.
  - 1. Place joints perpendicular to main reinforcement. Continue reinforcement across construction joints unless otherwise indicated. Do not continue reinforcement through sides of strip placements of floors and slabs.

- 2. Space vertical joints in walls as indicated. Locate joints beside piers integral with walls, near corners, and in concealed locations where possible.
- 3. Use a bonding agent at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
- 4. Use epoxy-bonding adhesive at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
- C. Contraction Joints in Slabs-on-Grade: Form weakened-plane contraction joints, sectioning concrete into areas as indicated. Construct contraction joints for a depth equal to at least one-fourth of concrete thickness as follows:
  - 1. Grooved Joints: Form contraction joints after initial floating by grooving and finishing each edge of joint to a radius of 1/8 inch (3.2 mm). Repeat grooving of contraction joints after applying surface finishes. Eliminate groover tool marks on concrete surfaces.
  - 2. Sawed Joints: Form contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch- (3.2-mm-) wide joints into concrete when cutting action does not tear, abrade, or otherwise damage surface and before concrete develops random contraction cracks.
- D. Doweled Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or asphalt coat one-half of dowel length to prevent concrete bonding to one side of joint.

# 3.8 CONCRETE PLACEMENT

- A. Before placing concrete, verify that installation of formwork, reinforcement, and embedded items is complete and that required inspections are completed.
- B. Do not add water to concrete during delivery, at Project site, or during placement unless approved by Architect.
- C. Before test sampling and placing concrete, water may be added at Project site, subject to limitations of ACI 301 (ACI 301M).
  - 1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.
- D. Deposit concrete continuously in one layer or in horizontal layers of such thickness that no new concrete is placed on concrete that has hardened enough to cause seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as indicated. Deposit concrete to avoid segregation.
  - 1. Deposit concrete in horizontal layers of depth not to exceed formwork design pressures and in a manner to avoid inclined construction joints.
  - 2. Consolidate placed concrete with mechanical vibrating equipment according to ACI 301 (ACI 301M).
  - 3. Do not use vibrators to transport concrete inside forms. Insert and withdraw vibrators vertically at uniformly spaced locations to rapidly penetrate placed layer and at least 6 inches (150 mm) into preceding layer. Do not insert vibrators into lower layers of concrete that have begun to lose plasticity. At each insertion, limit duration of vibration to time

necessary to consolidate concrete and complete embedment of reinforcement and other embedded items without causing mixture constituents to segregate.

- E. Deposit and consolidate concrete for floors and slabs in a continuous operation, within limits of construction joints, until placement of a panel or section is complete.
  - 1. Consolidate concrete during placement operations, so concrete is thoroughly worked around reinforcement and other embedded items and into corners.
  - 2. Maintain reinforcement in position on chairs during concrete placement.
  - 3. Screed slab surfaces with a straightedge and strike off to correct elevations.
  - 4. Slope surfaces uniformly to drains where required.
  - 5. Begin initial floating using bull floats or darbies to form a uniform and open-textured surface plane, before excess bleedwater appears on the surface. Do not further disturb slab surfaces before starting finishing operations.

# 3.9 FINISHING FLOORS AND SLABS

- A. General: Comply with ACI 302.1R recommendations for screeding, restraightening, and finishing operations for concrete surfaces. Do not wet concrete surfaces.
- B. Float Finish: Consolidate surface with power-driven floats or by hand floating if area is small or inaccessible to power-driven floats. Restraighten, cut down high spots, and fill low spots. Repeat float passes and restraightening until surface is left with a uniform, smooth, granular texture.
  - 1. Apply float finish to surfaces to receive trowel finish.
- C. Trowel Finish: After applying float finish, apply first troweling and consolidate concrete by hand or power-driven trowel. Continue troweling passes and restraighten until surface is free of trowel marks and uniform in texture and appearance. Grind smooth any surface defects that would telegraph through applied coatings or floor coverings.
  - 1. Apply a trowel finish to surfaces exposed to view or to be covered with resilient flooring, carpet, ceramic or quarry tile set over a cleavage membrane, paint, or another thin-film-finish coating system.
  - 2. Finish surfaces to the following tolerances, according to ASTM E 1155 (ASTM E 1155M), for a randomly trafficked floor surface:
    - a. Specified overall values of flatness, F(F) 35; and of levelness, F(L) 25; with minimum local values of flatness, F(F) 24; and of levelness, F(L) 17; for slabs-on-grade.

# 3.10 MISCELLANEOUS CONCRETE ITEM INSTALLATION

A. Filling In: Fill in holes and openings left in concrete structures after work of other trades is in place unless otherwise indicated. Mix, place, and cure concrete, as specified, to blend with inplace construction. Provide other miscellaneous concrete filling indicated or required to complete the Work.

- B. Curbs: Provide monolithic finish to interior curbs by stripping forms while concrete is still green and by steel-troweling surfaces to a hard, dense finish with corners, intersections, and terminations slightly rounded.
- C. Equipment Bases and Foundations:
  - 1. Coordinate sizes and locations of concrete bases with actual equipment provided.
  - 2. Construct concrete bases 4 inches high unless otherwise indicated, and extend base not less than 6 inches (150 mm) in each direction beyond the maximum dimensions of supported equipment unless otherwise indicated or unless required for seismic anchor support.
  - 3. Minimum Compressive Strength: match supporting construction.
  - 4. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch (450-mm) centers around the full perimeter of concrete base.
  - 5. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete substrate.
  - 6. Prior to pouring concrete, place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
  - 7. Cast anchor-bolt insert into bases. Install anchor bolts to elevations required for proper attachment to supported equipment.

# 3.11 CONCRETE PROTECTING AND CURING

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. Comply with ACI 306.1 for cold-weather protection and ACI 301 (ACI 301M) for hot-weather protection during curing.
- B. Evaporation Retarder: Apply evaporation retarder to unformed concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h (1 kg/sq. m x h) before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying concrete, but before float finishing.
- C. Formed Surfaces: Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces. If forms remain during curing period, moist cure after loosening forms. If removing forms before end of curing period, continue curing for remainder of curing period.
- D. Unformed Surfaces: Begin curing immediately after finishing concrete. Cure unformed surfaces, including floors and slabs, concrete floor toppings, and other surfaces.
- E. Cure concrete according to ACI 308.1, by one or a combination of the following methods:
  - 1. Moisture Curing: Keep surfaces continuously moist for not less than seven days with the following materials:
    - a. Water.
    - b. Continuous water-fog spray.
    - c. Absorptive cover, water saturated, and kept continuously wet. Cover concrete surfaces and edges with 12-inch (300-mm) lap over adjacent absorptive covers.

- 2. Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches (300 mm), and sealed by waterproof tape or adhesive. Cure for not less than seven days. Immediately repair any holes or tears during curing period, using cover material and waterproof tape.
  - a. Moisture cure or use moisture-retaining covers to cure concrete surfaces to receive floor coverings.
  - b. Moisture cure or use moisture-retaining covers to cure concrete surfaces to receive penetrating liquid floor treatments.
  - c. Cure concrete surfaces to receive floor coverings with either a moisture-retaining cover or a curing compound that the manufacturer certifies does not interfere with bonding of floor covering used on Project.

# 3.12 JOINT FILLING

- A. Prepare, clean, and install joint filler according to manufacturer's written instructions.
  - 1. Defer joint filling until concrete has aged at least one month(s). Do not fill joints until construction traffic has permanently ceased.
- B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joints clean and dry.
- C. Install semirigid joint filler full depth in saw-cut joints and at least 2 inches (50 mm) deep in formed joints. Overfill joint and trim joint filler flush with top of joint after hardening.

# 3.13 CONCRETE SURFACE REPAIRS

- A. Defective Concrete: Repair and patch defective areas when approved by Architect. Remove and replace concrete that cannot be repaired and patched to Architect's approval.
- B. Patching Mortar: Mix dry-pack patching mortar, consisting of 1 part portland cement to 2-1/2 parts fine aggregate passing a No. 16 (1.18-mm) sieve, using only enough water for handling and placing.
- C. Repairing Formed Surfaces: Surface defects include color and texture irregularities, cracks, spalls, air bubbles, honeycombs, rock pockets, fins and other projections on the surface, and stains and other discolorations that cannot be removed by cleaning.
  - Immediately after form removal, cut out honeycombs, rock pockets, and voids more than 1/2 inch (13 mm) in any dimension to solid concrete. Limit cut depth to 3/4 inch (19 mm). Make edges of cuts perpendicular to concrete surface. Clean, dampen with water, and brush-coat holes and voids with bonding agent. Fill and compact with patching mortar before bonding agent has dried. Fill form-tie voids with patching mortar or cone plugs secured in place with bonding agent.

- 2. Repair defects on surfaces exposed to view by blending white portland cement and standard portland cement so that, when dry, patching mortar matches surrounding color. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching. Compact mortar in place and strike off slightly higher than surrounding surface.
- 3. Repair defects on concealed formed surfaces that affect concrete's durability and structural performance as determined by Architect.
- D. Repairing Unformed Surfaces: Test unformed surfaces, such as floors and slabs, for finish and verify surface tolerances specified for each surface. Correct low and high areas. Test surfaces sloped to drain for trueness of slope and smoothness; use a sloped template.
  - 1. Repair finished surfaces containing defects. Surface defects include spalls, popouts, honeycombs, rock pockets, crazing and cracks in excess of 0.01 inch (0.25 mm) wide or that penetrate to reinforcement or completely through unreinforced sections regardless of width, and other objectionable conditions.
  - 2. After concrete has cured at least 14 days, correct high areas by grinding.
  - 3. Correct localized low areas during or immediately after completing surface finishing operations by cutting out low areas and replacing with patching mortar. Finish repaired areas to blend into adjacent concrete.
  - 4. Correct other low areas scheduled to receive floor coverings with a repair underlayment. Prepare, mix, and apply repair underlayment and primer according to manufacturer's written instructions to produce a smooth, uniform, plane, and level surface. Feather edges to match adjacent floor elevations.
  - 5. Correct other low areas scheduled to remain exposed with a repair topping. Cut out low areas to ensure a minimum repair topping depth of 1/4 inch (6 mm) to match adjacent floor elevations. Prepare, mix, and apply repair topping and primer according to manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.
  - 6. Repair defective areas, except random cracks and single holes 1 inch (25 mm) or less in diameter, by cutting out and replacing with fresh concrete. Remove defective areas with clean, square cuts and expose steel reinforcement with at least a 3/4-inch (19-mm) clearance all around. Dampen concrete surfaces in contact with patching concrete and apply bonding agent. Mix patching concrete of same materials and mixture as original concrete, except without coarse aggregate. Place, compact, and finish to blend with adjacent finished concrete. Cure in same manner as adjacent concrete.
  - 7. Repair random cracks and single holes 1 inch (25 mm) or less in diameter with patching mortar. Groove top of cracks and cut out holes to sound concrete and clean off dust, dirt, and loose particles. Dampen cleaned concrete surfaces and apply bonding agent. Place patching mortar before bonding agent has dried. Compact patching mortar and finish to match adjacent concrete. Keep patched area continuously moist for at least 72 hours.
- E. Perform structural repairs of concrete, subject to Architect's approval, using epoxy adhesive and patching mortar.
- F. Repair materials and installation not specified above may be used, subject to Architect's approval.

# 3.14 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a special inspector and qualified testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Testing Agency: Engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports.
- C. Inspections:
  - 1. Steel reinforcement placement.
  - 2. Steel reinforcement welding.
  - 3. Headed bolts and studs.
  - 4. Verification of use of required design mixture.
  - 5. Concrete placement, including conveying and depositing.
  - 6. Curing procedures and maintenance of curing temperature.
  - 7. Verification of concrete strength before removal of shores and forms from beams and slabs.
- D. Concrete Tests: Testing of composite samples of fresh concrete obtained according to ASTM C 172/C 172M shall be performed according to the following requirements:
  - 1. Testing Frequency: Obtain one composite sample for each day's pour of each concrete mixture exceeding 5 cu. yd. (4 cu. m), but less than 25 cu. yd. (19 cu. m), plus one set for each additional 100 cu. yd. (38 cu. m) or fraction thereof.
  - 2. Slump: ASTM C 143/C 143M; one test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture. Perform additional tests when concrete consistency appears to change.
  - 3. Air Content: ASTM C 231/C 231M, pressure method, for normal-weight concrete; one test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
  - 4. Concrete Temperature: ASTM C 1064/C 1064M; one test hourly when air temperature is 40 deg F (4.4 deg C) and below or 80 deg F (27 deg C) and above, and one test for each composite sample.
  - 5. Compression Test Specimens: ASTM C 31/C 31M.
    - a. Cast and laboratory cure two sets of two standard cylinder specimens for each composite sample.
    - b. Cast and field cure two sets of two standard cylinder specimens for each composite sample.
  - 6. Compressive-Strength Tests: ASTM C 39/C 39M; test one set of three laboratory-cured specimens at 7 days and one set of three specimens at 28 days.
    - a. Test one set of three field-cured specimens at 7 days and one set of three specimens at 28 days.
    - b. A compressive-strength test shall be the average compressive strength from a set of three specimens obtained from same composite sample and tested at age indicated.

- 7. When strength of field-cured cylinders is less than 85 percent of companion laboratorycured cylinders, Contractor shall evaluate operations and provide corrective procedures for protecting and curing in-place concrete.
- 8. Strength of each concrete mixture will be satisfactory if every average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength and no compressive-strength test value falls below specified compressive strength by more than 500 psi (3.4 MPa).
- 9. Test results shall be reported in writing to Architect, concrete manufacturer, and Contractor within 48 hours of testing. Reports of compressive-strength tests shall contain Project identification name and number, date of concrete placement, name of concrete testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mixture proportions and materials, compressive breaking strength, and type of break for both 7- and 28-day tests.
- 10. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
- 11. Additional Tests: Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect. Testing and inspecting agency may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C 42/C 42M or by other methods as directed by Architect.
- 12. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.
- 13. Correct deficiencies in the Work that test reports and inspections indicate do not comply with the Contract Documents.
- E. Measure floor and slab flatness and levelness according to ASTM E 1155 (ASTM E 1155M) within 24 hours of finishing.

END OF SECTION 033000
# SECTION 066400 - PLASTIC PANELING

#### 1.1 SUMMARY

- A. Section Includes:
  - 1. Plastic sheet paneling.
- B. Related Requirements:
  - 1. Section 102600 "Wall and Door Protection" for corner guards installed over plastic paneling.

## 1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For plastic paneling, in manufacturer's standard sizes.

## 1.3 QUALITY ASSURANCE

A. Testing Agency: Acceptable to authorities having jurisdiction

# 1.4 **PROJECT CONDITIONS**

A. Environmental Limitations: Do not deliver or install plastic paneling until spaces are enclosed and weathertight and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

# PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

A. Source Limitations: Obtain plastic paneling and trim accessories from single manufacturer.

# 2.2 PLASTIC SHEET PANELING

A. Glass-Fiber-Reinforced Plastic Paneling: Gelcoat-finished, glass-fiber-reinforced plastic panels complying with ASTM D5319. Panels shall be USDA accepted for incidental food contact.

## PLASTIC PANELING

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Crane Composites, Inc.
  - b. Marlite.
  - c. Nudo Products, Inc.
- 2. Surface-Burning Characteristics: As follows when tested by a qualified testing agency according to ASTM E84. Identify products with appropriate markings of applicable testing agency.
  - a. Flame-Spread Index: 25 or less.
  - b. Smoke-Developed Index: 450 or less.
- 3. Nominal Thickness: Not less than 0.075 inch
- 4. Surface Finish: As indicated on drawings or as selected by Architect from manufacturer's full range.
- 5. Color: As indicated on drawings or as selected by Architect from manufacturer's full range.

# 2.3 ACCESSORIES

- A. Trim Accessories: Manufacturer's standard one-piece vinyl extrusions designed to retain and cover edges of panels. Provide division bars, inside corners, outside corners, and caps as needed to conceal edges.
  - 1. Color: As indicated on drawings or as selected by Architect from manufacturer's full range
- B. Exposed Fasteners: Nylon drive rivets recommended by panel manufacturer.
- C. Concealed Mounting Splines: Continuous, H-shaped aluminum extrusions designed to fit into grooves routed in edges of factory-laminated panels and to be fastened to substrate.
- D. Adhesive: As recommended by plastic paneling manufacturer.
- E. Sealant: Mildew-resistant, single-component, neutral-curing silicone sealant recommended by plastic paneling manufacturer.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

# PLASTIC PANELING

## 3.2 PREPARATION

- A. Remove wallpaper, vinyl wall covering, loose or soluble paint, and other materials that might interfere with adhesive bond.
- B. Prepare substrate by sanding high spots and filling low spots as needed to provide flat, even surface for panel installation.
- C. Clean substrates of substances that could impair adhesive bond, including oil, grease, dirt, and dust.
- D. Condition panels by unpacking and placing in installation space before installation according to manufacturer's written recommendations.
- E. Lay out paneling before installing. Locate panel joints to provide equal panels at ends of walls not less than half the width of full panels.
  - 1. Mark plumb lines on substrate at panel joint locations for accurate installation.
  - 2. Locate panel joints to allow clearance at panel edges according to manufacturer's written instructions.

# 3.3 INSTALLATION

- A. Install plastic paneling according to manufacturer's written instructions.
- B. Install panels in a full spread of adhesive.
- C. Install factory-laminated panels using concealed mounting splines in panel joints.
- D. Install trim accessories with adhesive. Do not fasten through panels.
- E. Fill grooves in trim accessories with sealant before installing panels, and bed inside corner trim in a bead of sealant.
- F. Maintain uniform space between panels and wall fixtures. Fill space with sealant.
- G. Maintain uniform space between adjacent panels and between panels and floors, ceilings, and fixtures. Fill space with sealant.
- H. Remove excess sealant and smears as paneling is installed. Clean with solvent recommended by sealant manufacturer and then wipe with clean dry cloths until no residue remains.

END OF SECTION 066400

## PLASTIC PANELING

## SECTION 077200 - ROOF ACCESSORIES

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Roof curbs.
  - 2. Equipment supports.
  - 3. Pipe and duct supports.
  - 4. Preformed flashing sleeves.
- B. Related Requirements:
  - 1. Section 230548 "Vibration and Seismic Controls for HVAC" for special curbs designed to accommodate seismic and vibration controls.

## 1.3 COORDINATION

- A. Coordinate layout and installation of roof accessories with adjoining construction to provide a leakproof, weathertight, secure, and noncorrosive installation.
- B. Coordinate dimensions with rough-in information or Shop Drawings of equipment to be supported.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of roof accessory.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
- B. Shop Drawings: For roof accessories.
  - 1. Include plans, elevations, keyed details, and attachments to other work. Indicate dimensions, loadings, and special conditions. Distinguish between plant- and field-assembled work.

- C. Samples: For each exposed product and for each color and texture specified, prepared on Samples of size to adequately show color.
- D. Delegated-Design Submittal: For roof curbs and equipment supports indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
  - 1. Detail mounting, securing, and flashing of roof-mounted items to roof structure. Indicate coordinating requirements with roof membrane system.
  - 2. Wind-Restraint Details: Detail fabrication and attachment of wind restraints. Show anchorage details and indicate quantity, diameter, and depth of penetration of anchors.

# 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Roof plans, drawn to scale, and coordinating penetrations and roofmounted items. Show the following:
  - 1. Size and location of roof accessories specified in this Section.
  - 2. Method of attaching roof accessories to roof or building structure.
  - 3. Other roof-mounted items including mechanical and electrical equipment, ductwork, piping, and conduit.
  - 4. Required clearances.
- B. Sample Warranties: For manufacturer's special warranties.

# 1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For roof accessories to include in operation and maintenance manuals.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. General Performance: Roof accessories shall withstand exposure to weather and resist thermally induced movement without failure, rattling, leaking, or fastener disengagement due to defective manufacture, fabrication, installation, or other defects in construction.
- B. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design roof curbs and equipment supports to comply with wind performance requirements, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- C. Wind-Restraint Performance: TBD

# 2.2 ROOF CURBS

- A. Roof Curbs: Internally reinforced roof-curb units capable of supporting superimposed live and dead loads, including equipment loads and other construction indicated on Drawings, bearing continuously on roof structure, and capable of meeting performance requirements; with welded or mechanically fastened and sealed corner joints,[straight sides,] [integral metal cant,] [stepped integral metal cant raised the thickness of roof insulation,] and integrally formed deck-mounting flange at perimeter bottom.
  - 1. <u><Double click here to find, evaluate, and insert list of manufacturers and products.></u>
- B. Size: Coordinate dimensions with roughing-in information or Shop Drawings of equipment to be supported.
- C. Supported Load Capacity: [Coordinate load capacity with information on Shop Drawings of equipment to be supported] <Insert load requirements>.
- D. Material: [Zinc-coated (galvanized)] [Aluminum-zinc alloy-coated] steel sheet, [0.052 inch (1.32 mm)] [0.064 inch (1.63 mm)] [0.079 inch (2.01 mm)] <Insert dimension> thick.
  - 1. Finish: [Mill phosphatized] [Factory prime coating] [Two-coat fluoropolymer] [Baked enamel or powder coat] <Insert finish>.
  - 2. Color: [As indicated by manufacturer's designations] [Match Architect's sample] [As selected by Architect from manufacturer's full range] <Insert color>.
- E. Material: Aluminum sheet, [0.090 inch (2.28 mm)] [0.125 inch (3.17 mm)] <Insert dimension> thick.
  - 1. Finish: [Mill] [Factory prime coating] [Clear anodic] [Color anodic] [Two-coat fluoropolymer] [Baked enamel or powder coat] <Insert finish>.
  - 2. Color: [As indicated by manufacturer's designations] [Match Architect's sample] [As selected by Architect from manufacturer's full range] [Light bronze] [Medium bronze] [Dark bronze] <Insert color>.
- F. Material: Stainless steel sheet, [0.0781 inch (1.983 mm)] <Insert dimension> thick.
  - 1. Finish: [Manufacturer's standard] [ASTM A480/A480M, No. 2D, directional polish finish] <Insert finish>.
- G. Construction:
  - 1. Curb Profile: **Profile as indicated on Drawings** compatible with roofing system.
  - 2. On ribbed or fluted metal roofs, form deck-mounting flange at perimeter bottom to conform to roof profile.
  - 3. Fabricate curbs to minimum height of 12 inches above roofing surface unless otherwise indicated.
  - 4. Top Surface: Level top of curb, with roof slope accommodated
  - 5. Sloping Roofs: Where roof slope exceeds 1:48, fabricate curb with perimeter curb height tapered to accommodate roof slope so that top surface of perimeter curb is level. Equip unit with water diverter or cricket on side that obstructs water flow.

- 6. Insulation: Factory insulated with [1-1/2-inch- (38-mm-)] <Insert dimension> thick glass-fiber board insulation.
- 7. Liner: Same material as curb, of manufacturer's standard thickness and finish.
- 8. Nailer: Factory-installed wood nailer [along top flange of curb] [under top flange on side of curb], continuous around curb perimeter.
- 9. Wind Restraint Straps and Base Flange Attachment: Provide wind restraint straps, welded strap connectors, and base flange attachment to roof structure at perimeter of curb, of size and spacing required to meet wind uplift requirements.
- 10. Platform Cap: Where portion of roof curb is not covered by equipment, provide weathertight platform cap formed from 3/4-inch- (19-mm-) thick plywood covered with metal sheet of same type, thickness, and finish as required for curb.
- 11. Metal Counterflashing: Manufacturer's standard, removable, fabricated of same metal and finish as curb.
- 12. Damper Tray: Provide damper tray or shelf with opening [3 inches (76 mm)] <Insert dimension> [less than interior curb dimensions indicated] [of size indicated].

# 2.3 EQUIPMENT SUPPORTS

- A. Equipment Supports: [Internally reinforced perimeter] [Rail-type] metal equipment supports capable of supporting superimposed live and dead loads between structural supports, including equipment loads and other construction indicated on Drawings, spanning between structural supports; capable of meeting performance requirements; with welded[ or mechanically fastened and sealed] corner joints,[ integral metal cant,] [ stepped integral metal cant raised the thickness of roof insulation,] and integrally formed structure-mounting flange at bottom.
  - 1. <a>Souther click here to find, evaluate, and insert list of manufacturers and products.</a>
- B. Size: Coordinate dimensions with roughing-in information or Shop Drawings of equipment to be supported.
- C. Supported Load Capacity: [Coordinate load capacity with information on Shop Drawings of equipment to be supported] <Insert load requirements>.
- D. Material: [Zinc-coated (galvanized)] [Aluminum-zinc alloy-coated] steel sheet, [0.052 inch (1.32 mm)] [0.064 inch (1.63 mm)] [0.079 inch (2.01 mm)] <Insert dimension> thick.
  - 1. Finish: [Mill phosphatized] [Factory prime coating] [Two-coat fluoropolymer] [Baked enamel or powder coat] <Insert finish>.
  - 2. Color: [As indicated by manufacturer's designations] [Match Architect's sample] [As selected by Architect from manufacturer's full range] <Insert color>.
- E. Material: Aluminum sheet, [0.090 inch (2.28 mm)] [0.125 inch (3.17 mm)] <Insert dimension> thick.
  - 1. Finish: [Mill] [Factory prime coating] [Clear anodic] [Color anodic] [Two-coat fluoropolymer] [Baked enamel or powder coat] <Insert finish>.

- 2. Color: [As indicated by manufacturer's designations] [Match Architect's sample] [As selected by Architect from manufacturer's full range] [Light bronze] [Medium bronze] [Dark bronze] <Insert color>.
- F. Material: Stainless steel sheet, [0.0781 inch (1.983 mm)] <Insert dimension> thick.
  - 1. Finish: [Manufacturer's standard] [ASTM A480/A480M, No. 2D, directional polish finish] <Insert finish>.

# G. Construction:

- 1. Curb Profile: [Manufacturer's standard] [Profile as indicated on Drawings] compatible with roofing system.
- 2. Insulation: Factory insulated with [1-1/2-inch- (38-mm-)] <Insert dimension> thick glass-fiber board insulation.
- 3. Liner: Same material as equipment support, of manufacturer's standard thickness and finish.
- Nailer: Factory-installed continuous wood nailers [3-1/2 inches (90 mm)] [5-1/2 inches (140 mm)] <Insert dimension> wide [on top flange of equipment supports] [under top flange on side of curb], continuous around support perimeter.
- 5. Wind Restraint Straps and Base Flange Attachment: Provide wind restraint straps, welded strap connectors, and base flange attachment to roof structure at perimeter of curb of size and spacing required to meet wind uplift requirements.
- 6. Platform Cap: Where portion of equipment support is not covered by equipment, provide weathertight platform cap formed from 3/4-inch- (19-mm-) thick plywood covered with metal sheet of same type, thickness, and finish as required for curb.
- 7. Metal Counterflashing: Manufacturer's standard, removable, fabricated of same metal and finish as equipment support.
- 8. On ribbed or fluted metal roofs, form deck-mounting flange at perimeter bottom to conform to roof profile.
- 9. Fabricate equipment supports to minimum height of [12 inches (305 mm)] <Insert dimension> above roofing surface unless otherwise indicated.
- 10. Sloping Roofs: Where roof slope exceeds 1:48, fabricate each support with height to accommodate roof slope so that tops of supports are level with each other. Equip supports with water diverters or crickets on sides that obstruct water flow.
- 11. Security Grille: [Provide for all units] [Provide where indicated on Drawings].

# 2.4 PIPE AND DUCT SUPPORTS

- A. Fixed-Height Cradle-Type Pipe Supports: Polycarbonate pipe stand accommodating up to [1-1/2-inch- (38-mm-)] <Insert dimension> diameter pipe or conduit; with provision for pipe retainer and with manufacturer's support pad or deck plate as recommended for penetration-free installation over roof membrane type; as required for quantity of pipe runs and sizes.
- B. Fixed-Height Roller-Bearing Pipe Supports: Polycarbonate pipe stand with [polycarbonate] [stainless steel] roller carrying assembly accommodating up to [7-inch- (178-mm-)] <Insert dimension> diameter pipe or conduit; with provision for pipe retainer and with manufacturer's support pad or deck plate as recommended for penetration-free installation over roof membrane type; as required for quantity of pipe runs and sizes.

- C. Adjustable-Height Roller-Bearing Pipe Supports: Polycarbonate pipe stand base, pipe support, and roller housing, with stainless steel threaded rod designed for adjusting support height, accommodating up to [18 inch (457 mm)] <Insert dimension> diameter pipe or conduit; with provision for pipe retainer and with manufacturer's support pad or deck plate as recommended for penetration-free installation over roof membrane type; as required for quantity of pipe runs and sizes.
- D. Adjustable-Height Structure-Mounted Pipe Supports: Extruded-aluminum tube, filled with urethane insulation; [2 inches (50 mm)] <Insert dimension> in diameter; accommodating up to [7-inch- (178-mm-)] <Insert dimension> diameter pipe or conduit, with provision for pipe retainer; with aluminum baseplate, EPDM base seal, manufacturer's recommended hardware for mounting to structure or structural roof deck as indicated, stainless steel roller and retainer, and extruded-aluminum carrier assemblies; as required for quantity of pipe runs and sizes.
- E. Curb-Mounted Pipe Supports: Galvanized steel support with welded or mechanically fastened and sealed corner joints,[straight sides,] [ integral metal cant,] [ stepped integral metal cant raised the thickness of roof insulation,] and integrally formed deck-mounting flange at perimeter bottom; with adjustable-height roller-bearing pipe support accommodating up to [20inch- (508-mm-)] <Insert dimension> diameter pipe or conduit and with provision for pipe retainer; as required for quantity of pipe runs and sizes.
  - 1. <a>Souther click here to find, evaluate, and insert list of manufacturers and products.</a>
- F. Duct Supports: Extruded-aluminum, urethane-insulated supports, [2 inches (50 mm)] <Insert dimension> in diameter; with manufacturer's recommended hardware for mounting to structure or structural roof deck.
  - 1. <u><Double click here to find, evaluate, and insert list of manufacturers and products.></u>
  - 2. Finish: [Manufacturer's standard] <Insert finish>.

# 2.5 PIPE PORTALS

- A. Curb-Mounted Pipe Portal: Insulated roof-curb units with welded or mechanically fastened and sealed corner joints, [straight sides,] [integral metal cant,] [stepped integral metal cant raised the thickness of roof insulation,] and integrally formed deck-mounting flange at perimeter bottom; with weathertight curb cover with single or multiple collared openings and pressure-sealed conically shaped EPDM protective rubber caps sized for piping indicated, with stainless steel snaplock swivel clamps.
  - 1. <u><Double click here to find, evaluate, and insert list of manufacturers and products.></u>
- B. Flashing Pipe Portal: Formed aluminum membrane-mounting flashing flange and sleeve with collared opening and pressure-sealed conically shaped EPDM protective rubber cap sized for piping indicated, with stainless steel snaplock swivel clamps.
  - 1. <a>Souther click here to find, evaluate, and insert list of manufacturers and products.</a>

# 2.6 PREFORMED FLASHING SLEEVES

- A. Exhaust Vent Flashing: Double-walled metal flashing sleeve or boot, insulation filled, with integral deck flange, [12 inches (300 mm)] <Insert dimension> high, with removable metal hood and [slotted] [perforated] metal collar.
  - 1. <Double click here to find, evaluate, and insert list of manufacturers and products.>
  - 2. Metal: Aluminum sheet, [0.063 inch (1.60 mm)] <Insert thickness> thick.
  - 3. Diameter: [As indicated on Drawings] [3 inches (76 mm)] [4 inches (100 mm)] [5 inches (125 mm)] [6 inches (150 mm)] [7 inches (175 mm)] [8 inches (200 mm)] [9 inches (225 mm)] [10 inches (250 mm)]
  - 4. Finish: [Manufacturer's standard] <Insert finish>.
- B. Vent Stack Flashing: Metal flashing sleeve, uninsulated, with integral deck flange.
  - 1. < Double click here to find, evaluate, and insert list of manufacturers and products.>
  - 2. Metal: [Aluminum sheet, 0.063 inch (1.60 mm) thick] <Insert material and thickness>.
  - 3. Height: [7 inches (175 mm)] [13 inches (330 mm)] [19 inches (480 mm)] <Insert dimension>.
  - 4. Diameter: [As indicated on Drawings] [2 inches (50 mm)] [3 inches (76 mm)] [4 inches (100 mm)] [5 inches (125 mm)] [6 inches (150 mm)] <Insert dimension>.
  - 5. Finish: [Manufacturer's standard] <Insert finish>.

#### 2.7 GENERAL FINISH REQUIREMENTS

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

# PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, to verify actual locations, dimensions, and other conditions affecting performance of the Work.
- B. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
- C. Verify dimensions of roof openings for roof accessories.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 INSTALLATION

- A. Install roof accessories according to manufacturer's written instructions.
  - 1. Install roof accessories level; plumb; true to line and elevation; and without warping, jogs in alignment, buckling, or tool marks.
  - 2. Anchor roof accessories securely in place so they are capable of resisting indicated loads.
  - 3. Use fasteners, separators, sealants, and other miscellaneous items as required to complete installation of roof accessories and fit them to substrates.
  - 4. Install roof accessories to resist exposure to weather without failing, rattling, leaking, or loosening of fasteners and seals.
- B. Metal Protection: Protect metals against galvanic action by separating dissimilar metals from contact with each other or with corrosive substrates by painting contact surfaces with bituminous coating or by other permanent separation as recommended by manufacturer.
  - 1. Coat concealed side of [**uncoated aluminum**] [**stainless steel**] roof accessories with bituminous coating where in contact with wood, ferrous metal, or cementitious construction.
  - 2. Underlayment: Where installing roof accessories directly on cementitious or wood substrates, install a course of underlayment and cover with manufacturer's recommended slip sheet.
  - 3. Bed flanges in thick coat of asphalt roofing cement where required by manufacturers of roof accessories for waterproof performance.
- C. Roof Curb Installation: Install each roof curb so top surface is level.
- D. Equipment Support Installation: Install equipment supports so top surfaces are level with each other.
- E. Pipe Support Installation: Comply with MSS SP-58 and MSS SP-89. Install supports and attachments as required to properly support piping. Arrange for grouping of parallel runs of horizontal piping, and support together.
  - 1. Pipes of Various Sizes: Space supports for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.
- F. Preformed Flashing-Sleeve[ and Flashing Pipe Portal] Installation: Secure flashing sleeve to roof membrane according to flashing-sleeve manufacturer's written instructions; flash sleeve flange to surrounding roof membrane according to roof membrane manufacturer's instructions.

# 3.3 REPAIR AND CLEANING

- A. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas and repair galvanizing according to ASTM A780/A780M.
- B. Touch up factory-primed surfaces with compatible primer ready for field painting.
- C. Clean exposed surfaces according to manufacturer's written instructions.

- D. Clean off excess sealants.
- E. Replace roof accessories that have been damaged or that cannot be successfully repaired by finish touchup or similar minor repair procedures.

END OF SECTION 077200

# SECTION 078413 - PENETRATION FIRESTOPPING

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Penetrations in fire-resistance-rated walls.
  - 2. Penetrations in horizontal assemblies.
  - 3. Penetrations in smoke barriers.
  - 4. Putty pad sealant.
  - 5. Delegated design.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Deferred Submittal Product Schedule: For each penetration firestopping system. Include location, illustration of firestopping system, and design designation of qualified testing and inspecting agency.
  - 1. Engineering Judgments: Where Project conditions require modification to a qualified testing agency's illustration for a particular firestopping system condition, submit illustration, with modifications marked, approved by firestopping system manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly.

## 1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

#### 1.5 CLOSEOUT SUBMITTALS

A. Installer Certificates: From Installer indicating that penetration firestopping systems have been installed in compliance with requirements and manufacturer's written instructions.

## 1.6 QUALITY ASSURANCE

A. Installer Qualifications: A firm that has been approved by FM Global according to FM Global 4991, "Approval of Firestop Contractors," or been evaluated by UL and found to comply with its "Qualified Firestop Contractor Program Requirements."

#### 1.7 **PROJECT CONDITIONS**

- A. Environmental Limitations: Do not install penetration firestopping system when ambient or substrate temperatures are outside limits permitted by penetration firestopping system manufacturers or when substrates are wet because of rain, frost, condensation, or other causes.
- B. Install and cure penetration firestopping materials per manufacturer's written instructions using natural means of ventilations or, where this is inadequate, forced-air circulation.

## 1.8 COORDINATION

- A. Coordinate construction of openings and penetrating items to ensure that penetration firestopping systems can be installed according to specified firestopping system design.
- B. Coordinate sizing of sleeves, openings, core-drilled holes, or cut openings to accommodate penetration firestopping systems.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics:
  - 1. Perform penetration firestopping system tests by a qualified testing agency acceptable to authorities having jurisdiction.
  - 2. Test per testing standards referenced in "Penetration Firestopping Systems" Article. Provide rated systems complying with the following requirements:
    - a. Penetration firestopping systems shall bear classification marking of a qualified testing agency.
      - 1) UL in its "Fire Resistance Directory."
      - 2) Intertek Group in its "Directory of Listed Building Products."
      - 3) FM Global in its "Building Materials Approval Guide."

# 2.2 PENETRATION FIRESTOPPING SYSTEMS

A. Penetration Firestopping Systems: Systems that resist spread of fire, passage of smoke and other gases, and maintain original fire-resistance rating of construction penetrated. Penetration

firestopping systems shall be compatible with one another, with the substrates forming openings, and with penetrating items if any.

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - a. A/D Fire Protection Systems Inc.
  - b. GCP (formerly Grace Construction Products).
  - c. Hilti, Inc.
  - d. Johns Manville.
  - e. Nelson Firestop Products.
  - f. NUCO Inc.
  - g. Passive Fire Protection Partners.
  - h. RectorSeal Corporation.
  - i. Specified Technologies Inc.
  - j. 3M Fire Protection Products.
  - k. Tremco, Inc.; Tremco Fire Protection Systems Group.
- B. USGCorporation Penetrations in Fire-Resistance-Rated Walls: Penetration firestopping systems with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa).
  - 1. F-Rating: Not less than the fire-resistance rating of constructions penetrated.
- C. Penetrations in Horizontal Assemblies: Penetration firestopping systems with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa).
  - 1. F-Rating: At least one hour, but not less than the fire-resistance rating of constructions penetrated.
  - 2. T-Rating: At least one hour, but not less than the fire-resistance rating of constructions penetrated except for floor penetrations within the cavity of a wall.
  - 3. W-Rating: Provide penetration firestopping systems showing no evidence of water leakage when tested according to UL 1479.
- D. Penetrations in Smoke Barriers: Penetration firestopping systems with ratings determined per UL 1479, based on testing at a positive pressure differential of 0.30-inch wg (74.7 Pa).
  - 1. L-Rating: Not exceeding 5.0 cfm/sq. ft. (0.025 cu. m/s per sq. m) of penetration opening at and no more than 50-cfm (0.024-cu. m/s) cumulative total for any 100 sq. ft. (9.3 sq. m) at both ambient and elevated temperatures.
- E. Exposed Penetration Firestopping Systems: Flame-spread and smoke-developed indexes of less than 25 and 450, respectively, per ASTM E 84.
- F. Putty Pad Sealant: Intumescent putty sheet providing fire resistance at electrical boxes and other penetrations.

- 1. Approved Products:
  - a. CP-617 Firestop Putty Pad by Hilti; www.hilti.com.
  - b. Nelson FSP Firestop Moldable Putty Pads by Nelson Firestop Products; www.nelsonfirestop.com.
  - c. TREMstop MP by Tremco; www.tremco.com.
- G. Accessories: Provide components for each penetration firestopping system that are needed to install fill materials and to maintain ratings required. Use only those components specified by penetration firestopping system manufacturer and approved by qualified testing and inspecting agency for conditions indicated.
  - 1. Permanent forming/damming/backing materials.
  - 2. Substrate primers.
  - 3. Collars.
  - 4. Steel sleeves.

## 2.3 FILL MATERIALS

- A. Cast-in-Place Firestop Devices: Factory-assembled devices for use in cast-in-place concrete floors and consisting of an outer sleeve lined with an intumescent strip, a flange attached to one end of the sleeve for fastening to concrete formwork, and a neoprene gasket.
- B. Latex Sealants: Single-component latex formulations that do not re-emulsify after cure during exposure to moisture.
- C. Firestop Devices: Factory-assembled collars formed from galvanized steel and lined with intumescent material sized to fit specific diameter of penetrant.
- D. Intumescent Composite Sheets: Rigid panels consisting of aluminum-foil-faced intumescent elastomeric sheet bonded to galvanized-steel sheet.
- E. Intumescent Putties: Nonhardening, water-resistant, intumescent putties containing no solvents or inorganic fibers.
- F. Intumescent Wrap Strips: Single-component intumescent elastomeric sheets with aluminum foil on one side.
- G. Mortars: Prepackaged dry mixes consisting of a blend of inorganic binders, hydraulic cement, fillers and lightweight aggregate formulated for mixing with water at Project site to form a nonshrinking, homogeneous mortar.
- H. Pillows/Bags: Reusable heat-expanding pillows/bags consisting of glass-fiber cloth cases filled with a combination of mineral-fiber, water-insoluble expansion agents, and fire-retardant additives. Where exposed, cover openings with steel-reinforcing wire mesh to protect pillows/bags from being easily removed.
- I. Silicone Foams: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.

PENETRATION FIRESTOPPING

078413 - 4

J. Silicone Sealants: Single-component, silicone-based, neutral-curing elastomeric sealants.

## 2.4 MIXING

A. Penetration Firestopping Materials: For those products requiring mixing before application, comply with penetration firestopping system manufacturer's written instructions for accurate proportioning of materials, water (if required), type of mixing equipment, selection of mixer speeds, mixing containers, mixing time, and other items or procedures needed to produce products of uniform quality with optimum performance characteristics for application indicated.

# PART 3 - EXECUTION

## 3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 PREPARATION

- A. Surface Cleaning: Before installing penetration firestopping systems, clean out openings immediately to comply with manufacturer's written instructions and with the following requirements:
  - 1. Remove from surfaces of opening substrates and from penetrating items foreign materials that could interfere with adhesion of penetration firestopping materials.
  - 2. Clean opening substrates and penetrating items to produce clean, sound surfaces capable of developing optimum bond with penetration firestopping materials. Remove loose particles remaining from cleaning operation.
  - 3. Remove laitance and form-release agents from concrete.
- B. Prime substrates where recommended in writing by manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

#### 3.3 INSTALLATION

- A. General: Install penetration firestopping systems to comply with manufacturer's written installation instructions and published drawings for products and applications.
- B. Install forming materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings.

- 1. After installing fill materials and allowing them to fully cure, remove combustible forming materials and other accessories not forming permanent components of firestopping.
- C. Install fill materials by proven techniques to produce the following results:
  - 1. Fill voids and cavities formed by openings, forming materials, accessories and penetrating items to achieve required fire-resistance ratings.
  - 2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.
  - 3. For fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

# 3.4 IDENTIFICATION

- A. Wall Identification: Permanently label walls containing penetration firestopping systems with the words "FIRE AND/OR SMOKE BARRIER PROTECT ALL OPENINGS," using lettering not less than 3 inches (76 mm) high and with minimum 0.375-inch (9.5-mm) strokes.
  - 1. Locate in accessible concealed floor, floor-ceiling, or attic space at 15 feet (4.57 m) from end of wall and at intervals not exceeding 30 feet (9.14 m).
- B. Penetration Identification: Identify each penetration firestopping system with legible metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches (150 mm) of penetration firestopping system edge so labels are visible to anyone seeking to remove penetrating items or firestopping systems. Use mechanical fasteners or self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:
  - 1. The words "Warning Penetration Firestopping Do Not Disturb. Notify Building Management of Any Damage."
  - 2. Contractor's name, address, and phone number.
  - 3. Designation of applicable testing and inspecting agency.
  - 4. Date of installation.
  - 5. Manufacturer's name.
  - 6. Installer's name.

# 3.5 CLEANING AND PROTECTION

- A. Clean off excess fill materials adjacent to openings as the Work progresses by methods and with cleaning materials that are approved in writing by penetration firestopping system manufacturers and that do not damage materials in which openings occur.
- B. Provide final protection and maintain conditions during and after installation that ensure that penetration firestopping systems are without damage or deterioration at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, immediately cut out and remove damaged or deteriorated penetration firestopping material and install new materials to produce systems complying with specified requirements.

## 3.6 PENETRATION FIRESTOPPING SYSTEM SCHEDULE

- A. Where UL-classified systems are indicated, they refer to system numbers in UL's "Fire Resistance Directory" under product Category XHEZ.
- B. Where Intertek Group-listed systems are indicated, they refer to design numbers in Intertek Group's "Directory of Listed Building Products" under "Firestop Systems."
- C. Where FM Global-approved systems are indicated, they refer to design numbers listed in FM Global's "Building Materials Approval Guide" under "Wall and Floor Penetration Fire Stops."
- D. Firestop Systems with No Penetrating Items : Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-, C-BJ, F-A- or W-L- 0001-0999.
- E. Firestop Systems for Metallic Pipes, Conduit, or Tubing Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-, F-A-, F-C-, W-J-, or W-L- 1001-1999.
- F. Firestop Systems for Nonmetallic Pipe, Conduit, or Tubing : Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-, F-A-, F-C- or W-L- 2001-2999.
- G. Firestop Systems for Electrical Cables : Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-, C-BJ-, F-A-, F-C-, or W-L- 3001-3999.
- H. Firestop Systems for Cable Trays: Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-, C-BJ-, or W-L- 4001-4999.
- I. Firestop Systems for Insulated Pipes: Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-, C-BJ-, F-A-, F-C- 5001-5999.
- J. Firestop Systems for Miscellaneous Electrical Penetrants: Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-, or F-A-6001-6999.
- K. Firestop Systems for Miscellaneous Mechanical Penetrations: Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-7001-7999.
- L. Firestop Systems for Groupings of Penetrations: Comply with the following:
  - 1. Available UL-Classified Systems: C-AJ-, C-BJ-, F-A-, or W-L-8001-8999.

#### END OF SECTION 078413

# SECTION 079513.13 - INTERIOR EXPANSION JOINT COVER ASSEMBLIES

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

A. Section includes interior ceiling expansion joint cover assemblies.

## 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for expansion joint cover assemblies.
- B. Shop Drawings: For each expansion joint cover assembly.
  - 1. Include plans, elevations, sections, details, splices, block-out requirement, attachments to other work, and line diagrams showing entire route of each expansion joint.
  - 2. Where expansion joint cover assemblies change planes, provide isometric or clearly detailed drawing depicting how components interconnect.
- C. Samples for Initial Selection: For each type of exposed finish.
  - 1. Include manufacturer's color charts showing the full range of colors and finishes available for each exposed metal and elastomeric-seal material.
- D. Samples for Verification: For each type of expansion joint cover assembly, full width by 6 inches (150 mm) long in size.

# PART 2 - PRODUCTS

#### 2.1 ASSEMBLY DESCRIPTION

- A. Furnish units in longest practicable lengths to minimize field splicing.
- B. Include factory-fabricated closure materials and transition pieces, T-joints, corners, curbs, crossconnections, and other accessories as required to provide continuous expansion joint cover assemblies.

#### INTERIOR EXPANSION JOINT COVER ASSEMBLIES

## 2.2 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Expansion joint cover assemblies shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- B. Expansion Joint Design Criteria:
  - 1. Type of Movement: Seismic.
    - a. Joint Movement: As indicated on Drawings.

## 2.3 CEILING EXPANSION JOINT COVERS

- A. Elastomeric-Seal Ceiling Joint Cover: Assembly consisting of elastomeric seal anchored to frames fixed to sides of joint gap.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Balco; a CSW Industrials Company.
    - b. BASF Corp. Watson Bowman Acme Corp.
    - c. Construction Specialties, Inc.
    - d. Nystrom.
  - 2. Application: Ceiling to ceiling.
  - 3. Seal: Preformed elastomeric membranes or extrusions.
    - a. Color: White

#### 2.4 MATERIALS

- A. Aluminum: ASTM B221 (ASTM B221M), Alloy 6063-T5 for extrusions; ASTM B209 (ASTM B209M), Alloy 6061-T6 for sheet and plate.
  - 1. Apply manufacturer's standard protective coating on aluminum surfaces to be placed in contact with cementitious materials.
- B. Elastomeric Seals: Manufacturer's standard preformed elastomeric membranes or extrusions to be installed in metal frames.

# PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine surfaces where expansion joint cover assemblies will be installed for installation tolerances and other conditions affecting performance of the Work.
- B. Notify Architect where discrepancies occur that will affect proper expansion joint cover assembly installation and performance.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 PREPARATION

- A. Prepare substrates according to expansion joint cover assembly manufacturer's written instructions.
- B. Coordinate and furnish anchorages, setting drawings, and instructions for installing expansion joint cover assemblies. Provide fasteners of metal, type, and size to suit type of construction indicated and to provide for secure attachment of expansion joint cover assemblies.

## 3.3 INSTALLATION

- A. Comply with manufacturer's written instructions for storing, handling, and installing expansion joint cover assemblies and materials unless more stringent requirements are indicated.
- B. Metal Frames: Perform cutting, drilling, and fitting required to install expansion joint cover assemblies.
  - 1. Repair or grout block out as required for continuous frame support using nonmetallic, shrinkage-resistant grout.
  - 2. Install frames in continuous contact with adjacent surfaces.
    - a. Shimming is not permitted.
  - 3. Install in true alignment and proper relationship to joints and adjoining finished surfaces measured from established lines and levels.
  - 4. Adjust for differences between actual structural gap and nominal design gap due to ambient temperature at time of installation.
  - 5. Cut and fit ends to accommodate thermal expansion and contraction of metal without buckling of frames.
  - 6. Locate anchors at interval recommended by manufacturer, but not less than 3 inches (75 mm) from each end and not more than 24 inches (600 mm) o.c.
- C. Seals: Install elastomeric seals and membranes in frames to comply with manufacturer's written instructions. Install with minimum number of end joints.

# INTERIOR EXPANSION JOINT COVER ASSEMBLIES

- 1. Provide in continuous lengths for straight sections.
- 2. Seal transitions. Vulcanize or heat-weld field-spliced joints as recommended by manufacturer.
- 3. Installation: Mechanically lock seals into frames or adhere to frames with adhesive or pressure-sensitive tape as recommended by manufacturer.
- D. Install with hairline mitered corners where expansion joint cover assemblies change direction or abut other materials.
- E. Terminate exposed ends of expansion joint cover assemblies with field- or factory-fabricated termination devices.

#### 3.4 **PROTECTION**

- A. Do not remove protective covering until finish work in adjacent areas is complete. When protective covering is removed, clean exposed metal surfaces to comply with manufacturer's written instructions.
- B. Protect the installation from damage by work of other Sections. Where necessary due to heavy construction traffic, remove and properly store cover plates or seals and install temporary protection over expansion joint cover assemblies. Reinstall cover plates or seals prior to Substantial Completion.

END OF SECTION 079513.13

# SECTION 092216 - NON-STRUCTURAL METAL FRAMING

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Requirements:
  - 1. Section 092900 "Gypsum Board" for board materials applied to metal framing.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Non-load-bearing steel framing systems for interior partitions.
  - 2. Suspension systems for interior ceilings and soffits.
  - 3. Metal blocking for supporting wall-mounted items.

# 1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

# PART 2 - PRODUCTS

## 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For fire-resistance-rated assemblies that incorporate nonload-bearing steel framing, provide materials and construction identical to those tested in assembly indicated, according to ASTM E 119 by an independent testing agency.
- B. Horizontal Deflection: For wall assemblies, limited to 1/240 of the wall height based on horizontal loading of 10 lbf/sq. ft. (480 Pa)

#### 2.2 FRAMING SYSTEMS

- A. Framing Members, General: Comply with ASTM C 754 for conditions indicated.
  - 1. Steel Sheet Components: Comply with ASTM C 645 requirements for metal unless otherwise indicated.

#### NON-STRUCTURAL METAL FRAMING

092216 - 1

- 2. Protective Coating hot-dip galvanized unless otherwise indicated.
- B. Studs and Tracks: ASTM C 645.
  - 1. Steel Studs and Tracks, minimum 22 gauge (0.027 inch).
- C. Minimum Base-Metal Thickness: As required by performance requirements for horizontal deflection Slip-Type Head Joints: Where indicated, provide one of the following:
  - 1. Clip System: Clips designed for use in head-of-wall deflection conditions that provide a positive attachment of studs to tracks while allowing 1-1/2-inch (38-mm) vertical movement.
  - 2. Double-Track System: ASTM C 645 top outer tracks, inside track with 2-inch- (51-mm-) deep flanges in thickness not less than indicated for studs and fastened to studs, and outer track sized to friction-fit over inner track.
  - 3. Deflection Track: Steel sheet top track manufactured to prevent cracking of finishes applied to interior partition framing resulting from deflection of structure above; in thickness not less than indicated for studs and in width to accommodate depth of studs.
    - a. Basis-of-Design Products:
      - 1) Non-Fire-Rated deflection head: Vertitrack; Steel Network.
      - 2) Fire-rated deflection head: BlazeFrame DSL2; Clark Dietrich.
- D. Cold-Rolled Channel Bridging: Steel, 0.0538-inch (1.367-mm) minimum base-metal thickness, with minimum 1/2-inch- (13-mm-) wide flanges.
  - 1. Depth: 1-1/2 inches (38 mm).
  - 2. Clip Angle: Not less than 1-1/2 by 1-1/2 inches (38 by 38 mm), 0.068-inch- (1.72-mm-) thick, galvanized steel.
- E. Hat-Shaped, Rigid Furring Channels: ASTM C 645.
  - 1. Minimum Base-Metal Thickness: 0.0179 inch (0.455 mm).
  - 2. Depth: 7/8 inch (22.2 mm).
- F. Resilient Furring Channels: 1/2-inch- (13-mm-) deep, steel sheet members designed to reduce sound transmission.
  - 1. Configuration: Asymmetrical or hat shaped.

# 2.3 SUSPENSION SYSTEMS

A. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- (1.59-mm-) diameter wire, or double strand of 0.048-inch- (1.21-mm-) diameter wire.

- B. Hanger Attachments to Concrete:
  - 1. Post-Installed Anchors: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC01 as appropriate for the substrate.
    - a. Uses: Securing hangers to structure.
    - b. Type: Torque-controlled, expansion anchor or adhesive anchor.
    - c. Material for Interior Locations: Carbon-steel components zinc-plated to comply with ASTM B 633 or ASTM F 1941 (ASTM F 1941M), Class Fe/Zn 5, unless otherwise indicated.
- C. Wire Hangers: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.16 inch (4.12 mm) in diameter.
- D. Carrying Channels (Main Runners): Cold-rolled, commercial-steel sheet with a base-metal thickness of 0.0538 inch (1.367 mm) and minimum 1/2-inch- (13-mm-) wide flanges.
  - 1. Depth: 2-1/2 inches (64 mm).
- E. Furring Channels (Furring Members):
  - 1. Cold-Rolled Channels: 0.0538-inch (1.367-mm) uncoated-steel thickness, with minimum 1/2-inch- (13-mm-) wide flanges, 3/4 inch (19 mm) deep.
  - 2. Steel Studs and Tracks: ASTM C 645.
    - a. Minimum Base-Metal Thickness: 0.0179 inch (0.455 mm).
    - b. Depth: 1-5/8 inches (41 mm) See "Embossed Steel Studs and Tracks" Article in the Evaluations for information about embossed steel studs and tracks.
- F. Grid Suspension System for Gypsum Board Ceilings: ASTM C 645, direct-hung system composed of main beams and cross-furring members that interlock.
  - 1. Basis-of-Design Product: Drywall Grid System; Armstrong Ceiling & Wall Solutions.
- G. Putty Pad Sealant: At acoustic rated partitions and fire-rated partitions in order to provide noise transmission resistance and fire resistance at electrical boxes and other penetrations. Refer to Section 078413 "Penetration Firestopping".

# 2.4 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards.
  - 1. Fasteners for Steel Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.

# PART 3 - EXECUTION

## 3.1 EXAMINATION

- A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 PREPARATION

- A. Suspended Assemblies: Coordinate installation of suspension systems with installation of overhead structure to ensure that inserts and other provisions for anchorages to building structure have been installed to receive hangers at spacing required to support the Work and that hangers will develop their full strength.
  - 1. Furnish concrete inserts and other devices indicated to other trades for installation in advance of time needed for coordination and construction.

## 3.3 INSTALLATION, GENERAL

- A. Installation Standard: ASTM C 754.
  - 1. Gypsum Plaster Assemblies: Also comply with requirements in ASTM C 841 that apply to framing installation.
  - 2. Portland Cement Plaster Assemblies: Also comply with requirements in ASTM C 1063 that apply to framing installation.
  - 3. Gypsum Veneer Plaster Assemblies: Also comply with requirements in ASTM C 844 that apply to framing installation.
  - 4. Gypsum Board Assemblies: Also comply with requirements in ASTM C 840 that apply to framing installation.
- B. Install framing and accessories plumb, square, and true to line, with connections securely fastened.
- C. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.
- D. Install bracing at terminations in assemblies.
- E. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.
- F. Putty Pad Sealant: Acoustically seal with putty pads, electrical boxes in walls and ceilings in which resilient sound isolation clips are used.

## NON-STRUCTURAL METAL FRAMING

## 3.4 INSTALLING FRAMED ASSEMBLIES

- A. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
  - 1. Single-Layer Application: As required by horizontal deflection performance requirements unless otherwise indicated.
  - 2. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.
- B. Install studs so flanges within framing system point in same direction.
- C. Install tracks at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts that penetrate partitions above ceiling.
  - 1. Install two studs at each jamb unless otherwise indicated.
  - 2. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch (13-mm) clearance from jamb stud to allow for installation of control joint in finished assembly.
  - 3. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.
  - 4. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
  - 5. Fire-Resistance-Rated Partitions: Install framing to comply with fire-resistance-rated assembly indicated and support closures and to make partitions continuous from floor to underside of solid structure.
    - a. Firestop Track: Where indicated, install to maintain continuity of fire-resistance-rated assembly indicated.
  - 6. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.
- D. Direct Furring:
  - 1. Screw to wood framing.
  - 2. Attach to concrete or masonry with stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches (610 mm) on center.
- E. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch (3 mm) from the plane formed by faces of adjacent framing.

## 3.5 INSTALLING CEILING SUSPENSION SYSTEMS

- A. Install suspension system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
  - 1. Hangers: 48 inches (1219 mm) on center.
  - 2. Carrying Channels (Main Runners): 48 inches (1219 mm) on center.

#### NON-STRUCTURAL METAL FRAMING

092216 - 5

- 3. Furring Channels (Furring Members): 16 inches (406 mm).
- B. Isolate suspension systems from building structure where they abut or are penetrated by building structure to prevent transfer of loading imposed by structural movement.
- C. Suspend hangers from building structure as follows:
  - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or suspension system.
    - a. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, counter splaying, or other equally effective means.
  - 2. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with locations of hangers required to support standard suspension system members, install supplemental suspension members and hangers in the form of trapezes or equivalent devices.
  - 3. Wire Hangers: Secure by looping and wire tying, either directly to structures or to inserts, eye screws, or other devices and fasteners that are secure and appropriate for substrate, and in a manner that will not cause hangers to deteriorate or otherwise fail.
  - 4. Flat Hangers: Secure to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices and fasteners that are secure and appropriate for structure and hanger, and in a manner that will not cause hangers to deteriorate or otherwise fail.
  - 5. Do not attach hangers to steel roof deck.
  - 6. Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
  - 7. Do not attach hangers to rolled-in hanger tabs of composite steel floor deck.
  - 8. Do not connect or suspend steel framing from ducts, pipes, or conduit.
- D. Fire-Resistance-Rated Assemblies: Wire tie furring channels to supports.
- E. Seismic Bracing: Sway-brace suspension systems with hangers used for support Grid suspension systems are suitable for use with gypsum board. They might be acceptable for gypsum veneer plaster; consult gypsum veneer plaster and grid suspension system manufacturers.
- F. Grid Suspension Systems: Attach perimeter wall track or angle where grid suspension systems meet vertical surfaces. Mechanically join main beam and cross-furring members to each other and butt-cut to fit into wall track.
- G. Installation Tolerances: Install suspension systems that are level to within 1/8 inch in 12 feet (3 mm in 3.6 m) measured lengthwise on each member that will receive finishes and transversely between parallel members that will receive finishes.

END OF SECTION 092216

NON-STRUCTURAL METAL FRAMING

## SECTION 092900 - GYPSUM BOARD

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Interior gypsum board.
  - 2. Mold-resistant gypsum board.
- B. Related Requirements:
  - 1. Section 092216 "Non-Structural Metal Framing" for non-structural steel framing and suspension systems that support gypsum board panels.

## 1.3 DELIVERY, STORAGE AND HANDLING

A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

## 1.4 FIELD CONDITIONS

- A. Environmental Limitations: Comply with ASTM C 840 requirements or gypsum board manufacturer's written instructions, whichever are more stringent.
- B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.
- C. Do not install panels that are wet, moisture damaged, and mold damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
  - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

# PART 2 - PRODUCTS

## 2.1 PERFORMANCE REQUIREMENTS

A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.

## 2.2 GYPSUM BOARD, GENERAL

A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

#### 2.3 INTERIOR GYPSUM BOARD

- A. Gypsum Wallboard: ASTM C 1396/C 1396M.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. American Gypsum.
  - 2. CertainTeed Corp.
  - 3. Georgia-Pacific Gypsum LLC.
  - 4. Lafarge North America Inc.
  - 5. National Gypsum Company.
  - 6. PABCO Gypsum.
  - 7. Temple-Inland.
  - 8. USG Corporation.
- C. Gypsum Board, Type X: ASTM C 1396/C 1396M.
  - 1. Thickness: 5/8 inch (15.9 mm).
  - 2. Long Edges: Tapered
- D. Mold-Resistant Gypsum Board: ASTM C1396/C1396M. With moisture- and mold-resistant core and paper surfaces.
  - 1. Core: 5/8 inch (15.9 mm); Type X, where required for fire-resistance.
  - 2. Long Edges: Tapered.
  - 3. Mold Resistance: ASTM D3273, score of 10 as rated according to ASTM D3274.

# 2.4 TRIM ACCESSORIES

- A. Interior Trim: ASTM C 1047.
  - 1. Material: Galvanized or aluminum-coated steel sheet or rolled zinc

#### **GYPSUM BOARD**

092900 - 2

- 2. Shapes:
  - a. Cornerbead.
  - b. L-Bead: L-shaped; exposed long flange receives joint compound.
  - c. Expansion (control) joint.

# 2.5 JOINT TREATMENT MATERIALS

- A. General: Comply with ASTM C 475/C 475M.
- B. Joint Tape:
  - 1. Interior Gypsum Board: Paper.
  - 2. Glass-Mat Gypsum Sheathing Board: 10-by-10 glass mesh.
  - 3. Tile Backing Panels: As recommended by panel manufacturer.
- C. Joint Compound for Interior Gypsum Board: For each coat, use formulation that is compatible with other compounds applied on previous or for successive coats.
  - 1. Prefilling: At open joints, rounded or beveled panel edges, and damaged surface areas, use setting-type taping compound.
  - 2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use drying-type, all-purpose compound.
    - a. Use setting-type compound for installing paper-faced metal trim accessories.
  - 3. Fill Coat: For second coat, use drying-type, all-purpose compound.
  - 4. Finish Coat: For third coat, use drying-type, all-purpose compound.
  - 5. Skim Coat: For final coat of Level 5 finish, use drying-type, all-purpose compound.
- D. Joint Compound for Tile Backing Panels:
  - 1. Glass-Mat, Water-Resistant Backing Panel: As recommended by backing panel manufacturer.
  - 2. Cementitious Backer Units: As recommended by backer unit manufacturer.
  - 3. Water-Resistant Gypsum Backing Board: Use setting-type taping compound and setting-type, sandable topping compound.

# 2.6 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards and manufacturer's written instructions.
- B. Steel Drill Screws: ASTM C 1002 unless otherwise indicated.
  - 1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch (0.84 to 2.84 mm) thick.

- 2. For fastening cementitious backer units, use screws of type and size recommended by panel manufacturer.
- C. Sound-Attenuation Blankets: ASTM C 665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.
  - 1. Fire-Resistance-Rated Assemblies: Comply with mineral-fiber requirements of assembly.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine areas and substrates including welded hollow-metal frames and support framing, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.
- B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 APPLYING AND FINISHING PANELS, GENERAL

- A. Comply with ASTM C 840.
- B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.
- C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch (1.5 mm) of open space between panels. Do not force into place.
- D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Do not make joints other than control joints at corners of framed openings.
- E. Form control and expansion joints with space between edges of adjoining gypsum panels.
- F. Cover both faces of support framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases braced internally.
  - 1. Unless concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than 8 sq. ft. (0.7 sq. m) in area.
  - 2. Fit gypsum panels around ducts, pipes, and conduits.

- 3. Where partitions intersect structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by structural members; allow 1/4-to 3/8-inch- (6.4- to 9.5-mm-) wide joints to install sealant.
- G. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments. Provide 1/4- to 1/2-inch- (6.4- to 12.7-mm-) wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.
- H. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.
- I. Wood Framing: Install gypsum panels over wood framing, with floating internal corner construction. Do not attach gypsum panels across the flat grain of wide-dimension lumber, including floor joists and headers. Float gypsum panels over these members or provide control joints to counteract wood shrinkage.
- J. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical sealant. Install acoustical sealant at both faces of partitions at perimeters and through penetrations. Comply with ASTM C 919 and with manufacturer's written instructions for locating edge trim and closing off sound-flanking paths around or through assemblies, including sealing partitions above acoustical ceilings.
- K. Install sound attenuation blankets before installing gypsum panels unless blankets are readily installed after panels have been installed on one side.

# 3.3 APPLYING INTERIOR GYPSUM BOARD

- A. Install interior gypsum board in the following locations:
  - 1. Wallboard Type: As indicated on Drawings
  - 2. Type X: As indicated on Drawings
  - 3. Ceiling Type: Ceiling surfaces
  - 4. Mold-Resistant Type: Minimum 3 feet (914 mm) in all directions centered on plumbing fixtures. Required both sides of walls containing fixtures.
  - 5. Glass-Mat Interior Type: As indicated on Drawings.
- B. Single-Layer Application:
  - 1. On ceilings, apply gypsum panels before wall/partition board application to greatest extent possible and at right angles to framing unless otherwise indicated.
  - 2. On partitions/walls, apply gypsum panels horizontally (perpendicular to framing) unless otherwise indicated or required by fire-resistance-rated assembly, and minimize end joints.
    - a. Stagger abutting end joints not less than one framing member in alternate courses of panels.
    - b. At stairwells and other high walls, install panels horizontally unless otherwise indicated or required by fire-resistance-rated assembly.

- 3. On Z-shaped furring members, apply gypsum panels vertically (parallel to framing) with no end joints. Locate edge joints over furring members.
- 4. Fastening Methods: Apply gypsum panels to supports with steel drill screws.
- C. Multilayer Application:
  - 1. On ceilings, apply gypsum board indicated for base layers before applying base layers on walls/partitions; apply face layers in same sequence. Apply base layers at right angles to framing members and offset face-layer joints one framing member, 16 inches (400 mm) minimum, from parallel base-layer joints, unless otherwise indicated or required by fire-resistance-rated assembly.
  - 2. On partitions/walls, apply gypsum board indicated for base layers and face layers vertically (parallel to framing) with joints of base layers located over stud or furring member and face-layer joints offset at least one stud or furring member with base-layer joints unless otherwise indicated or required by fire-resistance-rated assembly. Stagger joints on opposite sides of partitions.
  - 3. On Z-shaped furring members, apply base layer vertically (parallel to framing) and face layer either vertically (parallel to framing) or horizontally (perpendicular to framing) with vertical joints offset at least one furring member. Locate edge joints of base layer over furring members.
  - 4. Fastening Methods: Fasten base layers with screws; fasten face layers with adhesive and supplementary fasteners

## 3.4 INSTALLING TRIM ACCESSORIES

- A. General: For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.
- B. Control Joints: Install control joints according to ASTM C 840 and in specific locations approved by Architect for visual effect.
- C. Interior Trim: Install in the following locations:
  - 1. Cornerbead: Use at outside corners
  - 2. L-Bead: Use where indicated or recommended by manufacturer.
  - 3. J-trim: Use at exposed edges of boards and where boards abut caulked joints with dissimilar materials.

#### 3.5 FINISHING GYPSUM BOARD

- A. General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.
- B. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.

- C. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:
  - 1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
  - 2. Level 2: Panels that are substrate for tile
    - a. Primer and its application to surfaces are specified in Section 099123 "Interior Painting."
  - 3. Level 3: Mechanical, electrical rooms, custodial closets, and storage rooms
  - 4. Level 4: Classrooms
  - 5. Level 5: Corridors, gymnasiums, cafeteria/Commons, offices, high traffic/public areas.
- D. Glass-Mat Gypsum Sheathing Board: Finish according to manufacturer's written instructions for use as exposed soffit board.
- E. Cementitious Backer Units: Finish according to manufacturer's written instructions.
- F. Clean gypsum board of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

## 3.6 **PROTECTION**

- A. Protect adjacent surfaces from drywall compound and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.
- B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.
- C. Provide Vapor retarder (minimum: 4–6 mil) behind gypsum board on all wet (plumbing) walls, behind slop sinks, in dishwash rooms, and exterior walls of walk-in coolers
- D. Remove and replace panels that are wet, moisture damaged, and mold damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
  - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

#### END OF SECTION 092900
# SECTION 095113 - ACOUSTICAL PANEL CEILINGS

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Acoustical ceiling panels.
  - 2. Exposed suspension systems for interior ceilings.
- B. Products furnished, but not installed under this Section, include anchors, clips, and other ceiling attachment devices to be cast in concrete.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color and texture specified, provide 6-inch (150-mm) sample size.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For testing agency.
- B. Product Test Reports: For each acoustical panel ceiling, for tests performed by a qualified testing agency.
- C. Evaluation Reports: For each acoustical panel ceiling suspension system and anchor and fastener type, from ICC-ES.

#### 1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For finishes to include in maintenance manuals.

# 1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Acoustical Ceiling Units: Full-size panels equal to 2 percent of quantity installed.
  - 2. Suspension-System Components: Quantity of each exposed component equal to 2 percent of quantity installed.

### 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver acoustical panels, suspension-system components, and accessories to Project site and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.
- B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.

#### 1.8 FIELD CONDITIONS

A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

# PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Source Limitations: Obtain each type of acoustical ceiling panel and its supporting suspension system from single source from single manufacturer.
- B. Basis-of-Design Product: Provide Armstrong World Industries, Inc. No substitutions.

### 2.2 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Acoustical ceiling shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- B. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Flame-Spread Index: Class A according to ASTM E 1264.
  - 2. Smoke-Developed Index: 50 or less.

#### ACOUSTICAL PANEL CEILINGS

095113 - 2

# 2.3 ACOUSTICAL PANELS (ACT-1)

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Clean Room VL 870 as manufactured by Armstrong World Industries, Inc., no substitutions.
- B. Acoustical Panel Standard: Provide manufacturer's standard panels according to ASTM E 1264 and designated by type, form, pattern, acoustical rating, and light reflectance unless otherwise indicated.
- C. Classification: Provide panels as follows:
  - 1. Type and Form: Type IV, mineral base with membrane-faced overlay; Form 2, water felted; with factory-applied latex paint on DuraBrite acoustically transparent membranes.
  - 2. Pattern: E (lightly textured).
- D. Color: White.
- E. Light Reflectance (LR): Not less than 0.80.
- F. Ceiling Attenuation Class (CAC): Not less than 40.
- G. Noise Reduction Coefficient (NRC): N/A.
- H. Edge/Joint Detail: Square Lay-in.
- I. Thickness: 5/8 inch.
- J. Modular Size: 24 by 48 inches
- K. Antimicrobial Treatment: Manufacturer's standard broad spectrum, antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D 3273, ASTM D 3274, or ASTM G 21 and evaluated according to ASTM D 3274 or ASTM G 21.

# 2.4 METAL SUSPENSION SYSTEMS, GENERAL

- A. Metal Suspension-System Standard: Provide manufacturer's standard direct-hung metal suspension systems of types, structural classifications, and finishes indicated that comply with applicable requirements in ASTM C 635/C 635M.
  - 1. High-Humidity Finish: Comply with ASTM C 635/C 635M requirements for "Coating Classification for Severe Environment Performance" where high-humidity finishes are indicated.
- B. Attachment Devices: Size for five times the design load indicated in ASTM C 635/C 635M, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.

- C. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
  - 1. Zinc-Coated, Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
  - 2. Size: Select wire diameter so its stress at three times hanger design load (ASTM C 635/C 635M, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.135-inch- (3.5-mm-) diameter wire.
- D. Seismic Stabilizer Bars: Manufacturer's standard perimeter stabilizers designed to accommodate seismic forces.
- E. Seismic Struts: Manufacturer's standard compression struts designed to accommodate seismic forces.
- F. Seismic Clips: seismic clips designed and spaced to secure acoustical panels in place.
  - 1. Hemmed aluminum-capped angle molding with prefinished exposed flanges, 7/8-inch width. Basis of Design Seismic clip: BERC2 retaining clip.

#### 2.5 METAL SUSPENSION SYSTEM

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Prelude XL as manufactured by Armstrong World Industries, Inc., or a comparable product:
- B. Metal Suspension-System Standard: Provide manufacturer's standard, direct-hung, metal suspension system and accessories according to ASTM C 635/C 635M and designated by type, structural classification, and finish indicated.
  - 1. High-Humidity Finish: Where indicated, provide coating tested and classified for "severe environment performance" according to ASTM C 635/C 635M.
- C. Narrow-Face, Capped, Double-Web, Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet; prepainted, electrolytically zinc coated, or hot-dip galvanized, G30 (Z90) coating designation; with prefinished 15/16 inch wide metal caps on flanges.
  - 1. Structural Classification: Intermediate-duty system.
  - 2. End Condition of Cross Runners: Override (stepped) or butt-edge type.
  - 3. Face Design: Flat, flush.
  - 4. Cap Material: Cold-rolled steel.
  - 5. Cap Finish: As indicated in Color and Materials Schedule in drawings or if not indicated, as selected by Architect from full range of industry colors.

# 2.6 ACCESSORIES

A. Attachment Devices: Size for five times the design load indicated in ASTM C 635/C 635M, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.

#### ACOUSTICAL PANEL CEILINGS

- B. Wire Hangers, Braces, and Ties: Provide wires as follows:
  - 1. Zinc-Coated, Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
  - 2. Size: Wire diameter sufficient for its stress at three times hanger design load (ASTM C 635/C 635M, Table 1, "Direct Hung") will be less than yield stress of wire, but not less than 0.106-inch- (2.69-mm-) diameter wire.
- C. Hanger Rods: Mild steel, zinc coated or protected with rust-inhibitive paint.
- D. Flat Hangers: Mild steel, zinc coated or protected with rust-inhibitive paint.
- E. Angle Hangers: Angles with legs not less than 7/8 inch (22 mm) wide; formed with 0.04-inch-(1-mm-) thick, galvanized-steel sheet complying with ASTM A 653/A 653M, G90 (Z275) coating designation; with bolted connections and 5/16-inch- (8-mm-) diameter bolts.
- F. Seismic Stabilizer Bars: Manufacturer's standard perimeter stabilizers designed to accommodate seismic forces.
- G. Seismic Struts: Manufacturer's standard compression struts designed to accommodate seismic forces.
- H. Three way clips: GC3W Grip clip 3-Way for ACT-1 & ACT-5 grid only

# 2.7 METAL EDGE MOLDINGS AND TRIM

- A. Roll-Formed, Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that comply with seismic design requirements; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension-system runners.
  - 1. Edge moldings shall fit acoustical panel edge details and suspension systems indicated and match width and configuration of exposed runners unless otherwise indicated.
    - a. Moldings for seismic constraint; Basis of Design Product: BERC2 retaining clip, part of the Seismic RX system by Armstrong World Industries, Inc.
  - 2. Where indicated on drawings for lay-in panels with reveal edge details, provide stepped edge molding that forms reveal of same depth and width as that formed between edge of panel and flange at exposed suspension member.
    - a. Armstrong Shadow Molding
  - 3. For circular penetrations of ceiling, provide edge moldings fabricated to diameter required to fit penetration exactly.
- B. Extruded-Aluminum Edge Moldings and Trim: Where indicated, provide manufacturer's extruded-aluminum edge moldings and trim of profile indicated or referenced by manufacturer's

designations, including splice plates, corner pieces, and attachment and other clips, complying with seismic design requirements.

- 1. Baked-Enamel or Powder-Coat Finish: Minimum dry film thickness of 1.5 mils (0.04 mm). Comply with ASTM C 635/C 635M and coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.
- C. Seismic Restraint Wall Moldings: Hemmed aluminum-capped angle molding with prefinished exposed flanges, 7/8-inch width. Basis of Design Seismic clip: BERC2 retaining clip.

# PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.
- B. Examine acoustical panels before installation. Reject acoustical panels that are wet, moisture damaged, or mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders unless otherwise indicated, and comply with layout shown on reflected ceiling plans.
- B. Layout openings for penetrations centered on the penetrating items.

# 3.3 INSTALLATION

- A. Install acoustical panel ceilings according to ASTM C 636/C 636M and manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."
  - 1. Fire-Rated Assembly: Install fire-rated ceiling systems according to tested fire-rated design.
- B. Suspend ceiling hangers from building's structural members and as follows:
  - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.

- 2. Splay hangers only where required and, if permitted with fire-resistance-rated ceilings, to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
- 3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension-system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
- 4. Secure wire hangers to ceiling-suspension members and to supports above with a minimum of three tight turns. Connect hangers directly to structure or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
- 5. Secure flat, angle, channel, and rod hangers to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices that are secure and appropriate for both the structure to which hangers are attached and the type of hanger involved. Install hangers in a manner that will not cause them to deteriorate or fail due to age, corrosion, or elevated temperatures.
- 6. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, postinstalled mechanical or adhesive anchors, or power-actuated fasteners that extend through forms into concrete.
- 7. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
- 8. Do not attach hangers to steel deck tabs.
- 9. Do not attach hangers to steel roof deck. Attach hangers to structural members.
- 10. Space hangers not more than 48 inches (1200 mm) o.c. along each member supported directly from hangers unless otherwise indicated; provide hangers not more than 8 inches (200 mm) from ends of each member.
- 11. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards.
- C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or postinstalled anchors.
- D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
  - 1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
  - 2. Screw attach moldings to substrate at intervals not more than 16 inches (400 mm) o.c. and not more than 3 inches (75 mm) from ends. Miter corners accurately and connect securely.
  - 3. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- E. Install suspension-system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- F. Install acoustical panels with undamaged edges and fit accurately into suspension-system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide precise fit.

# ACOUSTICAL PANEL CEILINGS

- 1. Arrange directionally patterned acoustical panels as follows:
  - a. As indicated on reflected ceiling plans.
- 2. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension-system runners and moldings.
- 3. For reveal-edged panels on suspension-system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.
- 4. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.

### 3.4 ERECTION TOLERANCES

- A. Suspended Ceilings: Install main and cross runners level to a tolerance of 1/8 inch in 12 feet (3 mm in 3.6 m), non-cumulative.
- B. Moldings and Trim: Install moldings and trim to substrate and level with ceiling suspension system to a tolerance of 1/8 inch in 12 feet (3 mm in 3.6 m), non-cumulative.

### 3.5 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a qualified special inspector to perform the following special inspections:
  - 1. Compliance of seismic design.

# 3.6 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension-system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage.
- B. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 095113

# SECTION 096513 - RESILIENT BASE AND ACCESSORIES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Resilient base, for use if resilient sheet flooring alternate is not taken.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color and texture specified, not less than 4 inches (300 mm) long.
- C. Product Schedule: For resilient base and accessory products. Use same designations indicated on Drawings.

#### 1.4 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Furnish not less than 10 linear feet (3 linear m) for every 500 linear feet (150 linear m) or fraction thereof, of each type, color, pattern, and size of resilient product installed.

# 1.5 QUALITY ASSURANCE

- A. Fire Performance Characteristics: Provide products with the following fire performance characteristics as determined by testing products per ASTM test method indicated below by UL or another testing and inspecting agency acceptable to authorities having jurisdiction.
  - 1. Critical Radiant Flux: 0.45 watts per sq. cm or more per ASTM E 648.
  - 2. Smoke Density: Less than 450 per ASTM E 662.

# RESILIENT BASE AND ACCESSORIES

- B. Installer Qualifications: A qualified installer who employs workers for this Project who are competent in techniques required by manufacturer for resilient base.
- C. Provide 5-year unconditional warranty for installation.

### 1.6 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F (10 deg C) or more than 90 deg F (32 deg C).

# 1.7 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F (21 deg C) or more than 95 deg F (35 deg C), in spaces to receive resilient products during the following time periods:
  - 1. 48 hours before installation.
  - 2. During installation.
  - 3. 48 hours after installation.
- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F (13 deg C) or more than 95 deg F (35 deg C).
- C. Install resilient products after other finishing operations, including painting, have been completed.

# PART 2 - PRODUCTS

### 2.1 RESILIENT WALL BASE (RB-1)

- A. Products: Basis-of-Design products from Johnsonite | Tarkett, Inc. Traditional Rubber Cove Base or comparable product by one of the following:
  - 1. Roppe Corporation, USA.
  - 2. VPI Corporation.
- B. Product Standard: ASTM F 1861
  - 1. Group: I (solid, homogeneous).
  - 2. Meet or exceed ASTM E 84/NFPA 225 Class A flame spread index, less than 450 smoke density.
  - 3. Style:
    - a. Cove

# **RESILIENT BASE AND ACCESSORIES**

- C. Thickness: 1/8 inch (3mm).
- D. Height:
  - 1. 6 inches (102 mm).
- E. Lengths: Coils in manufacturer's standard length.
- F. Outside Corners: Preformed.
- G. Inside Corners: Job formed.
- H. Colors: As indicated in Color and Material Schedule in drawings or if not indicated, dark-colored as selected by Architect from full range of industry colors.

#### 2.2 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.

# PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
  - 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
  - 1. Installation of resilient products indicates acceptance of surfaces and conditions.

#### 3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Concrete Substrates for Resilient Stair Accessories: Prepare horizontal surfaces according to ASTM F 710.

#### **RESILIENT BASE AND ACCESSORIES**

096513 - 3

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
- 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.
- 3. Alkalinity and Adhesion Testing: Perform tests recommended by manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 10 pH.
- 4. Moisture Testing: Proceed with installation only after substrates pass testing according to manufacturer's written recommendations, but not less stringent than the following:
  - a. Perform anhydrous calcium chloride test according to ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. (1.36 kg of water/92.9 sq. m) in 24 hours.
  - b. Perform relative humidity test using in situ probes according to ASTM F 2170. Proceed with installation only after substrates have maximum 75 percent relative humidity level.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install resilient products until they are the same temperature as the space where they are to be installed.
  - 1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

# 3.3 RESILIENT BASE INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient base.
- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.
- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.
- G. Preformed Corners: Install preformed corners before installing straight pieces.

# RESILIENT BASE AND ACCESSORIES

### H. Job-Formed Corners:

- 1. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches (76 mm) in length.
  - a. Cope corners to minimize open joints.

# 3.4 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Perform the following operations immediately after completing resilient-product installation:
  - 1. Remove adhesive and other blemishes from exposed surfaces.
  - 2. Sweep and vacuum horizontal surfaces thoroughly.
  - 3. Damp-mop horizontal surfaces to remove marks and soil.
- C. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 096513

# SECTION 096516 - RESILIENT SHEET FLOORING

# PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes
  - 1. Kitchen slip-resistant flooring. (ALTERNATE #1)
- B. Related Requirements:
  - 1. Section 012300 "Alternates" for Alternate No. 1.
  - 2. Section 096513 "Resilient Base and Accessories" for resilient base, stair accessories, transition strips, and other accessories installed with resilient floor coverings.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For each type of flooring. Include flooring layouts, locations of seams, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.
  - 1. Show details of special patterns.
  - 2. Layout, colors, widths, and dimensions of game lines and markers.
  - 3. Locations of floor inserts for athletic equipment installed through flooring.
  - 4. Seam locations for sheet flooring.
- C. Samples: For each exposed product and for each color and texture specified in manufacturer's standard size, but not less than 6-by-9-inch (150-by-230-mm) sections.
- D. Welded-Seam Samples: For seamless-installation technique indicated and for each resilient sheet flooring product, color, and pattern required; with seam running lengthwise and in center of 6-by-9-inch (150-by-230-mm) Sample applied to a rigid backing and prepared by Installer for this Project.
- E. Product Schedule: For resilient sheet flooring. Use same designations indicated on Drawings.

### 1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

### 1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of resilient sheet flooring to include in maintenance manuals. Include methods for maintaining installed products, and precautions against cleaning materials and methods detrimental to finishes and performance.

#### 1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Resilient Sheet Flooring: Furnish not less than 10 linear feet (3 linear m) for every 500 linear feet (150 linear m) or fraction thereof, in roll form and in full roll width for each type, color, and pattern of flooring installed.

### 1.7 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs workers for this Project who are competent in techniques required by manufacturer for resilient sheet flooring installation and seaming method indicated.
  - 1. Engage an installer who employs workers for this Project who are trained or certified by resilient sheet flooring manufacturer for installation techniques required.
  - 2. Provide trained technical representative from manufacturer for additional training prior to installation.
  - 3. Provide 5-year unconditional warranty for installation.

### 1.8 DELIVERY, STORAGE, AND HANDLING

A. Store resilient sheet flooring and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F (10 deg C) or more than 90 deg F (32 deg C). Store rolls upright.

#### 1.9 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F (21 deg C) or more than 85 deg F (29 deg C), in spaces to receive resilient sheet flooring during the following time periods:
  - 1. 48 hours before installation.
  - 2. During installation.

#### RESILIENT SHEET FLOORING

- 3. 48 hours after installation.
- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F (13 deg C) or more than 95 deg F (35 deg C).
- C. Close spaces to traffic during resilient sheet flooring installation.
- D. Close spaces to traffic for 48 hours after resilient sheet flooring installation.
- E. Install resilient sheet flooring after other finishing operations, including painting, have been completed.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For resilient sheet flooring, as determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.
  - 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

# 2.2 HOMOGENOUS VINYL SHEET FLOORING (RF-4)

- A. Products: Provide Reliance 25, No. D2517, Vault by Altro, or comparable products from:
  - 1. Armstrong World Industries.
  - 2. Forbo Flooring Systems.
- B. Product Standard: ASTM F 1913.
  - 1. Type (Binder Content): Type II, minimum binder content of 34 percent.
  - 2. Wear-Layer Thickness: 0.098 inch (2.5 mm).
  - 3. Overall Thickness: 0.098-inch (2.5-mm).
  - 4. Interlayer Material: None.
- C. Wearing Surface: Smooth.
- D. Sheet Width: As standard with manufacturer.
- E. Seamless-Installation Method: Heat welded.
- F. Base: Integral self-cove base, 4 inches (102 mm) high.
- G. Colors and Patterns: As indicated in Color and Material Schedule in drawings or if not indicated, as selected by Architect from full range of industry colors.

# RESILIENT SHEET FLOORING

# 2.3 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by resilient sheet flooring manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by flooring and adhesive manufacturers to suit resilient sheet flooring and substrate conditions indicated.
- C. Seamless-Installation Accessories:
  - 1. Cold welding Compound: At all location except where indicated to be heat-welded Manufacturer's product for cold welding seams.
    - a. Colors: As indicated in Color and Materials Schedule in drawings or if not indicated, as selected by Architect from full range of industry colors.
- D. Integral-Flash-Cove-Base Accessories:
  - 1. Cove Strip: 1-inch (25-mm) radius provided or approved by resilient sheet flooring manufacturer.
  - 2. Cap Strip: Square metal, vinyl, or rubber cap provided or approved by resilient sheet flooring manufacturer.
  - 3. Corners: Metal inside and outside corners and end stops provided or approved by resilient sheet flooring manufacturer.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
  - 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient sheet flooring.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 PREPARATION

- A. Prepare substrates according to resilient sheet flooring manufacturer's written instructions to ensure adhesion of resilient sheet flooring.
- B. Concrete Substrates: Prepare according to ASTM F 710.
  - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.

#### RESILIENT SHEET FLOORING

096516 - 4

- 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by resilient sheet flooring manufacturer. Do not use solvents.
- 3. Alkalinity and Adhesion Testing: Perform tests recommended by resilient sheet flooring manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
- 4. Moisture Testing: Proceed with installation only after substrates pass testing according to resilient sheet flooring manufacturer's written recommendations, but not less stringent than the following:
  - a. Perform relative humidity test using in situ probes according to ASTM F 2170. Proceed with installation only after substrates have a maximum 85 percent relative humidity level.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install resilient sheet flooring until it is the same temperature as the space where it is to be installed.
  - 1. At least 48 hours in advance of installation, move flooring and installation materials into spaces where they will be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient sheet flooring.

# 3.3 RESILIENT SHEET FLOORING INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient sheet flooring.
- B. Unroll resilient sheet flooring and allow it to stabilize before cutting and fitting.
- C. Lay out resilient sheet flooring as follows:
  - 1. Maintain uniformity of flooring direction.
  - 2. Minimize number of seams; place seams in inconspicuous and low-traffic areas, at least 6 inches (152 mm) away from parallel joints in flooring substrates.
  - 3. Match edges of flooring for color shading at seams.
  - 4. Avoid cross seams.
- D. Scribe and cut resilient sheet flooring to butt neatly and tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, and door frames.
- E. Extend resilient sheet flooring into toe spaces, door reveals, closets, and similar openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on resilient sheet flooring as marked on substrates. Use chalk or other nonpermanent marking device.

# RESILIENT SHEET FLOORING

- G. Install resilient sheet flooring on covers for telephone and electrical ducts and similar items in installation areas. Maintain overall continuity of color and pattern between pieces of flooring installed on covers and adjoining flooring. Tightly adhere flooring edges to substrates that abut covers and to cover perimeters.
- H. Adhere resilient sheet flooring to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.
- I. Seamless Installation:
  - 1. Cold Welded Seams: Bond seams with chemical-bonding compound to permanently fuse sections into a seamless flooring. Prepare seams and apply compound to produce tightly fitted seams without gaps, overlays, or excess bonding compound on flooring surfaces.
  - 2. Install metal corners at inside and outside corners.

# 3.4 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient sheet flooring.
- B. Perform the following operations immediately after completing resilient sheet flooring installation:
  - 1. Remove adhesive and other blemishes from surfaces.
  - 2. Sweep and vacuum surfaces thoroughly.
  - 3. Damp-mop surfaces to remove marks and soil.
- C. Protect resilient sheet flooring from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Cover resilient sheet flooring until Substantial Completion.

END OF SECTION 096516

# SECTION 096519 - RESILIENT TILE FLOORING

# PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Vinyl composition tile (VCT), patch and match existing (BASE BID).
- B. Related Sections:
  - 1. Section 096513 "Resilient Base Accessories" for transition strips.
  - 2. Section 096516 "Resilient Sheet Flooring" for Alternate No. 1.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For each type of floor tile. Include floor tile layouts, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.
  - 1. Show details of special patterns.
- C. Samples for Verification: Full-size units of each color and pattern of floor tile required.
  - 1. For heat-welding bead, manufacturer's standard-size Samples, but not less than 9 inches (230 mm) long, of each color required.
- D. Product Schedule: Refer to Color & Material Schedule and Room Finish Schedule for locations.

#### 1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

#### 1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of floor tile to include in maintenance manuals.

#### RESILIENT TILE FLOORING

096519 - 1

# 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs workers for this Project who are competent in techniques required by manufacturer for floor tile installation and seaming method indicated.
  - 1. Engage an installer who employs workers for this Project who are trained or certified by floor tile manufacturer for installation techniques required.

### 1.7 DELIVERY, STORAGE, AND HANDLING

A. Store floor tile and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F (10 deg C) or more than 90 deg F (32 deg C). Store floor tiles on flat surfaces.

#### 1.8 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F (21 deg C) or more than 95 deg F (35 deg C), in spaces to receive floor tile during the following time periods:
  - 1. 48 hours before installation.
  - 2. During installation.
  - 3. 48 hours after installation.
- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F (13 deg C) or more than 95 deg F (35 deg C).
- C. Close spaces to traffic during floor tile installation.
- D. Close spaces to traffic for 48 hours after floor tile installation.
- E. Install floor tile after other finishing operations, including painting, have been completed.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For resilient tile flooring, as determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.
  - 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

#### **RESILIENT TILE FLOORING**

### 2.2 VINYL COMPOSITION TILE (VCT-1), BASE BID

- A. Basis-of-Design Product: Provide Standard Excelon VCT by Armstrong World Industries, or comparable product by one of the following:
  - 1. Tarkett VCT, by Tarkett (formerly Johnsonite).
- B. Tile Standard: ASTM F1066, Class 2, through pattern.
- C. Wearing Surface: Smooth.
- D. Thickness: 0.125 inch (3.2 mm).
- E. Size: 12 by 12 inches (305 by 305 mm).
- F. Colors and Patterns: Match existing as indicated on Color and Material Schedule on Drawings.

### 2.3 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by floor tile manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by floor tile and adhesive manufacturers to suit floor tile and substrate conditions indicated.
  - 1. Adhesives shall comply with the following limits for VOC content:
    - a. Rubber Floor Adhesives: 60 g/L or less.
    - b. Encore "E-Grip" one-component urethane adhesive.
      - 1) Sealant (Floor Polish): Apply 2-3 coats of finish as recommended by manufacturer.
  - 2. Adhesives shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

# PART 3 - EXECUTION

#### 3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

#### RESILIENT TILE FLOORING

- 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of floor tile.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Prepare substrates according to floor tile manufacturer's written instructions to ensure adhesion of resilient products.
- B. Concrete Substrates: Prepare according to ASTM F 710.
  - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
  - 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by floor tile manufacturer. Do not use solvents.
  - 3. Alkalinity and Adhesion Testing: Perform tests recommended by floor tile manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
  - 4. Moisture Testing: Proceed with installation only after substrates pass testing according to floor tile manufacturer's written recommendations, but not less stringent than the following:
    - a. Perform anhydrous calcium chloride test according to ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lbs of water/1000 sq. ft. (1.36 kg of water/92.9 sq. m) in 24 hours.
    - b. Perform relative humidity test using in situ probes according to ASTM F 2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level.
- C. Access Flooring Panels: Remove protective film of oil or other coating using method recommended by access flooring manufacturer.
- D. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- E. Do not install floor tiles until they are the same temperature as the space where they are to be installed.
  - 1. At least 48 hours in advance of installation, move resilient floor tile and installation materials into spaces where they will be installed.
- F. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient floor tile.

# 3.3 FLOOR TILE INSTALLATION

- A. Comply with manufacturer's written instructions for installing floor tile.
- B. Lay out floor tiles from center marks established with principal walls, discounting minor offsets, so tiles at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half tile at perimeter.
  - 1. Lay tiles square with corridor entry door of room.
- C. Match floor tiles for color and pattern by selecting tiles from cartons in the same sequence as manufactured and packaged, if so numbered. Discard broken, cracked, chipped, or deformed tiles.
  - 1. Lay tiles with grain direction alternating in adjacent tiles (basket-weave pattern).
- D. Scribe, cut, and fit floor tiles to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.
- E. Extend floor tiles into toe spaces, door reveals, closets, and similar openings. Extend floor tiles to center of door openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on floor tiles as marked on substrates. Use chalk or other nonpermanent marking device.
- G. Install floor tiles on covers for telephone and electrical ducts, building expansion-joint covers, and similar items in finished floor areas. Maintain overall continuity of color and pattern between pieces of tile installed on covers and adjoining tiles. Tightly adhere tile edges to substrates that abut covers and to cover perimeters.
- H. Adhere floor tiles to flooring substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.
- I. Seamless Installation:
  - 1. Heat-Welded Seams: Comply with ASTM F 1516. Rout joints and heat weld with welding bead to permanently fuse sections into a seamless flooring. Prepare, weld, and finish seams to produce surfaces flush with adjoining flooring surfaces.

### 3.4 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting floor tile.
- B. Perform the following operations immediately after completing floor tile installation:
  - 1. Remove adhesive and other blemishes from exposed surfaces.
  - 2. Sweep and vacuum surfaces thoroughly.
  - 3. Damp-mop surfaces to remove marks and soil.

# RESILIENT TILE FLOORING

- C. Protect floor tile from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Cover floor tile until Substantial Completion.

END OF SECTION 096519

# SECTION 099123 - INTERIOR PAINTING

### PART 1 - GENERAL

### 1.1 SUMMARY

- A. Section includes surface preparation and the application of paint systems on interior substrates. All labor, materials, tools and other equipment, services and supervision required to complete all interior painting and decorating work as indicated on Finish Schedules and to the full extent of the Drawings and Specifications. Interior paint systems will be utilized for interior substrates.
- B. Related Requirements:
  - 1. Color and Material Schedule on drawings for paint colors.

### 1.2 DEFINITIONS

- A. Gloss Level 1: Matte or Flat Finish: Not more than 5 units at 60 degrees and 10 units at 85 degrees, according to ASTM D 523.
- B. Gloss Level 3: Eggshell Finish: 10 to 25 units at 60 degrees and 10 to 35 units at 85 degrees, according to ASTM D 523.
- C. Gloss Level 4: Satin Finish: 20 to 35 units at 60 degrees and not less than 35 units at 85 degrees, according to ASTM D 523.
- D. Gloss Level 5: Semi-Gloss Finish: 35 to 70 units at 60 degrees, according to ASTM D 523.
- E. Gloss Level 6: Gloss Finish: 70 to 85 units at 60 degrees, according to ASTM D 523.
- F. Gloss Level 7: High Gloss Finish: More than 85 units at 60 degrees, according to ASTM D 523.

#### 1.3 REFERENCES

- A. ASTM International:
  - 1. ASTM C834 Latex Sealing Compounds.
  - 2. ASTM D16 Standard Terminology Relating to Paint, Varnish, Lacquer, and Related Products.
  - 3. ASTM D4442 Standard Test Methods for Direct Moisture Content Measurement of Wood and Wood-base Materials.
- B. Architectural Painting Specification Manual by the Master Painters Institute (MPI), including Evaluation, Systems, Preparation and Approved Product List (MPI Manual).

#### INTERIOR PAINTING

C. Test Method for Measuring Total Volatile Organic Compound Content of Consumer Products, Method 24 (for Surface Coatings) of the Environmental Protection Agency (EPA).

# 1.4 SYSTEM DESCRIPTION

- A. Painting and finishing shall include all coating systems materials, including primers, emulsions (except asphalt based), enamels, stains, sealers and fillers and other applied materials, whether used as prime, intermediate or finish coats.
  - 1. Materials to Paint:
    - a. Unless otherwise indicated in documents, Work receives painting and finishing. Consult Drawings, Schedules, and other specification Sections for complete requirements. Where materials required to be finished are not indicated in the Finish Schedule or Drawings, refer to the MPI Manual for the appropriate finish; provide premium grade finish.
    - b. Paint all exposed structure, fire protection piping, ductwork, exposed conduits at open to structure ceilings.
    - c. At "cloud ceilings", paint exposed structure and other mechanical and electrical items to minimum 5 feet beyond (behind) edge of suspended cloud ceiling.
  - 2. Materials Not to Paint:
    - a. Finished metal surfaces of anodized aluminum, polyvinylidene fluoride (PVDF), stainless steel, chromium plate, copper, bronze, and similar finished metals will not require finish painting, except as indicated otherwise.
    - b. Glass and plastic, except as noted otherwise.
    - c. Materials having complete factory finish or that require installer finishing, except as indicated otherwise. Shop priming of ferrous metal items and shop-fabricated components is included under various Sections.
    - d. Walls and ceilings in concealed and generally inaccessible areas, above suspended ceilings, furred areas, pipe spaces, duct shafts, and the like.
    - e. Acoustical ceiling tile and their suspension systems, unless indicated otherwise.
    - f. Concrete floors, except as indicated to be painted.
    - g. CMU except where indicated to be painted.
    - h. Moving parts of operating units, moving parts of mechanical and electrical units, linkages, sensing devices, motor and fan shafts, and the like.
    - i. Code-required labels such as Underwriter's Laboratories, Factory Mutual, and Warnock-Hershey or any equipment identification, performance rating, name or nomenclature plates, and the like.

# 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include preparation requirements and application instructions.
- B. Samples for Verification: For each type of paint system and in each color and gloss of topcoat.

# INTERIOR PAINTING

099123 - 2

- 1. Submit Samples on rigid backing, 8 inches square.
- 2. Step coats on Samples to show each coat required for system.
- 3. Label each coat of each Sample.
- 4. Label each Sample for location and application area.
- C. Product List: For each product indicated, include the following:
  - 1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.
  - 2. VOC content.

### 1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Paint: 5 percent, but not less than 1 gal. of each material and color applied.

### 1.7 QUALITY ASSURANCE

- A. Quality Standard:
  - 1. Work of this Section shall conform to not less than the minimum standards for material and Work including inspection and warranty requirements set forth in the MPI Manual.
  - 2. Work of this Section shall be of the grade and finish system in accordance with the MPI as indicated in Painting and Finishing Schedule in Part 3 of this Section.
- B. Qualifications:
  - 1. Product Manufacturers: As listed in MPI and Color and Material Schedule in Drawings. No substitutions.
  - 2. Applicator: Company specializing in and regularly engaged in performing Work of this Section with not less than three (3) years experience. Maintain regular work force of qualified journey-level personnel, trained, skilled, and experienced in performing required Work and constant competent supervision. Apprentices may be employed working under qualified journeymen's directions in accordance with trade regulations.
- C. Regulatory Requirements:
  - 1. Comply with applicable federal, state, and local requirements and publications pertaining to environmental protection and the protection of the health and safety of workers, visitors to the site, and persons occupying the Project Site.
  - 2. Where conflict among requirements or with this specification exists, the most stringent shall govern.

### 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.
  - 1. Maintain containers in clean condition, free of foreign materials and residue.
  - 2. Remove rags and waste from storage areas daily.

### 1.9 FIELD CONDITIONS

- A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F.
- B. Perform no interior painting or decorating work unless adequate continuous ventilation and sufficient heating facilities are in place to maintain ambient air and substrate temperatures above minimum requirements for 24 hours before, during and after paint application. Provide supplemental ventilating and heating equipment if ventilation and heating from existing system is inadequate to meet minimum requirements.
- C. Do not apply paints when relative humidity exceeds 85 percent; at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.
- D. Apply paint only to dry, clean, properly cured and adequately prepared surfaces in areas where dust is no longer generated by construction activities such that airborne particles will not affect the quality of finished surfaces.
- E. Perform no painting or decorating work unless a minimum lighting level of 323 Lux (30-foot candles) is provided on surfaces to be painted or decorated.
- F. Perform no painting or decorating work when the maximum moisture content of the substrate exceeds:
  - 1. 15 percent for wood.
  - 2. 12 percent for plaster and gypsum board.
- G. Conduct moisture tests using a properly calibrated electronic moisture meter.

# PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. As listed in the Interior Painting Schedule.
  - 1. Benjamin Moore (Basis-of-Design colors).
  - 2. Miller Paint.
  - 3. Rodda Paint Company.
  - 4. Sherwin Williams (Basis-of-Design products).

#### INTERIOR PAINTING

- B. The following manufacturers will be considered for substitution subject to compliance with procedures specified in Section 012500 "Substitution Procedures," and the properties specified for each product in the PART 3 Interior Painting Schedule.
  - 1. PPG.

# 2.2 PAINT, GENERAL

- A. Materials:
  - 1. Only materials (primers, paints, coatings, varnishes, stains, lacquers, fillers, etc.) listed in the latest edition of the MPI Approved Product List (APL) are acceptable for use on this project. All such material shall be from a single source manufacturer for each system used.
  - 2. Other materials such as linseed oil, shellac, thinners, solvents, etc., shall be the highest quality product of an MPI listed manufacturer and shall be compatible with paint materials being used as required.
- B. VOC Content: Products shall comply with VOC limits of authorities having jurisdiction and, for interior paints and coatings applied at Project site, the following VOC limits, exclusive of colorants added to a tint base, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 1. Flat Paints and Coatings: 50 g/L.
  - 2. Nonflat Paints and Coatings: 150 g/L.
  - 3. Dry-Fog Coatings: 400 g/L.
  - 4. Primers, Sealers, and Undercoaters: 200 g/L.
  - 5. Anticorrosive and Antirust Paints Applied to Ferrous Metals: 250 g/L.
  - 6. Zinc-Rich Industrial Maintenance Primers: 340 g/L.
  - 7. Pretreatment Wash Primers: 420 g/L.
  - 8. Floor Coatings: 100 g/L.
  - 9. Shellacs, Clear: 730 g/L.
  - 10. Shellacs, Pigmented: 550 g/L.

# 2.3 EQUIPMENT

- A. Painting and Decorating Equipment: To best trade standards for type of product and application.
- B. Spray Painting Equipment: Of ample capacity, suited to the type and consistency of paint or coating being applied and kept clean and in good working order at all times.

# 2.4 MIXING AND TINTING

A. Unless otherwise specified herein or pre-approved, all paint shall be ready-mixed and pre-tinted. Re-mix all paint in containers prior to and during application to ensure break-up of lumps, complete dispersion of settled pigment, and color and gloss uniformity.

- B. Paste, powder or catalyzed paint mixes shall be mixed in strict accordance with manufacturer's written instructions.
- C. Where thinner is used, addition shall not exceed paint manufacturer's recommendations. Do not use kerosene or any such organic solvents to thin water-based paints.
- D. If required, thin paint for spraying according in strict accordance with paint manufacturer's instructions. If directions are not on container, obtain instructions in writing from manufacturer and provide copy of instructions to Consultant.

### 2.5 FINISH AND COLORS

- A. Unless otherwise specified herein, all painting work shall be in accordance with MPI Premium Grade finish requirements.
- B. Refer to Color and Material Schedule and Drawings for identification and location of colors, PT-1 though PT-6.
- C. Except as noted herein or indicated in the Color and Material Schedule, interior walls and ceiling surfaces shall be painted in accordance with the following criteria over appropriate prime / sealer coat:
  - 1. All areas (except as noted): washable latex with GL3 (eggshell) finish.
  - 2. Laundry facilities / rooms, public wash / shower / bathrooms: washable latex with G5 (semi-gloss) finish.
  - 3. Public change / wash / shower rooms with institutional facility bathing and shower rooms: G5 (semi-gloss) finish for wet surfaces.
  - 4. Public and institutional facility "clean" or "sanitary" areas such as food preparation and laboratory areas: G5 (semi-gloss) finish for dry surfaces.
- D. Access doors, prime coated butts, and other prime coated hardware, registers, radiators and covers, exposed piping and electrical panels shall be painted to match adjacent surfaces (i.e. same color, texture and sheen), unless otherwise noted or where pre-finished.
- E. Plywood service panels (e.g. electrical, telephone, and cable vision panels) including edges shall be back-primed and painted to match painted wall mounted on.
- F. The inside of light valances shall be painted gloss white.
- G. The inside of all duct work behind louvers, grills and diffusers for a minimum of 18" (460 mm) or beyond sight-line, whichever is greater, shall be painted using flat black (non-reflecting) paint.

### 2.6 GLOSS AND SHEEN RATINGS

A. As indicated in Part 3 of these Specifications.

# INTERIOR PAINTING

# PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
  - 1. Concrete: 12 percent.
  - 2. Masonry (Clay and CMU): 12 percent.
  - 3. Wood: 15 percent.
  - 4. Portland Cement Plaster: 12 percent.
  - 5. Gypsum Board: 12 percent.
- C. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.
- D. Proceed with coating application only after unsatisfactory conditions have been corrected.
  - 1. Application of coating indicates acceptance of surfaces and conditions.

# 3.2 PREPARATION

- A. Comply with manufacturer's written instructions and recommendations in "MPI Manual" applicable to substrates and paint systems indicated.
- B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
  - 1. Carefully clean and replace all such items upon completion of painting work in each area. Do not use solvent or reactive cleaning agents on items that will mar or remove finishes (e.g. lacquer finishes).
  - 2. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
- C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
  - 1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.
- D. Protect all adjacent interior surfaces and areas, including rating and instruction labels on doors, frames, equipment, piping, etc., from painting operations and damage with drop cloths, shields, masking, templates, or other suitable protective means and make good any damage caused by failure to provide such protection.

#### **INTERIOR PAINTING**

- E. Substrate defects shall be made good and sanded by others ready for painting particularly after the first coat of paint. Start of finish painting of defective surfaces (e.g. gypsum board) shall indicate acceptance of substrate and any costs of making good defects shall be borne by the painter including re-painting of entire defective surface (no touch-up painting).
- F. Wood Substrates:
  - 1. Scrape and clean knots and, apply coat of knot sealer before applying primer.
  - 2. Sand surfaces that will be exposed to view and dust off.
  - 3. Prime edges, ends, faces, undersides, and backsides of wood.
  - 4. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.

# 3.3 APPLICATION

- A. Apply paints according to manufacturer's written instructions and recommendations.
  - 1. Use applicators and techniques suited for paint and substrate indicated.
  - 2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
  - 3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
  - 4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
  - 5. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.
- B. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Tint undercoats to match color of topcoat but, provide sufficient difference in shade of undercoats to distinguish each separate coat.
- C. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.
- D. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

# 3.4 FIELD QUALITY CONTROL

A. Tolerances: Final application shall match color and texture of approved samples and shall be smooth, uniform in appearance, color, texture, sheen, and shall be free of runs, sags, holidays, lap marks, air bubbles, pin holes, and other detrimental effects in accordance with requirements of the MPI and this Specification.

# B. Inspection and Testing:

- 1. Provide and pay for inspection and testing of the Work of this Section in accordance with the warranty provisions of the MPI.
- 2. Inspection Agency's Duties:
  - a. Provide qualified personnel at Project Site. Cooperate with Architect and Contractor in performance of services.
  - b. Perform required inspection, sampling, and testing of Products and applications and ascertain compliance with requirements of MPI.
  - c. After each inspection and test, submit 1 copy of written report within 5 calendar days to Architect and Contractor. Include in each report the Project title, date of report, date and time of inspection, weather conditions during visit, name of inspector, identification of Product and substrate, location in Project, type of inspection or test, results of tests, and whether results indicate conformity with Contract Documents.
  - d. Promptly notify Architect and Contractor in writing of observed irregularities or non-conformity of workmanship of Projects. When requested by Architect, provide interpretation of test results, evaluation of analysis of cause (in event of test failure), and recommendations for remedial action.
- 3. Inspection Agency's Limitations:
  - a. Inspection Agency may not release, revoke, alter, or enlarge on requirements of Contract Documents.
  - b. Inspection Agency many not approve or accept any portion of the Work for Owner or Architect.
  - c. Inspection Agency may not assume duties of Contractor or Applicator.
  - d. Inspection Agency has no authority to stop the Work.
- 4. Applicator's Duties:
  - a. Pay inspection fees associated with inspection and warranty requirements set forth in MPI.
  - b. Notify inspection agency not less than 10 full working days prior to beginning Work of this Section.
  - c. Notify inspection agency not less than 2 full working days prior to expected time for operations requiring inspection or testing services.
  - d. Allow full access to the Work. Cooperate with inspection and testing personnel in performance of their duties of inspecting and testing of Work.
  - e. Provide incidental labor and facilities to provide access to Work to be inspected or tested. Repair destructive testing sites.
  - f. Correct deficiencies noted by Inspection Agency.

### 3.5 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

#### **INTERIOR PAINTING**

- B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

### 3.6 INTERIOR PAINTING SCHEDULE

- A. Gypsum Board: (Damp areas with higher maintenance requirements including Culinary Classroom)
  - 1. Two water-based high-performance acrylic coats (over vinyl acrylic primer).
  - 2. Finish Sheen: Gloss Level 5.
    - a. Primer: S-W ProMar 200 Zero VOC Interior Latex Primer B28W02600 (Volume Solids: 26 percent plus or minus 2 percent).
    - b. Finish: S-W Pro Industrial Acrylic Semi-Gloss, B66 Series, (less than 50 g/L VOC), (Volume Solids: 35 percent plus or minus 2 percent.
- B. Existing Painted CMU:
  - 1. TBD
  - 2. Finish Sheen: Gloss Level 5.
    - a. TBD
    - b. TBD

END OF SECTION 099123

# SECTION 101100 - VISUAL DISPLAY UNITS

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Visual display board assemblies.
  - 2. Magnetic marker-board panels (MBD-#).
- B. Related Requirements:
  - 1. Color and Material Schedule on drawings for visual display unit sizes and colors.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, finishes, and accessories for visual display units.
  - 2. Include electrical characteristics for motorized units.
- B. Shop Drawings: For visual display units.
  - 1. Include plans, elevations, sections, details, and attachment to other work.
  - 2. Include sections of typical trim members.
- C. Samples for Verification: For each type of visual display unit indicated.
  - 1. Visual Display Panel: Not less than 8-1/2 by 11 inches (215 by 280 mm), with facing, core, and backing indicated for final Work. Include one panel for each type, color, and texture required.
  - 2. Trim: 6-inch- (150-mm-) long sections of each trim profile.
  - 3. Display Rail: 6-inch- (150-mm-) long section of each type.
  - 4. Accessories: Full-size Sample of each type of accessory.
- D. Product Schedule: For visual display units. Use same designations indicated on Drawings.

# VISUAL DISPLAY UNITS
#### 1.4 INFORMATIONAL SUBMITTALS

A. Sample Warranties: For special warranties.

### 1.5 QUALITY ASSURANCE

A. Source Limitations: Obtain visual display surfaces from single source from single manufacturer.

### 1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver factory-fabricated visual display units completely assembled in one piece. If dimensions exceed maximum manufactured unit size, or if unit size is impracticable to ship in one piece, provide two or more pieces with joints in locations indicated on approved Shop Drawings.

### 1.7 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install visual display units until spaces are enclosed and weather-tight, wet-work in spaces is complete and dry, work above ceilings is complete, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.
- B. Field Measurements: Verify actual dimensions of construction contiguous with visual display units by field measurements before fabrication.
  - 1. Allow for trimming and fitting where taking field measurements before fabrication might delay the Work.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

A. Source Limitations: Obtain each type of visual display unit from single source from single manufacturer.

#### 2.2 PERFORMANCE REQUIREMENTS

- A. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Flame-Spread Index: 25 or less.
  - 2. Smoke-Developed Index: 450 or less.

# VISUAL DISPLAY UNITS

### 2.3 VISUAL DISPLAY MARKERBOARD ASSEMBLY (MBD)

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Claridge Products and Equipment, Inc.
  - 2. ADP Lemco, Inc.
- B. Visual Display Board Assembly Factory fabricated.
  - 1. Basis-of-Design Product: LCS Magnetic Marker-Boards by Claridge.
  - 2. Assembly: Marker-Board.
  - 3. Corners: Square.
  - 4. Width: As indicated on Drawings.
  - 5. Height: As indicated on Drawings.
  - 6. Mounting Method: Direct to wall.
  - 7. Frame: Aluminum angle trim, white color.
  - 8. Frame depth: To match depth of marker-board.
- C. Marker-Board Panel: Porcelain-enamel-faced markerboard panel on core indicated.
  - 1. Color: Claridge No. 100, "White".
- D. Joints: Make joints only where total length exceeds maximum manufactured length. Fabricate with minimum number of joints, as indicated on approved Shop Drawings.
- E. Chalk Tray: Manufacturer's standard; continuous.
  - 1. Extruded aluminum, 3-1/4 inches wide with radius front edge, grooved tray, and castaluminum end closures; powder coat white finish.
- F. Display Rail: Manufacturer's standard, extruded-aluminum display rail with plastic-impregnatedcork insert, end stops, and continuous paper holder, designed to hold accessories.
  - 1. Size: 1-inch by length of markerboard.
  - 2. Map Hooks: Two map hooks for every 48 inches (1200 mm) of display rail or fraction thereof.
  - 3. Flag Holder: One.
- G. Paper Holder Display Rail: Extruded aluminum; designed to hold paper by clamping action.

#### 2.4 VISUAL DISPLAY TACKBOARD ASSEMBLY (TBD)

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Claridge Products and Equipment, Inc.
  - 2. ADP Lemco, Inc.

#### VISUAL DISPLAY UNITS

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- B. Visual Display Board Assembly Factory fabricated.
  - 1. Basis-of-Design Product: 800 Series Tackboard by Claridge.
  - 2. Assembly: tack-board with aluminum trim
  - 3. Corners: Square.
  - 4. Width: As indicated on Drawings.
  - 5. Height: As indicated on Drawings.
  - 6. Mounting Method: Direct to wall.
  - 7. Frame: Aluminum angle trim; color, white.
  - 8. Frame depth: To match depth of tack-board.
- C. Joints: Make joints only where total length exceeds maximum manufactured length. Fabricate with minimum number of joints, as indicated on approved Shop Drawings.

# 2.5 MATERIALS

- A. Porcelain-Enamel Face Sheet: PEI-1002, with face sheet manufacturer's standard two- or three-coat process.
- B. Particleboard: ANSI A208.1, Grade M-1, made with binder containing no urea formaldehyde.
- C. Extruded Aluminum: ASTM B 221 (ASTM B 221M), Alloy 6063.
- D. Adhesives for Field Application: Mildew-resistant, non-staining adhesive for use with specific type of panels, sheets, or assemblies; and for substrate application; as recommended in writing by visual display unit manufacturer.
  - 1. Adhesives shall have a VOC content of 50 g/L or less.

## 2.6 GENERAL FINISH REQUIREMENTS

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

## 2.7 ALUMINUM FINISHES

A. Clear Anodic Finish: AAMA 611, AA-M12C22A31, Class II, 0.010 mm or thicker.

# PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances, surface conditions of wall, and other conditions affecting performance of the Work.
- B. Examine roughing-in for electrical power systems to verify actual locations of connections before installation of motorized, sliding visual display units.
- C. Examine walls and partitions for proper preparation and backing for visual display units.
- D. Examine walls and partitions for suitable framing depth where sliding visual display units will be installed.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Comply with manufacturer's written instructions for surface preparation.
- B. Clean substrates of substances, such as dirt, mold, and mildew, that could impair the performance of and affect the smooth, finished surfaces of visual display boards.
- C. Prepare surfaces to achieve a smooth, dry, clean surface free of flaking, unsound coatings, cracks, defects, projections, depressions, and substances that will impair bond between visual display units and wall surfaces.

#### 3.3 INSTALLATION

- A. General: Install visual display surfaces in locations indicated on Drawings; mounting heights are to be coordinated with the Owner. Keep perimeter lines straight, level, and plumb. Provide grounds, clips, backing materials, adhesives, brackets, anchors, trim, and accessories necessary for complete installation.
- B. Factory-Fabricated Visual Display Board Assemblies: Attach concealed clips, hangers, and grounds to wall surfaces and to visual display board assemblies with fasteners at not more than 16 inches (400 mm) on center. Secure tops and bottoms of boards to walls.

## 3.4 CLEANING AND PROTECTION

- A. Clean visual display units according to manufacturer's written instructions. Attach one removable cleaning instructions label to visual display unit in each room.
- B. Touch up factory-applied finishes to restore damaged or soiled areas.

#### VISUAL DISPLAY UNITS

C. Cover and protect visual display units after installation and cleaning.

END OF SECTION 101100

VISUAL DISPLAY UNITS

## SECTION 102600 - WALL AND DOOR PROTECTION

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Corner guards (CG-1).

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, impact strength, dimensions of individual components and profiles, and finishes.

#### 1.4 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of wall and door protection product to include in maintenance manuals.

### 1.5 DELIVERY, STORAGE, AND HANDLING

A. Store wall and door protection in original undamaged packages and containers inside wellventilated area protected from weather, moisture, soiling, extreme temperatures, and humidity.

### PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

A. Source Limitations: Obtain wall- and door-protection products from single source from single manufacturer.

## 2.2 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines for Buildings and Facilities and ICC A117.1.

### 2.3 CORNER GUARDS (CG-1)

- A. Surface-Mounted, Metal Corner Guards: Fabricated as one piece from formed metal with formed edges; with 90-degree turn to match wall condition.
  - 1. Manufacturers: Subject to compliance with requirements, provide products from one of the following:
    - a. American Floor Products, Inc.
    - b. Babcock-Davis
    - c. Balco, Inc.
    - d. Construction Specialties, Inc.
    - e. InPro Corp. (IPC).
    - f. Nystrom.
  - 2. Material: Stainless-steel sheet, Type 304.
    - a. Thickness: Minimum 0.0625 inch (1.6 mm).
    - b. Finish: Directional satin, No. 4.
  - 3. Wing Size and Length:
    - a. 1-1/2 by 1-1/2 inches (38 by 38 mm) by 6 feet long.
  - 4. Corner Radius: 1/8 inch (3 mm).
  - 5. Mounting: Flat-head, countersunk screws through factory-drilled mounting holes. Locate holes 1 inch from corner (not centered on wing), to coordinate with MDF and gypsum board seams.

### 2.4 MATERIALS

A. Fasteners: Aluminum, nonmagnetic stainless-steel, or other noncorrosive metal screws, bolts, and other fasteners compatible with items being fastened. Use security-type fasteners where exposed to view.

### 2.5 FABRICATION

A. Fabricate wall and door protection according to requirements indicated for design, performance, dimensions, and member sizes, including thicknesses of components.

B. Quality: Fabricate components with uniformly tight seams and joints and with exposed edges rolled. Provide surfaces free of wrinkles, chips, dents, uneven coloration, and other imperfections. Fabricate members and fittings to produce flush, smooth, and rigid hairline joints.

## 2.6 FINISHES

- A. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

## PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine substrates and wall areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine walls to which wall and door protection will be attached for blocking, grounds, and other solid backing that have been installed in the locations required for secure attachment of support fasteners.
  - 1. For wall and door protection attached with adhesive, verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 PREPARATION

- A. Complete finishing operations, including painting, before installing wall and door protection.
- B. Before installation, clean substrate to remove dust, debris, and loose particles.

#### 3.3 INSTALLATION

A. Installation Quality: Install wall and door protection according to manufacturer's written instructions, level, plumb, and true to line without distortions. Do not use materials with chips, cracks, voids, stains, or other defects that might be visible in the finished Work.

### 3.4 CLEANING

- A. Immediately after completion of installation, clean plastic covers and accessories using a standard ammonia-based household cleaning agent.
- B. Remove excess adhesive using methods and materials recommended in writing by manufacturer.

END OF SECTION 102600

# SECTION 102800 - TOILET AND CUSTODIAL ACCESSORIES

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Lavatory accessories.
  - 2. Under lavatory guards.
  - 3. Custodial accessories.
- B. Related Requirements:
  - 1. WHS Owner Furnished Material & Equipment Schedule on the Drawings.
  - 2. Accessories Schedule on the Drawings.

#### 1.3 DEFINITIONS

- A. OFCI: Owner Furnished, Contractor Installed.
- B. CFCI: Contractor Furnished, Contractor Installed.

#### 1.4 COORDINATION

- A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.
- B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

#### TOILET, BATH, AND LAUNDRY ACCESSORIES

102800 - 1

- 2. Include anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
- B. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.
  - 1. Identify locations using room designations indicated.
  - 2. Identify accessories using designations indicated.

# 1.6 INFORMATIONAL SUBMITTALS

A. Sample Warranty: For manufacturer's special warranty.

# 1.7 CLOSEOUT SUBMITTALS

A. Maintenance Data: For accessories to include in maintenance manuals.

# PART 2 - PRODUCTS

# 2.1 OWNER-FURNISHED MATERIALS

A. Owner-Furnished Materials: See WHS Owner Furnished Material & Equipment Schedule.

## 2.2 LAVATORY ACCESSORIES

- A. Source Limitations: Obtain public-use washroom accessories from single source from single manufacturer. Refer to Accessories Schedule on drawings for products.
- B. Paper Towel Dispenser (PTD): OFCI.
- C. Liquid-Soap Dispenser (SD): OFCI.

# 2.3 UNDERLAVATORY GUARDS (CFCI)

- A. Under-lavatory Guards (UG):
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Plumberex Specialty Products, Inc.
    - b. Truebro by IPS Corporation.

## TOILET, BATH, AND LAUNDRY ACCESSORIES

102800 - 2

- 2. Description: Insulating pipe covering for supply and drain piping assemblies that prevents direct contact with and burns from piping; allow service access without removing coverings.
- 3. Material and Finish: Antimicrobial, molded plastic, white.

### 2.4 MATERIALS

- A. Stainless Steel: ASTM A 666, Type 304, 0.031-inch (0.8-mm) minimum nominal thickness unless otherwise indicated.
- B. Brass: ASTM B 19, flat products; ASTM B 16/B 16M, rods, shapes, forgings, and flat products with finished edges; or ASTM B 30, castings.
- C. Steel Sheet: ASTM A 1008/A 1008M, Designation CS (cold rolled, commercial steel), 0.036inch (0.9-mm) minimum nominal thickness.
- D. Galvanized-Steel Sheet: ASTM A 653/A 653M, with G60 (Z180) hot-dip zinc coating.
- E. Galvanized-Steel Mounting Devices: ASTM A 153/A 153M, hot-dip galvanized after fabrication.
- F. Fasteners: Screws, bolts, and other devices of same material as accessory unit and tamper-and-theft resistant where exposed, and of galvanized steel where concealed.

## PART 3 - EXECUTION

#### 3.1 INSTALLATION

A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.

### 3.2 ADJUSTING AND CLEANING

- A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.
- B. Remove temporary labels and protective coatings.
- C. Clean and polish exposed surfaces according to manufacturer's written instructions.

## END OF SECTION 102800

## TOILET, BATH, AND LAUNDRY ACCESSORIES

# SECTION 114000 - FOOD SERVICE EQUIPMENT

### PART 1 - GENERAL

### 1.1 SECTION INCLUDES: FOOD SERVICE EQUIPMENT

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 0 and Division 1 Specification Sections, apply to this Section.

### 1.2 RELATED WORK

- A. Rough-ins and Final Connections: Service lines from rough-in to point of final connections are provided by plumbing and electrical contractors.
- B. Electrical: Wiring, conduit, fuses, breakers, final disconnects, junction boxes, and other required electrical apparatus not built-in or mounted on equipment are provided by electrical contractor.
- C. Plumbing: Controls, regulators, valves, stops, traps, strainers, checks, grease traps, and fittings not mounted on/in equipment are provided by plumbing contractor.
- D. Mechanical: Ductwork from above finished ceiling to building exhaust and supply fans, flue pipes, exhaust and supply fans for hoods, room ventilation, and air supply blowers are provided by mechanical contractor.
- E. Miscellaneous
  - 1. Provides backing plates or blocking in wall or ceiling partitions.
  - 2. Provides fittings secured to structural ceiling to accommodate hangers.
  - 3. Provides the forming of architectural enclosures, floor, wall openings or recesses for equipment.
  - 4. Caulks and seals Cold Storage Room floor sections to building floor.
  - 5. Finishes floors (masonry or poured-in-place) in cold storage rooms, concrete curbs and pads.

### 1.3 SYSTEM DESCRIPTION

- A. Delegated Design: Design canopy hoods with fire protection system, walk-in cold storage rooms, and seismic restraint of equipment using performance requirements and design criteria indicated, including comprehensive engineering analysis by a qualified professional engineer licensed by the State.
- B. Fabricated Equipment: Constructed to configuration, dimension, detail, and design as shown with materials and workmanship as specified.

- C. Manufactured Equipment: Mass produced and referenced by manufacturer's name and model number.
- D. Each model number includes the code \*H011 as a suffix. This code is known as the Specified Identification System. It is not to be removed by the bidders. Its purpose is to identify the Food Service Consultant to the vendors providing equipment in the event it is necessary to communicate questions, clarifications, and comments, from prior to bid award through the final purchase. It is to be used on all correspondence, including fax and e-mail, when communicating with manufacturer representatives and factories.

### 1.4 DEFINITIONS

- A. Furnish Supply and deliver to Project Site, ready for unloading, unpacking, assembly, installation, and similar operations.
- B. Install (set in place) Work at Project Site, including actual unloading, unpacking, assembly, erecting, rigging, placing, anchoring, applying, finishing, curing, protecting, cleaning, and similar operations, ready for final utility connections by other Sections as appropriate.
- C. Coordinate Relay required information requested by other trades to ensure they are able to correctly perform their work related to the food service or laundry equipment installation.
- D. Provide Furnish and install complete, ready for intended use.
- E. Contractor All references to the Contractor in this Section 114000 shall refer to the Kitchen Equipment Contractor. Reference to any other Contractor shall be specific, such as General Contractor, Plumbing Contractor, Electrical Contractor, Architect, designated, etc.

## 1.5 LAWS, ORDINANCES AND STANDARDS

- A. STANDARDS: Except as otherwise indicated, comply with the following standards as applicable to the manufacture, fabrication, and installation of the work of this Section:
  - 1. Air Conditioning and Refrigeration Institute (ARI): Comply with the applicable regulations and references of the latest edition of standards for remote refrigeration system(s), components, and installation.
  - 2. American Gas Association (AGA): Comply with AGA standards for gas heated equipment and provide equipment with the AGA seal. Automatic safety pilots shall be provided on all equipment, where available. (Canadian Gas Association or alternate testing lab's seals may be accepted if acceptable to local code jurisdictions.)
  - 3. American National Standards Institute (ANSI): Comply with ANSI Z21-Series standards for gas-burning equipment and provide labels indicating name of testing agency.
  - 4. American National Standards Institute (ANSI): Comply with ANSI B57.1 for compressed gas cylinder connections and with applicable standards of the Compressed Gas Association for compressed gas piping.
  - 5. American National Standards Institute (ANSI): Comply with ANSI A40.4 and A40.6 for water connection air gaps and vacuum breakers.

- 6. American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE): Comply with the applicable regulations and the latest edition of standards for remote refrigeration system(s), components, and installation.
- 7. American Society of Mechanical Engineers (ASME): Comply with ASME Boiler Code requirements for steam generating and steam heated equipment and provide ASME inspection, stamp, and registration with National Board.
- 8. American Society for Testing and Materials (ASTM): Comply with ASTM C1036 for flat glass.
- 9. American Society for Testing and Materials (ASTM): Comply with ASTM C1048 for heat-treated flat glass Kind HS, Kind FT coated and uncoated glass.
- 10. American Welding Society (AWS): Comply with AWS D1.1 structural welding code.
- 11. National Electric Code (NEC): Comply with NFPA Volume 5 for electrical wiring and devices included with food service equipment, ANSI C2 and C73, and applicable NEMA and NECA standards.
- 12. National Electrical Manufacturers Association (NEMA): Comply with NEMA LD3 for high-pressure decorative laminates.
- 13. National Fire Protection Association (NFPA): Comply with the applicable sections of the NFPA for exhaust hood, ventilators, duct and fan materials, hoods fire suppression systems, construction and installation, as well as local codes and standards.
- 14. National Sanitation Foundation (NSF): Comply with the latest Standards and Revisions established by NSF for equipment and installation. Provide NSF Seal of Approval on each applicable manufactured item and on items of custom fabricated work. (UL Sanitation approval and seal may be accepted if acceptable to local code jurisdictions.)
- 15. Sheet Metal and Air Conditioning National Association (SMACNA): Comply with the latest edition of SMACNA guidelines for seismic restraint of kitchen equipment and applicable local regulatory agencies requirements.
- 16. Underwriters Laboratories (UL): Provide either UL labeled products for electrical components and assemblies or, where no labeling service is available, "recognized markings" to indicate listing in the UL "Recognized Component Index". (Canadian Standards Association or alternate testing lab's seals may be accepted if acceptable to local code jurisdictions.)
- 17. UL 300 Standard: Wet chemical fire suppression systems for exhaust hoods/ventilators shall comply with these requirements.
- 18. American with Disabilities Act (ADA): Comply with requirements as applicable to this Project.
- 19. Refrigeration Service Engineers Society (RSES): Comply with the applicable regulations, the latest edition of standards for remote refrigeration system(s), components and installation, and the 1995 requirements of the Montreal Protocol Agreement.
- 20. All refrigerants used for any purpose shall comply with the 1995 requirements of the Montreal Protocol Agreement and subsequent revisions and amendments. No CFC refrigerants shall be allowed on this Project.
- 21. All refrigeration components installation, repairs, and/or associated work on any refrigeration system, self-contained or remote, shall be performed by a Certified Refrigeration Mechanic.
- 22. Comply with all applicable local codes, standards and regulations, and any special local conditions (example only: City of Los Angeles Testing Lab requirements or seismic standards compliance).

- 23. Jails, prisons, and all detention facilities shall comply with Correctional Standards as applicable to the specific Project. Verify the level of security and construction required with the Project Architect and provide all items in compliance. As a minimum, no part or component of any item provided shall be easily removable and used as a weapon.
- 24. Subway grating installed in floor drain troughs must meet IBC 1104.3.1 standards for maximum opening sizes in grates.
- 25. Confirm all drawings, specifications, and project documentation meet all federal, state, and local codes and regulations.

## 1.6 CONTRACTOR QUALIFICATIONS

- A. In addition to requirements of Related Sections 1.02, submit evidence of compliance with the following qualifications and conditions:
  - 1. Five (5) years minimum continuous operation under the same company name and ownership.
  - 2. Evidence of Company's financial stability and financial ability to complete this Project without endangering that stability.
  - 3. List a minimum of comparable size and scope projects completed in the last five (5) years with Owner's contact name and telephone number.
  - 4. Have manufacturer's authorization to purchase, distribute, and install all items specified with this Project.
  - 5. Maintain a staff or have access to personnel with a minimum of five (5) years' experience in the installation of comparable size and scope projects, and meeting NSF standards and requirements. (UL Sanitation standards and requirements may be accepted if acceptable to local code jurisdictions.)
  - 6. Maintain or have access to a fabrication shop meeting NSF standards and labeling requirements. (UL Sanitation approval and seal may be accepted if acceptable to local code jurisdictions.) If other than the Contractor 's own fabrication shop, they shall have five (5) years minimum experience in the fabrication of comparable size, scope, and level of quality projects. The Contractor shall submit their company name and credentials to the Architect, who shall have the right of approval or disapproval
  - 7. Maintain a staff or have access to personnel experienced in the preparation of professional style shop drawings and submittals.
  - 8. Maintain or have access to manufacturer's authorized service personnel together with readily available stock of repair and replacement parts.
  - 9. Any sub-Contractor employed by Contractor for this Project shall comply with the same qualification requirements.

## 1.7 SUBSTITUTIONS

A. Refer to Division 1 for Substitution Request requirements.

## 1.8 APPROVED SUBSTITUTIONS AND/OR LISTED ALTERNATES

- A. Substitutions approved as noted in article 1.07 and/or any Listed Alternate Manufacturers listed in these Itemized Specifications or added by Addendum may be utilized in lieu of the primary specified manufacturer with the following conditions and understanding:
  - 1. The Project Documents are designed and engineered using the primary specified manufacturer and model. The Contractor shall assume total responsibility for any deviations required due to the utilization of a substitution/alternate manufacturer or model including, but not limited to, fitting alternates into the available space, providing directions for required changes, and assuming any and all associated costs for utility, building, food service design, architectural, or engineering changes directly or indirectly related to the substitution.
  - 2. The Contractor shall be responsible for supplying the model, which is equal to the primary specified model in regard to general function, features, options, sizes, accessories, utility requirements, finish, operation, and listing approvals. If the Owner or their appointed representative determines at any time during the construction and installation, prior to the final acceptance of the Project, that the substitution/alternate model submitted is not equal to the primary specified model, the Contractor shall assume all associated cost and implications required to replace the model submitted with the correct model.
  - 3. The bid proposal shall clearly state any substitutions/alternates which will be utilized, including the manufacturer and model number. The proposal shall also include a data sheet for each substitution/alternate with all deviations between the primary specified manufacturer and the substitution/alternate manufacturer itemized and listed on the data sheet. The manufacturers' cut sheets are not acceptable as a substitute for the data sheet. Complex alternates, such as utility distribution systems, exhaust hoods, ventilators, etc., shall include a shop drawing specific to the Project.
  - 4. Inclusion of an alternate manufacturer in the Itemized Specifications is not intended to indicate that there is an equal alternate unit to match every primary specified unit. It shall be the responsibility of the Contractor to ensure that the alternate unit submitted matches the primary specified unit and meets the other conditions, as stated above.
  - 5. Manufacturers not approved as substitutions or listed as a Listed Alternate will not be permitted unless submitted for prior approval, as described above and in the General and Supplementary Conditions and applicable Division-1 Specifications Sections.
  - 6. Submittal of a substitution/alternate manufacturer or model shall indicate agreement to the above stated conditions. Solely at the Owner's discretion, failure to comply with any of these conditions or to supply complete and correct data information shall result in the Contractor being required to provide the primary specified manufacturer at no additional cost to the Owner or to adjust the Contract cost.

# 1.9 DISCREPANCIES

A. Where discrepancies are discovered between the drawings and the specifications regarding quality or quantity, the higher quality or the greater quantity shall be included in the Bid Proposal. The Contractor shall notify the Architect, in writing, of any discrepancies discovered and await clarification prior to proceeding with the items or areas in question.

### 1.10 SUBMITTALS

- A. The Contractor shall review all submittals for basic compliance with the Contract Documents and correct as required prior to submitting to the Design Team (Architects/Engineers/ Consultants/Owner) for review. Failure to comply with this requirement, the submission of submittal(s) which are significantly inconsistent with the Contract Documents, or inconsistencies that are discovered during review by a Design Team member shall be justification for reimbursement by the Contractor to the Design Team member's company for the "lost" time or for the time required for a second review.
- B. Rough-In Drawings
  - 1. Submit electronic PDF file for approval. After approval, reproduce and supply the required number of distribution prints for record and construction purposes.
  - 2. Submit 1/4 inch (1:50) scale rough-in drawings for approval. These drawings shall be dimensioned from grid lines showing location of ducts, stubs, floor and wall sleeves for ventilation, plumbing, steam, electrical, refrigeration lines, beverage lines, concrete base and curb dimensions as required for equipment so supported.
  - 3. Site-verify mechanical, electrical and ventilating rough-in and sleeve locations.
  - 4. The Contractor shall be responsible for the accuracy of the information on their submittals.
  - 5. In the event rough-ins have been accomplished before the award of this contract, the Contractor shall check the existing facility and make adjustments to their equipment to suit building conditions and utilities, where possible. If not possible, the Contractor shall so state in a letter to the Owner and Architect with reasons and an alternate method and pricing.
- C. Shop Drawings
  - 1. Submit electronic PDF file for approval. After approval, reproduce and supply the required number of distribution prints for record and construction purposes.
  - 2. Submit shop drawings for items of custom fabrication included in this contract. Shop drawings shall be submitted at 3/4 inch (1:20) and/or 1-1/2 inch (1:10) scale and shall show dimensions, materials, details of construction, features and options, installation and relation of adjoining work requiring cutting or close fitting. Shop drawings shall also indicate reinforcements, anchorage and related work required for the complete installation of fixtures.
  - 3. Before proceeding with the fabrication of any item, the Kitchen Equipment Contractor (KEC) shall be responsible for verifying and coordinating all dimensions and details with site dimensions and conditions.

### WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

# D. Product Data Submittal Manuals

- 1. Submit electronic PDF file of Product Data Submittal Manuals with a cover sheet and detailed information on every item included in this Section for approval. Detailed information shall include, but not be limited to, item number, description, quantity, model numbers, options and accessories provided, exact utility requirements, manufacturer's cut-sheets, reference to specific shop drawings, etc. Distribute one additional copy of installation and start-up instructions to the Installer. Mark each data sheet with the applicable project equipment item number. Each data sheet shall include NEMA plug and receptacle configuration for applicable items, where applicable. Every cover sheet and associated detailed submittal shall provide sufficient and complete information to verify that the Contractor is providing each item in compliance with the Contract documents.
- 2. Architect review of drawings, shop details, product data brochures, and service and parts manuals are for general conformance with the design concept and contract documents. Markings or comments shall not be construed as relieving the Contractor from compliance with the contract documents or departures there from. The Contractor remains responsible for details and accuracy, for confirming and correlating all quantities and dimensions, for selecting fabrication processes, for techniques of assembly, and for performing their work in a safe, satisfactory, and professional manner.

## 1.11 OPERATION AND MAINTENANCE DATA MANUALS

- A. Operation and Maintenance Manuals (Service and Parts Manuals): Three (3) bound sets of manuals shall be furnished for items of standard manufacture on/or before the date of the first event to occur of the following: demo/start-up, start-up for intended use by the Owner/Operator, completion of installation of kitchen equipment contract package, or final acceptance of installation by Owner. Manuals shall be in alphabetical order according to manufacturer, including item numbers and utility options provided for the equipment installed.
  - 1. Installing company's name, address, telephone number, and date of completed installation.
  - 2. Serial numbers of principal pieces of equipment.
  - 3. Part numbers of all replaceable items.
  - 4. Lubrication data and belt sizes.
  - 5. Electrical characteristics including data for motors and heaters.
- B. Service Agency List: Submit a complete list of local service agencies with the service and parts manuals for included manufacturers, complete with telephone numbers for all buy-out equipment installed.
- C. Provide video tapes for maintenance, training, operation, etc. where available from the manufacturer.

### 1.12 AS-BUILT/RECORD DOCUMENTS

- A. Maintain one record set of Food service Equipment Plans with any related corrections, revisions, additions, deletions, changes, etc. noted during construction and installation. Provide an "as-built" set in reproducible transparency form and electronic computer disk form.
- B. Provide one (1) final set of Product Data Submittal Manuals with any related corrections, revisions, additions, deletions, changes, etc. noted during construction and installation as a specifications record set.
- C. These documents shall be provided on/or before the date of the first event to occur of the following: demo/start-up, start-up for intended use by the Owner/Operator, completion of installation of kitchen equipment contract package, or final acceptance of installation by Owner.
- D. Provide two (2) final complete set of Submittals to be retained by Architect as a Record Set.

### 1.13 SCHEDULE

- A. General: Time is of the essence in this agreement. Acceptance constitutes a guarantee that the Contractor can and will obtain materials, equipment, and manpower to permit overall completion of the entire building project on schedule upon notice to proceed. The Contractor shall coordinate their work with the progress schedule, as prepared and updated periodically by the General Contractor or Construction Manager.
- B. The Contractor shall notify the Food Service Consultant and the Architect in writing of anticipated delays not within the realm of control of the Contractor immediately upon the Contractor 's realization that delays are imminent.
- C. The Contractor will not be granted relief for failure to meet schedules or failure of manufacturers to meet promised delivery dates unless the Contractor can establish, in writing, that orders were received by the manufacturer with reasonable lead times.
- D. The Contractor shall pay extra charges resulting from special handling or air shipment in order to meet the schedule if insufficient time was allowed in placing factory orders.

#### 1.14 PRODUCT HANDLING

- A. Delivery of Materials: Deliver materials (except bulk materials) in manufacturer's containers fully identified with manufacturer's name, trade name, type, class, grade, size, color, power requirement, if any, and item number.
- B. Storage of Materials, Equipment and Fixtures: Contractor is responsible for receiving and warehousing of equipment and fixtures until ready for installation. The Contractor will store materials, equipment, and fixtures in sealed containers. They shall be stored off the ground and under cover, protected from damage.

C. Handling Materials and Equipment: The Contractor will verify and coordinate conditions at the building site, particularly door and/or wall openings and passages to assure access for all equipment. Pieces too bulky for existing facilities shall be hoisted or otherwise handled with apparatus as required. All special handling equipment charges shall be arranged for and paid for by the Contractor.

### 1.15 PRODUCT PROTECTION

- A. The Contractor is responsible to protect their equipment against theft or damage during the progress of the project until final acceptance by the Owner. Items delivered to the job site at the Owner's or Contract Manager's request before the site is ready for installation should be signed for as approved by the Owner or Contract Manager.
- B. The Contractor will use all reasonable means to protect the materials of this Section before, during, and after installation and to protect the associated work and materials of the other trades.
- C. Pre-fabricated walk-in boxes, on-site and installed in advance of the rest of the equipment are not to be used for general storage by other trades and should be locked before leaving the site. Damage and theft resulting from the failure to secure boxes shall be repaired or replaced at the Contractor 's own expense. The Contractor shall be available, as needed, to open and secure walk-in boxes for the other trades to perform their work related to these walk-in boxes, within the other trades' schedules as not to delay their work.
- D. Contractor will verify if the flooring is to be acid washed. In the event of this type of cleansing, any equipment constructed of stainless steel shall not be delivered until a minimum of 24 hours after the final cleansing is completed.

#### 1.16 WARRANTY

- A. Work shall be guaranteed against defects for one (1) year from the date of operation of the equipment. The Contractor will provide a written warranty of each component to include work in this Section to cover all testing and re-testing as may become necessary for one year past the Contract final acceptance date. Any equipment, system, or element failing to perform as directed in this Section shall be repaired or replaced at no cost to the Owner (including labor and transportation), excluding replacement cost of damaged components or work caused by misuse of the equipment.
- B. Additional Warranty: Refrigeration systems shall include a start-up and one-year service and maintenance contract in addition to the regular one-year warranty as stated above, plus an additional four-year warranty on sealed portions of condensing units, including refrigerant lost. This shall include all refrigerators, ice cream makers and cabinets, ice makers, freezers, dispensers, walk-in coolers/freezers compressors, and/or any other items with refrigeration system(s).

# PART 2 - PRODUCTS

#### 2.1 EQUIPMENT

A. Equipment schedule: Refer to schedule on Food service Drawings and Part 5 Itemized Specifications for equipment included in this Section.

### 2.2 MATERIALS

#### A. Metals

- 1. Stainless Steel: AISI Type 302/304, hardest workable temper, and No.4 directional polish. Standard gauges are noted in these specifications under Heading 2.04; Section B.1.
- 2. Galvanized Steel Sheet: ASTM A526, except ASTM A527 for extensive forming; ASTM A525, G90 zinc coating, chemical treatment.

Note: Where painted finish is indicated, provide mill phosphatized treatment in lieu of chemical treatment.

- 3. Steel Sheet: ASTM A569 hot-rolled carbon steel.
- 4. Galvanized Steel Pipe: ASTM A53 or ASTM A120, welded or seamless, schedule 40, galvanized.
- 5. Steel Structural Members: Hot rolled or cold formed, carbon steel unless stainless steel is indicated.

Note: Galvanized Finish (G.I.): ASTM A123 hot-dipped zinc coating, applied after fabrication.

- 6. Aluminum: ASTM B209B221 sheet, plate and extrusions (as indicated), alloy, temper and finish as determined by manufacture / fabricator, except 0.40-mil natural anodized finish on exposed work unless another finish is indicated.
- B. Plastic Laminate: NEMA LD3, Type 2, 0.050" thick, except Type 3, 0.042" for post-forming smooth (non-textured). Color and texture as selected by the Architect/Interior Designer.
  - 1. Comply with NSF Standard No. 35.
  - 2. Veneered with approved waterproof and heat proof cement. Rubber base adhesives are not acceptable.
  - 3. Applied directly over close grained plywood, such as solid Mahogany or solid Birch, of selected, smooth, sanded stock to ensure a smooth ripple-free laminated surface; or commercial grade furniture particle board, Cortron or equal.
  - 4. If specified plywood or particle board is unavailable, submit specifications and sample of alternate material for approval. If specified for a "wet" area, only marine grade wood products will be approved for these areas.
  - 5. Exposed faces and edges shall be faced with 1/16 inch (1.6mm) thick material. Cover corresponding backs with approved backing and balancing sheet material. No unfinished exposed plywood/particle board will be acceptable.

- C. Hardwood Work Surfaces: Laminated edge grained hard maple (Acer saccharum), NHLA First Grade with knots, holes and other blemishes culled out, kiln dried at 8 percent or less moisture, waterproof glue, machined, sanded, and finished with NSF approved oil-sealer.
- D. Solid Surface Material (SSM): Unless otherwise specified, provide 1/2" thick 100% homogeneous filled acrylic material meeting ANSI Z124.6 Type 6, as manufactured by DuPont Company and known as Corian. Color(s) and pattern(s) as selected by the Architect/ Interior Designer.
  - 1. Comply with NSF Standard No. 51.
  - 2. Acrylic adhesive shall be used for all joints.
  - 3. Install directly over 3/4" thick (minimum) substrate of close grained plywood, such as solid Mahogany or solid Birch, of selected, smooth, sanded stock to ensure a smooth ripple-free surface or a commercial grade furniture particle board, Cortron or equal. Provide additional bracing and support as required by the SSM manufacturer.
  - 4. Fabrication shall be by a fabricator trained by DuPont factory authorized training personnel and Certified as a Commercial Corian Fabricator.
  - 5. Installation shall be by an installer trained by DuPont factory authorized training personnel and Certified as a Commercial Corian Installer.
  - 6. All fabrication and installation of Corian and all components attached to or installed in or through Corian shall be in compliance with manufacturer's instructions and the DuPont Corian Food Service Guidelines and Design Manual. Of particular concern are the sections, details, and instructions on the installation of drop-in or built-in hot or cold components.
  - 7. All other Solid Surface Material (SSM), which may be specified by others to be used in food service areas, must comply with NSF certification and ANSI Standard No. 51.
- E. Insulation
  - 1. For low temperature applications, such as ice bins, cold pans, or fabricated under counter freezers, use urethane, rigid board foam or foamed-in-place, not less than 2 inches (50mm) thick, except that vertical surfaces of cold pans and ice bins may be 1 inch (25mm) thick. Insulation shall be bonded at joints to prevent condensation on exterior.
  - 2. For refrigerated applications, such as fabricated undercounter refrigerators, use urethane rigid board foam or foamed-in-place, or Styrofoam rigid board foam 2 inches (50mm) thick, bonded at joints.
  - 3. For heated type applications, such as plate warmers, use block type rock wool, minimum 1 inch (25mm) thick.
  - 4. At counter tops, subject to heat from cooking equipment and refrigeration compressors, use 1 inch (25mm) thick B&Z Products (1-800-999-0890) Marinite I, or equal, to insulate underside of top.
  - 5. Marinite material shall be added between freezer or refrigerator and 14 gauge (2.0) stainless steel top.
  - 6. All insulation shall be fully encased or enclosed.

### F. Joint Materials

- 1. Sealants: 1-part or 2-part, polyurethane or silicone based, liquid elastomeric sealant, nonsolvent release type, Shore A hardness of 30, except 45 if subject to traffic. Sealants shall be NSF Listed for use in food zones. Installation shall comply with applicable requirements of NSF Standards.
- 2. Backer Rod: 3/8 inch or larger joints shall be polyurethane rod stock, larger than joint width.
- 3. Gaskets: Solid or hollow (but not cellular) neoprene or polyvinyl chloride, light grey, minimum of 40 Shore A hardness, self-adhesive or prepared for either adhesive application or mechanical anchorage.
- G. Paint and Coatings
  - 1. Provide the types of painting and coating materials which, after drying or curing, are suitable for use in conjunction with food service, durable, non-toxic, non-dusting, non-flaking, mildew resistant, and comply with governing regulations for food service.
  - 2. Galvanize Repair Paint: MIL-P-21035.
  - 3. Sound Deadener: NSF listed sound deaden material such as latex sound deadener for internal surfaces of metal work and underside of metal counters and tables between work top and underbracing.
  - 4. Pretreatment: SSPC-PT2 or PT3, of FS TT-C490.
  - 5. Primer Coating for Metal: FS TT-P-86, type suitable for baking, where indicated.
  - 6. Enamel for Metal: Synthetic type, FA TT-P-491, type suitable for baking, where indicated.

## 2.3 FABRICATED PRODUCTS

## A. Hardware

- 1. General: Manufacturer's standard, but not less than ANSI 156.9 Type 2 (Institutional), satin finish stainless steel or dull chrome finish on brass, bronze, or steel.
- 2. Hinged Door Hardware: Hinged doors shall be mounted with heavy duty NSF approved hinges with Component Hardware Group, Model No. P62-1010 pulls, or equal. Catches shall be heavy-duty magnetic type, except as otherwise indicated.
- 3. Drawer Hardware: Slides to be 200 pounds minimum capacity per pair, 300 series stainless steel, full extension, side-mounting, self-closing type, with stainless steel ball bearings and positive stops, Component Hardware Group Series S52, or equal. Pulls shall be Component Hardware Group, Model No. P62-1 012, or equal.
- 4. Sliding Door Hardware: Sliding doors shall be mounted on large, quiet ball bearing rollers in 14-gauge (2.0mm) stainless steel overhead tracks and be removable without the use of tools. Bottom of cabinet shall have stainless steel guide-pins and not channel tracks for doors.
- 5. All hardware shall be identified with manufacturer's name and number so that broken or worn parts may be replaced.

# B. Casters

- 1. Type and size as recommended by caster manufacturer, NSF approved for the type and weight of equipment supported, but not less than 5 inch (127mm) diameter heavy-duty, ball bearing, solid or disc wheel with non-marking grease proof rubber, neoprene or polyurethane tire, unless otherwise specified. Minimum width of tread shall be 1-3/16 inch (30mm). Minimum capacity per caster shall be 250 pound (113.4kg), unless otherwise noted in itemized specifications.
- 2. Provide solid material wheels with stainless steel rotating wheel guard.
- 3. To be sanitary, provide sealed wheel and swivel bearings and polished plated finish per NSF.
- 4. Unless otherwise indicated, equip each item with two (2) swivel-type casters and two (2) fixed casters. Provide foot brakes on two (2) casters on opposite front corners of equipment.
- 5. Unless equipment item is equipped with another form of all-around protective bumper, provide circular rotating bumper above each caster, 5 inch (127mm) diameter tire of light grey synthetic rubber (hollow or closed-cell) on cadmium-plated disc.
- C. Plumbing Fittings, Trim and Accessories
  - 1. General: Where exposed or semi-exposed, provide bright chrome plated brass or polished stainless steel units. Provide copper or brass where not exposed.
  - 2. Vacuum Breakers: Provide with food service equipment as listed in the itemized specifications.
  - 3. Water Outlets: At sinks and at other locations where water is supplied (by manual, automatic or remote control), furnish commercial quality faucets, valves, dispensers or fill devices of the type and size indicated and as required to operate as indicated.
  - 4. Waste Fittings: Except as otherwise indicated, furnish 2 inch (50mm) remote-lever waste valve and 3-1/2 inch (89mm) strainer basket.
- D. Electrical Materials
  - 1. General: Provide standard materials, devices and components as recommended by the manufacturer or fabricator, selected and installed in accordance with NEMA standards and recommendations and as required for safe and efficient use and operation of the food service equipment without objectionable noise, vibration and sanitation problems.
  - 2. Before ordering equipment, confirm pertinent electrical requirements with the serving electrical utility, such as actual voltages available, number of phases and number of wires in the system.
  - 3. Wire electrical work for fabricated equipment completely to a junction or pull box which is wholly accessible and mounted on the equipment. Wiring shall be labeled for outlet or item served. Verify local requirements for UL Listing on complete assembly and provide if required.
  - 4. Components shall bear the UL label or be approved by the prevailing authority.
  - 5. Provide Custom fabricated refrigerator units with vapor tight light receptacles, shatterproof lamps and automatic switches. Conceal wiring.

- 6. Controls and Signals: Provide recognized commercial grade signals, on-off push buttons or switches, and other speed and temperature controls as required for operation, complete with pilot lights and permanent signs and graphics to assist the user of each item. Provide stainless steel cover plates at control and signal electrical boxes. Locate controls and switches out of heat zones, in easily accessible locations that preclude accidental contact by employees.
- 7. Internal Wiring of Fixtures and Equipment
  - a. The Contractor shall be responsible for internal wiring of electrical devices built into or forming an integral part of fabricated equipment items. Wiring will be in metal conduit, connected to an accessible pull-box or j-box, and tagged for intended use. Refer to Section 26 Specifications for color coding of wiring.
  - b. Each standard item shipped in sections shall be properly connected internally and verified by the Contractor.
  - c. Furnish dish washers and conveyors internally wired to junction box or distribution panel as specified, including push button switches, motors, immersion heaters, solenoids, etc.
  - d. Where light fixtures are specified or detailed as part of counters, furnish and install cases or fixtures, light fixtures, lamps and shields. Provide warm white lamps unless otherwise specified. If fluorescent light fixtures are specified, provide ballasts and include shields. Provide shields for all light fixtures.
  - e. Wiring for built-in strip heaters or immersion-type elements shall be provided as follows:
    - 1) In heat zone: shall have UL approved insulation and be not less than 300volt rated heat resistant insulation with nickel wire.
    - 2) Connection wiring extended in raceway or conduit to junction or pull box shall be not less than 600 volt rated heat resistant insulation covered wire, UL approved, or equal.
  - f. Wiring for fabricated refrigerator and freezer cabinets shall be UL approved insulated cable from exterior junction box to internal components, within insulation unless code requires metallic conduit:
    - 1) Conduit shall be Electrical Metallic Tubing, rigid or flexible (Greenfield). For freezer applications, Seal-Tite Flex or approved equal shall be used.
    - 2) Internal wiring shall be UL approved rubber covered 600 volt rated conductor, except door heaters, which shall be Nichrome wire with silicone braided jacket, having resistance of 10.4 watts per lineal foot.
    - 3) Mount convenience outlets, lighting receptacles, (rubber or porcelain) and door switches in approved boxes. Convenience outlets for evaporators shall be twist lock type. Solid connections, as for freezer evaporators, shall be made vapor tight.
  - g. Exposed flexible steel conduit on kitchen equipment shall be neoprene jacketed Seal -Tite conduit equal to Anaconda type "UA". UL approved, complete with approved liquid tight connectors on each end, and designed to provide electrical grounding continuity.

- h. Exposed electrical conduit used in kitchen wet area applications, except for flexible connections, shall be rigid galvanized steel. Thin wall conduit (EMT) shall not be permitted for wet areas. Exposed outlet boxes shall be liquid tight type, with threaded hubs.
- 8. Convenience and Power Outlets
  - a. Make cutouts and install appropriate boxes or outlets in fabricated fixtures, complete with wiring, conduit, outlet and stainless steel cover plate.
  - b. Outlets and plugs shall conform to NEMA standards.
  - c. Electrical outlets and devices shall be first quality "Specification Grade".
  - d. Furnish GFCI outlets where adjacent to sink compartments, as per the National Electrical Code.
- 9. Plugs and Cords: Where cords and plugs are provided, they shall comply with National Electrical Manufacturer's Association (NEMA) requirements. Indicate NEMA configuration for each applicable item.
- 10. Heating Equipment
  - a. Install electric and heating equipment as to be readily cleanable or removable for cleaning.
  - b. Steam heated custom fabricated equipment shall be a self-contained assembly, complete with control valves located in an accessible position.
- 11. Motors: Totally enclosed type, except drip-proof type where not exposed to a dust or moisture condition; ball bearings, except sleeve bearings on small timing motors; windings impregnated to resist moisture; horse-power and duty-cycle ratings as required for the service indicated.
- 12. Power Characteristics: Refer to Division 26 specifications for project power characteristics. Also, refer to individual equipment requirements, for loads and ratings.

## 2.4 FABRICATION OF METAL WORK

- A. General Fabrication Requirements
  - 1. Remove burrs from sheared edges of metalwork, ease the corners and smooth to eliminate cutting hazard. Bend sheets of metal at not less than the minimum radius required to avoid grain separation in the metal. Maintain flat, smooth surfaces without damage to finish.
  - 2. Reinforce metal at locations of hardware, anchorages, and accessory attachments wherever metal is less than 14 gauge (2.0mm) or requires mortised application. Conceal reinforcements to the greatest extent possible. Weld in place, on concealed faces.
  - 3. Exposed screws or bolt heads, rivets, and butt joints made by riveting straps under seams and then filled with solder will not be accepted. Where fasteners are permitted, provide Phillips head, flat or oval head machine screws. Cap threads with acorn nuts, unless fully concealed in inaccessible construction, and provide nuts and lock washers unless metal for tapping is at least 12 gauge (2.5mm). Match fastener head finish with finish of metal fastened.

- 4. Where components of fabricated metal work are indicated to be galvanized and involve welding or machining of metal heavier than 16 gauge (1.6mm), complete the fabrication and provide hot-dip galvanizing of each component, after fabrication, to the greatest extent possible (depending upon available dip-tank sizes). Comply with ASTM A123.
- 5. Welding and Soldering
  - Materials 18-gauge (1.27mm), or heavier, shall be welded. a.
  - Seams and joints shall be shop welded or soldered as the nature of the material b. may require.
  - Welds must be ground smooth and polished to match original finish. c.
  - Where galvanizing has been burned off, clean and touch up the weld with high d. grade aluminum paint.
- 6. Provide removable panels for access to mechanical and electrical service connections, which are concealed behind or within food service equipment, but only where access is not possible and not indicated through other work.
- 7. Closures: Where ends of fixtures, splash backs, shelves, etc., are open, fill by forming the metal or welding sections, if necessary, to close entire opening flush to walls or adjoining fixtures.
- 8. Rolled Edges: Rolled edges shall be as detailed, with corners bull nose, ground and polished.
- 9. Coved Corners: Stainless steel food service equipment shall have 1/2 inch (13mm) or larger radius coves in horizontal and vertical corners, and intersections, per NSF standards.
- B. Metal and Gauges
  - Except as otherwise indicated, fabricate exposed metalwork from stainless steel. 1. Fabricate the following components from the gauge of metal indicated and other components from not less than 20 gauge (0.8mm) metal:

18 gauge.

- Table and counter tops: 14 gauge. a.
- Sinks and drain boards: 14 gauge. b.
- 16 gauge. Shelves: c.
  - 18 gauge (double pan construction). d. Front drawer and door panels:
  - e. Single pan doors and drawer fronts: 16 gauge.
  - Enclosed base cabinets: f.
  - Enclosed wall cabinets: 18 gauge. g.
  - Exhaust hoods and ventilators: 18 gauge. h. 16 gauge.
  - Pan-type insets and trays: i.
  - Removable covers and panels: 18 gauge. j. 18 gauge.
  - Skirts and enclosure panels: k.
  - Closure and trim strips over 4" wide: 18 gauge. 1.
  - 12 gauge. Hardware reinforcement: m.
  - Gusset plates: 10 gauge. n.
  - Custom channel bases: 14 gauge. о.

# C. Work-Surface Fabrication

- 1. Fabricate metal work surfaces by forming and welding to provide seamless construction using welding rods matching sheet metal, grinding and polishing. Where necessary for disassembly, provide waterproof gasketed draw-type joints with concealed bolting.
- 2. Reinforce work surfaces 30 inches on center both ways with galvanized or stainless steel concealed structural members. Reinforce edges, which are not self-reinforced, by formed edges.
- D. Metal Top Construction
  - 1. Metal tops shall be one-piece welded construction, including field joints. Secure to a full perimeter galvanized steel channel frame cross-braced not farther than 2'-6" (760mm) on center. Fasten top with stud bolts or tack welds. If hat sections are used in lieu of channels, close ends.
  - 2. Use properly designed draw fastening, trim strip, or commercial joint material to suit requirement, only if specified.
- E. Structural Framing
  - 1. Except as otherwise indicated, provide framing of minimum 1 inch (25mm) pipe-size round pipe or tube members with mitered and welded joints and gusset plates ground smooth. Provide 14 gauge (2.0mm) stainless steel tube for exposed framing, and galvanized steel pipe for concealed framing.
  - 2. Where indicated, flange rear and end edges up to form splashes integrally with top, with vertical and horizontal corners coved of not less than 1/4 inch (6mm) radius, die formed. Turn back splashes 1 inch to wall across top and ends with rounded edge on break, unless otherwise specified.
  - 3. For die-crimped edges, use inverted "V" 1/2 inch (13mm) deep inside and 2 inch (38mm) deep on outside, unless otherwise shown. For straight down flanges, make 1- 3/4 inch (45mm) deep on outside. For bull nose edges, roll down 1-3/4 inch (45mm).
  - 4. Edges: die-formed, integral with top. For rounded corners, form to 1 inch radius, weld, and polish to original finish.
- F. Field Joints: For any field joint required because of size of fixture, use butt-joints, reinforce on underside with angles of same material, bolt together with non-corrosive bolts and nuts, field weld, grind and polish.
- G. Pipe Bases: Construct pipe bases of 1-5/8 inch (41mm) diameter 18 gauge (1.2mm) stainless steel tubing. Fit legs with polished stainless steel sanitary adjustable bullet feet to provide for adjustment of approximately 1-1/2 inch (38mm), without exposing threads. Space legs to provide ample support for tops, precluding any possibility of buckling or sagging and in no case more than 6'-0" centers.
- H. Legs and Cross-rails
  - 1. Equipment legs and cross rails shall be 1-5/8 inch (41mm), 16-gauge (1.59mm) stainless steel tubing.
  - 2. Welds at cross rails shall be continuous and ground smooth. Please note: tack welds are not acceptable.

- 3. Camber bottom of legs inward and fit with a stainless steel bullet-type foot with not less than 2 inch (50mm) adjustment. Flanged feet with bolt holes may be required dependent on design applications. Provide proper type feet in compliance with local codes. Use stainless steel in all applications.
- 4. Peg free standing legs to floor with 1/4 inch (6mm) stainless steel rod.
- 5. Components
  - a. Stainless Steel Gusset: Stainless steel exterior to fit 1-5/8 inch (41mm) tubing, with Allen screw for fastening and adjustment. Not less than 3 inches (76mm) diameter at top and 3-3/4 inch (95mm) long. Outer shell 16-gauge (1.6mm) stainless steel, reinforced with 12-gauge (2.5mm) mild steel insert welded interior shell, or approved equal.
  - b. Stainless Steel Low Counter Legs: Stainless steel exterior 5-3/4 inch (146mm) minimum, 7 inch (1.78mm) maximum length with stainless steel 3- 1/2 inch (89mm) square plate with four counter-sunk holes, welded to top for fastening.
  - c. Stainless Steel Adjustable Foot: Stainless steel 1-1/2 inch (38mm) diameter tapered at bottom to 1 inch (25mm) diameter, fitted with threaded cold rolled rod for minimum 1-1/2 inch (38mm) diameter x 3/4 inch (19mm) threaded bushing plug welded to legs, or approved equal. Push-in foot not acceptable.
- 6. Fasten legs to equipment with gussets, as follows:
  - a. Sinks: Reinforced with bushings and set screw.
  - b. Metal Top Tables and Dish Tables: Welded to galvanized steel channels, 14gauge (1.98mm) or heavier, anchored to top with screws through slotted holes.
  - c. Wood Top Tables: Welded to stainless steel channels, 14-gauge (1.98mm) or heavier, anchored to top with screws through slotted holes.

## I. Shelves

- 1. Construct solid shelves under pipe base tables of 16 gauge stainless steel, with 1-1/2 inch turned down and under edges on exposed sides, and 2 inch turn up against walls or equipment. Fully weld to pipe legs.
- 2. In fixtures with enclosed bases, turn up shelves on back and sides with 1/4 inch (6mm) (minimum) radius and feather slightly to ensure a tight fit to enclosure panels.
- J. Sinks
  - 1. Construct sinks of 14 gauge stainless steel with No.4 finish inside and outside.
  - 2. Form back, bottom and front of one piece, with ends and partitions welded into place. Partitions: double thickness, 1 inch minimum space between walls. Multiple compartments shall be continuous on the exterior, without applied facing strips or panels.
  - 3. Cove interior vertical and horizontal corners of each tub not less than 1/4 inch radius, die formed. Outer ends of drain boards to have roll rim risers not less than 3 inches high.
  - 4. Drill faucet holes in splashes 2-1/2 inches below top edge. Verify center spacing with faucet specified.
  - 5. Sink insets shall be deep drawn of 16-gauge (1.59mm), or heavier, polished stainless steel. Weld into sink drain boards with 1-1/2 inch x 1-1/2 inch x 14 gauge stainless steel angle brackets, securely welded to sinks and galvanized cross angles spot welded to underside of drain boards to form an integral part of the installation.

- 6. The bottom of each compartment shall be creased such as to ensure complete drainage to waste opening. Slope bottom of sink bowls toward outlet.
- K. Drains, Wastes and Faucets
  - 1. Furnish and install Chicago Faucets stainless steel rotary drain assembly with connected overflow assembly as specified see itemized 2.8. Waste connection shall have 2 inch (50mm) external thread size, with 1-1/2 inch (38mm) internal thread size.
  - 2. Rotary Handle: Of sufficient length to extend to front edge of sink. No riveting, screws or soldering permitted to fit drains to sinks, with all parts of drains easily removable for servicing and replacement. Rotary handle bracket to be provided as part of the sink fabrication.
  - 3. Water pans for steam tables shall be fitted with 1 inch (25mm) drains with chrome-plated brass stand pipes.
  - 4. All faucets furnished with equipment included in this Section shall be lead-free and comply with NSF Standard #61, Section #9, such as manufactured by Chicago Faucets. Where the itemized specifications list a faucet by manufacturer and model, the Contractor shall verify that the listed faucet complies with this requirement.
  - 5. If the listed faucet does not comply, the Contractor shall submit similar model which does comply from the same manufacturer where available or from one of the above manufacturers.
- L. Workmanship
  - 1. Best quality in the trade. Field verify dimensions before fabricating, conform all items to dimensions of building, neatly fit around pipes, offsets and other obstructions.
  - 2. Fabricate only in accordance with approved shop drawings, showing pipes, obstructions to be built around, and location of utilities and services.
- M. Enclosures
  - 1. Provide enclosures, including panels, housings, and skirts for service lines, operating components and mechanical and electrical devices associated with the food service equipment, except as specifically indicated to be "open".
  - 2. Where equipment is exposed to customer view, enclose of service lines, operating components, and mechanical and electrical devices.
- N. Casework
  - 1. Enclosure: except as otherwise indicated, provide each unit of casework (base, wall, overhead and free-standing) with a complete-enclosure metal cabinet, including fronts, backs, tops, bottoms, and sides.
  - 2. Bases shall be made of 18-gauge (1.27mm) stainless steel sheets reinforced by forming the metal.
  - 3. Ends, partitions and shelves are stainless steel.
  - 4. Unexposed backs and structural members are galvanized.
  - 5. Vertical ends and partitions are single wall, with a 2 inch (50mm) face.
  - 6. Sides and through partitions are flush with bottom rail, welded at intersections.

- 7. Shelves: Provide adjustable standards for positioning and support of shelves in casework, except bottom shelf of cabinet mounted on legs or as specified. Turn back of shelf units up 2 inches and hem. Turn other edges down to form open channel. Reinforce shelf units to support 40 pounds per square foot loading, plus 100 percent impact loading.
- 8. Bottom front rail of bases set on masonry platform shall be continuously closed and sealed to platform.
- O. Doors
  - 1. Metal doors shall be double-cased stainless steel. Outer pans shall be 18-gauge (1.27mm) stainless steel with corners welded, ground smooth and polished. Inner pan shall be 20-gauge (.95mm) stainless steel fitted tightly into outer pan with a sound-deadening material such as Celotex or Styrofoam used as a core. The two pans shall be tack welded together and joints solder filled. Doors shall finish approximately 3/4 inch (19mm) thick and be fitted with flush recessed type stainless steel door pulls.
  - 2. Wood doors shall be fabricated as detailed. If Formica or other plastic surfaces are used, sides and backs must be laminated.
  - 3. Hinged doors shall be mounted on heavy-duty NSF approved hinges, or as noted on plans or specifications.
- P. Drawer Assemblies
  - 1. Assemblies shall consist of removable drawer body mounted in a ball bearing slide assembly with fully enclosed housing.
  - 2. Slide assembly consists of one pair of 200 pound stainless steel roller bearing extension slides, with side and back enclosure panels, front spacer angle, two drawer carrier angles secured to slides and stainless steel front.
  - 3. Drawer bodies for general storage are to be 20 inches x 20 inches (508mm x 508mm), with 18 gauge stainless steel containers.
  - 4. Drawers intended to hold food products shall be removable type with 12 x 20 (305mm x 508mm) stainless steel food pans in a stainless steel assembly.
  - 5. Drawer fronts are double cased, 3/4 inch (19mm) thick with 18 gauge (1.27mm) stainless steel welded and polished front pan. Steel back pan is tightly fitted and tack welded. Sound deaden with rigid insulation material.
  - 6. Provide drawers with replaceable soft neoprene bumpers or for refrigerated drawers, a full perimeter soft gasket.
- Q. Closed Base: Where casework is indicated to be located on a raised-floor base, prepare casework for support without legs and for anchorage and sealant application, as required for a completely enclosed and concealed base.
- R. Support from Floor: Equip floor supported mobile units with casters and equip items indicated as roll-out units with manufacturer's standard one-directional rollers. Otherwise, and except for closed-base units, provide pipe or tube legs with adjustable bullet-design feet for floor supported items of fabricated metalwork. Provide 1-1/2 inch adjustment of feet (concealed threading).

## S. Shop Painting

- 1. Clean and prepare metal surfaces to be painted. Remove rust and dirt. Apply treatment to zinc coated surfaces which have not been mill phosphatized. Coat welded and abraded areas of zinc coated surfaces with galvanize repair paint.
- 2. Apply 1.5 mil (dry film thickness) metal primer coating, followed by 2, 1.0 mil (dry film thickness) metal enamel finish coatings.
- 3. Bake primer and finish coatings in accordance with paint manufacturer's instructions for a baked enamel finish.
- T. Sound Deadening
  - 1. Sound deaden underside of metal tops, drain boards, under shelves, cabinet interior shelves, etc., above the underbracing/reinforcing/framing only.

# 2.5 FILTER EXHAUST HOODS

- A. General
  - 1. 18 Gauge type 304 stainless steel external welded construction, in accordance with the latest edition of NFPA No.96, including all applicable appendices. Exposed welds to be ground and polished.
  - 2. Grease Removal: UL classified, non-adjustable, stainless steel grease filters with dripchannel gutters, drains and collection basins.
  - 3. Light Fixtures: Furnish type of fixture specified. Fixtures shall be UL listed for hoods, NSF approved, with sealed safety lenses and stainless steel exposed conduit for wiring.
  - 4. Exhaust Duct: Furnish welded stainless steel formed duct collars at ceiling or wall duct connections, where exposed. Furnish exposed to view ductwork as specified. Verify size and location of duct connections required in this contract, before fabrication. Other ductwork will be by the Mechanical Section.
  - 5. Fire Extinguishing System: Pre-piped liquid chemical or water fire suppressant system, as specified, complying with applicable local and NFPA regulations. Wet chemical fire suppression systems shall comply with UL 300 Standards.

## 2.6 REFRIGERATION EQUIPMENT

#### A. General

- 1. Furnish either single or multiple compressor units, as specified or recommended by the manufacturer for the sizes and variations between connected evaporator loads as indicated.
- 2. Furnish units of the capacities indicated, arranged to respond to multiple-evaporator thermostats and defrosting timers. Include coils, receivers, compressors, motors, motor starters, mounting bases, vibration isolation units, fans, dryers, valves, piping, insulation, gauges, winter control equipment and complete automatic control system.

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 3. Refrigerant: Pre-charge units with type or types recommended by manufacturer for services indicated, with quick-disconnect type connections where specified, ready to receive refrigerant piping runs to evaporators and (where remote) to condensers. All refrigerant and associated components shall comply with the requirements of the Montreal Protocol Agreement. No CFC refrigerants or associated components shall be allowed on this Project. HFC refrigerants and components shall be used where available. HCFC refrigerants and components, with a minimum 2010 phase-out date, and intermediate replacement refrigerants are to be used only when HFC refrigerants are not available. Contractor shall be responsible for coordinating with manufacturers. Provide refrigerant leak monitoring devices where required by federal, state, or local codes.
- 4. The minimum outdoor operating ambient temperature for design of units is -10 degrees Fahrenheit, or as applicable for extreme low local conditions. The maximum indoor design temperature for operation of compressor units is 95 degrees Fahrenheit. The maximum outdoor ambient design temperature shall be determined with prevailing conditions at mounting location(s) of compressor(s), such as sun exposure, limited ventilation, high fences/walls, roof color and materials, local climatic extremes, etc., but in no case shall it be less than 100 degrees Fahrenheit.
- B. Components
  - 1. Coils: Coils for fabricated refrigerators shall have vinyl plastic coatings, stainless steel housings and shall be installed in such a manner as to be replaceable.
  - 2. Expansion Valves: Remote refrigeration system shall be complete with thermostatic expansion valves at the evaporator.
  - 3. Thermometers
    - a. Fabricated refrigerated compartments to be fitted minimally with a flush dial thermometer, with chrome plated bezels and to be provided as specified.
    - b. Thermometers shall be adjustable and shall be calibrated after installation.
    - c. Thermometers shall have an accuracy of  $\pm 2$  degrees Fahrenheit (1 degree Centigrade).
  - 4. Hardware
    - a. Refrigerator hardware for fabricated refrigerator compartments shall be heavy-duty components.
    - b. Self-closing hinges.
    - c. Latches to be magnetic edge mount type, unless specified or detailed otherwise.
  - 5. Locks
    - a. Doors and drawers for walk-in coolers/freezers and reach-in refrigerated compartments, both fabricated and standard, shall be fitted with cylinder locking type latches and provided with master keys.
- C. Cold Pans: Ice pans, refrigerated pans and cabinets shall be provided with breaker strips, where adjoining top or cabinet face materials, to prevent transfer of cold.

- D. All open top mechanically cooled custom fabricated or standard buy-out refrigerators and/or cold pans shall comply with NSF Standard #7 requirements, as of April 1, 1998. The Contractor shall verify that the specified unit complies with this requirement or submit a similar model, which does comply, from the same manufacturer where available.
- E. Ventilation of Refrigerated Equipment
  - 1. Adequate ventilation shall be provided for custom fabricated equipment with integral refrigeration condensing units, both built-in and drop-in. If flow through ventilation cannot be provided, provide flow direction partitions and an additional fan capable of cooling the condensing unit.
  - 2. If, in the opinion of the Contractor, additional room ventilation is required to ensure correct operating temperatures of standard buy-out, custom fabricated or remote refrigeration condensing units, or compressor rack assemblies, they shall so state in a letter to the Architect for evaluation and direction.

# 2.7 MISCELLANEOUS MATERIALS

- A. Nameplates: Whenever possible, locate nameplates and labels on manufactured items, in accessible position, but not within customer's normal view. Do not apply name-plates or labels on custom fabricated work, except as required for compliance with governing regulations, insurance requirements, or operator performance.
- B. Manufactured Equipment Items: Furnish items as scheduled or herein specified. Verify dimensions, spaces, rough-in and service requirements, and electrical characteristics before ordering. Provide trim, accessories and miscellaneous items for complete installation.
- C. Insert Pans
  - 1. General: Provide cut-outs, openings, drawers, or equipment specified or detailed to hold stainless steel insert pans with a full complement of pans as follows:
    - a. One (1) stainless steel, 20-gauge (0.95mm) minimum, solid insert pan for each space, sized per plans, details, or specifications.
    - b. Where pan sizes are not indicated in plans, details, or specifications, provide one full-size pan for each opening.
    - c. Provide maximum depth pan to suit application and space.
  - 2. Provide 18-gauge (1.27mm) removable stainless steel adapter bars where applicable.
  - 3. Provide all cut-outs and openings or equipment specified or detailed to hold stainless steel insert pans with a hinged stainless steel removable night cover.
- D. Tray Slides: Before fabrication of counters with tray slides, verify:
  - 1. Size and shape of tray. Edge of tray shall not overhang outer support/slider by more than 2". If edge of tray exceeds this dimension, notify Architect, in writing, for evaluation and adjustment, if necessary.
  - 2. Configuration of corners, turns, and shape of tray slides for proper support and safe guidance of trays.

- 3. Tray slide capable of supporting 200 pounds per linear foot, live load.
- E. Self-leveling dispensers: Verify type and make of ware, dimensions and weight, request samples from Operator and submit to the dispenser manufacturer for proper sizing and calibration of dispensers.
- F. Carbon dioxide (co') equipment: Where equipment requires connection with compressed co' cylinder for operation, provide proper sized cylinder manifold and control system (integral with equipment) with proper connectors for Department of Transportation (DOT) approved type cylinders, complete with cylinder safety devices and supports.
- G. Reasonable quietness of operation of equipment is a requirement. The Kitchen Equipment Contractor will be required to replace or repair any equipment producing out-of-the-ordinary intolerable noise. This also includes providing and installing bumpers and gaskets for doors and drawers on fabricated and standard manufactured items and sound insulation where feasible.

### 2.8 ITEMIZED SPECIFICATIONS

A. Refer to the following pages for specific specification information on each item included in this Section.

ITEM 1 SLIM JIM WASTE RECEPTACLES: 5 REQUIRED

A.

- ITEM 2 UTILITY CART: 1 REQUIRED
  - A.
- ITEM 3 HAND WASHING SINKS: 2 REQUIRED

A.

ITEM 4 DISPOSERS: 7 REQUIRED

A.

ITEM 5 POT WASHING SINK TABLE WITH REMOVABLE SINK COVERS: 1 REQUIRED

A.
## ITEM 6 UNDERCOUNTER WAREWASHER: 1 REQUIRED

- A. Existing equipment. Relocate and re-install in location shown.
- ITEM 7 MOBILE POT AND PAN SHELVING: 1 REQUIRED
  - A.
- ITEM 8 CORNER/CHANNEL GUARDS: 1 LOT REQUIRED

A.

ITEM 9 REACH-IN REFRIGERATOR: 1 REQUIRED

А.

- ITEM 10 CLOTHES WASHER AND DRYER: 1
  - A. Owner furnished and installed.
- ITEM 11 DRY STORAGE SHELVING: 1 LOT REQUIRED
  - A. Existing equipment.
- ITEM 12 NOT USED

ITEM 13 NOT USED

ITEM 14 NOT USED

ITEM 15 CANOPY HOOD WITH FIRE PROTECTION SYSTEM: 1 REQUIRED

Α.

ITEM 16 STAINLESS STEEL WALL FLASHING: 1 LOT REQUIRED

A.

# ITEM 17 COMBI-OVEN STEAMER: 1 REQUIRED

A.

# ITEM 18 ADA PREP WORK TABLE: 1 REQUIRED

A.

- ITEM 19 NOT USED
- ITEM 20 MOBILE PROOFING CABINET: 1 REQUIRED
  - A.
- ITEM 21 CANOPY HOOD WITH FIRE PROTECTION SYSTEM: 1 REQUIRED
  - Α.
- ITEM 22 4-BURNER OPEN RANGES: 7 REQUIRED
  - A.
- ITEM 23 INDUCTION WOK: 1 REQUIRED
  - А.
- ITEM 24 TEACHERS MAPLE TOP WORK TABLE: 1 REQUIRED
  - A.
- ITEM 25 MOBILE INGREDIENT CARTS: 6 REQUIRED
  - A.

# ITEM 26 MOBILE TABLE: 1 REQUIRED

A.

# ITEM 27 MOBILE ISLAND WORK TABLES: 6 REQUIRED

A. Existing equipment.

- B. Modify existing leg sets and install all swivel caster sets; two with brakes.
- C. Relocate and reinstall in position shown.

ITEM 28 NOT USED

ITEM 29 REACH-IN FREEZER: 1 REQUIRED

A.

ITEM 30 STUDENT WORK STATION COUNTER: 1 REQUIRED

A.

ITEM 31 MICROWAVE OVENS: 6 REQUIRED

A. Existing equipment. Relocate and re-install in location shown.

ITEM 32 CANOPY HOOD WITH FIRE PROTECTION SYSTEM: 1 REQUIRED

A.

ITEM 33 CANOPY HOOD WITH FIRE PROTECTION SYSTEM: 1 REQUIRED

A.

ITEM 34 STUDENT WORK STATION COUNTER: 1 REQUIRED

A.

ITEM 35 CANOPY HOOD WITH FIRE PROTECTION SYSTEM: 1 REQUIRED

А.

ITEM 36 CANOPY HOOD WITH FIRE PROTECTION SYSTEM: 1 REQUIRED

A.

ITEM 37 MOBILE INGREDIENT BINS: 3 REQUIRED

A.

## PART 3 - EXECUTION

#### 3.1 SUPERVISION

A. A competent supervisor, representing the Contractor, shall be present at all times during progress of the Contractor's work.

#### 3.2 SITE EXAMINATION

- A. Verify site conditions under the provisions of the General Conditions, Supplementary Conditions and applicable provisions of Division 1 Sections. Notify the Architect, in writing, of unsatisfactory conditions for proper installation of food service equipment.
- B. Verify wall, column, door, window, and ceiling locations and dimensions. Fabrication and installation should not proceed until dimensions and conditions have been verified and coordinated with fabrication details.
- C. Verify that wall reinforcement or backing has been provided and is correct for wall supported equipment. Coordinate placement dimensions with wall construction Section.
- D. Verify that ventilation ducts are of the correct characteristics, and in the required locations.
- E. Verify that utilities are available, of the correct characteristics, and in the required locations.

## 3.3 INSTALLATION

- A. Sequence installation and erection to ensure correct mechanical and electrical utility connections are achieved.
- B. Install items in accordance with manufacturer's instructions.
- C. Set each item of non-mobile and non-portable equipment securely in place, leveled and adjusted to correct height. Anchor to supporting substrate where indicated, and where required for sustained operation and use without shifting or dislocation. Conceal anchorages wherever possible. Adjust counter tops and other work surfaces to a level tolerance of 1/16 inch (maximum offset, and plus or minus on dimension, and maximum variation in 2'-0" run from level or indicated slope). Provide anchors, supports, bracing, clips, attachments, etc., as required to comply with the local seismic restraint requirements. The Guidelines for Seismic Restraint of Kitchen Equipment, as prepared for the Sheet Metal Industry Fund of Los Angeles and endorsed by SMACNA, should be followed.
- D. Complete field assembly joints in the work (joints which cannot be completed in the shop) by welding, bolting-and-gasketing, or similar methods as indicated and specified. Grind welds smooth and restore finish. Set or trim flush, except for "T" gaskets as indicated.
- E. Provide closure plates and strips where required, with joints coordinated with units of equipment.

- F. Provide sealants and gaskets all around each unit to make joints airtight, waterproof, verminproof, and sanitary for cleaning purposes.
- G. Joints up to 3/8 inch wide will be stuffed with backer rod to shape sealant bead properly, at 1/4 inch depth.
- H. At internal corner joints, apply sealant or gaskets to form a sanitary cove of not less than 3/8 inch radius.
- I. Shape exposed surfaces of sealant slightly concave with edges flush with faces of materials at joint.
- J. Provide sealant filled or gasketed joints up to 3/8 inch joint width. Wider than 3/8 inch, provide matching metal closure strips, with sealant application each side of strips. Anchor gaskets mechanically or with adhesives to prevent displacement.
- K. Treat enclosed spaces, inaccessible after equipment installation, by covering horizontal surfaces with powdered borax at a rate of 4 ounces per square foot.
- L. Insulate to prevent electrolysis between dissimilar metals.
- M. Cut and drill components for service outlets, fixtures, piping, conduit, and fittings.
- N. Coordinate the installation of approved dry pendant sprinkler head in each cooler and freezer. Sprinkler heads should be installed in coolers/freezers only if required by local codes.
- O. Verify and coordinate the mounting heights of all wall shelves and equipment, with equipment located below them for proper clearances.
- P. Coordinate with the Plumbing and Electrical Divisions and provide holes in food service equipment for plumbing and electrical service to and through the fixtures, as required. This includes welded sleeves, collars, ferrules, or escutcheons. Locate these services so that they do not interfere with intended use and/or servicing of the fixture. No alterations of the building are allowed without written permission by the General Contractor and/or Architect. (i.e. routing refrigerant lines).

# 3.4 ADJUSTING

- A. Test and adjust equipment, controls and safety devices to ensure proper working order and conditions.
- B. Repair or replace equipment, which is found to be defective in its operation, including units which are below capacity or operating with excessive noise or vibration.

# 3.5 CLEANING AND RESTORING FINISHES

A. After completion of installation and completion of other major work in food service areas, remove protective coverings and clean food service equipment internally and externally.

- B. Restore exposed and semi-exposed finishes, to remove abrasions and other damages, polish exposed metal surfaces and touch-up painted surfaces. Replace work, which cannot be successfully restored.
- C. Polish glass, plastic, hardware and accessories, fixtures and fittings.
- D. Wash and clean equipment and leave in a condition ready for the Owner to sanitize and use.

## 3.6 TESTING, START-UP AND INSTRUCTIONS

- A. Delay the start-up of equipment until service lines have been tested, balanced, and adjusted for pressure, voltage and similar considerations and until water and steam lines have been cleaned and treated for sanitation.
- B. Make arrangements for demonstration of food service equipment operation and maintenance in advance with the Owner/Operator.
- C. Demonstrate food service equipment to familiarize the Owner and the Operator on operation and maintenance procedures, including periodic preventative maintenance measures required. Include an explanation of service requirements and simple on-site service procedures as well as information concerning the name, address and telephone number of qualified local source of service. The individual performing the demonstration shall be knowledgeable of operating and service aspects of the equipment.
- D. Provide a written report of the demonstration to the Owner, outlining the equipment demonstrated and malfunctions or deficiencies noted. Indicate individuals present at demonstration.
- E. Final Cleaning: After testing and start-up, clean the food service equipment and leave in a condition ready for the Owner to sanitize and use.

#### 3.7 CLEAR AWAY

A. Throughout the progress of their work, the Contractor shall keep the working area free from debris and shall remove rubbish from premises resulting from work being done by them. At the completion of their work, the Contractor shall leave the premises in a clean and finished condition.

END OF SECTION 114000

# SECTION 115200 - AUDIO VISUAL EQUIPMENT

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Manual and electrically operated, front-projection screens and controls.
  - 2. Projector support mounts.
- B. Related Requirements:
  - 1. Section 270528 "Pathways for Communications Systems" for other projection screens and projection equipment.

## 1.3 DEFINITIONS

- A. Gain: Ratio of light reflected from screen material to that reflected perpendicularly from a magnesium carbonate surface as determined per SMPTE RP 94.
- B. Half-Gain Angle: The angle, measured from the axis of the screen surface to the most central position on a perpendicular plane through the horizontal centerline of the screen where the gain is half of the peak gain.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Show layouts and types of front-projection screens. Include the following:
  - 1. Drop lengths.
  - 2. Location of seams in viewing surfaces.
  - 3. Location of screen centerline relative to ends of screen case.
  - 4. Anchorage details, including connection to supporting structure for suspended units.
  - 5. Details of juncture of exposed surfaces with adjacent finishes.
  - 6. Location of wiring connections for electrically operated units.
  - 7. Wiring diagrams for electrically operated units.
  - 8. Accessories.

#### AUDIO VISUAL EQUIPMENT

115200 - 1

C. Samples for Initial Selection: For finishes of surface-mounted screen cases.

## 1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For front-projection screens to include in maintenance manuals.

#### 1.6 DELIVERY, STORAGE, AND HANDLING

A. Environmental Limitations: Do not deliver or install front-projection screens until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

#### 1.7 COORDINATION

A. Coordinate layout and installation of front-projection screens with adjacent construction, including ceiling suspension systems, light fixtures, HVAC equipment, and partitions.

# PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

A. Source Limitations for Projection Screens: Obtain front-projection screens from single manufacturer. Obtain accessories, including necessary mounting hardware, from screen manufacturer.

#### 2.2 MANUALLY OPERATED, FRONT-PROJECTION SCREENS

- A. General: Manufacturer's standard units consisting of case, screen, mounting accessories, and other components necessary for a complete installation. Provide units that are listed and labeled as an assembly by UL or another testing and inspecting agency acceptable to authorities having jurisdiction.
- B. Mounting: surface-mounted on wall.
- C. Size: As indicated on drawings.
- D. Basis-of Design Product: Da-Lite Model C, with CSR (controlled screen return), Projection Screen.
  - 1. Other Manufacturers: Subject to compliance with requirements, products by one of the following will also be acceptable:

## AUDIO VISUAL EQUIPMENT

- a. Draper.
- b. Stewart Filmscreen Corporation.

## 2.3 FRONT-PROJECTION SCREEN MATERIAL

- A. Matte Reflective Viewing Surface: Peak gain of not less than 1.3, and half-gain angle of at least 40 degrees from the axis of the screen surface.
- B. Material: vinyl sheet.
- C. Mildew-Resistance Rating: Zero or 1 when tested according to ASTM G 21.
- D. Flame Resistance: Passes NFPA 701.
- E. Flame-Spread Index: Not greater than 75 when tested according to ASTM E 84.
- F. Seamless Construction: Provide screens, in sizes indicated, without seams.
- G. Edge Treatment: Black masking borders.
- H. Size of Viewing Surface: As indicated on drawings.

#### 2.4 CEILING MOUNTED PROJECTOR MOUNT

A. TBD

#### 2.5 CEILING MOUNTED PROJECTOR

A. Owner Furnished, Contractor Installed. Basis of Design is TBD (talk to Eddie re: ACMA in Library.)

## PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Install front-projection screens at locations indicated to comply with screen manufacturer's written instructions.
- B. Install front-projection screens with screen cases in position and in relation to adjoining construction indicated. Securely anchor to supporting substrate in a manner that produces a smoothly operating screen with vertical edges plumb and viewing surface flat when screen is lowered.
  - 1. Test manually operated units to verify that screen-operating components are in optimum functioning condition.

AUDIO VISUAL EQUIPMENT

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

END OF SECTION 115200

# SECTION 122413 - ROLLER WINDOW SHADES

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Manually operated roller shades with single rollers (RS-1).

## 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, features, finishes, and operating instructions for roller shades.
- B. Shop Drawings: Show fabrication and installation details for roller shades, including shadeband materials, their orientation to rollers, and their seam and batten locations.
- C. Samples for Initial Selection: For each type and color of shadeband material.
  - 1. Include Samples of accessories involving color selection.
- D. Samples for Verification: For each type of roller shade.
  - 1. Shadeband Material: Not less than 10 inches (250 mm) square. Mark interior face of material if applicable.
  - 2. Roller Shade: Full-size operating unit, not less than 16 inches (400 mm) wide by 36 inches (900 mm) long for each type of roller shade indicated.
  - 3. Installation Accessories: Full-size unit, not less than 10 inches (250 mm) long.
- E. Product Schedule: For roller shades. Use same designations indicated on Drawings.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Certificates: For each type of shadeband material.

C. Product Test Reports: For each type of shadeband material, for tests performed by manufacturer and witnessed by a qualified testing agency.

# 1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For roller shades to include in maintenance manuals.

## 1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Roller Shades: Full-size units equal to 5 percent of quantity installed for each size, color, and shadeband material indicated, but no fewer than two units.

## 1.7 QUALITY ASSURANCE

A. Installer Qualifications: Fabricator of products.

# 1.8 DELIVERY, STORAGE, AND HANDLING

A. Deliver roller shades in factory packages, marked with manufacturer, product name, and location of installation using same designations indicated on Drawings.

#### 1.9 FIELD CONDITIONS

- A. Environmental Limitations: Do not install roller shades until construction and finish work in spaces, including painting, is complete and dry and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.
- B. Field Measurements: Where roller shades are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Allow clearances for operating hardware of operable glazed units through entire operating range. Notify Architect of installation conditions that vary from Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

# PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

A. Source Limitations: Obtain roller shades from single source from single manufacturer.

## 2.2 MANUALLY OPERATED SHADES WITH SINGLE ROLLERS (RS-1)

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Mecho/5 System as manufactured by MechoShade Systems, Inc., EuroTwill or comparable product by one of the following:
  - 1. Draper Inc.
  - 2. Hunter Douglas Contract.
- B. Chain-and-Clutch Operating Mechanisms: With continuous-loop bead chain and clutch that stops shade movement when bead chain is released; permanently adjusted and lubricated.
  - 1. Bead Chains: Stainless steel.
    - a. Loop Length: Full length of roller shade.
    - b. Limit Stops: Provide upper and lower ball stops.
    - c. Chain-Retainer Type: Chain tensioner, sill mounted.
  - 2. Spring Lift-Assist Mechanisms: Manufacturer's standard for balancing roller shade weight and for lifting heavy roller shades.
    - a. Provide for shadebands that weigh more than 10 lb (4.5 kg) or for shades as recommended by manufacturer, whichever criterion is more stringent.
- C. Rollers: Corrosion-resistant steel or extruded-aluminum tubes of diameters and wall thicknesses required to accommodate operating mechanisms and weights and widths of shadebands indicated without deflection. Provide with permanently lubricated drive-end assemblies and idle-end assemblies designed to facilitate removal of shadebands for service.
  - 1. Roller Drive-End Location: Right or left side of interior face of shade as required for access.
  - 2. Direction of Shadeband Roll: Regular, from back (exterior face) of roller.
  - 3. Shadeband-to-Roller Attachment: Removable spline fitting into integral channel in tube.
- D. Mounting Hardware: Brackets or endcaps, corrosion resistant and compatible with roller assembly, operating mechanism, installation accessories, and mounting location and conditions indicated. Window Jamb Mounting.
- E. Roller-Coupling Assemblies: Coordinated with operating mechanism and designed to join up to three inline rollers into a multiband shade that is operated by one roller drive-end assembly.
- F. Shadebands:
  - 1. Shadeband Material:
    - a. Light-filtering fabric at exterior windows; 3 percent openness.
  - 2. Shadeband Bottom (Hem) Bar: Steel or extruded aluminum.
  - 3. Color and Finish: As indicated in Color and Materials Schedule in drawings or if not indicated, as selected by Architect from full range of industry colors.

## G. Accessories:

- 1. Fascia: Removable extruded aluminum fascia, size as required to conceal shade mounting, attachable to brackets without exposed fasteners.
  - a. Finish: Baked enamel. Color: White.

## 2.3 SHADEBAND MATERIALS

- A. Shadeband Material Flame-Resistance Rating: Comply with NFPA 701. Testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
- B. Light-Filtering Fabric: Woven fabric, stain and fade resistant.
  - 1. Source: Roller shade manufacturer.
  - 2. Type: Vinyl coated polyester.
  - 3. Orientation on Shadeband: Up the bolt.
  - 4. Openness Factor: 3 percent.
  - 5. Color:

## 2.4 ROLLER SHADE FABRICATION

- A. Product Safety Standard: Fabricate roller shades to comply with WCMA A 100.1, including requirements for flexible, chain-loop devices; lead content of components; and warning labels.
- B. Unit Sizes: Fabricate units in sizes to fill window and other openings as follows, measured at 74 deg F (23 deg C):
  - 1. Outside of Jamb Installation: Width and length as indicated, with terminations between shades of end-to-end installations at centerlines of mullion or other defined vertical separations between openings.
- C. Shadeband Fabrication: Fabricate shadebands without battens or seams to extent possible, except as follows:
  - 1. Vertical Shades: Where width-to-length ratio of shadeband is equal to or greater than 1:4, provide battens and seams at uniform spacings along shadeband length to ensure shadeband tracking and alignment through its full range of movement without distortion of the material.

## PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, operational clearances, locations of connections to building electrical system, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 ROLLER SHADE INSTALLATION

- A. Install roller shades level, plumb, and aligned with adjacent units according to manufacturer's written instructions.
- B. Roller Shade Locations: At exterior windows.
- C. Mount to window header per manufacturer's typical details. Align to top of mullion UNO.

## 3.3 ADJUSTING

A. Adjust and balance roller shades to operate smoothly, easily, safely, and free from binding or malfunction throughout entire operational range.

#### 3.4 CLEANING AND PROTECTION

- A. Clean roller shade surfaces, after installation, according to manufacturer's written instructions.
- B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that roller shades are without damage or deterioration at time of Substantial Completion.
- C. Replace damaged roller shades that cannot be repaired, in a manner approved by Architect, before time of Substantial Completion.

#### 3.5 ROLLER SHADE SCHEDULE

- 1. RS-1: Manual operation, single-roller shades with light-filtering shade fabric.
  - a. Application: All exterior windows.

## END OF SECTION 122413

# SECTION 210523 - GENERAL-DUTY VALVES FOR FIRE PROTECTION PIPING

PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Bronze butterfly valves with indicators.
  - 2. Iron butterfly valves with indicators.
  - 3. Check valves.
  - 4. NRS gate valves.
  - 5. Indicator posts.
  - 6. Trim and drain valves.

# 1.3 DEFINITIONS

- A. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.
- B. NRS: Nonrising stem.
- C. OS&Y: Outside screw and yoke.
- D. SBR: Styrene-butadiene rubber.

#### 1.4 ACTION SUBMITTALS

A. Product Data: For each type of valve.

# 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
  - 1. Protect internal parts against rust and corrosion.
  - 2. Protect threads, flange faces, and weld ends.
  - 3. Set valves open to minimize exposure of functional surfaces.

#### GENERAL-DUTY VALVES FOR FIRE PROTECTION PIPING

- B. Use the following precautions during storage:
  - 1. Maintain valve end protection.
  - 2. Store valves indoors and maintain at higher than ambient dew point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use operating handles or stems as lifting or rigging points.
- D. Protect flanges and specialties from moisture and dirt.

# PART 2 - PRODUCTS

## 2.1 GENERAL REQUIREMENTS FOR VALVES

- A. UL Listed: Valves shall be listed in UL's "Online Certifications Directory" under the headings listed below and shall bear UL mark:
  - 1. Main Level: HAMV Fire Main Equipment.
    - a. Level 1: HCBZ Indicator Posts, Gate Valve.
    - b. Level 1: HLOT Valves.
      - 1) Level 3: HLUG Ball Valves, System Control.
      - 2) Level 3: HLXS Butterfly Valves.
      - 3) Level 3: HMER Check Valves.
      - 4) Level 3: HMRZ Gate Valves.
  - 2. Main Level: VDGT Sprinkler System & Water Spray System Devices.
    - a. Level 1: VQGU Valves, Trim and Drain.
- B. FM Global Approved: Valves shall be listed in its "Approval Guide," under the headings listed below:
  - 1. Automated Sprinkler Systems:
    - a. Indicator posts.
    - b. Valves.
      - 1) Gate valves.
      - 2) Check valves.
        - a) Single check valves.
      - 3) Miscellaneous valves.
- C. Source Limitations for Valves: Obtain valves for each valve type from single manufacturer.

#### GENERAL-DUTY VALVES FOR FIRE PROTECTION PIPING

210523 - 2

## D. ASME Compliance:

- 1. ASME B16.1 for flanges on iron valves.
- 2. ASME B1.20.1 for threads for threaded-end valves.
- 3. ASME B31.9 for building services piping valves.
- E. AWWA Compliance: Comply with AWWA C606 for grooved-end connections.
- F. NFPA Compliance: Comply with NFPA 24 for valves.
- G. Valve Pressure Ratings: Not less than the minimum pressure rating indicated or higher as required by system pressures.
- H. Valve Sizes: Same as upstream piping unless otherwise indicated.
- I. Valve Actuator Types:
  - 1. Worm-gear actuator with handwheel for quarter-turn valves, except for trim and drain valves.
  - 2. Handwheel: For other than quarter-turn trim and drain valves.
  - 3. Handlever: For quarter-turn trim and drain valves NPS 2 and smaller.

## 2.2 TWO-PIECE BALL VALVES WITH INDICATORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. NIBCO INC.
  - 2. Victaulic Company.
- B. Description:
  - 1. UL 1091, except with ball instead of disc and FM Global standard for indicating valves (butterfly or ball type), Class Number 1112.
  - 2. Minimum Pressure Rating: 175 psig.
  - 3. Body Design: Two piece.
  - 4. Body Material: Forged brass or bronze.
  - 5. Port Size: Full or standard.
  - 6. Seats: PTFE.
  - 7. Stem: Bronze or stainless steel.
  - 8. Ball: Chrome-plated brass.
  - 9. Actuator: Worm gear or traveling nut.
  - 10. Supervisory Switch: Internal or external.
  - 11. End Connections for Valves NPS 1 through NPS 2: Threaded ends.
  - 12. End Connections for Valves NPS 2-1/2: Grooved ends.

#### GENERAL-DUTY VALVES FOR FIRE PROTECTION PIPING

# 2.3 BRONZE BUTTERFLY VALVES WITH INDICATORS

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:
  - 1. Globe Fire Sprinkler Corporation.
  - 2. Milwaukee Valve Company.
- B. Description:
  - 1. Standard: UL 1091 and FM Global standard for indicating valves, (butterfly or ball type), Class Number 1112.
  - 2. Minimum: Pressure rating: 175 psig.
  - 3. Body Material: Bronze.
  - 4. Seat Material: EPDM.
  - 5. Stem Material: Bronze or stainless steel.
  - 6. Disc: Bronze.
  - 7. Actuator: Worm gear or traveling nut.
  - 8. Ends Connections for Valves NPS 1 through NPS 2: Threaded ends.
  - 9. Ends Connections for Valves NPS 2-1/2: Grooved ends.

## 2.4 CHECK VALVES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Globe Fire Sprinkler Corporation.
  - 2. Kennedy Valve Company; a division of McWane, Inc.
  - 3. Matco-Norca.
  - 4. Mueller Co.
  - 5. NIBCO INC.
  - 6. Reliable Automatic Sprinkler Co., Inc. (The).
  - 7. Tyco Fire Products LP.
  - 8. United Brass Works, Inc.
  - 9. Venus Fire Protection Ltd.
  - 10. Victaulic Company.
  - 11. WATTS.

#### B. Description:

- 1. Standard: UL 312 and FM Global standard for swing check valves, Class Number 1210.
- 2. Minimum Pressure Rating: 175 psig.
- 3. Type: Single swing check.
- 4. Body Material: Cast iron, ductile iron, or bronze.
- 5. Clapper: Bronze, ductile iron, or stainless steel.
- 6. Clapper Seat: Brass, bronze, or stainless steel.
- 7. Hinge Shaft: Bronze or stainless steel.
- 8. Hinge Spring: Stainless steel.
- 9. End Connections: Flanged, grooved, or threaded.

#### GENERAL-DUTY VALVES FOR FIRE PROTECTION PIPING

210523 - 4

## 2.5 TRIM AND DRAIN VALVES

- A. Ball Valves:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:
    - a. Apollo Flow Controls; Conbraco Industries, Inc.
  - 2. Description:
    - a. Pressure Rating: 175 psig.
    - b. Body Design: Two piece.
    - c. Body Material: Forged brass or bronze.
    - d. Port size: Full or standard.
    - e. Seats: PTFE.
    - f. Stem: Bronze or stainless steel.
    - g. Ball: Chrome-plated brass.
    - h. Actuator: Handlever.
    - i. End Connections for Valves NPS 1 through NPS 2-1/2: Threaded ends.
    - j. End Connections for Valves NPS 1-1/4 and NPS 2-1/2: Grooved ends.

## PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- E. Do not attempt to repair defective valves; replace with new valves.

# 3.2 GENERAL REQUIREMENTS FOR VALVE INSTALLATION

A. Comply with requirements in the following Sections for specific valve installation requirements and applications:

GENERAL-DUTY VALVES FOR FIRE PROTECTION PIPING

- 1. Section 211313 "Wet-Pipe Sprinkler Systems" for application of valves in wet-pipe, firesuppression sprinkler systems.
- B. Install listed fire-protection shutoff valves supervised-open, located to control sources of water supply except from fire-department connections. Install permanent identification signs indicating portion of system controlled by each valve.
- C. Install check valve in each water-supply connection. Install backflow preventers instead of check valves in potable-water-supply sources.
- D. Install valves having threaded connections with unions at each piece of equipment arranged to allow easy access, service, maintenance, and equipment removal without system shutdown. Provide separate support where necessary.
- E. Install valves in horizontal piping with stem at or above the pipe center.
- F. Install valves in position to allow full stem movement.
- G. Install valve tags. Comply with requirements in Section 210553 "Identification for Fire-Suppression Piping and Equipment" for valve tags and schedules and signs on surfaces concealing valves; and the NFPA standard applying to the piping system in which valves are installed. Install permanent identification signs indicating the portion of system controlled by each valve.
- H. Install listed fire-protection shutoff valves supervised-open, located to control sources of water supply except from fire-department connections.
- I. Install check valve in each water-supply connection. Install backflow preventers instead of check valves in potable-water-supply sources.

END OF SECTION 210523

# SECTION 210529 - HANGERS AND SUPPORTS FOR FIRE SUPRESSION PIPING AND EQUIPMENT

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Metal pipe hangers and supports.
  - 2. Trapeze pipe hangers.
  - 3. Metal framing systems.
  - 4. Thermal hanger-shield inserts.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Signed and sealed by a qualified professional engineer. Show fabrication and installation details and include calculations for the following:
  - 1. Trapeze pipe hangers.
  - 2. Metal framing systems.
  - 3. Equipment supports.
- C. Delegated-Design Submittal: For trapeze hangers indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
  - 1. Detail fabrication and assembly of trapeze hangers.
  - 2. Include design calculations for designing trapeze hangers.

## 1.4 INFORMATIONAL SUBMITTALS

A. Welding certificates.

# 1.5 QUALITY ASSURANCE

- A. Structural-Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.
- B. Pipe Welding Qualifications: Qualify procedures and operators according to 2015 ASME Boiler and Pressure Vessel Code, Section IX.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design trapeze pipe hangers and equipment supports.
- B. Structural Performance: Hangers and supports for fire-suppression piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
  - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
  - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
  - 3. Design seismic-restraint hangers and supports for piping and equipment and obtain approval from authorities having jurisdiction.
- C. NFPA Compliance: Comply with NFPA 13.
- D. UL Compliance: Comply with UL 203.

# 2.2 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
  - 1. Description: Factory-fabricated components, NFPA approved, UL listed, or FM approved for fire-suppression piping support.
  - 2. Galvanized Metallic Coatings: Pregalvanized or hot-dip galvanized.
  - 3. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

#### 2.3 TRAPEZE PIPE HANGERS

A. Description: MSS SP-58, Type 59, shop- or field-fabricated pipe-support assembly, made from structural-carbon-steel shapes, with NFPA-approved, UL-listed, or FM-approved carbon-steel hanger rods, nuts, saddles, and U-bolts.

## 2.4 METAL FRAMING SYSTEMS

- A. MFMA Manufacturer Metal Framing Systems:
  - 1. Description: Shop- or field-fabricated pipe-support assembly, made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
  - 2. Standard: Comply with MFMA-4, factory-fabricated components for field assembly.
  - 3. Channels: Continuous slotted carbon-steel channel with inturned lips.
  - 4. Channel Width: Selected for applicable load criteria.
  - 5. Channel Nuts: Formed or stamped nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
  - 6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
  - 7. Metallic Coating: No coating.
- B. Non-MFMA Manufacturer Metal Framing Systems:
  - 1. Description: Shop- or field-fabricated pipe-support assembly, made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
  - 2. Standard: Comply with MFMA-4, factory-fabricated components for field assembly.
  - 3. Channels: Continuous slotted carbon-steel channel with inturned lips.
  - 4. Channel Width: Select for applicable load criteria.
  - 5. Channel Nuts: Formed or stamped nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
  - 6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
  - 7. Metallic Coating: No coating.

## 2.5 EQUIPMENT SUPPORTS

A. Description: NFPA-approved, UL-listed, or FM-approved, welded, shop- or field-fabricated equipment support, made from structural-carbon-steel shapes.

# 2.6 MATERIALS

- A. Aluminum: ASTM B221.
- B. Carbon Steel: ASTM A1011/A1011M.
- C. Structural Steel: ASTM A36/A36M, carbon-steel plates, shapes, and bars; black and galvanized.
- D. Stainless Steel: ASTM A240/A240M.
- E. Grout: ASTM C1107/C1107M, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout, suitable for interior and exterior applications.
  - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
  - 2. Design Mix: 5000-psi, 28-day compressive strength.

## PART 3 - EXECUTION

#### 3.1 APPLICATION

A. Strength of Support Assemblies: Where not indicated, select sizes of components, so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

## 3.2 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with installation requirements of approvals and listings. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-58. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
  - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size, or install intermediate supports for smaller-diameter pipes as specified for individual pipe hangers.
  - 2. Field fabricate from ASTM A36/A36M carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal strut systems.
- D. Thermal Hanger-Shield Installation: Install in pipe hanger or shield for insulated piping.
- E. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- F. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- G. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- H. Install lateral bracing with pipe hangers and supports to prevent swaying.
- I. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms, and install reinforcing bars through openings at top of inserts.
- J. Load Distribution: Install hangers and supports, so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.

K. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.

## 3.3 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
  - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  - 2. Obtain fusion without undercut or overlap.
  - 3. Remove welding flux immediately.
  - 4. Finish welds at exposed connections, so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

#### 3.4 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches Insert dimension.

#### 3.5 PAINTING

- A. Touchup: Clean field welds and abraded, shop-painted areas. Paint exposed areas immediately after erecting hangers and supports. Use same materials as those used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
  - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Touchup: Cleaning and touchup painting of field welds, bolted connections, and abraded, shoppainted areas on miscellaneous metal are specified in Section 099123 "Interior Painting."
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas, and apply galvanizing-repair paint to comply with ASTM A780/A780M.

# 3.6 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with NFPA requirements for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finishes.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports and attachments for general service applications.
- F. Horizontal-Piping Hangers and Supports: Comply with NFPA requirements. Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
  - 2. Steel Pipe Clamps (MSS Type 4): For suspension of NPS 1/2 to NPS 24 if little or no insulation is required.
  - 3. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steelpipe base stanchion support and cast-iron floor flange or carbon-steel plate.
- G. Hanger-Rod Attachments: Comply with NFPA requirements.
- H. Building Attachments: Comply with NFPA requirements. Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Steel or Malleable-Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
  - 2. C-Clamps (MSS Type 23): For structural shapes.
  - 3. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
- I. Saddles and Shields: Comply with NFPA requirements. Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
  - 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
  - 3. Thermal Hanger-Shield Inserts: For supporting insulated pipe.
- J. Comply with NFPA requirements for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- K. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

END OF SECTION 210529

# SECTION 210553 - IDENTIFICATION FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT

PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Equipment labels.
  - 2. Warning signs and labels.
  - 3. Pipe labels.
  - 4. Stencils.
  - 5. Valve tags.
  - 6. Warning tags.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Equipment-Label Schedule: Include a listing of all equipment to be labeled and the proposed content for each label.
- D. Valve Schedules: Valve numbering scheme.

# PART 2 - PRODUCTS

## 2.1 VALVE TAGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Actioncraft Products, Inc.; a division of Industrial Test Equipment Co., Inc.
  - 2. Brady Corporation.
  - 3. Brimar Industries, Inc.
  - 4. Carlton Industries, LP.

## IDENTIFICATION FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT 210553 - 1

- 5. Champion America.
- 6. Craftmark Pipe Markers.
- 7. Emedco.
- 8. Kolbi Pipe Marker Co.
- 9. LEM Products Inc.
- 10. Marking Sevices Inc.
- 11. Seton Identification Products.
- B. Description: Stamped or engraved with 1/4-inch letters for piping-system abbreviation and 1/2-inch numbers.
  - 1. Tag Material: Brass, 0.032 inch thick, with predrilled holes for attachment hardware.
  - 2. Fasteners: Brass beaded chain.
  - 3. Valve-Tag Color: Safety Red.
  - 4. Letter Color: White.
- C. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.
  - 1. Valve-tag schedule shall be included in operation and maintenance data.

# PART 3 - EXECUTION

# 3.1 PREPARATION

A. Clean piping and equipment surfaces of incompatible primers, paints, and encapsulants, as well as dirt, oil, grease, release agents, and other substances that could impair bond of identification devices.

# 3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be installed.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

# 3.3 PIPE LABEL INSTALLATION

A. Piping: Painting of piping is specified in Section 099123 "Interior Painting."

# IDENTIFICATION FOR FIRE-SUPPRESSION PIPING AND EQUIPMENT 210553 - 2

- B. Stenciled Pipe-Label Option: Stenciled labels may be provided instead of manufactured pipe labels, at Installer's option. Install stenciled pipe labels, complying with ASME A13.1, with painted, color-coded bands or rectangles on each piping system.
  - 1. Identification Paint: Use for contrasting background.
  - 2. Stencil Paint: Use for pipe marking.
- C. Pipe-Label Locations: Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
  - 1. Near each valve and control device.
  - 2. Near each branch connection excluding short takeoffs. Where flow pattern is not obvious, mark each pipe at branch.
  - 3. Near penetrations and on both sides of through walls, floors, ceilings, and inaccessible enclosures.
  - 4. At access doors, manholes, and similar access points that permit a view of concealed piping.
  - 5. Near major equipment items and other points of origination and termination.
  - 6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
  - 7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.
- D. Directional Flow Arrows: Arrows shall be used to indicate direction of flow in pipes including pipes where flow is allowed in both directions.

## 3.4 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in fire-suppression piping systems. List tagged valves in a valve-tag schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and with captions similar to those indicated in "Valve-Tag Size and Shape" Subparagraph below:
  - 1. Valve-Tag Size and Shape:
    - a. Wet-Pipe Sprinkler System: 1-1/2 inches, round.

# END OF SECTION 210553

# SECTION 211313 - WET-PIPE SPRINKLER SYSTEMS

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Pipes, fittings, and specialties.
  - 2. Cover system for sprinkler piping.
  - 3. Specialty valves.
  - 4. Sprinklers.
  - 5. Alarm devices.
  - 6. Manual control stations.
  - 7. Control panels.
  - 8. Pressure gages.
- B. Related Requirements:
  - 1. Section 210523 "General-Duty Valves for Fire Protection Piping" for ball, butterfly, check, gate, post-indicator, and trim and drain valves.

#### 1.3 DEFINITIONS

A. Standard-Pressure Sprinkler Piping: Wet-pipe sprinkler system piping designed to operate at working pressure of 175-psig maximum.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Shop Drawings: For wet-pipe sprinkler systems.
  - 1. Include plans, elevations, sections, and attachment details.
  - 2. Include diagrams for power, signal, and control wiring.

C. Delegated-Design Submittal: For wet-pipe sprinkler systems indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

# 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Sprinkler systems, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
  - 1. Domestic water piping.
  - 2. Compressed air piping.
  - 3. HVAC ductwork.
  - 4. HVAC hydronic piping.
  - 5. Items penetrating finished ceiling include the following:
    - a. Lighting fixtures.
    - b. Air outlets and inlets.
- B. Design Data:
  - 1. Approved Sprinkler Piping Drawings: Working plans, prepared according to NFPA 13, that have been approved by authorities having jurisdiction, including hydraulic calculations if applicable.
- C. Field Test Reports:
  - 1. Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13. Include "Contractor's Material and Test Certificate for Aboveground Piping."
  - 2. Fire-hydrant flow test report.
- D. Field quality-control reports.

# 1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For wet-pipe sprinkler systems and specialties to include in emergency, operation, and maintenance manuals.

# 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Sprinkler Cabinets: Finished, wall-mounted, steel cabinet with hinged cover, and with space for minimum of six spare sprinklers plus sprinkler wrench. Include number of sprinklers required by NFPA 13 and sprinkler wrench. Include separate cabinet with sprinklers and wrench for each type of sprinkler used on Project.

## 1.8 QUALITY ASSURANCE

- A. Installer Qualifications:
  - 1. Installer's responsibilities include designing, fabricating, and installing sprinkler systems and providing professional engineering services needed to assume engineering responsibility. Base calculations on results of fire-hydrant flow test.

## PART 2 - PRODUCTS

## 2.1 PERFORMANCE REQUIREMENTS

- A. Sprinkler system equipment, specialties, accessories, installation, and testing shall comply with the following:
  - 1. NFPA 13.
- B. Standard-Pressure Piping System Component: Listed for 175-psig (1200-kPa) minimum working pressure.
- C. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design wet-pipe sprinkler systems.
  - 1. Available fire-hydrant flow test records indicate the following conditions:
    - a. Static Pressure at Residual Fire Hydrant R: 78 psi
    - b. Measured Flow at Flow Fire Hydrant F: 1930 gpm.
    - c. Residual Pressure at Residual Fire Hydrant R: 62 psi.
  - 2. Sprinkler system design shall be approved by authorities having jurisdiction.
    - a. Margin of Safety for Available Water Flow and Pressure: 10 percent, including losses through water-service piping, valves, and backflow preventers.
    - b. Sprinkler Occupancy Hazard Classifications:
      - 1) As indicated and as required by NFPA 13 and AHJ, whichever requirement is more stringent.
  - 3. Minimum Density for Automatic-Sprinkler Piping Design:
    - a. Light-Hazard Occupancy: 0.10 gpm over 1500-sq. ft. (4.1 mm/min. over 139-sq. m) area.
    - b. Ordinary-Hazard, Group 1 Occupancy: 0.15 gpm over 1500-sq. ft. (6.1 mm/min. over 139-sq. m) area.
    - c. Ordinary-Hazard, Group 2 Occupancy: 0.20 gpm over 1500-sq. ft. (8.1 mm/min. over 139-sq. m) area.

- 4. Maximum Protection Area per Sprinkler:
  - a. Office Spaces: 225 sq. ft.
  - b. Storage Areas: 130 sq. ft.
  - c. Mechanical Equipment Rooms: 130 sq. ft.
  - d. Electrical Equipment Rooms: 130 sq. ft.
  - e. Other Areas: According to NFPA 13 recommendations unless otherwise indicated.
- D. Seismic Performance: Sprinkler piping shall withstand the effects of earthquake motions determined according to NFPA 13 and ASCE/SEI 7.

# 2.2 STEEL PIPE AND FITTINGS

- A. Schedule 30, Galvanized- and Black-Steel Pipe: ASTM A135/A135M; ASTM A795/A795M, Type E; or ASME B36.10M wrought steel, with wall thickness not less than Schedule 30 and not more than Schedule 40. Pipe ends may be factory or field formed to match joining method.
- B. Schedule 10, Black-Steel Pipe: ASTM A135/A135M or ASTM A795/A795M, Schedule 10 in NPS 5 (DN 125) and smaller; and NFPA 13-specified wall thickness in NPS 6 to NPS 10 (DN 150 to DN 250), plain end.
- C. Galvanized- and Black-Steel Pipe Nipples: ASTM A733, made of ASTM A53/A53M, standard-weight, seamless steel pipe with threaded ends.
- D. Malleable- or Ductile-Iron Unions: UL 860.
- E. Grooved-Joint, Steel-Pipe Appurtenances:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Anvil International.
    - b. Victaulic Company.
  - 2. Pressure Rating: 175-psig (1200-kPa) minimum.
  - 3. Galvanized Painted Grooved-End Fittings for Steel Piping: ASTM A47/A47M, malleable-iron casting or ASTM A536, ductile-iron casting, with dimensions matching steel pipe.
  - 4. Grooved-End-Pipe Couplings for Steel Piping: AWWA C606 and UL 213 rigid pattern, unless otherwise indicated, for steel-pipe dimensions. Include ferrous housing sections, EPDM-rubber gasket, and bolts and nuts.

# 2.3 SPECIALTY VALVES

A. Listed in UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."

- B. Pressure Rating:
  - 1. Standard-Pressure Piping Specialty Valves: 175-psig minimum.
- C. Body Material: Cast or ductile iron.
- D. Size: Same as connected piping.
- E. End Connections: Flanged or grooved.
- F. Alarm Valves:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Globe Fire Sprinkler Corporation.
    - b. Reliable Automatic Sprinkler Co., Inc. (The).
    - c. Viking Corporation.
  - 2. Standard: UL 193.
  - 3. Design: For horizontal or vertical installation.
  - 4. Include trim sets for bypass, drain, electrical sprinkler alarm switch, pressure gages, and fill-line attachment with strainer.
  - 5. Drip Cup Assembly: Pipe drain with check valve to main drain piping.
  - 6. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- G. Automatic (Ball Drip) Drain Valves:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Reliable Automatic Sprinkler Co., Inc. (The).
    - b. Tyco Fire Products LP.
  - 2. Standard: UL 1726.
  - 3. Pressure Rating: 175-psig minimum.
  - 4. Type: Automatic draining, ball check.
  - 5. Size: NPS 3/4.
  - 6. End Connections: Threaded.

# 2.4 SPRINKLER PIPING SPECIALTIES

- A. Branch Outlet Fittings:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- a. AGF Manufacturing, Inc.
- b. Tyco Fire Products LP.
- c. Victaulic Company.
- 2. Standard: UL 213.
- 3. Pressure Rating: 175-psig minimum.
- 4. Body Material: Ductile-iron housing with EPDM seals and bolts and nuts.
- 5. Type: Mechanical-tee and -cross fittings.
- 6. Configurations: Snap-on and strapless, ductile-iron housing with branch outlets.
- 7. Size: Of dimension to fit onto sprinkler main and with outlet connections as required to match connected branch piping.
- 8. Branch Outlets: Grooved, plain-end pipe, or threaded.
- B. Flow Detection and Test Assemblies:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Tyco Fire Products LP.
    - b. Victaulic Company.
  - 2. Standard: UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."
  - 3. Pressure Rating: 175-psig minimum.
  - 4. Body Material: Cast- or ductile-iron housing with orifice, sight glass, and integral test valve.
  - 5. Size: Same as connected piping.
  - 6. Inlet and Outlet: Threaded or grooved.
- C. Branch Line Testers:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. AGF Manufacturing, Inc.
    - b. Potter Roemer LLC.
  - 2. Standard: UL 199.
  - 3. Pressure Rating: 175 psig.
  - 4. Body Material: Brass.
  - 5. Size: Same as connected piping.
  - 6. Inlet: Threaded.
  - 7. Drain Outlet: Threaded and capped.
  - 8. Branch Outlet: Threaded, for sprinkler.
- D. Sprinkler Inspector's Test Fittings:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. AGF Manufacturing, Inc.

- b. Triple R Specialty.
- c. Victaulic Company.
- 2. Standard: UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."
- 3. Pressure Rating: 175-psig minimum.
- 4. Body Material: Cast- or ductile-iron housing with sight glass.
- 5. Size: Same as connected piping.
- 6. Inlet and Outlet: Threaded.
- E. Flexible Sprinkler Hose Fittings:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Fivalco Inc.
    - b. Victaulic Company.
  - 2. Standard: UL 1474.
  - 3. Type: Flexible hose for connection to sprinkler, and with bracket for connection to ceiling grid.
  - 4. Pressure Rating: 175-psig minimum.
  - 5. Size: Same as connected piping, for sprinkler.

## 2.5 SPRINKLERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Reliable Automatic Sprinkler Co., Inc. (The).
  - 2. Tyco Fire Products LP.
  - 3. Venus Fire Protection Ltd.
  - 4. Viking Corporation.
- B. Listed in UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."
- C. Pressure Rating for Residential Sprinklers: 175-psig maximum.
- D. Pressure Rating for Automatic Sprinklers: 175-psig minimum.
- E. Automatic Sprinklers with Heat-Responsive Element:
  - 1. Early-Suppression, Fast-Response Applications: UL 1767.
  - 2. Nonresidential Applications: UL 199.
  - 3. Characteristics: Nominal 1/2-inch orifice with Discharge Coefficient K of 5.6, and for "Ordinary" temperature classification rating unless otherwise indicated or required by application.
- F. Sprinkler Finishes: Chrome plated bronze and painted.

- G. Special Coatings: Wax lead and corrosion-resistant paint.
- H. Sprinkler Escutcheons: Materials, types, and finishes for the following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.
  - 1. Ceiling Mounting: Chrome-plated steel, one piece, flat.
  - 2. Sidewall Mounting: Chrome-plated steel, one piece, flat.
- I. Sprinkler Guards:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Reliable Automatic Sprinkler Co., Inc. (The).
    - b. Tyco Fire Products LP.
    - c. Viking Corporation.
  - 2. Standard: UL 199.
  - 3. Type: Wire cage with fastening device for attaching to sprinkler.

# 2.6 ALARM DEVICES

- A. Alarm-device types shall match piping and equipment connections.
- B. Water-Motor-Operated Alarm:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Globe Fire Sprinkler Corporation.
    - b. Viking Corporation.
  - 2. Standard: UL 753.
  - 3. Type: Mechanically operated, with Pelton wheel.
  - 4. Alarm Gong: Cast aluminum with red-enamel factory finish.
  - 5. Size: 8-1/2-inches diameter.
  - 6. Components: Shaft length, bearings, and sleeve to suit wall construction.
  - 7. Inlet: NPS 3/4.
  - 8. Outlet: NPS 1 drain connection.
- C. Water-Flow Indicators:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. ADT Security Services, Inc.
    - b. McDonnell & Miller.
    - c. Potter Electric Signal Company, LLC.

- d. System Sensor.
- e. Viking Corporation.
- f. WATTS.
- 2. Standard: UL 346.
- 3. Water-Flow Detector: Electrically supervised.
- 4. Components: Two single-pole, double-throw circuit switches for isolated alarm and auxiliary contacts, 7 A, 125-V ac and 0.25 A, 24-V dc; complete with factory-set, field-adjustable retard element to prevent false signals and tamperproof cover that sends signal if removed.
- 5. Type: Paddle operated.
- 6. Pressure Rating: 250 psig.
- 7. Design Installation: Horizontal or vertical.
- D. Valve Supervisory Switches:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Kennedy Valve Company; a division of McWane, Inc.
    - b. Potter Electric Signal Company, LLC.
    - c. System Sensor.
  - 2. Standard: UL 346.
  - 3. Type: Electrically supervised.
  - 4. Components: Single-pole, double-throw switch with normally closed contacts.
  - 5. Design: Signals that controlled valve is in other than fully open position.
  - 6. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

#### 2.7 PRESSURE GAGES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. AGF Manufacturing, Inc.
  - 2. AMETEK, Inc.
  - 3. Ashcroft Inc.
  - 4. Brecco Corporation.
  - 5. WIKA Instrument Corporation.
- B. Standard: UL 393.
- C. Dial Size: 3-1/2- to 4-1/2-inch diameter.
- D. Pressure Gage Range: 0- to 250-psig minimum.
- E. Label: Include "WATER" label on dial face.

# PART 3 - EXECUTION

## 3.1 PREPARATION

- A. Perform fire-hydrant flow test according to NFPA 13 and NFPA 291. Use results for system design calculations required in "Quality Assurance" Article.
- B. Report test results promptly and in writing.

## 3.2 PIPING INSTALLATION

- A. Locations and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of piping. Install piping as indicated on approved working plans.
  - 1. Deviations from approved working plans for piping require written approval from authorities having jurisdiction. File written approval with Architect before deviating from approved working plans.
  - 2. Coordinate layout and installation of sprinklers with other construction that penetrates ceilings, including light fixtures, HVAC equipment, and partition assemblies.
- B. Piping Standard: Comply with NFPA 13 requirements for installation of sprinkler piping.
- C. Install seismic restraints on piping. Comply with NFPA 13 requirements for seismic-restraint device materials and installation.
- D. Use listed fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.
- E. Install unions adjacent to each valve in pipes NPS 2 and smaller.
- F. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.
- G. Install "Inspector's Test Connections" in sprinkler system piping, complete with shutoff valve, and sized and located according to NFPA 13.
- H. Install sprinkler piping with drains for complete system drainage.
- I. Install sprinkler control valves, test assemblies, and drain risers adjacent to standpipes when sprinkler piping is connected to standpipes.
- J. Install automatic (ball drip) drain valve at each check valve for fire-department connection, to drain piping between fire-department connection and check valve. Install drain piping to and spill over floor drain or to outside building.
- K. Install alarm devices in piping systems.

- L. Install hangers and supports for sprinkler system piping according to NFPA 13. Comply with requirements for hanger materials in NFPA 13.
- M. Install pressure gages on riser or feed main, at each sprinkler test connection, and at top of each standpipe. Include pressure gages with connection not less than NPS 1/4 and with soft-metal seated globe valve, arranged for draining pipe between gage and valve. Install gages to permit removal, and install where they are not subject to freezing.
- N. Fill sprinkler system piping with water.
- O. Install sleeves for piping penetrations of walls, ceilings, and floors.Retain first paragraph below for piping that penetrates an exterior concrete wall or concrete slab.

# 3.3 JOINT CONSTRUCTION

- A. Install couplings, flanges, flanged fittings, unions, nipples, and transition and special fittings that have finish and pressure ratings same as or higher than system's pressure rating for aboveground applications unless otherwise indicated.
- B. Install unions adjacent to each valve in pipes NPS 2 and smaller.
- C. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.
- D. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- E. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- F. Flanged Joints: Select appropriate gasket material in size, type, and thickness suitable for water service. Join flanges with gasket and bolts according to ASME B31.9.
- G. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- H. Twist-Locked Joints: Insert plain end of steel pipe into plain-end-pipe fitting. Rotate retainer lugs one-quarter turn or tighten retainer pin.
- I. Steel-Piping, Pressure-Sealed Joints: Join lightwall steel pipe and steel pressure-seal fittings with tools recommended by fitting manufacturer.
- J. Welded Joints: Construct joints according to AWS D10.12M/D10.12, using qualified processes and welding operators according to "Quality Assurance" Article.

- 1. Shop weld pipe joints where welded piping is indicated. Do not use welded joints for galvanized-steel pipe.
- K. Steel-Piping, Cut-Grooved Joints: Cut square-edge groove in end of pipe according to AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings according to AWWA C606 for steel-pipe joints.
- L. Steel-Piping, Roll-Grooved Joints: Roll rounded-edge groove in end of pipe according to AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings according to AWWA C606 for steel-pipe grooved joints.
- M. Dissimilar-Material Piping Joints: Make joints using adapters compatible with materials of both piping systems.

## 3.4 VALVE AND SPECIALTIES INSTALLATION

- A. Install listed fire-protection valves, trim and drain valves, specialty valves and trim, controls, and specialties according to NFPA 13 and authorities having jurisdiction.
- B. Install listed fire-protection shutoff valves supervised open, located to control sources of water supply except from fire-department connections. Install permanent identification signs indicating portion of system controlled by each valve.
- C. Install check valve in each water-supply connection. Install backflow preventers instead of check valves in potable-water-supply sources.
- D. Specialty Valves:
  - 1. Install valves in vertical position for proper direction of flow, in main supply to system.
  - 2. Install alarm valves with bypass check valve and retarding chamber drain-line connection.
  - 3. Install deluge valves in vertical position, in proper direction of flow, and in main supply to deluge system. Install trim sets for drain, priming level, alarm connections, ball drip valves, pressure gages, priming chamber attachment, and fill-line attachment.

#### 3.5 SPRINKLER INSTALLATION

- A. Install sprinklers in suspended ceilings in center of narrow dimension of acoustical ceiling panels.
- B. Install dry-type sprinklers with water supply from heated space. Do not install pendent or sidewall, wet-type sprinklers in areas subject to freezing.
- C. Install sprinklers into flexible, sprinkler hose fittings, and install hose into bracket on ceiling grid.

## 3.6 IDENTIFICATION

- A. Install labeling and pipe markers on equipment and piping according to requirements in NFPA 13.
- B. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

## 3.7 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
  - 1. Leak Test: After installation, charge systems and test for leaks. Repair leaks and retest until no leaks exist.
  - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
  - 3. Flush, test, and inspect sprinkler systems according to NFPA 13, "Systems Acceptance" Chapter.
  - 4. Energize circuits to electrical equipment and devices.
  - 5. Coordinate with fire-alarm tests. Operate as required.
  - 6. Verify that equipment hose threads are same as local fire department equipment.
- B. Sprinkler piping system will be considered defective if it does not pass tests and inspections.
- C. Prepare test and inspection reports.

## 3.8 CLEANING

- A. Clean dirt and debris from sprinklers.
- B. Only sprinklers with their original factory finish are acceptable. Remove and replace any sprinklers that are painted or have any other finish than their original factory finish.

#### 3.9 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain specialty valves.

#### 3.10 PIPING SCHEDULE

- A. Standard-pressure, wet-pipe sprinkler system, NPS 2 and smaller, shall be the following:
  - 1. Standard-weight, galvanized-steel pipe with threaded ends; galvanized, gray-iron threaded fittings; and threaded joints.
- B. Standard-pressure, wet-pipe sprinkler system, NPS 2-1/2 and larger, shall be one of the following:

- 1. Standard-weight, black-steel pipe with threaded ends; uncoated, gray-iron threaded fittings; and threaded joints.
- 2. Standard-weight, galvanized-steel pipe with threaded ends; galvanized, gray-iron threaded fittings; and threaded joints.
- 3. Standard-weight or Schedule 30, black-steel pipe with cut- or roll-grooved ends; uncoated, grooved-end fittings for steel piping; grooved-end-pipe couplings for steel piping; and grooved joints.

# 3.11 SPRINKLER SCHEDULE

- A. Use sprinkler types in subparagraphs below for the following applications:
  - 1. Rooms without Ceilings: Upright sprinklers.
  - 2. Rooms with Suspended Ceilings: Concealed sprinklers.
  - 3. Wall Mounting: Concealed Sidewall sprinklers.
- B. Provide sprinkler types in subparagraphs below with finishes indicated.
  - 1. Concealed Sprinklers: Rough brass, with factory-painted white cover plate.
  - 2. Upright Pendent Sprinklers: Chrome plated in finished spaces exposed to view; rough bronze in unfinished spaces not exposed to view; wax coated where exposed to acids, chemicals, or other corrosive fumes.

# END OF SECTION 211313

# SECTION 220518 - ESCUTCHEONS FOR PLUMBING PIPING

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Escutcheons.
  - 2. Floor plates.

#### 1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

# PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. BrassCraft Manufacturing Co.; a Masco company.
  - 2. Dearborn Brass.

# 2.2 ESCUTCHEONS

- A. One-Piece, Cast-Brass Type: With polished, chrome-plated finish and setscrew fastener.
- B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with polished, chrome-plated finish and spring-clip fasteners.
- C. One-Piece, Stamped-Steel Type: With polished, chrome-plated finish and spring-clip fasteners.
- D. Split-Plate, Stamped-Steel Type: With polished, chrome-plated finish; concealed and exposed-rivet hinge; and spring-clip fasteners.

## ESCUTCHEONS FOR PLUMBING PIPING

# 2.3 FLOOR PLATES

A. Split Floor Plates: Cast brass with concealed hinge.

# PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.
- B. Install escutcheons with ID to closely fit around pipe, tube, and insulation of insulated piping and with OD that completely covers opening.
  - 1. Escutcheons for New Piping:
    - a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep pattern.
    - b. Insulated Piping: One-piece stamped steel or split-plate, stamped steel with exposed-rivet hinge with polished, chrome-plated finish.
    - c. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece cast brass with polished, chrome-plated finish.
    - d. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece cast brass with polished, chrome-plated finish.
    - e. Bare Piping in Unfinished Service Spaces: One-piece cast brass with polished, chrome-plated finish.
    - f. Bare Piping in Equipment Rooms: One-piece cast brass with polished, chromeplated finish.
    - g. Bare Piping in Equipment Rooms: One-piece stamped steel or split-plate, stamped steel with exposed-rivet hinge with polished, chrome-plated finish.
- C. Install floor plates for piping penetrations of equipment-room floors.
- D. Install floor plates with ID to closely fit around pipe, tube, and insulation of piping and with OD that completely covers opening.
  - 1. New Piping: One-piece, floor plate.

# 3.2 FIELD QUALITY CONTROL

A. Using new materials, replace broken and damaged escutcheons and floor plates.

# END OF SECTION 220518

## ESCUTCHEONS FOR PLUMBING PIPING

# SECTION 220523.12 - BALL VALVES FOR PLUMBING PIPING

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Bronze ball valves.

#### 1.3 DEFINITIONS

A. CWP: Cold working pressure.

## 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of valve.
  - 1. Certification that products comply with NSF 61and NSF 372.

# 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
  - 1. Protect internal parts against rust and corrosion.
  - 2. Protect threads, flange faces, and soldered ends.
  - 3. Set ball valves open to minimize exposure of functional surfaces.
- B. Use the following precautions during storage:
  - 1. Maintain valve end protection.
  - 2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use operating handles or stems as lifting or rigging points.

#### BALL VALVES FOR PLUMBING PIPING

# PART 2 - PRODUCTS

## 2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.
- B. ASME Compliance:
  - 1. ASME B1.20.1 for threads for threaded end valves.
  - 2. ASME B16.1 for flanges on iron valves.
  - 3. ASME B16.5 for flanges on steel valves.
  - 4. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
  - 5. ASME B16.18 for solder-joint connections.
  - 6. ASME B31.9 for building services piping valves.
- C. NSF Compliance: NSF 61 and NSF 372 for valve materials for potable-water service.
- D. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.
- E. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- F. Valve Sizes: Same as upstream piping unless otherwise indicated.
- G. Valve Actuator Types:
  - 1. Gear Actuator: For quarter-turn valves NPS 4 and larger.
  - 2. Handlever: For quarter-turn valves smaller than NPS 4.
- H. Valves in Insulated Piping:
  - 1. Include 2-inch stem extensions.
  - 2. Extended operating handles of nonthermal-conductive material and protective sleeves that allow operation of valves without breaking vapor seals or disturbing insulation.
  - 3. Memory stops that are fully adjustable after insulation is applied.

## 2.2 BRONZE BALL VALVES

- A. Bronze Ball Valves, Two-Piece with Full Port, and Bronze or Brass or Bronze Trim, Threaded or Soldered Ends:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Milwaukee Valve Company.
    - b. NIBCO INC.

#### BALL VALVES FOR PLUMBING PIPING

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- c. Red-White Valve Corporation.
- d. WATTS.
- 2. Description:
  - a. Standard: MSS SP-110 or MSS-145.
  - b. CWP Rating: 600 psig.
  - c. Body Design: Two piece.
  - d. Body Material: Bronze.
  - e. Ends: Threaded and soldered.
  - f. Seats: PTFE.
  - g. Stem: Bronze or brass.
  - h. Ball: Chrome-plated brass.
  - i. Port: Full.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- E. Do not attempt to repair defective valves; replace with new valves.

# 3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.
- D. Install valves in position to allow full stem movement.
- E. Install valve tags. Comply with requirements in Section 220553 "Identification for Plumbing Piping and Equipment" for valve tags and schedules.

#### BALL VALVES FOR PLUMBING PIPING

#### 220523.12 - 3

## 3.3 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.
- B. Select valves with the following end connections:
  - 1. For Copper Tubing, NPS 2 and Smaller: Threaded ends except where solder-joint valveend option or press-end option is indicated in valve schedules below.
  - 2. For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
  - 3. For Copper Tubing, NPS 5 and Larger: Flanged ends.
  - 4. For Steel Piping, NPS 2 and Smaller: Threaded ends.
  - 5. For Steel Piping, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
  - 6. For Steel Piping, NPS 5 and Larger: Flanged ends.

## 3.4 LOW-PRESSURE, COMPRESSED-AIR VALVE SCHEDULE (150 PSIG OR LESS)

- A. Pipe NPS 2-1/2 and Smaller:
  - 1. Bronze Valves: May be provided with solder-joint ends instead of threaded ends.
  - 2. Bronze ball valves, two-piece with full port and brass or bronze trim.

#### 3.5 DOMESTIC HOT- AND COLD-WATER VALVE SCHEDULE

- A. Pipe NPS 2-1/2 and Smaller:
  - 1. Bronze ball valves, two-piece with full port and brass or bronze trim. Provide with threaded or solder-joint ends.

#### END OF SECTION 220523.12

BALL VALVES FOR PLUMBING PIPING

# SECTION 220523.14 - CHECK VALVES FOR PLUMBING PIPING

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Bronze swing check valves.
  - 2. Iron swing check valves.

## 1.3 DEFINITIONS

- A. CWP: Cold working pressure.
- B. EPDM: Ethylene propylene-diene terpolymer rubber.
- C. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.

# 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of valve.
  - 1. Certification that products comply with NSF 61.

# 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
  - 1. Protect internal parts against rust and corrosion.
  - 2. Protect threads, flange faces, grooves, and weld ends.
  - 3. Set check valves in either closed or open position.
- B. Use the following precautions during storage:
  - 1. Maintain valve end protection.
  - 2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

# CHECK VALVES FOR PLUMBING PIPING

#### 220523.14 - 1

C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.

# PART 2 - PRODUCTS

# 2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.
- B. ASME Compliance:
  - 1. ASME B1.20.1 for threads for threaded end valves.
  - 2. ASME B16.1 for flanges on iron valves.
  - 3. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
  - 4. ASME B16.18 for solder joint.
  - 5. ASME B31.9 for building services piping valves.
- C. AWWA Compliance: Comply with AWWA C606 for grooved-end connections.
- D. Drinking Water System Components Health Effects and Drinking Water System Components Lead Content Compliance: NSF 61 and NSF 372.
- E. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.
- F. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- G. Valve Sizes: Same as upstream piping unless otherwise indicated.
- H. Valve Bypass and Drain Connections: MSS SP-45.

## 2.2 BRONZE SWING CHECK VALVES

- A. Bronze Swing Check Valves with Bronze Disc, Class 125:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Milwaukee Valve Company.
    - b. NIBCO INC.
    - c. Red-White Valve Corp.
    - d. WATTS.

## CHECK VALVES FOR PLUMBING PIPING

- 2. Description:
  - a. Standard: MSS SP-80, Type 3.
  - b. CWP Rating: 200 psig.
  - c. Body Design: Horizontal flow.
  - d. Body Material: ASTM B62, bronze.
  - e. Ends: Threaded or soldered. See valve schedule articles.
  - f. Disc: Bronze.

## 2.3 IRON SWING CHECK VALVES

- A. Iron Swing Check Valves with Metal Seats, Class 125:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Milwaukee Valve Company.
    - b. NIBCO INC.
    - c. Red-White Valve Corp.
    - d. WATTS.
  - 2. Description:
    - a. Standard: MSS SP-71, Type I.
    - b. CWP Rating: 200 psig.
    - c. Body Design: Clear or full waterway.
    - d. Body Material: ASTM A126, gray iron with bolted bonnet.
    - e. Ends: Flanged or threaded. See valve schedule articles.
    - f. Trim: Bronze.
    - g. Gasket: Asbestos free.

# PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.

#### CHECK VALVES FOR PLUMBING PIPING

#### 220523.14 - 3

E. Do not attempt to repair defective valves; replace with new valves.

# 3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.
- D. Install valves in position to allow full stem movement.
- E. Check Valves: Install check valves for proper direction of flow.
  - 1. Swing Check Valves: In horizontal position with hinge pin level.
- F. Install valve tags. Comply with requirements in Section 220553 "Identification for Plumbing Piping and Equipment" for valve tags and schedules.

## 3.3 ADJUSTING

A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

#### 3.4 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. If valve applications are not indicated, use the following:
  - 1. Pump-Discharge Check Valves:
    - a. NPS 2 and Smaller: Bronze swing check valves with bronze disc.
- B. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.
- C. End Connections:
  - 1. For Copper Tubing, NPS 2 and Smaller: Threaded or soldered or press-ends.
  - 2. For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged or threaded.

#### 3.5 DOMESTIC HOT- AND COLD-WATER VALVE SCHEDULE

- A. Pipe NPS 2 and Smaller:
  - 1. Bronze swing check valves with bronze disc, Class 125, with soldered end connections.

#### CHECK VALVES FOR PLUMBING PIPING

220523.14 - 4

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- B. Pipe NPS 2-1/2 and Larger:
  - 1. Iron swing check valves with metal seats, Class 125, with threaded or flanged end connections.

END OF SECTION 220523.14

CHECK VALVES FOR PLUMBING PIPING

# SECTION 220529 - HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

# 1.1 SUMMARY

- A. Section Includes:
  - 1. Metal pipe hangers and supports.
  - 2. Trapeze pipe hangers.
  - 3. Thermal-hanger shield inserts.
  - 4. Fastener systems.
  - 5. Pipe positioning systems.
  - 6. Equipment supports.

# 1.2 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Design trapeze pipe hangers and equipment supports, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- B. Structural Performance: Hangers and supports for plumbing piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated.
  - 1. Design supports for multiple pipes capable of supporting combined weight of supported systems, system contents, and test water.
  - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

# PART 2 - PRODUCTS

# 2.1 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
  - 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
  - 2. Galvanized Metallic Coatings: Pregalvanized or hot dipped.
  - 3. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
  - 4. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

# B. Copper Pipe Hangers:

- 1. Description: MSS SP-58, Types 1 through 58, copper- or epoxy-coated-steel, factory-fabricated components.
- 2. Hanger Rods: Continuous-thread rod, nuts, and washer made of copper-coated steel or stainless steel.

# 2.2 TRAPEZE PIPE HANGERS

A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

# 2.3 METAL FRAMING SYSTEMS

- A. Manufacturer Metal Framing Systems:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Allied Tube & Conduit.
    - b. Cooper B-Line, Inc.
    - c. Flex-Strut Inc.
    - d. Thomas & Betts Corporation.
    - e. Unistrut Corporation; Tyco International, Ltd.
  - 2. Description: Shop- or field-fabricated pipe-support assembly for supporting multiple parallel pipes.
  - 3. Channels: Continuous slotted steel channel with inturned lips.
  - 4. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
  - 5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

# 2.4 THERMAL-HANGER SHIELD INSERTS

- A. Insulation-Insert Material for Cold Piping: ASTM C 552, Type II cellular glass with 100-psig (688-kPa) or ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig (862-kPa) minimum compressive strength and vapor barrier.
- B. Insulation-Insert Material for Hot Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate with 100-psig (688-kPa), ASTM C 552, Type II cellular glass with 100-psig (688-kPa) or ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig (862-kPa) minimum compressive strength.
- C. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- D. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.

E. Insert Length: Extend 2 inches (50 mm) beyond sheet metal shield for piping operating below ambient air temperature.

## 2.5 PIPE STANDS

- A. Refer to details on the plans for specific products.
- B. General Requirements for Pipe Stands: Shop- or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.
- C. Compact Pipe Stand: One-piece plastic unit with integral-rod roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.
- D. Low-Type, Single-Pipe Stand: One-piece plastic or stainless-steel base unit with plastic roller, for roof installation without membrane penetration.

# 2.6 PIPE POSITIONING SYSTEMS

A. Description: IAPMO PS 42, positioning system of metal brackets, clips, and straps for positioning piping in pipe spaces; for plumbing fixtures in commercial applications.

## 2.7 EQUIPMENT SUPPORTS

A. Description: Welded, shop- or field-fabricated equipment support made from structural carbonsteel shapes.

# 2.8 MISCELLANEOUS MATERIALS

A. Structural Steel: ASTM A 36/A 36M, carbon-steel plates, shapes, and bars; black and galvanized.

# PART 3 - EXECUTION

# 3.1 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.
- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.

- 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.
- 2. Field fabricate from ASTM A 36/A 36M, carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.
- D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.
- E. Pipe Positioning-System Installation: Install support devices to make rigid supply and waste piping connections to each plumbing fixture.
- F. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- G. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- H. Install lateral bracing with pipe hangers and supports to prevent swaying.
- I. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 (DN 65) and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- J. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- K. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- L. Insulated Piping:
  - 1. Attach clamps and spacers to piping.
    - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
    - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
    - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
  - 2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
    - a. Saddles exposed to view shall have a paint grip surface.

- b. Option: Thermal-hanger shield inserts may be used. Include steel weightdistribution plate for pipe NPS 4 (DN 100) and larger if pipe is installed on rollers.
- 3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
  - a. Option: Thermal-hanger shield inserts may be used. Include steel weightdistribution plate for pipe NPS 4 (DN 100) and larger if pipe is installed on rollers.
- 4. Shield Dimensions for Pipe: Not less than the following:
  - a. NPS 1/4 to NPS 3-1/2 (DN 8 to DN 90): 12 inches (305 mm) long and 0.048 inch (1.22 mm) thick.
  - b. NPS 4 (DN 100): 12 inches (305 mm) long and 0.06 inch (1.52 mm) thick.
  - c. NPS 5 and NPS 6 (DN 125 and DN 150): 18 inches (457 mm) long and 0.06 inch (1.52 mm) thick.
  - d. NPS 8 to NPS 14 (DN 200 to DN 350): 24 inches (610 mm) long and 0.075 inch (1.91 mm) thick.
  - e. NPS 16 to NPS 24 (DN 400 to DN 600): 24 inches (610 mm) long and 0.105 inch (2.67 mm) thick.
- 5. Pipes NPS 8 (DN 200) and Larger: Include wood or reinforced calcium-silicateinsulation inserts of length at least as long as protective shield.
- 6. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

# 3.2 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Provide lateral bracing, to prevent swaying, for equipment supports.

# 3.3 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
  - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  - 2. Obtain fusion without undercut or overlap.
  - 3. Remove welding flux immediately.

4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

#### 3.4 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches (40 mm).

## 3.5 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting.
  - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils (0.05 mm).
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

#### 3.6 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports and metal trapeze pipe hangers and attachments for general service applications.
- F. Use copper- or epoxy-plated pipe hangers and copper attachments for copper piping and tubing.
- G. Use padded hangers for piping that is subject to scratching.
- H. Use thermal-hanger shield inserts for insulated piping and tubing.

- I. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30 (DN 15 to DN 750).
  - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F (566 deg C), pipes NPS 4 to NPS 24 (DN 100 to DN 600), requiring up to 4 inches (100 mm) of insulation.
  - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36 (DN 20 to DN 900), requiring clamp flexibility and up to 4 inches (100 mm) of insulation.
  - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 (DN 15 to DN 600) if little or no insulation is required.
  - 5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4 (DN 15 to DN 100), to allow off-center closure for hanger installation before pipe erection.
  - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8 (DN 20 to DN 200).
  - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8 (DN 15 to DN 200).
  - 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8 (DN 15 to DN 200).
  - 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8 (DN 15 to DN 200).
  - 10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8 (DN 10 to DN 200).
  - 11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3 (DN 10 to DN 80).
  - 12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30 (DN 15 to DN 750).
  - 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
  - 14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36 (DN 100 to DN 900), with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
  - 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36 (DN 100 to DN 900), with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
  - 16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 (DN 65 to DN 900) if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
  - 17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30 (DN 25 to DN 750), from two rods if longitudinal movement caused by expansion and contraction might occur.
  - 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24 (DN 65 to DN 600), from single rod if horizontal movement caused by expansion and contraction might occur.
  - 19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 (DN 50 to DN 1050) if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.

- 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 (DN 50 to DN 600) if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
- 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 (DN 50 to DN 750) if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- J. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24 (DN 24 to DN 600).
  - 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 (DN 20 to DN 600) if longer ends are required for riser clamps.
- K. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches (150 mm) for heavy loads.
  - 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F (49 to 232 deg C) piping installations.
- L. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
  - 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
  - 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
  - 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
  - 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
  - 6. C-Clamps (MSS Type 23): For structural shapes.
  - 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
  - 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
  - 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel Ibeams for heavy loads.
  - 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel Ibeams for heavy loads, with link extensions.
  - 11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
  - 12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
    - a. Light (MSS Type 31): 750 lb (340 kg).
    - b. Medium (MSS Type 32): 1500 lb (680 kg).

- c. Heavy (MSS Type 33): 3000 lb (1360 kg).
- 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
- 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
- 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- M. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Saddles and shields exposed to view shall have a paint grip surface.
  - 2. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
  - 3. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
  - 4. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- N. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- O. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- P. Use pipe positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

END OF SECTION 220529

# SECTION 220548 - VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Pipe-riser resilient supports.
  - 2. Resilient pipe guides.
  - 3. Restraint channel bracings.
  - 4. Restraint cables.
  - 5. Seismic-restraint accessories.
  - 6. Mechanical anchor bolts.
  - 7. Adhesive anchor bolts.
- B. Related Requirements:
  - 1. Section 230548 "Vibration and Seismic Controls for HVAC" for devices for HVAC equipment and systems.

#### 1.3 DEFINITIONS

- A. IBC: International Building Code.
- B. ICC-ES: ICC-Evaluation Service.
- C. OSHPD: Office of Statewide Health Planning & Development (for the State of California).

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
  - 2. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of vibration isolation device and seismic-restraint component required.

- a. Tabulate types and sizes of seismic restraints, complete with report numbers and rated strength in tension and shear as evaluated by an agency acceptable to authorities having jurisdiction.
- b. Annotate to indicate application of each product submitted and compliance with requirements.
- 3. Interlocking Snubbers: Include ratings for horizontal, vertical, and combined loads.
- B. Shop Drawings:
  - 1. Detail fabrication and assembly of equipment bases. Detail fabrication including anchorages and attachments to structure and to supported equipment.
- C. Delegated-Design Submittal: For each vibration isolation and seismic-restraint device.
  - 1. Include design calculations and details for selecting vibration isolators and seismic restraints complying with performance requirements, design criteria, and analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
  - 2. Design Calculations: Calculate static and dynamic loading due to equipment weight and operation, due to seismic forces required to select vibration isolators, and due to seismic restraints.
  - 3. Riser Supports: Include riser diagrams and calculations showing anticipated expansion and contraction at each support point, initial and final loads on building structure, spring deflection changes, and seismic loads. Include certification that riser system was examined for excessive stress and that none exists.
  - 4. Seismic-Restraint Details:
    - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads.
    - b. Details: Indicate fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events. Indicate association with vibration isolation devices.
    - c. Coordinate seismic-restraint and vibration isolation details with wind-restraint details required for equipment mounted outdoors. Comply with requirements in other Sections for equipment mounted outdoors.
    - d. Preapproval and Evaluation Documentation: By an agency acceptable to authorities having jurisdiction, showing maximum ratings of restraint items and the basis for approval (tests or calculations).

# 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show coordination of vibration isolation device installation and seismic bracing for plumbing piping and equipment with other systems and equipment in the vicinity, including other supports and restraints, if any.
- B. Qualification Data: For professional engineer and testing agency.

- C. Welding certificates.
- D. Field quality-control reports.

# 1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is an NRTL as defined by OSHA in 29 CFR 1910.7 and that is acceptable to authorities having jurisdiction.
- B. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.
- C. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."
- D. Seismic-restraint devices shall have horizontal and vertical load testing and analysis and shall bear anchorage preapproval OPA number from OSHPD, preapproval by ICC-ES, or preapproval by another agency acceptable to authorities having jurisdiction, showing maximum seismic-restraint ratings. Ratings based on independent testing are preferred to ratings based on calculations. If preapproved ratings are unavailable, submittals based on independent testing are preferred. Calculations (including combining shear and tensile loads) to support seismicrestraint designs must be signed and sealed by a qualified professional engineer.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Seismic-Restraint Loading:
  - 1. Site Class as Defined in the IBC: See S0.1.
  - 2. Assigned Seismic Use Group or Building Category as Defined in the IBC: See S0.1.
    - a. Component Importance Factor: 1.0.
    - b. Component Response Modification Factor: Refer to ASCE Standard 7-10, Chapter 13.
    - c. Component Amplification Factor: Refer to ASCE Standard 7-10, Chapter 13.
  - 3. Design Spectral Response Acceleration at Short Periods (0.2 Second): See S0.1.
  - 4. Design Spectral Response Acceleration at 1.0-Second Period: See S0.1.
  - 5. Rated strengths, features, and applications shall be as defined in reports by an agency acceptable to authorities having jurisdiction.
    - a. Structural Safety Factor: Allowable strength in tension, shear, and pullout force of components shall be at least four times the maximum seismic forces to which they are subjected.

## 2.2 RESTRAINT CHANNEL BRACINGS

A. Description: MFMA-4, shop- or field-fabricated bracing assembly made of slotted steel channels with accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; rated in tension, compression, and torsion forces.

## 2.3 RESTRAINT CABLES

A. Restraint Cables: ASTM A 603 galvanized-steel cables. End connections made of steel assemblies with thimbles, brackets, swivel, and bolts designed for restraining cable service; with a minimum of two clamping bolts for cable engagement.

#### 2.4 SEISMIC-RESTRAINT ACCESSORIES

- A. Hanger-Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections to hanger rod.
- B. Hinged and Swivel Brace Attachments: Multifunctional steel connectors for attaching hangers to rigid channel bracings.
- C. Bushings for Floor-Mounted Equipment Anchor Bolts: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchor bolts and studs.
- D. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices used.
- E. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.

# 2.5 MECHANICAL ANCHOR BOLTS

A. Mechanical Anchor Bolts: Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

A. Examine areas and equipment to receive vibration isolation and seismic-control devices for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 APPLICATIONS

- A. Multiple Pipe Supports: Secure pipes to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.
- B. Hanger-Rod Stiffeners: Install hanger-rod stiffeners where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods due to seismic forces.
- C. Strength of Support and Seismic-Restraint Assemblies: Where not indicated, select sizes of components so strength is adequate to carry present and future static and seismic loads within specified loading limits.

# 3.3 VIBRATION CONTROL AND SEISMIC-RESTRAINT DEVICE INSTALLATION

- A. Installation of vibration isolators must not cause any change of position of equipment, piping, or ductwork resulting in stresses or misalignment.
- B. Comply with requirements in Section 077200 "Roof Accessories" for installation of roof curbs, equipment supports, and roof penetrations.
- C. Equipment Restraints:
  - 1. Install seismic snubbers on plumbing equipment mounted on vibration isolators. Locate snubbers as close as possible to vibration isolators and bolt to equipment base and supporting structure.
  - 2. Install resilient bolt isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
  - 3. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction that provides required submittals for component.
- D. Piping Restraints:
  - 1. Comply with requirements in MSS SP-127.
  - 2. Space lateral supports a maximum of 40 feet o.c., and longitudinal supports a maximum of 80 feet o.c.
  - 3. Brace a change of direction longer than 12 feet.
- E. Install cables so they do not bend across edges of adjacent equipment or building structure.
- F. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction that provides required submittals for component.

- G. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.
- H. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- I. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.
- J. Drilled-in Anchors:
  - 1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify the structural engineer if reinforcing steel or other embedded items are encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
  - 2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
  - 3. Wedge Anchors: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
  - 4. Adhesive Anchors: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
  - 5. Set anchors to manufacturer's recommended torque, using a torque wrench.
  - 6. Install zinc-coated steel anchors for interior and stainless-steel anchors for exterior applications.

# 3.4 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

A. Install flexible connections in piping where they cross seismic joints, where adjacent sections or branches are supported by different structural elements, and where the connections terminate with connection to equipment that is anchored to a different structural element from the one supporting the connections as they approach equipment. Comply with requirements in Section 221116 "Domestic Water Piping" for piping flexible connections.

# 3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Perform tests and inspections.
- C. Tests and Inspections:
  - 1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.

- 2. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
- 3. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
- 4. Test at least four of each type and size of installed anchors and fasteners selected by Architect.
- 5. Test to 90 percent of rated proof load of device.
- 6. Measure isolator restraint clearance.
- 7. Measure isolator deflection.
- 8. Verify snubber minimum clearances.
- D. Remove and replace malfunctioning units and retest as specified above.
- E. Prepare test and inspection reports.

# 3.6 ADJUSTING

- A. Adjust isolators after piping system is at operating weight.
- B. Adjust limit stops on restrained-spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.

# END OF SECTION 220548
# SECTION 220553 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Equipment labels.
  - 2. Warning signs and labels.
  - 3. Pipe labels.
  - 4. Valve tags.
  - 5. Warning tags.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- D. Valve numbering scheme.
- E. Valve Schedules: For each piping system to include in maintenance manuals.

# PART 2 - PRODUCTS

### 2.1 EQUIPMENT LABELS

- A. Metal Labels for Equipment:
  - 1. Material and Thickness: Brass, 0.032-inch stainless steel, 0.025-inch or anodized aluminum, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.

### IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

220553 - 1

- 2. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- 3. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- 4. Fasteners: Stainless-steel rivets.
- 5. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- B. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), and the Specification Section number and title where equipment is specified.
- C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number, and identify Drawing numbers where equipment is indicated (plans, details, and schedules) and the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

# 2.2 WARNING SIGNS AND LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
- B. Letter Color: Black, Uppercase.
- C. Background Color: White.
- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- G. Fasteners: Stainless-steel rivets.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Label Content: Include caution and warning information plus emergency notification instructions.

## 2.3 PIPE LABELS

- A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.
- B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.
- C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.
- D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings; also include pipe size and an arrow indicating flow direction.
  - 1. Flow-Direction Arrows: Integral with piping-system service lettering to accommodate both directions or as separate unit on each pipe label to indicate flow direction.

## 2.4 VALVE TAGS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
  - 1. Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
  - 2. Fasteners: Brass wire-link chain.
- B. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.
  - 1. Valve-tag schedule shall be included in operation and maintenance data.

### 2.5 WARNING TAGS

- A. Description: Preprinted or partially preprinted accident-prevention tags of plasticized card stock with matte finish suitable for writing.
  - 1. Size: Approximately 4 by 7 inches.
  - 2. Fasteners: Reinforced grommet and wire or string.
  - 3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
  - 4. Color: Safety yellow background with black lettering.

# PART 3 - EXECUTION

#### 3.1 PREPARATION

A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

# 3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

### 3.3 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

#### 3.4 PIPE LABEL INSTALLATION

- A. Piping Color Coding: Painting of piping is specified in Section 099123 "Interior Painting."
- B. Stenciled Pipe Label Option: Stenciled labels may be provided instead of manufactured pipe labels, at Installer's option. Install stenciled pipe labels, complying with ASME A13.1, with painted, color-coded bands or rectangles on each piping system.
  - 1. Identification Paint: Use for contrasting background.
  - 2. Stencil Paint: Use for pipe marking.
- C. Pipe Label Locations: Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
  - 1. Near each valve and control device.
  - 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
  - 3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
  - 4. At access doors, manholes, and similar access points that permit view of concealed piping.
  - 5. Near major equipment items and other points of origination and termination.

# IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

220553 - 4

- 6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
- 7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.
- D. Directional Flow Arrows: Arrows shall be used to indicate direction of flow in pipes, including pipes where flow is allowed in both directions.
- E. Pipe Label Color Schedule:
  - 1. Domestic Water Piping
    - a. Background: Safety green.
    - b. Letter Colors: White.
  - 2. Sanitary Waste and vent, and Storm Drainage Piping:
    - a. Background Color: Safety white.
    - b. Letter Color: Black.

# 3.5 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in piping systems, except check valves, valves within factory-fabricated equipment units, shutoff valves, faucets, convenience and lawn-watering hose connections, and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:
  - 1. Valve-Tag Size and Shape:
    - a. Cold Water: 2 inches, round.
    - b. Hot Water: 2 inches, round.
  - 2. Valve-Tag Colors:
    - a. Cold Water: Natural.
    - b. Hot Water: Natural.
  - 3. Letter Colors:
    - a. Cold Water: Black.
    - b. Hot Water: Black.
- C. All valves above ceilings require labels clearly marked on the ceiling grid or access panel with a printed label.

### 3.6 WARNING-TAG INSTALLATION

A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION 220553

IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

# SECTION 220719 - PLUMBING PIPING INSULATION

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section includes insulating the following plumbing piping services:
  - 1. Domestic cold-water piping.
  - 2. Domestic hot-water piping.
  - 3. Domestic recirculating hot-water piping.
  - 4. Supplies and drains for handicap-accessible lavatories and sinks.

# 1.3 SUBMITTALS

A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory- and field-applied, if any).

#### 1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84 by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
  - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
  - 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.
- C. Comply with the following applicable standards and other requirements specified for miscellaneous components:
  - 1. Supply and Drain Protective Shielding Guards: ICC A117.1.

### 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.
- B. Materials on site shall be stored inside, protected from weather conditions and shall not be subjected to direct, or indirect, moisture. Any insulation which has been subjected to moisture shall be removed from site and shall not be used.

### 1.6 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment."
- B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.
- C. Coordinate installation and testing of heat tracing.

#### 1.7 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

#### PART 2 - PRODUCTS

#### 2.1 INSULATION MATERIALS

- A. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule," "Outdoor, Aboveground Piping Insulation Schedule," and "Outdoor, Underground Piping Insulation Schedule" articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.

- E. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type I. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. CertainTeed Corp.; SoftTouch Duct Wrap.
    - b. Johns Manville; Microlite.
    - c. Knauf Insulation; Friendly Feel Duct Wrap.
    - d. Manson Insulation Inc.; Alley Wrap.
    - e. Owens Corning; SOFTR All-Service Duct Wrap.
- F. Mineral-Fiber, Preformed Pipe Insulation:
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Fibrex Insulations Inc.; Coreplus 1200.
    - b. Johns Manville; Micro-Lok.
    - c. Knauf Insulation; 1000-Degree Pipe Insulation.
    - d. Manson Insulation Inc.; Alley-K.
    - e. Owens Corning; Fiberglas Pipe Insulation.
  - 2. Type I, 850 Deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A, with factory-applied ASJ. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

# 2.2 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated, unless otherwise indicated.
- B. Flexible Elastomeric and Polyolefin Adhesive: Comply with MIL-A-24179A, Type II, Class I.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Aeroflex USA, Inc.; Aeroseal.
    - b. Armacell LLC; Armaflex 520 Adhesive.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-75.
    - d. K-Flex USA; R-373 Contact Adhesive.
  - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Use adhesive that complies with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers," including 2004 Addenda.

C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.

- 1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-127.
  - b. Eagle Bridges Marathon Industries; 225.
  - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-60/85-70.
  - d. Mon-Eco Industries, Inc.; 22-25.
- 2. For indoor applications, use adhesive that has a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- 3. Use adhesive that complies with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers," including 2004 Addenda.
- D. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-82.
    - b. Eagle Bridges Marathon Industries; 225.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-20.
    - d. Mon-Eco Industries, Inc.; 22-25.
  - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Use adhesive that complies with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers," including 2004 Addenda.
- E. PVC Jacket Adhesive: Compatible with PVC jacket.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Dow Corning Corporation; 739, Dow Silicone.
    - b. Johns Manville; Zeston Perma-Weld, CEEL-TITE Solvent Welding Adhesive.
    - c. P.I.C. Plastics, Inc.; Welding Adhesive.
    - d. Speedline Corporation; Polyco VP Adhesive.
  - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Use adhesive that complies with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers," including 2004 Addenda.

### 2.3 SEALANTS

- A. FSK and Metal Jacket Flashing Sealants:
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-76.
    - b. Eagle Bridges Marathon Industries; 405.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 95-44.
    - d. Mon-Eco Industries, Inc.; 44-05.
  - 2. Materials shall be compatible with insulation materials, jackets, and substrates.
  - 3. Fire- and water-resistant, flexible, elastomeric sealant.
  - 4. Service Temperature Range: Minus 40 to plus 250 deg F (Minus 40 to plus 121 deg C).
  - 5. Color: Aluminum.
  - 6. For indoor applications, use sealants that have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 7. Use sealants that comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers," including 2004 Addenda.
- B. ASJ Flashing Sealants, and Vinyl, PVDC, and PVC Jacket Flashing Sealants:
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-76.
  - 2. Materials shall be compatible with insulation materials, jackets, and substrates.
  - 3. Fire- and water-resistant, flexible, elastomeric sealant.
  - 4. Service Temperature Range: Minus 40 to plus 250 deg F (Minus 40 to plus 121 deg C).
  - 5. Color: White.
  - 6. For indoor applications, use sealants that have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 7. Use sealants that comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers," including 2004 Addenda.

# 2.4 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
  - 1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.

# 2.5 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.
- B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Johns Manville; Zeston.
    - b. P.I.C. Plastics, Inc.; FG Series.
    - c. Proto Corporation; LoSmoke.
    - d. Speedline Corporation; SmokeSafe.
  - 2. Adhesive: As recommended by jacket material manufacturer.
  - 3. Color: White.
  - 4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
    - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

### 2.6 TAPES

- A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ABI, Ideal Tape Division; 428 AWF ASJ.
    - b. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0836.
    - c. Compac Corporation; 104 and 105.
    - d. Venture Tape; 1540 CW Plus, 1542 CW Plus, and 1542 CW Plus/SQ.
  - 2. Width: 3 inches.
  - 3. Thickness: 11.5 mils.
  - 4. Adhesion: 90 ounces force/inch in width.
  - 5. Elongation: 2 percent.
  - 6. Tensile Strength: 40 lbf/inch in width.
  - 7. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.
- B. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ABI, Ideal Tape Division; 370 White PVC tape.
    - b. Compac Corporation; 130.

#### PLUMBING PIPING INSULATION

220719 - 6

- c. Venture Tape; 1506 CW NS.
- 2. Width: 2 inches.
- 3. Thickness: 6 mils.
- 4. Adhesion: 64 ounces force/inch in width.
- 5. Elongation: 500 percent.
- 6. Tensile Strength: 18 lbf/inch in width.

#### 2.7 SECUREMENTS

- A. Bands:
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ITW Insulation Systems; Gerrard Strapping and Seals.
    - b. RPR Products, Inc.; Insul-Mate Strapping and Seals.
  - 2. Stainless Steel: ASTM A 167 or ASTM A 240/A 240M, Type 304 or Type 316; 0.015 inch thick, 1/2 inch wide with wing seal or closed seal.
  - 3. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 1/2 inch wide with wing seal or closed seal.
- B. Staples: Outward-clinching insulation staples, nominal 3/4-inch- wide, stainless steel or Monel.
- C. Wire: 0.080-inch nickel-copper alloy.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. C & F Wire.
    - b. Childers Products.

# 2.8 PROTECTIVE SHIELDING GUARDS

- A. Protective Shielding Pipe Covers:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Engineered Brass Company.
    - b. Insul-Tect Products Co.; a subsidiary of MVG Molded Products.
    - c. McGuire Manufacturing.
    - d. Plumberex.
    - e. Truebro; a brand of IPS Corporation.
    - f. Zurn Industries, LLC; Tubular Brass Plumbing Products Operation.

- 2. Description: Manufactured plastic piping covers for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with Americans with Disabilities Act (ADA) requirements.
  - a. Material: Rigid, high impact stain resistant PVC, 0.125 in wall thickness.
  - b. Burning Characteristics: ASTM D-635 Self extinguished Self extinguished 0 sec (ATB) mm (AEB).
  - c. Bacteria/Fungus Resistance: 0 growth when tested in accordance with ASTM G21 and G22.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
  - 1. Verify that systems to be insulated have been tested and are free of defects.
  - 2. Verify that surfaces to be insulated are clean and dry.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Surface Preparation: Clean and prepare surfaces to be insulated. Before insulating, apply a corrosion coating to insulated surfaces as follows:
  - 1. Carbon Steel: Coat carbon steel operating at a service temperature between 32 and 300 deg F (0 and 149 deg C) with an epoxy coating. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
- C. Coordinate insulation installation with the trade installing heat tracing. Comply with requirements for heat tracing that apply to insulation.
- D. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless-steel surfaces, use demineralized water.

# 3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.
- B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of pipe system as specified in insulation system schedules.

- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- G. Keep insulation materials dry during application and finishing.
- H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- I. Install insulation with least number of joints practical.
- J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  - 1. Install insulation continuously through hangers and around anchor attachments.
  - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
  - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- L. Install insulation with factory-applied jackets as follows:
  - 1. Draw jacket tight and smooth.
  - 2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
  - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.
    - a. For below-ambient services, apply vapor-barrier mastic over staples.
  - 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.

- M. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches (100 mm) beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- P. For above-ambient services, do not install insulation to the following:
  - 1. Vibration-control devices.
  - 2. Testing agency labels and stamps.
  - 3. Nameplates and data plates.
  - 4. Cleanouts.

### 3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches (50 mm) below top of roof flashing.
  - 4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.
- C. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches (50 mm).
  - 4. Seal jacket to wall flashing with flashing sealant.
- D. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.

- E. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.
  - 1. Comply with requirements in Division 07 Section "Penetration Firestopping" for firestopping and fire-resistive joint sealers.
- F. Insulation Installation at Floor Penetrations:
  - 1. Pipe: Install insulation continuously through floor penetrations.
  - 2. Seal penetrations through fire-rated assemblies. Comply with requirements in Division 07 Section "Penetration Firestopping."

### 3.5 GENERAL PIPE INSULATION INSTALLATION

- A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:
  - 1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
  - 2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
  - 3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
  - 4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
  - 5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
  - 6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.

- 7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
- 8. For services not specified to receive a field-applied jacket except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
- 9. Stencil or label the outside insulation jacket of each union with the word "union." Match size and color of pipe labels.
- C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.
- D. Install removable insulation covers at locations indicated. Installation shall conform to the following:
  - 1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
  - 2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.
  - 3. Construct removable valve insulation covers in same manner as for flanges, except divide the two-part section on the vertical center line of valve body.
  - 4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches (50 mm) over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
  - 5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

# 3.6 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

- A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- B. Insulation Installation on Pipe Flanges:
  - 1. Install pipe insulation to outer diameter of pipe flange.
  - 2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.

- 3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
- 4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- C. Insulation Installation on Pipe Fittings and Elbows:
  - 1. Install mitered sections of pipe insulation.
  - 2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- D. Insulation Installation on Valves and Pipe Specialties:
  - 1. Install preformed valve covers manufactured of same material as pipe insulation when available.
  - 2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
  - 3. Install insulation to flanges as specified for flange insulation application.
  - 4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

# 3.7 INSTALLATION OF MINERAL-FIBER INSULATION

- A. Insulation Installation on Straight Pipes and Tubes:
  - 1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
  - 2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
  - 3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward clinched staples at 6 inches o.c.
  - 4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.
- B. Insulation Installation on Pipe Flanges:
  - 1. Install preformed pipe insulation to outer diameter of pipe flange.
  - 2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
  - 3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
  - 4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch (25 mm), and seal joints with flashing sealant.

- C. Insulation Installation on Pipe Fittings and Elbows:
  - 1. Install preformed sections of same material as straight segments of pipe insulation when available.
  - 2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.
- D. Insulation Installation on Valves and Pipe Specialties:
  - 1. Install preformed sections of same material as straight segments of pipe insulation when available.
  - 2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
  - 3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
  - 4. Install insulation to flanges as specified for flange insulation application.

# 3.8 FIELD-APPLIED JACKET INSTALLATION

- A. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints. Seal with manufacturer's recommended adhesive.
  - 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

# 3.9 FINISHES

- A. Insulation with ASJ, Glass-Cloth, or Other Paintable Jacket Material: Paint jacket with paint system identified below and as specified in Division 09 painting Sections.
  - 1. Flat Acrylic Finish: Two finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.
    - a. Finish Coat Material: Interior, flat, latex-emulsion size.
- B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.
- C. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.

# 3.10 FIELD QUALITY CONTROL

A. Perform tests and inspections.

# B. Tests and Inspections:

- 1. Inspect pipe, fittings, strainers, and valves, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to three locations of straight pipe and fittings, two locations of strainers, and three locations of valves for each pipe service defined in the "Piping Insulation Schedule, General" Article.
- C. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

# 3.11 PIPING INSULATION SCHEDULE, GENERAL

- A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.
- B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
  - 1. Drainage piping located in crawl spaces.
  - 2. Underground piping.
  - 3. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

# 3.12 INDOOR PIPING INSULATION SCHEDULE

- A. Domestic Cold Water:
  - 1. NPS 1-1/4 and Smaller Insulation shall be:
    - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1/2 inch thick.
  - 2. NPS 1-1/2 and Larger Insulation shall be:
    - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
- B. Domestic Hot and Recirculated Hot Water (Potable):
  - 1. NPS 1-1/4 and Smaller Insulation shall be:
    - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
  - 2. NPS 1-1/2 and Larger Insulation shall be:
    - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1-1/2 inch thick.
- C. Exposed Sanitary Drains, Domestic Water, Domestic Hot Water, and Stops for Plumbing Fixtures for People with Disabilities:

1. All Pipe Sizes: Insulation shall be protective shielding guards.

### 3.13 INDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Piping, Concealed:
  - 1. None.
- D. Piping, Exposed, Including Valves:
  - 1. PVC 20 mils thick, within 96 inches of finished floor and areas subject to abuse.

END OF SECTION 220719

# SECTION 221116 - DOMESTIC WATER PIPING

### PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

#### A. Section Includes:

- 1. Copper tube and fittings.
- 2. Piping joining materials.
- 3. Encasement for piping.
- 4. Transition fittings.
- 5. Dielectric fittings.

#### 1.3 ACTION SUBMITTALS

A. Product Data: For transition fittings and dielectric fittings.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. System purging and disinfecting activities report.
- B. Field quality-control reports.

#### 1.5 FIELD CONDITIONS

- A. Interruption of Existing Water Service: Do not interrupt water service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary water service according to requirements indicated:
  - 1. Notify Architect no fewer than two days in advance of proposed interruption of water service.
  - 2. Do not interrupt water service without Architect's written permission.

# PART 2 - PRODUCTS

#### 2.1 PIPING MATERIALS

- A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.
- B. Potable-water piping and components shall comply with NSF 14 and NSF 61 Annex G. Plastic piping components shall be marked with "NSF-pw."
- C. Comply with NSF 372 for low lead.

## 2.2 COPPER TUBE AND FITTINGS

- A. Hard Copper Tube: ASTM B 88, Type L water tube, drawn temper.
- B. Soft Copper Tube: ASTM B 88, Type K water tube, annealed temper.
- C. Cast-Copper, Solder-Joint Fittings: ASME B16.18, pressure fittings.
- D. Wrought-Copper, Solder-Joint Fittings: ASME B16.22, wrought-copper pressure fittings.
- E. Bronze Flanges: ASME B16.24, Class 150, with solder-joint ends.
- F. Copper Unions:
  - 1. MSS SP-123.
  - 2. Cast-copper-alloy, hexagonal-stock body.
  - 3. Ball-and-socket, metal-to-metal seating surfaces.
  - 4. Solder-joint or threaded ends.

### 2.3 PIPING JOINING MATERIALS

- A. Pipe-Flange Gasket Materials:
  - 1. AWWA C110/A21.10, rubber, flat face, 1/8 inch thick or ASME B16.21, nonmetallic and asbestos free unless otherwise indicated.
  - 2. Full-face or ring type unless otherwise indicated.
- B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.
- C. Brazing Filler Metals: AWS A5.8M/A5.8, BCuP Series, copper-phosphorus alloys for generalduty brazing unless otherwise indicated.

# 2.4 TRANSITION FITTINGS

- A. General Requirements:
  - 1. Same size as pipes to be joined.
  - 2. Pressure rating at least equal to pipes to be joined.
  - 3. End connections compatible with pipes to be joined.
- B. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.

# 2.5 DIELECTRIC FITTINGS

- A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.
- B. Dielectric Unions:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Capitol Manufacturing Company.
    - b. Jomar Valve.
    - c. WATTS.
  - 2. Standard: ASSE 1079.
  - 3. Pressure Rating: 150 psig.
  - 4. End Connections: Solder-joint copper alloy and threaded ferrous.
- C. Dielectric Flanges:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Capitol Manufacturing Company.
    - b. Central Plastics Company.
    - c. WATTS.
  - 2. Standard: ASSE 1079.
  - 3. Factory-fabricated, bolted, companion-flange assembly.
  - 4. Pressure Rating: 150 psig.
  - 5. End Connections: Solder-joint copper alloy and threaded ferrous; threaded solder-joint copper alloy and threaded ferrous.
- D. Dielectric-Flange Insulating Kits:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

# DOMESTIC WATER PIPING

- a. Advance Products & Systems, Inc.
- b. Calpico, Inc.
- c. Central Plastics Company.
- d. Pipeline Seal and Insulator, Inc.
- 2. Nonconducting materials for field assembly of companion flanges.
- 3. Pressure Rating: 150 psig.
- 4. Gasket: Neoprene or phenolic.
- 5. Bolt Sleeves: Phenolic or polyethylene.
- 6. Washers: Phenolic with steel backing washers.
- E. Dielectric Nipples:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Grinnell Mechanical Products.
    - b. Matco-Norca.
    - c. Precision Plumbing Products.
  - 2. Standard: IAPMO PS 66.
  - 3. Electroplated steel nipple complying with ASTM F 1545.
  - 4. Pressure Rating and Temperature: 300 psig at 225 deg F.
  - 5. End Connections: Male threaded or grooved.
  - 6. Lining: Inert and noncorrosive, propylene.

# PART 3 - EXECUTION

#### 3.1 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install copper tubing under building slab according to CDA's "Copper Tube Handbook."
- C. Install underground copper tube in PE encasement according to ASTM A 674 or AWWA C105/A21.5.
- D. Install shutoff valve, hose-end drain valve, strainer, pressure gage, and test tee with valve inside the building at each domestic water-service entrance. Comply with requirements for drain valves and strainers in Section 221119 "Domestic Water Piping Specialties."
- E. Install shutoff valve immediately upstream of each dielectric fitting.

- F. Install water-pressure-reducing valves downstream from shutoff valves. Comply with requirements for pressure-reducing valves in Section 221119 "Domestic Water Piping Specialties."
- G. Install domestic water piping level with 0.25 percent slope downward toward drain and plumb.
- H. Install seismic restraints on piping. Comply with requirements for seismic-restraint devices in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- I. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- J. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- K. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.
- L. Install piping to permit valve servicing.
- M. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than the system pressure rating used in applications below unless otherwise indicated.
- N. Install piping free of sags and bends.
- O. Install fittings for changes in direction and branch connections.
- P. Install unions in copper tubing at final connection to each piece of equipment, machine, and specialty.
- Q. Install thermostats in hot-water circulation piping.

### 3.2 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- C. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.

- D. Brazed Joints for Copper Tubing: Comply with CDA's "Copper Tube Handbook," "Brazed Joints" chapter.
- E. Soldered Joints for Copper Tubing: Apply ASTM B 813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B 828 or CDA's "Copper Tube Handbook."
- F. Flanged Joints: Select appropriate asbestos-free, nonmetallic gasket material in size, type, and thickness suitable for domestic water service. Join flanges with gasket and bolts according to ASME B31.9.
- G. Joints for Dissimilar-Material Piping: Make joints using adapters compatible with materials of both piping systems.
- 3.3 TRANSITION FITTING INSTALLATION
  - A. Install transition couplings at joints of dissimilar piping.
  - B. Transition Fittings in Underground Domestic Water Piping:
    - 1. Fittings for NPS 1-1/2 and Smaller: Fitting-type coupling.
    - 2. Fittings for NPS 2 and Larger: Sleeve-type coupling.
  - C. Transition Fittings in Aboveground Domestic Water Piping NPS 2 and Smaller: Plastic-to-metal transition fittings.

#### 3.4 DIELECTRIC FITTING INSTALLATION

- A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.
- B. Dielectric Fittings for NPS 2 and Smaller: Use dielectric nipples.
- C. Dielectric Fittings for NPS 2-1/2 to NPS 4: Use dielectric flanges.

#### 3.5 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements for seismic-restraint devices in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- B. Comply with requirements for pipe hanger, support products, and installation in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."
  - 1. Vertical Piping: MSS Type 8 or 42, clamps.
  - 2. Individual, Straight, Horizontal Piping Runs:
    - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    - c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.

#### DOMESTIC WATER PIPING

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
- 4. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Support vertical piping and tubing at base and at each floor.
- D. Rod diameter may be reduced one size for double-rod hangers, to a minimum of 3/8 inch.
- E. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 3/4 and Smaller: 60 inches with 3/8-inch rod.
  - 2. NPS 1 and NPS 1-1/4: 72 inches with 3/8-inch rod.
  - 3. NPS 1-1/2 and NPS 2: 96 inches with 3/8-inch rod.
  - 4. NPS 2-1/2: 108 inches with 1/2-inch rod.
  - 5. NPS 3 to NPS 5: 10 feet with 1/2-inch rod.
  - 6. NPS 6: 10 feet with 5/8-inch rod.
  - 7. NPS 8: 10 feet with 3/4-inch rod.
- F. Install supports for vertical copper tubing every 10 feet.
- G. Support piping and tubing not listed in this article according to MSS SP-58 and manufacturer's written instructions.
- 3.6 CONNECTIONS
  - A. Drawings indicate general arrangement of piping, fittings, and specialties.
  - B. When installing piping adjacent to equipment and machines, allow space for service and maintenance.
  - C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.
  - D. Connect domestic water piping to water-service piping with shutoff valve; extend and connect to the following:
    - 1. Water Heaters: Cold-water inlet and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.
    - 2. Plumbing Fixtures: Cold- and hot-water-supply piping in sizes indicated, but not smaller than that required by plumbing code.
    - 3. Equipment: Cold- and hot-water-supply piping as indicated, but not smaller than equipment connections. Provide shutoff valve and union for each connection. Use flanges instead of unions for NPS 2-1/2 and larger.

# 3.7 IDENTIFICATION

- A. Identify system components. Comply with requirements for identification materials and installation in Section 220553 "Identification for Plumbing Piping and Equipment."
- B. Label pressure piping with system operating pressure.

# 3.8 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
  - 1. Piping Inspections:
    - a. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.
    - b. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:
      - 1) Roughing-in Inspection: Arrange for inspection of piping before concealing or closing in after roughing in and before setting fixtures.
      - 2) Final Inspection: Arrange for authorities having jurisdiction to observe tests specified in "Piping Tests" Subparagraph below and to ensure compliance with requirements.
    - c. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.
    - d. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
  - 2. Piping Tests:
    - a. Fill domestic water piping. Check components to determine that they are not air bound and that piping is full of water.
    - b. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit a separate report for each test, complete with diagram of portion of piping tested.
    - c. Leave new, altered, extended, or replaced domestic water piping uncovered and unconcealed until it has been tested and approved. Expose work that was covered or concealed before it was tested.
    - d. Cap and subject piping to static water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials. Isolate test source and allow it to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.
    - e. Repair leaks and defects with new materials, and retest piping or portion thereof until satisfactory results are obtained.
    - f. Prepare reports for tests and for corrective action required.

B. Domestic water piping will be considered defective if it does not pass tests and inspections.
DOMESTIC WATER PIPING 221116 - 8

C. Prepare test and inspection reports.

### 3.9 ADJUSTING

- A. Perform the following adjustments before operation:
  - 1. Close drain valves, hydrants, and hose bibbs.
  - 2. Open shutoff valves to fully open position.
  - 3. Open throttling valves to proper setting.
  - 4. Adjust balancing valves in hot-water-circulation return piping to provide adequate flow.
    - a. Manually adjust ball-type balancing valves in hot-water-circulation return piping to provide hot-water flow in each branch.
    - b. Adjust calibrated balancing valves to flows indicated.
  - 5. Remove plugs used during testing of piping and for temporary sealing of piping during installation.
  - 6. Remove and clean strainer screens. Close drain valves and replace drain plugs.
  - 7. Remove filter cartridges from housings and verify that cartridges are as specified for application where used and are clean and ready for use.
  - 8. Check plumbing specialties and verify proper settings, adjustments, and operation.

#### 3.10 CLEANING

- A. Clean and disinfect potable domestic water piping as follows:
  - 1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
  - 2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction; if methods are not prescribed, use procedures described in either AWWA C651 or AWWA C652 or follow procedures described below:
    - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
    - b. Fill and isolate system according to either of the following:
      - 1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.
      - 2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for three hours.
    - c. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
    - d. Repeat procedures if biological examination shows contamination.
    - e. Submit water samples in sterile bottles to authorities having jurisdiction.
- B. Clean non-potable domestic water piping as follows:

#### DOMESTIC WATER PIPING

- 1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
- 2. Use purging procedures prescribed by authorities having jurisdiction or; if methods are not prescribed, follow procedures described below:
  - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
  - b. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedures if biological examination shows contamination.
- C. Prepare and submit reports of purging and disinfecting activities. Include copies of watersample approvals from authorities having jurisdiction.
- D. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.

# 3.11 PIPING SCHEDULE

- A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.
- B. Flanges and unions may be used for aboveground piping joints unless otherwise indicated.
- C. Fitting Option: Extruded-tee connections and brazed joints may be used on aboveground copper tubing.
- D. Under-building-slab, domestic water, building-service piping, NPS 3 and smaller, shall be the following:
  - 1. Soft copper tube, ASTM B 88, Type K; wrought-copper, solder-joint fittings; and brazed joints.
- E. Under-building-slab, domestic water piping, NPS 2 and smaller, shall be the following:
  - 1. soft copper tube, ASTM B 88, Type K; wrought-copper, solder-joint fittings; and brazed joints.
- F. Aboveground exposed domestic water piping, NPS 2 and smaller, shall be the following:
  - 1. Hard copper tube, ASTM B 88, Type L; cast- or wrought-copper, solder-joint fittings; and soldered joints.
- G. Aboveground concealed domestic water piping, NPS 2 and smaller, shall be one of the following:
  - 1. Hard copper tube, ASTM B 88, Type L; cast- or wrought-copper, solder-joint fittings; and soldered joints.
- H. Aboveground domestic water piping, NPS 2-1/2 to NPS 4, shall be the following:

#### DOMESTIC WATER PIPING

1. Hard copper tube, ASTM B 88, Type L (ASTM B 88M, Type B); cast- or wrought-copper, solder-joint fittings; and soldered joints.

## 3.12 VALVE SCHEDULE

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
  - 1. Shutoff Duty: Use ball or gate valves for piping NPS 2 and smaller. Use butterfly, ball, or gate valves with flanged ends for piping NPS 2-1/2 and larger.
  - 2. Throttling Duty: Use ball or globe valves for piping NPS 2 and smaller. Use ball valves with flanged ends for piping NPS 2-1/2 and larger.
  - 3. Hot-Water Circulation Piping, Balancing Duty: Calibrated balancing valves.
  - 4. Drain Duty: Hose-end drain valves.
- B. Use check valves to maintain correct direction of domestic water flow to and from equipment.

END OF SECTION 221116

# SECTION 221119 - DOMESTIC WATER PIPING SPECIALTIES

## PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Vacuum breakers.
  - 2. Strainers.
  - 3. Trap-seal primer systems.
- B. Related Requirements:
  - 1. Section 221116 "Domestic Water Piping" for water meters.

### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For domestic water piping specialties.
  - 1. Include diagrams for power, signal, and control wiring.

### 1.4 INFORMATIONAL SUBMITTALS

A. Field quality-control reports.

# 1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For domestic water piping specialties to include in emergency, operation, and maintenance manuals.

DOMESTIC WATER PIPING SPECIALTIES

# PART 2 - PRODUCTS

## 2.1 GENERAL REQUIREMENTS FOR PIPING SPECIALTIES

- A. Potable-water piping and components shall comply with NSF 61 and NSF 14.
- B. Comply with NSF 372 for low lead.

### 2.2 PERFORMANCE REQUIREMENTS

A. Minimum Working Pressure for Domestic Water Piping Specialties: 125 (860) psig (kPa) unless otherwise indicated.

### 2.3 VACUUM BREAKERS

- A. Pipe-Applied, Atmospheric-Type Vacuum Breakers:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Ames. Co.
    - b. Cash ACME.
    - c. Conbraco Industries, Inc.
    - d. FEBCO; SPX Valves & Controls.
    - e. Watts Industries, Inc.; Water Products Div.
    - f. Zurn Plumbing Products Group; Wilkins Div.
  - 2. Standard: ASSE 1001.
  - 3. Size: NPS 1/4 to NPS 3 (DN 8 to DN 80), as required to match connected piping.
  - 4. Body: Bronze.
  - 5. Inlet and Outlet Connections: Threaded.
  - 6. Finish: Rough bronze or Chrome plated.
- B. Hose-Connection Vacuum Breakers:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. MIFAB, Inc.
    - b. Watts Industries, Inc.; Water Products Div.
    - c. Woodford Manufacturing Company.
    - d. Zurn Plumbing Products Group; Light Commercial Operation.
    - e. Zurn Plumbing Products Group; Wilkins Div.
  - 2. Standard: ASSE 1011.
  - 3. Body: Bronze, nonremovable, with manual drain.
  - 4. Outlet Connection: Garden-hose threaded complying with ASME B1.20.7.

# DOMESTIC WATER PIPING SPECIALTIES

221119 - 2

5. Finish: Chrome or nickel plated or Rough bronze.

## 2.4 BALANCING VALVES

- A. Copper-Alloy Calibrated Balancing Valves:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. ITT Industries; Bell & Gossett Div.
    - b. NIBCO, Inc.
  - 2. Type: Ball valve with two readout ports and memory-setting indicator.
  - 3. Body: Brass.
  - 4. Size: Same as connected piping, but not larger than NPS 2 (DN 50).
  - 5. Accessories: Meter hoses, fittings, valves, differential pressure meter, and carrying case.
  - 6. Valve shall be certified lead-free.

# 2.5 STRAINERS FOR DOMESTIC WATER PIPING

- A. Y-Pattern Strainers:
  - 1. Pressure Rating: 125 psig (860 kPa) minimum unless otherwise indicated.
  - 2. Body: Bronze for NPS 2 (DN 50) and smaller; cast iron with interior lining that complies with AWWA C550 or that is FDA approved, epoxy coated and for NPS 2-1/2 (DN 65) and larger.
  - 3. End Connections: Threaded for NPS 2 (DN 50) and smaller; flanged for NPS 2-1/2 (DN 65) and larger.
  - 4. Screen: Stainless steel with round perforations unless otherwise indicated.
  - 5. Perforation Size:
    - a. Strainers NPS 2 (DN 50) and Smaller: 0.062 (1.57) inch (mm).
    - b. Strainers NPS 2-1/2 to NPS 4 (DN 65 to DN 100): 0.062 (1.57) inch (mm).
  - 6. Drain: Pipe plug.

### 2.6 TRAP-SEAL PRIMER SYSTEMS

- A. Trap-Seal Primer Systems:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. PPP Inc.
    - b. Sioux Chief Manufacturing Company, Inc.
  - 2. Standard: ASSE 1044.

#### DOMESTIC WATER PIPING SPECIALTIES

221119 - 3
- 3. Piping: NPS 3/4, ASTM B 88, Type L (DN 20, ASTM B 88M, Type B); copper, water tubing.
- 4. Cabinet: Recessed or Surface-mounted steel box with stainless-steel cover.
- 5. Electric Controls: 24-hour timer, solenoid valve, and manual switch for 120-V ac power.
  - a. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- 6. Vacuum Breaker: ASSE 1001.
- 7. Number Outlets: As shown on drawings, with additional outlet for spare capacity.
- 8. Size Outlets: NPS 1/2 (DN 15).

# PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Balancing Valves: Install in locations where they can easily be adjusted.
- B. Y-Pattern Strainers: For water, install on supply side of each control valve, water pressurereducing valve, solenoid valve, and pump.
- C. Trap-Seal Primer Systems: Install with outlet piping pitched down toward drain trap a minimum of 1 percent, and connect to floor-drain body, trap, or inlet fitting. Adjust system for proper flow.

#### 3.2 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. When installing piping specialties adjacent to equipment and machines, allow space for service and maintenance.

## 3.3 IDENTIFICATION

- A. Plastic Labels for Equipment: Install engraved plastic-laminate equipment nameplate or sign on or near each of the following:
  - 1. Pressure vacuum breakers.
  - 2. Intermediate atmospheric-vent backflow preventers.
  - 3. Reduced-pressure-principle backflow preventers.
  - 4. Water pressure-reducing valves.
  - 5. Calibrated balancing valves.
  - 6. Primary, thermostatic, water mixing valves.
  - 7. Primary water tempering valves.
  - 8. Outlet boxes.

# DOMESTIC WATER PIPING SPECIALTIES

- 9. Hose stations.
- 10. Supply-type, trap-seal primer valves.
- 11. Trap-seal primer systems.
- B. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit. Nameplates and signs are specified in Section 220553 "Identification for Plumbing Piping and Equipment."
- 3.4 FIELD QUALITY CONTROL
  - A. Perform the following tests and inspections:
    - 1. Test each pressure vacuum breaker and reduced-pressure-principle backflow preventer according to authorities having jurisdiction and the device's reference standard.
  - B. Domestic water piping specialties will be considered defective if they do not pass tests and inspections.
  - C. Prepare test and inspection reports.

#### 3.5 ADJUSTING

- A. Set field-adjustable pressure set points of water pressure-reducing valves.
- B. Set field-adjustable flow set points of balancing valves.
- C. Set field-adjustable temperature set points of temperature-actuated, water mixing valves.

END OF SECTION 221119

# SECTION 221316 - SANITARY WASTE AND VENT PIPING

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Hubless, cast-iron soil pipe and fittings.

## 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For hubless, single-stack drainage system. Include plans, elevations, sections, and details.

# 1.4 INFORMATIONAL SUBMITTALS

- A. Seismic Qualification Certificates: For waste and vent piping, accessories, and components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Detailed description of piping anchorage devices on which the certification is based and their installation requirements.
- B. Field quality-control reports.

#### 1.5 FIELD CONDITIONS

- A. Interruption of Existing Sanitary Waste Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:
  - 1. Notify Architect no fewer than two days in advance of proposed interruption of sanitary waste service.

2. Do not proceed with interruption of sanitary waste service without Architect's written permission.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Components and installation shall be capable of withstanding the following minimum working pressure unless otherwise indicated:
  - 1. Soil, Waste, and Vent Piping: 10-foot head of water.
- B. Seismic Performance: Soil, waste, and vent piping and support and installation shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

## 2.2 PIPING MATERIALS

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

# 2.3 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS

- A. Pipe and Fittings: ASTM A 888 or CISPI 301.
- B. Heavy-Duty, Hubless-Piping Couplings:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. ANACO-Husky.
    - b. Clamp-All Corp.
    - c. MIFAB, Inc.
    - d. Tyler Pipe; a subsidiary of McWane Inc.
  - 2. Standards: ASTM C 1277 and ASTM C 1540.
  - 3. Description: Stainless-steel shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.

# 2.4 SPECIALTY PIPE FITTINGS

A. Transition Couplings:

- 1. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.
- 2. Unshielded, Nonpressure Transition Couplings:
  - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - 1) Dallas Specialty & Mfg. Co.
    - 2) Fernco Inc.
    - 3) Mission Rubber Company, LLC; a division of MCP Industries.
    - 4) Plastic Oddities.
  - b. Standard: ASTM C 1173.
  - c. Description: Elastomeric, sleeve-type, reducing or transition pattern. Include shear ring and corrosion-resistant-metal tension band and tightening mechanism on each end.
  - d. End Connections: Same size as and compatible with pipes to be joined.
  - e. Sleeve Materials:
    - 1) For Cast-Iron Soil Pipes: ASTM C 564, rubber.
    - 2) For Dissimilar Pipes: ASTM D 5926, PVC or other material compatible with pipe materials being joined.
- 3. Shielded, Nonpressure Transition Couplings:
  - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - 1) Cascade Waterworks Mfg. Co.
    - 2) Mission Rubber Company, LLC; a division of MCP Industries.
  - b. Standard: ASTM C 1460.
  - c. Description: Elastomeric or rubber sleeve with full-length, corrosion-resistant outer shield and corrosion-resistant-metal tension band and tightening mechanism on each end.
  - d. End Connections: Same size as and compatible with pipes to be joined.
- B. Dielectric Fittings:
  - 1. Dielectric Unions:
    - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
      - 1) Capitol Manufacturing Company.
      - 2) Central Plastics Company.
      - 3) HART Industrial Unions, LLC.
      - 4) Jomar Valve.
      - 5) Matco-Norca.
      - 6) WATTS.

## SANITARY WASTE AND VENT PIPING

- 7) Wilkins.
- b. Description:
  - 1) Standard: ASSE 1079.
  - 2) Pressure Rating: 125 psig minimum at 180 deg F.
  - 3) End Connections: Solder-joint copper alloy and threaded ferrous.
- 2. Dielectric Flanges:
  - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - 1) Capitol Manufacturing Company.
    - 2) Central Plastics Company.
    - 3) Matco-Norca.
    - 4) WATTS.
    - 5) Wilkins.
  - b. Description:
    - 1) Standard: ASSE 1079.
    - 2) Factory-fabricated, bolted, companion-flange assembly.
    - 3) Pressure Rating: 125 psig minimum at 180 deg F.
    - 4) End Connections: Solder-joint copper alloy and threaded ferrous; threaded solder-joint copper alloy and threaded ferrous.
- 3. Dielectric-Flange Insulating Kits:
  - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - 1) Advance Products & Systems, Inc.
    - 2) Calpico, Inc.
    - 3) Central Plastics Company.
    - 4) Pipeline Seal and Insulator, Inc.
  - b. Description:
    - 1) Nonconducting materials for field assembly of companion flanges.
    - 2) Pressure Rating: 150 psig.
    - 3) Gasket: Neoprene or phenolic.
    - 4) Bolt Sleeves: Phenolic or polyethylene.
    - 5) Washers: Phenolic with steel backing washers.
- 4. Dielectric Nipples:
  - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- 1) Elster Perfection Corporation.
- 2) Grinnell Mechanical Products.
- 3) Matco-Norca.
- 4) Precision Plumbing Products.
- 5) Victaulic Company.

# b. Description:

- 1) Standard: IAPMO PS 66.
- 2) Electroplated steel nipple.
- 3) Pressure Rating: 300 psig at 225 deg F.
- 4) End Connections: Male threaded or grooved.
- 5) Lining: Inert and noncorrosive, propylene.

# PART 3 - EXECUTION

# 3.1 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems.
  - 1. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations.
  - 2. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping to permit valve servicing.
- F. Install piping at indicated slopes.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Install seismic restraints on piping. Comply with requirements for seismic-restraint devices specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."

- K. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends.
  - 1. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical.
  - 2. Use long-turn, double Y-branch and 1/8-bend fittings if two fixtures are installed back to back or side by side with common drain pipe.
    - a. Straight tees, elbows, and crosses may be used on vent lines.
  - 3. Do not change direction of flow more than 90 degrees.
  - 4. Use proper size of standard increasers and reducers if pipes of different sizes are connected.
    - a. Reducing size of waste piping in direction of flow is prohibited.
- L. Lay buried building waste piping beginning at low point of each system.
  - 1. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream.
  - 2. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements.
  - 3. Maintain swab in piping and pull past each joint as completed.
- M. Install soil and waste and vent piping at the following minimum slopes unless otherwise indicated:
  - 1. Building Sanitary Waste: 2 percent downward in direction of flow for piping NPS 3 and smaller; 2 percent downward in direction of flow for piping NPS 4 and larger.
  - 2. Horizontal Sanitary Waste Piping: 2 percent downward in direction of flow.
  - 3. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.
- N. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
  - 1. Install encasement on underground piping according to ASTM A 674 or AWWA C105/A 21.5.
- O. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.
- P. Install escutcheons for piping penetrations of walls, ceilings, and floors.
  - 1. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

# 3.2 JOINT CONSTRUCTION

- A. Join hubless, cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-piping coupling joints.
- B. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1.
  - 1. Cut threads full and clean using sharp dies.
  - 2. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
    - a. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
    - b. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
    - c. Do not use pipe sections that have cracked or open welds.

# 3.3 SPECIALTY PIPE FITTING INSTALLATION

- A. Transition Couplings:
  - 1. Install transition couplings at joints of piping with small differences in ODs.
  - 2. In Waste Drainage Piping: Unshielded or Shielded, nonpressure transition couplings.
- B. Dielectric Fittings:
  - 1. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.
  - 2. Dielectric Fittings for NPS 2 and Smaller: Use dielectric nipples or unions.
  - 3. Dielectric Fittings for NPS 2-1/2 to NPS 4: Use dielectric flanges or flange kits or nipples.

# 3.4 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements for pipe hanger and support devices and installation specified in Section 220548 "Vibration Controls for Plumbing Piping and Equipment."
  - 1. Install carbon-steel pipe hangers for horizontal piping in noncorrosive environments.
  - 2. Install carbon-steel pipe support clamps for vertical piping in noncorrosive environments.
  - 3. Vertical Piping: MSS Type 8 or Type 42, clamps.
  - 4. Install individual, straight, horizontal piping runs:
    - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    - c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.
  - 5. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
  - 6. Base of Vertical Piping: MSS Type 52, spring hangers.

- B. Install hangers for cast-iron steel and copper soil piping, with maximum horizontal spacing and minimum rod diameters, to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- C. Support horizontal piping and tubing within 12 inches of each fitting, valve, and coupling.
- D. Support vertical runs of cast iron steel and copper soil piping to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

# 3.5 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.
- C. Connect waste and vent piping to the following:
  - 1. Plumbing Fixtures: Connect waste piping in sizes indicated, but not smaller than required by plumbing code.
  - 2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
  - 3. Plumbing Specialties: Connect waste and vent piping in sizes indicated, but not smaller than required by plumbing code.
  - 4. Install test tees (wall cleanouts) in conductors near floor and floor cleanouts with cover flush with floor.
  - 5. Comply with requirements for cleanouts and drains specified in Section 221319 "Sanitary Waste Piping Specialties."
  - 6. Equipment: Connect waste piping as indicated.
    - a. Provide shutoff valve if indicated and union for each connection.
    - b. Use flanges instead of unions for connections NPS 2-1/2 and larger.
- D. Where installing piping adjacent to equipment, allow space for service and maintenance of equipment.
- E. Make connections according to the following unless otherwise indicated:
  - 1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
  - 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.

# 3.6 IDENTIFICATION

A. Identify exposed sanitary waste and vent piping.

B. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

# 3.7 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
  - 1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
  - 2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test sanitary waste and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:
  - 1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired.
    - a. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
  - 2. Leave uncovered and unconcealed new, altered, extended, or replaced waste and vent piping until it has been tested and approved.
    - a. Expose work that was covered or concealed before it was tested.
  - 3. Roughing-in Plumbing Test Procedure: Test waste and vent piping except outside leaders on completion of roughing-in.
    - a. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water.
    - b. From 15 minutes before inspection starts to completion of inspection, water level must not drop.
    - c. Inspect joints for leaks.
  - 4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight.
    - a. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg.
    - b. Use U-tube or manometer inserted in trap of water closet to measure this pressure.
    - c. Air pressure must remain constant without introducing additional air throughout period of inspection.

#### SANITARY WASTE AND VENT PIPING

- d. Inspect plumbing fixture connections for gas and water leaks.
- 5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
- 6. Prepare reports for tests and required corrective action.

## 3.8 CLEANING AND PROTECTION

- A. Clean interior of piping. Remove dirt and debris as work progresses.
- B. Protect sanitary waste and vent piping during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.
- D. Repair damage to adjacent materials caused by waste and vent piping installation.

# 3.9 PIPING SCHEDULE

- A. Flanges and unions may be used on aboveground pressure piping unless otherwise indicated.
- B. Aboveground, soil and waste piping NPS 4 and smaller shall be the following:
  - 1. Hubless, cast-iron soil pipe and fittings; heavy-duty hubless-piping couplings; and coupled joints.
  - 2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- C. Aboveground, vent piping NPS 4 and smaller shall be the following:
  - 1. Hubless, cast-iron soil pipe and fittings; heavy-duty hubless-piping couplings; and coupled joints.
  - 2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- D. Underground, soil, waste, and vent piping NPS 4 and smaller shall be any of the following:
  - 1. Hubless, cast-iron soil pipe and fittings; heavy-duty hubless-piping couplings; and coupled joints.
  - 2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- E. Underground/Aboveground, grease-waste, and grease-vent piping NPS 4 and smaller shall be any of the following:
  - 1. Hubless, cast-iron soil pipe and fittings; heavy-duty cast-iron hubless-piping couplings; and coupled joints.
  - 2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.

## END OF SECTION 221316

# SECTION 221319 - SANITARY WASTE PIPING SPECIALTIES

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Cleanouts.
  - 2. Miscellaneous sanitary drainage piping specialties.

#### 1.3 DEFINITIONS

- A. ABS: Acrylonitrile-butadiene-styrene.
- B. FOG: Fats, oils, and greases.
- C. PVC: Polyvinyl chloride.

# 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include rated capacities, operating characteristics, and accessories for the following:
  - 1. FOG disposal systems.
- B. Shop Drawings:
  - 1. Show fabrication and installation details for frost-resistant vent terminals.
  - 2. Wiring Diagrams: Power, signal, and control wiring.

## 1.5 INFORMATIONAL SUBMITTALS

- A. Seismic Qualification Data: For FOG disposal systems, accessories, and components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.

## SANITARY WASTE PIPING SPECIALTIES

- 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
- 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- B. Field quality-control reports.

# 1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For sanitary waste piping specialties to include in emergency, operation, and maintenance manuals.

# 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Cultures: Provide 1-gal. (3.8-L) bottles of bacteria culture recommended by manufacturer of FOG disposal systems equal to 200 percent of amount installed, but no fewer than 2 1-gal. (3.8-L) bottles.

# PART 2 - PRODUCTS

# 2.1 ASSEMBLY DESCRIPTIONS

- A. Sanitary waste piping specialties shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 14 for plastic sanitary waste piping specialty components.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing, and marked for intended location and application.

# 2.2 CLEANOUTS

- A. Cast-Iron Exposed Cleanouts:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Jay R. Smith Mfg. Co.
    - b. Josam Company.
    - c. MIFAB, Inc.
    - d. Tyler Pipe; a subsidiary of McWane Inc.
    - e. WATTS.

# SANITARY WASTE PIPING SPECIALTIES

- f. Zurn Industries, LLC.
- 2. Standard: ASME A112.36.2M.
- 3. Size: Same as connected drainage piping
- 4. Body Material: Hubless, cast-iron soil pipe test tee as required to match connected piping.
- 5. Closure: Countersunk, plug.
- 6. Closure Plug Size: Same as or not more than one size smaller than cleanout size.
- B. Cast-Iron Exposed Floor Cleanouts:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Jay R. Smith Mfg. Co.
    - b. Josam Company.
    - c. Tyler Pipe; a subsidiary of McWane Inc.
    - d. WATTS.
    - e. Zurn Industries, LLC.
  - 2. Standard: ASME A112.36.2M for cast-iron soil pipe with cast-iron ferrule cleanout.
  - 3. Size: Same as connected branch.
  - 4. Type: Cast-iron soil pipe with cast-iron ferrule.
  - 5. Body or Ferrule: Cast iron.
  - 6. Clamping Device: Not required.
  - 7. Outlet Connection: Inside calk.
  - 8. Closure: Brass plug with straight threads and gasket.
  - 9. Adjustable Housing Material: Cast iron with threads.
  - 10. Frame and Cover Material and Finish: Nickel-bronze, copper alloy.
  - 11. Frame and Cover Shape: Round.
  - 12. Top Loading Classification: Heavy Duty.
  - 13. Riser: ASTM A 74, Service class, cast-iron drainage pipe fitting and riser to cleanout.
- C. Cast-Iron Wall Cleanouts:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Jay R. Smith Mfg. Co.
    - b. Josam Company.
    - c. MIFAB, Inc.
    - d. Tyler Pipe; a subsidiary of McWane Inc.
    - e. WATTS.
    - f. Zurn Industries, LLC.
  - 2. Standard: ASME A112.36.2M. Include wall access.
  - 3. Size: Same as connected drainage piping.
  - 4. Body: Hubless, cast-iron soil pipe test tee as required to match connected piping.
  - 5. Closure Plug:

#### SANITARY WASTE PIPING SPECIALTIES

- a. Cast iron.
- b. Countersunk head.
- c. Drilled and threaded for cover attachment screw.
- d. Size: Same as or not more than one size smaller than cleanout size.
- 6. Wall Access: Round, flat, chrome-plated brass or stainless-steel cover plate with screw.
- 7. Wall Access: Round, nickel-bronze, copper-alloy, or stainless-steel wall-installation frame and cover.

# 2.3 MISCELLANEOUS SANITARY DRAINAGE PIPING SPECIALTIES

- A. Floor-Drain, Trap-Seal Primer Fittings:
  - 1. Description: Cast iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
  - 2. Size: Same as floor drain outlet with NPS 1/2 (DN 15) side inlet.
- B. Air-Gap Fittings:
  - 1. Standard: ASME A112.1.2, for fitting designed to ensure fixed, positive air gap between installed inlet and outlet piping.
  - 2. Body: Bronze or cast iron.
  - 3. Inlet: Opening in top of body.
  - 4. Outlet: Larger than inlet.
  - 5. Size: Same as connected waste piping and with inlet large enough for associated indirect waste piping.

# PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Install cleanouts in aboveground piping and building drain piping according to the following, unless otherwise indicated:
  - 1. Size same as drainage piping up to NPS 4 (DN 100). Use NPS 4 (DN 100) for larger drainage piping unless larger cleanout is indicated.
  - 2. Locate at each change in direction of piping greater than 45 degrees.
  - 3. Locate at minimum intervals of 50 feet (15 m) for piping NPS 4 (DN 100) and smaller and 100 feet (30 m) for larger piping.
  - 4. Locate at base of each vertical soil and waste stack.
- B. For floor cleanouts for piping below floors, install cleanout deck plates with top flush with finished floor.
- C. For cleanouts located in concealed piping, install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall.

# SANITARY WASTE PIPING SPECIALTIES

- D. Install floor-drain, trap-seal primer fittings on inlet to floor drains that require trap-seal primer connection.
  - 1. Exception: Fitting may be omitted if trap has trap-seal primer connection.
  - 2. Size: Same as floor drain inlet.
- E. Install air-gap fittings on draining-type backflow preventers and on indirect-waste piping discharge into sanitary drainage system.
- F. Install sleeve and sleeve seals with each riser and stack passing through floors with waterproof membrane.
- G. Install vent caps on each vent pipe passing through roof.
- H. Install expansion joints on vertical stacks and conductors. Position expansion joints for easy access and maintenance.
- I. Install frost-proof vent caps on each vent pipe passing through roof. Maintain 1-inch (25-mm) clearance between vent pipe and roof substrate.
- J. Install traps on plumbing specialty drain outlets. Omit traps on indirect wastes unless trap is indicated.

# 3.2 CONNECTIONS

- A. Comply with requirements in Section 221316 "Sanitary Waste and Vent Piping" for piping installation requirements. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment to allow service and maintenance.
- C. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

# 3.3 FLASHING INSTALLATION

- A. Fabricate flashing from single piece unless large pans, sumps, or other drainage shapes are required.
- B. Install sheet flashing on pipes, sleeves, and specialties passing through or embedded in floors and roofs with waterproof membrane.
  - 1. Pipe Flashing: Sleeve type, matching pipe size, with minimum length of 10 inches (250 mm), and skirt or flange extending at least 8 inches (200 mm) around pipe.
  - 2. Sleeve Flashing: Flat sheet, with skirt or flange extending at least 8 inches (200 mm) around sleeve.
  - 3. Embedded Specialty Flashing: Flat sheet, with skirt or flange extending at least 8 inches (200 mm) around specialty.

# SANITARY WASTE PIPING SPECIALTIES

- C. Set flashing on floors and roofs in solid coating of bituminous cement.
- D. Secure flashing into sleeve and specialty clamping ring or device.
- E. Extend flashing up vent pipe passing through roofs and turn down into pipe, or secure flashing into cast-iron sleeve having calking recess.

#### 3.4 LABELING AND IDENTIFYING

- A. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit.
  - 1. Nameplates and signs are specified in Section 220553 "Identification for Plumbing Piping and Equipment."

#### 3.5 FIELD QUALITY CONTROL

- A. Perform tests and inspections, and prepare test reports.
  - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect field-assembled FOG disposal systems and their installation, including piping and electrical connections, and to assist in testing.
- B. Tests and Inspections:
  - 1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
  - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

## 3.6 **PROTECTION**

- A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.
- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION 221319

SANITARY WASTE PIPING SPECIALTIES

# SECTION 221319.13 - SANITARY DRAINS

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Floor sinks.

#### 1.3 DEFINITIONS

- A. ABS: Acrylonitrile-butadiene styrene.
- B. FRP: Fiberglass-reinforced plastic.
- C. HDPE: High-density polyethylene.
- D. PE: Polyethylene.
- E. PP: Polypropylene.
- F. PVC: Polyvinyl chloride.

#### 1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

## PART 2 - PRODUCTS

#### 2.1 DRAIN ASSEMBLIES

- A. Sanitary drains shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 14 for plastic sanitary piping specialty components.

## SANITARY DRAINS

## 2.2 FLOOR SINKS

## A. Cast-Iron Floor Sinks:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam Company; Josam Div.
  - b. MIFAB, Inc.
  - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - d. Watts Drainage Products Inc.
  - e. Zurn Plumbing Products Group; Specification Drainage Operation.
- 2. Standard: ASME A112.6.7.
- 3. Pattern: Floor drain.
- 4. Body Material: Cast iron.
- 5. Anchor Flange: Required.
- 6. Clamping Device: Not required.
- 7. Outlet: Bottom, no-hub connection.
- 8. Coating on Interior Surfaces: Not required.
- 9. Sediment Bucket: Not required.
- 10. Internal Strainer: Dome.
- 11. Internal Strainer Material: Aluminum.
- 12. Top Grate Material: Cast iron, loose.
- 13. Top of Body and Grate Finish: Nickel bronze.
- 14. Top Shape: Square.
- 15. Funnel: Not required.

# PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Install floor drains at low points of surface areas to be drained. Set grates of drains flush with finished floor, unless otherwise indicated.
  - 1. Position floor drains for easy access and maintenance.
  - 2. Set floor drains below elevation of surrounding finished floor to allow floor drainage.
  - 3. Set with grates depressed according to the following drainage area radii:
    - a. Radius, 30 Inches or Less: Equivalent to 1 percent slope, but not less than 1/4-inch total depression.
    - b. Radius, 30 to 60 Inches: Equivalent to 1 percent slope.
    - c. Radius, 60 Inches or Larger: Equivalent to 1 percent slope, but not greater than 1-inch total depression.
  - 4. Install floor-drain flashing collar or flange, so no leakage occurs between drain and adjoining flooring.

#### SANITARY DRAINS

- a. Maintain integrity of waterproof membranes where penetrated.
- 5. Install individual traps for floor drains connected to sanitary building drain, unless otherwise indicated.
- B. Comply with ASME A112.3.1 for installation of stainless-steel channel drainage systems.
  - 1. Install on support devices, so that top will be flush with adjacent surface.

## 3.2 CONNECTIONS

- A. Comply with requirements in Section 221316 "Sanitary Waste and Vent Piping" for piping installation requirements. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Comply with requirements in Section 221319 "Sanitary Waste Piping Specialties" for backwater valves, air admittance devices and miscellaneous sanitary drainage piping specialties.
- C. Comply with requirements in Section 221323 "Sanitary Waste Interceptors" for grease interceptors, grease-removal devices, oil interceptors, sand interceptors, and solid interceptors.
- D. Install piping adjacent to equipment to allow service and maintenance.
- E. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

## 3.3 LABELING AND IDENTIFYING

A. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit. Nameplates and signs are specified in Section 220553 "Identification for Plumbing Piping and Equipment."

## 3.4 **PROTECTION**

- A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.
- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

#### END OF SECTION 221319.13

## SANITARY DRAINS

# SECTION 221323 - SANITARY WASTE INTERCEPTORS

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Grease interceptors.
  - 2. Garbage Disposers
  - 3. Solids Interceptors

#### 1.3 DEFINITIONS

- A. FRP: Fiberglass-reinforced plastic.
- B. PP: Polypropylene plastic.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of concrete interceptor indicated. Include materials of fabrication, dimensions, rated capacities, retention capacities, operating characteristics, size and location of each pipe connection, furnished specialties, and accessories.
- B. Shop Drawings: For each type and size of precast-concrete interceptor indicated.
  - 1. Include materials of construction, dimensions, rated capacities, retention capacities, location and size of each pipe connection, furnished specialties, and accessories.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Interceptors, drawn to scale, on which the following items are shown and coordinated with each other, based on input from Installers of the items involved:
  - 1. Interceptors.
  - 2. Piping connections. Include size, location, and elevation of each.
  - 3. Interface with underground structures and utility services.

## SANITARY WASTE INTERCEPTORS

## 1.6 **PROJECT CONDITIONS**

- A. Interruption of Existing Sewer Services: Do not interrupt services to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary sewer services according to requirements indicated:
  - 1. Notify Architect and Owner no fewer than seven days in advance of proposed interruption of service.
  - 2. Do not proceed with interruption of sewer services without Architect's and Owner's written permission.

## PART 2 - PRODUCTS

#### 2.1 GREASE INTERCEPTORS

- A. Plastic Grease Interceptors:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Green Turtle Zurn.
    - b. Schier Products Company.
    - c. Zurn Industries, LLC.
  - 2. Standard: PDI G101 and ASME A112.14.3, for intercepting and retaining FOG from food-preparation wastewater.
  - 3. PDI Seal: Not required.
  - 4. Body Material: Plastic.
  - 5. Body Dimensions: See plans.
  - 6. Body Extension: Not required.
  - 7. Capacities and Characteristics:
    - a. See plans.

#### 2.2 GARBAGE DISPOSER

- A. Garbage Disposer, GD-1
  - 1. Manufacturers: Subject to compliance with requirements, provide the product indicated on Drawings or a comparable product by one of the following:
    - a. Josam Company.
    - b. MIFAB, Inc.
    - c. Smith, Jay R. Mfg. Co.
    - d. Watts Drainage Products.
    - e. Insinkerator Foodservice.

#### SANITARY WASTE INTERCEPTORS

- 2. Type: Compact residential disposer made for removing foodwaste from waste water.
- 3. Grind Chamber: Corrosion Resistant Stainless Steel.
- 4. Finish: Waterborne enamel.
- 5. Shredding Elements: Stationary and rotating; galvanized steel.
- 6. Motor: 1/2 HP induction motor.
- 7. Body Dimensions: 7"x7"x13.
- 8. Capacity: 26 oz.

## 2.3 ACID NEUTRALIZATION TANKS

- A. Acid Neutralization Tanks:
  - 1. Manufacturers: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
    - a. Josam Company.
    - b. Schier Products Company.
    - c. Smith, Jay R. Mfg. Co.
    - d. Watts Drainage Products.
    - e. Zurn Plumbing Products Group.
  - 2. Type: Factory-fabricated tank for separating and neutralizing acid in wastewater.
  - 3. Include inlets, outlets, vents, cover, riser system, monitoring equipment
  - 4. Cover: Pedestrian-rated 2,000 lb capacity; water/gas-tight seal
  - 5. Body Material: Seamless, rotationally molded, high density polyethylene tank with minimum of 3/8" uniform wall thickness
  - 6. Inlet and Outlet Size: As indicated.
  - 7. Vent Connection: As indicated.
  - 8. Mounting: Recessed, flush with floor
  - 9. Flow-Control Fitting: Built-in
  - 10. Liquid Holding Capacity: As indicated.

# PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Install precast-concrete interceptors according to ASTM C 891. Set level and plumb.
- B. Install manhole risers from top of underground concrete interceptors to manholes and gratings at finished grade.
- C. Set tops of manhole frames and covers flush with finished surface in pavements. Set tops 3 inches above finish surface elsewhere, unless otherwise indicated.
- D. Set tops of grating frames and grates flush with finished surface.

#### SANITARY WASTE INTERCEPTORS

## 3.2 CONNECTIONS

- A. Piping installation requirements are specified in Section 221316 "Sanitary Waste and Vent Piping." Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Make piping connections between interceptors and piping systems.

#### 3.3 COMMISSIONING

- A. Commissioning Authority
  - 1. The commissioning authority (CA) has been contracted directly with the owner for this project. The CA has overall responsibility for planning and coordinating the commissioning process. However commissioning involves all parties involved with the design and construction process, including the mechanical (Division 22 & 23) contractor, and all specialty sub-contractors within Division 23, such as sheet metal, piping, refrigeration, water treatment, TAB and controls, plus major equipment suppliers as required.

END OF SECTION 221323

# SECTION 230529 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Metal pipe hangers and supports.
  - 2. Trapeze pipe hangers.
  - 3. Metal framing systems.
  - 4. Thermal hanger-shield inserts.
  - 5. Equipment supports.
- B. Related Requirements:
  - 1. Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment" for vibration isolation devices.

#### 1.3 ACTION SUBMITTALS

- A. Shop Drawings: Signed and sealed by a qualified professional engineer. Show fabrication and installation details and include calculations for the following:
  - 1. Trapeze pipe hangers.
  - 2. Metal framing systems.
  - 3. Equipment supports.
- B. Delegated-Design Submittal: For trapeze hangers indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
  - 1. Detail fabrication and assembly of trapeze hangers.
  - 2. Include design calculations for designing trapeze hangers.

# 1.4 INFORMATIONAL SUBMITTALS

A. Welding certificates.

#### HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

# 1.5 QUALITY ASSURANCE

- A. Structural-Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.
- B. Pipe Welding Qualifications: Qualify procedures and operators according to 2015 ASME Boiler and Pressure Vessel Code, Section IX.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design trapeze pipe hangers and equipment supports.
- B. Structural Performance: Hangers and supports for plumbing piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
  - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
  - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
  - 3. Design seismic-restraint hangers and supports for piping and equipment and obtain approval from authorities having jurisdiction.

# 2.2 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
  - 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
  - 2. Galvanized Metallic Coatings: Pregalvanized, hot-dip galvanized, or electro-galvanized.
  - 3. Nonmetallic Coatings: Plastic coated or epoxy powder coated.
  - 4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
  - 5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
- B. Stainless-Steel Pipe Hangers and Supports:
  - 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
  - 2. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
  - 3. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.

# 2.3 TRAPEZE PIPE HANGERS

A. Description: MSS SP-58, Type 59, shop- or field-fabricated pipe-support assembly, made from structural-carbon-steel shapes, with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

## 2.4 METAL FRAMING SYSTEMS

- A. MFMA Manufacturer Metal Framing Systems:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. B-line, an Eaton business.
    - b. Thomas & Betts Corporation; A Member of the ABB Group.
    - c. Unistrut; Part of Atkore International.
  - 2. Description: Shop- or field-fabricated pipe-support assembly, made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
  - 3. Standard: Comply with MFMA-4, factory-fabricated components for field assembly.
  - 4. Channels: Continuous slotted carbon-steel channel with inturned lips.
  - 5. Channel Width: Selected for applicable load criteria.
  - 6. Channel Nuts: Formed or stamped nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
  - 7. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

# 2.5 THERMAL HANGER-SHIELD INSERTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Carpenter & Paterson, Inc.
  - 2. ERICO International Corporation.
  - 3. Pipe Shields Inc.
  - 4. Rilco Manufacturing Co., Inc.
  - 5. Value Engineered Products, Inc.
- B. Insulation-Insert Material for Cold Piping: ASTM C 552, Type II cellular glass with 100-psig minimum compressive strength and vapor barrier.
- C. Insulation-Insert Material for Hot Piping: ASTM C 552, Type II cellular glass with 100-psig minimum compressive strength.
- D. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- E. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.

## HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT 230529 - 3

F. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

# 2.6 EQUIPMENT SUPPORTS

A. Description: Welded, shop- or field-fabricated equipment support made from structural-carbonsteel shapes.

## 2.7 MATERIALS

- A. Aluminum: ASTM B 221.
- B. Carbon Steel: ASTM A 1011/A 1011M.
- C. Structural Steel: ASTM A 36/A 36M carbon-steel plates, shapes, and bars; black and galvanized.
- D. Stainless Steel: ASTM A 240/A 240M.
- E. Grout: ASTM C 1107/C 1107M, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
  - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
  - 2. Design Mix: 5000-psi, 28-day compressive strength.

#### PART 3 - EXECUTION

## 3.1 APPLICATION

A. Strength of Support Assemblies: Where not indicated, select sizes of components, so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

# 3.2 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-58. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-58. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
  - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size, or install intermediate supports for smaller-diameter pipes as specified for individual pipe hangers.

HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT 230529 - 4

- 2. Field fabricate from ASTM A 36/A 36M carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.
- C. Fiberglass Pipe-Hanger Installation: Comply with applicable portions of MSS SP-58. Install hangers and attachments as required to properly support piping from building structure.
- D. MetalFraming System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.
- E. Thermal Hanger-Shield Installation: Install in pipe hanger or shield for insulated piping.
- F. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- H. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- I. Install lateral bracing with pipe hangers and supports to prevent swaying.
- J. Load Distribution: Install hangers and supports, so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- K. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- L. Insulated Piping:
  - 1. Attach clamps and spacers to piping.
    - a. Piping Operating Above Ambient Air Temperature: Clamp may project through insulation.
    - b. Piping Operating Below Ambient Air Temperature: Use thermal hanger-shield insert with clamp sized to match OD of insert.
    - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
  - 2. Install MSS SP-58, Type 39 protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
    - a. Option: Thermal hanger-shield inserts may be used. Include steel weightdistribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
  - 3. Install MSS SP-58, Type 40 protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
    - a. Option: Thermal hanger-shield inserts may be used. Include steel weightdistribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

- 4. Shield Dimensions for Pipe: Not less than the following:
  - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
  - b. NPS 4: 12 inches long and 0.06 inch thick.
  - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
  - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
  - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
- 5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
- 6. Thermal Hanger Shields: Install with insulation of same thickness as piping insulation.

# 3.3 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
  - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  - 2. Obtain fusion without undercut or overlap.
  - 3. Remove welding flux immediately.
  - 4. Finish welds at exposed connections, so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

# 3.4 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

# 3.5 PAINTING

- A. Touchup: Clean field welds and abraded, shop-painted areas. Paint exposed areas immediately after erecting hangers and supports. Use same materials as those used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
  - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.

# HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT 230529 - 6

230529 - 7

- B. Touchup: Cleaning and touchup painting of field welds, bolted connections, and abraded, shoppainted areas on miscellaneous metal are specified in Section 099123 "Interior Painting."
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas, and apply galvanizing-repair paint to comply with ASTM A 780/A 780M.

# 3.6 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-58 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finishes.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports and attachments for general service applications.
- F. Use padded hangers for piping that is subject to scratching.
- G. Use thermal hanger-shield inserts for insulated piping and tubing.
- H. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
  - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
  - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
  - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
  - 5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow offcenter closure for hanger installation before pipe erection.
  - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
  - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
  - 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
  - 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
  - 10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.

HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

- 11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
- 12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
- 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
- 14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steelpipe base stanchion support and cast-iron floor flange or carbon-steel plate.
- 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
- 16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
- 17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction occurs.
- 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction occurs.
- 19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction occurs but vertical adjustment is unnecessary.
- 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction occurs and vertical adjustment is unnecessary.
- 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation, in addition to expansion and contraction, is required.
- I. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
  - 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.
- J. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Steel Turnbuckles (MSS Type 13): For adjustment of up to 6 inches for heavy loads.
  - 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
  - 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11 split pipe rings.
  - 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
  - 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- K. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

## HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

- 1. Steel or Malleable-Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
- 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
- 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
- 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
- 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
- 6. C-Clamps (MSS Type 23): For structural shapes.
- 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
- 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
- 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel Ibeams for heavy loads.
- 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel Ibeams for heavy loads, with link extensions.
- 11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
- 12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
  - a. Light (MSS Type 31): 750 lb.
  - b. Medium (MSS Type 32): 1500 lb.
  - c. Heavy (MSS Type 33): 3000 lb.
- 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
- 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
- 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- L. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
  - 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
  - 3. Thermal Hanger-Shield Inserts: For supporting insulated pipe.
- M. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
  - 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
  - 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.

HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

- 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
- 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
- 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
- 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
- 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
  - a. Horizontal (MSS Type 54): Mounted horizontally.
  - b. Vertical (MSS Type 55): Mounted vertically.
  - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- N. Comply with MSS SP-58 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- O. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- P. Use mechanical-expansion anchors instead of building attachments where required in concrete construction.
- Q. Use pipe-positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

END OF SECTION 230529

# SECTION 220548 - VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Pipe-riser resilient supports.
  - 2. Resilient pipe guides.
  - 3. Restraint channel bracings.
  - 4. Restraint cables.
  - 5. Seismic-restraint accessories.
  - 6. Mechanical anchor bolts.
  - 7. Adhesive anchor bolts.

#### 1.3 DEFINITIONS

- A. IBC: International Building Code.
- B. ICC-ES: ICC-Evaluation Service.
- C. OSHPD: Office of Statewide Health Planning & Development (for the State of California).

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
  - 2. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of vibration isolation device and seismic-restraint component required.
    - a. Tabulate types and sizes of seismic restraints, complete with report numbers and rated strength in tension and shear as evaluated by an agency acceptable to authorities having jurisdiction.
- b. Annotate to indicate application of each product submitted and compliance with requirements.
- 3. Interlocking Snubbers: Include ratings for horizontal, vertical, and combined loads.
- B. Shop Drawings:
  - 1. Detail fabrication and assembly of equipment bases. Detail fabrication including anchorages and attachments to structure and to supported equipment.
- C. Delegated-Design Submittal: For each vibration isolation and seismic-restraint device.
  - 1. Include design calculations and details for selecting vibration isolators and seismic restraints complying with performance requirements, design criteria, and analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
  - 2. Design Calculations: Calculate static and dynamic loading due to equipment weight and operation, due to seismic forces required to select vibration isolators, and due to seismic restraints.
  - 3. Riser Supports: Include riser diagrams and calculations showing anticipated expansion and contraction at each support point, initial and final loads on building structure, spring deflection changes, and seismic loads. Include certification that riser system was examined for excessive stress and that none exists.
  - 4. Seismic-Restraint Details:
    - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads.
    - b. Details: Indicate fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events. Indicate association with vibration isolation devices.
    - c. Coordinate seismic-restraint and vibration isolation details with wind-restraint details required for equipment mounted outdoors. Comply with requirements in other Sections for equipment mounted outdoors.
    - d. Preapproval and Evaluation Documentation: By an agency acceptable to authorities having jurisdiction, showing maximum ratings of restraint items and the basis for approval (tests or calculations).

# 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show coordination of vibration isolation device installation and seismic bracing for plumbing piping and equipment with other systems and equipment in the vicinity, including other supports and restraints, if any.
- B. Qualification Data: For professional engineer and testing agency.
- C. Welding certificates.

# VIBRATION AND SEISMIC CONTROLS FOR HVAC

D. Field quality-control reports.

### 1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is an NRTL as defined by OSHA in 29 CFR 1910.7 and that is acceptable to authorities having jurisdiction.
- B. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.
- C. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."
- D. Seismic-restraint devices shall have horizontal and vertical load testing and analysis and shall bear anchorage preapproval OPA number from OSHPD, preapproval by ICC-ES, or preapproval by another agency acceptable to authorities having jurisdiction, showing maximum seismic-restraint ratings. Ratings based on independent testing are preferred to ratings based on calculations. If preapproved ratings are unavailable, submittals based on independent testing are preferred. Calculations (including combining shear and tensile loads) to support seismic-restraint designs must be signed and sealed by a qualified professional engineer.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Seismic-Restraint Loading:
  - 1. Site Class as Defined in the IBC: See S0.1.
  - 2. Assigned Seismic Use Group or Building Category as Defined in the IBC: See S0.1.
    - a. Component Importance Factor: 1.0.
    - b. Component Response Modification Factor: Refer to ASCE Standard 7-10, Chapter 13.
    - c. Component Amplification Factor: Refer to ASCE Standard 7-10, Chapter 13.
  - 3. Design Spectral Response Acceleration at Short Periods (0.2 Second): See S0.1.
  - 4. Design Spectral Response Acceleration at 1.0-Second Period: See S0.1.
  - 5. Rated strengths, features, and applications shall be as defined in reports by an agency acceptable to authorities having jurisdiction.
    - a. Structural Safety Factor: Allowable strength in tension, shear, and pullout force of components shall be at least four times the maximum seismic forces to which they are subjected.

### 2.2 RESTRAINT CHANNEL BRACINGS

A. Description: MFMA-4, shop- or field-fabricated bracing assembly made of slotted steel channels with accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; rated in tension, compression, and torsion forces.

### 2.3 RESTRAINT CABLES

A. Restraint Cables: ASTM A 603 galvanized-steel cables. End connections made of steel assemblies with thimbles, brackets, swivel, and bolts designed for restraining cable service; with a minimum of two clamping bolts for cable engagement.

### 2.4 SEISMIC-RESTRAINT ACCESSORIES

- A. Hanger-Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections to hanger rod.
- B. Hinged and Swivel Brace Attachments: Multifunctional steel connectors for attaching hangers to rigid channel bracings.
- C. Bushings for Floor-Mounted Equipment Anchor Bolts: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchor bolts and studs.
- D. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices used.
- E. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.

# 2.5 MECHANICAL ANCHOR BOLTS

A. Mechanical Anchor Bolts: Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

A. Examine areas and equipment to receive vibration isolation and seismic-control devices for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

#### VIBRATION AND SEISMIC CONTROLS FOR HVAC

- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 APPLICATIONS

- A. Multiple Pipe Supports: Secure pipes to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.
- B. Hanger-Rod Stiffeners: Install hanger-rod stiffeners where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods due to seismic forces.
- C. Strength of Support and Seismic-Restraint Assemblies: Where not indicated, select sizes of components so strength is adequate to carry present and future static and seismic loads within specified loading limits.

# 3.3 VIBRATION CONTROL AND SEISMIC-RESTRAINT DEVICE INSTALLATION

- A. Installation of vibration isolators must not cause any change of position of equipment, piping, or ductwork resulting in stresses or misalignment.
- B. Comply with requirements in Section 077200 "Roof Accessories" for installation of roof curbs, equipment supports, and roof penetrations.
- C. Equipment Restraints:
  - 1. Install seismic snubbers on plumbing equipment mounted on vibration isolators. Locate snubbers as close as possible to vibration isolators and bolt to equipment base and supporting structure.
  - 2. Install resilient bolt isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
  - 3. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction that provides required submittals for component.
- D. Piping Restraints:
  - 1. Comply with requirements in MSS SP-127.
  - 2. Space lateral supports a maximum of 40 feet o.c., and longitudinal supports a maximum of 80 feet o.c.
  - 3. Brace a change of direction longer than 12 feet.
- E. Install cables so they do not bend across edges of adjacent equipment or building structure.
- F. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction that provides required submittals for component.

- G. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.
- H. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- I. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.
- J. Drilled-in Anchors:
  - 1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify the structural engineer if reinforcing steel or other embedded items are encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
  - 2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
  - 3. Wedge Anchors: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
  - 4. Adhesive Anchors: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
  - 5. Set anchors to manufacturer's recommended torque, using a torque wrench.
  - 6. Install zinc-coated steel anchors for interior and stainless-steel anchors for exterior applications.

# 3.4 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

A. Install flexible connections in piping where they cross seismic joints, where adjacent sections or branches are supported by different structural elements, and where the connections terminate with connection to equipment that is anchored to a different structural element from the one supporting the connections as they approach equipment. Comply with requirements in Section 221116 "Domestic Water Piping" for piping flexible connections.

# 3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Perform tests and inspections.
- C. Tests and Inspections:
  - 1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.

# VIBRATION AND SEISMIC CONTROLS FOR HVAC

- 2. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
- 3. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
- 4. Test at least four of each type and size of installed anchors and fasteners selected by Architect.
- 5. Test to 90 percent of rated proof load of device.
- 6. Measure isolator restraint clearance.
- 7. Measure isolator deflection.
- 8. Verify snubber minimum clearances.
- D. Remove and replace malfunctioning units and retest as specified above.
- E. Prepare test and inspection reports.

# 3.6 ADJUSTING

- A. Adjust isolators after piping system is at operating weight.
- B. Adjust limit stops on restrained-spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.

# END OF SECTION 230548

# SECTION 230553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Equipment labels.
  - 2. Pipe labels.
  - 3. Duct labels.
  - 4. Valve tags.

### 1.3 SUBMITTAL

A. Product Data: For each type of product indicated.

# PART 2 - PRODUCTS

### 2.1 EQUIPMENT LABELS

- A. Metal Labels for Equipment:
  - 1. Material and Thickness: Brass, 0.032-inch, Stainless steel, 0.025-inch or anodized aluminum, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
  - 2. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
  - 3. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
  - 4. Fasteners: Stainless-steel rivets or self-tapping screws.
  - 5. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- B. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified.

### IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

- C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number and identify Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.
- D. Dual Point Connection Equipment: Label "MORE THAN ONE DISCONNECT REQUIRED TO DE-ENERGIZE EQUIPMENT" in easily viewable location on RTU's listed as connected to emergency power.

# 2.2 DUCT LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.
- B. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- C. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- D. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- E. Fasteners: Stainless-steel rivets or self-tapping screws.
- F. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- G. Duct Label Contents: Include identification of duct service using same designations or abbreviations as used on Drawings, duct size, and an arrow indicating flow direction.
  - 1. Flow-Direction Arrows: Integral with duct system service lettering to accommodate both directions or as separate unit on each duct label to indicate flow direction.
  - 2. Lettering Size: At least 1-1/2 inches high.

# PART 3 - EXECUTION

# 3.1 PREPARATION

A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

# 3.2 EQUIPMENT LABEL INSTALLATION

A. All air and piping systems shown on plans shall be labeled.

# IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

- B. Install or permanently fasten labels on each major item of mechanical equipment.
- C. Locate equipment labels where accessible and visible.
- D. Provide P-touch labels on ceiling tiles to indicate location of equipment above ceiling-such as VAV boxes, shut-off valves for heating, air and plumbing piping, and all other equipment that are accessed for maintenance.

### 3.3 DUCT LABEL INSTALLATION

- A. Install self-adhesive duct labels with permanent adhesive on air ducts in the following color codes:
  - 1. Blue: For cold-air supply ducts.
  - 2. Yellow: For hot-air supply ducts.
  - 3. Green: For exhaust, return.
- B. Locate labels near points where ducts enter into concealed spaces and at maximum intervals of 50 feet in each space where ducts are exposed or concealed by removable ceiling system.

END OF SECTION 230553

# SECTION 230593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Balancing Air Systems:
    - a. Constant-volume air systems.
    - b. Variable-air-volume systems.
  - 2. Balancing Hydronic Piping Systems:
    - a. Constant-flow hydronic systems.
    - b. Variable-flow hydronic systems.
  - 3. Balancing Domestic Piping Systems:
    - a. Constant-flow domestic hot water circulation systems.
  - 4. Flow meter verification
    - a. Variable flow hydronic systems.

#### 1.3 DEFINITIONS

- A. AABC: Associated Air Balance Council.
- B. NEBB: National Environmental Balancing Bureau.
- C. TAB: Testing, adjusting, and balancing.
- D. TABB: Testing, Adjusting, and Balancing Bureau.
- E. TAB Specialist: An entity engaged to perform TAB Work.

# 1.4 SUBMITTALS

- A. Qualification Data: Within 14 days of Contractor's Notice to Proceed, submit documentation that the TAB contractor and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article.
- B. Contract Documents Examination Report: Within 14 days of Contractor's Notice to Proceed, submit the Contract Documents review report as specified in Part 3.
- C. Strategies and Procedures Plan: Within 30 days of Contractor's Notice to Proceed, submit TAB strategies and step-by-step procedures as specified in "Preparation" Article.
- D. Certified TAB reports.
- E. Sample report forms.
- F. Instrument calibration reports, to include the following:
  - 1. Instrument type and make.
  - 2. Serial number.
  - 3. Application.
  - 4. Dates of use.
  - 5. Dates of calibration.

# 1.5 QUALITY ASSURANCE

- A. TAB Contractor Qualifications: Engage a TAB entity certified by AABC, NEBB or TABB.
  - 1. TAB Field Supervisor: Employee of the TAB contractor and certified by AABC, NEBB or TABB.
  - 2. TAB Technician: Employee of the TAB contractor and who is certified by AABC, NEBB or TABB as a TAB technician.
- B. TAB Conference: Meet with Architect on approval of the TAB strategies and procedures plan to develop a mutual understanding of the details. Require the participation of the TAB field supervisor and technicians. Provide seven days' advance notice of scheduled meeting time and location.
  - 1. Agenda Items:
    - a. The Contract Documents examination report.
    - b. The TAB plan.
    - c. Coordination and cooperation of trades and subcontractors.
    - d. Coordination of documentation and communication flow.
- C. Certify TAB field data reports and perform the following:
  - 1. Review field data reports to validate accuracy of data and to prepare certified TAB reports.

- 2. Certify that the TAB team complied with the approved TAB plan and the procedures specified and referenced in this Specification.
- D. TAB Report Forms: Use standard TAB contractor's forms approved by Architect.
- E. Instrumentation Type, Quantity, Accuracy, and Calibration: As described in ASHRAE 111, Section 5, "Instrumentation."

### 1.6 PROJECT CONDITIONS

- A. Full Owner Occupancy: Owner will occupy the site and existing building during entire TAB period. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.
- B. Partial Owner Occupancy: Owner may occupy completed areas of building before Substantial Completion. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.

### 1.7 COORDINATION

- A. Notice: Provide seven days' advance notice for each test. Include scheduled test dates and times.
- B. Perform TAB after leakage and pressure tests on air and water distribution systems have been satisfactorily completed.

# PART 2 - PRODUCTS (NOT APPLICABLE)

# PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems' designs that may preclude proper TAB of systems and equipment.
- B. All air and hydronic systems shall be tested, adjusted and balanced.
- C. Examine systems for installed balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are accessible.
- D. Examine the approved submittals for HVAC systems and equipment.

- E. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems' output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- F. Examine ceiling plenums used for supply, return, or relief air to verify that they meet the leakage class of connected ducts as specified in Section 233113 "Metal Ducts" and are properly separated from adjacent areas. Verify that penetrations in plenum walls are sealed and fire-stopped if required.
- G. Examine equipment performance data including fan and pump curves.
  - 1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
  - 2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems Duct Design." Compare results with the design data and installed conditions.
- H. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.
- I. Examine test reports specified in individual system and equipment Sections.
- J. Examine HVAC equipment and filters and verify that bearings are greased, belts are aligned and tight, and equipment with functioning controls is ready for operation.
- K. Examine terminal units, such as variable-air-volume boxes, and verify that they are accessible and their controls are connected and functioning.
- L. Examine strainers. Verify that startup screens are replaced by permanent screens with indicated perforations.
- M. Examine three-way valves for proper installation for their intended function of diverting or mixing fluid flows.
- N. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- O. Examine operating safety interlocks and controls on HVAC equipment.
- P. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

### 3.2 PREPARATION

- A. Prepare a TAB plan that includes strategies and step-by-step procedures.
- B. Complete system-readiness checks and prepare reports. Verify the following:
  - 1. Permanent electrical-power wiring is complete.
  - 2. Hydronic systems are filled, clean, and free of air.
  - 3. Automatic temperature-control systems are operational.
  - 4. Equipment and duct access doors are securely closed.
  - 5. Balance, smoke, and fire dampers are open.
  - 6. Isolating and balancing valves are open and control valves are operational.
  - 7. Ceilings are installed in critical areas where air-pattern adjustments are required and access to balancing devices is provided.
  - 8. Windows and doors can be closed so indicated conditions for system operations can be met.

# 3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Perform testing and balancing procedures on each system according to the procedures contained in AABC's "National Standards for Total System Balance" ASHRAE 111 NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems" SMACNA's "HVAC Systems - Testing, Adjusting, and Balancing," and in this Section.
  - 1. Comply with requirements in ASHRAE 62.1-2004, Section 7.2.2, "Air Balancing."
- B. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary for TAB procedures.
  - 1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
  - 2. After testing and balancing, install test ports and duct access doors that comply with requirements in Division 23 Section "Air Duct Accessories."
  - 3. Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish according to Division 230713 Section "Duct Insulation."
- C. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.
- D. Take and report testing and balancing measurements in inch-pound (IP) units.

### 3.4 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Crosscheck the summation of required outlet volumes with required fan volumes.

- B. Prepare schematic diagrams of systems' "as-built" duct layouts.
- C. For variable-air-volume systems, develop a plan to simulate diversity.
- D. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.
- E. Check airflow patterns from the outdoor-air louvers and dampers and the return- and exhaust-air dampers through the supply-fan discharge and mixing dampers.
- F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- G. Verify that motor starters are equipped with properly sized thermal protection.
- H. Check dampers for proper position to achieve desired airflow path.
- I. Check for airflow blockages.
- J. Check condensate drains for proper connections and functioning.
- K. Check for proper sealing of air-handling-unit components.
- L. Verify that air duct system is sealed as specified in Division 23 Section "Metal Ducts."

# 3.5 PROCEDURES FOR CONSTANT-VOLUME AIR SYSTEMS

- A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.
  - 1. Measure total airflow.
    - a. Where sufficient space in ducts is unavailable for Pitot-tube traverse measurements, measure airflow at terminal outlets and inlets and calculate the total airflow.
  - 2. Measure fan static pressures as follows to determine actual static pressure:
    - a. Measure outlet static pressure as far downstream from the fan as practical and upstream from restrictions in ducts such as elbows and transitions.
    - b. Measure static pressure directly at the fan outlet or through the flexible connection.
    - c. Measure inlet static pressure of single-inlet fans in the inlet duct as near the fan as possible, upstream from the flexible connection, and downstream from duct restrictions.
    - d. Measure inlet static pressure of double-inlet fans through the wall of the plenum that houses the fan.
  - 3. Measure static pressure across each component that makes up an air-handling unit, rooftop unit, and other air-handling and -treating equipment.
    - a. Report the cleanliness status of filters and the time static pressures are measured.

TESTING, ADJUSTING, AND BALANCING FOR HVAC

- 4. Measure static pressures entering and leaving other devices, such as sound traps, heatrecovery equipment, and air washers, under final balanced conditions.
- 5. Review Record Documents to determine variations in design static pressures versus actual static pressures. Calculate actual system-effect factors. Recommend adjustments to accommodate actual conditions.
- 6. Obtain approval from Architect for adjustment of fan speed higher or lower than indicated speed. Comply with requirements in Division 23 Sections for air-handling units for adjustment of fans, belts, and pulley sizes to achieve indicated air-handling-unit performance.
- 7. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload will occur. Measure amperage in full-cooling, full-heating, economizer, and any other operating mode to determine the maximum required brake horsepower.
- B. Adjust volume dampers for main duct, sub-main ducts, and major branch ducts to indicated airflows within specified tolerances.
  - 1. Measure airflow of sub-main and branch ducts.
    - a. Where sufficient space in sub-main and branch ducts is unavailable for Pitot-tube traverse measurements, measure airflow at terminal outlets and inlets and calculate the total airflow for that zone.
  - 2. Measure static pressure at a point downstream from the balancing damper, and adjust volume dampers until the proper static pressure is achieved.
  - 3. Re-measure each sub-main and branch duct after all have been adjusted. Continue to adjust sub-main and branch ducts to indicated airflows within specified tolerances.
- C. Measure air outlets and inlets without making adjustments.
  - 1. Measure terminal outlets using a direct-reading hood or outlet manufacturer's written instructions and calculating factors.
- D. Adjust air outlets and inlets for each space to indicated airflows within specified tolerances of indicated values. Make adjustments using branch volume dampers rather than extractors and the dampers at air terminals.
  - 1. Adjust each outlet in same room or space to within specified tolerances of indicated quantities without generating noise levels above the limitations prescribed by the Contract Documents.
  - 2. Adjust patterns of adjustable outlets for proper distribution without drafts.

# 3.6 PROCEDURES FOR MOTORS

- A. Motors, 1/2 HP and Larger: Test at final balanced conditions and record the following data:
  - 1. Manufacturer's name, model number, and serial number.
  - 2. Motor horsepower rating.

- 3. Motor rpm.
- 4. Efficiency rating.
- 5. Nameplate and measured voltage, each phase.
- 6. Nameplate and measured amperage, each phase.
- 7. Starter thermal-protection-element rating.
- B. Motors Driven by Variable-Frequency Controllers: Test for proper operation at speeds varying from minimum to maximum. Test the manual bypass of the controller to prove proper operation. Record observations including name of controller manufacturer, model number, serial number, and nameplate data.

### 3.7 TOLERANCES

- A. Set HVAC system's air flow rates and water flow rates within the following tolerances:
  - 1. Supply, Return, and Exhaust Fans and Equipment with Fans: Plus or minus 10 percent.
  - 2. Air Outlets and Inlets: Plus or minus 5 percent.
  - 3. Heating-Water Flow Rate: Plus or minus 10 percent.
- B. Set domestic hot water recirculation system water flow rates to maintain measurable water flow through each branch.

#### 3.8 REPORTING

- A. Initial Construction-Phase Report: Based on examination of the Contract Documents as specified in "Examination" Article, prepare a report on the adequacy of design for systems' balancing devices. Recommend changes and additions to systems' balancing devices to facilitate proper performance measuring and balancing. Recommend changes and additions to HVAC systems and general construction to allow access for performance measuring and balancing devices.
- B. Status Reports: Prepare weekly progress reports to describe completed procedures, procedures in progress, and scheduled procedures. Include a list of deficiencies and problems found in systems being tested and balanced. Prepare a separate report for each system and each building floor for systems serving multiple floors. Include significant testing notes and comments where airflows and water flows or other recorded data outputs are not within the AABC, NEBB and/or spec standard tolerances form design numbers. Describe issues such that they can communicate whether the design, installation, access testing conditions, or other factors can be identified to the project team for response.

### 3.9 FINAL REPORT

- A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.
  - 1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.

TESTING, ADJUSTING, AND BALANCING FOR HVAC

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 2. Include a list of instruments used for procedures, along with proof of calibration.
- B. Final Report Contents: In addition to certified field-report data, include the following:
  - 1. Pump curves.
  - 2. Fan curves.
  - 3. Manufacturers' test data.
  - 4. Field test reports prepared by system and equipment installers.
  - 5. Other information relative to equipment performance; do not include Shop Drawings and product data.
- C. General Report Data: In addition to form titles and entries, include the following data:
  - 1. Title page.
  - 2. Name and address of the TAB contractor.
  - 3. Project name.
  - 4. Project location.
  - 5. Architect's name and address.
  - 6. Engineer's name and address.
  - 7. Contractor's name and address.
  - 8. Report date.
  - 9. Signature of TAB supervisor who certifies the report.
  - 10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
  - 11. Summary of contents including the following:
    - a. Indicated versus final performance.
    - b. Notable characteristics of systems.
    - c. Description of system operation sequence if it varies from the Contract Documents.
    - d. Summarized of testing notes and comments where airflows, water flows, or recorded outputs are not within AABC, NEBB and/or spec standard tolerances from design numbers.
  - 12. Nomenclature sheets for each item of equipment.
  - 13. Data for terminal units, including manufacturer's name, type, size, and fittings.
  - 14. Notes to explain why certain final data in the body of reports vary from indicated values.
  - 15. Test conditions for fans and pump performance forms including the following:
    - a. Settings for outdoor-, return-, and exhaust-air dampers.
    - b. Conditions of filters.
    - c. Cooling coil, wet- and dry-bulb conditions.
    - d. Face and bypass damper settings at coils.
    - e. Fan drive settings including settings and percentage of maximum pitch diameter.
    - f. Inlet vane settings for variable-air-volume systems.
    - g. Settings for supply-air, static-pressure controller.
    - h. Other system operating conditions that affect performance.

- D. System Diagrams: Include schematic layouts of air and hydronic distribution systems. Present each system with single-line diagram and include the following:
  - 1. Quantities of outdoor, supply, return, and exhaust airflows.
  - 2. Water and steam flow rates.
  - 3. Duct, outlet, and inlet sizes.
  - 4. Pipe and valve sizes and locations.
  - 5. Terminal units.
  - 6. Balancing stations.
  - 7. Position of balancing devices.
- E. Air-Handling-Unit Test Reports: For air-handling units with coils, include the following:
  - 1. Unit Data:
    - a. Unit identification.
    - b. Location.
    - c. Make and type.
    - d. Model number and unit size.
    - e. Manufacturer's serial number.
    - f. Unit arrangement and class.
    - g. Discharge arrangement.
    - h. Sheave make, size in inches (mm), and bore.
    - i. Center-to-center dimensions of sheave, and amount of adjustments in inches (mm).
    - j. Number, make, and size of belts.
    - k. Number, type, and size of filters.
  - 2. Motor Data:
    - a. Motor make, and frame type and size.
    - b. Horsepower and rpm.
    - c. Volts, phase, and hertz.
    - d. Full-load amperage and service factor.
    - e. Sheave make, size in inches (mm), and bore.
    - f. Center-to-center dimensions of sheave, and amount of adjustments in inches (mm).
  - 3. Test Data (Indicated and Actual Values):
    - a. Total air flow rate in cfm (L/s).
    - b. Total system static pressure in inches wg (Pa).
    - c. Fan rpm.
    - d. Discharge static pressure in inches wg (Pa).
    - e. Filter static-pressure differential in inches wg (Pa).
    - f. Preheat-coil static-pressure differential in inches wg (Pa).
    - g. Cooling-coil static-pressure differential in inches wg (Pa).
    - h. Heating-coil static-pressure differential in inches wg (Pa).
    - i. Outdoor airflow in cfm (L/s).
    - j. Return airflow in cfm (L/s).
    - k. Outdoor-air damper position.

- 1. Return-air damper position.
- m. Vortex damper position.
- F. Apparatus-Coil Test Reports:
  - 1. Coil Data:
    - a. System identification.
    - b. Location.
    - c. Coil type.
    - d. Number of rows.
    - e. Fin spacing in fins per inch (mm) o.c.
    - f. Make and model number.
    - g. Face area in sq. ft. (sq. m).
    - h. Tube size in NPS (DN).
    - i. Tube and fin materials.
    - j. Circuiting arrangement.
  - 2. Test Data (Indicated and Actual Values):
    - a. Air flow rate in cfm (L/s).
    - b. Average face velocity in fpm (m/s).
    - c. Air pressure drop in inches wg (Pa).
    - d. Outdoor-air, wet- and dry-bulb temperatures in deg F (deg C).
    - e. Return-air, wet- and dry-bulb temperatures in deg F (deg C).
    - f. Entering-air, wet- and dry-bulb temperatures in deg F (deg C).
    - g. Leaving-air, wet- and dry-bulb temperatures in deg F (deg C).
    - h. Water flow rate in gpm (L/s).
    - i. Water pressure differential in feet of head or psig (kPa).
    - j. Entering-water temperature in deg F (deg C).
    - k. Leaving-water temperature in deg F (deg C).
    - 1. Refrigerant expansion valve and refrigerant types.
    - m. Refrigerant suction pressure in psig (kPa).
    - n. Refrigerant suction temperature in deg F (deg C).
    - o. Inlet steam pressure in psig (kPa).
- G. Gas- and Oil-Fired Heat Apparatus Test Reports: In addition to manufacturer's factory startup
- H. Round, Flat-Oval, and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:
  - 1. Report Data:
    - a. System and air-handling-unit number.
    - b. Location and zone.
    - c. Traverse air temperature in deg F (deg C).
    - d. Duct static pressure in inches wg (Pa).
    - e. Duct size in inches (mm).
    - f. Duct area in sq. ft. (sq. m).

### TESTING, ADJUSTING, AND BALANCING FOR HVAC

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- g. Indicated air flow rate in cfm (L/s).
- h. Indicated velocity in fpm (m/s).
- i. Actual air flow rate in cfm (L/s).
- j. Actual average velocity in fpm (m/s).
- k. Barometric pressure in psig (Pa).

### I. Instrument Calibration Reports:

- 1. Report Data:
  - a. Instrument type and make.
  - b. Serial number.
  - c. Application.
  - d. Dates of use.
  - e. Dates of calibration.

### 3.10 INSPECTIONS

- A. Initial Inspection:
  - 1. After testing and balancing are complete, operate each system and randomly check measurements to verify that the system is operating according to the final test and balance readings documented in the final report.
  - 2. Check the following for each system:
    - a. Measure airflow of at least 20 percent of air outlets.
    - b. Measure water flow of at least 10 percent of terminals.
    - c. Measure room temperature at each thermostat/temperature sensor. Compare the reading to the set point.
    - d. Verify that balancing devices are marked with final balance position.
    - e. Note deviations from the Contract Documents in the final report.
- B. Final Inspection:
  - 1. After initial inspection is complete and documentation by random checks verifies that testing and balancing are complete and accurately documented in the final report, request that a final inspection be made by Architect.
  - 2. The TAB contractor's test and balance engineer shall conduct the inspection in the presence of Architect.
  - 3. Architect and Commissioning Authority shall randomly select measurements, documented in the final report, to be rechecked. Rechecking shall be limited to either 10 percent of the total measurements recorded or the extent of measurements that can be accomplished in a normal 8-hour business day.
  - 4. If rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."
  - 5. If the number of "FAILED" measurements is greater than 10 percent of the total measurements checked during the final inspection, the testing and balancing shall be considered incomplete and shall be rejected.

- C. TAB Work will be considered defective if it does not pass final inspections. If TAB Work fails, proceed as follows:
  - 1. Recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes; resubmit the final report and request a second final inspection.
  - 2. If the second final inspection also fails, Owner may contract the services of another TAB contractor to complete TAB Work according to the Contract Documents and deduct the cost of the services from the original TAB contractor's final payment.
- D. Prepare test and inspection reports.

### 3.11 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional TAB to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional TAB during near-peak summer and winter conditions.

END OF SECTION 230593

# SECTION 230713 - DUCT INSULATION

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section includes insulating the following duct services:
  - 1. Indoor, concealed supply and outdoor air.
  - 2. Indoor, exposed supply and outdoor air.
  - 3. Indoor, concealed, Type I, commercial, kitchen hood exhaust.
  - 4. Indoor, concealed oven and warewash exhaust.
- B. Related Sections:
  - 1. Section 233113 "Metal Ducts" for duct liners.

# 1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory- and field-applied if any).

### 1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
  - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
  - 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

### 1.5 DELIVERY, STORAGE, AND HANDLING

A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

### 1.6 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 230529 "Hangers and Supports for HVAC Piping and Equipment."
- B. Coordinate clearance requirements with duct Installer for duct insulation application. Before preparing ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.
- C. Coordinate installation and testing of heat tracing.

### 1.7 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

#### PART 2 - PRODUCTS

#### 2.1 INSULATION MATERIALS

- A. Comply with requirements in Part 3 schedule articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- D. Cellular Glass: Inorganic, incombustible, foamed or cellulated glass with annealed, rigid, hermetically sealed cells. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 1. Products: Subject to compliance with requirements, provide one of the following available products that may be incorporated into the Work include, but are not limited to, the following:

- a. Cell-U-Foam Corporation; Ultra-CUF.
- b. Pittsburgh Corning Corporation; Foamglass Super K.
- c. Or approved equal
- 2. Block Insulation: ASTM C 552, Type I.
- 3. Special-Shaped Insulation: ASTM C 552, Type III.
- E. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials and Type II for sheet materials.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Aeroflex USA Inc.; Aerocel.
    - b. Armacell LLC; AP Armaflex.
    - c. RBX Corporation; Insul-Sheet 1800 and Insul-Tube 180.
    - d. Or approved equal
- F. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type III with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. CertainTeed Corporation.
    - b. Johns Manville; a Berkshire Hathaway company.
    - c. Knauf Insulation.
    - d. Manson Insulation Inc.
    - e. Owens Corning.
- G. Mineral-Fiber, Pipe and Tank Insulation: Mineral or glass fibers bonded with a thermosetting resin. Semirigid board material with factory-applied ASJ complying with ASTM C 1393, Type II or Type IIIA Category 2, or with properties similar to ASTM C 612, Type IB. Nominal density is 2.5 lb/cu. ft. or more. Thermal conductivity (k-value) at 100 deg F is 0.29 Btu x in./h x sq. ft. x deg F or less. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. CertainTeed Corporation.
    - b. Johns Manville; a Berkshire Hathaway company.
    - c. Knauf Insulation.
    - d. Manson Insulation Inc.
    - e. Owens Corning.

#### DUCT INSULATION

# 2.2 FIRE-RATED INSULATION SYSTEMS

- A. Fire-Rated Blanket: High-temperature, flexible, blanket insulation with FSK jacket that is tested and certified to provide a 2-hour fire rating by an NRTL acceptable to authorities having jurisdiction.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. 3M.
    - b. CertainTeed Corporation.
    - c. Johns Manville; a Berkshire Hathaway company.
    - d. Nelson Firestop; a brand of Emerson Industrial Automation.
    - e. Thermal Ceramics.
    - f. Unifrax Corporation.

# 2.3 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.
- B. Cellular-Glass, Phenolic, Polyisocyanurate, and Polystyrene Adhesive: Solvent-based resin adhesive, with a service temperature range of minus 75 to plus 300 deg F.
  - 1. Products: Subject to compliance with requirements, provide one of the following available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Childers Products, Division of ITW; CP-96.
    - b. Foster Products Corporation, H. B. Fuller Company; 81-33.
    - c. Or approved equal
- C. Flexible Elastomeric and Polyolefin Adhesive: Comply with MIL-A-24179A, Type II, Class I.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Aeroflex USA, Inc.
    - b. Armacell LLC.
    - c. Foster Brand; H. B. Fuller Construction Products.
    - d. K-Flex USA.
  - 2. Adhesives shall have a VOC content of 50 g/L or less.
  - 3. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

- D. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Childers Brand; H. B. Fuller Construction Products.
    - b. Foster Brand; H. B. Fuller Construction Products.
    - c. ITW TACC, Division of Illinois Tool Works; S-90/80.
    - d. Marathon Industries, Inc.; 225.
    - e. Mon-Eco Industries, Inc.
- E. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Childers Brand; H. B. Fuller Construction Products.
    - b. Eagle Bridges Marathon Industries.
    - c. Foster Brand; H. B. Fuller Construction Products.
    - d. Mon-Eco Industries, Inc.
  - 2. Adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- F. PVC Jacket Adhesive: Compatible with PVC jacket.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Dow Corning Corporation.
    - b. Johns Manville; a Berkshire Hathaway company.
    - c. P.I.C. Plastics, Inc.
    - d. Red Devil, Inc.; Celulon Ultra Clear.
    - e. Speedline Corporation.

# 2.4 SEALANTS

A. FSK and Metal Jacket Flashing Sealants:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - a. Childers Brand; H. B. Fuller Construction Products.
  - b. Foster Brand; H. B. Fuller Construction Products.
  - c. Marathon Industries, Inc.; 225.
  - d. Mon-Eco Industries, Inc.
  - e. Vimasco Corporation; 750.
- 2. Materials shall be compatible with insulation materials, jackets, and substrates.
- 3. Fire- and water-resistant, flexible, elastomeric sealant.
- 4. Service Temperature Range: Minus 40 to plus 250 deg F.
- 5. Color: Aluminum.
- B. ASJ Flashing Sealants, and Vinyl and PVC Jacket Flashing Sealants:
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Childers Brand; H. B. Fuller Construction Products.
    - b. Or approved equal
  - 2. Materials shall be compatible with insulation materials, jackets, and substrates.
  - 3. Fire- and water-resistant, flexible, elastomeric sealant.
  - 4. Service Temperature Range: Minus 40 to plus 250 deg F.
  - 5. Color: White.

#### 2.5 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
  - 1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.
  - 2. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.
  - 3. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.
  - 4. FSP Jacket: Aluminum-foil, fiberglass-reinforced scrim with polyethylene backing; complying with ASTM C 1136, Type II.

- 5. PVDC Jacket for Indoor Applications: 4-mil thick, white PVDC biaxially oriented barrier film with a permeance at 0.02 perms when tested according to ASTM E 96 and with a flame-spread index of 5 and a smoke-developed index of 20 when tested according to ASTM E 84.
  - a. Products: Subject to compliance with requirements, provide one of the following available products that may be incorporated into the Work include, but are not limited to, the following:
    - 1) Dow Chemical Company (The); Saran 540 Vapor Retarder Film and Saran 560 Vapor Retarder Film.
    - 2) Or approved equal.
- 6. PVDC Jacket for Outdoor Applications: 6-mil thick, white PVDC biaxially oriented barrier film with a permeance at 0.01 perms when tested according to ASTM E 96 and with a flame-spread index of 5 and a smoke-developed index of 25 when tested according to ASTM E 84.
  - a. Products: Subject to compliance with requirements, provide one of the following available products that may be incorporated into the Work include, but are not limited to, the following:
    - 1) Dow Chemical Company (The); Saran 540 Vapor Retarder Film and Saran 560 Vapor Retarder Film.
    - 2) Or approved equal.
- 7. PVDC-SSL Jacket: PVDC jacket with a self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip.
  - a. Products: Subject to compliance with requirements, provide one of the following available products that may be incorporated into the Work include, but are not limited to, the following:
    - 1) Dow Chemical Company (The); Saran 540 Vapor Retarder Film and Saran 560 Vapor Retarder Film.
    - 2) Or approved equal.
- 8. Vinyl Jacket: White vinyl with a permeance of 1.3 perms when tested according to ASTM E 96, Procedure A, and complying with NFPA 90A and NFPA 90B.

# 2.6 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.
- B. FSK Jacket: Aluminum-foil-face, fiberglass-reinforced scrim with kraft-paper backing.

- C. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Johns Manville; a Berkshire Hathaway company.
    - b. P.I.C. Plastics, Inc.
    - c. Proto Corporation.
    - d. Speedline Corporation.
  - 2. Adhesive: As recommended by jacket material manufacturer.
  - 3. Color: Color-code jackets based on system. Color as selected by Architect.
  - 4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
    - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.
  - 5. Factory-fabricated tank heads and tank side panels.
- D. Aluminum Jacket: Comply with ASTM B 209, Alloy 3003, 3005, 3105 or 5005, Temper H-14.
  - 1. Products: Subject to compliance with requirements, provide one of the following available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Childers Products, Division of ITW; Metal Jacketing Systems.
    - b. PABCO Metals Corporation; Surefit.
    - c. RPR Products, Inc.; Insul-Mate.
  - 2. Sheet and roll stock ready for shop or field sizing.
  - 3. Finish and thickness are indicated in field-applied jacket schedules.
  - 4. Moisture Barrier for Indoor Applications: 3-mil thick, heat-bonded polyethylene and kraft paper.
  - 5. Moisture Barrier for Outdoor Applications: 3-mil thick, heat-bonded polyethylene and kraft paper.
  - 6. Factory-Fabricated Fitting Covers:
    - a. Same material, finish, and thickness as jacket.
    - b. Preformed 2-piece or gore, 45- and 90-degree, short- and long-radius elbows.
    - c. Tee covers.
    - d. Flange and union covers.
    - e. End caps.
    - f. Beveled collars.
    - g. Valve covers.
    - h. Field fabricate fitting covers only if factory-fabricated fitting covers are not available.

### DUCT INSULATION

- E. Self-Adhesive Outdoor Jacket: 60-mil thick, laminated vapor barrier and waterproofing membrane for installation over insulation located aboveground outdoors; consisting of a rubberized bituminous resin on a crosslaminated polyethylene film covered with white aluminum-foil facing.
  - 1. Products: Subject to compliance with requirements, provide one of the following available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Polyguard; Alumaguard 60.
    - b. Or approved equal.
- F. PVDC-SSL Jacket: PVDC jacket with a self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip.
  - 1. Products: Subject to compliance with requirements, provide one of the following available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Dow Chemical Company (The); Saran 540 Vapor Retarder Film and Saran 560 Vapor Retarder Film.
    - b. Or approved equal

### 2.7 TAPES

- A. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Avery Dennison Corporation, Specialty Tapes Division.
    - b. Compac Corporation.
    - c. Ideal Tape Co., Inc., an American Biltrite Company.
    - d. Venture Tape.
  - 2. Width: 3 inches.
  - 3. Thickness: 6.5 mils.
  - 4. Adhesion: 90 ounces force/inch in width.
  - 5. Elongation: 2 percent.
  - 6. Tensile Strength: 40 lbf/inch in width.
  - 7. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.
- B. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - a. Avery Denison Corporation, Specialty Tapes Division; Fasson 0555.
  - b. Compac Corporation.
  - c. Ideal Tape Co., Inc., an American Biltrite Company.
  - d. Venture Tape.
- 2. Width: 2 inches.
- 3. Thickness: 6 mils.
- 4. Adhesion: 64 ounces force/inch in width.
- 5. Elongation: 500 percent.
- 6. Tensile Strength: 18 lbf/inch in width.
- C. Aluminum-Foil Tape: Vapor-retarder tape with acrylic adhesive.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Avery Dennison Corporation, Specialty Tapes Division.
    - b. Compac Corporation.
    - c. Ideal Tape Co., Inc., an American Biltrite Company.
    - d. Venture Tape.
  - 2. Width: 2 inches.
  - 3. Thickness: 3.7 mils.
  - 4. Adhesion: 100 ounces force/inch in width.
  - 5. Elongation: 5 percent.
  - 6. Tensile Strength: 34 lbf/inch in width.

#### 2.8 SECUREMENTS

- A. Insulation Pins and Hangers:
  - 1. Metal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
    - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
      - 1) AGM Industries, Inc.
      - 2) Gemco.
      - 3) Midwest Fasteners, Inc.

#### DUCT INSULATION

- b. Baseplate: Perforated, galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
- c. Spindle: Copper- or zinc-coated, low-carbon steel, fully annealed, 0.106-inchdiameter shank, length to suit depth of insulation indicated.
- d. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
- 2. Nonmetal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate fastened to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
  - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - 1) Gemco.
    - 2) Midwest Fasteners, Inc.
  - b. Baseplate: Perforated, nylon sheet, 0.030 inch thick by 1-1/2 inches in diameter.
  - c. Spindle: Nylon, 0.106-inch-diameter shank, length to suit depth of insulation indicated, up to 2-1/2 inches.
  - d. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
- 3. Self-Sticking-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
  - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - 1) AGM Industries, Inc.
    - 2) Gemco.
    - 3) Midwest Fasteners, Inc.
  - b. Baseplate: Galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
  - c. Spindle: Copper- or zinc-coated, low-carbon steel, fully annealed, 0.106-inchdiameter shank, length to suit depth of insulation indicated.
  - d. Adhesive-backed base with a peel-off protective cover.
- 4. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick, galvanized-steel sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.

- a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1) AGM Industries, Inc.
  - 2) Gemco.
  - 3) Midwest Fasteners, Inc.
  - 4) Nelson Stud Welding.
- b. Protect ends with capped self-locking washers incorporating a spring steel insert to ensure permanent retention of cap in exposed locations.
- 5. Nonmetal Insulation-Retaining Washers: Self-locking washers formed from 0.016-inchthick nylon sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
  - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - 1) Gemco.
    - 2) Midwest Fasteners, Inc.
- B. Staples: Outward-clinching insulation staples, nominal 3/4-inch-wide, stainless steel or Monel.
- C. Wire: 0.062-inch soft-annealed, galvanized steel.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. C & F Wire.
    - b. Childers Products.
    - c. PABCO Metals Corporation.
    - d. RPR Products, Inc.

### 2.9 CORNER ANGLES

- A. PVC Corner Angles: 30 mils thick, minimum 1 by 1 inch, PVC according to ASTM D 1784, Class 16354-C. White or color-coded to match adjacent surface.
- B. Aluminum Corner Angles: 0.040 inch thick, minimum 1 by 1 inch, aluminum according to ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14.

# PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
  - 1. Verify that systems to be insulated have been tested and are free of defects.
  - 2. Verify that surfaces to be insulated are clean and dry.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Coordinate insulation installation with the trade installing heat tracing. Comply with requirements for heat tracing that applies to insulation.
- C. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless-steel surfaces, use demineralized water.

# 3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of ducts and fittings.
- B. Install insulation materials, vapor barriers or retarders, jackets, and thicknesses required for each item of duct system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Keep insulation materials dry during application and finishing.
- G. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- H. Install insulation with least number of joints practical.

- I. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  - 1. Install insulation continuously through hangers and around anchor attachments.
  - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
- J. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- K. Install insulation with factory-applied jackets as follows:
  - 1. Draw jacket tight and smooth.
  - 2. Cover circumferential joints with 3-inch-wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
  - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 4 inches o.c.
    - a. For below ambient services, apply vapor-barrier mastic over staples.
  - 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct flanges and fittings.
- L. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- M. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- N. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- O. Duct liner is not acceptable method; all insulation to be externally wrapped.
- P. For above ambient services, do not install insulation to the following:
  - 1. Vibration-control devices.
  - 2. Testing agency labels and stamps.
  - 3. Nameplates and data plates.
  - 4. Manholes.
  - 5. Handholes.
  - 6. Cleanouts.
### 3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
  - 4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
  - 4. Seal jacket to wall flashing with flashing sealant.
- C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.
  - 1. Comply with requirements in Section 078413 "Penetration Firestopping."
- E. Insulation Installation at Floor Penetrations:
  - 1. Duct: For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
  - 2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

#### 3.5 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

### 3.6 INSTALLATION OF MINERAL-FIBER INSULATION

- A. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
  - 1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
  - 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
  - 3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitordischarge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
    - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    - b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    - d. Do not overcompress insulation during installation.
    - e. Impale insulation over pins and attach speed washers.
    - f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
  - 4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
    - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vaporbarrier seal.
    - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.
  - 5. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. At end joints, secure with steel bands spaced a maximum of 18 inches o.c.
  - 6. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
  - 7. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch-wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

### 3.7 FIELD-APPLIED JACKET INSTALLATION

- A. Where FSK jackets are indicated, install as follows:
  - 1. Draw jacket material smooth and tight.
  - 2. Install lap or joint strips with same material as jacket.
  - 3. Secure jacket to insulation with manufacturer's recommended adhesive.
  - 4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch-wide joint strips at end joints.
  - 5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.
- B. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints; for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturer's recommended adhesive.
  - 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.
- C. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.

# 3.8 FIRE-RATED INSULATION SYSTEM INSTALLATION

- A. Where fire-rated insulation system is indicated, secure system to ducts and duct hangers and supports to maintain a continuous fire rating.
- B. Insulate duct access panels and doors to achieve same fire rating as duct.
- C. Install firestopping at penetrations through fire-rated assemblies. Fire-stop systems are specified in Section 078413 "Penetration Firestopping."

#### 3.9 FINISHES

- A. Insulation with ASJ, Glass-Cloth, or Other Paintable Jacket Material: Paint jacket with paint system identified below and as specified in Section 099123 "Interior Painting."
  - 1. Flat Acrylic Finish: Two finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.
    - a. Finish Coat Material: Interior, flat, latex-emulsion size.
- B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.

- C. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.
- D. Do not field paint aluminum or stainless-steel jackets.
- 3.10 FIELD QUALITY CONTROL
  - A. Perform tests and inspections.
  - B. Tests and Inspections:
    - 1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location(s) for each duct system defined in the "Duct Insulation Schedule, General" Article.
  - C. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

#### 3.11 DUCT INSULATION SCHEDULE, GENERAL

- A. Plenums and Ducts Requiring Insulation:
  - 1. Indoor, concealed supply and outdoor air.
  - 2. Indoor, exposed supply and outdoor air.
  - 3. Indoor, concealed, Type I, commercial, kitchen hood exhaust.
  - 4. Indoor, concealed oven and warewash exhaust.
  - 5. Indoor, concealed exhaust between isolation damper and penetration of building exterior.
  - 6. Indoor, exposed exhaust between isolation damper and penetration of building exterior.
  - 7. Outdoor, exposed supply and return.
- B. Items Not Insulated:
  - 1. Factory-insulated flexible ducts.
  - 2. Flexible connectors.
  - 3. Vibration-control devices.
  - 4. Factory-insulated access panels and doors.

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

## 3.12 INDOOR DUCT AND PLENUM INSULATION SCHEDULE

#### A. Indoor:

DUCT TYPE	DUCT LOCATION	INSULATION R VALUE	INSULATION TYPE	OTHER REQUIREMENTS
Supply, Makeup Air	On exterior of building, on roof, in attic, in enclosed ceiling space, in walls.	R-7	Mineral fiber blanket.	Approved weather proof barrier.
Type I & Type II Commercial Kitchen Hood Exhaust Duct	All		Fire rated blanket.	2 hour rating.

# 3.13 FIELD-APPLIED JACKET SCHEDULE

# A. Indoor:

- 1. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- 2. If more than one material is listed, selection from materials listed is Contractor's option.

END OF SECTION 230713

# SECTION 230800 – HVAC COMMISSIONING REQUIREMENTS

#### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes general requirements that apply to implementation of commissioning of HVAC systems and components. It will assist operating staff training and familiarization with new systems. It will serve as a tool to reduce post-occupancy critical systems operational difficulty or failure. It will also be used to develop test protocol and record the associated test data to advance the building systems from a state of substantial completion to operation.
- B. All mechanical systems in the project shall perform in accordance with the design intent and the Owner's operational needs.
- C. The Commissioning Process Overview, applying to the HVAC systems and HVAC commissioning team members, can be found in specifications section 019113, General Commissioning Requirements.
- D. Systems to be commissioned:
  - 1. HVAC and mechanical system and all integral equipment controls. All HVAC systems shall be commissioned, including, but not limited to:
    - a. Building Controls
    - b. Makeup air units
    - c. Exhaust fans
    - d. TAB

#### 1.2 RESPONSIBILITIES

A. Overview: The responsibilities of the HVAC commissioning team members in the commissioning process are summarized in specifications section 019113, General Commissioning Requirements.

#### 1.3 SUBMITTALS

- A. Other Equipment and System Information.
  - 1. When not included with the standard submittals, the Trade Subcontractors shall provide to the Commissioning Provider requested shop drawings, the manufacturer's printed installation and detailed start-up procedures, full sequences of operation, O&M data, performance data, any performance test procedures and control drawings. In addition, the manufacturer installation and checkout materials that are shipped inside the equipment and the field checkout forms to be used by the factory or field technicians shall be

#### HVAC COMMISSIONING REQUIREMENTS

submitted to the Commissioning Provider. This documentation may be required prior to the normal O&M manual submittals.

- B. All equipment and system documentation requested by the Commissioning Provider shall be included by the Trade Subcontractors later in the O&M manuals.
- C. The Trade Subcontractors shall submit startup forms and procedures.

## 1.4 QUALITY ASSURANCE

#### A. Test Equipment:

- 1. All standard testing equipment required for the Trade Subcontractors to perform installation, start-up and initial checkout and required functional testing shall be provided by the Trade Subcontractors.
- 2. Special tools and instruments, only available from vendor, specific to a piece of equipment, required for testing equipment according to these Contract Documents shall be provided.
- 3. Instrumentation will be provided by the Subcontractor. Instruments used for measurements shall be accurate. Calibration histories for each instrument shall be available for examination. Calibration and maintenance of instruments shall be in accordance with the requirements of NEBB or AABC Standards.
- 4. Application of instruments and accuracy of measurements shall be in accordance with NEBB or AABC Standards.
- 5. The Trade Subcontractors shall provide datalogging equipment for setting up and testing of cold rooms, clean room certification, fume hoods and lab room pressurization and equipment required to perform specified electrical equipment testing.
- 6. Datalogging equipment required for testing equipment in support areas shall be provided and used by the Commissioning Provider.

# 1.5 COORDINATION

A. Commissioning Team: The members of the commissioning team consist of the Commissioning Provider, the Owner/Owner Representative, the GC, the Architect and Design Engineers, the mechanical contractor, the testing adjusting and balancing contractor, the controls contractor, any other installing subcontractors or suppliers of commissioned equipment or systems and the facility or plant operator/engineer.

# PART 2 - PRODUCTS NOT USED

HVAC COMMISSIONING REQUIREMENTS

# PART 3 - EXECUTION

# 3.1 MEETINGS

- A. Kick-off Meeting: The Commissioning Provider will schedule, plan and conduct a commissioning kick-off meeting with the entire commissioning team in attendance, including the controls, electrical, plumbing, mechanical, adjusting and balancing and other appropriate Trade Subcontractors and the facility operator or Owner Representative in attendance. Prior to this meeting, the commissioning plan will be distributed to all members. The commissioning plan, the overall commissioning process and general responsibilities of each team member, reporting and communication protocols and next steps will be discussed. Meeting minutes will be distributed to all parties by the Commissioning Provider.
- B. Miscellaneous Meetings: Deficiencies identified through the commissioning process shall be discussed, as needed, in portions of regular construction meetings. Meetings dedicated to deficiencies or commissioning: status, coordination and planning shall also be conducted, if needed. The Commissioning Provider will plan, conduct and take minutes at commissioning meetings. When practical, commissioning meetings will be an appendage to regular construction meetings. All commissioning meetings shall be attended by the GC, the mechanical and the controls subcontractor. Selected meetings shall require the attendance of the electrical, TAB or other trades of commissioned systems.
- C. Controls Integration Meeting: The Commissioning Provider coordinates the meeting to go over the control drawings, sequences of operation included in the controls submittal. This meeting is held prior to the approval of the controls submittal. The intent is to clarify control related issues for the controls contractor, mechanical, fire alarm, plumbing and electrical contractor, facility staff and Commissioning Provider prior to startup, testing and balancing and functional testing.
  - 1. The controls contractor shall attend the meeting. The mechanical, electrical and general contractor shall attend when issues regarding equipment they are responsible for are discussed. The control technicians attending the meetings must be the same technicians that are/will install and program the DDC system.
  - 2. Primary issues discussed and clarified are:
    - a. Control drawing content
    - b. Point database (points (monitored points, software points, naming conventions, alarms, report format)
    - c. Sequences of operation and setpoints
    - d. Interlocks to packaged controls and other systems
    - e. Operator workstation graphics
    - f. Field sensor and panel locations
  - 3. The Commissioning Provider takes minutes at these meetings.

# 3.2 COMMISSIONING CHECKLISTS, START-UP, AND INITIAL CHECKOUT

A. The following procedures apply to all equipment and systems to be commissioned:

# HVAC COMMISSIONING REQUIREMENTS

- 1. Commissioning Checklists:
  - a. GC and Trade Subcontractors are to execute pre-functional system checks using the Commissioning Provider's created forms on the web based commissioning software Facility Grid.
  - b. The Commissioning Provider develops and completes the commissioning checklists and procedures for commissioned equipment and systems.
  - c. Calibrations: The construction checklists will contain requirements for calibrations when applicable. The Trade Subcontractors is responsible to calibrate all field-installed sensors and actuators using checkout documentation methods approved by the Commissioning Provider.
- 2. Manufacturer Installation and Startup Procedures:
  - a. A start-up plan shall be developed and submitted by the installing Subcontractor. Start-up plan to include the following:
    - 1) Flushing and cleaning of pipe
    - 2) Filters, strainers, and screens.
    - 3) Valve/damper positions.
    - 4) Electrical tests.
    - 5) Safeties.
    - 6) Manufacturer's tests.
  - b. The Trade Subcontractors shall complete the pre-start procedures in the manufacturer startup forms prior to starting equipment, including but not limited to verification of completion of wiring, safeties, lubrication, drive rotation and proper electrical test readings. Startup shall be conducted under supervision of responsible manufacturer representatives for major pieces of equipment. The GC shall notify the Commissioning Provider at least 5 days in advance of any equipment start-up, providing the Commissioning Provider a copy of the start-up plan at that time.
  - c. The Commissioning Provider shall observe startup and checkout of selected systems.
  - d. The Trade Subcontractors and manufacturer representatives shall execute start-up and provide the Commissioning Provider with a signed and dated copy of the completed start-up documentation. The Trade Subcontractors shall clearly note any items that have not been completed and the plan for their completion.
  - e. The Trade Subcontractors shall operate each commissioned device or system to the full extent of its capability, from minimum to maximum, under automatic and manual control and verify that the equipment, system and assembly is functioning according to the specifications, manufacturer recommendations and good operating practice.
  - f. The manufacturer startup reports and procedures for a given system shall be successfully completed and submitted prior to testing, adjusting and balancing of the equipment.
  - g. The Commissioning Provider will review startup documentation and identify incomplete areas.
  - h. The Trade Subcontractors shall correct all areas that are deficient or incomplete in the startup documentation in a timely manner.

#### HVAC COMMISSIONING REQUIREMENTS

3. Designated systems requiring test and balance work shall have this activity commence after systems have successfully completed start-up. System and equipment deficiencies observed during this activity is to be noted and corrected.

# 3.3 FUNCTIONAL TESTING

- A. Functional Performance Testing begins after operational testing, adjusting, and balancing of the systems have been completed by the Subcontractors. Functional tests for a given system shall not be conducted until they are fully operational under normal and reliable control with control calibrations, programming and control system graphics complete and checked out and the Trade Subcontractors have submitted completed, applicable startup reports, satisfactory to the Commissioning Provider.
- B. The objective of the Functional Performance Testing is to advance the building systems from a state of substantial completion to full dynamic operation in accordance with the specified design requirements and design intent.
- C. Any test ports, gauges, test equipment, etc., needed to accomplish the functional performance tests shall be provided by Subcontractors.
- D. Subcontractors shall provide to the Commissioning Team documentation of calibration of controls. Documentation shall include dates, setpoints, calibration coefficients, control loop verification, and other data required to verify system check-out. Documentation shall be dated and initialed by field engineer or technician performing the work.

# 3.4 DEFICIENCIES AND NON-CONFORMANCE

- A. Deficiency Management
  - 1. The Commissioning Provider will record the results of document reviews, field observations, tests conducted or reviewed and trend logs or monitoring. All deficiencies will be recorded on a Deficiency Log kept by the Commissioning Provider. The Deficiency Log will be kept updated by the Commissioning Provider.
  - 2. All deficiencies will be tracked using the online commissioning software Facility Grid. A current copy of the Deficiency Log will be provided to the GC and Owner/Owner Representative on a regular basis, as requested. New deficiencies will be identified.
  - 3. Items that are incomplete or are requiring Designer input will be sent to the Designer and Owner/Owner Representative by the Commissioning Provider via appropriate channels.
  - 4. When completion of a deficiency has been identified by the Commissioning Provider as holding up or is likely to delay any commissioning process, particularly functional testing, the GC, shall be required to notify the Commissioning Provider providing the planned actions and an expected date of completion. The GC shall notify the Commissioning Provider listing the actions taken to resolve the issue. It is not the responsibility of the Commissioning Provider to obtain this status information through meeting attendance, asking questions or field observation.
  - 5. The Commissioning Provider documents resolutions in the Deficiency Log and schedules retesting and backchecking as needed.

# HVAC COMMISSIONING REQUIREMENTS

- 6. Every effort will be made to expedite the testing process and minimize unnecessary delays, while not compromising the integrity of the procedures. However, the Commissioning Provider will not be pressured into overlooking deficient work or loosening acceptance criteria to satisfy scheduling or cost issues, unless there is an overriding reason to do so.
  - a. The time for the Commissioning Provider to direct, document and evaluate any retesting required because a specific construction checklist or start-up test item, reported to have been successfully completed, but determined during testing to be faulty, will be charged to the GC.
  - b. The GC shall reimburse the Commissioning Provider for costs when a scheduled test cannot be completed due to:
    - 1) Failure of the GC to schedule the test with all parties required to perform the test or with regulatory authorities required to witness the test.
    - 2) Failure of the GC to provide required notice for tests that have been cancelled or rescheduled.
    - 3) Failure of the GC or Trade Subcontractors to have in place test equipment, support equipment, instrumentation, permits, or other ancillary equipment or systems required for successful execution of the test.
    - 4) Failure of the Trade Subcontractors to complete pre-start or start-up procedures or other work required as a prerequisite for execution of the test.
- 7. The GC shall respond in writing to the Commissioning Provider at least as often as commissioning meetings are being scheduled concerning the status of each outstanding deficiency identified during commissioning. Discussion shall cover explanations of any disagreements and proposals for their resolution.
- B. Approval and Acceptance: The Commissioning Provider will note each satisfactorily demonstrated function on the test form. Functional testing or acceptance of a system is indicated after all testing and monitoring is complete and there are no outstanding deficiencies for that equipment or system in the Commissioning Provider's Deficiency Log.

# 3.5 DEFERRED TESTING

- A. Unforeseen Deferred Tests: If any functional test cannot be completed due to the building structure, required occupancy condition or other deficiency, execution of functional testing may be delayed.
- B. Seasonal Testing: During the warranty period, seasonal testing (tests delayed until weather conditions are closer to the system's design) specified in the testing requirements shall be completed as part of this contract. The Commissioning Provider will coordinate this activity. Tests will be executed, documented and deficiencies corrected by the Trade Subcontractors, with facilities staff and the Commissioning Provider witnessing. The Trade Subcontractors shall make needed final adjustments to the O&M manuals and record documents due to the testing results.

# HVAC COMMISSIONING REQUIREMENTS

#### 3.6 ADDITIONAL DOCUMENTATION

- A. Documentation required of the Trade Subcontractors shall consist of the following:
  - 1. Startup and initial checkout forms completed.
  - 2. Record of deficiencies and incomplete items for tests they are responsible to document.
  - 3. Training record.
- B. O&M Documentation Completion and Review:
  - 1. Prior to substantial completion, the Commissioning Provider shall review the O&M manuals for systems that were commissioned to verify compliance with the specifications. The Commissioning Provider will communicate deficiencies in the manuals to the Commissioning Team.
  - 2. The Commissioning Provider will also review each equipment warranty and verify that requirements to keep the warranty valid are clearly stated.
  - 3. This work does not supersede the Design Team's review of the O&M manuals.

# 3.7 TRAINING OF FACILITY PERSONNEL

A. The Trade Subcontractors are responsible to provide training for facility personnel per the Contract Documents. The Trade Subcontractors shall work with the Commissioning Provider to develop appropriate training and orientation agendas for equipment and systems and provide skilled trainers for the sessions. The Commissioning Provider will verify that the Trade Subcontractors execute training per the Contract Documents.

END OF SECTION 230800

HVAC COMMISSIONING REQUIREMENTS

# SECTION 230923 – DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

### PART 1 - GENERAL

### 1.1 WORK INCLUDED GENERAL

- A. Provide controls that will connect to the existing Trane TracerSC controls system. Provide monitoring and control of the new systems as part of compliance with the existing site system.
- B. Provide all necessary BACnet-compliant hardware and software to meet the system's functional specifications. Provide Protocol Implementation Conformance Statement (PICS) for Windows-based control software and every controller in system, including unitary controllers.
- C. Prepare individual hardware layouts, interconnection drawings, and software configuration from project design data.
- D. Implement the detailed design for all analog and binary objects, system databases, graphic displays, logs, and management reports based on control descriptions, logic drawings, configuration data, and bid documents.
- E. Design, provide, and install all equipment cabinets, panels, data communication network cables needed, and all associated hardware.
- F. Provide and install all interconnecting cables between supplied cabinets, application controllers, and input/output devices.
- G. Provide and install all interconnecting cables between all operator's terminals and peripheral devices (such as printers, etc.) supplied under this section.
- H. Provide complete manufacturer's specifications for all items that are supplied. Include vendor name of every item supplied.
- I. Provide supervisory specialists and technicians at the job site to assist in all phases of system installation, startup, and commissioning.
- J. Provide a comprehensive operator and technician training program as described herein.
- K. Provide as-built documentation, operator's terminal software, diagrams, and all other associated project operational documentation (such as technical manuals) on approved media, the sum total of which accurately represents the final system.
- L. Provide new sensors, dampers, valves, and install only new electronic actuators. No used components shall be used as any part or piece of installed system.

# 1.2 SYSTEM DESCRIPTION

- A. Distributed logic control system complete with all software and hardware functions shall be provided and installed. System shall be completely based on ANSI/ASHRAE Standard 135-2008, BACnet and achieved listing under the BACnet Testing Laboratories BACnet Advanced Workstation Software (B-AWS). This system is to control all mechanical equipment, including all unitary equipment such as VAV boxes, AC units, etc., and all air handlers, and any other listed equipment using native BACnet-compliant components. Non-BACnet-compliant or proprietary equipment or systems (including gateways) shall not be acceptable and are specifically prohibited.
- The Building Automation System (BAS) application program shall be written to communicate B. specifically utilizing BACnet protocols. Software functions delivered on this project shall include password protection, scheduling (including optimum start), alarming, logging of historical data, full graphics including animation, demand limiting, and a full suite of field engineering tools including graphical programming and applications. Systems using operating systems other than that described above are strictly prohibited. All software required to program application specific controllers and all field level devices and controllers will be left with the owner. All software passwords required to program and make future changes to the system will also become the property of the owner. All software required to make any program changes anywhere in the system, along with scheduling and trending applications, will be left with the owner. All software passwords required to program and make future changes to schedules, trends and related program changes will also become the property of the owner. All software required for all field engineering tools including graphical programming and applications will be left with the owner. All software passwords required to program and make future changes to field engineering tools, including graphical programming and applications will be left with the owner.
- C. Room sensors shall be provided stainless steel plates with no adjustment or temperature readout.
- D. All application controllers for every terminal unit (VAV, HP, UV, etc.) air handler, all central plant equipment, and any other piece of controlled equipment shall be fully programmable. Application controllers shall be mounted next to controlled equipment and communicate with building controller through BACnet LAN.

# 1.3 APPROVED MANUFACTURERS

1. Existing system is Trane TracerSC, system installed shall be compatible with this system.

# 1.4 QUALITY ASSURANCE

A. The Building Automation System (BAS) system shall be designed, installed, commissioned, and serviced by manufacturer authorized and trained personnel. The Controls contractor shall be regularly engaged in the engineering, programming, installation, and service of Control systems by the selected manufacturer and shall have a minimum of five years' experience with the complete, turn-key installation of Controls by the same manufacturer of similar size and technical complexity. If portions of the installation will be performed by a subcontractor, the

#### DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

Controls Contractor will submit to the owner two sample installations performed by subcontractor which are similar to the current project. The controls contractors shall have local branch facility within a 75-mile radius of the job site. Emergency Service shall be available on a 24-hour, 7-day a week basis.

- B. The contractor shall provide an experienced project manager for this work, responsible for direct supervision of the design, installation, start-up and commissioning of the BAS system.
- C. Materials and equipment shall be manufacturer's latest standard design that complies with the specification requirements.
- D. All BAS peer-to-peer network controllers, central system controllers and local user displays shall be UL Listed under Standard UL 916, category PAZX.
- E. All electronic equipment shall conform to the requirements of FCC Regulation, Part 15, Governing Radio Frequency Electromagnetic Interference and be so labeled.
- F. Control system shall be engineered, programmed and supported completely by representative's local office.

# 1.5 REFERENCE STANDARDS

- A. The latest edition of the following standards and codes in effect and amended as of supplier's proposal date, and any applicable subsections thereof, shall govern design and selection of equipment and material supplied:
  - 1. American Society of Heating, Refrigerating and Air Conditioning Engineers (ASHRAE).
  - 2. ANSI/ASHRAE Standard 135-2008, BACnet.
  - 3. 2012 IBC Effective July 1, 2014.
  - 4. UL 916 Underwriters Laboratories Standard for Energy Management Equipment. Canada and the US.
  - 5. National Electrical Code (NEC).
  - 6. FCC Part 15, Subpart J, Class A.
  - 7. EMC Directive 89/336/EEC (European CE Mark).
  - 8. BTL BACnet Testing Laboratory
- B. City, county, state, and federal regulations and codes in effect as of contract date.
- C. Except as otherwise indicated, the system supplier shall secure and pay for all permits, inspections, and certifications required for his work, and arrange for necessary approvals by the governing authorities.

#### 1.6 SUBMITTALS

A. Drawings:

# DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

- 1. The system supplier shall submit engineered drawings, control sequence, and bill of materials for approval.
- 2. Drawings shall be submitted in the following standard sizes: 11" x 17" (ANSI B).
- 3. Submittal drawings and system documentation (see System Documentation) shall be provided to BSD, contractor and architects in pdf format that is searchable for all text in design drawings showing controls systems, equipment, devices, and materials.
- B. System Documentation

Include the following in submittal package:

- 1. System configuration diagrams in simplified block format.
- 2. All input/output object listings and an alarm point summary listing.
- 3. Electrical drawings that show all system internal and external connection points, terminal block layouts, and terminal identification.
- 4. Complete bill of materials, valve schedule and damper schedule.
- 5. Manufacturer's instructions and drawings for installation, maintenance, and operation of all purchased items.
- 6. Overall system operation and maintenance instructions—including preventive maintenance and troubleshooting instructions.
- 7. For all system elements—operator's workstation(s), building controller(s), application controllers, routers, and repeaters—provide BACnet Protocol Implementation Conformance Statements (PICS) as per ANSI/ASHRAE Standard 135-2001.
- 8. Provide complete description and documentation of any proprietary (non-BACnet) services and/or objects used in the system.
- 9. A list of all functions available and a sample of function block programming that shall be part of delivered system.
- C. Project Management
  - 1. The vendor shall provide a detailed project design and installation schedule with time markings and details for hardware items and software development phases. Schedule shall show all the target dates for transmission of project information and documents, and shall indicate timing and dates for system installation, debugging, and commissioning.
- D. BACnet Device Object Naming Conventions
  - 1. The BAS manufacturer's representative shall submit a BACnet Device Object Naming Convention Plan (DONCP) to the owner and consulting engineer during the submittal process. The plan must be approved by the owner and consulting engineer prior to implementation. It is the responsibility of the BAS contractor to coordinate the DONCP with the owner and consulting engineer.
  - 2. The DONCP shall be designed to eliminate any confusion between individual points in a facility/campus wide EMCS system. It will also be designed to allow for future expansion and consistency. Each device on a BACnet internetwork (including other manufacturer's devices) must have a unique device instance. This is a major consideration when adding to an existing system or interconnecting networks. Thorough and accessible site documentation is critical.

- 3. A consistent object (point) naming convention shall be used to facilitate familiarity and operational ease across an eventual large campus or inventory of facilities. The following section is designed as recommendations only. It is the responsibility of the BAS contractor to coordinate the DONCP with the owner and consulting engineer to provide a naming convention that is compatible with BSD standards.
- 4. BACnet requires that all devices have a Device object name that is unique throughout the entire internetwork. To comply with this requirement all BACnet devices should be configured with a Device Object Name that is based on the naming conventions described in this section. This includes all physical devices as well as any logical BACnet devices that are represented by gateways. The vendor shall coordinate with the owner's staff to ensure that the correct names are used. Device Object Name properties shall support strings of at least 50 characters in length.
- 5. Follow naming convention as required
- 6. Every system device has addresses by which any other BACnet device can identify it and route information to and from it. Although there are a number of addresses to consider, the scheme is fairly straightforward. It can become complicated, however, if addresses have not been documented adequately or there is no logical addressing scheme.
- 7. When you set up and plan a BACnet network or add to an existing network, considering and documenting your addressing scheme is of the utmost importance. Adopt a hierarchical and uniform addressing scheme for device instances to help you quickly identify the function and location of different devices when troubleshooting. Additionally, it's very important to document every element of your addressing scheme and update the site documentation with any changes.
- 8. This section first covers the important addressing issues with respect to BACnet LANs and it gives a practical application you can use to check your understanding.
- 9. BACnet addressing
- 10. Three types of addresses are important in any BACnet system: network numbers, media access control (MAC) addresses, and device instances. Each BACnet device has these addresses associated with it. Though all three can be thought of as addresses, they are all very different both in how they function and how they are assigned.
- 11. Network numbers Identifies the network to which a BACnet device belongs. Every network on a BACnet LAN has a unique numerical identifier—a network number. This network number is used by BACnet devices only; it does not rely on nor does it affect any other network protocols. LANs connected by a router must have different network numbers. No interconnected BACnet networks can have the same network number. Network number range is 1–65,534, for a maximum of 65,534 interconnected BACnet networks.

IMPORTANT BACnet reserves network numbers 0 and 65,535 for special purposes. Don't use network 0 or 65,535.

- 12. MAC addresses Hardware-oriented. The MAC address uniquely identifies a device on its particular network. Each network type—Ethernet and MS/TP—has its own MAC addressing scheme. A device that exists on two or more networks will have a MAC address for each one. Devices can have the same MAC addresses as long as they are on networks with different network numbers.
- 13. Note It's helpful to think of the MAC address as a house number and the network number as the street number. Two houses can have the same house number (MAC address) as long as they are on different streets (networks).

- a. Ethernet devices: For Ethernet LANs, the IEEE assigns a certain range of MAC addresses to manufacturers of Ethernet products. The manufacturer then assigns a unique MAC address to each of its Ethernet devices.
- b. MS/TP devices: For devices on an MS/TP LAN, you assign the MAC address for each controller. For BACtalk VLCs, these are assigned with DIP switches. Devices on an MS/TP LAN are designated as either masters or slaves, which affects how they can be addressed. This is a requirement of the BACnet specification. All BACtalk MS/TP devices are masters.
- c. IMPORTANT BACnet reserves MS/TP MAC address 255 for special purposes. Don't use MS/TP MAC 255.
- d. Device instances Software-oriented. The device instance identifies the device to the BACnet software and is the address most often encountered. The device instance is a shortcut to having to specify a MAC address and network number each time an operation is performed. Device instances range from 0–4194302.
- e. Note BACnet reserves device instance 4194303 for special purposes. Don't use device instance 4194303.

# 1.7 WARRANTY

- A. Warranty shall cover all costs for parts, labor, associated travel, and expenses for a period of one (1) year from completion of system acceptance.
- B. Hardware and software personnel supporting this warranty agreement shall provide on-site or off-site service in a timely manner after failure notification to the vendor. The maximum acceptable response time to provide this service at the site shall be 24 hours, Monday through Friday, and 48 hours on Saturday and Sunday.
- C. This warranty shall apply equally to both hardware and software.

# 1.8 RELATED WORK IN OTHER SECTIONS

- A. Refer to Division 0 and Division 1 for related contractual requirements.
- B. Refer to other sections in Division 23 for General Mechanical Provisions.
- C. Refer to Division 26 for General Electrical Provisions.

# PART 2 - PRODUCTS

# 2.1 CENTRAL PLANT AND AIR HANDLER APPLICATION CONTROLLERS

A. Provide one or more native BACnet application controllers for each air handler and provide native BACnet application controllers as needed for central plant control that adequately cover all objects listed in object list. All controllers shall interface to building controller through either MS/TP LAN using BACnet protocol, or Ethernet LAN using BACnet over Ethernet or BACnet

# DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

TCP/IP. No gateways shall be used. Controllers shall include input, output and self-contained logic program as needed for complete control of units. Controllers shall be fully programmable using graphical programming blocks. Programming tool shall be resident on operator workstation and be the same tool as used for the building controller. No auxiliary or non-BACnet controllers shall be used.

- B. BACnet Conformance
  - 1. Application controllers shall be approved by the BTL as meeting the BACnet Advanced Application Controller requirements.
  - 2. Please refer to section 22.2, BACnet Functional Groups, in the BACnet standard, for a complete list of the services that must be directly supported to provide each of the functional groups listed above. All proprietary services, if used in the system, shall be thoroughly documented and provided as part of the submittal data. All necessary tools shall be supplied for working with proprietary information.
  - 3. Standard BACnet object types supported shall include, as a minimum, Analog Input, Analog Output, Analog Value, Binary Input, Binary Output, Binary Value, Multi-state Values, Device, File, and Program object types. All proprietary object types, if used in the system, shall be thoroughly documented and provided as part of the submittal data. All necessary tools shall be supplied for working with proprietary information.
- C. Application controllers shall include universal inputs with 12-bit resolution that accept 3K and 10K thermistors, 0–10VDC, Platinum 1000 Ohm RTD, 0–5VDC, 4–20mA and dry contact signals. Any input on a controller may be either analog or digital with a minimum of three (3) inputs that accept pulses. Controller shall also include support and modifiable programming for interface to intelligent room sensor with digital display. Controller shall include binary and analog outputs on board. Analog outputs with 12-bit resolution shall support either 0–10VDC or 0–20mA. Binary outputs shall have LED indication of status. Software shall include scaling features for analog outputs. Application controller shall include 20VDC voltage supply for use as power supply to external sensors.
  - 1. All outputs must have on-board Hand-Off-Auto (HOA) switches and a status indicator light. HOA switch position shall be monitored. Each analog output shall include a potentiometer for manually adjusting the output when the HOA switch is in the Hand position. The position of each and every HOA switch shall be available system wide as a BACnet object property.
- D. All program sequences shall be stored on board application controller in EEPROM. No batteries shall be needed to retain logic program. All program sequences shall be executed by controller up to 20 times per second (minimum of 10 times per second) and capable of multiple PID loops for control of multiple devices. All calculations shall be completed using floating-point math and system shall support display of all information in floating-point nomenclature at operator's terminal.
  - 1. The following control blocks shall be supported:
    - a. Natural Log
    - b. Exponential
    - c. Log base 10

# DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- d. X to the power of Y
- e. Nth square root of X
- f. 5<sup>th</sup> Order Polynomial Equations
- g. Astronomical Clock (sunrise/sunset calculation)
- h. Time-based schedules
- E. Programming of application controller shall be completely modifiable in the field over installed BACnet LANs or remotely using modem interface. Operator shall program logic sequences by graphically moving function blocks on screen and tying blocks together on screen. Application controller shall be programmed using programming tools as described in operator's terminal section.
- F. Application controller shall include support for intelligent room sensor (see Section 2.9.B.) Display on intelligent room sensor shall be programmable at application controller and include an operating mode and a field service mode. All button functions and display data shall be programmable to show specific controller data in each mode, based on which button is pressed on the sensor. See sequence of operation for specific display requirements at intelligent room sensor.
- G. Schedules
  - 1. The controller shall support a minimum of three (3) BACnet Schedule Objects and have a real-time clock on board with battery backup to maintain time through a power loss.
- H. Logging Capabilities
  - 1. Controller shall support a minimum of 50 trendlogs. Any object in the controller (real or calculated) may be logged. Sample time interval shall be adjustable at the operator's workstation.
  - 2. Controller shall periodically upload trended data to system server for long-term archiving if desired. Archived data stored in (MS Jet Database or SQL) database form and shall be available for use in third-party spreadsheet or database programs.
- I. Alarm Generation
  - 1. Alarms may be generated within the controller for any object change of value or state (either real or calculated). This includes things such as analog object value changes, and binary object state changes.
  - 2. Alarm log shall be provided for alarm viewing. Log may be viewed on-site at the operator's terminal or off-site using remote communications.
  - 3. Controller must be able to handle up to 25 alarm setups stored as BACnet event enrollment objects, with system destination and actions individually configurable.
- J. The controller processor shall be a 32-bit processor.
- K. The packaging of the controller shall provide operable doors to cover the terminals once installation is complete. The housing of the controller shall provide for DIN rail mounting and also fully enclose circuit board.

- 2.2 TERMINAL UNIT APPLICATION CONTROLLERS (Heat Pumps, AC Units, Fan-Coils, Boilers, Mini Split Systems)
  - A. Provide one (1) native BACnet application controller for each piece of unitary mechanical equipment that adequately covers all objects listed in object list for unit. All controllers shall interface to building controller through MS/TP LAN using BACnet protocol. No gateways shall be used. Controllers shall include input, output and self-contained logic program as needed for complete control of unit.
  - B. BACnet Conformance
    - 1. Application controllers shall, as a minimum, support MS/TP BACnet LAN types. They shall communicate directly using this BACnet LAN at 9.6, 19.2, 38.4 and 76.8 Kbps, as a native BACnet device. Application controllers shall be approved by the BTL as meeting the BACnet Application Specific Controller requirements and support all BACnet services necessary to provide the following BACnet functional groups:
      - a. Files Functional Group
      - b. Reinitialize Functional Group
      - c. Device Communications Functional Group
    - 2. Please refer to Section 22.2, BACnet Functional Groups in the BACnet standard, for a complete list of the services that must be directly supported to provide each of the functional groups listed above. All proprietary services, if used in the system, shall be thoroughly documented and provided as part of the submittal data. All necessary tools shall be supplied for working with proprietary information.
    - 3. Standard BACnet object types supported shall include, as a minimum, Analog Input, Analog Output, Analog Value, Binary Input, Binary Output, Binary Value, Device, File, and Program Object Types. All proprietary object types, if used in the system, shall be thoroughly documented and provided as part of the submittal data. All necessary tools shall be supplied for working with proprietary information.
  - C. Application controllers shall include universal inputs with 10-bit resolution that can accept 3K and 10K thermistors, 0–5VDC, 4–20mA, dry contact signals and a minimum of three (3) pulse inputs. Any input on controller may be either analog or digital. Controller shall also include support and modifiable programming for interface to intelligent room sensor. Controller shall include binary outputs on board with analog outputs as needed.
  - D. All program sequences shall be stored on board controller in EEPROM. No batteries shall be needed to retain logic program. All program sequences shall be executed by controller 10 times per second and shall be capable of multiple PID loops for control of multiple devices. Programming of application controller shall be completely modifiable in the field over installed BACnet LANs or remotely through modem interface. Operator shall program logic sequences by graphically moving function blocks on screen and tying blocks together on screen. Application controller shall be programmed using same programming tools as building controller and as described in operator workstation section. All programming tools shall be provided and installed as part of system.

E. Application controller shall include support for intelligent room sensor (see Section 2.9.B.) Display on room sensor shall be programmable at controller and include an operating mode and a field service mode. All button functions and display data shall be programmable to show specific controller data in each mode based on which button is pressed on the sensor. See sequence of operation for specific display requirements at intelligent room sensor.

# 2.3 AUXILIARY CONTROL DEVICES

- A. Temperature Sensors
  - 1. All temperature sensors to be solid-state electronic, interchangeable with housing appropriate for application. Wall sensors to be installed as indicated on drawings. Mount 48 inches above finished floor. Duct sensors to be installed such that the sensing element is in the main air stream. Immersion sensors to be installed in wells provided by control contractor, but installed by mechanical contractor. Immersion wells shall be filled with thermal compound before installation of immersion sensors. Outside air sensors shall be installed away from exhaust or relief vents, not in an outside air intake, and in a location that is in the shade most of the day.
- B. Wall Sensor (for spaces with temperature control only)
- C. Blank brushed stainless steel wall plate with high precision 10K ohm Type II thermistor epoxied to the backside. Pack the back of the sensor with insulation where there is potential for in-wall draft. Avoid mounting temperature sensor on outside walls or next to doors leading to the hallway. After-hours override pushbutton on sensors for cafeteria, gym, library and front office only. Room Carbon Dioxide CO2 with Temperature Sensor (for spaces with CO2 & temperature control). Pack the back of the sensor with insulation where there is potential for in-wall draft. Avoid mounting temperature sensor on outside walls or next to doors leading to the hallway. After-hours override pushbutton on sensors for cafeteria, gym, library and front office only.
  - 1. Input Power 12 to 30VDC/24AC; 100mA Maximum
  - 2. Analog Output 0-10VDC
  - 3. Operating Temperature Range 0° to 50°C (32° to 122°F)
  - 4. Housing Material High impact plastic
  - 5. Sensor Type Non-dispersive infrared, diffusion sampling
  - 6. Measurement Range 0-2000/5000 ppm
  - 7. Accuracy  $\pm 40 \text{ ppm} \pm 3\%$  of measured value\*
  - 8. Repeatability  $\pm 20$  ppm  $\pm 1\%$  of measured value
  - 9. Response Time <60 seconds for 90% step change
  - 10. Sample time 3 seconds.
  - 11. Memory Digital CMOS

# 2.4 ELECTRONIC ACTUATORS AND VALVES

A. Quality Assurance for Actuators and Valves

# DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 1. UL Listed Standard 873 and C.S.A. Class 4813 02 certified.
- 2. NEMA 2 rated enclosures for inside mounting, provide with weather shield for outside mounting.
- 3. Five-year manufacturer's warranty. Two-year unconditional and three-year product defect from date of installation.
- 4. All valves and actuators shall be manufactured by Belimo USA.
- B. Execution Details for Actuators and Valves
  - 1. Furnish a Freeze-stat and install "Hard Wire" interlock to disconnect the mechanical spring return actuator power circuit for fail-safe operation. Use of the control signal to drive the actuators closed is not acceptable.
  - 2. VAV damper actuators and valves are tri-state, utilizing a true PI algorithm from the controller. 4-20 ma or 1-10VDC are not acceptable.
  - 3. Primary valve control shall be analog (2–10 VDC, 4–20 mA).
- C. Actuators for damper and control valves 0.5–6 inches shall be electric unless otherwise specified, provide actuators as follows:
  - 1. UL Listed Standard 873 and Canadian Standards Association Class 481302 shall certify actuators.
  - 2. NEMA 2 rated actuator enclosures for inside mounting. Use additional weather shield to protect actuator when mounted outside.
  - 3. Five-year manufacturer's warranty. Two-year unconditional and three-year product defect from date of installation.
  - 4. Mechanical spring shall be provided when specified. Capacitors or other non-mechanical forms of fail-safe are not acceptable.
  - 5. Position indicator device shall be installed and made visible to the exposed side of the actuator. For damper short shaft mounting, a separate indicator shall be provided to the exposed side of the actuator.
  - 6. Overload Protection: Actuators shall provide protection against actuator burnout by using an internal current limiting circuit or digital motor rotation sensing circuit. Circuit shall insure that actuators cannot burn out due to stalled damper or mechanical and electrical paralleling. End switches to deactivate the actuator at the end of rotation are acceptable only for butterfly valve actuators.
  - 7. A pushbutton gearbox release shall be provided for all non-spring actuators.
  - 8. Modulating actuators shall be 24 VAC and consume 10 VA power or less.
  - 9. Conduit connectors are required when specified and when code requires it.
- D. Damper Actuators
  - 1. Outside air and exhaust air damper actuators shall be mechanical spring return. Capacitors or other non-mechanical forms of fail-safe are not acceptable. The actuator mounting arrangement and spring return feature shall permit normally open or normally closed positions of the damper as required.
  - 2. AHU economizer actuators shall utilize analog control 4-20 ma or 2–10 VDC; floating control is not acceptable.

- 3. Electric damper actuators (including VAV box actuators) shall be direct shaft-mounted and use a V-bolt and toothed V-clamp causing a cold weld effect for positive gripping. Single bolt or set-screw type fasteners are not acceptable.
- 4. One (1) electronic actuator shall be direct shaft-mounted per damper section. No connecting rods or jackshafts shall be needed. Small outside air and return air economizer dampers may be mechanically linked together if one (1) actuator has sufficient torque to drive both and damper drive shafts are both horizontal installed.
- 5. Multi-section dampers with electric actuators shall be arranged so that each damper section operates individually. One (1) electronic actuator shall be direct shaft-mounted per damper section. (See below execution section for more installation details.)
- E. Valve Actuators 0.5–6 inches
  - 1. Modulating valves and actuators on air handlers shall be 4-20 ma or 0-10VDC. Mechanical spring shall be provided on all actuators for pre-heat coil and actuators for AHU heating or cooling coil when units are mounted outside. See plans for fail-safe flow function: Normal Open or Normal Closed. Capacitors or other non-mechanical forms of fail-safe are not acceptable.
  - 2. All zone service actuators shall be non-spring return unless otherwise specified.
  - 3. The valve actuator shall be capable of providing the minimum torque required for proper valve close-off for the required application.
  - 4. All control valves actuators shall have an attached 3-foot cable for easy installation to a junction box.
  - 5. Override handle and gearbox release shall be provided for all non-spring return valve actuators.
- F. Control Dampers
  - 1. The sheet metal contractor shall furnish and size all automatic control dampers unless provided with packaged equipment. The sheet metal contractor shall install all dampers unless provided with packaged equipment.
  - 2. All dampers used for modulating service shall be opposed blade type and arranged for normally open or normally closed operation as required. The damper is to be sized so that, when wide open, the pressure drop is a sufficient amount of its close-off pressure drop for effective throttling.
  - 3. All dampers used for two-position or open-close control shall be parallel blade type arranged for normally open or closed operation as required.
  - 4. Damper linkage hardware shall be constructed of aluminum or corrosion-resistant zinc and nickel-plated steel and furnished as follows:
    - a. Bearing support bracket and drive blade pin extension shall be provided for each damper section. Sheet metal contractor shall install bearing support bracket and drive blade pin extension. Sheet metal contractor shall provide permanent indication of blade position by scratching or marking the visible end of the drive blade pin extension.

- b. Drive pin may be round only if V-bolt and toothed V-clamp is used to cause a cold weld effect for positive gripping. For single bolt or set-screw type actuator fasteners, round damper pin shafts must be milled with at least one side flat to avoid slippage.
- 5. Damper manufacturer shall supply alignment plates for all multi-section dampers.
- G. Control Valves 0.5–6 inches
  - 1. The BAS contractor shall furnish all specified motorized control valves and actuators. BAS contractor shall furnish all control wiring to actuators. The plumbing contractor shall install all valves. Equal percentage control characteristic shall be provided for all water coil control valves. Linear valve characteristic is acceptable for 3-way valves that are 2.5 inches and above.
  - 2. Characterized control valves shall be used for hydronic heating or cooling applications and small to medium AHU water-coil applications to 100GPM. Actuators are non-spring return for terminal unit coil control unless otherwise noted. If the coil is exposed to the outside air stream, see plans for spring return requirement.
    - a. Leakage is 0% (zero percent), close-off is 200psi, maximum differential is 30psi; rangeability is 500:1.
    - b. Valves 0.5–2 inches shall be nickel-plated forged brass body, NPT screw type connections.
    - c. Valves 0.5–1.25 inches shall be rated for ANSI Class 600 working pressure. Valves 1.5 and 2 inches shall be rated for ANSI Class 400 working pressure.
    - d. The operating temperature range shall be 0–250 degrees F.
    - e. Stainless steel ball and stem shall be furnished on all modulating valves.
    - f. Seats shall be fiberglass reinforced Teflon.
    - g. Two-way and three-way valves shall have an equal percentage control port. Full stem rotation is required for maximum flow to insure stable BTU control of the coil.
    - h. Three-way valve shall be applicable for both mixing and diverting.
    - i. The characterizing disc is made of TEFZEL and shall be keyed and held secure by a retaining ring.
    - j. The valves shall have a blow-out proof stem design.
    - k. The stem packing shall consist of two (2) lubricated O-rings designed for on-off or modulating service and require no maintenance.
    - 1. The valves shall have an ISO type, 4-bolt flange for mounting actuator in any orientation parallel or perpendicular to the pipe.
    - m. A non-metallic thermal isolation adapter shall separate valve flange from actuator.
    - n. One (1) fastening screw shall secure the direct coupling of the thermal isolation adapter between the actuator and the valve. This will prevent all lateral or rotational forces from affecting the stem and its packing O-rings.
  - 3. Globe valves 0.5–2 inches shall be used for steam control or water flow applications.
    - a. Valves shall be bronze body, NPT screw type, and shall be rated for ANSI Class 250 working pressure.

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- b. Valves 0.5 inches (DN15) through 2 inches (DN50) with spring return actuators shall close off against 50 psi pressure differential with Class III leakage (0.1%).
- c. The operating temperature range shall be 20–280 degrees F.
- d. Spring loaded TFE packing shall protect against leakage at the stem.
- e. Two-way valves shall have an equal percentage control port.
- f. Three-way valves shall have a linear control and bypass port.
- g. Mixing and diverting valves must be installed specific to the valve design.
- 4. Globe Valves 2.5–6 inches
  - a. Valves 2.5 inches (DN65) through 6 inches (DN50) shall be iron body, 125 lb. flanged with Class III (0.1%) close-off leakage at 50 psi differential.
  - b. Valves with spring return actuators shall close off against 50 psi pressure differential with Class III leakage (0.1%).
  - c. Flow type for two-way valves shall be equal percentage. Flow type for three-way valves shall be linear.
  - d. Mixing and diverting valves must be installed specific to the valve design.
- H. Butterfly valves
  - 1. Butterfly valves shall be sized for modulating service at 60–70 degree stem rotation. Isolation valves shall be line-size. Design velocity shall be less than 12 feet per second when used with standard EPDM seats.
    - a. Body is cast iron.
    - b. Disc is aluminum bronze standard.
    - c. Seat is EPDM standard.
    - d. Body Pressure is 200 psi, -30–275 degrees F.
    - e. Flange is ANSI 125/250.
    - f. Media Temperature Range is -22–240 degree F.
    - g. Maximum Differential Pressure is 200 psi for 2- to 6- inch size.
- I. Butterfly Valve Industrial Actuators
  - 1. Actuators shall be approved under Canadian Standards Association or other Nationally Recognized Testing Laboratory to UL standards. CSA Class 4813 02 or equal. Enclosure shall be NEMA 4 (weatherproof) enclosure and will have an industrial quality coating.
    - a. Actuator shall have a motor rated for continuous duty. The motor shall be fractional horsepower; permanent split capacitor type designed to operate on a 120 VAC, 1pH, 60 Hz supply. Two (2) adjustable cam-actuated end travel limit switches shall be provided to control direction of travel. A self-resetting thermal switch shall be imbedded in the motor for overload protection.
    - b. Reduction gearing shall be designed to withstand the actual motor stall torque. Gears shall be hardened alloy steel, permanently lubricated. A self-locking gear assembly or a brake shall be supplied.
    - c. Actuator shall have a 6-foot wiring harness provided for ease in field wiring (above 1500 in-lbs). Two (2) adjustable SPDT cam-actuated auxiliary switches, rated at 250 VAC shall be provided for indication of open and closed position.

DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

Actuator shall have heater and thermostat to minimize condensation within the actuator housing.

- d. Actuator shall be equipped with a hand wheel for manual override to permit operation of the valve in the event of electrical power failure or system malfunction. Hand wheel must be permanently attached to the actuator and when in manual operation electrical power to the actuator will be permanently interrupted. The hand wheel will not rotate while the actuator is electrically driven.
- e. The actuator shall be analog, floating, or two position as called out in the control sequence of operation. All Analog valves shall be positive positioning, and respond to a 2–10 VDC, 4-20 mA, or adjustable signal as required. Analog actuators shall have a digital control card allowing any voltage input for control and any DC voltage feedback signal for position indication.
- 2. Performance Verification Test
  - a. Control loops shall cause productive actuation with each movement of the actuator and actuators shall modulate at a rate that is stable and responsive. Actuator movement shall not occur before the effects of previous movement have affected the sensor.
  - b. Actuator shall have capability of signaling a trouble alarm when the actuator Stop-Go Ratio exceeds 30%.
- 3. Actuator mounting for damper and valve arrangements shall comply with the following:
  - a. Damper actuators: Shall not be installed in the air stream.
  - b. A weather shield shall be used if actuators are located outside. For damper actuators, use clear plastic enclosure.
  - b. Damper or valve actuator ambient temperature shall not exceed 122 degrees F through any combination of medium temperature or surrounding air. Appropriate air gaps, thermal isolation washers or spacers, standoff legs, or insulation shall be provided as necessary.
  - c. Actuator cords or conduit shall incorporate a drip leg if condensation is possible. Water shall not be allowed to contact actuator or internal parts. Location of conduits in temperatures dropping below dew point shall be avoided to prevent water from condensing in conduit and running into actuator.
- 4. Valve Sizing for Water Coil
  - a. On/Off control valves shall be line-size.
  - b. Modulating control valve body size may be reduced, at most, two (2) pipe sizes from the line size or not less than half the pipe size. The BAS contractor shall size all water coil control valves for the application as follows:
    - 1) Modulating control valves shall be sized for maximum of 5 psig pressure drop at full open position.
    - 2) Butterfly valves shall be sized for modulating service at 60–70 degree rotation. Design velocity shall be 12 feet per second or less when used with standard EPDM seats.

- c. Valve mounting arrangements shall comply with the following:
  - 1) Unions shall be provided on all ports of two-way and three-way valves.
  - 2) Install three-way equal percentage characterized control valves in a mixing configuration with the "A" port piped to the coil.
  - 3) Install 2.5 inches and above, three-way globe valves, as manufactured for mixing or diverting service to the coil.

#### 2.5 ENCLOSURES

- A. All controllers, power supplies and relays shall be mounted in enclosures.
- B. Enclosures may be NEMA 1 when located in a clean, dry, indoor environment. Indoor enclosures shall be NEMA 12 when installed in other than a clean environment.
- C. Enclosures shall have hinged, locking doors.
- D. Provide laminated plastic nameplates for all enclosures in any mechanical room or electrical room. Include location and unit served on nameplate. Laminated plastic shall be 0.125 inches thick and appropriately sized to make label easy to read.

#### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Prior to starting work, carefully inspect installed work of other trades and verify that such work is complete to the point where work of this section may properly commence.
- B. Notify the owner's representative in writing of conditions detrimental to the proper and timely completion of the work.
- C. Do not begin work until all unsatisfactory conditions are resolved.

#### 3.2 INSTALLATION (GENERAL)

- A. Install in accordance with manufacturer's instructions.
- B. Provide all miscellaneous devices, hardware, software, interconnections, installation, and programming required to ensure a complete operating system in accordance with the sequences of operation and point schedules.

### 3.3 LOCATION AND INSTALLATION OF COMPONENTS

- A. Locate and install components for easy accessibility; in general, mount 48 inches above floor with minimum three (3) feet of clear access space in front of units. Obtain approval on locations from owner's representative prior to installation.
- B. All instruments, switches, transmitters, etc., shall be suitably wired and mounted to protect them from vibration, moisture, and high or low temperatures.
- C. Identify all equipment and panels. Provide permanently mounted tags for all panels.
- D. Provide stainless steel or brass thermowells suitable for respective application and for installation under other sections, and sized to suit pipe diameter without restricting flow.

#### 3.4 INTERLOCKING AND CONTROL WIRING

- A. Provide all interlock and control wiring. All wiring shall be installed neatly and professionally, in accordance with Specification Division 16 and all national, state and local electrical codes.
- B. Provide wiring as required by functions as specified and as recommended by equipment manufacturers, to serve specified control functions. Provide shielded low capacitance wire for all communications trunks.
- C. Control wiring shall not be installed in power circuit raceways. Magnetic starters and disconnect switches shall not be used as junction boxes. Provide auxiliary junction boxes as required. Coordinate location and arrangement of all control equipment with the owner's representative prior to rough-in.
- D. Provide auxiliary pilot duty relays on motor starters as required for control function.
- E. Provide power for all control components from nearest electrical control panel or as indicated on the electrical drawings; coordinate with electrical contractor.
- F. All control wiring in the mechanical, electrical, telephone and boiler rooms to be installed in raceways. All other wiring to be installed neatly and inconspicuously per local code requirements. If local code allows, control wiring above accessible ceiling spaces may be run with plenum-rated cable (without conduit).

#### 3.5 DDC OBJECT TYPE SUMMARY

- A. Provide all database generation.
- B. Displays
  - 1. System displays shall show all analog and binary object types within the system. They shall be logically laid out for easy use by the owner. Provide outside air temperature indication on all system displays associated with economizer cycles.

# DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

# C. Run Time Totalization

- 1. At a minimum, run time totalization shall be incorporated for each monitored supply fan, return fan, exhaust fan, hot water and chilled water pumps. Warning limits for each point shall be entered for alarm and or maintenance purposes.
- D. Trendlog
  - 1. All binary and analog object types (including zones) shall have the capability to be automatically trended.
- E. Alarm
  - 1. All analog inputs (High/Low Limits) and selected binary input alarm points shall be prioritized and routed (locally or remotely) with alarm message per owner's requirements.
- F. Database Save
  - 1. Provide backup database for all standalone application controllers on disk.

### 3.6 FIELD SERVICES

- A. Prepare and start logic control system under provisions of this section.
- B. Start up and commission systems. Allow sufficient time for startup and commissioning prior to placing control systems in permanent operation.
- C. Provide the capability for off-site monitoring at control contractor's local or main office. At a minimum, off-site facility shall be capable of system diagnostics and software download. Owner shall provide phone line for this service for one (1) year or as specified.
- D. Provide owner's representative with spare parts list. Identify equipment critical to maintaining the integrity of the operating system.
- E. Commissioning: Provide a DDC technician for 50 hours who is fully trained in programming DDC systems. The technician shall also be trained in operating the installed Building Automation System. The technician shall have previous experience working with a commissioning authority to operate the BAS during testing.

# 3.7 AS-BUILT DOCUMENTATION REQUIRED

- A. Provide complete documentation in hardcopy (3 sets) and electronic format (searchable pdf.)
- B. Provide controls system floor plans showing the following
  - 1. All rooms with numbers and names for the entire building.

#### DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

- 2. Locations of all controlled equipment with symbol identifier based on the mechanical engineering drawings.
- 3. Installed location of all control devices with device instance name and number.
- 4. Tables of point to point check out of all installed devices including but not limited to the following.
  - a. LOCATION
  - b. DRAWING
  - c. DEVICE DESCRIPTION
  - d. POINT DESCRIPTION
  - e. MAC/EXP ADDRESS
  - f. DEVICE INSTANCE
  - g. POINT TYPE
  - h. POINT #
  - i. SIGNAL TYPE
  - j. UNITS MEASURED, SENSED OR CONTROLLED
  - k. CONTROL PANEL
- 5. Floor Plans showing wiring diagrams of all interconnecting device wiring including:
  - a. Wire runs located on floor plans
  - b. Wire furn type and gauge
  - c. All equipment being controlled
  - d. Provide wiring diagram for each control panel and device placed in the enclosure the diagram describes.
- 6. Cut sheets for all devices.
- 7. Finalized Sequence of Control.
- 8. Operations and Maintenance data for all devices.
- 9. Points list.

# 3.8 TRAINING

- A. Provide initial walk through of project for familiarization of building, systems, and controls with BSD facilities personnel.
- B. Remaining training will be quoted as an allowance of 8 hours to be utilized by the District "as needed" for overall training.

# 3.9 DEMONSTRATION

- A. Demonstrate complete operating system to owner's representative.
- B. Provide certificate stating that control system has been tested and adjusted for proper operation.

### PART 4 - SEQUENCE OF OPERATIONS FOR HVAC CONTROLS

#### 4.1 GENERAL

- A. Provide a complete and operational temperature control and building automation system based on the following points and sequence of operation. The system shall be complete and will meet all sequences of control and standard control practices. The determined point list is the minimum amount of points that are to be provided. If additional points are required to meet the sequence of operation, they will be provided at no extra charge to the owner.
- B. BACnet Object List
  - 1. The following points as defined for each piece of equipment are designated as follows:
    - a. Binary Out (BO): Defined as any two-state output (start/stop) (enable/disable), etc.
    - b. Binary In (BI): Defined as any two-state input (alarm, status), etc.
    - c. Analog In (AI): Defined as any variable input (temperature) (position), etc.
    - d. Analog Out (AO): Defined as any electrical variable output. 0–20mA, 4–20mA and 0–10VDC are the only acceptable analog outputs. The driver for analog outputs must come from both hardware and software resident in the controllers. Transducers will not be acceptable under any circumstance.
    - e. Analog Value (AV):
- C. Sequence of control and controls diagrams
  - 1. The control diagram, points list, and sequences are included on the design drawings and are listed in association with the control diagram. The control diagram, points list, and sequence of operation depict the general nature of the system control and do not indicate every device, function, mode or step in the unit operation. It is the controls contractor's responsibility working with other contractors and equipment supplier to install and program the systems and equipment to at minimum meet the sequences of control.

END OF SECTION 230923

# SECTION 231123 - FACILITY NATURAL-GAS PIPING

# PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Pipes, tubes, and fittings.
  - 2. Piping specialties.
  - 3. Piping and tubing joining materials.
  - 4. Manual gas shutoff valves.
  - 5. Motorized gas valves.
  - 6. Earthquake valves.
  - 7. Pressure regulators.
  - 8. Dielectric fittings.
  - 9. Gas Service Fittings

#### 1.3 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawlspaces, and tunnels.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of the following:
  - 1. Piping specialties.
  - 2. Valves. Include pressure rating, capacity, settings, and electrical connection data of selected models.
  - 3. Pressure regulators. Indicate pressure ratings and capacities.
  - 4. Dielectric fittings.

# FACILITY NATURAL-GAS PIPING

- B. Shop Drawings: For facility natural-gas piping layout. Include plans, piping layout and elevations, sections, and details for fabrication of pipe anchors, hangers, supports for multiple pipes, alignment guides, expansion joints and loops, and attachments of the same to building structure. Detail location of anchors, alignment guides, and expansion joints and loops.
  - 1. Shop Drawing Scale: 1/4 inch per foot.
  - 2. Detail mounting, supports, and valve arrangements for pressure regulator assembly.
- C. Delegated-Design Submittal: For natural-gas piping and equipment indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
  - 1. Detail fabrication and assembly of seismic restraints.
  - 2. Design Calculations: Calculate requirements for selecting seismic restraints.

# 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Plans and details, drawn to scale, on which natural-gas piping is shown and coordinated with other installations, using input from installers of the items involved.
- B. Site Survey: Plans, drawn to scale, on which natural-gas piping is shown and coordinated with other services and utilities.
- C. Qualification Data: For qualified professional engineer.
- D. Welding certificates.
- E. Field quality-control reports.

#### 1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For motorized gas valves and pressure regulators to include in emergency, operation, and maintenance manuals.

#### 1.7 QUALITY ASSURANCE

- A. Steel Support Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."
- B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

### 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Handling Flammable Liquids: Remove and dispose of liquids from existing natural-gas piping according to requirements of authorities having jurisdiction.
- B. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.
- C. Store and handle pipes and tubes having factory-applied protective coatings to avoid damaging coating, and protect from direct sunlight.
- D. Protect stored PE pipes and valves from direct sunlight.

#### 1.9 PROJECT CONDITIONS

- A. Perform site survey, research public utility records, and verify existing utility locations. Contact utility-locating service for area where Project is located.
- B. Interruption of Existing Natural-Gas Service: Do not interrupt natural-gas service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide purging and startup of natural-gas supply according to requirements indicated:
  - 1. Notify Architect and Owner no fewer than two days in advance of proposed interruption of natural-gas service.
  - 2. Do not proceed with interruption of natural-gas service without Owner's written permission.

#### 1.10 COORDINATION

A. Coordinate sizes and locations of concrete bases with actual equipment provided.

# PART 2 - PRODUCTS

#### 2.1 PERFORMANCE REQUIREMENTS

- A. Minimum Operating-Pressure Ratings:
  - 1. Piping and Valves: 100 psig minimum unless otherwise indicated.
  - 2. Service Regulators: 65 psig minimum unless otherwise indicated.
- A. Natural-Gas System Pressure within Buildings: More than 0.5 psig but not more than 2 psig.

# FACILITY NATURAL-GAS PIPING

B. Delegated Design: Design restraints and anchors for natural-gas piping and equipment, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

# 2.2 PIPES, TUBES, AND FITTINGS

- A. Steel Pipe: ASTM A 53/A 53M, black steel, Schedule 40, Type E or S, Grade B.
  - 1. Malleable-Iron Threaded Fittings: ASME B16.3, Class 150, standard pattern.
  - 2. Wrought-Steel Welding Fittings: ASTM A 234/A 234M for butt welding and socket welding.
  - 3. Unions: ASME B16.39, Class 150, malleable iron with brass-to-iron seat, ground joint, and threaded ends.
  - 4. Forged-Steel Flanges and Flanged Fittings: ASME B16.5, minimum Class 150, including bolts, nuts, and gaskets of the following material group, end connections, and facings:
    - a. Material Group: 1.1.
    - b. End Connections: Threaded or butt welding to match pipe.
    - c. Lapped Face: Not permitted underground.
    - d. Gasket Materials: ASME B16.20, metallic, flat, asbestos free, aluminum o-rings, and spiral-wound metal gaskets.
    - e. Bolts and Nuts: ASME B18.2.1, carbon steel aboveground and stainless steel underground.
  - 5. Protective Coating for Underground Piping: Factory-applied, three-layer coating of epoxy, adhesive, and PE.
    - a. Joint Cover Kits: Epoxy paint, adhesive, and heat-shrink PE sleeves.
  - 6. Mechanical Couplings:
    - a. Steel flanges and tube with epoxy finish.
    - b. Buna-nitrile seals.
    - c. Steel bolts, washers and nuts.
    - d. Coupling shall be capable of joining PE pipe to PE pipe, steel pipe to PE pipe, or steel pipe to steel pipe.
    - e. Steel body couplings installed underground on plastic pipe shall be factory equipped with anode.

# 2.3 PIPING SPECIALTIES

- A. Appliance Flexible Connectors:
  - 1. Indoor, Fixed-Appliance Flexible Connectors: Comply with ANSI Z21.24.
  - 2. Indoor, Movable-Appliance Flexible Connectors: Comply with ANSI Z21.69.
  - 3. Outdoor, Appliance Flexible Connectors: Comply with ANSI Z21.75.
  - 4. Corrugated stainless-steel tubing with polymer coating.
  - 5. Operating-Pressure Rating: 0.5 psig.

#### FACILITY NATURAL-GAS PIPING
- 6. End Fittings: Zinc-coated steel.
- 7. Threaded Ends: Comply with ASME B1.20.1.
- 8. Maximum Length: 72 inches
- B. Y-Pattern Strainers:
  - 1. Body: ASTM A 126, Class B, cast iron with bolted cover and bottom drain connection.
  - 2. End Connections: Threaded ends for NPS 2 and smaller; flanged ends for NPS 2-1/2 and larger.
  - 3. Strainer Screen: 40-mesh startup strainer, and perforated stainless-steel basket with 50 percent free area.
  - 4. CWP Rating: 125 psig.
- C. Weatherproof Vent Cap: Cast- or malleable-iron increaser fitting with corrosion-resistant wire screen, with free area at least equal to cross-sectional area of connecting pipe and threaded-end connection.

# 2.4 JOINING MATERIALS

- A. Joint Compound and Tape: Suitable for natural gas.
- B. Welding Filler Metals: Comply with AWS D10.12/D10.12M for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

# 2.5 MANUAL GAS SHUTOFF VALVES

- A. See "Aboveground Manual Gas Shutoff Valve Schedule" Articles for where each valve type is applied in various services.
- B. General Requirements for Metallic Valves, NPS 2 and Smaller: Comply with ASME B16.33.
  - 1. CWP Rating: 125 psig.
  - 2. Threaded Ends: Comply with ASME B1.20.1.
  - 3. Dryseal Threads on Flare Ends: Comply with ASME B1.20.3.
  - 4. Tamperproof Feature: Locking feature for valves indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
  - 5. Listing: Listed and labeled by an NRTL acceptable to authorities having jurisdiction for valves 1 inch and smaller.
  - 6. Service Mark: Valves 1-1/4 inches to NPS 2 shall have initials "WOG" permanently marked on valve body.
- C. General Requirements for Metallic Valves, NPS 2-1/2 and Larger: Comply with ASME B16.38.
  - 1. CWP Rating: 125 psig.
  - 2. Flanged Ends: Comply with ASME B16.5 for steel flanges.

- 3. Tamperproof Feature: Locking feature for valves indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
- 4. Service Mark: Initials "WOG" shall be permanently marked on valve body.
- D. Two-Piece, Full-Port, Bronze Ball Valves with Stainless Steel Trim: MSS SP-110.
  - 1. Body: Bronze, complying with ASTM B 584.
  - 2. Ball: Chrome-plated bronze.
  - 3. Stem: Bronze; blowout proof.
  - 4. Seats: Reinforced TFE; blowout proof.
  - 5. Springs and Valve Trim: Stainless Steel.
  - 6. Packing: Threaded-body packnut design with adjustable-stem packing.
  - 7. Ends: Threaded, flared, or socket as indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
  - 8. CWP Rating: 600 psig.
  - 9. Listing: Valves NPS 1 and smaller shall be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
  - 10. Service: Suitable for natural-gas service with "WOG" indicated on valve body.
  - 11. Service: Suitable for natural-gas service with "WOG" indicated on valve body.
- E. Bronze Plug Valves: MSS SP-78.
  - 1. Body: Bronze, complying with ASTM B 584.
  - 2. Plug: Bronze.
  - 3. Ends: Threaded, socket, or flanged as indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
  - 4. Operator: Square head or lug type with tamperproof feature where indicated.
  - 5. Pressure Class: 125 psig.
  - 6. Listing: Valves NPS 1 and smaller shall be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
  - 7. Service: Suitable for natural-gas service with "WOG" indicated on valve body.
- F. Valve Boxes:
  - 1. Cast-iron, two-section box.
  - 2. Top section with cover with "GAS" lettering.
  - 3. Bottom section with base to fit over valve and barrel a minimum of 5 inches in diameter.
  - 4. Adjustable cast-iron extensions of length required for depth of bury.
  - 5. Include tee-handle, steel operating wrench with socket end fitting valve nut or flat head, and with stem of length required to operate valve.

# 2.6 MOTORIZED GAS VALVES

- A. Automatic Gas Valves: Comply with ANSI Z21.21.
  - 1. Body: Brass or aluminum.
  - 2. Seats and Disc: Nitrile rubber.

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 3. Springs and Valve Trim: Stainless steel.
- 4. Normally closed.
- 5. Visual position indicator.
- 6. Mechanical operator for actuation by appliance automatic shutoff device.
- B. Electrically Operated Valves: Comply with UL 429.
  - 1. Pilot operated.
  - 2. Body: Brass or aluminum.
  - 3. Seats and Disc: Nitrile rubber.
  - 4. Springs and Valve Trim: Stainless steel.
  - 5. 120-V ac, 60 Hz, Class B, continuous-duty molded coil, and replaceable.
  - 6. NEMA ICS 6, Type 4, coil enclosure.
  - 7. Normally closed.
  - 8. Visual position indicator.

## 2.7 PRESSURE REGULATORS

- A. General Requirements:
  - 1. Single stage and suitable for natural gas.
  - 2. Steel jacket and corrosion-resistant components.
  - 3. Elevation compensator.
  - 4. End Connections: Threaded for regulators NPS 2 and smaller; flanged for regulators NPS 2-1/2 and larger.
- B. Service Pressure Regulators: Comply with ANSI Z21.80.
  - 1. Body and Diaphragm Case: Cast iron or die-cast aluminum.
  - 2. Springs: Zinc-plated steel; interchangeable.
  - 3. Diaphragm Plate: Zinc-plated steel.
  - 4. Seat Disc: Nitrile rubber resistant to gas impurities, abrasion, and deformation at the valve port.
  - 5. Orifice: Aluminum; interchangeable.
  - 6. Seal Plug: Ultraviolet-stabilized, mineral-filled nylon.
  - 7. Single-port, self-contained regulator with orifice no larger than required at maximum pressure inlet, and no pressure sensing piping external to the regulator.
  - 8. Pressure regulator shall maintain discharge pressure setting downstream, and not exceed 150 percent of design discharge pressure at shutoff.
  - 9. Overpressure Protection Device: Factory mounted on pressure regulator.
  - 10. Atmospheric Vent: Factory- or field-installed, stainless-steel screen in opening if not connected to vent piping.
  - 11. Maximum Inlet Pressure: 100 psig.
- C. Line Pressure Regulators: Comply with ANSI Z21.80.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. American Meter Company.
- b. Invensys.
- c. Maxitrol Company.
- 2. Body and Diaphragm Case: Cast iron or die-cast aluminum.
- 3. Springs: Zinc-plated steel; interchangeable.
- 4. Diaphragm Plate: Zinc-plated steel.
- 5. Seat Disc: Nitrile rubber resistant to gas impurities, abrasion, and deformation at the valve port.
- 6. Orifice: Aluminum; interchangeable.
- 7. Seal Plug: Ultraviolet-stabilized, mineral-filled nylon.
- 8. Single-port, self-contained regulator with orifice no larger than required at maximum pressure inlet, and no pressure sensing piping external to the regulator.
- 9. Pressure regulator shall maintain discharge pressure setting downstream, and not exceed 150 percent of design discharge pressure at shutoff.
- 10. Overpressure Protection Device: Factory mounted on pressure regulator.
- 11. Atmospheric Vent: Factory- or field-installed, stainless-steel screen in opening if not connected to vent piping.
- 12. Maximum Inlet Pressure: 2 psig.
- D. Appliance Pressure Regulators: Comply with ANSI Z21.18.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limite4d to the following:
    - a. Eaton.
    - b. Harper Wyman Co.
    - c. Maxitrol Company.
  - 2. Body and Diaphragm Case: Die-cast aluminum.
  - 3. Springs: Zinc-plated steel; interchangeable.
  - 4. Diaphragm Plate: Zinc-plated steel.
  - 5. Seat Disc: Nitrile rubber.
  - 6. Seal Plug: Ultraviolet-stabilized, mineral-filled nylon.
  - 7. Factory-Applied Finish: Minimum three-layer polyester and polyurethane paint finish.
  - 8. Regulator may include vent limiting device, instead of vent connection, if approved by authorities having jurisdiction.
  - 9. Maximum Inlet Pressure: 2 psig.

### 2.8 DIELECTRIC FITTINGS

- A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.
- B. Dielectric Unions:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - a. Capitol Manufacturing Company.
  - b. Central Plastics Company.
  - c. WATTS.
- 2. Description:
  - a. Standard: ASSE 1079.
  - b. Pressure Rating: 125 psig minimum at 180 deg F.
  - c. End Connections: Solder-joint copper alloy and threaded ferrous.
- C. Dielectric Flanges:
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Capitol Manufacturing Company.
    - b. Central Plastics Company.
    - c. WATTS.
  - 2. Description:
    - a. Standard: ASSE 1079.
    - b. Factory-fabricated, bolted, companion-flange assembly.
    - c. Pressure Rating: 125 psig minimum at 180 deg F.
    - d. End Connections: Solder-joint copper alloy and threaded ferrous; threaded solderjoint copper alloy and threaded ferrous.

# 2.9 LABELING AND IDENTIFYING

A. Detectable Warning Tape: Acid- and alkali-resistant, PE film warning tape manufactured for marking and identifying underground utilities, a minimum of 6 inches wide and 4 mils thick, continuously inscribed with a description of utility, with metallic core encased in a protective jacket for corrosion protection, detectable by metal detector when tape is buried up to 30 inches deep; colored yellow.

# PART 3 - EXECUTION

# 3.1 EXAMINATION

A. Examine roughing-in for natural-gas piping system to verify actual locations of piping connections before equipment installation.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 PREPARATION

- A. Close equipment shutoff valves before turning off natural gas to premises or piping section.
- B. Inspect natural-gas piping according to International Fuel Gas Code to determine that naturalgas utilization devices are turned off in piping section affected.
- C. Comply with International Fuel Gas Code requirements for prevention of accidental ignition.

# 3.3 OUTDOOR PIPING INSTALLATION

- A. Comply with the International Fuel Gas Code for installation and purging of natural-gas piping.
- B. Steel Piping with Protective Coating:
  - 1. Apply joint cover kits to pipe after joining to cover, seal, and protect joints.
  - 2. Repair damage to PE coating on pipe as recommended in writing by protective coating manufacturer.
  - 3. Replace pipe having damaged PE coating with new pipe.

# 3.4 INDOOR PIPING INSTALLATION

- A. Comply with the International Fuel Gas Code for installation and purging of natural-gas piping.
- B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- C. Arrange for pipe spaces, chases, slots, sleeves, and openings in building structure during progress of construction, to allow for mechanical installations.
- D. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- E. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- F. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- G. Locate valves for easy access.
- H. Install natural-gas piping at uniform grade of 2 percent down toward drip and sediment traps.

- I. Install piping free of sags and bends.
- J. Install fittings for changes in direction and branch connections.
- K. Verify final equipment locations for roughing-in.
- L. Comply with requirements in Sections specifying gas-fired appliances and equipment for roughing-in requirements.
- M. Drips and Sediment Traps: Install drips at points where condensate may collect, including service-meter outlets. Locate where accessible to permit cleaning and emptying. Do not install where condensate is subject to freezing.
  - 1. Construct drips and sediment traps using tee fitting with bottom outlet plugged or capped. Use nipple a minimum length of 3 pipe diameters, but not less than 3 inches long and same size as connected pipe. Install with space below bottom of drip to remove plug or cap.
- N. Extend relief vent connections for service regulators, line regulators, and overpressure protection devices to outdoors and terminate with weatherproof vent cap.
- O. Conceal pipe installations in walls, pipe spaces, utility spaces, above ceilings, below grade or floors, and in floor channels unless indicated to be exposed to view.
- P. Concealed Location Installations: Except as specified below, install concealed natural-gas piping and piping installed under the building in containment conduit constructed of steel pipe with welded joints as described in Part 2. Install a vent pipe from containment conduit to outdoors and terminate with weatherproof vent cap.
  - 1. Above Accessible Ceilings: Natural-gas piping, fittings, valves, and regulators may be installed in accessible spaces without containment conduit.
  - 2. In Floors: Install natural-gas piping with welded or brazed joints and protective coating in cast-in-place concrete floors. Cover piping to be cast in concrete slabs with minimum of 1-1/2 inches of concrete. Piping may not be in physical contact with other metallic structures such as reinforcing rods or electrically neutral conductors. Do not embed piping in concrete slabs containing quick-set additives or cinder aggregate.
  - 3. In Walls or Partitions: Protect tubing installed inside partitions or hollow walls from physical damage using steel striker barriers at rigid supports.
    - a. Exception: Tubing passing through partitions or walls does not require striker barriers.
  - 4. Prohibited Locations:
    - a. Do not install natural-gas piping in or through circulating air ducts, clothes or trash chutes, chimneys or gas vents (flues), ventilating ducts, or dumbwaiter or elevator shafts.
    - b. Do not install natural-gas piping in solid walls or partitions.

- Q. Use eccentric reducer fittings to make reductions in pipe sizes. Install fittings with level side down.
- R. Connect branch piping from top or side of horizontal piping.
- S. Install unions in pipes NPS 2 and smaller, adjacent to each valve, at final connection to each piece of equipment. Unions are not required at flanged connections.
- T. Do not use natural-gas piping as grounding electrode.
- U. Install strainer on inlet of each line-pressure regulator and automatic or electrically operated valve.

# 3.5 VALVE INSTALLATION

- A. Install manual gas shutoff valve for each gas appliance ahead of corrugated stainless-steel tubing, aluminum, or copper connector.
- B. Install regulators and overpressure protection devices with maintenance access space adequate for servicing and testing.

## 3.6 PIPING JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- C. Threaded Joints:
  - 1. Thread pipe with tapered pipe threads complying with ASME B1.20.1.
  - 2. Cut threads full and clean using sharp dies.
  - 3. Ream threaded pipe ends to remove burrs and restore full inside diameter of pipe.
  - 4. Apply appropriate tape or thread compound to external pipe threads unless dryseal threading is specified.
  - 5. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- D. Welded Joints:
  - 1. Construct joints according to AWS D10.12/D10.12M, using qualified processes and welding operators.
  - 2. Bevel plain ends of steel pipe.
  - 3. Patch factory-applied protective coating as recommended by manufacturer at field welds and where damage to coating occurs during construction.

## 3.7 HANGER AND SUPPORT INSTALLATION

- A. Install seismic restraints on piping. Comply with requirements for seismic-restraint devices specified in Section 230548 "Vibration and Seismic Controls for HVAC."
- B. Comply with requirements for pipe hangers and supports specified in Section 230529 "Hangers and Supports for HVAC Piping and Equipment."
- C. Install hangers for horizontal steel piping with the following maximum spacing and minimum rod sizes:
  - 1. NPS 1 and Smaller: Maximum span, 96 inches; minimum rod size, 3/8 inch.
  - 2. NPS 1-1/4: Maximum span, 108 inches; minimum rod size, 3/8 inch.
  - 3. NPS 1-1/2 and NPS 2: Maximum span, 108 inches; minimum rod size, 3/8 inch.
  - 4. NPS 2-1/2 to NPS 3-1/2: Maximum span, 10 feet; minimum rod size, 1/2 inch.
  - 5. NPS 4 and Larger: Maximum span, 10 feet; minimum rod size, 5/8 inch.

## 3.8 CONNECTIONS

- A. Connect to utility's gas main according to utility's procedures and requirements.
- B. Install natural-gas piping electrically continuous, and bonded to gas appliance equipment grounding conductor of the circuit powering the appliance according to NFPA 70.
- C. Install piping adjacent to appliances to allow service and maintenance of appliances.
- D. Connect piping to appliances using manual gas shutoff valves and unions. Install valve within 72 inches of each gas-fired appliance and equipment. Install union between valve and appliances or equipment.
- E. Sediment Traps: Install tee fitting with capped nipple in bottom to form drip, as close as practical to inlet of each appliance.

#### 3.9 LABELING AND IDENTIFYING

- A. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for piping and valve identification.
- B. Install detectable warning tape directly above gas piping, 12 inches below finished grade, except 6 inches below subgrade under pavements and slabs.

# 3.10 PAINTING

A. Comply with requirements in Section 099123 "Interior Painting" for painting interior and exterior natural-gas piping.

- B. Paint exposed, exterior metal piping, valves, service regulators, service meters and meter bars, earthquake valves, and piping specialties, except components, with factory-applied paint or protective coating.
  - 1. Alkyd System: MPI EXT 5.1D.
    - a. Prime Coat: Alkyd anticorrosive metal primer.
    - b. Intermediate Coat: Exterior alkyd enamel matching topcoat.
    - c. Topcoat: Exterior alkyd enamel (semigloss).
    - d. Color: Insert color.
- C. Paint exposed, interior metal piping, valves, service regulators, service meters and meter bars, earthquake valves, and piping specialties, except components, with factory-applied paint or protective coating.
  - 1. Latex Over Alkyd Primer System: MPI INT 5.1Q.
    - a. Prime Coat: Alkyd anticorrosive metal primer.
- D. Damage and Touchup: Repair marred and damaged factory-applied finishes with materials and by procedures to match original factory finish.

# 3.11 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Tests and Inspections:
  - 1. Test, inspect, and purge natural gas according to the International Fuel Gas Code and authorities having jurisdiction.
- C. Natural-gas piping will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.

# 3.12 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain earthquake valves.

# 3.13 OUTDOOR PIPING SCHEDULE

- A. Aboveground natural-gas piping shall be the following:
  - 1. Steel pipe with malleable-iron fittings and threaded joints.
  - 2. Steel pipe with wrought-steel fittings and welded joints.

B. Containment Conduit: Steel pipe with wrought-steel fittings and welded joints. Coat pipe and fittings with protective coating for steel piping.

# 3.14 INDOOR PIPING SCHEDULE FOR SYSTEM PRESSURES LESS THAN 0.5 PSIG

- A. Aboveground, branch piping NPS 1 and smaller shall be the following:
  - 1. Steel pipe with malleable-iron fittings and threaded joints.
- B. Aboveground, distribution piping shall be one of the following:
  - 1. Steel pipe with malleable-iron fittings and threaded joints.
  - 2. Steel pipe with wrought-steel fittings and welded joints.
  - 3. Drawn-temper copper tube with wrought-copper fittings and brazed joints.
- C. Containment Conduit: Steel pipe with wrought-steel fittings and welded joints. Coat pipe and fittings with protective coating for steel piping.
- D. Containment Conduit Vent Piping: Steel pipe with malleable-iron fittings and threaded or wrought-steel fittings with welded joints. Coat underground pipe and fittings with protective coating for steel piping.

# 3.15 INDOOR PIPING SCHEDULE FOR SYSTEM PRESSURES MORE THAN 0.5 PSIG AND LESS THAN 5 PSIG

- A. Aboveground, branch piping NPS 1 and smaller shall be the following:
  - 1. Steel pipe with malleable-iron fittings and threaded joints.
- B. Aboveground, distribution piping shall be the following:
  - 1. Steel pipe with steel welding fittings and welded joints.
- C. Containment Conduit: Steel pipe with wrought-steel fittings and welded joints. Coat underground pipe and fittings with protective coating for steel piping.
- D. Containment Conduit Vent Piping: Steel pipe with malleable-iron fittings and threaded or wrought-steel fittings with welded joints. Coat underground pipe and fittings with protective coating for steel piping.

# 3.16 ABOVEGROUND MANUAL GAS SHUTOFF VALVE SCHEDULE

- A. Valves for pipe sizes NPS 2 and smaller at service meter shall be the following:
  - 1. Two-piece, full-port, bronze ball valves with stainless steel trim.
- B. Valves for pipe sizes NPS 2-1/2 and larger at service meter shall be the following:

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 1. Two-piece, full-port, bronze ball valves with stainless steel trim.
- C. Valves in branch piping for single appliance shall be the following:
  - 1. Two-piece, full-port, bronze ball valves with stainless steel trim.

END OF SECTION 231123

# SECTION 233113 - METAL DUCTS

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Single-wall rectangular ducts and fittings.
  - 2. Single-wall round ducts and fittings.
  - 3. Sheet metal materials.
  - 4. Duct liner.
  - 5. Sealants and gaskets.
  - 6. Hangers and supports.
  - 7. Seismic-restraint devices.
- B. Related Sections:
  - 1. Section 230593 "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing requirements for metal ducts.
  - 2. Section 233300 "Air Duct Accessories" for dampers, sound-control devices, ductmounting access doors and panels, turning vanes, and flexible ducts.

## 1.3 PERFORMANCE REQUIREMENTS

- A. Delegated Duct Design: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible" and performance requirements and design criteria indicated in "Duct Schedule" Article.
- B. Structural Performance: Duct hangers and supports and seismic restraints shall withstand the effects of gravity and seismic loads and stresses within limits and under conditions described in SMACNA's "HVAC Duct Construction Standards Metal and Flexible", ASCE/SEI 7, SMACNA's "Round Industrial Duct Construction Standards."
- C. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

# 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of the following products:
  - 1. Liners and adhesives.
  - 2. Sealants and gaskets.
  - 3. Seismic-restraint devices.
- B. Sustainable Design Submittals:
  - 1. Product Data: For adhesives, indicating VOC content.
  - 2. Laboratory Test Reports: For adhesives, indicating compliance with requirements for low-emitting materials.
- C. Shop Drawings:
  - 1. Fabrication, assembly, and installation, including plans, elevations, sections, components, and attachments to other work.
  - 2. Factory- and shop-fabricated ducts and fittings.
  - 3. Duct layout indicating sizes, configuration, liner material, and static-pressure classes.
  - 4. Elevation of top of ducts.
  - 5. Dimensions of main duct runs from building grid lines.
  - 6. Fittings.
  - 7. Reinforcement and spacing.
  - 8. Seam and joint construction.
  - 9. Penetrations through fire-rated and other partitions.
  - 10. Equipment installation based on equipment being used on Project.
  - 11. Locations for duct accessories, including dampers, turning vanes, and access doors and panels.
  - 12. Hangers and supports, including methods for duct and building attachment, seismic restraints, and vibration isolation.
- D. Delegated-Design Submittal:
  - 1. Sheet metal thicknesses.
  - 2. Joint and seam construction and sealing.
  - 3. Reinforcement details and spacing.
  - 4. Materials, fabrication, assembly, and spacing of hangers and supports.
  - 5. Design Calculations: Calculations, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation for selecting hangers and supports and seismic restraints.

# 1.5 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

- 1. Duct installation in congested spaces, indicating coordination with general construction, building components, and other building services. Indicate proposed changes to duct layout.
- 2. Suspended ceiling components.
- 3. Structural members to which duct will be attached.
- 4. Size and location of initial access modules for acoustical tile.
- 5. Penetrations of smoke barriers and fire-rated construction.
- 6. Items penetrating finished ceiling including the following:
  - a. Luminaires.
  - b. Air outlets and inlets.
  - c. Speakers.
  - d. Sprinklers.
  - e. Access panels.
  - f. Perimeter moldings.
- B. Welding certificates.
- C. Field quality-control reports.

# 1.6 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel," for hangers and supports. AWS D9.1M/D9.1, "Sheet Metal Welding Code," for duct joint and seam welding.
- B. Welding Qualifications: Qualify procedures and personnel according to the following:
  - 1. AWS D1.1/D1.1M, "Structural Welding Code Steel," for hangers and supports.
  - 2. AWS D1.2/D1.2M, "Structural Welding Code Aluminum," for aluminum supports.
  - 3. AWS D9.1M/D9.1, "Sheet Metal Welding Code," for duct joint and seam welding.
- C. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 "Systems and Equipment" and Section 7 "Construction and System Start-up."
- D. ASHRAE/IES Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6.4.4 "HVAC System Construction and Insulation."

# PART 2 - PRODUCTS

# 2.1 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS

A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.

- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, ductsupport intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards -Metal and Flexible."
- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible."
- D. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Chapter 4, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible."

## 2.2 SINGLE-WALL ROUND DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Ductmate Industries, Inc.
    - b. McGill AirFlow LLC.
    - c. SEMCO LLC.
- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible."
- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 3-2, "Round Duct Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible."
- D. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

# 2.3 SHEET METAL MATERIALS

- A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
  - 1. Galvanized Coating Designation: G60.
  - 2. Finishes for Surfaces Exposed to View: Mill phosphatized.
- C. PVC-Coated, Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
  - 1. Galvanized Coating Designation: G60.
  - 2. Minimum Thickness for Factory-Applied PVC Coating: 4 mils thick on sheet metal surface of ducts and fittings exposed to corrosive conditions, and minimum 1 mil thick on opposite surface.
  - 3. Coating Materials: Acceptable to authorities having jurisdiction for use on ducts listed and labeled by an NRTL for compliance with UL 181, Class 1.
- D. Carbon-Steel Sheets: Comply with ASTM A 1008/A 1008M, with oiled, matte finish for exposed ducts.
- E. Stainless-Steel Sheets: Comply with ASTM A 480/A 480M, Type 304 or 316, as indicated in the "Duct Schedule" Article; cold rolled, annealed, sheet. Exposed surface finish shall be No. 2B, No. 2D, No. 3, or No. 4 as indicated in the "Duct Schedule" Article.
- F. Factory- or Shop-Applied Antimicrobial Coating:
  - 1. Apply to the surface of sheet metal that will form the interior surface of the duct. An untreated clear coating shall be applied to the exterior surface.
  - 2. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.
  - 3. Coating containing the antimicrobial compound shall have a hardness of 2H, minimum, when tested according to ASTM D 3363.
  - 4. Surface-Burning Characteristics: Maximum flame-spread index of 25 and maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
  - 5. Shop-Applied Coating Color: White.
  - 6. Antimicrobial coating on sheet metal is not required for duct containing liner treated with antimicrobial coating.
- G. Reinforcement Shapes and Plates: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
  - 1. Where black- and galvanized-steel shapes and plates are used to reinforce aluminum ducts, isolate the different metals with butyl rubber, neoprene, or EPDM gasket materials.
- H. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

#### METAL DUCTS

233113 - 5

## 2.4 DUCT LINER

- A. Fibrous-Glass Duct Liner: Comply with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. CertainTeed Corporation.
    - b. Johns Manville; a Berkshire Hathaway company.
    - c. Knauf Insulation.
  - 2. Thermal Requirements
    - a. Type I, Flexible: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
    - b. Type II, Rigid: 0.23 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
  - 3. Antimicrobial Erosion-Resistant Coating: Apply to the surface of the liner that will form the interior surface of the duct to act as a moisture repellent and erosion-resistant coating. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.
  - 4. Water-Based Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 916.
    - a. Adhesive shall have a VOC content of 80 g/L or less.
    - b. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- B. Insulation Pins and Washers:
  - 1. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
  - 2. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick galvanized steel; with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
- C. Shop Application of Duct Liner: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 7-11, "Flexible Duct Liner Installation."
  - 1. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
  - 2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
  - 3. Butt transverse joints without gaps, and coat joint with adhesive.
  - 4. Fold and compress liner in corners of rectangular ducts or cut and fit to ensure buttededge overlapping.

#### METAL DUCTS

233113 - 6

- 5. Do not apply liner in rectangular ducts with longitudinal joints, except at corners of ducts, unless duct size and dimensions of standard liner make longitudinal joints necessary.
- 6. Apply adhesive coating on longitudinal seams in ducts with air velocity of 2500 fpm.
- 7. Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.
- 8. Secure transversely oriented liner edges facing the airstream with metal nosings that have either channel or "Z" profiles or are integrally formed from duct wall. Fabricate edge facings at the following locations:
  - a. Fan discharges.
  - b. Intervals of lined duct preceding unlined duct.
  - c. Upstream edges of transverse joints in ducts where air velocities are higher than 2500 fpm or where indicated.
- 9. Terminate inner ducts with buildouts attached to fire-damper sleeves, dampers, turning vane assemblies, or other devices. Fabricated buildouts (metal hat sections) or other buildout means are optional; when used, secure buildouts to duct walls with bolts, screws, rivets, or welds.

# 2.5 SEALANT AND GASKETS

- A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
- B. Two-Part Tape Sealing System:
  - 1. Tape: Woven cotton fiber impregnated with mineral gypsum and modified acrylic/silicone activator to react exothermically with tape to form hard, durable, airtight seal.
  - 2. Tape Width: 3 inches.
  - 3. Sealant: Modified styrene acrylic.
  - 4. Water resistant.
  - 5. Mold and mildew resistant.
  - 6. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
  - 7. Service: Indoor and outdoor.
  - 8. Service Temperature: Minus 40 to plus 200 deg F.
  - 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum.
  - 10. Sealant shall have a VOC content of 420 g/L or less.
  - 11. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- C. Water-Based Joint and Seam Sealant:

1. Application Method: Brush on. METAL DUCTS

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 2. Solids Content: Minimum 65 percent.
- 3. Shore A Hardness: Minimum 20.
- 4. Water resistant.
- 5. Mold and mildew resistant.
- 6. VOC: Maximum 75 g/L (less water).
- 7. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
- 8. Service: Indoor or outdoor.
- 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.
- D. Solvent-Based Joint and Seam Sealant:
  - 1. Application Method: Brush on.
  - 2. Base: Synthetic rubber resin.
  - 3. Solvent: Toluene and heptane.
  - 4. Solids Content: Minimum 60 percent.
  - 5. Shore A Hardness: Minimum 60.
  - 6. Water resistant.
  - 7. Mold and mildew resistant.
  - 8. Sealant shall have a VOC content of 420 g/L or less.
  - 9. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
  - 10. Maximum Static-Pressure Class: 10-inch wg, positive or negative.
  - 11. Service: Indoor or outdoor.
  - 12. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.
- E. Flanged Joint Sealant: Comply with ASTM C 920.
  - 1. General: Single-component, acid-curing, silicone, elastomeric.
  - 2. Type: S.
  - 3. Grade: NS.
  - 4. Class: 25.
  - 5. Use: O.
  - 6. Sealant shall have a VOC content of 420 g/L or less.
  - 7. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- F. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.

#### 2.6 HANGERS AND SUPPORTS

A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.

- B. Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.
- C. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."
- D. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A 603.
- E. Steel Cables for Stainless-Steel Ducts: Stainless steel complying with ASTM A 492.
- F. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.
- G. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.
- H. Trapeze and Riser Supports:
  - 1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
  - 2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.
  - 3. Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate.

# 2.7 SEISMIC-RESTRAINT DEVICES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. B-line, an Eaton business.
  - 2. Ductmate Industries, Inc.
  - 3. Mason Industries, Inc.
- B. General Requirements for Restraint Components: Rated strengths, features, and applications shall be as defined in reports by an agency acceptable to authorities having jurisdiction.
  - 1. Structural Safety Factor: Allowable strength in tension, shear, and pullout force of components shall be at least four times the maximum seismic forces to which they will be subjected.
- C. Channel Support System: Shop- or field-fabricated support assembly made of slotted steel channels rated in tension, compression, and torsion forces and with accessories for attachment to braced component at one end and to building structure at the other end. Include matching components and corrosion-resistant coating.
- D. Restraint Cables: ASTM A 603, galvanized-steel cables with end connections made of cadmium-plated steel assemblies with brackets, swivel, and bolts designed for restraining cable service; and with an automatic-locking and clamping device or double-cable clips.

E. Mechanical Anchor Bolts: Drilled-in and stud-wedge or female-wedge type. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488.

# PART 3 - EXECUTION

## 3.1 DUCT INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and Coordination Drawings.
- B. Install ducts according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible" unless otherwise indicated.
- C. Install ducts in maximum practical lengths.
- D. Install ducts with fewest possible joints.
- E. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.
- F. Unless otherwise indicated, install ducts vertically and horizontally, and parallel and perpendicular to building lines.
- G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.
- H. Install ducts with a clearance of 1 inch, plus allowance for insulation thickness.
- I. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.
- J. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.
- K. Where ducts pass through fire-rated interior partitions and exterior walls, install fire dampers. Comply with requirements in Section 233300 "Air Duct Accessories" for fire and smoke dampers.
- L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials. Comply with SMACNA's "IAQ Guidelines for Occupied Buildings Under Construction," Appendix G, "Duct Cleanliness for New Construction Guidelines."

# 3.2 ADDITIONAL INSTALLATION REQUIREMENTS FOR COMMERCIAL KITCHEN HOOD EXHAUST DUCT

- A. Install commercial kitchen hood exhaust ducts without dips and traps that may hold grease, and sloped a minimum of 2 percent to drain grease back to the hood.
- B. Install fire-rated access panel assemblies at each change in direction and at maximum intervals of 20 feet in horizontal ducts, and at every floor for vertical ducts, or as indicated on Drawings.
- C. Do not penetrate fire-rated assemblies except as allowed by applicable building codes and authorities having jurisdiction.
- D. Installation of grease duct shall comply with requirements of 2019 OMSC, Chapter 5.

# 3.3 DUCT SEALING

- A. Seal ducts for duct static-pressure, seal classes, and leakage classes specified in "Duct Schedule" Article according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible."
- B. Seal ducts at a minimum to the following seal classes according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible":
  - 1. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible."
  - 2. Outdoor, Supply-Air Ducts: Seal Class A.
  - 3. Outdoor, Exhaust Ducts: Seal Class C.
  - 4. Outdoor, Return-Air Ducts: Seal Class C.
  - 5. Unconditioned Space, Supply-Air Ducts in Pressure Classes 2-Inch wg and Lower: Seal Class B.
  - 6. Unconditioned Space, Supply-Air Ducts in Pressure Classes Higher Than 2-Inch wg: Seal Class A.
  - 7. Unconditioned Space, Exhaust Ducts: Seal Class C.
  - 8. Unconditioned Space, Return-Air Ducts: Seal Class B.
  - 9. Conditioned Space, Supply-Air Ducts in Pressure Classes 2-Inch wg and Lower: Seal Class C.
  - 10. Conditioned Space, Supply-Air Ducts in Pressure Classes Higher Than 2-Inch wg: Seal Class B.
  - 11. Conditioned Space, Exhaust Ducts: Seal Class B.
  - 12. Conditioned Space, Return-Air Ducts: Seal Class C.

# 3.4 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Chapter 5, "Hangers and Supports."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.

- 1. Where practical, install concrete inserts before placing concrete.
- 2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
- 3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
- 4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.
- 5. Do not use powder-actuated concrete fasteners for seismic restraints.
- C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.
- D. Hangers Exposed to View: Threaded rod and angle or channel supports.
- E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet.
- F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

# 3.5 SEISMIC-RESTRAINT-DEVICE INSTALLATION

- A. Install ducts with hangers and braces designed to support the duct and to restrain against seismic forces required by applicable building codes. Comply with ASCE/SEI 7.
  - 1. Space lateral supports a maximum of 40 feet o.c., and longitudinal supports a maximum of 80 feet o.c.
  - 2. Brace a change of direction longer than 12 feet.
- B. Select seismic-restraint devices with capacities adequate to carry present and future static and seismic loads.
- C. Install cables so they do not bend across edges of adjacent equipment or building structure.
- D. Install cable restraints on ducts that are suspended with vibration isolators.
- E. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction.
- F. Attachment to Structure: If specific attachment is not indicated, anchor bracing and restraints to structure, to flanges of beams, to upper truss chords of bar joists, or to concrete members.
- G. Drilling for and Setting Anchors:
  - 1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcement or embedded items during drilling. Notify the Architect if reinforcing steel or other embedded items are encountered during

drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.

- 2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
- 3. Wedge Anchors: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
- 4. Set anchors to manufacturer's recommended torque, using a torque wrench.
- 5. Install zinc-coated steel anchors for interior applications and stainless-steel anchors for applications exposed to weather.

## 3.6 CONNECTIONS

- A. Make connections to equipment with flexible connectors complying with Section 233300 "Air Duct Accessories."
- B. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

# 3.7 PAINTING

A. Paint interior of metal ducts that are visible through registers and grilles and that do not have duct liner. Apply one coat of flat, black, latex paint over a compatible galvanized-steel primer. Paint materials and application requirements are specified in Section 099123 "Interior Painting."

# 3.8 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Leakage Tests:
  - 1. Comply with SMACNA's "HVAC Air Duct Leakage Test Manual." Submit a test report for each test.
  - 2. Test the following systems:
    - a. Ducts with a Pressure Class Higher Than 3-Inch wg: Test representative duct sections, selected by Architect from sections installed, totaling no less than 25 percent of total installed duct area for each designated pressure class.
  - 3. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
  - 4. Test for leaks before applying external insulation.
  - 5. Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If static-pressure classes are not indicated, test system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure.
  - 6. Give seven days' advance notice for testing.

- C. Duct System Cleanliness Tests:
  - 1. Visually inspect duct system to ensure that no visible contaminants are present.
  - 2. Test sections of metal duct system, chosen randomly by Owner, for cleanliness according to "Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems."
    - a. Acceptable Cleanliness Level: Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm.
- D. Duct system will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

## 3.9 DUCT CLEANING

- A. Clean new duct system(s) before testing, adjusting, and balancing.
- B. Use service openings for entry and inspection.
  - 1. Create new openings and install access panels appropriate for duct static-pressure class if required for cleaning access. Provide insulated panels for insulated or lined duct. Patch insulation and liner as recommended by duct liner manufacturer. Comply with Section 233300 "Air Duct Accessories" for access panels and doors.
  - 2. Disconnect and reconnect flexible ducts as needed for cleaning and inspection.
  - 3. Remove and reinstall ceiling to gain access during the cleaning process.
- C. Particulate Collection and Odor Control:
  - 1. When venting vacuuming system inside the building, use HEPA filtration with 99.97 percent collection efficiency for 0.3-micron-size (or larger) particles.
  - 2. When venting vacuuming system to outdoors, use filter to collect debris removed from HVAC system, and locate exhaust downwind and away from air intakes and other points of entry into building.
- D. Clean the following components by removing surface contaminants and deposits:
  - 1. Air outlets and inlets (registers, grilles, and diffusers).
  - 2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.
  - 3. Air-handling unit internal surfaces and components including mixing box, coil section, air wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.
  - 4. Coils and related components.
  - 5. Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and mechanical equipment rooms.
  - 6. Supply-air ducts, dampers, actuators, and turning vanes.
  - 7. Dedicated exhaust and ventilation components and makeup air systems.

# E. Mechanical Cleaning Methodology:

- 1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.
- 2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
- 3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
- 4. Clean fibrous-glass duct liner with HEPA vacuuming equipment; do not permit duct liner to get wet. Replace fibrous-glass duct liner that is damaged, deteriorated, or delaminated or that has friable material, mold, or fungus growth.
- 5. Clean coils and coil drain pans according to NADCA 1992. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.
- 6. Provide drainage and cleanup for wash-down procedures.
- 7. Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus is present. Apply antimicrobial agents according to manufacturer's written instructions after removal of surface deposits and debris.

# 3.10 START UP

A. Air Balance: Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC."

# 3.11 DUCT SCHEDULE

- A. Fabricate ducts with galvanized sheet steel except as otherwise indicated.
- B. Supply Ducts:
  - 1. Ducts Connected downstream of Terminal Units (VAV-X):
    - a. Pressure Class: Positive 1-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 12.
    - d. SMACNA Leakage Class for Round and Flat Oval: 12.
  - 2. Ducts Connected to Variable-Air-Volume Air-Handling Units (RTU-X, AHU-X, MAU-X):
    - a. Pressure Class: Positive 4-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 3.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.
  - 3. Ducts Connected to Equipment Not Listed Above:

- a. Pressure Class: Positive 2-inch wg.
- b. Minimum SMACNA Seal Class: A.
- c. SMACNA Leakage Class for Rectangular: 6.
- d. SMACNA Leakage Class for Round and Flat Oval: 6.
- C. Return Ducts:
  - 1. Ducts Connected to Air-Handling Units (RTU-X, AHU-X, MAU-X):
    - a. Pressure Class: Positive or negative 2-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 6.
    - d. SMACNA Leakage Class for Round and Flat Oval: 6.
  - 2. Ducts Connected to Equipment Not Listed Above:
    - a. Pressure Class: Positive or negative 2-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 3.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.
- D. Exhaust Ducts:
  - 1. Ducts Connected to Fans Exhausting (ASHRAE 62.1, Class 1 and 2) Air (EF-X):
    - a. Pressure Class: Negative 2-inch wg.
    - b. Minimum SMACNA Seal Class: A if negative pressure, and A if positive pressure.
    - c. SMACNA Leakage Class for Rectangular: 12.
    - d. SMACNA Leakage Class for Round and Flat Oval: 6.
  - 2. Ducts Connected to Air-Handling Units (RTU-X, AHU-X, MAU-X):
    - a. Pressure Class: Positive or negative 3-inch wg.
    - b. Minimum SMACNA Seal Class: A if negative pressure, and A if positive pressure.
    - c. SMACNA Leakage Class for Rectangular: 6.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.
  - 3. Ducts Connected to Commercial Kitchen Hoods: Comply with NFPA 96 (EF-X).
    - a. Exposed to View: Type 304, stainless-steel sheet, No. 3 finish.
    - b. Concealed: Type 304, stainless-steel sheet, No. 2D finish.
    - c. Welded seams and joints.
    - d. Pressure Class: Positive or negative 3-inch wg.
    - e. Airtight/Watertight.
  - 4. Ducts Connected to Equipment Not Listed Above:
    - a. Pressure Class: Positive or negative 2-inch wg.

- b. Minimum SMACNA Seal Class: A if negative pressure, and A if positive pressure.
- c. SMACNA Leakage Class for Rectangular: 6.
- d. SMACNA Leakage Class for Round and Flat Oval: 3.
- E. Outdoor-Air (Not Filtered, Heated, or Cooled) Ducts:
  - 1. Ducts Connected to Air-Handling Units (MAU-X):
    - a. Pressure Class: Positive or negative 3-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 6.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.
  - 2. Ducts Connected to Equipment Not Listed Above:
    - a. Pressure Class: Positive or negative 2-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 6.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.
- F. Intermediate Reinforcement:
  - 1. Galvanized-Steel Ducts: Galvanized steel.
  - 2. PVC-Coated Ducts:
    - a. Exposed to Airstream: Match duct material.
    - b. Not Exposed to Airstream: Match duct material.
  - 3. Stainless-Steel Ducts:
    - a. Exposed to Airstream: Match duct material.
    - b. Not Exposed to Airstream: Match duct material.
- G. Liner Only Where Indicated:
  - 1. Supply Air Ducts: Fibrous glass, Type I, 1 inch thick.
  - 2. Return Air Ducts: Fibrous glass, Type I, 1 inch thick.
  - 3. Transfer Ducts: Fibrous glass, Type I, 1 inch thick.
- H. Elbow Configuration:
  - 1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 4-2, "Rectangular Elbows."
    - a. Radius Type RE 1 with minimum 1.5 radius-to-diameter ratio.
    - b. Radius Type RE 3 with minimum 1.0 radius-to-diameter ratio and two vanes.
    - c. Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 4-3, "Vanes and Vane Runners," and Figure 4-4, "Vane Support in Elbows."

- 2. Round Duct: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 3-4, "Round Duct Elbows."
  - Minimum Radius-to-Diameter Ratio and Elbow Segments: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 3-1, "Mitered Elbows." Elbows with less than 90-degree change of direction have proportionately fewer segments.
    - 1) Radius-to Diameter Ratio: 1.5.
  - b. Round Elbows, 12 Inches and Smaller in Diameter: Stamped or pleated.
  - c. Round Elbows, 14 Inches and Larger in Diameter: Standing seam.
- I. Branch Configuration:
  - 1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 4-6, "Branch Connection."
    - a. Rectangular Main to Rectangular Branch: 45-degree entry.
    - b. Rectangular Main to Round Branch: Spin in.
  - Round and Flat Oval: Comply with SMACNA's "HVAC Duct Construction Standards -Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees." Saddle taps are permitted in existing duct.
    - a. Velocity 1500 fpm or Lower: Conical tap.
    - b. Velocity 1500 fpm or Higher: 45-degree lateral.

END OF SECTION 233113

# SECTION 233300 - AIR DUCT ACCESSORIES

# PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Backdraft dampers.
  - 2. Pressure relief access doors.
  - 3. Manual volume dampers.
  - 4. Control dampers.
  - 5. Flange connectors.
  - 6. Turning vanes.
  - 7. Duct-mounted access doors.
  - 8. Flexible connectors.
  - 9. Duct accessory hardware.
- B. Related Requirements:
  - 1. Section 233423 "HVAC Power Ventilators" for roof-mounted ventilator caps.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For duct accessories. Include plans, elevations, sections, details and attachments to other work.
  - 1. Detail duct accessories fabrication and installation in ducts and other construction. Include dimensions, weights, loads, and required clearances; and method of field assembly into duct systems and other construction. Include the following:
    - a. Special fittings.
    - b. Manual volume damper installations.
    - c. Control-damper installations.
    - d. Wiring Diagrams: For power, signal, and control wiring.

# AIR DUCT ACCESSORIES

# 1.4 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

# PART 2 - PRODUCTS

# 2.1 ASSEMBLY DESCRIPTION

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

# 2.2 MATERIALS

- A. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
  - 1. Galvanized Coating Designation: G60.
  - 2. Exposed-Surface Finish: Mill phosphatized.
- B. Stainless-Steel Sheets: Comply with ASTM A 480/A 480M, Type 304, and having a No. 2 finish for concealed ducts and No. 4 finish for exposed ducts.
- C. Aluminum Sheets: Comply with ASTM B 209, Alloy 3003, Temper H14; with mill finish for concealed ducts and standard, 1-side bright finish for exposed ducts.
- D. Extruded Aluminum: Comply with ASTM B 221, Alloy 6063, Temper T6.
- E. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.
- F. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

# 2.3 BACKDRAFT DAMPERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. Air Balance Inc.
  - 2. Greenheck Fan Corporation.

#### AIR DUCT ACCESSORIES

- 3. Nailor Industries Inc.
- 4. Pottorff.
- 5. Ruskin Company.
- B. Description: Gravity balanced.
- C. Maximum Air Velocity: 2000 fpm.
- D. Maximum System Pressure: 1-inch wg.
- E. Frame: Hat-shaped, 0.05-inch-thick, galvanized sheet steel, with welded corners or mechanically attached and mounting flange.
- F. Blades: Multiple single-piece blades, center pivoted, maximum 6-inch width, 0.025-inch-thick, roll-formed aluminum with sealed edges.
- G. Blade Action: Parallel.
- H. Blade Seals: Neoprene, mechanically locked.
- I. Blade Axles:
  - 1. Material: Nonferrous metal.
  - 2. Diameter: 0.20 inch.
- J. Tie Bars and Brackets: Aluminum.
- K. Return Spring: Adjustable tension.
- L. Bearings: Steel ball or synthetic pivot bushings.
- M. Accessories:
  - 1. Adjustment device to permit setting for varying differential static pressure.
  - 2. Counterweights and spring-assist kits for vertical airflow installations.
  - 3. Electric actuators.
  - 4. Chain pulls.
  - 5. Screen Mounting: Rear mounted.
  - 6. Screen Material: Galvanized steel.
  - 7. Screen Type: Bird.
  - 8. 90-degree stops.

# 2.4 MANUAL VOLUME DAMPERS

A. Standard, Steel, Manual Volume Dampers:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - a. Air Balance Inc.
  - b. Flexmaster U.S.A., Inc.
  - c. MetalAire, Inc.
  - d. Nailor Industries Inc.
  - e. Pottorff.
  - f. Ruskin Company.
  - g. Trox USA Inc.
  - h. Vent Products Co., Inc.
- 2. Standard leakage rating, with linkage outside airstream.
- 3. Suitable for horizontal or vertical applications.
- 4. Frames:
  - a. Frame: Hat-shaped, galvanized-steel channels, 0.064-inch minimum thickness.
  - b. Mitered and welded corners.
  - c. Flanges for attaching to walls and flangeless frames for installing in ducts.
- 5. Blades:
  - a. Multiple or single blade.
  - b. Parallel- or opposed-blade design.
  - c. Stiffen damper blades for stability.
  - d. Galvanized-steel, 0.064 inch thick.
- 6. Blade Axles: Galvanized steel.
- 7. Bearings:
  - a. Oil-impregnated bronze.
  - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
- 8. Tie Bars and Brackets: Galvanized steel.
- B. Standard, Aluminum, Manual Volume Dampers:
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Air Balance Inc.
    - b. Flexmaster U.S.A., Inc.
    - c. MetalAire, Inc.
    - d. Nailor Industries Inc.
    - e. Pottorff.
    - f. Ruskin Company.

#### AIR DUCT ACCESSORIES

g. Trox USA Inc.

- 2. Standard leakage rating, with linkage outside airstream.
- 3. Suitable for horizontal or vertical applications.
- 4. Frames: Hat-shaped, 0.10-inch-thick, aluminum sheet channels; frames with flanges for attaching to walls and flangeless frames for installing in ducts.
- 5. Blades:
  - a. Multiple or single blade.
  - b. Parallel- or opposed-blade design.
  - c. Stiffen damper blades for stability.
  - d. Roll-Formed Aluminum Blades: 0.10-inch-thick aluminum sheet.
  - e. Extruded-Aluminum Blades: 0.050-inch-thick extruded aluminum.
- 6. Blade Axles: Galvanized steel.
- 7. Bearings:
  - a. Oil-impregnated bronze.
  - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
- 8. Tie Bars and Brackets: Aluminum.
- C. Jackshaft:
  - 1. Size: 1-inch diameter.
  - 2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
  - 3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.
- D. Damper Hardware:
  - 1. Zinc-plated, die-cast core with dial and handle made of 3/32-inch-thick zinc-plated steel, and a 3/4-inch hexagon locking nut.
  - 2. Include center hole to suit damper operating-rod size.
  - 3. Include elevated platform for insulated duct mounting.

# 2.5 FLANGE CONNECTORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. Ductmate Industries, Inc.
  - 2. Nexus PDQ.
  - 3. Ward Industries; a brand of Hart & Cooley, Inc.

- B. Description: Add-on or roll-formed, factory-fabricated, slide-on transverse flange connectors, gaskets, and components.
- C. Material: Galvanized steel.
- D. Gage and Shape: Match connecting ductwork.

# 2.6 TURNING VANES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. Ductmate Industries, Inc.
  - 2. Duro Dyne Inc.
  - 3. MetalAire, Inc.
  - 4. SEMCO LLC.
  - 5. Ward Industries; a brand of Hart & Cooley, Inc.
- B. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
  - 1. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.
- C. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible"; Figures 4-3, "Vanes and Vane Runners," and 4-4, "Vane Support in Elbows."
- D. Vane Construction: Single wall.

# 2.7 DUCT-MOUNTED ACCESS DOORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. Cesco Products; a division of MESTEK, Inc.
  - 2. Ductmate Industries, Inc.
  - 3. Flexmaster U.S.A., Inc.
  - 4. Greenheck Fan Corporation.
  - 5. Nailor Industries Inc.
  - 6. Pottorff.
- B. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible"; Figures 7-2, "Duct Access Doors and Panels," and 7-3, "Access Doors Round Duct."
  - 1. Door:

# AIR DUCT ACCESSORIES
- a. Double wall, rectangular.
- b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
- c. Vision panel.
- d. Hinges and Latches: 1-by-1-inchbutt or piano hinge and cam latches.
- e. Fabricate doors airtight and suitable for duct pressure class.
- 2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
- 3. Number of Hinges and Locks:
  - a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
  - b. Access Doors up to 18 Inches Square: Two hinges and two sash locks.
  - c. Access Doors up to 24 by 48 Inches: Three hinges and two compression latches with outside and inside handles.
  - d. Access Doors Larger Than 24 by 48 Inches: Four hinges and two compression latches with outside and inside handles.

# 2.8 DUCT ACCESS PANEL ASSEMBLIES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. 3M.
  - 2. Ductmate Industries, Inc.
  - 3. Flame Gard, Inc.
- B. Labeled according to UL 1978 by an NRTL.
- C. Panel and Frame: Minimum thickness 0.0528-inch carbon steel.
- D. Fasteners: Carbon steel. Panel fasteners shall not penetrate duct wall.
- E. Gasket: Comply with NFPA 96; grease-tight, high-temperature ceramic fiber, rated for minimum 2000 deg F.
- F. Minimum Pressure Rating: 10-inch wg, positive or negative.

# 2.9 FLEXIBLE CONNECTORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. Ductmate Industries, Inc.
  - 2. Duro Dyne Inc.
  - 3. Ventfabrics, Inc.
  - 4. Ward Industries; a brand of Hart & Cooley, Inc.

# AIR DUCT ACCESSORIES

- B. Materials: Flame-retardant or noncombustible fabrics.
- C. Coatings and Adhesives: Comply with UL 181, Class 1.
- D. Metal-Edged Connectors: Factory fabricated with a fabric strip 3-1/2 inches wide attached to two strips of 2-3/4-inch-wide, 0.028-inch-thick, galvanized sheet steel or 0.032-inch-thick aluminum sheets. Provide metal compatible with connected ducts.
- E. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
  - 1. Minimum Weight: 26 oz./sq. yd.
  - 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
  - 3. Service Temperature: Minus 40 to plus 200 deg F.
- F. Outdoor System, Flexible Connector Fabric: Glass fabric double coated with weatherproof, synthetic rubber resistant to UV rays and ozone.
  - 1. Minimum Weight: 24 oz./sq. yd.
  - 2. Tensile Strength: 530 lbf/inch in the warp and 440 lbf/inch in the filling.
  - 3. Service Temperature: Minus 50 to plus 250 deg F.
- G. Thrust Limits: Combination coil spring and elastomeric insert with spring and insert in compression, and with a load stop. Include rod and angle-iron brackets for attaching to fan discharge and duct.
  - 1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
  - 2. Outdoor Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
  - 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
  - 4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
  - 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
  - 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
  - 7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.

# 2.10 DUCT ACCESSORY HARDWARE

- A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.
- B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

# PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.
- C. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel.
  - 1. Install steel volume dampers in steel ducts.
  - 2. Install aluminum volume dampers in aluminum ducts.
  - 3. Volume dampers not required between AHU discharge and VAV terminal units.
- D. Set dampers to fully open position before testing, adjusting, and balancing.
- E. Install test holes at fan inlets and outlets and elsewhere as indicated.
- F. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:
  - 1. Install pressure relief access door between air handling unit and first wall and/or floor penetration.
  - 2. Elsewhere as indicated.
- G. Install access doors with swing against duct static pressure.
- H. Access Door Sizes:
  - 1. One-Hand or Inspection Access: 8 by 5 inches.
  - 2. Two-Hand Access: 12 by 6 inches.
  - 3. Head and Hand Access: 18 by 10 inches.
  - 4. Head and Shoulders Access: 21 by 14 inches.
  - 5. Body Access: 25 by 14 inches.
  - 6. Body plus Ladder Access: 25 by 17 inches.
- I. Label access doors according to Section 230553 "Identification for HVAC Piping and Equipment" to indicate the purpose of access door.
- J. Install flexible connectors to connect ducts to equipment.

- K. For fans developing static pressures of 5-inch wg and more, cover flexible connectors with loaded vinyl sheet held in place with metal straps.
- L. Connect terminal units to supply ducts directly or with maximum 12-inch lengths of flexible duct. Do not use flexible ducts to change directions.
- M. Connect diffusers or light troffer boots to low-pressure ducts directly or with maximum 60-inch lengths of flexible duct clamped or strapped in place.
- N. Connect flexible ducts to metal ducts with liquid adhesive plus tape.
- O. Install duct test holes where required for testing and balancing purposes.
- P. Install thrust limits at centerline of thrust, symmetrical on both sides of equipment. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4-inch movement during start and stop of fans.
- Q. Install pressure relief access door between unit connection and first branch on supply and return for each air handling unit (AHU).
- R. Install acoustic turning vanes in all supply, return and exhaust system mitered elbows 45 degrees and larger and as indicated. Do not install turning vanes in commercial kitchen hood exhaust duct.

# 3.2 FIELD QUALITY CONTROL

- A. Tests and Inspections:
  - 1. Operate dampers to verify full range of movement.
  - 2. Inspect locations of access doors and verify that purpose of access door can be performed.
  - 3. Inspect turning vanes for proper and secure installation.
  - 4. Operate remote damper operators to verify full range of movement of operator and damper.

END OF SECTION 233300

# SECTION 233423 - HVAC POWER VENTILATORS

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Centrifugal ventilators roof upblast and sidewall.

## 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes for fans.
  - 2. Rated capacities, operating characteristics, and furnished specialties and accessories.
  - 3. Certified fan performance curves with system operating conditions indicated.
  - 4. Certified fan sound-power ratings.
  - 5. Motor ratings and electrical characteristics, plus motor and electrical accessories.
  - 6. Material thickness and finishes, including color charts.
  - 7. Dampers, including housings, linkages, and operators.
  - 8. Prefabricated roof curbs.
  - 9. Fan speed controllers.
- B. Shop Drawings:
  - 1. Include plans, elevations, sections, and attachment details.
  - 2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  - 3. Include diagrams for power, signal, and control wiring.
  - 4. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints.
- C. Delegated-Design Submittal: For unit hangars and supports indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.

# 1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Floor plans, reflected ceiling plans, and other details, or BIM model, drawn to scale, showing the items described in this Section and coordinated with all building trades.
- B. Seismic Qualification Data: For fans, accessories, and components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- C. Field quality-control reports.

# 1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For HVAC power ventilators to include in normal and emergency operation, and maintenance manuals.

# 1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Belts: One set(s) for each belt-driven unit.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design vibration isolation and seismic restraints, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- B. Seismic Performance: HVAC power ventilators shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

- 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."
- 2. Component Importance Factor: 1.0.
- C. Capacities and Characteristics:
  - 1. As indicated on drawings.

# 2.2 CENTRIFUGAL VENTILATORS - ROOF UPBLAST OR SIDEWALL

- A. Configuration: Centrifugal roof upblast, grease hood kitchen ventilator.
- B. Housing: Removable spun-aluminum dome top and outlet baffle; square, one-piece aluminum base with venturi inlet cone.
  - 1. Upblast Units: Provide spun-aluminum discharge baffle to direct discharge air upward, with rain and snow drains.
  - 2. Provide grease collector.
- C. Fan Wheels: Aluminum hub and wheel with backward-inclined blades; sparkproof construction.
- D. Belt Drives:
  - 1. Resiliently mounted to housing.
  - 2. Fan Shaft: Turned, ground, and polished steel; keyed to wheel hub.
  - 3. Shaft Bearings: Permanently lubricated, permanently sealed, self-aligning ball bearings; minimum ABMA9, L(10) of 100,000 hours.
  - 4. Fan Pulleys: Cast iron or cast steel with split, tapered bushing; dynamically balanced at factory.
  - 5. Motor Pulleys: Adjustable pitch for use with motors through 5 hp. Select pulley so pitch adjustment is at the middle of adjustment range at fan design conditions. Provide fixed pitch for use with motors larger than 5 hp.
  - 6. Fan and motor isolated from exhaust airstream.
- E. Accessories:
  - 1. Variable-Frequency Motor Controller: Solid-state control to reduce speed from 100 to less than 50 percent.
  - 2. Disconnect Switch: Nonfusible type, with thermal-overload protection mounted outside fan housing, factory wired through an internal aluminum conduit.
  - 3. Bird Screens: Removable, 1/2-inch mesh, aluminum or brass wire.
  - 4. Dampers: Counterbalanced, parallel-blade, backdraft dampers mounted in curb base; factory set to close when fan stops.
  - 5. Motorized Dampers: Parallel-blade dampers mounted in curb base with electric actuator; wired to close when fan stops.
  - 6. Spark-resistant, all-aluminum wheel construction.
  - 7. Mounting Pedestal: Galvanized steel with removable access panel.
  - 8. Wall Mount Adapter: Attach wall-mounted fan to wall.

# HVAC POWER VENTILATORS

- 9. Restaurant Kitchen Exhaust: UL 762 listed for grease-laden air exhaust.
- F. Prefabricated Kitchen Exhaust Roof Curbs: Galvanized steel; mitered and welded corners; ventilation openings on all sides to ventilate curb interstitial space. Size as required to suit roof opening and fan base.
  - 1. Configuration: Built-in cant and mounting flange.
  - 2. Overall Height: 18 inches.
  - 3. Sound Curb: Curb with sound-absorbing insulation and galvanized metal liner.
  - 4. Hinged sub-base to provide access to damper or as cleanout for grease applications.
  - 5. Pitch Mounting: Manufacture curb for roof slope.
  - 6. Metal Liner: Galvanized steel.
  - 7. Mounting Pedestal: Galvanized steel with removable access panel.
  - 8. Vented Curb: For kitchen exhaust; 12-inch-high galvanized steel; unlined, with louvered vents in vertical sides.
  - 9. NFPA 96 code requirements for commercial cooking operations.
  - 10. Kitchen Hood Exhaust: UL 762 listed for grease-laden air.

#### 2.3 MOTORS

- A. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors.
  - 1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.

## 2.4 SOURCE QUALITY CONTROL

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and application.
- B. AMCA Certification: Fans shall comply with AMCA 11 and bear the AMCA-Certified Ratings Seal.
- C. Fan Sound Ratings: Comply with AMCA 311, and label fans with the AMCA-Certified Ratings Seal. Sound ratings shall comply with AMCA 301. The fans shall be tested according to AMCA 300.
- D. Fan Performance Ratings: Comply with AMCA 211 and label fans with AMCA-Certified Rating Seal. The fans shall be tested for air performance flow rate, fan pressure, power, fan efficiency, air density, speed of rotation, and fan efficiency according to AMCA 210/ASHRAE 51.
- E. Operating Limits: Classify according to AMCA 99.
- F. UL Standards: Power ventilators shall comply with UL 705. Power ventilators for use for restaurant kitchen exhaust shall also comply with UL 762.

HVAC POWER VENTILATORS

# PART 3 - EXECUTION

## 3.1 INSTALLATION OF HVAC POWER VENTILATORS

- A. Install power ventilators level and plumb.
- B. Equipment Mounting:
  - 1. Comply with requirements for vibration isolation and seismic-control devices specified in Section 230548 "Vibration and Seismic Controls for HVAC."
- C. Secure roof-mounted fans to roof curbs with zinc-plated hardware. See Section 077200 "Roof Accessories" for installation of roof curbs.
- D. Install units with clearances for service and maintenance.
- E. Label units according to requirements specified in Section 230553 "Identification for HVAC Piping and Equipment."

## 3.2 DUCTWORK CONNECTIONS

A. Drawings indicate general arrangement of ducts and duct accessories. Make final duct connections with flexible connectors. Flexible connectors are specified in Section 233300 "Air Duct Accessories."

#### 3.3 ELECTRICAL CONNECTIONS

- A. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
- B. Install electrical devices furnished by manufacturer, but not factory mounted, according to NFPA 70 and NECA 1.
  - 1. Nameplate shall be laminated acrylic or melamine plastic signs, as specified in Section 260553 "Identification for Electrical Systems."
  - 2. Nameplate shall be laminated acrylic or melamine plastic signs with a black background and engraved white letters at least 1/2 inch high.

## 3.4 CONTROL CONNECTIONS

A. Install control and electrical power wiring to field-mounted control devices.

# 3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections.
- E. Tests and Inspections:
  - 1. Verify that shipping, blocking, and bracing are removed.
  - 2. Verify that unit is secure on mountings and supporting devices and that connections to ducts and electrical components are complete. Verify that proper thermal-overload protection is installed in motors, starters, and disconnect switches.
  - 3. Verify that there is adequate maintenance and access space.
  - 4. Verify that cleaning and adjusting are complete.
  - 5. Disconnect fan drive from motor, verify proper motor rotation direction, and verify fan wheel free rotation and smooth bearing operation. Reconnect fan drive system, align and adjust belts, and install belt guards.
  - 6. Adjust belt tension.
  - 7. Adjust damper linkages for proper damper operation.
  - 8. Verify lubrication for bearings and other moving parts.
  - 9. Verify that manual and automatic volume control and fire and smoke dampers in connected ductwork systems are in fully open position.
  - 10. Disable automatic temperature-control operators, energize motor and adjust fan to indicated rpm, and measure and record motor voltage and amperage.
  - 11. Shut unit down and reconnect automatic temperature-control operators.
  - 12. Remove and replace malfunctioning units and retest as specified above.
- F. Test and adjust controls and safeties. Controls and equipment will be considered defective if they do not pass tests and inspections.
- G. Prepare test and inspection reports.

# 3.6 ADJUSTING

- A. Adjust damper linkages for proper damper operation.
- B. Adjust belt tension.
- C. Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing procedures.
- D. Replace fan and motor pulleys as required to achieve design airflow.

#### HVAC POWER VENTILATORS

- E. Lubricate bearings.
- 3.7 DEMONSTRATION
  - A. Train Owner's maintenance personnel to adjust, operate, and maintain centrifugal fans.

END OF SECTION 233423

HVAC POWER VENTILATORS

# SECTION 233533 - LISTED KITCHEN VENTILATION SYSTEM EXHAUST DUCTS

PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Listed grease ducts.
  - 2. Access doors.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for listed grease ducts.
- B. Shop Drawings: For listed grease ducts.
  - 1. Include plans, elevations, sections, and attachment details.
  - 2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  - 3. Detail fabrication and assembly of hangers and seismic restraints.

# 1.4 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to the following:
  - 1. AWS D1.1/D1.1M, "Structural Welding Code Steel," for hangers and supports.
  - 2. AWS D9.1/D9.1M, "Sheet Metal Welding Code," for shop and field welding of joints and seams in listed grease ducts and field-fabricated grease ducts.

# PART 2 - PRODUCTS

## 2.1 LISTED GREASE DUCTS

- A. Description: Factory-fabricated, -listed, and -labeled, double-wall ducts tested according to UL 1978 and rated for 500 deg F continuously, or 2000 deg F for 30 minutes; with positive or negative duct pressure and complying with NFPA 211.
- B. Construction: Inner shell and outer jacket separated by at least a 1-inch annular space filled with high-temperature, ceramic-fiber insulation.
  - 1. Inner Shell: ASTM A 666, Type 316 stainless steel.
  - 2. Outer Jacket: Stainless steel where concealed. Stainless steel where exposed.
- C. Gaskets and Flanges: Ensure that gaskets and sealing materials are rated at 1500 deg F minimum.
- D. Hood Connectors: Constructed from same material as grease duct with internal or external continuously welded or brazed joints.
- E. Accessories: Tees, elbows, increasers, terminations, adjustable roof flashings, storm collars, support assemblies, thimbles, firestop spacers, and fasteners; fabricated from similar materials and designs as vent-pipe straight sections; all listed for same assembly. Include unique components required to comply with NFPA 96 including cleanouts, transitions, adapters, and drain fittings.
- F. Grease Duct Supports: Construct duct bracing and supports from non-combustible material.
  - 1. Design bracing and supports to carry static and seismic loads within stress limitations of the International Building Code.
  - 2. Ensure that bolts, screws, rivets and other mechanical fasteners do not penetrate duct walls.
- G. Comply with ASTM E 2336.
- H. Factory Tests: Test and inspect fire resistance of grease duct system according to ASTM E 2336.

## 2.2 ACCESS DOORS

- A. Description: Factory-fabricated, -listed, and -labeled, double-wall maintenance access doors tested according to UL 1978 and rated for 500 deg F continuously, or 2000 deg F for 30 minutes; with positive or negative duct pressure and complying with NFPA 211.
  - 1. Construction: 0.0625 inch ASTM A 666, Type 316 stainless-steel inner shell and stainless-steel outer cover with two handles.
  - 2. Fasteners: Stainless-steel bolts and wing nuts.

## LISTED KITCHEN VENTILATION SYSTEM EXHAUST DUCTS

233533 - 2

- a. Ensure that bolts do not penetrate interior of duct space.
- 3. Maintenance Access Door Dimensions: 7 x 7 inches.
- 4. Personnel Access Door Dimensions: 24 x 24 inches.
- 5. Door Label: Mark door with uppercase lettering as follows: "ACCESS PANEL. DO NOT OBSTRUCT."

## PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine areas and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

## 3.2 INSTALLATION

- A. Coordinate installation of roof curbs, equipment supports, and roof penetrations. Comply with requirements in Section 077200 "Roof Accessories."
- B. Coordinate connections to exhaust fans with requirements in Section 233423 "HVAC Power Ventilators."
- C. Coordinate firestopping where grease ducts penetrate fire separations with requirements in Section 078413 "Penetration Firestopping."
- D. Comply with minimum clearances from combustibles and minimum termination heights according to product listing or NFPA 211 and UL 2221, whichever is most stringent.
- E. Install airtight maintenance access doors where indicated.
- F. Seal between sections of grease exhaust ducts according to manufacturer's written installation instructions, using sealants recommended by manufacturer.
- G. Connections: Make grease duct connections according to the International Mechanical Code.
  - 1. Grease duct to exhaust fan connections: Connect grease ducts to inlet side of fan using flanges, gaskets, and bolts.
  - 2. Grease duct to hood connections:
    - a. Make grease duct to hood joints connections using internal or external continuously welded or brazed joints.
    - b. Make watertight grease duct to hood joints connections using flanges, gaskets, and bolts.

- H. Support ducts at intervals recommended by manufacturer to support weight of ducts and accessories, without applying loading on kitchen hoods.
  - 1. Securely attach supports and bracing to structure.
- I. Grease Duct Enclosures: Comply with requirements of the International Building Code and ASTM E 2336.
- J. Repair damage to adjacent materials caused by listed kitchen ventilation system exhaust ducts installation.

## 3.3 FIELD QUALITY CONTROL

A. Perform air leakage test before concealment of any portion of the grease duct system.

END OF SECTION 233533

# SECTION 237423.16 - PACKAGED, INDIRECT-FIRED, OUTDOOR, MAKEUP-AIR UNITS

PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

A. Section includes indirect-fired makeup-air units.

## 1.3 DEFINITIONS

A. DDC: Direct digital control.

## 1.4 ACTION SUBMITTALS

- A. Product Data: For each type and configuration of outdoor, indirect-fired makeup-air unit.
  - 1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Sustainable Design Submittals:
  - 1. Product Data: For ventilation equipment, indicating compliance with ASHRAE 62.1, Section 5 "Systems and Equipment."
- C. Shop Drawings: For each type and configuration of outdoor, indirect-fired heating and ventilating unit.
  - 1. Signed, sealed, and prepared by or under the supervision of a qualified professional engineer.
  - 2. Include plans, elevations, sections, and attachment details.
  - 3. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  - 4. Detail fabrication and assembly of gas-fired heating and ventilating units, as well as procedures and diagrams.
  - 5. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.

- 6. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include auxiliary motor slides and rails, and base weights.
- 7. Include diagrams for power, signal, and control wiring.

# 1.5 INFORMATIONAL SUBMITTALS

- A. Startup service reports.
- B. Sample Warranty: For manufacturer's special warranty.
- C. Seismic Qualification Certificates: For outdoor, indirect-fired makeup-air units, accessories, and components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

## 1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For indirect-fired makeup-air units to include in emergency, operation, and maintenance manuals.

# 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Filters: One sets for each unit.
- 1.8 QUALITY ASSURANCE
  - A. Comply with NFPA 70.
  - B. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 "Systems and Equipment" and Section 7 "Construction and Startup."
  - C. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6 "Heating, Ventilating, and Air-Conditioning."

237423.16 - 3

# 1.9 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of indirect-fired heating and ventilating units that fail in materials or workmanship within specified warranty period.
  - 1. Warranty Period for Heat Exchangers: Manufacturer's standard, but not less than 10 years from date of Substantial Completion.

## PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Accurex.
  - 2. CaptiveAire Systems.
  - 3. Greenheck Fan Corporation.

# 2.2 SYSTEM DESCRIPTION

- A. AHRI Compliance:
  - 1. Comply with AHRI 340/360 for testing and rating energy efficiencies for RTUs.
  - 2. Comply with AHRI 270 for testing and rating sound performance for RTUs.
- B. AMCA Compliance:
  - 1. Comply with AMCA 11 and bear the AMCA-Certified Ratings Seal for air and sound performance according to AMCA 211 and AMCA 311.
  - 2. Damper leakage tested in accordance with AMCA 500-D.
  - 3. Operating Limits: Classify according to AMCA 99.
- C. ASHRAE Compliance:
  - 1. Comply with ASHRAE 15 for refrigeration system safety.
  - 2. Comply with ASHRAE 33 for methods of testing cooling and heating coils.
  - 3. Comply with applicable requirements in ASHRAE 62.1, Section 5 "Systems and Equipment" and Section 7 "Construction and Startup."
- D. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6 "Heating, Ventilating, and Air-Conditioning."
- E. NFPA Compliance: Comply with NFPA 90A or NFPA 90B.
- F. UL Compliance: Comply with UL 1995.

#### PACKAGED, INDIRECT-FIRED, OUTDOOR, MAKEUP-AIR UNITS

## 2.3 UNIT CASINGS

- A. General Fabrication Requirements for Casings:
  - 1. Forming: Form walls, roofs, and floors with at least two breaks at each joint.
  - 2. Casing Joints: Sheet metal screws or pop rivets, factory sealed with water-resistant sealant.
  - 3. Factory Finish for Galvanized-Steel Casings: Apply manufacturer's standard primer immediately after cleaning and pretreating.
  - 4. Air-Handling-Unit Mounting Frame: Formed galvanized-steel channel or structural channel supports, designed for low deflection, welded with integral lifting lugs.
    - a. Seismic Fabrication Requirements: Fabricate mounting base and attachment to airhandling-unit sections, accessories, and components with reinforcement strong enough to withstand seismic forces defined in Section 230548 "Vibration and Seismic Controls for HVAC" when air-handling-unit frame is anchored to building structure.
  - 5. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
- B. Configuration: Horizontal unit with bottom discharge for roof-mounting installation.
- C. Cabinet: Galvanized-steel panels, formed to ensure rigidity and supported by galvanized-steel channels or structural channel supports with lifting lugs. Duct flanges at inlet and outlet. Pitched roof panels and knockouts with grommet seals for electrical and piping connections and lifting lugs.
- D. Outer Casing: 0.0598-inch-thick steel with heat-resistant, baked-enamel finish.
- E. Inner Casing:
  - 1. Burner Section Inner Casing: 0.0299-inch-thick steel.
  - 2. Double-wall casing with inner wall of solid steel, for the following sections:
    - a. Blower section.
    - b. Filter section.
    - c. Mixing box.
    - d. Inlet plenum.
    - e. Discharge plenum.
    - f. Access Panels: Lift out for burner and fan motor assemblies on both sides of unit.
  - 3. Internal Insulation: Fibrous-glass duct lining, neoprene coated, comply with ASTM C 1071, Type II, applied on complete unit.
    - a. Thickness: 2 inches.
    - b. Insulation Adhesive: Comply with ASTM C 916, Type I.
    - c. Density: 1.5 lb/cu. ft.

- d. Mechanical Fasteners: Galvanized steel suitable for adhesive, mechanical, or welding attachment to casing without damaging liner when applied as recommended by manufacturer and without causing air leakage.
- F. Casing Insulation and Adhesive:
  - 1. Materials: ASTM C 1071, Type I.
  - 2. Location and Application: Encased between outside and inside casing.
- G. Inspection and Access Panels and Access Doors:
  - 1. Panel and Door Fabrication: Formed and reinforced, single- or double-wall and insulated panels of same materials and thicknesses as casing.
  - 2. Inspection and Access Panels:
    - a. Fasteners: Two or more camlock type for panel lift-out operation. Arrangement shall allow panels to be opened against air-pressure differential.
    - b. Gasket: Neoprene, applied around entire perimeters of panel frames.
    - c. Size: Large enough to allow inspection and maintenance of air-handling unit's internal components.
  - 3. Access Doors:
    - a. Hinges: A minimum of two ball-bearing hinges or stainless-steel piano hinge and two wedge-lever-type latches, operable from inside and outside. Arrange doors to be opened against air-pressure differential.
    - b. Gasket: Neoprene, applied around entire perimeters of panel frames.
- H. Condensate Drain Pans:
  - 1. Fabricated with two percent slope in at least two planes to collect condensate from condensate-producing heat exchangers and from humidifiers, and to direct water toward drain connection.
    - a. Length: Extend drain pan downstream from leaving face to comply with ASHRAE 62.1.
    - b. Depth: A minimum of 2 inches deep.
  - 2. Formed sections.
  - 3. Double-wall, stainless-steel sheet with space between walls filled with foam insulation and moisture-tight seal.
  - 4. Drain Connection: Located at lowest point of pan and sized to prevent overflow. Terminate with threaded nipple on one end of pan.
  - 5. Pan-Top Surface Coating: Asphaltic waterproofing compound.

# 2.4 ACCESSORIES

- A. Filter differential pressure switch with sensor tubing on either side of filter. Set for final filter pressure loss.
- B. Hail guards of galvanized steel, painted to match casing.

# 2.5 OUTDOOR-AIR INTAKE HOOD

- A. Type: Manufacturer's standard hood or louver.
- B. Materials: Match cabinet.
- C. Bird Screen: Comply with requirements in ASHRAE 62.1.
- D. Filter: Aluminum, 1 inch cleanable.
- E. Configuration: Designed to inhibit wind-driven rain and snow from entering unit.

# 2.6 ROOF CURBS

- A. Roof curbs with vibration isolators and wind or seismic restraints are specified in Section 230548 "Vibration and Seismic Controls for HVAC."
- B. Materials: Galvanized steel with corrosion-protection coating, watertight gaskets, and factoryinstalled wood nailer; complying with NRCA standards.
  - 1. Curb Insulation and Adhesive: Comply with NFPA 90A or NFPA 90B.
    - a. Materials: ASTM C 1071, Type I or Type II.
    - b. Thickness: 1 inch.
  - 2. Application: Factory applied with adhesive and mechanical fasteners to the internal surface of curb.
    - a. Liner Adhesive: Comply with ASTM C 916, Type I.
    - b. Mechanical Fasteners: Galvanized steel, suitable for adhesive attachment, mechanical attachment, or welding attachment to duct without damaging liner when applied as recommended by manufacturer and without causing leakage in cabinet.
    - c. Liner materials applied in this location shall have air-stream surface coated with a temperature-resistant coating or faced with a plain or coated fibrous mat or fabric depending on service air velocity.
    - d. Liner Adhesive: Comply with ASTM C 916, Type I.
- C. Curb Height: 14 inches.

D. Wind and Seismic Restraints: Metal brackets compatible with the curb and casing, painted to match unit, used to anchor unit to the curb, and designed for loads at Project site. Comply with requirements in Section 230548 "Vibration and Seismic Controls for HVAC" for wind-load requirements.

# 2.7 SUPPLY-AIR FAN

- A. Fan Type: Centrifugal, rated according to AMCA 210; statically and dynamically balanced, galvanized steel; mounted on solid-steel shaft with heavy-duty, self-aligning, permanently lubricated ball bearings. Bearing rating: L10 of 120,000 hours.
- B. Drive: Direct
- C. Mounting: Fan wheel, motor, and drives shall be mounted in fan casing with restrained, isolators.
- D. Fan-Shaft Lubrication Lines: Extended to a location outside the casing.

# 2.8 AIR FILTERS

- A. Comply with NFPA 90A.
- B. Disposable Panel Filters: Factory-fabricated, flat-panel-type, disposable air filters with holding frames, with a MERV 8 filter.
  - 1. Thickness: 2 inches.
  - 2. Frame: Galvanized steel.
  - 3. Maximum Face Velocity: 500 fpm

# 2.9 DAMPERS

- A. Outdoor-Air and Return-Air Damper: Galvanized-steel, opposed-blade dampers with vinyl blade seals and stainless-steel jamb seals, having a maximum leakage of 4 cfm/sq. ft. of damper area, at a differential pressure of 2-inch wg.
- B. Damper Operator: Direct coupled, electronic with spring return or fully modulating as required by the control sequence.

# 2.10 INDIRECT-FIRED GAS BURNER

- A. Description: Factory assembled, piped, and wired; and complying with ANSI Z21.47, "Gas-Fired Central Furnaces," and with NFPA 54, "National Fuel Gas Code."
  - 1. CSA Approval: Designed and certified by and bearing label of CSA.
  - 2. Burners: Stainless steel.

# PACKAGED, INDIRECT-FIRED, OUTDOOR, MAKEUP-AIR UNITS 237423.16 - 7

- a. Gas Control Valve: Modulating.
- b. Fuel: Natural gas.
- c. Minimum Combustion Efficiency: 80 percent.
- d. Ignition: Electronically controlled electric spark with flame sensor.
- B. Venting: Power vented, with integral, motorized centrifugal fan interlocked with gas valve.
- C. Combustion-Air Intake: Separate combustion-air intake and vent terminal assembly.
- D. Heat Exchanger: Stainless steel.
- E. Heat-Exchanger Drain Pan: Stainless steel.
- F. Safety Controls:
  - 1. Vent Flow Verification: Flame rollout switch.
  - 2. Control Transformer: 24-V ac.
  - 3. High Limit: Thermal switch or fuse to stop burner.
  - 4. Gas Train: Regulated, redundant, 24-V ac gas valve assembly containing pilot solenoid valve, electronic-modulating temperature control valve, pilot filter, pressure regulator, pilot shutoff, and manual shutoff all in one body.
  - 5. Purge-period timer shall automatically delay burner ignition and bypass low-limit control.
  - 6. Gas Manifold: Safety switches and controls complying with ANSI standards and FM Global.
  - 7. Airflow Proving Switch: Differential pressure switch senses correct airflow before energizing pilot.
  - 8. Automatic-Reset, High-Limit Control Device: Stops burner and closes main gas valve if high-limit temperature is exceeded.
  - 9. Safety Lockout Switch: Locks out ignition sequence if burner fails to light after three tries. Controls are reset manually by turning the unit off and on.

# 2.11 UNIT CONTROL PANEL

- A. Factory-wired, fuse-protected control transformer, connection for power supply and field-wired unit to remote control panel.
- B. Control Panel: Surface-mounted remote panel, with engraved plastic cover and the following lights and switches:
  - 1. On-off-auto fan switch.
  - 2. Heat-vent-off switch.
  - 3. Supply-fan operation indicating light.
  - 4. Heating operation indicating light.
  - 5. Thermostat.
  - 6. Damper position potentiometer.
  - 7. Dirty-filter indicating light operated by unit-mounted differential pressure switch.
  - 8. Safety-lockout indicating light.

# PACKAGED, INDIRECT-FIRED, OUTDOOR, MAKEUP-AIR UNITS

9. Enclosure: NEMA 250, Type 3R.

#### 2.12 CONTROLS

- A. Comply with requirements in Section 230923 "Direct Digital Control (DDC) System for HVAC."
- B. Interface with DDC System for HVAC: Factory-installed hardware and software to enable the DDC system for HVAC to monitor, control, and display status and alarms of heating and ventilating unit.
  - 1. Hardwired Points:
    - a. Room temperature.
    - b. Discharge-air temperature.
    - c. Burner operating.
  - 2. ASHRAE 135.1 (BACnet) communication interface with the DDC system for HVAC shall enable the DDC system for HVAC operator to remotely control and monitor the heating and ventilating unit from an operator workstation. Control features and monitoring points displayed locally at heating and ventilating unit control panel shall be available through the DDC system for HVAC.

#### 2.13 MOTORS

- A. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors.
  - 1. Enclosure: Totally enclosed, fan cooled.

# 2.14 CAPACITIES AND CHARACTERISTICS

A. General: As indicated on drawings.

# PART 3 - EXECUTION

## 3.1 EXAMINATION

- A. Examine areas and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for piping, ducts, and electrical systems to verify actual locations of connections before equipment installation.

PACKAGED, INDIRECT-FIRED, OUTDOOR, MAKEUP-AIR UNITS 237423.16 - 9

- C. Verify cleanliness of airflow path to include inner-casing surfaces, filters, coils, turning vanes, fan wheels, and other components.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 INSTALLATION

- A. Equipment Mounting:
  - 1. Comply with requirements for vibration isolation and seismic control devices specified in Section 230548 "Vibration and Seismic Controls for HVAC."
- B. Unit Support: Install heating and ventilating unit level on structural curbs. Coordinate wall penetrations and flashing with wall construction. Secure units to structural support with anchor bolts.
- C. Install gas-fired units according to NFPA 54, "National Fuel Gas Code."
- D. Install controls and equipment shipped by manufacturer for field installation with indirect-fired heating and ventilating units.
- E. Roof Curb: Install on roof structure or concrete base, level and secure, according to ARI Guideline B. Install units on curbs and coordinate roof penetrations and flashing with roof construction specified in Section 077200 "Roof Accessories." Secure units to upper curb rail, and secure curb base to roof framing or concrete base with anchor bolts.
- F. Unit Support: Install unit level on structural curbs. Coordinate wall penetrations and flashing with wall construction. Secure units to structural support with anchor bolts.

# 3.3 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
  - 1. Gas Piping: Comply with requirements in Section 231123 "Facility Natural-Gas Piping." Connect gas piping with shutoff valve and union, and with sufficient clearance for burner removal and service. Make final connections of gas piping to unit with corrugated, stainless-steel tubing flexible connectors complying with ANSI LC 1/CSA 6.26 equipment connections.
- B. Install condensate drain, minimum connection size, with trap and indirect connection to nearest roof or area drain.
- C. Duct Connections: Connect supply and return ducts to indirect-fired heating and ventilating units with flexible duct connectors. Comply with requirements in Section 233300 "Air Duct Accessories" for flexible duct connectors.

D. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

# 3.4 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- B. Perform tests and inspections with the assistance of a factory-authorized service representative.
- C. Units will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

# 3.5 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
- B. Complete installation and startup checks according to manufacturer's written instructions and perform the following:
  - 1. Inspect for visible damage to burner combustion chamber.
  - 2. Inspect casing insulation for integrity, moisture content, and adhesion.
  - 3. Verify that clearances have been provided for servicing.
  - 4. Verify that controls are connected and operable.
  - 5. Verify that filters are installed.
  - 6. Purge gas line.
  - 7. Inspect and adjust vibration isolators and seismic restraints.
  - 8. Verify bearing lubrication.
  - 9. Inspect fan-wheel rotation for movement in correct direction without vibration and binding.
  - 10. Adjust fan belts to proper alignment and tension.
- C. Start unit according to manufacturer's written instructions.
  - 1. Complete startup sheets and attach copy with Contractor's startup report.
  - 2. Inspect and record performance of interlocks and protective devices; verify sequences.
  - 3. Operate unit for run-in period recommended by manufacturer.
  - 4. Perform the following operations for both minimum and maximum firing, and adjust burner for peak efficiency:
    - a. Measure gas pressure at manifold.
    - b. Measure combustion-air temperature at inlet to combustion chamber.
    - c. Measure supply-air temperature and volume when burner is at maximum firing rate and when burner is off. Calculate useful heat to supply air.
  - 5. Calibrate thermostats.

#### PACKAGED, INDIRECT-FIRED, OUTDOOR, MAKEUP-AIR UNITS 237423.16 - 11

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 6. Adjust and inspect high-temperature limits.
- 7. Inspect dampers, if any, for proper stroke and interlock with return-air dampers.
- 8. Inspect controls for correct sequencing of heating, mixing dampers, refrigeration, and normal and emergency shutdown.
- 9. Measure and record airflow. Plot fan volumes on fan curve.
- 10. Verify operation of remote panel, including pilot-operation and failure modes. Inspect the following:
  - a. High-limit heat.
  - b. Alarms.
- 11. After startup and performance testing, change filters, verify bearing lubrication, and adjust belt tension.
- 12. Verify drain-pan performance.
- 13. Verify outdoor-air damper operation.

## 3.6 ADJUSTING

- A. Adjust initial temperature set points.
- B. Set field-adjustable switches and circuit-breaker trip ranges as indicated.
- C. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

# 3.7 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain heating and ventilating units.

END OF SECTION 237423.16

# SECTION 260500 - COMMON WORK RESULTS FOR ELECTRICAL

# PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Electrical equipment coordination and installation.
  - 2. Sleeves for raceways and cables.
  - 3. Fire Rated Sleeves for cables.
  - 4. Grout.
  - 5. Common electrical installation requirements.
  - 6. Utility company coordination requirements.

# 1.3 DEFINITIONS

- A. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- B. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.
- C. "Provide": Furnish and install, complete and ready for the intended use.

#### 1.4 ACTION SUBMITTALS

A. Product Data: For Fire Rated Sleeves for cables.

## 1.5 COORDINATION

- A. Trade Coordination: Include physical characteristics, electrical characteristics, device layout plans, wiring diagrams, and connections as required per Division 26, Electrical Coordination Documents. For equipment with electrical connections, furnish copy of approved submittal for inclusion in Division 26, Electrical submittal.
- B. Location of electrical outlets and equipment:

#### COMMON WORK RESULTS FOR ELECTRICAL

- 1. Location of electrical outlets and equipment shown on electrical drawings are diagrammatic. Unless indicated otherwise do not use electrical drawings to locate electrical outlets and equipment.
- 2. Luminaires and outlets:
  - a. Ceiling mounted luminaires and outlets: use architectural reflected ceiling plans and details to determine location unless indicated otherwise.
  - b. Wall mounted luminaires and outlets:
    - 1) Use architectural elevation and section drawings to determine location unless indicated otherwise.
    - 2) Where architectural elevation and section drawings do not indicate location of wall outlets then locate the outlet within 12 inches of location shown on electrical drawings considering field conditions.
    - 3) Coordinate location with consideration of owner provided equipment such as wall mounted televisions, white boards, furniture, cabinets and the like.
  - c. Floor mounted outlets: use architectural drawings to determine location unless indicated otherwise. If not clearly indicated, then send request for information to Architect.
  - d. Cabinet mounted luminaires and outlets: use cabinet details and shop drawings to determine location unless indicated otherwise.
  - e. Exterior luminaire poles and bollards: use locations indicated on civil plans and landscape plans unless indicated otherwise
  - f. Landscape luminaires: use locations indicated on landscape drawings unless indicated otherwise.
  - g. Kitchen Equipment outlets: use location and mounting height indicated on kitchen drawings unless indicated otherwise.
- 3. Electrical equipment: Utilize approved manufacturer's shop drawing dimensions to determine location of equipment in space. Comply with NEC 110.26 access, working space and dedicated equipment space requirements. Maintain manufacturer requirements for maintenance access.
- 4. Electrical handholes and manholes: use location shown on civil plans unless indicated otherwise.
- 5. Outdoor Electrical equipment: use location shown on civil plans unless indicated otherwise.
- C. Electrical connections to equipment supplied by owner or other trades:
  - 1. Prior to procurement of electrical equipment and field work coordinate with shop drawings and/or manufacturer's installation instructions the actual electrical characteristics of the equipment to be connected.
  - 2. Notify engineer of significant deviations or conflicts between the shop drawings and/or the manufacturer's installation instructions and information in the contract documents.
- D. Coordinate arrangement, mounting, and support of electrical equipment:
  - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.

COMMON WORK RESULTS FOR ELECTRICAL

- 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
- 3. To allow right of way for piping and conduit installed at required slope so connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
- E. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- F. Coordinate location of access panels and doors for electrical items that are behind finished surfaces or otherwise concealed. Access doors and panels are specified in Division 08 Section "Access Doors and Frames."
- G. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."
- H. Coordinate and install wiring for appliances and systems furnished under other specification Divisions or furnished by the Owner. Install electrical wiring in accordance with manufacturer's instructions.:
  - 1. Kitchen equipment including walk-in freezer and coolers.
  - 2. Electric water coolers.
  - 3. Owner provided equipment

# 1.6 PERMITS AND FEES

A. Obtain and pay all fees for permits, licensing, and inspections applicable to work of Division 26, 27, and 28.

# 1.7 QUALITY ASSURANCE

- A. Regulatory Requirements: Install work and materials to conform with local, State and Federal codes, and other applicable laws and regulations.
- B. Drawings are intended to be diagrammatic and reflect the Basis of Design manufacturer's equipment. Drawings are not intended to show every item in its exact location, or details of equipment or proposed systems layout. Verify actual dimensions of systems (i.e. distribution equipment, duct banks, light fixtures, etc.) and equipment proposed to assure that systems and equipment will ft in available space. Contractor is responsible for design and construction costs incurred for equipment other than Basis of Design, including, but not limited to, architectural, structural, electrical, HVAC, fire sprinkler, and plumbing systems.
- C. Manufacturer's Instructions: Follow manufacturer's written instructions. If in conflict with Contract Documents, obtain clarification. Notify Engineer/Architect, in writing, before starting work.

- D. Items shown on Drawings are not necessarily included in Specifications or vice versa. Confirm requirements in all Contract Documents. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- E. Provide Qualified Personnel that are thoroughly knowledgeable of applicable codes related to electrical systems to perform the electrical work. Installations shall be performed by skilled electrical tradesmen fully aware of the latest techniques, practices, and standards of the industry. Refer to N.E.C. Article 100-Definitions, Qualified Person.
- F. Install electrical equipment and components in a neat and workmanlike manner in accordance with recognized practices and industry standards. Refer to N.E.C.110-12. Haphazard or poor installation practice will be cause for rejection of the work.

# PART 2 - PRODUCTS

# 2.1 SUBSTITUTION LIMITATIONS FOR ELECTRICAL EQUIPMENT

- A. Substitution requests for electrical equipment will be entertained under the following conditions:
  - 1. Substitution requests may be submitted for consideration if accompanied by value analysis data indicating that substitution will comply with Project performance requirements while significantly increasing value for Owner throughout life of facility.
  - 2. Substitution requests may be submitted for consideration concurrently with submission of power system study reports when those reports indicate that substitution is necessary for safety of maintenance personnel and facility occupants.
- B. Substitution and Variation from Basis of Design:
  - 1. The Basis of Design designated product establishes the qualities and characteristics for the evaluation of any comparable products by other listed acceptable manufacturers if included in this Specification or included in an approved Substitution Request as judged by the Design Professional.
  - 2. Proposed substitutions: If substitutions are proposed, it is the responsibility of parties concerned, involved in, and furnishing the substitute and/or equivalent equipment to verify and compare the characteristics and requirements of that furnished to that specified and/or shown. If greater capacity and/or more materials and/or more labor is required for the rough-in, circuitry or connections than for the item specified and provided for, then provide compensation for additional charges required for the proper rough-in, circuitry and connections for the equipment being furnished. No additional charges above the Base Bid, including resulting charges for work performed under other Divisions, will be allowed for such revisions. Coordinate with the requirements of "Submittals". For any product marked "or approved equivalent", a substitution request must be submitted to Engineer for approval prior to purchase, delivery, or installation.

# 2.2 SLEEVES FOR RACEWAYS AND CABLES

- A. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral water stop, unless otherwise indicated.
- B. Sleeves for Rectangular Openings: Galvanized sheet steel.
  - 1. Minimum Metal Thickness:
    - a. For sleeve cross-section rectangle perimeter less than 50 inches (1270 mm) and no side more than 16 inches (400 mm), thickness shall be 0.052 inch (1.3 mm).
    - b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches (1270 mm) and 1 or more sides equal to, or more than, 16 inches (400 mm), thickness shall be 0.138 inch (3.5 mm).
- C. EMT: Electrical Metallic Tubing.
- D. PVC: Schedule 40 or 80.

# 2.3 FIRE RATED SLEEVES FOR CABLES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. 3M.
  - 2. Hilti.
  - 3. Specified Technologies, Inc (STI).
  - 4. Wiremold.
- B. Factory assembled rectangular steel pathway containing an intumescent insert material that adjusts automatically to cable addition or subtraction.
- C. Sleeve shall have an F Rating equal to or greater than the rating of the wall in which the sleeve is installed.
- D. Sleeve shall be UL listed and bear the UL Classification marking.
- E. Sleeve shall be tested in accordance with ASTM E814 (ANSI/UL1479).
- F. Provide square wall plate kits for single sleeve applications. Provide multi-gang wall/floor plate kits for ganged applications.
- G. Subject to compatibility with requirements and field conditions, i.e. sleeve size, wall thickness, etc., acceptable products include the following:
  - 1. 3M Fire Barrier Pass-Through Devices.
  - 2. Hilti Speed Sleeves.
  - 3. Specified Technologies Inc. EZ-Path Fire Rated Pathway (series 33).
  - 4. Wiremold Flamestopper FS4 Series.

COMMON WORK RESULTS FOR ELECTRICAL

260500 - 5

# 2.4 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

## PART 3 - EXECUTION

# 3.1 INSTALLATION OF ELECTRICAL WORK

- A. Unless more stringent requirements are specified in the Contract Documents or manufacturers' written instructions, comply with NFPA 70 and NECA NEIS 1 for installation of Work specified in Division 26. Consult Architect for resolution of conflicting requirements.
- B. Comply with NECA 1.
- C. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- D. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- E. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electrical equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- F. Right of Way: Give to piping systems installed at a required slope.

## 3.2 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Electrical penetrations occur when raceways, cables, wireways, cable trays, or busways penetrate concrete slabs, concrete, masonry and gypsum board walls, or fire-rated floor and wall assemblies.
- B. Sleeves are required where cables (not in raceway) penetrate walls or floors. Sleeves are not required where raceways penetrate walls, except where raceways penetrate exterior walls/foundations below grade.
- C. Concrete Slabs and Walls: Install sleeves during erection of slabs and walls.
- D. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- E. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.

COMMON WORK RESULTS FOR ELECTRICAL

- F. Provide insulated bushings on EMT sleeves for cable not in conduit. Bushings shall be plenum rated where installed in a plenum.
- G. Extend sleeves installed in floors 4 inches (100 mm) above finished floor level unless noted otherwise.
- H. Size pipe sleeves to provide 1/4-inch (6.4-mm) annular clear space between sleeve and raceway or cable, unless indicated otherwise.
- I. Seal space outside of sleeves with grout for penetrations of concrete and masonry.
  - 1. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
- J. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants."
- K. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping."
- L. Underground, Exterior-Wall Penetrations: Install cast-iron pipe or PVC, schedule 40 or 80, sleeves. Size sleeves to allow for 1-inch (25-mm) annular clear space between raceway and sleeve. Cut sleeves to length for mounting flush with both surfaces of walls.
- M. Fire Rated Sleeves for cables: Fabricate openings in wall or floor assemblies per manufacturer's recommendations.

# 3.3 SLEEVE APPLICATION

- A. Sleeves for cables not in conduit:
  - 1. Through Non-Rated Interior Walls: EMT sleeves.
  - 2. Through Non-Rated Floors: EMT sleeves.
  - 3. Through Fire Rated Interior Walls: Fire Rated Sleeves for cables.
  - 4. Through Fire Rated Floors: Fire Rated Sleeves for cables.
- B. Sleeves for conduits:
  - 1. Through Exterior Walls Below Grade: Refer to details on structural Drawings. Absent any such details provide cast iron pipe or PVC, Schedule 40 or 80, sleeve two trade sizes larger than the conduit.
- C. Sleeves for Cable Trays:
  - 1. Through Non-Rated Interior Walls: Rectangular galvanized sheet metal opening.

COMMON WORK RESULTS FOR ELECTRICAL

260500 - 7

2. Through Fire Rated Walls: Stop cable tray 6 inches maximum for each side of wall and provide multiple fire rated sleeves for cables with combined allowable area for cable equal to the capacity of the cable tray unless noted otherwise.

# 3.4 FIRESTOPPING

A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for electrical installations to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 07 Section "Penetration Firestopping."

END OF SECTION 260500

COMMON WORK RESULTS FOR ELECTRICAL

# SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. Section Includes:
  - 1. Building wires and cables rated 600 V and less.
  - 2. Connectors, splices, and terminations rated 600 V and less.

#### 1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

# PART 2 - PRODUCTS

#### 2.1 CONDUCTORS AND CABLES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Alpha Wire.
  - 2. Belden Inc.
  - 3. Encore Wire Corporation.
  - 4. General Cable Technologies Corporation.
  - 5. Southwire Incorporated.
- B. Aluminum and Copper Conductors: Comply with NEMA WC 70/ICEA S-95-658.
- C. Conductor Insulation: Comply with NEMA WC 70/ICEA S-95-658 for Type THHN-2-THWN-2, Type XHHW-2.
- D. Multiconductor Cable: Comply with NEMA WC 70/ICEA S-95-658 for metal-clad cable, Type MC with ground wire.

LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

260519 - 1
# 2.2 CONNECTORS AND SPLICES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. AFC Cable Systems, Inc.
  - 2. Gardner Bender.
  - 3. Hubbell Power Systems, Inc.
  - 4. Ideal Industries, Inc.
  - 5. Ilsco; a branch of Bardes Corporation.
  - 6. NSi Industries LLC.
  - 7. O-Z/Gedney; a brand of the EGS Electrical Group.
  - 8. 3M; Electrical Markets Division.
- B. Description: Factory-fabricated spring connectors wire nuts and splices of size, ampacity rating, material, type, and class for application and service indicated.
- C. Quick push-in wire connectors are prohibited.

# 2.3 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.

# PART 3 - EXECUTION

# 3.1 CONDUCTOR MATERIAL APPLICATIONS

- A. Feeders: Copper for feeders smaller than No. 4 AWG; aluminum for feeders No. 4 AWG and larger. All feeder conductors shall be copper up to 100Amps and copper or compact aluminum above 100Amps; aluminum conductors shall not be allowed for branch circuit wiring.
- B. Branch Circuits: Copper. Stranded.

# 3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

- A. Service Entrance: Type XHHW-2, single conductors in raceway.
- B. Exposed Feeders: Type THHN-2-THWN-2, single conductors in raceway.
- C. Feeders Concealed in Ceilings, Walls, Partitions, and Crawlspaces: Type THHN-2-THWN-2, single conductors in raceway.

# LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES 260519 - 2

- D. Feeders Concealed in Concrete, below Slabs-on-Grade, and Underground: Type XHHW-2, single conductors in raceway.
- E. Exposed Branch Circuits, Including in Crawlspaces: Type THHN-2-THWN-2, single conductors in raceway.
- F. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN-2-THWN-2, single conductors in raceway, Metal-clad cable, Type MC. MC Cable shall not be used for multi-wire branch circuits, nor in any location in the kitchen environment. MC cable shall not be used in walls under the exterior windows or interior windows.
- G. Branch Circuits Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN-THWN, single conductors in raceway.
- H. Dedicated neutrals will be provided in multi-wire branch circuit runs.

# 3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Conceal cables in finished walls, ceilings, and floors unless otherwise indicated.
- B. Complete raceway installation between conductor and cable termination points according to Section 260533 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.
- C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- F. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."
- G. Provide an individual neutral conductor for each single hot (phase) wire. Do not share neutrals.
- H. Multiconductor cable: Rigid raceways must be used between panelboards and rooms, and must terminate in the ceiling space at a j-box. Multiconductor cable may only be used from this j-box to devices.

#### 3.4 CONNECTIONS

A. Tighten electrical connectors and terminals according to manufacturer's published torquetightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.

#### LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES 260519 - 3

- B. Make splices, terminations, and taps that are compatible with conductor material.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inches (150 mm) of slack.

### 3.5 IDENTIFICATION

- A. Identify and color-code conductors and cables according to Section 260553 "Identification for Electrical Systems."
- B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

#### 3.6 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

#### 3.7 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Section 260500 "Common work results for Electrical."

END OF SECTION 260519

# SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Hangers and supports for electrical equipment and systems.
  - 2. Construction requirements for concrete bases.

#### 1.3 DEFINITIONS

- A. EMT: Electrical metallic tubing.
- B. RMC: Rigid metal conduit.

# 1.4 PERFORMANCE REQUIREMENTS

- A. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
- B. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed for this Project, with a minimum structural safety factor of five times the applied force.

## 1.5 ACTION SUBMITTALS

- A. Product Data: For the following:
  - 1. Steel slotted support systems.
- B. Shop Drawings: Show fabrication and installation details and include calculations for the following:
  - 1. Trapeze hangers. Include Product Data for components.
  - 2. Steel slotted channel systems. Include Product Data for components.
  - 3. Equipment supports.

# HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

## 1.6 QUALITY ASSURANCE

A. Comply with NFPA 70.

## 1.7 COORDINATION

A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified together with concrete Specifications.

#### PART 2 - PRODUCTS

#### 2.1 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Comply with MFMA-4, factory-fabricated components for field assembly.
  - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Allied Tube & Conduit.
    - b. Cooper B-Line, Inc.; a division of Cooper Industries.
    - c. ERICO International Corporation.
    - d. GS Metals Corp.
    - e. Thomas & Betts Corporation.
    - f. Unistrut; Tyco International, Ltd.
    - g. Wesanco, Inc.
  - 2. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
  - 3. Channel Dimensions: Selected for applicable load criteria.
- B. Raceway and Cable Supports: As described in NECA 1 and NECA 101.
- C. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- D. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- E. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
  - 1. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.

#### HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

- a. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1) Cooper B-Line, Inc.; a division of Cooper Industries.
  - 2) Empire Tool and Manufacturing Co., Inc.
  - 3) Hilti Inc.
  - 4) MKT Fastening, LLC.
- 2. Concrete Inserts: Steel or malleable-iron, slotted support system units similar to MSS Type 18; complying with MFMA-4 or MSS SP-58.
- 3. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.
- 4. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
- 5. Toggle Bolts: All-steel springhead type.
- 6. Hanger Rods: Threaded steel.

# PART 3 - EXECUTION

# 3.1 APPLICATION

- A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems except if requirements in this Section are stricter.
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMT and RMC as required by NFPA 70 unless noted otherwise. Minimum rod size shall be 1/4 inch (6 mm) in diameter.
- C. Conduits shall be supported within 18" of outlets, boxes, panels, cabinets. Maximum distance between supports is not to exceed 5'-0". Prevent movement and / or sag of junction boxes, pull boxes, or other conduit terminating housings located above suspended ceilings by suspending them from appropriate supports or roof structure.
- D. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
  - 1. Secure raceways and cables to these supports with two-bolt conduit clamps.

# 3.2 SUPPORT INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this Article.
- B. Raceway Support Methods: In addition to methods described in NECA 1, EMT may be supported by openings through structure members, as permitted in NFPA 70.

HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

- C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb (90 kg).
- D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
  - 1. To Wood: Fasten with lag screws or through bolts.
  - 2. To New Concrete: Bolt to concrete inserts.
  - 3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
  - 4. To Existing Concrete: Expansion anchor fasteners.
  - 5. To Steel: Welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts. To Light Steel: Sheet metal screws.
  - 6. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate by means that meet seismic-restraint strength and anchorage requirements.
- E. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.

#### 3.3 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
  - 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils (0.05 mm).
- B. Touchup: Comply with requirements in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting" for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 260529

HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

# SECTION 260533 - RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

#### PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Metal conduits, tubing, and fittings.
  - 2. Nonmetal conduits, tubing, and fittings.
  - 3. Metal wireways and auxiliary gutters.
  - 4. Surface raceways.
  - 5. Boxes, enclosures, and cabinets.
  - 6. Handholes and boxes for exterior underground cabling.

# 1.3 DEFINITIONS

- A. GRC: Galvanized rigid steel conduit.
- B. IMC: Intermediate metal conduit.
- C. EMT: Electrical metallic tubing.
- D. FMC: Flexible metal conduit.
- E. LFMC: Liquidtight flexible metallic conduit.
- F. PVC: Rigid Polyvinyl Chloride conduit.
- G. RNC: Rigid Nonmetalic conduit.

#### 1.4 ACTION SUBMITTALS

A. Product Data: For surface raceways, wireways and fittings, hinged-cover enclosures, and cabinets.

# PART 2 - PRODUCTS

## 2.1 METAL CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. AFC Cable Systems, Inc.
  - 2. Allied Tube & Conduit; a Tyco International Ltd. Co.
  - 3. O-Z/Gedney; a brand of EGS Electrical Group.
  - 4. Southwire Company.
  - 5. Thomas & Betts Corporation.
  - 6. Western Tube and Conduit Corporation.
- B. Listing and Labeling: Metal conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. GRC: Comply with ANSI C80.1 and UL 6.
- D. IMC: Comply with ANSI C80.6 and UL 1242.
- E. EMT: Comply with ANSI C80.3 and UL 797.
- F. FMC: Comply with UL 1; zinc-coated steel.
- G. LFMC: Flexible steel conduit with PVC jacket and complying with UL 360.
- H. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
  - 1. Fittings for EMT:
    - a. Material: Steel.
    - b. Type: Setscrew with insulated throat.
  - 2. Expansion Fittings: PVC or steel to match conduit type, complying with UL 651, rated for environmental conditions where installed, and including flexible external bonding jumper.
- I. Joint Compound for IMC, GRC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

#### 2.2 NONMETALLIC CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. AFC Cable Systems, Inc.

- 2. Anamet Electrical, Inc.
- 3. Arnco Corporation.
- 4. CANTEX Inc.
- 5. CertainTeed Corp.
- 6. Condux International, Inc.
- 7. Electri-Flex Company.
- 8. Kraloy.
- 9. Lamson & Sessions; Carlon Electrical Products.
- 10. Niedax-Kleinhuis USA, Inc.
- 11. RACO; a Hubbell company.
- 12. Thomas & Betts Corporation.
- B. Listing and Labeling: Nonmetallic conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. RNC: Type EPC-40-PVC, complying with NEMA TC 2 and UL 651 unless otherwise indicated.
- D. Fittings for RNC: Comply with NEMA TC 3; match to conduit type and material.
- E. Solvent cements and adhesive primers shall have a VOC content of 510 and 550 g/L or less, respectively, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

#### 2.3 METAL WIREWAYS AND AUXILIARY GUTTERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Cooper B-Line, Inc.
  - 2. Hoffman; a Pentair company.
  - 3. Square D; a brand of Schneider Electric.
- B. Description: Sheet metal, complying with NEMA 250, Type 1 unless otherwise indicated, and sized according to NFPA 70.
  - 1. Metal wireways installed outdoors shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

#### 2.4 SURFACE RACEWAYS

- A. Surface Metal Raceways: Galvanized steel with snap-on covers complying with UL 5. Manufacturer's standard enamel finish in color selected by Architect.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. Panduit Corp.
- b. Thomas & Betts Corporation.
- c. Wiremold / Legrand.

# 2.5 BOXES, ENCLOSURES, AND CABINETS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Adalet.
  - 2. Cooper Technologies Company; Cooper Crouse-Hinds.
  - 3. Hoffman; a Pentair company.
  - 4. Hubbell Incorporated; Killark Division.
  - 5. Mono-Systems, Inc.
  - 6. O-Z/Gedney; a brand of EGS Electrical Group.
  - 7. RACO; a Hubbell Company.
  - 8. Thomas & Betts Corporation.
- B. General Requirements for Boxes, Enclosures, and Cabinets: Boxes, enclosures, and cabinets installed in wet locations shall be listed for use in wet locations.
- C. Sheet Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- D. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, ferrous alloy, Type FD, with gasketed cover.
- E. Luminaire Outlet Boxes: Nonadjustable, designed for attachment of luminaire weighing 50 lb (23 kg). Outlet boxes designed for attachment of luminaires weighing more than 50 lb (23 kg) shall be listed and marked for the maximum allowable weight.
- F. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- G. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, cast aluminum with gasketed cover.
- H. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- I. Device Box Dimensions: 4 inches square by 1-1/2 inches deep.
- J. Signal System Device Box Dimensions: 4 inches square by 2-1/8 inches deep.
- K. Floor Boxes: Provide floor boxes locations per electrical and communications drawings. All floor boxes shall be code-approved metal construction, with gasketed metal covers, flush with floor grade (even in use). Manufacturers: Wiremold Omnibox Series or Hubbell with adjustable collars and frames, or approved by Beaverton School District Representative. Minimum floor box requirements: 3 7/16" deep with 1" factory knockouts.

- L. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, Type 1 with continuous-hinge cover with flush latch unless otherwise indicated.
  - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
  - 2. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.

# PART 3 - EXECUTION

# 3.1 RACEWAY APPLICATION

- A. Outdoors: Apply raceway products as specified below unless otherwise indicated:
  - 1. Exposed Rooftop Conduit: IMC.
  - 2. Concealed Conduit, Aboveground: EMT.
  - 3. Underground Conduit: Type EPC-40-PVC, direct buried.
  - 4. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC, no more than 6 feet.
  - 5. Boxes and Enclosures, Aboveground: NEMA 250, Type 3R.
- B. Indoors: Apply raceway products as specified below unless otherwise indicated:
  - 1. Exposed, Not Subject to Physical Damage: EMT.
  - 2. Concealed in Ceilings and Interior Walls and Partitions: EMT.
  - 3. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations. Sealtite shall be used where flexible conduit connections are required and at connections to all motorized equipment and motors.
  - 4. Damp or Wet Locations: IMC.
  - 5. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4 stainless steel in institutional and commercial kitchens and damp or wet locations.
- C. Minimum Raceway Size: 3/4-inch (21-mm) trade size.
- D. Raceway Fittings: Compatible with raceways and suitable for use and location.
  - 1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
  - 2. EMT: Use setscrew, steel fittings with insulated throat. Comply with NEMA FB 2.10.
  - 3. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.
  - 4. All heavy wall conduits shall have two locknuts and a bushing at each termination outlet box, junction box, except where terminated in a threaded hub.
- E. Install surface raceways only where indicated on Drawings. Use metallic raceway.
- F. Do not install nonmetallic conduit where ambient temperature exceeds 120 deg F (49 deg C).
- G. Exposed low voltage cables are not allowed to be supported from electrical conduit system.

H. Conduit bodies are allowed for feeders and branch circuits less than or equal to 100 amps and for signal cabling not related to data communications.

# 3.2 INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except where requirements on Drawings or in this article are stricter.
- B. Keep raceways at least 6 inches (150 mm) away from parallel runs of flues and steam or hotwater pipes. Install horizontal raceway runs above water and steam piping.
- C. Complete raceway installation before starting conductor installation.
- D. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for hangers and supports.
- E. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- F. Install no more than the equivalent of three 90-degree bends in any conduit run except for control wiring and communications conduits, for which fewer bends are allowed. Support within 12 inches (300 mm) of changes in direction. Conduit bends shall be made with appropriate tools of proper size; radius of bends shall be at least six times the diameter of the conduit.
- G. Conceal conduit and EMT within finished walls, ceilings, and floors unless otherwise indicated.
- H. Support conduit within 12 inches (300 mm) of enclosures to which attached.
- I. Bushings and connectors shall be plastic insulated, lined, 105degC rated. A bushing shall be used where conduit enters a panelbox.
- J. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.
- K. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors including conductors smaller than No. 4 AWG.
- L. Cut conduit perpendicular to the length. For conduits 2-inch (53-mm) trade size and larger, use roll cutter or a guide to make cut straight and perpendicular to the length.
- M. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb (90-kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of pull wire. Cap underground raceways designated as spare above grade alongside raceways in use.
- N. Surface Raceways:
  - 1. Install surface raceway with a minimum 2-inch (50-mm) radius control at bend points.

#### RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

- 2. Secure surface raceway with screws or other anchor-type devices at intervals not exceeding 48 inches (1200 mm) and with no less than two supports per straight raceway section. Support surface raceway according to manufacturer's written instructions. Tape and glue are not acceptable support methods.
- O. Install devices to seal raceway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all raceways at the following points:
  - 1. Where an underground service raceway enters a building or structure.
  - 2. Where otherwise required by NFPA 70.
- P. Comply with manufacturer's written instructions for solvent welding RNC and fittings.
- Q. Expansion-Joint Fittings:
  - 1. Install expansion fittings at all locations where conduits cross building or structure expansion joints.
  - 2. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.
  - 3. Fittings shall be type "AX" or "TX" as made by O-Z Electric Company, or equal. Provide copper bonding jumper at each expansion fitting.
- R. Flexible Conduit Connections: Comply with NEMA RV 3. Use a maximum of 72 inches (1830 mm) of flexible conduit for recessed and semirecessed luminaires, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.
  - 1. Use LFMC in damp or wet locations subject to severe physical damage.
  - 2. Use LFMC in damp or wet locations not subject to severe physical damage.
- S. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to center of box unless otherwise indicated.
- T. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surfaces to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box.
- U. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
- V. Locate boxes so that cover or plate will not span different building finishes.
- W. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.
- X. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.

Y. Set metal floor boxes level and flush with finished floor surface.

#### 3.3 INSTALLATION OF UNDERGROUND HANDHOLES AND BOXES

- A. Install handholes and boxes level and plumb and with orientation and depth coordinated with connecting conduits to minimize bends and deflections required for proper entrances.
- B. Install handholes and boxes as required to avoid exceeding maximum allowed bends for raceways.
- C. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1/2-inch (12.5-mm) sieve to No. 4 (4.75-mm) sieve and compacted to same density as adjacent undisturbed earth.
- D. Elevation: In paved areas, set so cover surface will be flush with finished grade. Set covers of other enclosures 1 inch (25 mm) above finished grade.
- E. Field-cut openings for conduits according to enclosure manufacturer's written instructions. Cut wall of enclosure with a tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.

#### 3.4 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

#### 3.5 FIRESTOPPING

A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Comply with requirements in Section 260500 "Common Work Results for Electrical."

END OF SECTION 260533

# SECTION 260553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

# 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

# 1.2 SUMMARY

- A. Section Includes:
  - 1. Identification for conductors.
  - 2. Underground-line warning tape.
  - 3. Warning labels and signs.
  - 4. Equipment identification labels.
  - 5. Arc Flash label per NEC.

#### 1.3 ACTION SUBMITTALS

A. Product Data: For each electrical identification product indicated.

# 1.4 QUALITY ASSURANCE

A. Comply with NFPA 70.

#### 1.5 COORDINATION

- A. Coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual; and with those required by codes, standards, and 29 CFR 1910.145. Use consistent designations throughout Project.
- B. Labeling is to be reviewed and approved by the Facilities Project Manager & Electrical Supervisor.
- C. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- D. Coordinate installation of identifying devices with location of access panels and doors.
- E. Install identifying devices before installing acoustical ceilings and similar concealment.

#### IDENTIFICATION FOR ELECTRICAL SYSTEMS

F. Panels require labeling of necessary PPE with potential hazards as a result of Arc Flash Hazard Analysis. The Arc Flash Hazard Analysis shall be performed by the Electrical Contractor.

# PART 2 - PRODUCTS

## 2.1 CONDUCTOR IDENTIFICATION MATERIALS

- A. Color-Coding Conductor Tape: Colored, self-adhesive vinyl tape not less than 3 mils (0.08 mm) thick by 1 to 2 inches (25 to 50 mm) wide.
- 2.2 WARNING LABELS AND SIGNS
  - A. Comply with NFPA 70 and 29 CFR 1910.145.
  - B. Self-Adhesive Warning Labels: Factory-printed, multicolor, pressure-sensitive adhesive labels, configured for display on front cover, door, or other access to equipment unless otherwise indicated.
  - C. Baked-Enamel Warning Signs:
    - 1. Preprinted aluminum signs, punched or drilled for fasteners, with colors, legend, and size required for application.
    - 2. 1/4-inch (6.4-mm) grommets in corners for mounting.
    - 3. Nominal size, 7 by 10 inches (180 by 250 mm).
  - D. Warning label and sign shall include, but are not limited to, the following:
    - 1. Multiple Power Source Warning: "DANGER ELECTRICAL SHOCK HAZARD EQUIPMENT HAS MULTIPLE POWER SOURCES."

# 2.3 EQUIPMENT IDENTIFICATION LABELS

- A. Normal Power Equipment: Self-Adhesive, Engraved, Laminated Acrylic or Melamine Label: Adhesive backed, with white letters on a black background. Minimum letter height shall be 3/8 inch (10 mm).
- B. Emergency Power Equipment: Self-Adhesive, Engraved, Laminated Acrylic or Melamine Label: Adhesive backed, with white letters on a red background. Minimum letter height shall be 3/8 inch (10 mm).

PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Verify identity of each item before installing identification products.
- B. If banks of switching are installed that control various systems (i.e. lighting, AV, and projection screen, etc.) or various spaces (i.e. classroom and corridor, etc.) labeling with 1/8" black letters indicating function of each switch is required.
- C. Location: Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.
- D. Self-Adhesive Identification Products: Clean surfaces before application, using materials and methods recommended by manufacturer of identification device.
- E. Attach signs and plastic labels that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.

## 3.2 IDENTIFICATION SCHEDULE

- A. Accessible Raceways and Cables within Buildings: Identify the covers of each junction and pull box of the following systems with self-adhesive vinyl labels with the wiring system legend and system voltage. System legends shall be as follows:
  - 1. Emergency Power: White letters on a red background.
  - 2. Power: White letters on a black background.
- B. Power-Circuit Conductor Identification, 600 V or Less: For conductors in vaults, pull and junction boxes, manholes, and handholes, use color-coding conductor tape to identify the phase.
  - 1. Color-Coding for Phase and Voltage Level Identification, 600 V or Less: Use colors listed below for ungrounded service, feeder, and branch-circuit conductors.
    - a. Color shall be factory applied or field applied for sizes larger than No. 8 AWG, if authorities having jurisdiction permit.
    - b. Colors for 208/120-V Circuits:
      - 1) Phase A: Black.
      - 2) Phase B: Red.
      - 3) Phase C: Blue.
      - 4) Neutral: White.
      - 5) Ground: Green.
    - c. Colors for 480/277-V Circuits:
      - 1) Phase A: Brown.
      - 2) Phase B: Orange.

# IDENTIFICATION FOR ELECTRICAL SYSTEMS

- 3) Phase C: Yellow.
- 4) Neutral: Gray.
- 5) Ground: Green.
- d. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum distance of 6 inches (150 mm) from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.
- C. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and the Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification. Install engraved label on the inside of flush panels, visible when the door is open.
  - 1. Labeling Instructions:
    - a. Indoor Equipment: Engraved, laminated acrylic or melamine label, black with white core for normal power and red with white letters for emergency power. Unless otherwise indicated, provide a single line of text with 1/2-inch- (13-mm-) high letters on 1-1/2-inch- (38-mm-) high label; where two lines of text are required, use labels 2 inches (50 mm) high.
    - b. Outdoor Equipment: Engraved, laminated acrylic or melamine label.
  - 2. Equipment to Be Engraved Labeled:
    - a. Panelboards: Typewritten directory of circuits in the location provided by panelboard manufacturer, with separate columns for odd and even numbers, using final building room numbers and identifications. Panelboard identification shall be engraved, laminated acrylic or melamine label. Panelboard label shall identify panel, voltage, and electrical source. Each electrical panel ID should start with number where "2" will indicate 208/120V system and "4" will indicate 480/277V system.
    - b. Enclosures and electrical cabinets.
    - c. Access doors and panels for concealed electrical items.
    - d. Emergency system boxes and enclosures.
    - e. Enclosed switches.
    - f. Enclosed circuit breakers.
    - g. Enclosed controllers.
    - h. Variable-speed controllers.
    - i. Push-button stations.
    - j. Power transfer equipment.
    - k. Contactors.
    - 1. Remote-controlled switches, dimmer modules, and control devices.
    - m. Monitoring and control equipment.

IDENTIFICATION FOR ELECTRICAL SYSTEMS

- 3. On the cover of junction and pull boxes, use label, or legibly write with indelible ink, the panel number, circuit number and voltage for each box.
- 4. On the back of wiring devices including power receptacles and switches, use label, or legibly write with indelible ink, the panel number, circuit number and voltage for each wiring device.
- 5. Contractor to supply (2) laminated one-line diagrams showing disconnects with Record Drawings for posting in main electrical room and emergency room.

END OF SECTION 260553

IDENTIFICATION FOR ELECTRICAL SYSTEMS

## SECTION 262726 - WIRING DEVICES

#### PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Receptacles, receptacles with integral GFCI, and associated device plates.
  - 2. Tamper-resistant receptacles.
  - 3. Snap switches and wall-box dimmers.
  - 4. Wall-switch occupancy sensors.
  - 5. Key switch.
  - 6. Communications outlets.

# 1.3 DEFINITIONS

- A. EMI: Electromagnetic interference.
- B. GFCI: Ground-fault circuit interrupter.
- C. Pigtail: Short lead used to connect a device to a branch-circuit conductor.
- D. RFI: Radio-frequency interference.
- E. SPD: Surge protection device.
- F. UTP: Unshielded twisted pair.

# 1.4 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
  - 1. Receptacles for Owner-Furnished Equipment: Match plug configurations.
  - 2. Cord and Plug Sets: Match equipment requirements.

#### 1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

#### 1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For wiring devices to include in all manufacturers' packinglabel warnings and instruction manuals that include labeling conditions.

#### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Manufacturers' Names: Shortened versions (shown in parentheses) of the following manufacturers' names are used in other Part 2 articles:
  - 1. Hubbell Incorporated; Wiring Device-Kellems (Hubbell).
  - 2. Leviton Mfg. Company Inc. (Leviton).
  - 3. Pass & Seymour/Legrand (Pass & Seymour).
- B. Source Limitations: Obtain each type of wiring device and associated wall plate from single source from single manufacturer.

#### 2.2 GENERAL WIRING-DEVICE REQUIREMENTS

- A. Wiring Devices, Components, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.

## 2.3 STRAIGHT-BLADE RECEPTACLES

- A. Convenience Receptacles, 125 V, 20 A: Comply with NEMA WD 1, NEMA WD 6 Configuration 5-20R, UL 498, and FS W-C-596.
  - 1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Hubbell; HBL5351 (single), HBL5352 (duplex).
    - b. Leviton; 5891 (single), 5352 (duplex).
    - c. Pass & Seymour; 5361 (single), 5362 (duplex).

#### 2.4 GFCI RECEPTACLES

#### A. General Description:

- 1. Straight blade, non-feed-through type.
- 2. Comply with NEMA WD 1, NEMA WD 6, UL 498, UL 943 Class A, and FS W-C-596.
- 3. Include indicator light that shows when the GFCI has malfunctioned and no longer provides proper GFCI protection.
- B. Duplex GFCI Convenience Receptacles, 125 V, 20 A:
  - 1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Hubbell; GFR5352L.
    - b. Pass & Seymour; 2095.
    - c. Leviton; 7590.

# 2.5 TOGGLE SWITCHES

- A. Comply with NEMA WD 1, UL 20, and FS W-S-896.
- B. Switches, 120 V, 20 A:
  - 1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Single Pole:
      - 1) Hubbell; HBL1221.
      - 2) Leviton; 1221-2.
      - 3) Pass & Seymour; CSB20AC1.
    - b. Two Pole:
      - 1) Hubbell; HBL1222.
      - 2) Leviton; 1222-2.
      - 3) Pass & Seymour; CSB20AC2.
    - c. Three Way:
      - 1) Hubbell; HBL1223.
      - 2) Leviton; 1223-2.
      - 3) Pass & Seymour; CSB20AC3.
    - d. Four Way:
      - 1) Hubbell; HBL1224.
      - 2) Leviton; 1224-2.

- 3) Pass & Seymour; CSB20AC4.
- C. Key-Operated Switches, 120/277 V, 20 A:
  - 1. Products: Subject to compliance with requirements, provide the following:
    - a. Pass & Seymour; no substitution.
  - 2. Description: Momentary contact switch key for heavy-duty locking switch, 500K, with District-wide key standardization.

# 2.6 WALL PLATES

- A. Single and combination types shall match corresponding wiring devices.
  - 1. Plate-Securing Screws: Metal with head color to match plate finish.
  - 2. Material for Finished Spaces: Satin-finished type 302 stainless steel, beveled edge.
  - 3. Material for Unfinished Spaces: Galvanized steel.
  - 4. Material for Damp Locations: Thermoplastic with spring-loaded lift cover, and listed and labeled for use in wet and damp locations.

# 2.7 FINISHES

- A. Device Color:
  - 1. Wiring Devices Connected to Normal Power System Panelboards: Gray unless otherwise indicated or required by NFPA 70 or device listing.
  - 2. Wiring Devices Connected to Life Safety Generator Power Panelboards: Red.
  - 3. Wiring Devices Connected to Stand-By Generator Power Panelboards: Blue.

# PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Comply with NECA 1, including mounting heights listed in that standard, unless otherwise indicated.
- B. Coordination with Other Trades:
  - 1. Protect installed devices and their boxes. Do not place wall finish materials over device boxes and do not cut holes for boxes with routers that are guided by riding against outside of boxes.
  - 2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
- 4. Install wiring devices after all wall preparation, including painting, is complete.
- C. Conductors:
  - 1. Do not strip insulation from conductors until right before they are spliced or terminated on devices.
  - 2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
  - 3. The length of free conductors at outlets for devices shall meet provisions of NFPA 70, Article 300, without pigtails.
- D. Device Installation:
  - 1. Replace devices that have been in temporary use during construction and that were installed before building finishing operations were complete.
  - 2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.
  - 3. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
  - 4. Connect devices to branch circuits using pigtails that are not less than 6 inches (152 mm) in length.
  - 5. When there is a choice, use side wiring with binding-head screw terminals. Wrap solid conductor tightly clockwise, two-thirds to three-fourths of the way around terminal screw.
  - 6. Use a torque screwdriver when a torque is recommended or required by manufacturer.
  - 7. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.
  - 8. Tighten unused terminal screws on the device.
  - 9. When mounting into metal boxes, remove the fiber or plastic washers used to hold device-mounting screws in yokes, allowing metal-to-metal contact.
- E. Receptacle Orientation:
  - 1. Install ground pin of vertically mounted receptacles down, and on horizontally mounted receptacles to the right.
- F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.
- G. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

# 3.2 IDENTIFICATION

- A. Comply with Section 260553 "Identification for Electrical Systems."
- B. Identify each receptacle and switch. On the back of finish plate, use a label, or legibly write indelible ink, the panel number, circuit number and voltage for wiring device.

END OF SECTION 262726

SECTION 270000 - COMMUNICATIONS

## PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. Division 27 Communications governs the infrastructure for the low-voltage information transport systems, which include voice and data and their pathways.
- B. The Scope of Work covered by this document is to furnish and install the Structured Cabling Systems (SCS). This work will also provide the SCS for paging and video surveillance.
- C. Description of Work:
  - 1. Furnish and install materials for the communications infrastructure systems as specified herein and as shown on the Drawings. Upon completion, the systems shall be functioning in compliance with performance requirements specified.
  - 2. The cabling specified and shown on the Drawings is for complete, performance based, workable systems. Deviations from the cabling shown due to a particular manufacturer's requirements shall be made only with the written approval of the Architect and the Owner, and at no additional cost to the Owner.

#### 1.2 SECTION INCLUDES

- A. Related Documents, Codes, and Sections
- B. Abbreviations, Acronyms and Definitions
- C. Project Drawings
- D. Quality Assurance
- E. Submittal Requirements
- F. Additional Requirements

#### 1.3 RELATED DOCUMENTS AND CODES

- A. Comply with the referenced codes and standards and with the Contract Documents. Where conflicts occur, the more stringent shall apply.
- B. The latest versions, including addenda, as enforced by the local authority having jurisdiction of the following codes, associations, acts and agencies:

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

- 1. Federal Communications Commission (FCC).
- 2. National Fire Protection Association (NFPA), specifically:
  - a. NFPA 70, National Electrical Code<sup>®</sup> (*NEC*<sup>®</sup>)
  - b. NFPA 72, National Fire Alarm Code<sup>®</sup>
  - c. NFPA 76, Recommended Practice for the Fire Protection of Telecommunications Facilities
  - d. NFPA 101, Life Safety Code®
  - e. NFPA 262, Standard Method of Test for Flame Travel and Smoke of Wires and Cables for Use in Air-Handling Spaces
  - f. NFPA 780, Standard for the Installation of Lightning Protection Systems
  - g. NFPA 5000<sup>TM</sup>, Building Construction and Safety Code
- 3. National Electrical Safety Code (NESC)
- 4. Occupational Safety and Health Administration (OSHA)
- C. The following standards bodies:
  - 1. American National Standards Institute (ANSI)
  - 2. National Electrical Manufacturers Association (NEMA)
  - 3. Telecommunications Industries Association (TIA), specifically:
    - a. TIA TSB-125, Guidelines for Maintaining Optical Fiber Polarity through Reverse-Pair Positioning
    - b. TIA TSB-140, Additional Guidelines for Field-Testing Length, Loss and Polarity of Optical Fiber Cabling Systems
    - c. TIA-526-7, Measurement of Optical Power Loss of Installed Single-Mode Fiber Cable Plant – OFSTP-7
    - d. ANSI/TIA-568-C.2-2009, Balanced Twisted-Pair Telecommunications Cabling and Component Standard
    - e. ANSI/TIA-568-C.3, Optical Fiber Cabling Components Standard
    - f. ANSI/TIA-568.0-D-2015, Generic Telecommunications Cabling for Customer Premises
    - g. ANSI/TIA-568.1-D-2015 Commercial Building Telecommunications Infrastructure Standard
    - h. ANSI/TIA-569-D-2015, Telecommunications Pathways and Spaces
    - i. ANSI/TIA-598-C, Optical Fiber Cable Color Coding
    - j. ANSI/TIA-604.2-A, FOCIS 2—Fiber Optic Connector Intermateability Standard
    - k. ANSI/TIA-606, Administration Standard for Commercial Telecommunications Infrastructures
    - 1. ANSI/TIA/607-C, Commercial Building Grounding (Earthing) and Bonding Requirements for Telecommunications
    - m. ANSI/TIA-758-A, Customer-owned Outside Plant Telecommunications Infrastructure Standard
    - n. ANSI/TIA-854-A, Full Duplex Ethernet Specification for 1000 Mb/s (1000BASE-TX) Operating over Category 6 Balanced Twisted-Pair Cabling
    - o. ANSI/NECA/*Bicsi*<sup>®</sup> 568-2006, Standard for Installing Telecommunications Systems

# COMMUNICATIONS

# 4. Other Reference Materials

- a. ANSI/NECA/GICSI-568-2006, Standard, Installing Commercial Building Telecommunications Cabling
- b. *Bicsi®* Outside Plant Design Reference Manual (COOSP)
- c. *Bicsi*<sup>®</sup> Electronic Safety and Security Reference Manual (ESSDRM)
- d. Bicsi<sup>®</sup> Information Transport Systems Installation Methods Manual (ITSIM)
- e. *Bicsi®* Network Design Reference Manual (NDRM)
- f. Bicsi® Telecommunications Distribution Methods Manual (TDMM)
- g. Bicsi<sup>®</sup> Wireless Design Reference Manual (WDRM)
- h. Institute of Electrical and Electronic Engineers (IEEE)
- i. National Electrical Manufacturers Association (NEMA)
- j. Underwriters Laboratories (UL®) Cable Certification and Follow up Program
- k. American Standards Association (ASA)

#### 1.4 RELATED SECTIONS

- A. Section 270000 Communications
- B. Section 270526 Grounding and Bonding for Communications Systems
- C. Section 270528 Pathways for Communications Systems
- D. Section 270528.29 Hangers and Supports for Communications Systems
- E. Section 270536 Cable Trays for Communications Systems
- F. Section 270553 Identification for Communication Systems
- G. Section 271100 Communications Equipment Room Fittings
- H. Section 271116 Communications Racks, Frames and Enclosures
- I. Section 271313 Communications Copper Backbone Cabling
- J. Section 271323 Communications Optical Fiber Backbone Cabling
- K. Section 271513 Communications Copper Horizontal Cabling
- L. Section 274100 Audio-Video Systems
- M. Section 274123 Audio-Video Accessories
- N. Section 275113 Paging Systems
- O. Section 275313 Clock Systems
- P. Section 275319 Distributed Antenna System (DAS)

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- 1.5 ABBREVIATIONS AND ACRONYMS
  - A. AFF: Above Finished Floor
  - **B**. AWG: American Wire Gauge
  - C. Bicsi®: Formerly known as "Building Industry Consulting Services International"
  - D. CAT6: Category 6 Copper Cable
  - E. CAT6A: Category 6A Copper Cable
  - F. CMGC: Construction Manager/General Contractor
  - G. CMP: Communications Multipurpose Plenum: cable rating
  - H. CMR: Communications Multipurpose Riser: cable rating
  - I. DAS: Distributed Antenna System
  - J. ELFEXT: Equal-Level Far-End Crosstalk
  - K. Gbps: Gigabits per second
  - L. HVAC: Heating, Ventilation, and Air Conditioning
  - M. Mbps: Megabits per second
  - N. MMF: Multi-mode fiber optic cable, 50/125µm laser optimized core
  - O. NEXT: Near End Cross Talk
  - P. OSHA: Occupational Safety and Health Act
  - Q. PoE: Power over Ethernet
  - R. SCS: Structured Cabling System
  - S. SFF: Small Form Factor
  - T. TE: Telecommunications Enclosure
  - U. TIA: Telecommunications Industry Association
  - V. TR: Telecommunications Room
  - W. UL<sup>®:</sup> Underwriters Laboratory
  - X. UPS: Uninterruptible Power Supply

- Y. WAO: Work Area Outlet
- Z. WAN: Wide Area Network

#### 1.6 DEFINITIONS

- A. Advanced System Warranty: An extended warranty held either by the connectivity or cabling manufacturer directly with the Owner for this project that guarantees product and performance of the entire cabling system for the warranty period.
- B. Building Backbone Cabling: Building backbone cabling carries aggregate traffic and, as such, impacts multiple network devices and users. Building backbone cabling includes fiber optic and copper cabling.
- C. Category 6: A category of transmission performance that specifies electrical properties up to 250 MHz. Refer to ANSI/TIA/568 family of standards for more information on Category 6 and ISO/IEC 11801 for more information on Class E requirements.
- D. Category 6A: A category of transmission performance that specifies electrical properties up to 500 MHz and capable of supporting data applications operating at 10Gbps. Refer to ANSI/TIA/568 family of standards for more information on Category 6.
- E. Certification: The testing and documentation of the transmission performance of a permanent link or channel, based on sweep frequency testing of numerous parameters with results compared to a range of acceptable values. This project requires 100% certification of all permanent link cabling.
- F. Conduit: A raceway of circular cross-section.
- G. Conveniently Accessible: Being capable of being reached from floor or use of 8' step ladder without climbing or crawling under or over obstacles such as motors, pumps, belt guards, transformers, piping and duct work.
- H. Distributed Antenna System: A network of antenna nodes connected to common source(s) that provides wireless service.
- I. Equipment Room: An environmentally controlled centralized space for telecommunications equipment that usually houses a main or intermediate crossconnect, as well as video surveillance and security equipment.
- J. Horizontal Cabling: Cabling used to connect individual work area outlets to local Floor Distributors (FD) or other collection points. Unlike backbone cabling, horizontal cabling does not typically carry aggregate traffic and, as such, impacts only single network devices or users. In buildings, horizontal cabling almost exclusively consists of copper cabling. Fiber optic cabling may be used where situations dictate but, unlike horizontal copper cabling, horizontal fiber optic cabling is not installed in advance as default building facilities.

- K. Lead Telecommunications Installer: The project manager for the Telecommunications Subcontractor for all telecommunications work in the construction document Drawings and specifications, who shall be on-site at all times while Division 27 work is being performed. This individual shall attend all construction project meetings.
- L. Listed Communications Cable: A cable listed by the Underwriters Laboratory (UL<sup>®</sup>) and accepted by the local authority having jurisdiction as having met appropriate designated standards or has been tested and found suitable for installation in specific spaces. Refer to *NEC*<sup>®</sup> Article 800 for listing types and additional requirements.
- M. MDF: Main Distribution Frame, also known as the Main Equipment Room.
- N. Permanent Link A stationary cabling segment, consisting of the permanently installed cable and the permanently affixed jack at both ends (typically at the outlet faceplate and closet patch panel, or on a patch panel on both ends). The concept is based on the assumption that, while patch cords might be disconnected or moved over time, the permanent cable and jacks will not be disturbed and the electrical characteristics of the permanent link will remain unaltered.
- O. Owner: Beaverton School District.
- P. Owner's Representative: An entity assigned to represent the Owner in all matters pertaining to this project. Used synonymously with "Owner".
- Q. Plenum: A space within the building designed for the movement of environmental air; i.e., a space above a suspended ceiling or below an access floor.
- **R**. Plenum-: Listed by the Underwriters Laboratory as being suitable for installation into a plenum space. Communications cabling routed through plenum-rated space shall be plenum-rated and identified as Type CMP.
- S. Point of Entrance (Building Entrance): The point within a building at which the Outside Plant (OSP) communications wire or cable emerges from an external wall, from a concrete floor slab, or from a rigid metal conduit (Type RMC) or an intermediate metal conduit (Type IMC) connected by a grounding conductor to an electrode in accordance with the *NEC*<sup>®</sup>.
- T. Raceway: Any channel designed for holding wires or cables; i.e. conduit, electrical metal tubing, busways, wireways, ventilated flexible cableway.
- U. Subcontractor, Telecommunications: Entity responsible for all telecommunications work in the construction documents (Drawings and specification Sections 270000 through 275319).
- V. Telecommunications: In general, telecommunications refers to infrastructure/equipment needed for the voice, data, and video communications and transport systems.
- W. Telecommunications Room/Space: An environmentally enclosed architectural space designed to contain telecommunications equipment, cable terminations, or crossconnect cabling. The Main Equipment Room may also be known as the MDF, and may be co-located with the building's Entrance Room and Equipment Room. Telecommunications Rooms will also house equipment for additional systems, such as security, cable television, and audio/video.

#### COMMUNICATIONS

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

#### 1.7 PROJECT DRAWINGS

- A. General Drawing Specifications: Detail and elevation Drawings shall be D size  $(24" \times 36")$  with a minimum scale of 1/4" = 1'0" or larger. ER, TR and other enlarged detail floor plan Drawings shall be D size  $(24" \times 36")$  with a minimum scale of 1/4" = 1'0" or larger. Building composite floor plan Drawings shall be D size  $(24" \times 36")$  with a minimum scale of 1/4" = 1'0" or larger. Building composite floor plan Drawings shall be D size  $(24" \times 36")$  with a minimum scale of 1/8" = 1'0".
- B. Building composite floor plans: Provide building floor plans showing outlet locations and jack configuration, types of jacks, run distance for each jack cable, and cable routing/locations. Identify WAO's that, according to location and available pathway systems, require cable length greater than allowed by standards. Recommend alternatives for Owners Representative's consideration.
- C. Telecommunications space plans/elevations: Include enlarged floor plans of TRs indicating layout of equipment and devices, including receptacles and grounding provisions. Submit detailed plan views and elevations of telecommunications spaces showing racks, termination blocks, and cable paths.
- D. Logical Drawings: Provide logical riser or schematic Drawings for all systems. Include schematic symbol key.

#### 1.8 QUALITY ASSURANCE

- A. Telecommunications Subcontractor Qualifications
  - 1. Company Requirements
    - a. The Telecommunications Subcontractor shall have total responsibility for the coordination and installation of the work shown and described in the Drawings and Specifications.
    - b. Telecommunications Systems specified shall be assembled and installed under the direction of a qualified Telecommunications Subcontractor. Qualification requirements shall include submittal by the Telecommunications Subcontractor to the Architect of the following:
      - 1) List of previous projects of this scope and nature, including names and sizes of projects (to include square footage and construction cost overall and that of the Telecommunications Subcontractor), description of work, times of completion, and names of contact persons for reference.
      - 2) Installers shall certify that they are manufacturer-authorized or trained for work to be performed.
  - 2. Lead Telecommunications Installer Requirements:
    - a. Lead Communications Installer shall be a current member of *Bicsi*<sup>®</sup> in good standing and have completed (at a minimum) *Bicsi*<sup>®</sup> ITS Installer 2 Training (for both copper and fiber).

#### COMMUNICATIONS

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

- b. Submit certificate of ITS Installer 2 Training (or higher) with bid and preconstruction submittal package.
- c. Advanced training from connectivity manufacturer may be submitted in lieu of *Bicsi*<sup>®</sup> ITS Installer 2 Training. Submit manufacturer training certificates for review by Owner as substitution request as part of Pre- Bid questions. This training must be by the same manufacturer that will hold the Advanced System Warranty.
- 3. General Telecommunications Installer Requirements:
  - a. For all work associated with Specification Sections 27 all installers are to have a minimum of *Bicsi*<sup>®</sup> ITS Installer 1 Training or equivalent training from the connectivity manufacturer.
  - b. Submit a list with bid of names of all installers and appropriate copies of certificates verifying training with pre-construction submittal package.
- B. When articles, materials, operations or methods related to execution of communications work are noted, specified, or described in the specifications or are indicated or reasonably implied on Drawings and schedules, execute work as required or appropriate to provide complete and proper function, operation and installation.
- C. The Drawings utilize symbols and schematic diagrams to indicate items of work. These symbols and diagrams will not typically identify dimensions nor will they identify inclusion of specific accessories, appurtenances and related items necessary and appropriate for a complete and proper installation and operation. The Telecommunications Subcontractor shall install work complete and ready for proper operation, including related items not specifically identified, shown, indicated or specified. The work shall be installed, in accordance with the intent diagrammatically expressed on the Drawings, and in conformity with the dimensions indicated on architectural Drawings and on shop Drawings approved by the Owner.
- D. The Drawings include details for various items, which are specific with regard to the dimensions and positioning of the work. These details are intended only for the purpose of establishing general feasibility; they do not obviate field coordination for the indicated work. Work shall not proceed until actual field conditions and requirements are verified by the Telecommunications Subcontractor.
- E. The Drawings are diagrammatic and indicate the general arrangement of systems and equipment unless indicated otherwise by dimensions.

# 1.9 WARRANTY

A. Warranty Requirements: Comply with additional requirements in contract general requirements and extended warranties required in other specification sections. Refer to all other 27 sections for specific additional warranty requirements that exceed or are in addition to those of this section.

# WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- B. Contractor Warranty: Provide all services, materials and equipment necessary for successful operation of entire SCS system for a period of one year after system acceptance. Scope of warranty includes all equipment, devices, wiring, accessories, software, hardware, installation, and configuration required to maintain a complete and operable system. This shall apply to all items except those specifically excluded, or items wherein a longer period of service and warranty is specified or indicated. All warranties shall be effective for one year, minimum, from date Certificate of Final Acceptance is issued. Use of systems provided under this section for temporary services and facilities shall not constitute final acceptance of work nor beneficial use by Owner and shall not institute warranty period.
  - 1. The warranty shall cover repair or replacement of defective materials, equipment, workmanship, and installation that may be incurred during this period. Warranty work is to be done promptly and to Owner's satisfaction. In addition, warranty shall cover correction of damage caused in making necessary repairs and replacements under warranty.
- C. Project Warranty
  - 1. Equipment and materials required for installation under these specifications shall be the current model and new (less than one year from date of manufacture), unused and without blemish or defect, and are to be guaranteed to be free from defect.
  - 2. When a defect or problem is observed within the first year after substantial completion, the Owner will notify the governing subcontractor through the proper channels. The appropriate Subcontractor then has 48 hours to fix the defect or furnish and install a replacement part/system, all at no cost to the project or Owner.
- D. Advanced System Warranty for Telecommunications (Copper and Fiber Systems)
  - 1. Beyond the initial one year project warranty, the Telecommunications Systems shall be warranted for a minimum of 20 years by a national and reputable connectivity or cabling manufacturer.
    - a. This warranty shall cover any material defect, as well as the performance of the cabling system. (Example: A Category 6A cabling system is to deliver 10,000BASE-T speed, or 10 "Gig" performance for the entire length of the warranty period.)
    - b. This warranty shall cover material and labor for the entire warranty period.
  - 2. The Telecommunications Subcontract shall be certified by this manufacturer.
  - 3. The following manufacturers are conditionally approved to provide the system warranties (subject to specific project requirements):
    - a. Copper Connectivity Manufacturers
      - 1) CommScope (Systimax<sup>®</sup>, Uniprise<sup>®</sup>)
      - 2) Panduit
    - b. Fiber Connectivity Manufacturers

- 1) CommScope (Systimax<sup>®</sup>, Uniprise<sup>®</sup>,)
- 2) Panduit
- c. Cabling Manufacturers
  - 1) CommScope (Systimax<sup>®</sup>, Uniprise<sup>®</sup>)
  - 2) General (for Panduit product set)
- E. Owner's rights: This section shall not be interpreted to limit Owner's rights under applicable codes and under this Contract.

#### 1.10 SUBSTITUTIONS

- A. Substitution requests: Substitution requests will be considered only if submitted to Owner's Representative not less than 7 working days prior to project bid date. Acceptance or rejection of proposed substitution is at Owner's Representatives sole discretion. No exceptions. Requests for substitutions shall be considered not approved unless approval is issued in writing by Owner's Representative.
- B. Rejection: For equipment, cabling, wiring, materials, and all other products indicated or specified as no substitutions or no alternates, Owner does not expect nor desire requests for substitutions and alternate products other than those specified. Owner reserves right for Owner's Representative to reject proposed substitution requests and submissions of alternates without review or justification.

# 1.11 SUBMITTALS

- A. General Requirements
  - 1. Owner is to review all submittals related to Division 27 work. This includes, but is not limited to, relevant:
    - a. Pre-bid questions.
    - b. Contractor and personnel qualifications with bid.
    - c. Voluntary alternates and unit pricings with bid.
    - d. Pre-construction product submittals and shop Drawings.
    - e. Change order requests, requests for information (RFIs), design change directives (DCDs), and any other changes as directed by the architect/engineer.
  - 2. Allow a minimum of one week (five working days) for the Owner to review.
- **B**. The following submittals are due at the Pre-Bid deadline for questions:
  - 1. Requests for product substitution shall be in accordance with this document.
- 2. All products seeking approval either as "approved equivalent" or otherwise, shall be submitted as a product substitution request prior to bid. Failure to submit product substitution request in a timely manner (before pre-bid questions are due) may preclude product from being utilized on the project. Requests made with bid or post-bid will not be considered without a significant cost savings realized to the Owner.
- 3. The burden of proof is on the contractor to provide documentation that equivalent product meets the specifications and project requirements. Include in substitution request:
  - a. Product being replaced.
  - b. Reason for product substitution.
  - c. Full manufacturer specification sheet clearly indicating that all requirements in project documents have been met.
- 4. Failure to meet these requirements will result in the product substitution request being returned without review.
- 5. All product substitution requests are to be reviewed and approved by the Owner. Not all requests will be approved, and all decisions are final, without recourse.
- C. The following submittals are due with the Bid:
  - 1. Proof of Telecommunications Subcontractor and personnel qualifications
    - a. Provide a typed list with the following information:
      - 1) Company name of Telecommunications Subcontractor.
      - 2) List of connectivity or cabling manufacturers that the Telecommunications Subcontractor is certified to install and provide advanced warranty for.
      - 3) List of previous projects (minimum of 3) of this scope and nature, including:
        - a) Project name and date of completion.
        - b) Project size (square feet of building, total construction cost, total cost of telecommunications scope).
        - c) Name and contact information for building owner or IT Manager.
        - d) Name and contact information for Lead Telecommunications Installer.
        - e) Provide certificates or letter(s) from *Bicsi*<sup>®</sup> and / or manufacturers verifying by name these qualifications have been met.
        - f) Refer to Quality Assurance subsection in this specification section for additional requirements and qualifications.
  - 2. Voluntary alternatives (that realize substantial cost savings).
  - 3. Unit pricing for the following items:
    - a. All unit pricing relating to Division 27 as identified in these documents and accompanying T series Drawings.
- D. The following submittals are due at the Pre-Construction Phase (to be delivered to the Owner):
  - 1. General Requirements:

- a. Follow submission guidelines as outlined in this section.
  - 1) Strictly electronic submission to Owner is acceptable.
- b. Ensure a cover page with Project Title, Telecommunication Subcontractor Company, and point of contact is included for all physical submittals.
- c. Updated Personnel Qualifications.
  - 1) Provide a list of names of all telecommunications installers with appropriate certificates from  $Bicsi^{\text{®}}$  or the manufacturer.
- 2. Product Information, divided by Specification Section and in order, as listed in specification. Identify the start of each specification section.
  - a. Provide manufacturer's product information cutsheet or specifications sheet with the specific product number identified or filled out.
    - 1) Submitted cutsheets without specific product identified will result in the whole submittal being returned without review.
    - 2) No product substitutions will be considered post bid without a significant cost savings to the project to be realized by the owner a minimum of \$1000, either in material or labor savings. For any product substitution requests post-bid, Telecommunications Subcontractor shall submit an RFI through the proper channels with the requested documentation from the Prebid requirements above. Also, include realized cost savings. The project team may issue a change order (or its equivalent) for the product change at their discretion.
      - a) One exception to this is if the specified product goes out of production and is unavailable before submitted shop Drawings are approved. Telecommunications or Subcontractor is to submit an RFI explaining the situation and recommending an equivalent product with the same features at no cost change to the project or Owner.
      - b) Other exceptions may be considered. Telecommunications Subcontractor is to submit an RFI explaining the situation.
- 3. Shop Drawings
  - a. Generate electronic shop Drawings in AutoCAD<sup>®</sup>, dwg file format, version 2004 (or newer), saved to disk (CD-R or DVD+/-R) or USB Flash Drive with project name and number clearly indicated [or uploaded to project website]. Shop Drawings shall include Telecommunications or Subcontractor title block and included readily printable Plot/Drawing tabs with mview-window at a scale to not be less than 1/8" = 1'-0" unless otherwise noted. The scale shall also be indicated on the Drawings.
  - b. Acceptable electronic shop drawing sizes include:
    - 1) 8.5"x11"
    - 2) 11"x17"

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

- 3) 22"x34"
- 4) 24"x36"
- c. Refer to individual sections for additional requirements.
- d. Communications pathways.
  - 1) Hangers and Supports indicate proposed routing of all cabling supported by J-hooks.
  - 2) Cable Trays indicate size and proposed routing of all communications cable trays; should any of those locations or sizes differ from the construction Drawings due to minor coordination issues, cloud the affected area and note why the change is necessary. (For major coordination issues, please submit an RFI.)
  - 3) Firestopping indicate manufacturer, product/assembly, and UL system for all firestop penetrations required for communications cabling.
- E. The following submittals are due during Construction (project closeout), in accordance with the requirements of this Section 270000 Communications:
  - 1. 3 weeks prior to Substantial Completion:
    - a. Record Drawings.
      - 1) Modify reviewed and accepted AutoCAD<sup>®</sup> shop Drawings to include revisions based upon completion of work.
      - Provide one printed set of record Drawings to scale (not less than 1/8" = 1'-0").
      - 3) This set is to include system function diagrams and details not on original construction documents.
    - b. With the exception of the (1) printed set of record Drawings, submit these files electronically either on disk (CD or DVD) or USB Flash Drive, with project name and number clearly indicated.
  - 2. Within two weeks after Substantial Completion:
    - a. Warranty Certificates for the Advanced Telecommunications System Warranty for the copper and fiber systems with point of contact for any warranty claims.

## 1.12 ADDITIONAL REQUIREMENTS

- A. Integration: Responsibility for overall telecommunications system integration and coordination of work among trades, subcontractors, and suppliers shall rest with Contractor named in this contract. Work covered by this division of specifications shall be coordinated with related work indicated on Drawings or specified elsewhere under project specifications. All work related to telecommunications system and required for complete and operational systems as detailed in these specifications or the accompanying T series Drawings shall be performed under direct supervision of telecommunications system installer in a manner approved by product manufacturer.
- B. Coordination of work: Contractor shall be responsible for coordination of work among project specification divisions and contractor/subcontractors involved in this project. This coordination of work includes following instructions provided throughout all Division 27 specifications and the accompanying T series Drawings as well as electrical work (normally addressed in Division 26) as called out in the narrative portions of Division 27 or so referenced in the accompanying T series Drawings.
- C. General compliance requirements: Provide a complete and operable system in compliance with project Drawings, specifications, referenced standards, applicable building codes, and Authority Having Jurisdiction (AHJ) requirements. Scope of this contract includes planning, design, materials, equipment, labor, configuration, programming, testing, startup and commissioning services, and documentation costs for complete and operable system that meets all requirements indicated on Drawings or contained in specifications. Comply with all contract documents, specifications, Drawings, manufacturer's instructions, and Owner and AHJ requirements. In case of conflict among applicable documents or standards, contractor shall notify owner's representative in writing of apparent conflict, and then comply with most stringent requirements unless otherwise directed in writing from owner's representative.

## 1.13 DELIVERY STORAGE AND HANDLING

A. General: Owner will, at Contractor's request, provide appropriate space on site for Contractor trailer or job box; however, Contractor shall be responsible for the deliveries, storing and handling of all materials relative to the SCS systems, including materials supplied by others that are part of the SCS installation contract. Material shall be stored and protected according to manufacturer's instructions. Contractor shall be responsible for the security of all material during installation. For all material provided by contractor, or delivered to contractor on site, contractor assumes full responsibility and liability for any material shortages, damage or loss due to storage and handling methods.

## 1.14 PERMITS AND INSPECTIONS

A. General: All telecommunications systems shall meet or exceed the latest requirements of all national, state, county, municipal, and other authorities exercising jurisdiction over the telecommunications systems and the Project.

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

- B. Contractor shall obtain and pay for all licenses, permits, and inspection fees required by local agencies and/or other agencies having jurisdiction. Copies of all permits shall be delivered electronically to the Owner.
- C. Contractor agrees to furnish any additional labor or material required to comply with all local and other agencies having jurisdiction at no additional cost.
- D. Contractor shall obtain certificates of inspection and approval from all authorities having jurisdiction, and forward copies of same to Owner prior to request for Project acceptance inspections, final completion inspections, substantial completion inspections, and acceptance testing/demonstrations.
- E. All required permits and inspection certificates shall be made available at the completion of the telecommunications system installation and commissioning.
- F. Any portion of the telecommunications work which is not subject to the requirements of an electric code published by a specific AHJ shall be governed by the National Electrical Code and other applicable sections of the National Fire Code, as published by the National Fire Protection Association (NFPA).
- G. Installation procedures, methods and conditions shall comply with the latest requirements of the Federal Occupational Safety and Health Administration (OSHA).
- H. All work shall comply with the TIA Standards listed in this document.

## 1.15 EXAMINATION

- A. General: Prior to submitting a proposal, Contractor shall examine site, review Project Drawings and specifications, and determine exact extent of work required. Contractor shall include in their proposals all materials, labor, and equipment required to complete required work indicated. Work that is necessary to obtain complete and usable Project as specified herein shall be included in Contractor's proposal, even if not indicated or specified.
- **B**. Bidders' questions: Should bidders have questions as to intent of Drawings and specifications, quality of materials to be used, and work to be performed, questions shall be submitted in writing to the Owner in manner dictated by the Owner. All answers and clarifications to Drawings and specifications will be issued in writing.
- C. Extra payment will not be allowed for claims for due to unfamiliarity with work to be performed by other trades, existing conditions at job site, local or state laws and codes, and alterations due to field conditions.

### 1.16 ADDITIONAL COSTS

A. General: Project acceptance inspections, final completion inspections, substantial completion inspections, and acceptance testing/demonstrations shall be conducted after verification of system operation and completeness by Contractor.

# COMMUNICATIONS

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

- B. Inspections and testing: For Project acceptance inspections, final completion inspections, substantial completion inspections, and/or testing/demonstrations that require more than one site visit by Owner or Architect/Engineer to verify Project compliance for same material or equipment, Owner reserves right to obtain compensation from Contractor to defray cost of additional site visits that result from Project construction or testing deficiencies/incompleteness, incorrect information, or non-compliance with Project provisions. Owner will notify Contractor of hourly rates and travel expenses for additional site visits, and will issue an invoice to Contractor for additional site visits. Payment of additional site visit costs by Contractor is required within 30 days of invoicing. Owner reserves right to deduct additional costs defined herein that are indicated on past due invoices from Project amount due Contractor.
- C. Exclusions: Contractor shall not be eligible for extensions of Project schedule or additional charges resulting from additional site visits that result from Project construction or testing deficiencies/incompleteness, incorrect information, or non-compliance with Project provisions.

# PART 2 - PRODUCTS

# 2.1 GENERAL

- A. Materials and equipment furnished shall be of current production by manufacturers regularly engaged in the manufacture of such items, for which replacement parts are available.
- B. When more than one unit of the same class of equipment or material is required, such units shall be the products of a single manufacturer and part number.
- C. All products and materials shall be new and unused prior to their installation as part of this project. Refurbished items are not allowed.

# PART 3 - EXECUTION

## 3.1 GENERAL

- A. Coordinate with all other trades prior to installation.
  - 1. Telecommunications Subcontractor shall meet with Electrical, Mechanical, and General Contractors prior to construction to identify pathway and infrastructure space requirements.
    - a. At a minimum, the following items shall be discussed:
      - 1) Cable tray locations and clearance space above (12" if possible, with proper coordination).
      - 2) Placement for sleeving and wall penetrations.
      - 3) In-ceiling projection screens and other audio/video equipment.

## COMMUNICATIONS

270000 - 16

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

- b. Failure to coordinate sufficient space for telecommunications infrastructure shall result in relocation of various systems by the contractor at no additional cost to owner.
- 2. Prior to the start of work, the Telecommunications Subcontractor shall carefully inspect the installed work of other trades and verify that such work is complete to the point where Division 27 work may properly commence. Start of work indicates acceptance of conditions.
- 3. Coordinate location of equipment and conduit with other trades to minimize interference.
  - a. Holes through concrete and masonry structures shall be cut with a diamond core drill or concrete saw upon approval of the structural engineer of record for the base building.
  - b. Pneumatic hammer, impact electric, hand or manual hammer type drills shall not be allowed, except where permitted by the General Contractor as required by limited working space.
  - c. Holes shall be located so as not to affect structural sections such as ribs or beams.
  - d. Holes shall be laid out in advance. The General Contractor shall be advised prior to drilling through structural sections, for determination of proper layout.
  - e. Structural Penetrations: Where conduits, wireways and other raceways pass through fire partitions, fire walls or walls and floors, provide an effective barrier against the spread of fire, smoke and gases.
- B. Follow all manufacturers' instructions and install equipment in accordance with applicable codes and regulations, the original design and the referenced standards.
  - 1. In the event of discrepancy, immediately notify the Owner through the proper channels. Do not proceed with installation until unsatisfactory conditions and discrepancies have been fully resolved.
- C. Protection of Systems and Equipment
  - 1. Protect materials and equipment from damage during storage at the site and throughout the construction period. Equipment and materials shall be protected during shipment and storage against physical damage, dirt, theft, moisture, extreme temperature and rain.
  - 2. Damage from rain, dirt, sun and ground water shall be prevented by storing the equipment on elevated supports and covering them on sides with securely fastened protective rigid or flexible waterproof coverings.
  - 3. During installation, equipment shall be protected against entry of foreign matter on the inside and be vacuum-cleaned both inside (as appropriate) and outside before testing, operating or painting.
- D. As determined by the Owner, damaged equipment shall be fully repaired or shall be removed and replaced with new equipment to fully comply with requirements of the Contract Documents. Decision of the Owner shall be final.
- E. Painted surfaces shall be protected with removable heavy kraft paper, sheet vinyl or equal, installed at the factory and removed prior to final inspection.

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

- F. Damaged paint on equipment and materials shall be repainted with painting equipment and finished with same quality of paint and workmanship as used by manufacturer.
- G. Access to Equipment
  - 1. Equipment shall be installed as per the scaled detail on the Power & Signal Drawings.
  - 2. Working spaces shall be not less than specified in the National Electrical Code<sup>®</sup> for voltages specified.
  - 3. Where the Owner determines that the Telecommunications Subcontractor has installed equipment not "conveniently accessible" for operation and maintenance, equipment shall be removed and reinstalled, one time only, as directed by the Owner, at no additional cost to the Owner.
- H. Cleaning
  - 1. During construction, and prior to Owner acceptance of the building, remove from the premises and dispose of packing material and debris caused by communications work.
  - 2. Remove dust and debris from interiors and exteriors of telecommunications equipment (including electrical rough-in). Clean accessible current carrying elements prior to being energized.
- I. Completion
  - 1. General:
    - a. Upon completion of the work, remove excess debris, materials, equipment, apparatus, tools and similar items. Leave the premises clean, neat and orderly.
  - 2. Results Expected:
    - a. Systems shall be complete and operational.
    - b. Cleaning work shall be complete.
  - 3. Testing and Verification General Requirements.
    - a. Refer to individual sections for additional testing and verification requirements.
    - b. The Telecommunications Subcontractor shall verify that requirements of this specification are met. Verification shall be through a combination of analyses, inspections, demonstrations and tests, as described below.
    - c. Verification by Inspection: Verification by inspection includes examination of items and comparison of pertinent characteristics against the qualitative or quantitative standard set forth in the specifications.
    - d. Verification by Test and Demonstration: The Telecommunications Subcontractor shall verify by formal demonstrations or tests that the requirements of this Specification have been met. The Communications Subcontractor shall demonstrate that the communications systems components and subsystems meet specification requirements in the "as-installed" operating environment during the "System Operation Test".
      - Perform system operation tests after full enclosure of walls.

e.

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

- f. System Operation Tests Conducted Upon Completion of Work: Upon completion of the Telecommunications Subcontractor's Work, subject the system to functional and operational tests. When required corrections determined by initial test results have been completed, fully retest the system. The Owner shall be notified in writing not less than seven days in advance of date of proposed final testing and inspection. The advance notice shall include certification that the installation is complete and operable and that the Telecommunications Subcontractor has satisfactorily performed the final tests specified herein.
- g. The acceptance testing and final inspection shall be accomplished in the presence of the Owner. At least 10 days prior to scheduled system completion, the Telecommunications Subcontractor shall submit, for approval by Owner, a test plan to completely test the telecommunications system. The Telecommunications Subcontractor shall include in test plan, for acceptance by the Owner, a complete and detailed final acceptance test check-off list ("punch list"). The list shall be a complete representation of specified functions and conditions.
- 4. Commissioning
  - a. There shall be three phases of commissioning:
    - 1) Rough-in inspection.
    - 2) Above-ceiling inspection (after cables are placed).
    - 3) Final inspection.
  - b. At a minimum, the Owner shall check the following items:
    - 1) Accurate location and height AFF for all outlet boxes.
    - 2) Accurate dimensions (particularly depth) of all outlet boxes and diameter of in-wall conduit serving outlet boxes.
    - 3) Cable tray size, location, and clearance.
    - 4) Location and size of communications conduits or pathways.
    - 5) That power receptacles within the communications rooms meet the design requirements.
    - 6) The Owner is then to issue a written report to the General Contractor identifying all items which currently do not meet the construction document requirements. This report is to be forwarded to the appropriate subcontractor(s) and all items are to be addressed.
    - 7) This report is not necessarily all inclusive; should issues be discovered later in the project, the appropriate communications subcontractor is still responsible for corrections/repairs.
  - c. Once all communication cabling has been installed and properly supported and walls have been painted, but prior to the installation of ceiling tiles/material, the Owner shall schedule a time to be on-site to conduct above-ceiling inspection. At a minimum, the Owner shall check the following items:
    - 1) That all items from the previous inspection have been corrected.
    - 2) That communications cabling is routed correctly and adequately supported.
    - 3) That communications cabling is not painted or over sprayed.

## COMMUNICATIONS

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

- 4) That the installed communications cabling matches what was specified / submitted.
- 5) That there are no kinks, splices, or other damage to the installed communications cabling.
- d. The Owner is then to issue a written report to the General Contractor identifying all items which currently do not meet the construction document requirements. This report is to be forwarded to the appropriate subcontractor(s) and all items are to be addressed. This report is not necessarily all inclusive; should issues be discovered later in the project, the appropriate communications subcontractor is still responsible for corrections/repairs.
- e. Once all communications work has been completed, contractor shall request final inspection. This request shall be made 3 weeks before substantial completion. The Owner shall then schedule a time to be on-site to conduct this inspection. At a minimum, the Owner shall check the following items:
  - 1) That all items from the previous inspections have been corrected.
  - 2) That all faceplates are installed, with the correct modules, quantity of modules, and approved labeling scheme.
  - 3) That all equipment and cabling within communications rooms is installed per the contract documents, including all patch panels and wall blocks (with specified spare capacity), horizontal and backbone cabling labeling, and telecommunications grounding.
  - 4) And all other items necessary to guarantee contract documents are met and complete and functioning communications systems are installed.
- f. The Owner is then to issue a written report to the General Contractor identifying all items which currently do not meet the construction document requirements. This report is to be forwarded to the appropriate subcontractor(s) and all items are to be addressed prior to substantial completion. This report is not necessarily all-inclusive; should issues be discovered within one year after substantial completion, the appropriate communications subcontractor is still responsible for corrections/repairs.

END OF SECTION 270000

### COMMUNICATIONS

## SECTION 270500 - COMMON WORK RESULTS FOR COMMUNICATIONS

PART 1 - GENERAL

## 1.1 SECTION INCLUDES

- A. General Requirements
- B. Summary
- C. Environmental Considerations
- D. Site Specific Requirements

# 1.2 RELATED SECTIONS

- A. Section 270000 Communications
- B. Section 270526 Grounding and Bonding for Communications Systems
- C. Section 270528 Pathways for Communications Systems
- D. Section 270528.29 Hangers and Supports for Communications Systems
- E. Section 270536 Cable Trays for Communications Systems
- F. Section 270553 Identification for Communication Systems
- G. Section 271100 Communications Equipment Room Fittings
- H. Section 271116 Communications Cabinets, Racks, Frames and Enclosures
- I. Section 271313 Communications Copper Backbone Cabling
- J. Section 271323 Communications Optical Fiber Backbone Cabling
- K. Section 271513 Communications Copper Horizontal Cabling
- L. Section 274100 Audio-Video Systems
- M. Section 274123 Audio-Video Accessories
- N. Section 275113 Paging Systems
- O. Section 275313 Clock Systems

# COMMON WORK RESULTS FOR COMMUNICATIONS

270500 - 1

Copyright © 2020 by the American Institute of Architects. Warning: This AIA MasterSpec based document is protected by U.S. Copyright Law and International Treaties. A valid, current MasterSpec license is required for editing or use of this document.

P. Section 275319 – Distributed Antenna System (DAS)

### 1.3 SPECIFIC REQUIREMENTS

- A. Beaverton School District is a tobacco free environment. Tobacco in any form whatsoever is not permitted in this school or on the property owned by the District.
- **B**. Beaverton School District is constructing a new school as per the accompanying drawings. This contract will be responsible for all aspects of telecommunications cabling and supporting infrastructure required for functional systems.

### 1.4 SUMMARY

- A. The intent of the Division 27 Specifications and the accompanying Drawings is to provide a complete and workable system as shown, specified and required by applicable codes and the Authority Having Jurisdiction (AHJ). Include all work as specified in Division 27 and shown on the accompanying Drawings, including appurtenances, to provide a complete and functional system.
- B. The Division 27 Specifications and accompanying Drawings are complementary and what is called for in one shall be as binding as if called for in both. Items shown on the Drawings are not necessarily included in or called out in the Specifications and vice versa. Specifications shall supersede Drawings in the case of a conflict.
- C. Imperative language is frequently used in the Division 27 Specifications. Except as otherwise noted, such requirements are to be performed by the Contractor or a Sub-contractor directly responsible to the Prime Contractor performing the Division 27 work.
- D. The Drawings accompanying Division 27 are diagrammatic. They do not show every component of a complete premises distribution system which may be required to accommodate unique building construction features or materials installed by other trades. The Drawings are to be followed as closely as practical while making necessary adjustments in the placement of cable to facilitate the overall construction of the building without additional cost to the Owner. The right is reserved to make any reasonable changes in Work Area Outlet locations prior to roughing-in.

## 1.5 ENVIRONMENTAL CONSIDERATION

- A. When at all possible, equipment and materials are to be assembled at Distributors or Contractors location and delivered to construction site without packaging or shipping material.
- B. Except as noted for purposes of recycling, all construction related debris; packaging and waste materials will be removed from the job site each day and disposed of by the Contractor.

### COMMON WORK RESULTS FOR COMMUNICATIONS

## 1.6 SITE SPECIFIC REQUIREMENTS

- A. Contractor must conform to schedule prescribed by General Contractor.
- **B**. Site details are shown on the accompanying drawings.

### 1.7 DEVICE LOCATIONS

- A. Telecommunication Room location as per the Drawings.
- B. Cabling, pathway, fire stopping, and support structures as per the Drawings and specifications.
- C. Work Area Outlets (WAO) will be as per the Drawings. Owner reserves the right to make slight modifications in placement of the WAO prior to cover.

PART 2- (NOT USED)

PART 3 - (NOT USED)

END OF SECTION 270500

COMMON WORK RESULTS FOR COMMUNICATIONS

# SECTION 270528 - PATHWAYS FOR COMMUNICATIONS SYSTEMS

## PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

### A. Section Includes:

- 1. Metal conduits and fittings.
- 2. Nonmetallic conduits and fittings.
- 3. Optical-fiber-cable pathways and fittings.
- 4. Metal wireways and auxiliary gutters.
- 5. Nonmetallic wireways and auxiliary gutters.
- 6. Hooks.
- 7. Boxes, enclosures, and cabinets.
- 8. Polymer-concrete handholes and boxes for exterior underground cabling.
- 9. Fiberglass handholes and boxes for exterior underground cabling.

### 1.3 DEFINITIONS

- A. ARC: Aluminum rigid conduit.
- B. GRC: Galvanized rigid conduit.
- C. IMC: Intermediate metal conduit.
- D. RTRC: Reinforced thermosetting resin conduit.

### 1.4 ACTION SUBMITTALS

- A. Product data for the following:
  - 1. Wireways and fittings.
  - 2. Boxes, enclosures, and cabinets.
  - 3. Underground handholes and boxes.
- B. Shop Drawings: For custom enclosures and cabinets. Include plans, elevations, sections, and attachment details.

### PATHWAYS FOR COMMUNICATIONS SYSTEMS

### 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Pathway routing plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of items involved:
  - 1. Structural members in paths of pathway groups with common supports.
  - 2. HVAC and plumbing items and architectural features in paths of conduit groups with common supports.
  - 3. Underground ducts, piping, and structures in location of underground enclosures and handholes.
- B. Qualification Data: For professional engineer.
- C. Seismic Qualification Data: Provide seismic bracing for all pathway racks, enclosures, cabinets, equipment racks, and their mounting provisions, including those for internal components, from manufacturer.
  - 1. Confirm building occupancy category and seismic design category and provide stamped shop drawings from licensed structural engineer of seismic bracing and seismic movement assemblies for cabinets, racks and major equipment. Submit with shop drawings.
  - 2. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 3. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  - 4. Detailed description of equipment anchorage devices on which certification is based and their installation requirements.
  - 5. Detailed description of conduit support devices and interconnections on which certification is based and their installation requirements.
- D. Source quality-control reports.

# PART 2 - PRODUCTS

## 2.1 METAL CONDUITS AND FITTINGS

- A. Description: Metal raceway of circular cross section with manufacturer-fabricated fittings.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. AFC Cable Systems; a part of Atkore International.
  - 2. Allied Tube & Conduit; a part of Atkore International.
  - 3. O-Z/Gedney; a brand of Emerson Industrial Automation.
  - 4. Republic Conduit.
  - 5. Thomas & Betts Corporation; A Member of the ABB Group.
  - 6. Western Tube and Conduit Corporation.

# PATHWAYS FOR COMMUNICATIONS SYSTEMS

- C. General Requirements for Metal Conduits and Fittings:
  - 1. Listed and labeled as defined in NFPA 70, by a nationally recognized testing laboratory, and marked for intended location and application.
  - 2. Comply with TIA-569-D.
- D. GRC: Comply with ANSI C80.1 and UL 6.
- E. ARC: Comply with ANSI C80.5 and UL 6A.
- F. IMC: Comply with ANSI C80.6 and UL 1242.
- G. PVC-Coated Steel Conduit: PVC-coated GRC.
  - 1. Comply with NEMA RN 1.
  - 2. Coating Thickness: 0.040 inch, minimum.
- H. EMT: Comply with ANSI C80.3 and UL 797.
- I. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
  - 1. Fittings for EMT:
    - a. Material: Steel.
    - b. Type: Set Screw.
  - 2. Expansion Fittings: PVC or steel to match conduit type, complying with UL-467, rated for environmental conditions where installed, and including flexible external bonding jumper.
  - 3. Coating for Fittings for PVC-Coated Conduit: Minimum thickness of 0.040 inch with overlapping sleeves protecting threaded joints.
- J. Joint Compound for IMC, GRC, or ARC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

## 2.2 METAL WIREWAYS AND AUXILIARY GUTTERS

- A. Description: Sheet metal trough of rectangular cross section fabricated to required size and shape, without holes or knockouts, and with hinged or removable covers.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. B-line, an Eaton business.
  - 2. Hoffman; a brand of Pentair Equipment Protection.
  - 3. MonoSystems, Inc.
- C. General Requirements for Metal Wireways and Auxiliary Gutters:

### PATHWAYS FOR COMMUNICATIONS SYSTEMS

- 1. Comply with UL 870 and NEMA 250, Type 1 unless otherwise indicated, and sized according to NFPA 70.
- 2. Metal wireways installed outdoors shall be listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and application.
- 3. Comply with TIA-569-D.
- D. Fittings and Accessories: Include covers, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- E. Finish: Manufacturer's standard enamel finish.

# 2.3 HOOKS

- A. Description: Prefabricated sheet metal cable supports for telecommunications cable.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. MonoSystems, Inc.
  - 2. Panduit Corp.
- C. Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and application.
- D. Comply with TIA-569-D.
- E. Galvanized steel.
- F. J shape.

## 2.4 BOXES, ENCLOSURES, AND CABINETS

- A. Description: Enclosures for communications.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Adalet.
  - 2. Cooper Technologies Company; Cooper Crouse-Hinds.
  - 3. FSR Inc.
  - 4. Hoffman; a Pentair company.
  - 5. Hubbell Incorporated; Killark Division.
  - 6. Mono-Systems, Inc.
  - 7. O-Z/Gedney; a brand of EGS Electrical Group.
  - 8. RACO; a Hubbell Company.
  - 9. Thomas & Betts Corporation.
  - 10. Wiremold / Legrand.

# PATHWAYS FOR COMMUNICATIONS SYSTEMS

- C. General Requirements for Boxes, Enclosures, and Cabinets:
  - 1. Comply with TIA-569-D.
  - 2. Boxes, enclosures, and cabinets installed in wet locations shall be listed and labeled as defined in NFPA 70, by an NRTL, and marked for use in wet locations.
  - 3. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
  - 4. Device Box Dimensions: 4-11/16 inches square by 2-5/8 inches deep with a 5/8" single gang mud ring cover.
  - 5. Gangable boxes are prohibited.
- D. Sheet Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- E. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, ferrous alloy, Type FD, with gasketed cover.
- F. Metal Floor Boxes:
  - 1. See specification section 260533 for combined power and data floor box requirements.
- G. Nonmetallic Floor Boxes: Not Allowed.
- H. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- I. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, cast aluminum with gasketed cover.
- J. Nonmetallic Outlet and Device Boxes: Not Allowed
- K. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, Type 1, with continuous-hinge cover with flush latch unless otherwise indicated.
  - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
    - a. Finished inside with radio-frequency-resistant paint.
  - 2. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.
- L. Cabinets:
  - 1. NEMA 250, Type 1 galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.
  - 2. Hinged door in front cover with flush latch and concealed hinge.
  - 3. Key latch to match panelboards.
  - 4. Metal barriers to separate wiring of different systems and voltage.
  - 5. Accessory feet where required for freestanding equipment.

PART 3 - EXECUTION

### 3.1 PATHWAY APPLICATION

- A. Indoors: Apply pathway products as specified below unless otherwise indicated:
  - 1. Exposed, Not Subject to Physical Damage: EMT.
  - 2. Exposed and Subject to Severe Physical Damage: GRC Pathway locations include the following:
    - a. None anticipated in current scope.
  - 3. Concealed in Ceilings and Interior Walls and Partitions: EMT.
  - 4. Damp or Wet Locations: GRC.
  - 5. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4 stainless steel units in institutional and commercial kitchens and damp or wet locations.
- B. Minimum Pathway Size: 1-inch trade size for copper and aluminum cables, and 1-1/4 inch for optical-fiber cables.
- C. Pathway Fittings: Compatible with pathways and suitable for use and location.
  - 1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
  - 2. EMT: Use set-screw fittings. Comply with NEMA FB 2.10.
- D. Do not install aluminum conduits, boxes, or fittings in contact with concrete or earth.
- E. Install surface pathways only where indicated on Drawings.
- F. Do not install nonmetallic conduit where ambient temperature exceeds 120 deg F.

# 3.2 INSTALLATION

- A. Comply with the following standards for installation requirements except where requirements on Drawings or in this Section are stricter:
  - 1. NECA 1.
  - 2. NECA/BICSI 568.
  - 3. TIA-569-D.
  - 4. NECA 101
  - 5. NECA 102.
  - 6. NECA 105.
  - 7. NECA 111.
- B. Comply with NFPA 70 limitations for types of pathways allowed in specific occupancies and number of floors.

### PATHWAYS FOR COMMUNICATIONS SYSTEMS

- C. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping materials and installation for penetrations through fire-rated walls, ceilings, and assemblies.
- D. Comply with requirements in Section 270528.29 "Hangers and Supports for Communications Systems" for hangers and supports.
- E. Keep pathways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal pathway runs above water and steam piping.
- F. Complete pathway installation before starting conductor installation.
- G. All conduits to have bushings installed on ends prior to cable being pulled.
- H. In cases where EMT cannot be used, 1-1/4" flexible metallic conduit may be used.
- I. Provide conduit pathway in all inaccessible locations including walls, floors and ceilings.
- J. Provide conduit pathway where routed in exposed ceilings to structure.
- K. Install no more than the equivalent of two 90-degree bends in any pathway run. Provide pull boxes as needed to comply. Support within 12 inches of changes in direction. Utilize long radius ells for all optical-fiber cables.
- L. Conceal rigid conduit within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- M. Support conduit within 12 inches of enclosures to which attached.
- N. Stub-ups to Above Recessed Ceilings:
  - 1. Use EMT, IMC, or RMC for pathways.
  - 2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.
  - 3. Sleeves to protrude 3" to 6" above the surface of the floor.
- O. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of pathway and fittings before making up joints. Follow compound manufacturer's written instructions.
- P. Coat field-cut threads on PVC-coated pathway with a corrosion-preventing conductive compound prior to assembly.
- Q. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install insulated bushings on conduits terminated with locknuts.
- R. Install pathways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus one additional quarter-turn.
- S. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure, to assure a continuous ground path.

- T. Cut conduit perpendicular to the length. For conduits of 2-inch trade size and larger, use roll cutter or a guide to ensure cut is straight and perpendicular to the length.
- U. Install pull wires in empty pathways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire. Secure pull wire, so it cannot fall into conduit. Cap pathways designated as spare alongside pathways in use.
- V. Surface Pathways:
  - 1. Install surface pathway for surface telecommunications outlet boxes only where indicated on Drawings.
  - 2. Install surface pathway with a minimum 2-inch radius control at bend points.
  - 3. Secure surface pathway with screws or other anchor-type devices at intervals not exceeding 48 inches and with no less than two supports per straight pathway section. Support surface pathway according to manufacturer's written instructions. Tape and glue are not acceptable support methods.
- W. Install pathway-sealing fittings at accessible locations according to NFPA 70 and fill them with listed sealing compound. For concealed pathways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install pathway-sealing fittings according to NFPA 70.
- X. Install devices to seal pathway interiors at accessible locations. Locate seals, so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all pathways at the following points:
  - 1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
  - 2. Where an underground service pathway enters a building or structure.
  - 3. Where otherwise required by NFPA 70.
- Y. Comply with manufacturer's written instructions for solvent welding PVC conduit and fittings.
- Z. Expansion-Joint Fittings:
  - 1. Install in each run of aboveground RNC that is located where environmental temperature change may exceed 30 deg F, and that has straight-run length that exceeds 25 feet. Install in each run of aboveground RMC and EMT that is located where environmental temperature change may exceed 100 deg F, and that has straight-run length that exceeds 100 feet.
  - 2. Install type and quantity of fittings that accommodate temperature change listed for each of the following locations:
    - a. Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F temperature change.
    - b. Outdoor Locations Exposed to Direct Sunlight: 155 deg F temperature change.
    - c. Indoor Spaces Connected with Outdoors without Physical Separation: 125 deg F temperature change.
    - d. Attics: 135 deg F temperature change.

## PATHWAYS FOR COMMUNICATIONS SYSTEMS

- 3. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per deg F of temperature change for PVC conduits. Install fitting(s) that provide expansion and contraction for at least 0.000078 inch per foot of length of straight run per deg F of temperature change for metal conduits.
- 4. Install expansion fittings at all locations where conduits cross building or structure expansion joints.
- 5. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.
- AA. Hooks:
  - 1. Size to allow a minimum of 25 percent future capacity without exceeding design capacity limits.
  - 2. Shall be supported by dedicated support wires. Do not use ceiling grid support wire or support rods.
  - 3. Hook spacing shall allow no more than 6 inches of slack. The lowest point of the cables shall be no less than 6 inches adjacent to ceilings, mechanical ductwork and fittings, luminaires, power conduits, power and telecommunications outlets, and other electrical and communications equipment.
  - 4. Space hooks no more than 5 feet o.c.
  - 5. Provide a hook at each change in direction.
- BB. Mount WAP at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to center of box unless otherwise indicated.
- CC. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surface to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box.
- DD. Horizontally separate boxes mounted on opposite sides of walls, so they are not in the same vertical channel.
- EE. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.
- FF. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.
- GG. Set metal floor boxes level and flush with finished floor surface.
- HH. Set nonmetallic floor boxes level. Trim after installation to fit flush with finished floor surface.

# 3.3 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR COMMUNICATIONS PENETRATIONS

A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies.

### PATHWAYS FOR COMMUNICATIONS SYSTEMS

### 3.4 FIRESTOPPING

A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

## 3.5 **PROTECTION**

- A. Protect coatings, finishes, and cabinets from damage or deterioration.
  - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
  - 2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION 270528

## SECTION 270528.29 - HANGERS AND SUPPORTS FOR COMMUNICATIONS SYSTEMS

PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Steel slotted support systems for communication raceways.
  - 2. Conduit and cable support devices.
  - 3. Support for conductors in vertical conduit.
  - 4. Structural steel for fabricated supports and restraints.
  - 5. Mounting, anchoring, and attachment components, including powder-actuated fasteners, mechanical expansion anchors, concrete inserts, clamps, through bolts, toggle bolts, and hanger rods.
  - 6. Fabricated metal equipment support assemblies.
- B. Related Requirements:

### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for the following:
    - a. Slotted support systems, hardware, and accessories.
    - b. Clamps.
    - c. Hangers.
    - d. Sockets.
    - e. Eye nuts.
    - f. Fasteners.
    - g. Anchors.
    - h. Saddles.
    - i. Brackets.
  - 2. Include rated capacities and furnished specialties and accessories.

## HANGERS AND SUPPORTS FOR COMMUNICATIONS SYSTEMS

270528.29 - 1

- B. Shop Drawings: For fabrication and installation details for communications hangers and support systems.
  - 1. Trapeze hangers. Include product data for components.
  - 2. Steel slotted-channel systems.
  - 3. Equipment supports.
  - 4. Vibration Isolation Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.
- C. Delegated-Design Submittal: For hangers and supports for communications systems.
  - 1. Include design calculations and details of trapeze hangers.
  - 2. Include design calculations for seismic restraints.

# 1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
  - 1. Suspended ceiling components.
  - 2. Ductwork, piping, fittings, and supports.
  - 3. Structural members to which hangers and supports will be attached.
  - 4. Size and location of initial access modules for acoustical tile.
  - 5. Items penetrating finished ceiling, including the following:
    - a. Luminaires.
    - b. Air outlets and inlets.
    - c. Speakers.
    - d. Sprinklers.
    - e. Access panels.
    - f. Projectors.
- B. Seismic Qualification Certificates: For hangers and supports for communications equipment and systems, accessories, and components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- C. Welding certificates.

# 1.5 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.
- B. Welding Qualifications: Qualify procedures and personnel according to the following:
  - 1. AWS D1.1/D1.1M.

# PART 2 - PRODUCTS

# 2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design hanger and support system.
- B. Seismic Performance: Hangers and supports shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
  - 1. The term "withstand" means "the supported equipment and systems will remain in place without separation of any parts when subjected to the seismic forces specified."
  - 2. Component Importance Factor: 1.0.

# 2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Preformed steel channels and angles with minimum 13/32-inchdiameter holes at a maximum of 8 inches o.c. in at least one surface.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Allied Tube & Conduit; a part of Atkore International.
    - b. B-line, an Eaton business.
    - c. ERICO International Corporation.
    - d. GS Metals Corp.
    - e. Thomas & Betts Corporation; A Member of the ABB Group.
    - f. Unistrut; Part of Atkore International.
  - 2. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
  - 3. Material for Channel, Fittings, and Accessories: Galvanized steel.
  - 4. Channel Width: Selected for applicable load criteria.
  - 5. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
  - 6. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
  - 7. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
  - 8. Channel Dimensions: Selected for applicable load criteria.

HANGERS AND SUPPORTS FOR COMMUNICATIONS SYSTEMS 270528.29 - 3

- B. Conduit and Cable Support Devices: Steel clamps, hangers, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- C. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for nonarmored communications conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be made of malleable iron.
- D. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M steel plates, shapes, and bars; black and galvanized.
- E. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
  - 1. Mechanical-Expansion Anchors: Insert-wedge-type zinc-coated steel for use in hardened portland cement concrete, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
    - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
      - 1) B-line, an Eaton business.
      - 2) Empire Tool and Manufacturing Co., Inc.
      - 3) Hilti, Inc.
      - 4) ITW Ramset/Red Head; Illinois Tool Works, Inc.
  - 2. Concrete Inserts: Steel or malleable-iron, slotted support system units are similar to MSS Type 18 units and comply with MFMA-4 or MSS SP-58.
  - 3. Clamps for Attachment to Steel Structural Elements: MSS SP-58 units are suitable for attached structural element.
  - 4. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
  - 5. Toggle Bolts: All-steel springhead type.
  - 6. Hanger Rods: Threaded steel.

# 2.3 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.
- B. Materials: Comply with requirements in Section 055000 "Metal Fabrications" for steel shapes and plates.

## PART 3 - EXECUTION

### 3.1 APPLICATION

- A. Comply with the following standards for application and installation requirements of hangers and supports, except where requirements on Drawings or in this Section are stricter:
  - 1. NECA 1.
  - 2. NECA/BICSI 568.
  - 3. TIA-569-D.
  - 4. NECA 101
- B. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping materials and installation for penetrations through fire-rated walls, ceilings, and assemblies.
- C. Comply with requirements for pathways specified in Section 270528 "Pathways for Communications Systems."
- D. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMTs, IMCs, and RMCs as required by NFPA 70. Minimum rod size shall be 1/4 inch in diameter.
- E. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
  - 1. Secure raceways and cables to these supports with two-bolt conduit clamps.

## 3.2 SUPPORT INSTALLATION

- A. Raceway Support Methods: In addition to methods described in NECA 1, EMT may be supported by openings through structure members, according to NFPA 70.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components, so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.
- C. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten communications items and their supports to building structural elements by the following methods unless otherwise indicated by code:
  - 1. To Wood: Fasten with lag screws or through bolts.
  - 2. To New Concrete: Bolt to concrete inserts.
  - 3. To Masonry: Use approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
  - 4. To Existing Concrete: Use expansion anchor fasteners.

### HANGERS AND SUPPORTS FOR COMMUNICATIONS SYSTEMS

270528.29 - 5

- 5. To Steel: Welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts.
- 6. To Light Steel: Sheet metal screws.
- 7. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate by means that comply with seismic-restraint strength and anchorage requirements.
- D. Drill holes for expansion anchors in concrete at locations and to depths that avoid the need for reinforcing bars.

### 3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Comply with installation requirements in Section 055000 "Metal Fabrications" for site-fabricated metal supports.
- B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor communications materials and equipment.
- C. Field Welding: Comply with AWS D1.1/D1.1M.

### 3.4 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
  - 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.
- B. Touchup: Comply with requirements in Section 099123 "Interior Painting" for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas, and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 270528.29

HANGERS AND SUPPORTS FOR COMMUNICATIONS SYSTEMS

# SECTION 270553 - IDENTIFICATION FOR COMMUNICATIONS SYSTEMS

PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

- A. Section Includes:
  - 1. Color and legend requirements for labels and signs.
  - 2. Labels.
  - 3. Tapes.
  - 4. Signs.
  - 5. Cable ties.
  - 6. Fasteners for labels and signs.

# 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for communications identification products.
- B. Samples: For each type of label and sign to illustrate composition, size, colors, lettering style, mounting provisions, and graphic features of identification products.
- C. Identification Schedule:
  - 1. Outlets: Scaled drawings indicating location and proposed designation.
  - 2. Backbone Cabling: Riser diagram showing each communications room, backbone cable, and proposed backbone cable designation.
  - 3. Racks: Scaled drawings indicating location and proposed designation.
  - 4. Patch Panels: Enlarged scaled drawings showing rack row, number, and proposed designations.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Comply with NFPA 70 and TIA 606-B.
- B. Comply with ANSI Z535.4 for safety signs and labels.
- C. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, shall comply with UL 969.
- D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.

### 2.2 COLOR AND LEGEND REQUIREMENTS

- A. Equipment Identification Labels:
  - 1. Black letters on a white field.
  - 2. The labels shall be machine generated
  - 3. B. Shall meet the legibility, defacement, exposure and adhesion requirements of UL 969
  - 4. Shall be preprinted or computer printed type. Hand written labels are not acceptable
  - 5. Where insert type labels are used provide clear plastic cover over label.

### 2.3 LABELS

- A. Vinyl Wraparound Labels: Preprinted, flexible labels laminated with a clear, weather- and chemical-resistant coating and matching wraparound clear adhesive tape for securing label ends.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Brady Corporation.
    - b. Champion America.
    - c. emedco.
    - d. Grafoplast Wire Markers.
    - e. HellermannTyton.
    - f. LEM Products Inc.
    - g. Marking Services, Inc.
    - h. Panduit Corp.
- B. Snap-Around Labels: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeves, with diameters sized to suit diameters of raceway or cable they identify, that stay in place by gripping action.

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Brady Corporation.
  - b. HellermannTyton.
  - c. Marking Services, Inc.
  - d. Panduit Corp.
- C. Self-Adhesive Wraparound Labels: Preprinted, 3-mil-thick, polyester flexible labels with acrylic pressure-sensitive adhesive.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Brady Corporation.
    - b. Brother International Corporation.
    - c. Ideal Industries, Inc.
    - d. Panduit Corp.
  - 2. Self-Lamination: Clear; UV-, weather- and chemical-resistant; self-laminating protective shields over the legend. Labels sized such that the clear shield overlaps the entire printed legend.
  - 3. Marker for Labels: Permanent, waterproof black ink marker recommended by tag manufacturer.
  - 4. Marker for Labels: Machine-printed, permanent, waterproof black ink recommended by printer manufacturer.
- D. Self-Adhesive Labels: Polyester, thermal, transfer-printed, 3-mil-thick, multicolor, weather- and UV-resistant, pressure-sensitive adhesive labels, configured for intended use and location.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Brady Corporation.
    - b. Brother International Corporation.
    - c. Ideal Industries, Inc.
    - d. Panduit Corp.
  - 2. Minimum Nominal Size:
    - a. 1-1/2 by 6 inches for raceway and conductors.
    - b. 3-1/2 by 5 inches for equipment.
    - c. As required by authorities having jurisdiction.

# 2.4 UNDERGROUND-LINE WARNING TAPE

A. See section 260553 for requirements.

## IDENTIFICATION FOR COMMUNICATIONS SYSTEMS

## 2.5 CABLE TIES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. HellermannTyton.
  - 2. Ideal Industries, Inc.
  - 3. Marking Services, Inc.
- B. General-Purpose Cable Ties: Fungus inert, self-extinguishing, one piece, self-locking, and Type 6/6 nylon.
  - 1. Minimum Width: 3/16 inch.
  - 2. Tensile Strength at 73 deg F according to ASTM D 638: 12,000 psi.
  - 3. Temperature Range: Minus 40 to plus 185 deg F.
  - 4. Color: Black, except where used for color-coding.

### PART 3 - EXECUTION

## 3.1 PREPARATION

A. Self-Adhesive Identification Products: Before applying communications identification products, clean substrates of substances that could impair bond, using materials and methods recommended by manufacturer of identification product.

## 3.2 INSTALLATION

- A. Follow BSD Labeling Scheme as follows:
  - 1. Frame room number Panel in Frame Port on Panel, MDF will be "Frame room 1". IDF 2 will be "Frame room 2 and will continue sequentially for any additional IDFs.
  - 2. Panels will start with "Panel 1" at the top on the Rack. If additional panels are needed in other racks, they will continue with sequential numbers.
  - 3. Port label will indicate port number position on that panel (i.e., F1-P2-26). No deviation from the district labeling scheme will be allowed.
  - 4. In telecommunications room where more than one rack is present, each rack shall receive a label starting left-to-right with "RACK-1", "RACK-2" as so forth.
- B. Horizontal (Station) Cables:
  - 1. All cables will be labeled the same at both ends. The tag shall be secured to the sheath no more than 4 inches from the end of the cable. Each end of the UTP horizontal cables shall be labeled with the nomenclature 'Fx-PP-NN'. Where x indicates the Frame room number, PP indicates the patch panel number, and NN indicates the port number.

- C. Fiber and Copper Backbone Cables:
  - 1. Cables shall be labeled "From" "To", specifically:
    - a. "From <Frame-1> to <Frame-2>", where "Frame-1" is the originating location and "Frame-2" is the destination.
- D. Work Area Outlets (WAO): Each WAO shall be labeled at the top of the modular jack enclosure with the Telecommunication Room ID (Frame room number) of the room where the cables are terminated, patch panel and the port number ('F#-P#-##') where the cable is being terminated.
- E. Where WAPs are placed in the drop in ceiling the grid shall be labeled with bold black lettering on white background with <sup>1</sup>/<sub>2</sub>" minimum font height.
- F. Verify and coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and operation and maintenance manual. Use consistent designations throughout Project.
- G. Install identifying devices before installing acoustical ceilings and similar concealment.
- H. Verify identity of each item before installing identification products.
- I. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and operation and maintenance manual.
- J. Apply identification devices to surfaces that require finish after completing finish work.
- K. Install signs with approved legend to facilitate proper identification, operation, and maintenance of communications systems and connected items.
- L. Elevated Components: Increase sizes of labels, signs, and letters to those appropriate for viewing from the floor.
- M. Vinyl Wraparound Labels:
  - 1. Secure tight to surface of raceway or cable at a location with high visibility and accessibility.
  - 2. Attach labels that are not self-adhesive type with clear vinyl tape, with adhesive appropriate to the location and substrate.
  - 3. Provide label 6 inches from cable end.
- N. Snap-Around Labels:
  - 1. Secure tight to surface at a location with high visibility and accessibility.
  - 2. Provide label 6 inches from cable end.

### IDENTIFICATION FOR COMMUNICATIONS SYSTEMS

- O. Self-Adhesive Wraparound Labels:
  - 1. Secure tight to surface at a location with high visibility and accessibility.
  - 2. Provide label 6 inches from cable end.
- P. Self-Adhesive Labels:
  - 1. On each item, install unique designation label that is consistent with wiring diagrams, schedules, and operation and maintenance manual.
  - 2. Unless otherwise indicated, provide a single line of text with 1/2-inch-high letters on 1-1/2-inch-high label; where two lines of text are required, use labels 2 inches high.
- Q. Snap-Around, Color-Coding Bands: Secure tight to surface at a location with high visibility and accessibility.
- R. Underground-Line Warning Tape:
  - 1. During backfilling of trenches, install continuous underground-line warning tape directly above cable or raceway at 6 to 8 inches below finished grade. Use multiple tapes where width of multiple lines installed in a common trench exceeds 16 inches overall.
  - 2. Limit use of underground-line warning tape to direct-buried cables.
  - 3. Install underground-line warning tape for direct-buried cables and cables in raceways.

### 3.3 IDENTIFICATION SCHEDULE

- A. Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment. Install access doors or panels to provide view of identifying devices.
- B. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, pull points, and locations with high visibility. Identify by system and circuit designation.
- C. Accessible Fittings for Raceways and Cables within Buildings: Identify covers of each junction and pull box with self-adhesive labels containing wiring system legend.
  - 1. System legends shall be as follows:
    - a. Telecommunications.
- D. Faceplates: Label individual faceplates with self-adhesive labels. Place label at top of faceplate. Each faceplate shall be labeled with its individual, sequential designation, numbered clockwise when entering room from primary egress, composed of the following, in the order listed:
  - 1. Wiring closet designation.
  - 2. Colon.
  - 3. Faceplate number.

## IDENTIFICATION FOR COMMUNICATIONS SYSTEMS

# E. Equipment Room Labeling:

- 1. Racks, Frames, and Enclosures: Identify front and rear of each with self-adhesive labels.
- 2. Patch Panels: Label individual rows in each rack, starting at top and working down, with self-adhesive labels.
- 3. Data Outlets: Label each outlet with a self-adhesive label indicating the following, in the order listed:
  - a. Room number being served.
  - b. Colon.
  - c. Faceplate number.
- F. Backbone Cables: Label each cable with a vinyl-wraparound label indicating the location of the far or other end of the backbone cable. Patch panel or punch down block where cable is terminated should be labeled identically.
- G. Horizontal Cables: Label each cable with a vinyl-wraparound label indicating the following, in the order listed:
  - 1. Room number.
  - 2. Colon.
  - 3. Faceplate number.
- H. Locations of Underground Lines: Underground-line warning tape for copper, coaxial, hybrid copper/fiber, and optical-fiber cable.
- I. Instructional Signs: Self-adhesive labels.
- J. Warning Labels for Indoor Cabinets, Boxes, and Enclosures: Self-adhesive labels.
  - 1. Apply to exterior of door, cover, or other access.
- K. Equipment Identification Labels:
  - 1. Indoor Equipment: Self-adhesive label.
  - 2. Outdoor Equipment: Laminated-acrylic or melamine-plastic sign 4 inches high.
  - 3. Equipment to Be Labeled:
    - a. Communications cabinets.
    - b. Uninterruptible power supplies.
    - c. Computer room air conditioners.
    - d. Fire-alarm and suppression equipment.
    - e. Egress points.
    - f. Power distribution components.

## END OF SECTION 270553

## IDENTIFICATION FOR COMMUNICATIONS SYSTEMS
# SECTION 271513 - COMMUNICATIONS COPPER HORIZONTAL CABLING

## PART 1 - GENERAL

### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

### 1.2 SUMMARY

#### A. Section Includes:

- 1. Category 6 twisted pair cable.
- 2. Category 6A twisted pair cable.
- 3. Twisted pair cable hardware, including plugs and jacks.
- 4. Multiuser telecommunications outlet assembly.
- 5. Cable management system.
- 6. Cabling identification products.
- 7. Grounding provisions for twisted pair cable.
- 8. Source quality control requirements for twisted pair cable.
- B. Related Requirements:
  - 1. Section 270513 "Conductors and Cables for Communications Systems" for data cabling associated with system panels and devices.

#### 1.3 DEFINITIONS

- A. Cross-Connect: A facility enabling the termination of cable elements and their interconnection or cross-connection.
- B. EMI: Electromagnetic interference.
- C. FTP: Shielded twisted pair.
- D. F/FTP: Overall foil screened cable with foil screened twisted pair.
- E. F/UTP: Overall foil screened cable with unscreened twisted pair.
- F. IDC: Insulation displacement connector.
- G. LAN: Local area network.
- H. Jack: Also commonly called an "outlet," it is the fixed, female connector.

#### COMMUNICATIONS COPPER HORIZONTAL CABLING

- I. Plug: Also commonly called a "connector," it is the removable, male telecommunications connector.
- J. RCDD: Registered Communications Distribution Designer.
- K. Screen: A metallic layer, either a foil or braid, placed around a pair or group of conductors.
- L. Shield: A metallic layer, either a foil or braid, placed around a pair or group of conductors.
- M. S/FTP: Overall braid screened cable with foil screened twisted pair.
- N. S/UTP: Overall braid screened cable with unscreened twisted pairs.
- O. UTP: Unscreened (unshielded) twisted pair.

## 1.4 COPPER HORIZONTAL CABLING DESCRIPTION

- A. Horizontal cable cabling system shall provide interconnections between Distributor A, Distributor B, or Distributor C, and the equipment outlet, otherwise known as "Cabling Subsystem 1," in the telecommunications cabling system structure. Cabling system consists of horizontal cables, intermediate and main cross-connects, mechanical terminations, and patch cords or jumpers used for horizontal-to-horizontal cross-connection.
  - 1. TIA-568-C.1 requires that a minimum of two equipment outlets be installed for each work area.
  - 2. Horizontal cabling shall contain no more than one transition point or consolidation point between the horizontal cross-connect and the telecommunications equipment outlet.
  - 3. Bridged taps and splices shall not be installed in the horizontal cabling.
- B. A work area is approximately 100 sq. ft. and includes the components that extend from the equipment outlets to the station equipment.
- C. The maximum allowable horizontal cable length is 295 feet. This maximum allowable length does not include an allowance for the length of 16 feet to the workstation equipment or in the horizontal cross-connect.

## 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Reviewed and stamped by RCDD.
  - 1. System Labeling Schedules: Electronic copy of labeling schedules, in software and format selected by Owner.
  - 2. System Labeling Schedules: Electronic copy of labeling schedules that are part of the cabling and asset identification system of the software.
  - 3. Cabling administration Drawings and printouts.

## COMMUNICATIONS COPPER HORIZONTAL CABLING

- 4. Wiring diagrams and installation details of telecommunications equipment, to show location and layout of telecommunications equipment, including the following:
  - a. Telecommunications rooms plans and elevations.
  - b. Telecommunications pathways.
  - c. Telecommunications system access points.
  - d. Telecommunications grounding system.
  - e. Telecommunications conductor drop locations.
  - f. Typical telecommunications details.
- C. Twisted pair cable testing plan.

# 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer, installation supervisor, and field inspector.
- B. Product Certificates: For each type of product.
- C. Source quality-control reports.
- D. Field quality-control reports.

# 1.7 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For splices and connectors to include in maintenance manuals.
- B. Software and Firmware Operational Documentation:
  - 1. Software operating and upgrade manuals.
  - 2. Program Software Backup: On USB media or compact disk, complete with data files.
  - 3. Device address list.
  - 4. Printout of software application and graphic screens.

# 1.8 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Connecting Blocks: one of each type.
  - 2. Faceplates: one of each type.
  - 3. Jacks: Ten of each type.

## 1.9 QUALITY ASSURANCE

- A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.
  - 1. Layout Responsibility: Preparation of Shop Drawings and cabling administration Drawings by an RCDD.
  - 2. Installation Supervision: Installation shall be under the direct supervision of Technician, who shall be present at all times when Work of this Section is performed at Project site.
  - 3. Testing Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.
- B. Testing Agency Qualifications: Testing agency must have personnel certified by BICSI on staff.
  - 1. Testing Agency's Field Supervisor: Currently certified by BICSI as an RCDD.

# 1.10 DELIVERY, STORAGE, AND HANDLING

- A. Test cables upon receipt at Project site.
  - 1. Test each pair of twisted pair cable for open and short circuits.

### 1.11 PROJECT CONDITIONS

A. Environmental Limitations: Do not deliver or install cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

## 1.12 COORDINATION

A. Coordinate layout and installation of telecommunications pathways and cabling with Owner's telecommunications and LAN equipment and service suppliers.

#### 1.13 SOFTWARE SERVICE AGREEMENT

- A. Technical Support: Beginning with Substantial Completion, provide software support for two years.
- B. Upgrade Service: Update software to latest version at Project completion. Install and program software upgrades that become available within two years from date of Substantial Completion. Upgrading software shall include operating system. Upgrade shall include new or revised licenses for use of software.
  - 1. Provide 30 days' notice to Owner to allow scheduling and access to system and to allow Owner to upgrade computer equipment if necessary.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. General Performance: Horizontal cabling system shall comply with transmission standards in TIA-568-C.1, when tested according to test procedures of this standard.
- B. Telecommunications Pathways and Spaces: Comply with TIA-569-D.
- C. Grounding: Comply with TIA-607-B.

## 2.2 GENERAL CABLE CHARACTERISTICS

- A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with the applicable standard and NFPA 70 for the following types:
  - 1. Communications, Plenum Rated: Type CMP complying with UL 1685 or Type CMP in listed plenum communications raceway.
  - 2. Communications, Plenum Rated: Type CM, Type CMG, Type CMP, Type CMR, or Type CMX in metallic conduit installed according to NFPA 70, Article 300.22, "Wiring in Ducts, Plenums, and Other Air-Handling Spaces."
  - 3. Communications, Non-plenum: Type CMR complying with UL 1666.
- B. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Flame-Spread Index: 25 or less.
  - 2. Smoke-Developed Index: 50 or less.
- C. RoHS compliant.

### 2.3 CATEGORY 6 TWISTED PAIR CABLE

- A. Description: Four-pair, balanced-twisted pair cable certified to meet transmission characteristics of Category 6 cable at frequencies up to 250MHz.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. AMP NETCONNECT; a TE Connectivity Ltd. company.
  - 2. Belden CDT Networking Division/NORDX.
  - 3. Berk-Tek Leviton; a Nexans/Leviton alliance.
  - 4. CommScope, Inc.
  - 5. General Cable; General Cable Corporation.
  - 6. Hitachi Cable America Inc.
  - 7. Mohawk; a division of Belden Networking, Inc.
  - 8. Superior Essex Inc.

- C. Standard: Comply with NEMA WC 66/ICEA S-116-732 and TIA-568-C.2 for Category 6 cables.
- D. Conductors: 100-ohm, 23 AWG solid copper.
- E. Shielding/Screening: Unshielded twisted pairs (UTP).
- F. Cable Rating: Plenum.
- G. Jacket: White for Wifi thermoplastic.

## 2.4 TWISTED PAIR CABLE HARDWARE

- A. Description: Hardware designed to connect, splice, and terminate twisted pair copper communications cable.
- B. General Requirements for Twisted Pair Cable Hardware:
  - 1. Comply with the performance requirements of Category 6 and Category 6A.
  - 2. Comply with TIA-568-C.2, IDC type, with modules designed for punch-down caps or tools.
  - 3. Cables shall be terminated with connecting hardware of same category or higher.
- C. Source Limitations: Obtain twisted pair cable hardware from single source from single manufacturer.
- D. Cross-Connect: Modular array of connecting blocks arranged to terminate building cables and permit interconnection between cables.
  - 1. Number of Terminals per Field: One for each conductor in assigned cables.
- E. Patch Panel: Modular panels housing numbered jack units with IDC-type connectors at each jack location for permanent termination of pair groups of installed cables.
  - 1. Features:
    - a. Universal T568A and T568B wiring labels.
    - b. Labeling areas adjacent to conductors.
    - c. Replaceable connectors.
    - d. 24 or 48 ports.
  - 2. Construction: 16-gauge steel and mountable on 19-inch equipment racks.
  - 3. Number of Jacks per Field: One for each four-pair cable indicated.
- F. Patch Cords: Factory-made, four-pair cables; terminated with an eight-position modular plug at each end.
  - 1. Patch cords shall have bend-relief-compliant boots and color-coded icons to ensure performance. Patch cords shall have latch guards to protect against snagging.

- 2. Patch cords shall have color-coded boots for circuit identification.
  - a. Data Grey
  - b. VoIP Green
  - c. WAP White
  - d. IP based management systems
    - 1) HVAC Black
    - 2) Lighting Blue
    - 3) Specialty, Stage Orange
    - 4) Paging Pink
    - 5) Mechanical Purple
    - 6) AV systems Green
    - 7) Security Red
- G. Plugs and Plug Assemblies:
  - 1. Male; eight position; color-coded modular telecommunications connector designed for termination of a single four-pair, 100-ohm, unshielded or shielded twisted pair cable.
  - 2. Standard: Comply with TIA-568-C.2.
  - 3. Marked to indicate transmission performance.
- H. Jacks and Jack Assemblies:
  - 1. Female; eight position; modular; fixed telecommunications connector designed for termination of a single four-pair, 100-ohm, unshielded or shielded twisted pair cable.
  - 2. Designed to snap-in to a patch panel or faceplate.
  - 3. Standard: Comply with TIA-568-C.2.
  - 4. Standard Duplex locations to have one Orange and one Ivory jack.
  - 5. Marked to indicate transmission performance.
- I. Faceplate:
  - 1. Two port, vertical single gang faceplates designed to mount to single gang wall boxes.
  - 2. Faceplate: Coordinate color with Section 262726 "Wiring Devices."
  - 3. For use with snap-in jacks accommodating any combination of twisted pair, optical fiber, and coaxial work area cords.
    - a. Flush mounting jacks, positioning the cord at a 45-degree angle.
- J. Legend:
  - 1. Machine printed, in the field, using adhesive-tape label.
  - 2. Snap-in, clear-label covers and machine-printed paper inserts.
- K. All standard workstation outlets shall be Cat 6 and all outlets for WAP shall be Cat 6A.

## 2.5 IDENTIFICATION PRODUCTS

A. Comply with TIA-606-B and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.

#### 2.6 GROUNDING

- A. Comply with requirements in Section 270526 "Grounding and Bonding for Communications Systems" for grounding conductors and connectors.
- B. Comply with TIA-607-B.

### 2.7 SOURCE QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to evaluate cables.
- B. Factory test cables on reels according to TIA-568-C.1.
- C. Factory test twisted pair cables according to TIA-568-C.2.
- D. Cable will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

## PART 3 - EXECUTION

#### 3.1 WIRING METHODS

- A. Wiring Method: Install cables in raceways and cable trays, except within consoles, cabinets, desks, and counters. Conceal raceway and cables, except in unfinished spaces.
  - 1. Install plenum cable in environmental air spaces, including plenum ceilings.
  - 2. Comply with requirements for raceways and boxes specified in Section 270528 "Pathways for Communications Systems."
- B. Wiring Method: Conceal conductors and cables in accessible ceilings, walls, and floors where possible.
- C. Wiring within Enclosures: Bundle, lace, and train cables within enclosures. Connect to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools. Install conductors parallel with or at right angles to sides and back of enclosure.

## 3.2 INSTALLATION OF PATHWAYS

- A. Comply with requirements for demarcation point, cabinets, and racks specified in Section 271100 "Communications Equipment Room Fittings."
- B. Comply with Section 270528 "Pathways for Communications Systems."
- C. Comply with Section 270528.29 "Hangers and Supports for Communications Systems."
- D. Comply with Section 270536 "Cable Trays for Communications Systems."
- E. Drawings indicate general arrangement of pathways and fittings.

### 3.3 INSTALLATION OF TWISTED-PAIR HORIZONTAL CABLES

- A. Comply with NECA 1 and NECA/BICSI 568.
- B. General Requirements for Cabling:
  - 1. Comply with TIA-568-C.0, TIA-568-C.1, and TIA-568-C.2.
  - 2. Comply with BICSI's "Information Transport Systems Installation Methods Manual (ITSIMM), Ch. 5, "Copper Structured Cabling Systems," "Cable Termination Practices" Section.
  - 3. Do not untwist twisted pair cables more than 1/2 inch from the point of termination to maintain cable geometry.
  - 4. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.
  - 5. MUTOA shall not be used as a cross-connect point.
  - 6. Consolidation points may be used only for making a direct connection to equipment outlets:
    - a. Do not use consolidation point as a cross-connect point, as a patch connection, or for direct connection to workstation equipment.
    - b. Locate consolidation points for twisted-pair cables at least 49 feet from communications equipment room.
  - 7. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
  - 8. Install lacing bars to restrain cables, prevent straining connections, and prevent bending cables to smaller radii than minimums recommended by manufacturer.
  - 9. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI Information Transport Systems Installation Methods Manual, Ch. 5, "Copper Structured Cabling Systems," "Cable Termination Practices" Section. Use lacing bars and distribution spools.
  - 10. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation, and replace it with new cable.

- 11. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
- 12. In the communications equipment room, install a 10-foot- long service loop on each end of cable.
- 13. Pulling Cable: Comply with BICSI Information Transport Systems Installation Methods Manual, Ch. 5, "Copper Structured Cabling Systems," "Pulling and Installing Cable" Section. Monitor cable pull tensions.
- C. Open-Cable Installation:
  - 1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
  - 2. Suspend twisted pair cabling, not in a wireway or pathway, a minimum of 8 inches above ceilings by cable supports not more than 60 inches apart.
  - 3. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.
- D. Group connecting hardware for cables into separate logical fields.
- E. Separation from EMI Sources:
  - 1. Comply with recommendations from BICSI's "Telecommunications Distribution Methods Manual" and TIA-569-D for separating unshielded copper communication cable from potential EMI sources, including electrical power lines and equipment.
  - 2. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
    - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
    - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
    - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.
  - 3. Separation between communications cables in grounded metallic raceways, power lines, and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
    - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
    - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
    - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.
  - 4. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches.
  - 5. Separation between Communications Cables and Fluorescent Fixtures: A minimum of 5 inches.

## 3.4 FIRESTOPPING

- A. Comply with requirements in Section 078413 "Penetration Firestopping."
- B. Comply with TIA-569-D, Annex A, "Firestopping."

# COMMUNICATIONS COPPER HORIZONTAL CABLING

C. Comply with "Firestopping Systems" Article in BISCI's "Telecommunications Distribution Methods Manual."

### 3.5 GROUNDING

- A. Install grounding according to the "Grounding, Bonding, and Electrical Protection" chapter in BICSI's "Telecommunications Distribution Methods Manual."
- B. Comply with TIA-607-B and NECA/BICSI-607.
- C. Locate grounding bus bar to minimize the length of bonding conductors. Fasten to wall, allowing at least a 2-inch clearance behind the grounding bus bar. Connect grounding bus bar to suitable electrical building ground, using a minimum No. 4 AWG grounding electrode conductor.
- D. Bond metallic equipment to the grounding bus bar, using not smaller than a No. 6 AWG equipment grounding conductor.

## 3.6 IDENTIFICATION

- A. Identify system components, wiring, and cabling complying with TIA-606-B. Comply with requirements for identification specified in Section 270553 "Identification for Communications Systems."
- B. Cable Schedule: Install in a prominent location in each equipment room and wiring closet. List incoming and outgoing cables and their designations, origins, and destinations. Protect with rigid frame and clear plastic cover. Furnish an electronic copy of final comprehensive schedules for Project.
- C. Cabling Administration Drawings: Show building floor plans with cabling administration-point labeling. Identify labeling convention and show labels for telecommunications closets, terminal hardware and positions, horizontal cables, work areas and workstation terminal positions, grounding buses and pathways, and equipment grounding conductors.
- D. Cable and Wire Identification:
  - 1. Label each cable within 4 inches of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
  - 2. Each wire connected to building-mounted devices is not required to be numbered at the device if wire color is consistent with associated wire connected and numbered within panel or cabinet.
  - 3. Exposed Cables and Cables in Cable Trays and Wire Troughs: Label each cable at intervals not exceeding 15 feet.
  - 4. Label each terminal strip, and screw terminal in each cabinet, rack, or panel.
    - a. Individually number wiring conductors connected to terminal strips, and identify each cable or wiring group, extended from a panel or cabinet to a buildingmounted device, with the name and number of a particular device.

COMMUNICATIONS COPPER HORIZONTAL CABLING

- b. Label each unit and field within distribution racks and frames.
- 5. Identification within Connector Fields in Equipment Rooms and Wiring Closets: Label each connector and each discrete unit of cable-terminating and -connecting hardware. Where similar jacks and plugs are used for both voice and data communication cabling, use a different color for jacks and plugs of each service.
- E. Labels shall be preprinted or computer-printed type, with a printing area and font color that contrast with cable jacket color but still comply with TIA-606-B requirements for the following:
  - 1. Cables use flexible vinyl or polyester that flexes as cables are bent.

## 3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections.
- E. Tests and Inspections:
  - 1. Visually inspect jacket materials for NRTL certification markings. Inspect cabling terminations in communications equipment rooms for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA-568-C.1.
  - 2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
  - 3. Test twisted pair cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross-connection.
    - a. Test instruments shall meet or exceed applicable requirements in TIA-568-C.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
- F. Data for each measurement shall be documented. Data for submittals shall be printed in a summary report that is formatted similarly to Table 10.1 in BICSI's "Telecommunications Distribution Methods Manual," or shall be transferred from the instrument to the computer, saved as text files, printed, and submitted.
- G. Remove and replace cabling where test results indicate that they do not comply with specified requirements.

- H. End-to-end cabling will be considered defective if it does not pass tests and inspections.
- I. Prepare test and inspection reports.

END OF SECTION 271513

## SECTION 274100 - AUDIO-VIDEO SYSTEMS

### PART 1 - GENERAL

### 1.1 WORK INCLUDED

A. This project will include installation of classroom A/V Systems. Components may be, furnished by this contract or Owner Furnished, Contractor Installed as specified or as shown on Drawings.

### 1.2 RELATED SECTIONS

- A. Section 270000 Communications
- B. Section 270500 Common Work Results for Communications
- C. Section 270526 Grounding and Bonding for Communications Systems
- D. Section 270528 Pathways for Communications Systems
- E. Section 270528.29 Hangers and Support for Communications Systems
- F. Section 274123 Audio-Video Accessories

## 1.3 CLASSROOM AUDIO PRODUCT CONTACT

A. Classroom audio (sound reinforcement) components shall be from LightSPEED Technologies. Contact for this project is:

LightSPEED Classroom Audio Consultant 11509 SW Herman Road Tualatin, Oregon 97062

### 1.4 VIDEO SYSTEM

- A. Instructional areas (gym, commons, music room, library) shall have projection capabilities and supporting infrastructure.
- B. All classrooms and conference rooms shall have TV displays and supporting infrastructure.

### 1.5 CLASSROOM AUDIO CABLING

A. Cables shall terminate in the classroom audio faceplate, as shown on drawings.

### 1.6 CABLE RACEWAYS

A. All raceway routing and mounting height information shall be coordinated with the Electrical and Architectural Drawings.

### 1.7 SYSTEM CONTROL

- A. The operation shall be automated through the Owner provided classroom computer and projector remote control and shall not, typically, require adjustments or user intervention.
- B. Audio Visual Playback System shall be capable of playing DVD/PC based media, from Owner provided source equipment.

### PART 2 - PRODUCTS

## 2.1 SOUND REINFORCEMENT UNITS

- A. Classrooms will receive a sound reinforcement system. Units will be LightSPEED 955. Systems will include PageFirst<sup>™</sup> option.
  - 1. System are to be placed as per drawings.
  - 2. System shall include LightSPEED Media Connector.
  - 3. Ceiling mount speakers are to be placed as per drawings. Speaker assembly consists of the following Atlas components:
    - a. Speaker (FA-136)
    - b. Back can (FA95-6)
    - c. Tile support (FA81-6)
    - d. Speaker grille (FA51-6)
  - 4. Wall mount speakers are to be placed as per drawings. Lightspeed WMQ or approved.
  - 5. Include power supply, and cables, Media Connector and speakers.
  - 6. One Flexmike volume control lanyard microphone and one Sharemike handheld classroom microphone, with batteries and charger.
  - 7. System shall include LightSPEED PageFirst<sup>TM</sup> Option.

## 2.2 ANCILLARY COMPONENTS

A. Supply all ancillary cables, patch cords and adapters necessary to provide a completely functional system. See Section 27 41 23 Audio-Video Accessories for additional information.

# PART 3 - EXECUTION

### 3.1 GENERAL

- A. A complete system shall be installed in strict accordance with manufacturer's recommendations.
- B. All wiring shall be installed in raceways within walls where at all possible. Exposed cabling is not acceptable.
- C. All wiring shall be plenum rated, where routed through plenum ceiling areas.

### 3.2 CERTIFIED INSTALLATION CONTRACTOR REQUIREMENT

A. All LightSPEED components to be installed by a certified contractor to preserve factory warranty.

### 3.3 CABLE PLACEMENT AND PATHWAYS

- A. All cables must be completely enclosed (or above the dropped ceiling where applicable).
- **B**. Cables may be run in the area above the dropped ceiling. In such areas, cables are to be supported by Caddy<sup>®</sup> fasteners / hangers at intervals not exceeding 48 inches.

### 3.4 INSPECTION AND TEST UPON COMPLETION

- A. Check-out and final connections to the audio system shall be made by a factory trained technician certified by the manufacturer of the products installed. In addition, factory trained technicians shall demonstrate operation of the complete system and each major component to the Owner.
- **B.** System field wiring diagrams shall be provided to this subcontractor by the system manufacturer prior to installation.
- C. Training this contract shall provide training for not less than three District staff members. Training will include all aspects of the system as well as complete documentation covering all components requiring operator control or intervention.

## 3.5 WARRANTY

- A. All materials and installation shall be guaranteed for a minimum of one year from installation. Warranty work will be performed "on-site" at no cost to the Owner.
- B. Upon completion of the installation, two (2) copies of complete operational instructions shall be furnished. Instructions shall include part numbers and names, addresses, and telephone numbers of parts source.

- C. Upon completion of the installation of the equipment, the Contractor shall provide to the Owner a signed statement from the equipment supplier that the system has been wired, tested, and functions properly according to the specifications.
- D. Nothing herein contained shall be construed to relieve the Contractor from furnishing a complete and acceptable electrical wiring system in all its categories. The Owner or the Owner's Representative will condemn and reject any materials or labor which are or may become detrimental to the accomplishment of the intentions of these specifications.

END OF SECTION 274100

## SECTION 274123 - AUDIO-VIDEO ACCESSORIES

### PART 1 - GENERAL

### 1.1 SYSTEM OVERVIEW

- A. This project will include installation of multiple projectors as called out on the drawings. The mounting brackets and projectors will be Owner Furnished, Contractor Installed.
- **B**. Procure and supply components to provide a complete connectivity solution between the projector and presentation station location annotated on the drawings.

### 1.2 DEVICE REQUIREMENTS

- A. The projector will be connected to power via supplied cord. Coordinate power on testing and focusing with Owner.
- 1.3 Related Sections
  - A. Section 270000 Communications
  - B. Section 270500 Common Work Results for Communications
  - C. Section 270528 Pathways for Communications Systems
  - D. Section 270528.29 Hangers and Support for Communications Systems
  - E. Section 270553 Identification for Communication Systems
  - F. Section 271513 Communications Copper Horizontal Cabling
  - G. Section 274100 Audio-Video Systems

# 1.4 PRESENTATION STATION BACKBOXES

A. Backboxes are those mounted as shown on the drawings.

#### AUDIO-VIDEO ACCESSORIES

## PART 2 - PRODUCTS

### 2.1 DEVICE MOUNTS AND INSTALLATION

- A. This contract shall supply:
  - 1. Extron PCM 340. The PCM 340 is a mounting kit for suspending projectors from an ACT ceiling. One each per display location as shown on drawings.s
  - 2. Extron USFM 100. The USFM 100 is a mounting kit for suspending ultra-short throw projectors from a wall. One each per display location as shown on drawings.
  - 3. Extron UPB 125 universal projector bracket. One each per display location as shown on drawings.
- B. Elevation details to be coordinated with Architect and Electrical Engineer in each location prior to mounting.

### 2.2 AUDIO CABLING

- A. Audio cable as shown on the drawings. Field verify final placement prior to installation. Provide one set of cable assemblies per room.
- B. Stereo audio connection between the presenter location and the LightSPEED Amplifier.
- C. Stereo audio connection between the classroom projector and the LightSPEED Amplifier,

#### 2.3 VIDEO CABLING

- A. Video cable as shown on the Drawings. Provide one set of cable assemblies per room.
- B. Category 6 cable and extenders as required:
  - 1. Hubbell HDMI 1080P Extender, #IMH110ST2W
  - 2. Hubbell USB Extender, #IMU1101W
  - 3. Hubbell VGA Extender, #IMU15311015W
  - 4. Hubbell RCA Left/Right Audio Extender, #IMAR101W
- C. Blank inserts as required, #IMB05W Blank, white, Package of 5.
- D. Category 6 cable between each projector and the closest Telecommunications Room.

#### AUDIO-VIDEO ACCESSORIES

## WESTVIEW HIGH SCHOOL CULINARY CLASSROOM BEAVERTON SCHOOL DISTRICT PORTLAND, OREGON

## 2.4 PATCH CORDS

- A. Provide the following patch cords:
  - 1. RCA Stereo Audio Patch Cords (Red/White connector)

Length	3'	7'
Quantity	35	15

2. HDMI Patch Cords

Length	3'	7'
Quantity	35	15

# PART 3 - EXECUTION

## 3.1 GENERAL

- A. A complete system shall be installed in accordance with manufacturer's recommendations.
- B. Wiring shall be in raceways within walls. Surface mounted raceway is not acceptable
- C. All wiring shall be plenum rated, where routed through plenum ceiling areas.

## 3.2 PROJECTOR BRACKET

A. Mount as per manufacturer's instructions supplied with mounting kit.

# 3.3 CABLE PLACEMENT, PATHWAYS AND PATCHING

- A. All cables must be completely enclosed (or above the dropped ceiling where applicable) except for the patch cables that transition between the faceplate and the Device.
- B. Cables may be run in the area above the dropped ceiling. In such areas, cables are to be supported by Caddy<sup>®</sup> fasteners / hangers at intervals not exceeding 48 inches. Extra slack shall not be "stored" exposed at the projector.
- C. Patch HDMI and RCA cords between the wall place and the device at each location.
- D. The display will have an Ethernet connection. This contract shall connect the device to the telecommunications outlet.
- E. This contract shall connect an audio output from this device to an audio input on the LightSPEED 885.

## AUDIO-VIDEO ACCESSORIES

F. This contract shall extend HDMI, VGA, USB and two RCA inputs from a presentation station to the inputs on this device. See drawings for additional details.

# 3.4 INSPECTION AND TEST UPON COMPLETION

- A. All audio and video connections shall be tested, specifically
  - 1. By means of a HDMI enabled device connected to the projector
  - 2. By means of a VGA/PC video signal connected to the projector
  - 3. By means of a USB signal to the projector

### 3.5 SYSTEM DOCUMENTATION AND AS-BUILTS

A. Contractor shall provide a complete set of system documentation bound into a three-ring manual with a table of contents and tabs for each piece of equipment. As-built documentation shall be generated in AutoCAD<sup>®</sup> version 2010 or later and provided in hard copy as well as electronically on CD.

### 3.6 WARRANTY

- A. All materials and installation shall be guaranteed for a minimum of one year from installation. Warranty work will be performed "on-site" at no cost to the Owner.
- B. Nothing herein contained shall be construed to relieve the Contractor from furnishing a complete and acceptable electrical wiring system in all its categories. The Owner or the Owner's Representative will condemn and reject any materials or labor which are or may become detrimental to the accomplishment of the intentions of these specifications.

END OF SECTION 274123