

May 13, 2021

SOLICITATION ADDENDUM NO. 1

ITB 20-0041

Aloha High School Commons and K Hall Reroofing Project

THE FOLLOWING CHANGES/ADDITIONS TO THE ABOVE CITED SOLICITATION ARE ANNOUNCED:

This Addendum modifies the Invitation to Bid (ITB) document(s) only to the extent indicated herein. All other areas not changed or otherwise modified by this Addendum shall remain in full force and effect. This Addendum is hereby made an integral part of the ITB document. Bidder must be responsive to any requirements of this Addendum as if the requirements were set forth in the ITB. Failure to do so may result in Bid rejection. See the ITB regarding requests for clarification or change and protests of this Addendum, and the deadlines for the foregoing.

This addendum is to be acknowledged in the space provided on the Bidder Certification form supplied in the solicitation document. Failure to acknowledge receipt of this addendum may be cause to reject your offer.

The closing date **IS UNCHANGED:**
May 18, 2021 at 2:00 PM Pacific Time

CHANGES:

- 1) ATTACHMENT J DRAWINGS are hereby changed as detailed in the clarifications issued by PRC, which are attached to this Addendum 1 as "Drawing Revisions".**
- 2) The attached "AHS Snap Report" is included with the Solicitation for Bidders' information. The AHS Snap Report is not required to be returned with Bids.**
- 3) Alternate 1 and Alternate 2 noted on ATTACHMENT B BID SCHEDULE are a mandatory part of the Solicitation. At its discretion, the District may select either or both of the Alternates either before or after Contract execution. Selection after Contract execution shall be only occur by change order or change directive. If any alternates are selected prior to Contract Award, they shall be considered in Bid Evaluation per the Solicitation instructions.**

CLARIFICATIONS:

Question: Is there an asbestos report available?

Answer: Please see the attached AHS Snap Report.

Question: Is there an asbestos report available?

Answer: Please see the attached AHS Snap Report.

Drawing Revisions


Date: May 11, 2021

Beaverton School District / Aloha High School Partial Roof Replacement Project

This addendum is being issued for clarification and / or revision of the Contract Documents as noted. This document is hereby made a part of the Contract Documents to the extent as though it was originally included herein.

Bidder shall notify all sub-bidders of this addendum, and shall acknowledge receipt of this addendum by inserting the above addendum number in the space provided on the bid form prior to submitting bids. Failure to acknowledge receipt of any addendum may subject the bidder to disqualification.

The following are clarifications to the Contract Documents:

Item	Reference	Description
1.01	<i>Drawing R100</i>	Keynote #6: Add the following text: Replace existing support blocks at base of UNISTRUT supports and conduit (typical of 6 locations). Basis of Design: Miro Industries – 20-BS-4.
1.02	<i>General Information, Detail Clarification</i>	<p>Install spray foam insulation within utility line wall chase located at the NE corner of Area U (shown at right). Trim insulation flush with face of wall.</p>  <p>Install new base flashing to underside of wall chase; terminate flashing sheet per manufacturer.</p>

PROFESSIONAL ROOF CONSULTANTS, INC.

ASBESTOS MATERIALS



The following materials either tested positive or are presumed to be asbestos-containing. Materials that had mixed results are considered positive. Materials not sampled or not listed in this report may contain asbestos and should be tested to verify asbestos content prior to impact, demolition, renovation, etc.

(+) Tested Positive, (M) Mixed Results, (P) Presumed Positive

Aloha High (AHS)			
Result	Material	Location	Quantity
+	Mastic	A-10F; east wall entry of north tiled cut out, mastic on ceramic tile	0
+	Mastic	C-hall; north wall, brown mastic	0
+	Gypsum wallboard	J-Hall Practice Room #2	0
+	gypsum wallboard with joint compound	J-Hall Practice Room #2	0
+	Gypsum Wallboard	J-Hall Practice Room 2; sheetrock	0
+	Gypsum Wallboard/Joint Compound	J-Hall Practice Room 2; sheetrock tape and joint compound	0
+	Vinyl Floor Tile/Mastic	L Hall; outside locker rooms, 12"x12" brown vinyl floor tile with black mastic	0
+	Joint Compound with Gypsum Wallboard / Visible Postive / Cmnt: less than one percent asbestos in joint compound	Level 1 / Boiler Room	999 nq
+	Gypsum Wallboard/Joint Compound	Library, north wall	0
+	Mastic	Lobby #00; south of special education #101 (area 2), black amstic under tact boards	0
+	Mastic	Northeast corner of room A-08 (area 2); brown mastic under 12"x12" wall panels	0
+	Mastic	Room A-08 (area 2); black mastic beneath white boards	0
+	Mastic	Room A-10-B; east wall, southeast corner, black mastic, beneath white boards	0
+	Mastic	Room C-10; west wall under tact board (area 1); black mastic	0
M	Covebase/Mastic	Vice principal office 2; 4" tan covebase with brown mastic	0
M	Gypsum Wallboard/Joint Compound	Vice principal office 2; northeast corner, gypsum/joint compound	0
M	Gypsum Wallboard/Joint Compound	Vice principal office 2; northwest corner, gypsum/joint compound	0
M	Gypsum Wallboard/Joint Compound	Vice principal office 2; southeast corner, gypsum/joint compound	0

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
+	Mastic	A-10F; east wall entry of north tiled cut out, mastic on ceramic tile	0
+	Joint Compound / Less than 1 % joint compound skim coat on CMU	A-14	999 nq
+	Heat Resistant Tape	Above Auditorium	1000 lf
+	Hard Fittings/Fiberglass	Above ceiling in corridor near room A-8; mudded fitting and canvas debris	0
M	Gypsum Wallboard/Joint Compound	Aloha HS; office 12, gypsum and joint compound	0
M	Gypsum Wallboard/Joint Compound	Aloha HS; office 13, gypsum and joint compound wall	0
M	Gypsum Wallboard/Joint Compound	Aloha HS; room J-3, gypsum and joint compound wall	0
+	Gypsum Wallboard/Joint Compound	Area 1; central office, gypsum joint compound wall system	0
+	Vinyl Floor Tile/Mastic	Area 1; middle office, pink hue 12"x12" streaked vinyl tile with black mastic	0
+	Vinyl Floor Tile/Mastic	Area 1; Room C10, cream 12"x12" streaked vinyl tile with black mastic	0
+	Gypsum Wallboard/Joint Compound	Area 1; Room C10, gypsum joint compound wall system	0
+	Vinyl Floor Tile/Mastic	Area 1; Room C8, cream 12"x12" streaked vinyl tile with black mastic	0
+	Gypsum Wallboard/Joint Compound	Area 1; Room C8, gypsum joint compound wall system	0
+	Vinyl Floor Tile/Mastic	Area 2; CAD room, cream 12"X12" vinyl tile with black mastic	0
+	Vinyl Floor Tile/Mastic	Area 2; Room 106, cream 12"X12" vinyl tile with black mastic	0
+	Gypsum Wallboard	Area 2; Room 106, gypsum joint compound wall system	0
+	Gypsum Wallboard	Area 2; shop mezzanine east, gypsum joint compound wall system	0
+	Vinyl Floor Tile/Mastic	Area 2; woodshop office, tan 12"X12" vinyl tile with black mastic	0
M	Mastic / Brown mastic associated with glued ceiling tiles / less than 1%	Auditorium / music area hallways	999 nq
+	Dark Beige Floor Tile and Associated Mastic	Auditorium Floor	500 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
+	Tan Floor Tile (with streaks and spots) and associated Mastic	Auditorium Floor	1000 sf
+	Glue associated with Non-ACM Containing white acoustical Tiles	Auditorium Walls	2800 sf
+	Mastic	C-hall; north wall, brown mastic	0
+	Wood Grain Wall Panel & Associated Glue	Hallway at Room C-6	
+	Vinyl Floor Tile/Mastic	J-1 entryway; tan 12" tile with black mastic	0
+	Vinyl Floor Tile/Mastic	L Hall; outside locker rooms, 12"x12" brown vinyl floor tile with black mastic	0
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22958]	Level 1 / 103 Office	103 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22959]	Level 1 / 104 Control	77 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: separated and cracked [ID: 22960]	Level 1 / 105 Office	162 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / A10 Office) [ID: 22973]	Level 1 / 116 Office	63 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Covebase down, exposed mastic [ID: 23071]	Level 1 / 118 Girl's Dressing Room	260 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / 120 Storage) [ID: 22964]	Level 1 / 119 Storage	33 sf
P	Floor Tile and Mastic / Visible Positive 712x127 HSA 99, Cmnt: Covebase down, exposed mastic [ID: 22987]	Level 1 / 121 Boy's Dressing Room	275 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22966]	Level 1 / 125 Office	115 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22967]	Level 1 / 128 Office	109 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: carpeted [ID: 22968]	Level 1 / 132 Storage	94 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Choral Office) [ID: 22998]	Level 1 / 133 Office	165 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22970]	Level 1 / 134 Classroom	145 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22999]	Level 1 / 134 Classroom	464 sf
P	Pipe Covering / / / HSA 2,3, Cmnt: not observed. Above ceiling [ID: 23077]	Level 1 / A Hall	123 lf
P	Pipe Covering / / / HSA 2,3, (Old Room: Main Building / Level 1 / Corridor 100), Cmnt: not observed. Above ceiling [ID: 23002]	Level 1 / A Hall	130 lf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23076]	Level 1 / A Hall	62 ea
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, (Old Room: Main Building / Level 1 / Corridor 100), Cmnt: not observed. Above ceiling [ID: 23001]	Level 1 / A Hall	65 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Corridor 100), Cmnt: abated 64 SF on expansion joints- Dec. 2009 [ID: 23000]	Level 1 / A Hall	676 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22979]	Level 1 / A 2	774 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 8 sf December 2009 [ID: 22980]	Level 1 / A 4	734 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 1025 SF- Dec. 2007 [ID: 22981]	Level 1 / A 6	0
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: cracking at entrance, 2 broken tiles. Needs waxing (noted 12/14 inspection), Needs Wax and or mats or new treads (noted 6/14 inspection) consider abatement [ID: 22982]	Level 1 / A 8	1075 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / 106 Storage) [ID: 22983]	Level 1 / A 8 Storage	160 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / 106 Storage) [ID: 22961]	Level 1 / A 8 Storage	163 sf
+	Joint Compound / Fine Compact Powder with Paint / Tan / Tested Positive, Cmnt: Tested 5% Chrysotile (19766.012-0003 phase 100) [ID: 28226]	Level 1 / A Hall	999 nq

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22974]	Level 1 / A11	72 sf
P	MJP Pipe Fittings / / / , Cmnt: Abated 6 fittings - Dec. 2005 [ID: 27553]	Level 1 / A12	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: carpet [ID: 22976]	Level 1 / A12	140 sf
P	Floor Tile and Mastic / Non-Visible PACM / / HSA 99, Cmnt: Carpeted [ID: 22975]	Level 1 / A12	951 sf
P	Floor Tile and Mastic / Non-Visible PACM / / HSA 99, Cmnt: Carpeted [ID: 22977]	Level 1 / A12 Storage	125 sf
P	MJP Pipe Fittings / / / , Cmnt: Abated 5 fittings - Dec. 2005 [ID: 27554]	Level 1 / A13	0 sf
P	Floor Tile and Mastic / Non-Visible PACM / / HSA 99, Cmnt: Carpeted [ID: 22978]	Level 1 / A13	945 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Cracked tiles in several areas within auditorium, big missing piece at Aisle D - 2018 [ID: 22985]	Level 1 / Auditorium	6700 sf
P	Floor Tile and Mastic / Visible Positive 712x127 HSA 99 [ID: 22986]	Level 1 / AV Storage	400 sf
P	Pipe Covering / / / HSA 2,3, Cmnt: not observed. Above ceiling [ID: 23080]	Level 1 / B Hall	123 lf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23079]	Level 1 / B Hall	62 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: abated 47 SF on expansion joints - December 2009 [ID: 23078]	Level 1 / B Hall	653 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Security Office) [ID: 23142]	Level 1 / BKKPR	100 sf
P	MJP Pipe Fittings / / / , Cmnt: Abated 9 fittings - Dec. 2005 [ID: 27555]	Level 1 / Boys RR	0 sf
P	Pipe Covering / / / HSA 2,3, Cmnt: abated 400 LF - June 2005/ not observed. Above ceiling [ID: 23083]	Level 1 / C Hall	1078 lf
P	Fire Doors / / , Cmnt: Abated 4 fire doors - Aug. 2004 [ID: 27560]	Level 1 / C Hall	999 nq

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: some pipe fittings abated- not observed. Above ceiling [ID: 23082]	Level 1 / C Hall	700 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: 144 SF abated on east end of hall - June 2005 / 163.5 sf abated - December 2009 [ID: 23081]	Level 1 / C Hall	4112 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated spring 2005 [ID: 23084]	Level 1 / C Hall Commons	0 sf
P	Floor Tile and Mastic / Visible Positive 712x127 HSA 99, Cmnt: One damaged tile needs sealing per inspector. It has been sealed [ID: 22989]	Level 1 / C 2	615 sf
P	Floor Tile and Mastic / Visible Positive 7 12 x 12 7 HSA 99 [ID: 22990]	Level 1 / C 4	460 sf
P	Floor Tile and Mastic / Visible Positive 712x127 HSA 99 [ID: 22991]	Level 1 / C 6	412 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: broken tiles in doorway. Chipped/gouged tiles throughout room [ID: 22992]	Level 1 / C 7	744 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22993]	Level 1 / C 8	1420 sf
P	Mudded Hard Fittings / / / , Cmnt: abated 48 hard fittings - Dec. 2009 [ID: 28189]	Level 1 / C 8 / Above Ceiling	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22995]	Level 1 / C 9	808 sf
+	Glued-on Ceiling Tiles	Level 1 / C 9 / Dark room	999
P	Floor Tile and Mastic / Visible Positive 12x12 HSA 99 Cmnt: new flooring visible - 2018 [ID: 22988]	Level 1 / C10	1420 sf
P	Mudded Hard Fittings / / / , Cmnt: abated 49 hard fittings - Dec. 2009 [ID: 28190]	Level 1 / C10 / Above Ceiling	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / 108 Classroom), Cmnt: minor gouging [ID: 22962]	Level 1 / CAD	454 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 22997]	Level 1 / Campus Monitor Office	92 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: bare cement at 2009 inspection [ID: 23006]	Level 1 / Costume	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: abated in 2005 [ID: 23012]	Level 1 / Counseling Office 6- Reconfigured in remodel, now part of VP1	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated summer 2005 [ID: 23013]	Level 1 / Curriculum Room - Reconfigured during remodel, now part of B Hall	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23014]	Level 1 / Custodial 2	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Hall C Custodial) [ID: 23085]	Level 1 / Custodial 3	0 sf
+	Wallboard and Joint Compound-Composite / Off white/beige/brown / Tested Positive, Cmnt: Chrysotile .50% (0015809-001) [ID: 29103]	Level 1 / Custodial 5	999 nq
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / 116 Custodian), Cmnt: 14 tiles appear to have been removed at sink. Damage looks to be repaired - 2018[ID: 22963]	Level 1 / Custodial 5	102 sf
P	Pipe Covering / / / HSA 2,3, Cmnt: not observed. Above ceiling [ID: 23088]	Level 1 / D Hall	135 lf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23087]	Level 1 / D Hall	61 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: abated 13 SF- December 2009 [ID: 23086]	Level 1 / D Hall	757 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor separation [ID: 23015]	Level 1 / D 1	1013 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor separation [ID: 23017]	Level 1 / D 3	1014 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23018]	Level 1 / Dark Room	312 sf
P	Pipe Covering / / /HSA 2,3, Cmnt: not observed. Above ceiling [ID: 23093]	Level 1 / E Hall	737 lf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23092]	Level 1 / E Hall	361 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: abated 174 SF - December 2009. Couple gouges by E-6 - 2018 [ID: 23091]	Level 1 / E Hall	4016 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23019]	Level 1 / E 1	744 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23031]	Level 1 / E 2	740 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23036]	Level 1 / E 3	320 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: cracking in doorway [ID: 23037]	Level 1 / E 4	746 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23038]	Level 1 / E 5	760 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor cracking at entry [ID: 23039]	Level 1 / E 6	750 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23040]	Level 1 / E 7	714 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor cracking at entry [ID: 23041]	Level 1 / E 8	748 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23042]	Level 1 / E 9	716 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23020]	Level 1 / E10	200 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23021]	Level 1 / E11	760 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor cracking [ID: 23022]	Level 1 / E12	524 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23023]	Level 1 / E13	365 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: tile separation noted (NEEDS TO BE WATCHED- READY TO GO) [ID: 23024]	Level 1 / E14A	370 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: tile separation noted (NEEDS TO BE WATCHED- READY TO GO) [ID: 23025]	Level 1 / E14B	370 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23026]	Level 1 / E15	750 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23027]	Level 1 / E16A	370 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23028]	Level 1 / E16B	370 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23029]	Level 1 / E17	752 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor separation [ID: 23030]	Level 1 / E18	860 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23032]	Level 1 / E20	791 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: cracking and chipping near floor electrical outlets [ID: 23033]	Level 1 / E22	836 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor separation [ID: 23034]	Level 1 / E24	1104 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23035]	Level 1 / E26	1094 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Hall D Electrical) [ID: 23089]	Level 1 / Electrical 2	25 sf
P	Pipe Covering / / /HSA 2,3, Cmnt: not observed. Above ceiling [ID: 23096]	Level 1 / F Hall	739 lf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23095]	Level 1 / F Hall	340 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: abated 128 SF - December 2009 [ID: 23094]	Level 1 / F Hall	4076 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23043]	Level 1 / F 1	746 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23056]	Level 1 / F 2A	340 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23057]	Level 1 / F 2B	340 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: stage needs to be watched. Minor separation [ID: 23058]	Level 1 / F 3	916 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23059]	Level 1 / F 3 Storage	40 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23060]	Level 1 / F 4	416 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: sealed gouges / no mastic [ID: 23061]	Level 1 / F 5	380 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23062]	Level 1 / F 6A	370 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23063]	Level 1 / F 6B	370 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor separation [ID: 23064]	Level 1 / F 8	758 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Library Prep Room), Cmnt: abated 265 SF - summer 2005. Carpeted - 2018 [ID: 23122]	Level 1 / F 9	400 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23044]	Level 1 / F10	714 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / F9), Cmnt: carpeted [ID: 23065]	Level 1 / F11	2185 sf
+	Mudded Hard Fitting on Fiberglass Insulated Pipe / Fibrous Powder / Off White / Tested Positive, Cmnt: 8% Chrysotile (19766.012-0001 phase 8) [ID: 28180]	Level 1 / F11 / Above Ceiling	999 nq
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23045]	Level 1 / F12	726 sf
+	Covebase Mastic / Brown / Tested Positive, Cmnt: 3% Chrysotile [ID: 26180]	Level 1 / F13	999 nq
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: abated 28 SF - December 2009 [ID: 23046]	Level 1 / F13	170 sf
P	Pipe Covering / / / HSA 2,3 [ID: 23048]	Level 1 / F14	0 lf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23047]	Level 1 / F14	766 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: abated 133 SF - June 2005 [ID: 23049]	Level 1 / F15	970 sf
P	Floor Tile and Mastic / Non-Visible PACM / / HSA 99, Cmnt: abated 1137 SF - June 2005 [ID: 23051]	Level 1 / F16	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: abated 20 SF - June 2005 / loose tile by hood / exposed black mastic [ID: 23052]	Level 1 / F17	1063 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23053]	Level 1 / F18	752 sf
+	Floor Tile and Mastic / Tested Positive, Cmnt: Abated Dec 2012. Remaining black mastic residual tested positive Chrysotile 10% must be abated if during any future flooring projects. 0014604-001,002 [ID: 23054]	Level 1 / F20	233 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23055]	Level 1 / F22	390 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23066]	Level 1 / Fiction Room	180 sf
P	Pipe Covering / / / HSA 2,3, Cmnt: not observed. Above ceiling [ID: 23099]	Level 1 / G Hall	156 lf
P	Fire Doors / / , Cmnt: Abated 3 fire doors - Aug. 2004 [ID: 27561]	Level 1 / G Hall	999 nq
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23098]	Level 1 / G Hall	78 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 885 SF - summer 2005 [ID: 23097]	Level 1 / G Hall	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor separation [ID: 23068]	Level 1 / G11	750 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23070]	Level 1 / G13	750 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Athletic Office), Cmnt: Abated 208 SF - summer 2005 [ID: 22984]	Level 1 / Gallery	0 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	MJP Pipe Fittings / / / , Cmnt: Abated 8 fittings - Nov. 2004 [ID: 27556]	Level 1 / Girls RR	0 sf
P	Pipe Covering / / / HAS 2,3, Cmnt: some (most) abated summer 2005. not observed. Above ceiling. [ID: 23102]	Level 1 / H Hall	200 lf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: some (most) abated summer 2005 not observed. Above ceiling [ID: 23101]	Level 1 / H Hall	100 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated spring 2005 [ID: 23100]	Level 1 / H Hall	0 sf
P	MJP Pipe Fittings / / / , Cmnt: Abated 2 fittings - Mar. 2006 [ID: 27557]	Level 1 / H10	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor separation, areas of excessive wear [ID: 23072]	Level 1 / H10	760 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 750 SF - June 2005 [ID: 23073]	Level 1 / H12	0 sf
P	Sheet Flooring Material and Mastic / Visible PACM / / , Cmnt: Abated summer 2005 [ID: 23075]	Level 1 / H15	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23106]	Level 1 / Health Room	81 sf
P	Pipe Covering / / / HSA 2,3, (Old Room: Main Building / Level 1 / Corridor 103), Cmnt: Some cracking noted by inspector. Not observed. Above ceiling [ID: 23005]	Level 1 / I Hall	158 lf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, (Old Room: Main Building / Level 1 / Corridor 103), Cmnt: not observed above ceiling [ID: 23004]	Level 1 / I Hall	79 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Corridor 103), Cmnt: abated 36 sf- December 2009, Exposed mastic and 2 broken tiles near Taqueria and Stage Door [ID: 23003]	Level 1 / I Hall	864 sf
P	Pipe Covering / / / HSA 2,3, Cmnt: not observed. Above ceiling [ID: 23105]	Level 1 / J Hall	251 lf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23104]	Level 1 / J Hall	125 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: some cracking [ID: 23103]	Level 1 / J Hall	1353 sf
+	Gypsum Wallboard/Joint Compd.	Level 1 / J Hall / Practice Room 2	999 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: minor tile separation, gouging, cracking [ID: 23109]	Level 1 / J1 Storage	257 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99. Cmnt: looks newer - 2018 [ID: 23110]	Level 1 / J3	1157 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23111]	Level 1 / J3 Storage	29 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23112]	Level 1 / J4	638 sf
P	MJP Pipe Fittings / / / , Cmnt: Abated 2 fittings - Dec. 2005 not observed. Above ceiling. [ID: 27558]	Level 1 / Kitchen	999 nq
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated summer 2005 [ID: 22972]	Level 1 / Kitchen 150 Custodial Closet	0
P	Floor Tile and Mastic / / , Cmnt: Abated 48 SF - June 2005 [ID: 27549]	Level 1 / Kitchen Custodial 150 Closet	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 75 SF - summer 2005 [ID: 23114]	Level 1 / Kitchen Dressing Room	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 628 SF - summer 2005 [ID: 23115]	Level 1 / Kitchen Dry Storage	0 sf
P	MJP Pipe Fittings / / / , Cmnt: Abated 2 fittings - Dec. 2005 [ID: 27551]	Level 1 / Library	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 273 SF - June 2005 [ID: 23117]	Level 1 / Library	0 sf
P	Floor Tile and Mastic / / , (Old Room: Main Building / Level 1 / Library Curriculum Room), Cmnt: Abated 136 SF - June 2005 [ID: 27550]	Level 1 / Library Curriculum Room-reconfigured in remodel, now part of B Hall	0 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 146 SF - summer 2005 [ID: 23118]	Level 1 / Library Office 1- reconfigured in remodel, now part of B Hall	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 137 SF - summer 2005 [ID: 23119]	Level 1 / Library Office 1- reconfigured in remodel, now part of B Hall	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23120]	Level 1 / Library Office 1- reconfigured in remodel, now part of B Hall	180 sf
P	Floor Tile and Mastic / Non-Visible PACM / / HSA 99, Cmnt: carpet [ID: 23124]	Level 1 / Lighting Room	164 sf
P	Pipe Covering / / / HSA 2,3, Cmnt: not observed. Above ceiling [ID: 23126]	Level 1 / Lobby 1	391 lf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23125]	Level 1 / Lobby 1	195 ea
P	MJP Pipe Fittings / / / , Cmnt: Abated 1 fitting - Apr. 2005 [ID: 27559]	Level 1 / Main Gym	999 nq
P	Vinyl Floor Tile / 12 x 12, Cmnt: minor separation [ID: 27789]	Level 1 / Main Gym / SW Entry	130 sf
P	Floor Tile and Mastic / Non-Visible PACM / / HSA 99, Cmnt: carpet [ID: 23128]	Level 1 / Main Office	560 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Loose tile under water fountain [ID: 23129]	Level 1 / Main Office Halls	412 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23130]	Level 1 / Main Office Lobby	222 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23132]	Level 1 / Mechanical 2	143 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23133]	Level 1 / Mechanical 3	100 sf
+	4" brown covebase with brown mastic on wallboard (<1% from joint compound on wall)	Level 1 / Music Library	
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23134]	Level 1 / Music Library	290 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / 133 Storage), Cmnt: 01/2016- Abated 20 SF June 2015 [ID: 22969]	Level 1 / Office 4	108 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	MJP Pipe Fittings / / / , (Old Room: Main Building / Level 1 / Counseling Office 1), Cmnt: Abated 4 fittings - Dec. 2005 [ID: 27552]	Level 1 / Office 7	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Counseling Office 1) [ID: 23007]	Level 1 / Office 7	68 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Counseling Office 2) [ID: 23008]	Level 1 / Office 8	68 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Counseling Office 3) [ID: 23009]	Level 1 / Office 9	68 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Counseling Office 4) [ID: 23010]	Level 1 / Office 10	68 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Counseling Office 5) [ID: 23011]	Level 1 / Office 11	68 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / H13-H14 Office), Cmnt: Abated 110 SF - summer 2005 [ID: 23074]	Level 1 / Office 14	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / C 8-C10 Office) [ID: 22994]	Level 1 / Office 15	93 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23121]	Level 1 / Office 16	268 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 123 SF - summer 2005 [ID: 23135]	Level 1 / Office 20- reconfigured in remodel, now part of commons	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23136]	Level 1 / Practice Room 1	97 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23137]	Level 1 / Practice Room 2	72 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23138]	Level 1 / Practice Room 3	28 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23139]	Level 1 / Practice Room 4	28 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23140]	Level 1 / Practice Room 5	300 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / D1-D3 Project Room) [ID: 23016]	Level 1 / Prep 3	215 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmmt: carpeted. 9/29/15 Approx 30 SF abated March 2015 around perimeter of office, asbestos containing flooring remains in center of room. [ID: 23141]	Level 1 / Principal Office	182 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / 102 Health Room) [ID: 22957]	Level 1 / Printing	126 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Vault) [ID: 23147]	Level 1 / Records	90 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Hall D Storage) [ID: 23090]	Level 1 / Science Stock Room	870 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmmt: separation, cracking, lifting of tile at entrance [ID: 23143]	Level 1 / Stack Room	582 sf
P	Floor Tile and Mastic / Non-Visible PACM / / HSA 99, (Old Room: Main Building / Level 1 / 121), Cmmt: some tile separation. 1 missing tile at entrance to men's restroom [ID: 22965]	Level 1 / Storage 2	232 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Main Office Storage) [ID: 23131]	Level 1 / Storage 20	43 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmmt: Abated 376 SF - summer 2005 [ID: 23145]	Level 1 / Student Store	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23148]	Level 1 / Vice Principal Office 1	91 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23149]	Level 1 / Vice Principal Office 2	122 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23150]	Level 1 / Vice Principal Office 3	125 sf
+	Gypsum Wallboard/Joint Compd.	Level 1 / VP2	0
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Main Counseling Office) [ID: 23127]	Level 1 / Wait 1	370 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Level 1 / Library Work Room), Cmnt: abated 265 SF - summer 2005 [ID: 23123]	Level 1 / Work 1	550 sf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: abated 4 fittings - April 2004 [ID: 23151]	Level 2 / A10 Loft Mechanical Room	20 ea
P	Vinyl Floor Tile / 12 x 12 [ID: 27790]	Level 2 / A14 Loft	1450 sf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19 [ID: 23152]	Level 2 / A14 Loft Mechanical Room	22 ea
P	Hard Fittings on Fiberglass Pipe Insulation, Cmnt: Abated 3 hard fittings on fiberglass pipe insulation - Center gym area [ID: 29008]	Level 2 / Main Gymnasium	3 ea
P	Hard Fittings on Fiberglass Pipe Insulation, Cmnt: Abated 1 hard fittings on fiberglass pipe insulation - North gym area [ID: 29009]	Level 2 / Main Gymnasium	1 ea
P	Hard Fittings on Fiberglass Pipe Insulation, Cmnt: Abated 1 hard fittings on fiberglass pipe insulation - South gym area [ID: 29010]	Level 2 / Main Gymnasium	1 ea
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19 [ID: 23153]	Level 2 / Sector D	86 ea
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19 [ID: 23154]	Level 2 / Sector F	97 ea
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19 [ID: 23155]	Level 2 / Sector F Cat Walk	24 ea
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: 4 MJPS needing repair/replacement noted at last inspection, not observed during 15-year re-inspection [ID: 23156]	Level 2 / Sector G	283 ea
+	Hard Fittings on Fiberglass Pipe Insulation / Material Tested Positive, Cmnt: Abated 1 hard fittings on fiberglass pipe insulation - Tested Positive (19766.012-0018 Phase 0014) [ID: 29007]	Level 2 / Sector G / Upper Mechanical Room	3 ea
+	Hard Fittings on Fiberglass Pipe Insulation / Material Tested Positive, Cmnt: Abated 1 hard fittings on fiberglass pipe insulation - Tested Positive (19766.012-0017 Phase 0014) [ID: 29006]	Level 2 / Sector G / Upper Mechanical Room	3 ea

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
+	Hard Fittings on Fiberglass Pipe Insulation / Material Tested Positive, Cmnt: Abated 3 hard fittings on fiberglass pipe insulation - Tested Positive (19766.012-0016 Phase 0014) [ID: 29005]	Level 2 / Sector G / Upper Mechanical Room	3 ea
+	Gypsum Wallboard/Joint Compound	Library, north wall	0
+	Mastic	Lobby #00; south of special education #101 (area 2), black amstic under tact boards	0
+	Mastic	Loft mechanical room; south end, above auto shop, tan duct sealant putty off foil-faced fiberglass, rectangular ducts	0
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19 [ID: 23173]	Lower Level /	0 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Lower Level / Lower Gym Custodial), Cmnt: Abated 800 SF - June 2005 / existing tiles are separating and loose especially at the sink [ID: 23166]	Lower Level / Custodial 4	0 sf
P	Wall Board / / / /, Cmnt: Abated 6 SF- June 2012 [ID: 29087]	Lower Level / Lower Gym	999 nq
+	Gypsum Wallboard/Joint Compd. Dec 2019: Abated 30sf gyp/jc on NW wall	Lower Level / Lower Gym	30
P	Transite Panel / / / HSA 98, Cmnt: abated 3332 SF - June 2005 [ID: 23165]	Lower Level / Lower Gym	0 sf
P	Wall Board / / / /, Cmnt: Abated 6 SF- June 2012 [ID: 29088]	Lower Level / Lower Gym / Stairwell Mid Landing	999 nq
+	Stair Tread, Runner, Floor Tile and Mastic / Tested Positive, Cmnt: Abated 600 SF March 2007 [ID: 26741]	Lower Level / Lower Gym Stairwell and Bottom Landing	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 800 SF - June 2005 [ID: 23167]	Lower Level / Lower Hallway	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 310 SF - June 2005 [ID: 23159]	Lower Level / Men's Gym Office	0 sf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19 [ID: 23161]	Lower Level / Men's Locker Room	0 ea
P	Transite Panel / / / HSA 98, Cmnt: Abated 5303 SF - June 2005 [ID: 23160]	Lower Level / Men's Locker Room	0 sf

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: abated 3 fittings - Mar. 2006 / not observed. Above ceiling [ID: 23157]	Lower Level / Men's Locker Room All Ceiling Areas	197 ea
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99 [ID: 23169]	Lower Level / Stairs and Landings to Level 1	280 sf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, (Old Room: Main Building / Lower Level / Weight Room Storage), Cmnt: Inspector added 2004. [ID: 23179]	Lower Level / Storage 8	1 ea
P	Transite Panel / / / HSA 98, (Old Room: Main Building / Lower Level / Weight Room Storage) [ID: 23178]	Lower Level / Storage 8	227 sf
P	Transite Panel / / / HSA 98, (Old Room: Main Building / Lower Level / Weight Room 2), Cmnt: One damaged panel needs replacement per inspector. (noted still needs repair 6/14 inspection) [ID: 23177]	Lower Level / Storage 9	405 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Lower Level / Girl's Team Room), Cmnt: Abated 199 SF - June 2005 [ID: 23164]	Lower Level / Storage 10	0 sf
P	Pipe Covering / / / HSA 2,3, (Old Room: Main Building / Lower Level / Trainer) [ID: 23174]	Lower Level / Storage 12	0 lf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, (Old Room: Main Building / Lower Level / Trainer) [ID: 23172]	Lower Level / Storage 12	0 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: some cracking observed [ID: 23171]	Lower Level / Theater Storage 1	345 sf
P	Floor Tile and Mastic / Non-Visible PACM / / HSA 99, Cmnt: carpet [ID: 23170]	Lower Level / Theater Storage 1	1733 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HAS 99, (Old Room: Main Building / Lower Level / Referee's Office), Cmnt: some broken/cracked tile by lockers [ID: 23168]	Lower Level / TLT 4 & 5	102 sf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: Abated 9 fittings - Mar. 2006 [ID: 23175]	Lower Level / Training Room	0 ea

Aloha High (AHS) Aloha High Main Building (AHS1)			
Result	Material	Location	Quantity
P	Transite Panel / / / HSA 98, Cmnt: One damaged panel needs replacement per inspector. Appear to have covered damage with cardboard. [ID: 23176]	Lower Level / Weight Room	1216 sf
P	Floor Tile and Mastic / Visible Positive / 12 x 12 / HSA 99, Cmnt: Abated 385 SF - June 2005 [ID: 23162]	Lower Level / Women's Gym Office	0 sf
P	Transite Panel / / / HSA 98, Cmnt: Abated 3418 SF - June 2005 [ID: 23163]	Lower Level / Women's Locker Room	0 sf
P	MJP Pipe Fittings / / / HSA 4,5,6,11,16,17,18,19, Cmnt: not observed. Above ceiling [ID: 23158]	Lower Level / Women's Locker Room All Ceiling Areas	175 ea
+	Mastic	Northeast corner of room A-08 (area 2); brown mastic under 12"x12" wall panels	0
+	Mastic	Room A-08 (area 2); black mastic beneath white boards	0
+	Mastic	Room A-10-B; east wall, southeast corner, black mastic, beneath white boards	0
+	Mastic	Room C-10; west wall under tact board (area 1); black mastic	0
M	Gypsum Wallboard/Joint Compd./ less than 1%	Throughout interior walls in original construction areas	999 nq
+	4" Tan Cove Base & Associated Glue	Throughout Main Building	
+	Gypsum Board & Joint Compound	Throughout Main Building	
P	Stage Lighting Wiring / Visible Positive, Cmnt: Asbestos wiring abated from fourteen (14) individual Lighting "Scoops". [ID: 29031]	Upper Level / Stage	0 ea
+	Joint Compound / Tested Positive, Cmnt: Joint Compound Tested Positive (19766.012-0003 Phase 0011) [ID: 29028]	Upper Level / Stage / Mezzanine	999 nq
+	Pipe Fitting / Gray/Beige / Tested Positive, Cmnt: Chrysotile 15% (0015796-001) [ID: 29106]	Upper Level / Stage Mezzanine / HVAC unit	1 ea
+	Gypsum Wallboard/Joint Compd.	Walls Above Auditorium	2800 sf

MATERIALS THAT TESTED NEGATIVE

The following materials tested negative. Although no asbestos was detected, it is possible that further sampling could indicate asbestos content. It may be prudent to test prior to impact, demolition, renovation, etc.

Aloha High (AHS)	
Material	Location
Cementitious Pipe	Ball field trench; cementitious pipe
Mastic	Corridor A; east room from A-10 f; black mastic
Corkboard and mastic	J-Hall Practice Room #2
glued-on ceiling tile	J-Hall Practice Room #2
Gypsum Wallboard/Joint Compound	Library, book storage wall
Gypsum Wallboard/Joint Compound	Library, east wall
Built-up Roofing	Roof; center of area 1, multiple layered built-up roofing
Built-up Roofing	Roof; northwest corner of area 2, multiple layered built-up roofing
Mastic	Room c-08; east wall (area 1); brown mastic
Covebase/Mastic	Vice principal office 2; northeast corner, 4" tan covebase with brown mastic

Aloha High (AHS) Aloha High Concession Stand (AHS2)	
Material	Location
Built-up roofing / All 7 layers / Tested Negative, Cmmt: Non detect (19766.012-0001 task 002) [ID: 28202]	Roof / Center roof

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
Ceramic Tile/Grout	Aloha HS; east gym, water fountain area, white ceramic tile and grout
Covebase/Mastic	Aloha HS; room J-3, 4" black covebase with yellow and brown mastic
Mastic	Aloha HS; room J-3, white mastic behind corkboards
Mastic	Aloha HS; room J-3, yellow mastic behind wood wainscot
Ceramic Tile/Grout	Aloha HS; west gym, water fountain area, white ceramic tile and grout
Caulk	Aloha HS; west gym, water fountain area, white seam caulk
Lay-in Ceiling Tile	Area 1; Room C10, 1'X4' white ceiling tile with fissures
Lay-in Ceiling Tile	Area 1; Room C10, 2'X4' white ceiling tile with small fissures
Covebase/Mastic	Area 1; Room C10, brown 4" covebase with brown mastic

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
Vinyl Floor Tile/Mastic	Area 1; Room C8, 1'X4' white ceiling tile with fissures
Lay-in Ceiling Tile	Area 1; Room C8, 2'X4' white ceiling tile with small fissures
Covebase/Mastic	Area 1; Room C8, tan 4" covebase with yellow mastic
Covebase/Mastic	Area 2; CAD room, tan 4" covebase with brown mastic
Vinyl Floor Tile/Mastic	Area 2; Room 108, cream 12"X12" vinyl tile with black mastic
Gypsum Wallboard	Area 2; Room 108, gypsum joint compound wall system
Lay-in Ceiling Tile	Area 2; shop mezzanine east, 2'X4' white ceiling tile with small fissures
Lay-in Ceiling Tile	Area 2; shop mezzanine east, 1'X4' ceiling tile with fissures
Lay-in Ceiling Tile	Area 2; shop mezzanine west, 2'X4' white ceiling tile with small fissures
Lay-in Ceiling Tile	Area 2; shop mezzanine west, 1'X4' ceiling tile with fissures
Covebase/Mastic	Area 2; shop storage, brown 4" covebase with brown mastic
Ceramic Tile/Grout	Area 2; shop work room, cream ceramic tile and grout on wall
Ceramic Tile/Grout	Area 2; shop work room, tan ceramic tile and grout on floor
Gypsum Wallboard	Area 3; Room A11, gypsum inside wall panel
Mastic	Area 3; Room A12, yellow carpet mastic
Tan Cove Base and Glue	Auditorium
Wall and Ceiling Plaster	Auditorium Ceiling
Light Beige Floor Tile (with Streaks) and Associated Glue	Auditorium Floor
Concrete	Auditorium Floor
White Glued-on Acoustical Tiles	Auditorium Walls
Caulk	C-9 door frame; whiteish, rubbery caulking around door frame
Vinyl Floor Tile/Mastic	C-9 entryway; off-white 12" tile with yellow mastic
Gypsum Wallboard/Joint Compound	C-9 next to door frame; gypsum wallboard and joint compound

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
Covebase/Mastic	C-9 next to door frame; tan covebase with beige mastic
Mastic	C-9 next to door frame; yellow mastic under wainscot
CMU	Chimney
Exterior Texture	Chimney
Chicken Wire Mortar	Chimney
Upper Fire Brick and Grout	Chimney
Lower Fire Brick	Chimney
Mastic	Corridor A; east room from A-10 f; black mastic
Vinyl Floor Tile/Mastic	Costume shop; tan 12" vinyl floor tile with yellow mastic
Glued-on Ceiling Tiles	Drama storage; 12" white ceiling tile with brown mastic
Skimcoat	Drama storage; concrete ceiling plaster skim
Skimcoat	Drama storage; concrete wall plaster skim
Covebase/Mastic	Drama storage; dark brown 4" covebase with brown mastic
Covebase/Mastic	Drama storage; light brown 4" covebase with brown mastic
Vinyl Floor Tile/Mastic	Drama storage; thin salmon vinyl floor tile with yellow mastic
Mastic	Drama storage; wall chalkboard residual yellow mastic
Mastic	Drama storage; yellow carpet mastic
Built-up Roofing / Tested Negative, Cmnt: Built-up roofing - Non-detected (19766.012-0005,0006,0007,0008,0009,0010,0011,0012,0015 Phase 0014) [ID: 29015]	E and F Wing / Roofs
Mastic / Tested Negative, Cmnt: Roof parapet mastic application - Non-detected (19766.012-0001,0002,0003 Phase 0014) [ID: 29013]	E and F Wing / Roofs
Plaster/Stucco	Exterior Soffit
Grout	Exterior south wall of wood shop; tan grout with 1/4" crushed stone
Gypsum Wallboard/Joint Compound	G-10 entryway; gypsum wallboard and joint compound
Vinyl Floor Tile/Mastic	G-10 entryway; white 12" tile with yellow mastic
Ceramic Tile Grout	Gym Entrance Hall
Covebase/Mastic	Gym lobby; by girls room, covebase, black

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
Covebase/Mastic	Gym lobby; by girls room, covebase, tan
Covebase/Mastic	Gym lobby; by girls room, east door, covebase, tan
Covebase/Mastic	Hallway; south of Room A6, black 4" covebase with tan mastic
Paint	Hallway; south of Room A6, on concrete column and wall white paint with powdery layer below
Covebase/Mastic	I hall; by book storage door, 4" tan covebase with brown mastic
Covebase/Mastic	I hall; by stage doors, 4" tan covebase with brown mastic
Gypsum Wallboard/Joint Compound	J-1 entryway gypsum wallboard with joint compound
Covebase/Mastic	J-1 entryway; covebase (black) with off-white mastic
Covebase Mastic / Brown / Tested Negative, Cmnt: non-detect [ID: 26084]	Level 1 / A11
Carpet Mastic / Tan / Tested Negative, Cmnt: non-detect [ID: 26083]	Level 1 / A11
Covebase Mastic / Cream / Tested Negative, Cmnt: non-detect [ID: 26085]	Level 1 / A11
Vinyl Covebase / Brown / Tested Negative / 4", Cmnt: non-detect [ID: 26091]	Level 1 / A11
Vinyl Floor Tile / Grey / Tested Negative / 12 x 12, Cmnt: non-detect [ID: 26092]	Level 1 / A11 Entry
Floor Tile Mastic / Yellow / Tested Negative / 12 x 12, Cmnt: non-detect [ID: 26093]	Level 1 / A11 Entry
Carpet Mastic / Tan / Tested Negative, Cmnt: non-detect [ID: 26079]	Level 1 / A12
Vinyl Covebase / Brown / Tested Negative / 4", Cmnt: non-detect [ID: 26080]	Level 1 / A12
Covebase Mastic / Brown / Tested Negative, Cmnt: non-detect [ID: 26081]	Level 1 / A12
Covebase Mastic / Cream / Tested Negative, Cmnt: non-detect [ID: 26082]	Level 1 / A12
Vinyl Covebase / Brown / Tested Negative / 4", Cmnt: non-detect [ID: 26076]	Level 1 / A13
Covebase Mastic / Brown / Tested Negative, Cmnt: non-detect [ID: 26077]	Level 1 / A13
Covebase Mastic / Cream / Tested Negative, Cmnt: non-detect [ID: 26078]	Level 1 / A13

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
Carpet Mastic / Yellow / Tested Negative, Cmnt: non-detect [ID: 26075]	Level 1 / A13
Covebase and Mastic / / / /, Cmnt: 4/20/15 non-detect - all colors for cove base and mastic [ID: 29211]	Level 1 / C Hall
No asbestos Containing Material / Remodeled, Cmnt: Abated Spring 2005 [ID: 22996]	Level 1 / Cafeteria
No Asbestos Containing Material / / / [ID: 24344]	Level 1 / Commons
No Asbestos Containing Material / / / [ID: 27744]	Level 1 / C-Store
Covebase Mastic / Brown / Tested Negative, Cmnt: non-detect [ID: 24531]	Level 1 / E 5
Covebase Mastic / Cream / Tested Negative, Cmnt: non-detect [ID: 26179]	Level 1 / F13
No Asbestos Containing Material / / Completely Guttled in 2005 remodel [ID: 23067]	Level 1 / G10
No Asbestos Containing Material / / Completely Guttled in 2005 remodel [ID: 23069]	Level 1 / G12
Covebase Mastic / Brown / Tested Negative, Cmnt: non-detect (19766.012-0005 phase 100) [ID: 28228]	Level 1 / Health Room
Cork Board / Layer 2 / Tan / Tested Negative, Cmnt: Non-Detect (0015366-001) [ID: 29091]	Level 1 / J Hall
Canvas / Layer 1 / Green/White / Tested Negative, Cmnt: Non-Detect (0015366-001) [ID: 29090]	Level 1 / J Hall
Mastic / Layer 3 / Brown / Tested Negative, Cmnt: Non-Detect (0015366-001) [ID: 29092]	Level 1 / J Hall
Wallboard / Layer 4 / Off White/Brown / Tested Negative, Cmnt: Non-Detect (0015366-001) [ID: 29093]	Level 1 / J Hall
Wallboard / Off White/Brown / Tested Negative, Cmnt: Non-Detect (0015366-002) [ID: 29094]	Level 1 / J Hall
Glued-on Ceiling Tiles / 12"x12"	Level 1 / J Hall / Practice Room 2
Cork board and Mastic / 4 layers	Level 1 / J Hall / Practice Room 2
No Inventoried Asbestos Material / None / [ID: 23107]	Level 1 / J1
No Inventoried Asbestos Material / None / / /, (Old Room: Main Building / Level 1 / 137 Choral) [ID: 22971]	Level 1 / J2 Choral
No Inventoried Asbestos Material / None / [ID: 23113]	Level 1 / J5
No Asbestos Containing Materials / / / [ID: 27739]	Level 1 / K Hall (all rooms)
No Asbestos Containing Material / Completely Guttled in Remodel, (Old Room: Main Building / Level 1 / Main Office Conference Room) [ID: 27736]	Level 1 / Mail

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
Covebase and Mastic / Multiple Areas / Tested Negative, Cmnt: non-detect (19766.012-0001 through 0004 & 0006 through 0009, phase 100) [ID: 28227]	Level 1 / Main Office
No Inventoried Asbestos Material / None / , (Old Room: Main Building / Level 1 / J1 Office) [ID: 23108]	Level 1 / Office 1
No Asbestos Containing Material / / Completely Guttled in 2005 remodel, (Old Room: Main Building / Level 1 / Ticket Office) [ID: 23146]	Level 1 / Office 2
No Asbestos Containing Material / / Completely Guttled in 2005 remodel, (Old Room: Main Building / Level 1 / 109 Storage) [ID: 27548]	Level 1 / Office 3
No Asbestos Containing Material / / Completely Guttled in 2005 remodel, (Old Room: Main Building / Level 1 / Kitchen Office) [ID: 23116]	Level 1 / Office 6
Ceiling Tile / Off White/Brown / Tested Negative, Cmnt: Non-Detect [ID: 29104]	Level 1 / Practice Room 5
Ceiling Tile Mastic / Dark Brown / Tested Negative, Cmnt: Non-Detect [ID: 29105]	Level 1 / Practice Room 5
No Asbestos Containing Material / / Completely Guttled in 2005 remodel, (Old Room: Main Building / Level 1 / F15- F17 Project Room) [ID: 23050]	Level 1 / Prep 1
Wall Tile Grout / White / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Men Auditorium), Cmnt: non-detect [ID: 26763]	Level 1 / Restroom Boys 1
Lay-in Ceiling Tile / White / Tested Negative / 2' x 4', (Old Room: Main Building / Level 1 / Restroom Men Auditorium), Cmnt: non-detect [ID: 26757]	Level 1 / Restroom Boys 1
Gypsum Wallboard / Paper Backing / Tan / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Men Auditorium / East Wall), Cmnt: non-detect [ID: 26766]	Level 1 / Restroom Boys 1 / East Wall
Gypsum Wallboard / Compact Chalky Material / White / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Men Auditorium / East Wall), Cmnt: non-detect [ID: 26765]	Level 1 / Restroom Boys 1 / East Wall
Moisture Barrier / Fibrous Tar / Black / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Men Auditorium / Inside Wet Wall Urinals), Cmnt: non-detect [ID: 26767]	Level 1 / Restroom Boys 1 / Inside Wet Wall Urinals
Wall and Ceiling Plaster / Grey / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Men Auditorium / South Wall), Cmnt: non-detect [ID: 26764]	Level 1 / Restroom Boys 1 / South Wall

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
Gypsum Wallboard / Compact Chalky Material / White / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Men Auditorium / Wall above Entrance), Cmnt: non-detect [ID: 26768]	Level 1 / Restroom Boys 1 / Wall above Entrance
Gypsum Wallboard / Paper Backing / Tan / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Men Auditorium / Wall above Entrance), Cmnt: non-detect [ID: 26769]	Level 1 / Restroom Boys 1 / Wall above Entrance
Wall Tile Grout / White / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Women Auditorium), Cmnt: non-detect [ID: 26758]	Level 1 / Restroom Girls 1
Wall and Ceiling Plaster / Behind Wall Tiles / Grey / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Women Auditorium), Cmnt: non-detect [ID: 26761]	Level 1 / Restroom Girls 1
Lay-in Ceiling Tile / White / Tested Negative / 2' x 4', (Old Room: Main Building / Level 1 / Restroom Women Auditorium), Cmnt: non-detect [ID: 26756]	Level 1 / Restroom Girls 1
Gypsum Wallboard / Compact Chalky Material / White / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Women Auditorium / Above Ceiling / Wall with Sinks), Cmnt: non-detect [ID: 26759]	Level 1 / Restroom Girls 1 / Above Ceiling / Wall with Sinks
Gypsum Wallboard / Paper Backing / Tan / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Women Auditorium / Above Ceiling / Wall with Sinks), Cmnt: non-detect [ID: 26760]	Level 1 / Restroom Girls 1 / Above Ceiling / Wall with Sinks
Wall and Ceiling Plaster / Grey / Tested Negative, (Old Room: Main Building / Level 1 / Restroom Women Auditorium / Chase at South Wall), Cmnt: non-detect [ID: 26762]	Level 1 / Restroom Girls 1 / Chase at South Wall
No Asbestos Containing Material / Completely Guttred in 2005 Remodel [ID: 23144]	Level 1 / Staff Room
Roll up door jambs / Wall and Ceiling Plaster / Tested Negative, Cmnt: non-detect all layers (19766.012-0001 & 0002 phase 100) [ID: 28225]	Level 1 / Stage
No Asbestos Containing Materials / / / [ID: 27738]	Level 1 / Vice Principal Office 4
Covebase/Mastic	Level 1 / VP2
No Asbestos Containing Materials / / / [ID: 27737]	Level 1/ Psych Office
Gypsum Wallboard/Joint Compound	Library, book storage wall
Gypsum Wallboard/Joint Compound	Library, east wall
Caulk	Loft mechanical room; south end, above auto shop, gray caulk between concrete tilt-up wall panels

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
No Asbestos Containing Materials / / / [ID: 27743]	Lower Level / Elevator Room
No Asbestos Containing Materials / / / [ID: 27740]	Lower Level / L Hall (all rooms)
No Asbestos Containing Materials / / / [ID: 27741]	Lower Level / Restroom Boys 7
No Asbestos Containing Materials / / / [ID: 27742]	Lower Level / Restroom Girls 7
Brick Grout	Main Building C-Hall, F-Hall, and A-Hall
Covebase/Mastic	Music library; by office 1 door, 4" brown covebase with yellow mastic on wood shelving
Covebase/Mastic	Music library; by office 133 door, 4" brown covebase with yellow mastic on wood shelving
Covebase/Mastic	Music library; by office 135 door, 4" brown covebase with brown mastic on wallboard
Brown Glue Associated with Corkboard	Music Room Office
Roof Curb Mastic	Roof
Built-up Roofing	Roof - Area D and SE Section of Area B
Roofing Mastic	Roof - Area E & Area B
Silver Paint	Roof - Area E, Area D & Area B
Built-up Roofing	Roof - Center Section of Area E
Built-up Roofing	Roof - East Section of Area E
Built-up Roofing	Roof - North Section of Area E
Built-up Roofing	Roof - North Side Covered Walkway
Built-up Roofing	Roof - Southeast Area of Area B
Built-up Roofing	Roof - Throughout Area A
Built-up Roofing	Roof - Throughout Area B
Built-up Roofing	Roof - West Section of Area E
Roofing Insulation	Roof (Chiller Area)
Tan Mastic - Roof Chiller	Roof Chiller
Caulking - Roof Chiller	Roof Chiller
Red Mastic - Roof Chiller Unit	Roof Chiller Unit
Built-up Roofing	Roof; center of area 1, multiple layered built-up roofing
Built-up Roofing	Roof; northwest corner of area 2, multiple layered built-up roofing
Mastic	Room c-08; east wall (area 1); brown mastic

Aloha High (AHS) Aloha High Main Building (AHS1)	
Material	Location
Concrete	Stage Floor
Concrete	Stage Wall
Settled Dust on Ceiling Tile	Throughout
Gypsum Wallboard & Joint Compound	Throughout B Building
4" Black Cove Base & Associated Glue	Throughout B Building
4" Black Cove Base & Associated Glue	Throughout Main Building
Covebase and Mastic / Tested Negative, Cmnt: Covebase/Mastic - Non-detected (19766.012-0001 Phase 0011) [ID: 29026]	Upper Level / Stage / Mezzanine
Glued-on Ceiling Tiles/Mastic / Tested Negative, Cmnt: Glued-on Ceiling Tiles/Mastic / Tested Negative (19766.012-0005 Phase 0011) [ID: 29030]	Upper Level / Stage / Mezzanine
Wall and Ceiling Plaster #1 / Tested Negative, Cmnt: Wall and Ceiling Plaster - Non-detected (19766.012- 0002 Phase 0011) [ID: 29027]	Upper Level / Stage / Mezzanine
Wall and Ceiling Plaster #2 / Tested Negative, Cmnt: Wall and Ceiling Plaster - Non-detected (19766.012- 0004 Phase 0011) [ID: 29029]	Upper Level / Stage / Mezzanine
Vapor Barrier	Wrestling gym; under tongue and groove floor, black plastic-like vapor barrier
Wood Fiber Insulation	Wrestling gym; under tongue and groove floor, brown wood fiber insulation

ASBESTOS SUMMARY

The following shows asbestos activities and projects. For more detailed information or related documents see the individual activity information in the database.

January 2004 to December 2012 -

Activity: Database Update - Location: AHS1

AHS1N Import Historical Materials without samples Batch 1

January 2004 to December 2012 - 19766.012 p08

Activity: Database Update - Location: AHS1 19766.012 p08

AHS1 Import Historical materials with Samples

January 2004 to December 2012 - 19766.012 p11

Activity: Database Update - Location: AHS1 19766.012 p11

AHS1 Import Historical materials with Samples

January 2004 to December 2012 - 19766.012 p14
Activity: Database Update - Location: AHS1 19766.012 p14

AHS1 Import Historical materials with Samples p14

January 2004 to December 2012 - 19766.012 p100
Activity: Database Update - Location: AHS1 19766.012 p100

AHS1N Import Historical materials with Samples

January 2004 to December 2012 - 19766.012 p
Activity: Database Update - Location: AHS2

AHS2 Import Historical materials with Samples

March 2016 to March 2016 - 23816.002 Phase 5
Activity: Sampling - Location: Aloha High School, Hall L

April 2016 to April 2016 - AHS1 Sampling3
Activity: Sampling - Location: Level 1 / C 9 / Dark Room

~~Floor plan~~
~~Results in Verdant~~
Consultant Invoice

April 2016 to April 2016 - 23816.004 Phase 1
Activity: Sampling - Location: Aloha HS Library

Floor plan
~~Results in Verdant~~
Consultant Invoice

April 2016 to April 2016 - 23816.004 Phase 1
Activity: Sampling - Location: Library Site

May 2016 to May 2016 - AHS1abatement2
Activity: O & M - Location: Level 1 / C9 / Dark Room

Abated 12 SF of ceiling tile and sheet rock for HVAC repair.

Missing:

DEQ Notification
Desposal Manifest

July 2016 to July 2016 - 1212

Activity: Major Abatement - Location: Throughout

Activity description

November 2016 to November 2016 - AHS1sampling2

Activity: Sampling - Location: Level 1 / J Hall / Practice 2

Floor plan X

Results received X

Results in Verdant X

Consultant Invoice

November 2016 to November 2016 - 23816.122

Activity: Sampling - Location: J-Hall Practice Room #2

January 2017 to January 2017 - 23816.134 Phase 1

Activity: Periodic Surveillance - Location: Ball field

March 2017 to March 2017 - 23816.011 Phase 1

Activity: Inspection/Survey - Location: Aloha HS

Floor plan

Results in Verdant X

Consultant Invoice

March 2017 to March 2017 - 23816.002 Phase 5

Activity: Sampling - Location: AHS

Floor plan

Results in Verdant X

Consultant Invoice

May 2017 to June 2017 - AHSabatment1

Activity: O & M - Location: Level 1 / A Hall above ceiling

map **x**

test results **X**

daily log **X**

contractor invoice **X**

close out docs X

PBS invoice X

DEQ notification

disposal manifest

May 2017 to May 2017 - 23816.149

Activity: Database Update - Location: AHS

AHS Import materials with Samples

June 2017 to June 2017 - 23816.121 Phase 1

Activity: Inspection/Survey - Location: Aloha High, CTE Interior Renovation

June 2017 to June 2017 - 23816.011 Phase 3

Activity: Major Abatement - Location: Aloha HS

Floor plan

Results in Verdant X

Daily Log

Consultant Invoice

Contractor Invoice

DEQ Notification

Disposal Manifest

Lab samples in Verdant

TEM Air clearance samples

Consultant Close out documents in Verdant

BOLI Form

Certified Payroll dates

July 2017 to July 2017 - 23816.011 Phase 3

Activity: Periodic Surveillance - Location: Aloha HS, CTE Interior Renovation

July 2017 to August 2017 - AHS1sampling1

Activity: Sampling - Location: Level 1 / C9, J1, G10 & G12

Floor plan **x**

Results received **x**

Results in Verdant **x**

Consultant Invoice

October 2017 to November 2017 - AHSsampling2

Activity: Sampling - Location: Level 1 / C Hall and Lobby2

Floor plan **x**

Results received **x**

Results in Verdant **x**

Consultant Invoice **x**

November 2017 to November 2017 - 23816.168 Phase 1

Activity: Sampling - Location: Gym Lobby

Floor plan X

Results in Verdant X

Consultant Invoice

March 2018 to June 2018 - AHS12019-1

Activity: Inspection/Survey - Location: AHS

Bond Project Manager: Jeff Hamman

Bond Project Coordinator: Angela Knotts

May 2018 to May 2018 - 1

Activity: Reinspection - Location: Aloha High

REINSPECTION SUMMARY

The 2018 Asbestos Hazard Emergency Response Act (AHERA) 3-Year Asbestos Reinspection for Aloha High School was completed on May 30, 2018, in accordance with the requirements of 40 CFR, Part 763, Asbestos-Containing Materials in Schools; Final Rule and Notice.

August 2018 to January 2019 - TRC #309290

Activity: Inspection/Survey - Location: Aloha High School

- _ Floor plan
- _ Results received
- _ Results in Verdant
- _ Daily log
- _ Consultant Invoice
- _ Contractor Invoice
- _ DEQ Notification
- _ Disposal Manifest
- _ Lab samples in Verdant
- _ TEM Air clearance samples
- _ Consultant Close out documents in Verdant
- _ BOLI Form
- _ Certified Payroll dates

September 2018 to September 2018 - 23816.201

Activity: Sampling - Location: Aloha High (AHS1) - Main Building

gypsum wallboard ceiling tested less than one percent asbestos in joint compound

Floor plan X

Results received X

Results in Verdant X

Consultant Invoice X

September 2018 to September 2018 - 23816.203

Activity: Sampling - Location: Aloha High School (AHS)

gypsum wallboard tested positive

Floor plan X

Results received X

Results in Verdant X

Consultant Invoice X

July 2019 to July 2019 - 23816.252

Activity: Sampling - Location: AHS1

Sampled building materials in the drama storage and costume storage areas under the stage. All materials tested negative. Floor tiles were 12-inch with yellow mastic on concrete. Chalkboards were steel on plywood with no visible adhesive. No materials were found concealed under carpet.

Floor plan x

Results received x

Results in Verdant x

Consultant Invoice x

September 2019 to September 2019 - 23816.256

Activity: Sampling - Location: AHS1

Sampled tan covebase and mastic in the I Hall near construction activities. Covebase was in poor condition in several locations. Covebase and mastic tested negative for asbestos.

Floor plan X

Results received X

Results in Verdant X

Consultant Invoice X

November 2019 to November 2019 - AHS2019-1

Activity: Sampling - Location: AHS

- _ Floor plan
- _ Results received
- _ Results in Verdant
- _ Daily log
- _ Consultant Invoice
- _ Contractor Invoice
- _ DEQ Notification
- _ Disposal Manifest
- _ Lab samples in Verdant
- _ TEM Air clearance samples
- _ Consultant Close out documents in Verdant
- _ BOLI Form
- _ Certified Payroll dates

Joint compound associated with wallboard walls tested positive, consistent with other parts of the school. Additional testing would likely characterize the material as less than one percent asbestos if desired.

November 2019 to November 2019 - AHS12020-2

Activity: Sampling - Location: Level 1 / VP2

- _ Floor plan
- _ Results received
- _ Results in Verdant
- _ Daily log
- _ Consultant Invoice
- _ Contractor Invoice
- _ DEQ Notification
- _ Disposal Manifest
- _ Lab samples in Verdant
- _ TEM Air clearance samples
- _ Consultant Close out documents in Verdant
- _ BOLI Form
- _ Certified Payroll dates

December 2019 to December 2019 - AHS12019-2

Activity: Sampling - Location: AHS1

Note: The ceramic tile, grout, and caulking tested negative. I wasn't able to see behind the ceramic tile, so I can't say what material it's adhered to. Knowing what we know of Aloha HS, if it's adhered to gypsum wallboard that has joint compound, it's possible that compound is positive like it is throughout the school. However, it could be adhered to wallboard without joint compound (unfinished) or it could be adhered to a bathroom-type backer board that would be negative.

- x Floor plan
- x Results received
- x Results in Verdant

- _ Consultant Invoice

December 2019 to December 2019 - AHS12020-1

Activity: O & M - Location: Lower Level / Lower Gym

- x Floor plan

- x Results in Verdant
- x Daily log
- _ Consultant Invoice
- x Contractor Invoice
- _ DEQ Notification
- _ Disposal Manifest

January 2020 to January 2020 - AHS12020-3

Activity: Inspection/Survey - Location: AHS

Bond Project Manager: Michael Lamberty

April 2020 to May 2020 - TRC #309290

Activity: Sampling - Location: Aloha High School

- _ Floor plan
- _ Results received
- _ Results in Verdant
- _ Daily log
- _ Consultant Invoice
- _ Contractor Invoice
- _ DEQ Notification
- _ Disposal Manifest
- _ Lab samples in Verdant
- _ TEM Air clearance samples
- _ Consultant Close out documents in Verdant
- _ BOLI Form
- _ Certified Payroll dates

February 2021 to February 2021 - AHS12021-1

Activity: Sampling - Location: Wrestling Gym

- _ Floor plan
- _ Results received
- _ Results in Verdant
- _ Daily log
- _ Consultant Invoice
- _ Contractor Invoice
- _ DEQ Notification
- _ Disposal Manifest
- _ Lab samples in Verdant
- _ TEM Air clearance samples
- _ Consultant Close out documents in Verdant
- _ BOLI Form
- _ Certified Payroll dates

March 2021 to March 2021 - AHS12021-2

Activity: Sampling - Location: Music Library

- _ Floor plan
- _ Results received
- _ Results in Verdant
- _ Daily log
- _ Consultant Invoice
- _ Contractor Invoice
- _ DEQ Notification
- _ Disposal Manifest
- _ Lab samples in Verdant
- _ TEM Air clearance samples
- _ Consultant Close out documents in Verdant
- _ BOLI Form
- _ Certified Payroll dates

ACTIVITIES

The following shows historic activities and projects. For more detailed information or related documents see the individual activity information in the database.

Activity Type	Location	Start Date	Related Documents
Sampling	Music Library	03/11/2021	Yes
Sampling	Wrestling Gym	02/19/2021	Yes
Sampling	Aloha High School	04/30/2020	Yes
Inspection/Survey	AHS	01/29/2020	Yes
O & M	Lower Level / Lower Gym	12/27/2019	Yes
Sampling	AHS1	12/03/2019	Yes
Sampling	Level 1 / VP2	11/11/2019	Yes
Sampling	AHS	11/04/2019	Yes
Sampling	AHS1	09/04/2019	Yes
Sampling	AHS1	07/29/2019	Yes
Sampling	Aloha High School (AHS)	09/19/2018	Yes
Water Testing	Aloha	09/12/2018	Yes
Sampling	Aloha High (AHS1) - Main Building	09/05/2018	Yes
Inspection/Survey	Aloha High School	08/20/2018	Yes
Reinspection	Aloha High	05/30/2018	Yes
Inspection/Survey	AHS	03/07/2018	Yes

Activity Type	Location	Start Date	Related Documents
O & M	Level 1 / J1 / at doorway	12/21/2017	Yes
Sampling	Gym Lobby	11/01/2017	Yes
Sampling	Level 1 / C Hall and Lobby2	10/30/2017	Yes
Sampling	Level 1 / C9, J1, G10 & G12	07/26/2017	Yes
Periodic Surveillance	Aloha HS, CTE Interior Renovation	07/06/2017	No
Major Abatement	Aloha HS	06/30/2017	Yes
Inspection/Survey	Aloha High, CTE Interior Renovation	06/09/2017	No
Database Update	AHS	05/08/2017	No
O & M	Level 1 / A Hall above ceiling	05/03/2017	Yes
Sampling	AHS	03/20/2017	Yes
Inspection/Survey	Aloha HS	03/14/2017	Yes
Water Testing	Staff and Training Rooms	02/15/2017	Yes
Periodic Surveillance	Ball field	01/30/2017	No
Sampling	J-Hall Practice Room #2	11/18/2016	Yes
Major Abatement	AHS room J4	11/10/2016	Yes
Major Abatement	AHS room J4	11/10/2016	Yes
Sampling	Level 1 / J Hall / Practice 2	11/01/2016	Yes
Major Abatement	Throughout	07/27/2016	No
Water Testing	Throughout	06/28/2016	Yes
O & M	Level 1 / C9 / Dark Room	05/01/2016	Yes
Sampling	Library Site	04/25/2016	No
Sampling	Aloha HS Library	04/24/2016	Yes
Sampling	Level 1 / C 9 / Dark Room	04/01/2016	Yes
Sampling	Aloha High School, Hall L	03/23/2016	No
Database Update	AHS1	01/01/2004	No
Database Update	AHS1 19766.012 p08	01/01/2004	No
Database Update	AHS1 19766.012 p11	01/01/2004	No
Database Update	AHS1 19766.012 p14	01/01/2004	No
Database Update	AHS1 19766.012 p100	01/01/2004	No
Database Update	AHS2	01/01/2004	No