



**ROCKFORD BOARD OF EDUCATION
INVITATION FOR BID ON SUPPLIES, MATERIALS, EQUIPMENT OR SERVICES
FOR SCHOOL DISTRICT NO. 205
ROCKFORD, ILLINOIS**

IFB No. 22-27 Westview E.S. Roof Replacement

DATE: February 23, 2022

RE: **ADDENDUM NO. 3**

To All Bidders:

Included are modifications, clarifications and/or corrections for the Project Manual and are hereby made a part of the contract documents. Please attach this addendum to the Project Manual(s) in your possession. Please note the receipt of this addendum on the bid form. Bidders shall review changes to all portions of this work as changes to one portion may affect the work of another.

If you plan to hand deliver your IFB submission on the due date, please note you must check in on the 1st floor prior to coming to the bid opening. Please allow time for this as late submission will not be accepted.

Refer all questions relative to the business aspect, Instructions to Bidders, Special Conditions, and questions concerning the technical aspect of the documents to the Director of Purchasing by email at purchasingdeptstaff@rps205.com.

ROCKFORD BOARD OF EDUCATION

By: Dane Youngblood
Director of Purchasing

ADDENDUM

TO: PROSPECTIVE BIDDERS

RE: ADDENDUM # 3

PROJECT NUMBER: BFA #1160 RPS205 2213
IFB NUMBER: IFB 22-27

FOR: Roof Replacement for:
ADDRESS: Westview Elementary School
1720 Halsted Road
Rockford, IL

DATE: 02-23-2022

Please attach Addendum 2 to the above Drawings, and kindly take same into consideration in preparing your proposal.

By 
Rob C. Belles,
Belles Firm of Architecture Inc.

This addendum consists of two text pages including this sheet.

RFI / QUESTIONS

1) The District will NOT accept a 1/4" coverboard.
"SecureShield" at 1/2" IS acceptable.

2) *I have a question in regard to the attachment of insulation and coverboard. Spec calls to fasten first layer and adhere all subsequent layers of insulation. Then it calls to fasten the coverboard. We suggest to fasten both layers of insulation and adhere coverboard and membrane.*

As long as this meets the warranty, and wind requirements this is acceptable. Please note NO mechanical fasteners are to be used at the roof area above the Gym. This is an exposed metal ceiling.