

**ADDENDUM-01 (FIRE & LIFE SAFETY PERMIT REVIEW UPDATES)
ADDENDUM -02 (MECHANICAL PERMIT REVIEW UPDATES)**

DLR GROUP
110 SW Yamhill St., Suite 105
Portland, OR 97204
Tel (503) 274-2675

September 28, 2021

NOTICE: Amend the Drawings and/or Project Manual to the above referenced project as follows:

PROJECT MANUAL

- ITEM NO. 1 SECTION 033000 – CAST-IN-PLACE CONCRETE
A. Add clarifying note for non-slip requirements to 2.1, A, 2.
- ITEM NO. 2 SECTION 033543 – POLISHED CONCRETE FINISHING
A. Add 2.1, “B. Comply with industry standards for OSHA and ADA non-slip requirements.”
- ITEM NO. 3 SECTION 062023 – INTERIOR FINISH CARPENTRY
A. Add 2.3, F, “5. Class C fire rated.”
- ITEM NO. 4 SECTION 084113 – ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
A. Modify 084113, 2.5, B, 3, a. to read “Egress Doors: Not more than 8½ pound force to fully open door.
- ITEM NO. 5 SECTION 092116 – NON-STRUCTURAL METAL FRAMING
A. Add clarification to 092116, 2.1 to include D & E for interior and nonstructural member performance requirements.

DRAWINGS

- ITEM NO. 6 SHEET G0.1 – COVER SHEET
A. Add noted at Deferred Submittal area regarding review procedure required per Code.
- ITEM NO. 7 SHEET CP1.1 – FIRST FLOOR CODE PLAN
A. Exit signage has been added to exit discharge doors, labeled Sign 3. (See A10.3 for more sign info.)
B. Egress through courtyard to be retained during construction. Suggested path noted on plan.
C. Update energy code references.
- ITEM NO. 8 SHEET A0.4 – TYPICAL WALL DETAILS
A. Add notes regarding fasteners at typical head and sill tracks of interior framing.

- ITEM NO. 9 SHEET AD1.1 – FIRST FLOOR DEMOLITION PLAN
- A. Add note to replace glazing in existing window frame to be tempered glazing.
 - B. Add note clarifying that P-lam counters are to be demolished (but retain salvaged base cabinets and uppers).
- ITEM NO. 10 SHEET A1.1 – FIRST FLOOR PLAN
- A. Add ADA clearance rectangle clarification at all sinks.
 - B. Add half height wall adjacent to drinking fountains.
 - C. Add window tag to existing west window “M” directing to Sheet A8.3.
- ITEM NO. 11 SHEET A1.3 – ROOF PLAN
- A. Add section tag directing to parapet height diagram on Sheet A9.1.
 - B. Add radon rooftop equipment references.
- ITEM NO. 12 SHEET A2.1 – RESTROOM PLANS AND ELEVATIONS
- A. Update elevation callout numbers on plan 2A. Adjust notes to reference Room G103 on elevations.
 - B. Relocate SND in individual restrooms.
 - C. Add note for forward approach ADA clearance at lower height drinking fountain.
 - D. Clarify accessible reach heights for toilet accessory mounting heights.
- ITEM NO. 13 SHEET A8.3 – FRAME ELEVATIONS
- A. Add note near Frame Schedule regarding accessible door hardware requirements.
 - B. Add drawing for existing window frame “M” to replace glazing.
 - C. Add notes for restroom doors to be undercut. (SHEET LABELED ADD-02)
- ITEM NO. 14 SHEET A8.4 – FRAME DETAILS
- A. Add note at Detail 4C regarding allowable slope at door thresholds.
- ITEM NO. 15 SHEET A9.1 – EXTERIOR DETAILS
- A. Add drawing 4E for clarification that existing parapet acts as a guardrail for the RTU.
- ITEM NO. 16 SHEET A9.2 – INTERIOR DETAILS
- A. Add note at Details 4A and 4B regarding allowable slope of at flooring transitions.
 - B. Add detail 1A for drinking fountain half height wall.
- ITEM NO. 17 SHEET A10.1 – INTERIOR ELEVATIONS
- A. Modify classroom counters to be 2’-10” high and coordinate associated base cabinets on elevations 2A and 3D.
 - B. Add ADA shelf at cubby within each classroom as shown on modified Detail 1C.
- ITEM NO. 18 SHEET A10.3 – INTERIOR SIGN DETAILS
- A. Add exit sign type 3. Also see CPI.1 for locations.
- ITEM NO. 19 SHEET A11.1 – CASEWORK SECTIONS
- A. Remove detail 2B for 2’-0” tall base cabinet. Not used this project.
 - B. Add clarifying notes to detail 4A regarding insulating drain and ADA clearance outline.
 - C. Add note for ADA shelf at single cubby on Detail 2C.
- ITEM NO. 20 SHEET A12.2 – FIRST FLOOR FINISH PLAN

- A. Add corner guards at new half height wall.
- ITEM NO. 21 SHEET M0.2 – MECHANICAL GENERAL NOTES (SHEET LABELED ADD-02)
- A. Clarify governing code list.
 - B. Clarify relevant deferred submittals list (also see G0.1)
- ITEM NO. 22 SHEET M1.3 – ROOF MECHANICAL PLAN
- A. Add Radon fan to roof.
- ITEM NO. 23 SHEET M2.1 – FIRST FLOOR PIPING PLAN
- A. Add Radon system below slab, and in ceiling space.
- ITEM NO. 24 SHEET M7.1 – MECHANICAL DETAILS AND SECTIONS (SHEET LABELED ADD-02)
- A. Add Radon piping detail.
- ITEM NO. 25 SHEET M8.1 – MECHANICAL SCHEDULES
- A. Add fan schedule for Radon fan.
 - B. Clarify ventilation calculation. (LABELED ADD-02)
- ITEM NO. 26 SHEET E1.1 – LIGHTING PLAN, LEVEL 1
- A. Add exterior lighting above two exterior doors.
 - B. Add clarification to existing light fixture at exit pathway and associated Note 1.
- ITEM NO. 27 SHEET E2.3 – ROOF POWER PLAN, LEVEL 1
- A. Add new exhaust fan references
- ITEM NO. 28 SHEET E7.1 – ELECTRICAL SCHEDULES
- A. Add new exhaust fan to mechanical equipment schedule
- ITEM NO. 29 SHEET E8.1 – PANEL SCHEDULES
- A. Re-use existing spare in panel 2A1 for exhaust fan.

PROJECT MANUAL ATTACHMENTS:

SECTION 033000 – CAST-IN-PLACE CONCRETE
SECTION 033543 – POLISHED CONCRETE FINISHING
SECTION 062023 – INTERIOR FINISH CARPENTRY
SECTION 084113 – ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
SECTION 092116 – NON-STRUCTURAL METAL FRAMING

DRAWING ATTACHMENTS:

SHEET G0.1 – COVER SHEET
SHEET CP1.1 – FIRST FLOOR CODE PLAN
SHEET A0.4 – TYPICAL WALL DETAILS
SHEET AD1.1 – FIRST FLOOR DEMOLITION PLAN
SHEET A1.1 – FIRST FLOOR PLAN
SHEET A1.3 – ROOF PLAN
SHEET A2.1 – RESTROOM PLANS AND ELEVATIONS
SHEET A8.3 – FRAME ELEVATIONS
SHEET A8.4 – FRAME DETAILS
SHEET A9.1 – EXTERIOR DETAILS
SHEET A9.2 – INTERIOR DETAILS
SHEET A10.1 – INTERIOR ELEVATIONS
SHEET A10.3 – INTERIOR SIGN DETAILS
SHEET A11.1 – CASEWORK SECTIONS
SHEET A12.2 – FINISH FLOOR FINISH PLAN
SHEET M0.2 – MECHANICAL GENERAL NOTES (SHEET LABELED ADD-02)
SHEET M1.3 – ROOF MECHANICAL PLAN
SHEET M2.1 – FIRST FLOOR PIPING PLAN
SHEET M7.1 – MECHANICAL DETAILS AND SECTIONS (SHEET LABELED ADD-02)
SHEET M8.1 – MECHANICAL SCHEDULES (SHEET LABELED ADD 01 & ADD 02)
SHEET E1.1 – LIGHTING PLAN, LEVEL 1
SHEET E2.3 – ROOF POWER PLAN, LEVEL 1
SHEET E7.1 – ELECTRICAL SCHEDULES
SHEET E8.1 – PANEL SCHEDULES

END OF ADDENDUM-01 & 02