

**ADDENDUM NO. 1**

PROJECT: 2022 Sitework Projects – Bid Package #2

OWNER: Dexter Community Schools

LANDSCAPE ARCHITECT/  
ENGINEER: Beckett & Raeder, Inc.  
535 W. William, Suite 101  
Ann Arbor, MI 48103

DATE: April 4, 2022

BID DUE DATE: April 11, 2022 (revised)

This Addendum is issued to inform Bidders of revisions to the Bidding Documents and to incorporate these changes into the Bidding Documents.

All requirements contained in the Bidding Documents shall apply to this Addendum and the general character of the work called for in the Addendum shall be the same as originally set forth in the applicable portions of the Bidding Documents for similar work unless otherwise specified under this Addendum.

The time of completion will not be affected in this Addendum.

This Addendum, as well as any previous Addendums, are hereby made a part of the Bidding Documents and shall be included in the Contract Documents.

On the Bid Form, the Contractor shall state all Addendum numbers in order to acknowledge receipt of the Addenda. The Contractor's base bid and unit prices shall reflect this Addendum.

**SPECIFICATIONS**

1. None.

**DRAWINGS:**

The drawing sheets below are hereby revised as described:

1. **Sheet C6.2** – DHS Twin Turf Fields – Utility and Restoration Plan (not reissued)
  - a. Revise note regarding domestic water source within Dexter High School building to change 2½" water source to 2" water source. Revised note shall read as follows:

*"PROVIDE 2 CW OFF EXISTING 3 OR LARGER CW MAIN IN BOILER ROOM. PROVIDE TEE AND LEAD FREE ISOLATION VALVE WITH RPZ AND ROUTE PIPING TO 12 INCHES A.F.F.. PROVIDE INLINE WATER METER ON NEW PIPING IN BOILER ROOM. WATER METER SHALL REPORT WATER CONSUMPTION TO EXISTING JCI BUILDING MANAGEMENT SYSTEM. COORDINATE TERMINATION POINT WITH BOILER ROOM WITH SITE UTILITY CONTRACTOR. PIPE MATERIAL TO BE TYPE L HARD COPPER. PROVIDE 1 FIBERGLASS INSULATION ON NEW CW PIPING. PROVIDE CLEVIS HANGERS WITH INSULATION SHIELDS. ROUTE RPZ DRAIN TO NEAREST FLOOR DRAIN IN BOILER ROOM."*

OTHER

1. None.

END OF ADDENDUM