



ADDENDUM NUMBER ONE
11 April 2022
EDUCATION CENTER FENCING PROJECT
BID B21-22

Issued By:
Lompoc Unified School District.
1301 North A St.
Lompoc, CA 93436

To all bidders submitting proposal(s) for the captioned project: this Addendum is hereby made part of the Contract Documents to the same extent as though it was originally included therein and takes precedence over the original documents and any previous addenda.

Acknowledge receipt of the Addendum on Form of Proposal

A. PRE-BID QUESTIONS

Q1: At gate C can we use existing concrete v swell to attach bolt down v-track.

A1: Yes. A bolt in is preferred.

Q2. At gate F, E, G, Both A's and Gate B on the road, can we use existing 6 5/8 gate posts as our gate posts as long as they are plum and have an extension welded to them to have a finished height of 8'. The Contractor would then clean and coat them black to match the new fence. Would this be acceptable?

A2: Yes, as long as they are painted to match.

Q3. Security temp fence must be in place on A street and Central ave. during removal and placement of these fences and gates?

A3: Yes.

Q4. 2500 psi. 5 sack acceptable concrete mix design.

A4: Yes.

Q5. On Gates it states that the school district would like 2.5" frames however the bottom rail of the slide gate is only 2" is a 2" 11 ga. frame sufficient for all gates except the bottom rail of the slide gate which will be 2x4?

A5: Yes.

END OF ADDENDUM NUMBER ONE