

ADDENDUM No. 1 FOR

RFQ/P No 2223-Bonds01 MATHSON PAVING

PLEASE SEE THE CHANGES/ADDITIONAL INFORMATION PROVIDED BELOW:

Item#1 BID FORM AND PROPOSAL:

Due to constraints, the district request the additional Additive/Deductive Alternate:

Alternate #4

_____ dollars \$ _____

Additive/Deductive

Scope:

- **Off-Hours Work for Task #1 (work to start not earlier than 3:00 p.m. and end not later than 10:30p.m.)**
- **Erect temporary Construction Fencing to Enclose the School Quad**

1 **REQ'D TEMPORARY FENCING**
CONSTRUCTION FENCING 1/2"-1'-0"

Item#2 Sheet EDU-1

This sheet conflicts with Sheet EDU-2 and EXHIBIT A – SCOPE OF WORK; the following updates are made to Sheet EDU-1 to clarify scope:

- Strike, "*Remove and fill ten (10) existing tree planters*"
- Replace with, "*Remove and fill seven (7) existing tree planters*"
- Strike, "*Retain three(3) existing tree planters*"
- Replace with, "*Retain six(6) existing tree planters*"

Item#3 Clarify Asphalt Paving Detail
Pedestrian Asphalt paving to be comprised of 2" Asphalt concrete over 6" Compacted Class II (New or Recycled) Aggregate Base; fog seal is **not required**

Item#4 Removal Depth
Remove not less than the existing 2" AC and recompact base; low traffic pedestrian area only

Item#5 Filled Tree planters
Planters will be filled and paved over with Asphalt Concrete conforming to Detail 1, Sheet D-1 and Item #3 above.

Please submit a signed copy of this addendum with your RFQ/P response.

Company name: _____

Signature: _____

Print Name: _____ Date: _____