

**Longview School District No. 122  
Reroof Projects at Business Office, RA Long HS Gym Building,  
and MOTF Main Building**

**ADDENDUM #2  
Date of Addendum: July 1, 2022**

**1.0 NOTICE TO ALL BIDDERS AND PLANHOLDERS**

The Contract Documents for the above-referenced Project are modified as set forth in this Addendum. The original Contract Documents and any previously issued addenda remain in full force and effect, except as modified by this Addendum, which is hereby made part of the Contract Documents. Bidder shall take this Addendum into consideration when preparing and submitting a bid and shall acknowledge receipt of this Addendum in the space provided on the Bid Form.

**2.0 CLARIFICATION**

2.1 Existing roof core cuts information is as follows:

Business / Administration Office:

Deck: 1/2" Plywood

Existing Roof: TPO membrane over 1/2" Dens Deck gypsum board

R.A. Long HS Gym:

Deck: Wood

Existing Roof: TPO membrane over 3.6" Polyisocyanurate

MOTF Main Building:

Deck: Wood

Existing Roof: TPO membrane over 3.6" Polyisocyanurate

2.2 Since the intent of the project is to reroof over the existing membrane roofing system, new crickets were not shown as being required. During the Construction Phase, if the selected Contractor deems additional crickets are necessary, the Contractor shall provide a change order proposal for a bidder-designed cricket layout that meets the required fire rating for Owner review and approval.

**3.0 BIDDING REQUIREMENTS**

3.1 Instructions to Bidders:

DELETE Section 1.04, C Bid Security. Per the Owner, a Bid Security will not be required for this project.

## **4.0 SCOPE OF WORK**

### **4.1 Business / Administration Office:**

Sheet A201: ADD the following to Keynote 4 "IF CONTRACTOR DEEMS IT NECESSARY TO REMOVE SAFETY LINES IN ORDER TO INSTALL ROOFING SYSTEM, THE CONTRACTOR IS REQUIRED TO RE-INSTALL AND RE-CERTIFY THE FALL PROTECTION SYSTEM."

### **4.2 R.A. Long HS Gym:**

Sheet A201: ADD the following to Keynote 5 "AND CURB TO BE REMOVED. INFILL OPENING WITH PLYWOOD DECK OF THICKNESS TO MATCH EXISTING DECK. SUPPORT WITH MINIMUM 2x8 WOOD FRAMING ATTACHED TO EXISTING ROOF FRAMING. PROVIDE INSULATION OF SAME THICKNESS AS EXISTING TO PROVIDE APPROPRIATE SURFACE FOR REROOFING."

DELETE General Note 1.

## **5.0 SITE VISIT**

5.1 Pre-Bid Conference Attendee Sign-In Sheet attached.

### **Attachments:**

Pre-Bid Conference Attendee Sign-In Sheet

**END OF ADDENDUM #2**

