

Alum Rock Unified School District

San Antonio Academy Playground Surface Installation

Adelante I Playground Surface Repair

1. Adelante Dual Language Academy – Adelante I, 2999 Ridgemont Dr.
2. San Antonio Elementary – 1721 E. San Antonio

SCOPE OF WORK

SAN ANTONIO REPLACEMENT

TASK 1 Work includes demolition and removal of existing rubber tiles material, and subsurface to base material.

Task 2 Excavate and remove existing materials as needed to provide for 10", type II road base material, 4" Poured in Place Safety Surfacing (or thickness required for critical fall height). Final ½" thick color wear surface to be selected by owner. Finish surface to be level and free of variations which would cause ponding or tripping hazard. Surface to be level with existing concrete grade with maximum slope 2% in any direction.

TASK 3 Alternative to Task 2. Excavate materials to allow for 12" thick layer of Wood Fibar or equivalent Safe Guard Surfacing Wood fiber Fill material. Installation of Geotextile Fabric Liner anchored to provide weed barrier. Level and compact wood fill material.

SCOPE OF WORK

ADELANTE I REPAIR

TASK 4: Provide clean cuts for repair areas as directed by owner. Remove existing damaged rubber surface material down to base material. Thoroughly clean and prep areas of repair. Provide 4" to match existing Poured in Place Safety Surfacing. Final ½" thick color wear surface to match to existing if possible. Finish surface to be level and free of variations which would cause ponding or tripping hazard. Surface to be level with existing concrete grade with maximum slope 2% in any direction.