

# Valley View Large Playground

## A3. ASPHALT REPAIRS AT (1) DRAIN LOCATION

Sawcut, demolish and remove (1) 10'x10' areas of 4" asphalt at drains to promote positive drainage.

Pour baserock and compact, as needed, and pour and compact 4" of hot mix asphalt.

## A4. ASPHALT CURB INSTALLATION AT EXTERIOR FENCE

Pour and compact roughly 165LF of 6"x7" asphalt berm to be backfilled with landscape material by the District.

Berm installed to retain landscape and protect from existing exposed concrete footings.

