

**ST. TAMMANY PARISH SCHOOL BOARD
COVINGTON, LOUISIANA**

The St. Tammany Parish School Board will receive sealed bids until 2:00 p.m., Friday, October 7, 2022, on Library Furniture for Abita Middle School, in accordance with the following instructions and attached specifications.

* * * * *

1. Bids shall be submitted on the attached bid form. All conventional paper bids shall be either hand delivered or sent by registered or certified mail, UPS or FedEx with a return receipt requested to the St. Tammany Parish School Board Office, 321 N. Theard Street, Covington, Louisiana 70433, in a sealed envelope clearly marked on the outside "BID #1811 ON LIBRARY FURNITURE FOR ABITA MIDDLE SCHOOL – OCTOBER 7, 2022." All bids arriving after this date and hour will be returned unopened to the bidders. No bid may be withdrawn for at least thirty (30) days after the scheduled closing time for receipt of bids.

2. Bids may also be submitted electronically. Please find bid related materials and place electronic bids at www.centralbidding.com.

3. For an appointment to visit the work site, contact Cameron Tipton, Lead Construction Supervisor, (985) 898-3291. A drawing of the school library with Furniture Tags and Item #'s indicating furniture placement is enclosed for your reference (see attachment #1).

4. All bids shall include costs of manufacturing, packing, prepaid delivery to school, unloading and storing where directed by the Owner within the library, uncrating, assembling, final placing, installing as per manufacturer's instructions, and removal of all debris from the premises.

5. Color samples for shelving, table, chairs, circulation desk, computer station, lounge units, high pressure laminate tops and steel shelves should be included as part of your bid. A full size shelving unit sample may be required and must be delivered within 10 days of request.

6. If bidding equipment other than as specified, deviations from specifications shall be stated in your bid. Catalog cuts, descriptive literature and manufacturer detailed specifications must be included as part of your bid.

7. Details of warranty shall be included as part of your bid.

8. Damage to the existing building or equipment caused by the work under this contract shall be repaired or replaced by new materials to original conditions as approved by the Owner.

9. A lump sum payment will be paid to the successful bidder after 100% job completion. The St. Tammany Parish School Board reserves the right to withhold payment because of damage or improperly installed furniture or equipment.

10. ALL BIDS SHALL BE ACCOMPANIED BY AN ORIGINAL, FULLY EXECUTED BID BOND, CERTIFIED/OFFICIAL CHECK, CASHIER'S CHECK OR MONEY ORDER IN THE AMOUNT OF FIVE PERCENT (5%) OF THE TOTAL AMOUNT OF THE BID. BIDS WILL NOT BE CONSIDERED UNLESS THE REQUIRED BID BOND OR CHECK IS ATTACHED.

11. ***If submitting bid electronically, then bid security must be in the form of a bid bond only. A copy of the bid bond must be included in your bid documents and the original bid bond must be received by the St. Tammany Parish School Board Office within 48 hours of the bid opening. No cashier's check, certified check or money order will be accepted for an electronic bid.*** Failure to comply will cause your bid to be non-responsive.

12. A Performance Bond in the total amount of the contract will be required from the successful bidder if the total cost of the order exceeds \$1,000.00 and cannot be delivered within a fourteen (14) day period.

13. The successful bidder(s) shall furnish a Certificate of Insurance within fifteen (15) calendar days after award of bid but prior to delivery of merchandise.

Certificate should provide for:

- a. Comprehensive General Liability - \$1,000,000.00 combined single limit. Coverage to include premises, operations, contractor's protective liability, products and completed operation, contractual liability.
- b. Comprehensive General Automobile Liability Insurance with minimum limits of Bodily Injury – Each Person \$1,000,000.00, Bodily Injury – Each Occurrence \$1,000,000.00, Property Damage – Each Occurrence \$1,000,000.00. Coverage shall be written to include all owned, non-owned and hired vehicles.
- c. Workers Compensation – State of Louisiana, Employer's Liability, Statutory requirements \$1,000,000.00.

14. Cash discounts, if offered, will be taken into consideration in determining the low bidder. DISCOUNTS LESS THAN THIRTY (30) DAYS WILL NOT BE CONSIDERED IN MAKING AN AWARD. Beginning date for discount period shall be determined by date of invoice or date of delivery of merchandise whichever occurs last.

15. Successful bidder must consent to and yield to the exclusive venue and jurisdiction of the 22nd Judicial District Court for the Parish of St. Tammany, and waive any and all claims of entitlement to removal of any case from this jurisdiction, including any removal to any Federal Court, in connection with any proposal or bid.

16. It is the intent of the specifications to invite bids on high quality merchandise. Mentioning a brand, manufacturer and number is done only to establish the standard of quality desired. It is not the intent to eliminate brands of equal quality but instead to set forth and convey to prospective bidders the general style, type, character, and quality of the product desired.

17. The School Board reserves the right to select a higher priced item where, in the judgment of the School Board, such item is of superior quality or design or would be more suitable for the purpose intended. The School Board further reserves the right to adjust quantities by increasing or decreasing and to reject any and all bids.

18. In accordance with LA Revised Statute 38:2252, "Preference is hereby given to materials, supplies and provisions, produced, manufactured or grown in Louisiana, quality being equal to articles offered by competitors outside of the state." As a bidder you must indicate on your bid response that you are claiming a preference.



FRANK J. JABBIA
Superintendent

**ST. TAMMANY PARISH SCHOOL BOARD
COVINGTON, LOUISIANA**

**SPECIFICATIONS AND BID FORM ON
LIBRARY SHELVING FOR ABITA MIDDLE SCHOOL**

SHELVING:

Library shelving to consist of wood shelving units with steel shelves. Wood finish units to be River Cherry on Maple. Metal shelves are 18-gauge steel with notches on the underside to rest on turned and grooved steel pegs. Color for metal shelves to be Sand. Flat shelf is 1" thick and triple bent front and back edges provide strength and eliminate sharp edges. Book stop shelf is bend upward to form 90° angle, 1⁵/₈" H above the shelf surface to function as a book stop. Electrostatically applied powder-coat finish. Metal shelf units are shipped with a wood base shelf. Base is a pre-assembled box with a finished outer kick rail enables shelving to be assembled in the vertical position. Bottom shelf is set into place by using steel pegs. All double-faced shelving units to be 24" deep. All single-faced shelving to be 12" deep. The end panels are 1-3/16" thick, particleboard core construction with Grade A Maple veneer on both faces. The vertical edges of the panel are banded with a 1.5 mm thick solid Maple external band with a 1/32" radius. On single-face units, the back vertical edge is not edge banded but left unfinished. The panel base has a 1/8" deep by 1/4" high vein line 4" from the bottom. Two (2) stainless steel adjustable glides are at the bottom of each panel. Top shelf is 3/4" thick Maple construction. The flush-fitting cornice rail at the face sides is 3/4" thick by 2¹/₈" high solid maple. Shelf is attached using 1¹/₄" x 1¹/₄" wood cleats with bolts and metal inserts in the end panels. Warranty: 15-year on CrossRoads Library Furniture. Manufacturers to be KI, or equal.

PERIODICAL SHELVING:

Periodical adjustable shelves include 3/4" solid wood angled bracket supports and an 18-gauge steel shelf pivot bracket. A 3/4" solid wood shelf with a 1/2" x 1¹/₂" stop rail is mounted at an angle of approximately 45° so that periodicals can be easily viewed. The shelf pivots and can be flipped up to lay flat for storage. Top shelf is 3/4" thick, solid Maple construction. The flush-fitting cornice rail at the face sides is 3/4" thick by 3³/₄" high solid maple and is attached with 1¹/₄" thick wood cleats and corner blocks. Base is a pre-assembled box with a finished outer kick rail enables shelving to be assembled in the vertical position. Bottom shelf is set into place and positioned by stop rails attached to the bottom. Two (2) adjustable shelves are 3/4" thick solid Maple construction with the front edge in select Maple with matching color and grain. The shelf is notched at the ends to fit over dowel pins and prevent accidental removal. Two (2) 1" thick rails mounted on the end panels are notched to hold eight newspaper sticks at an angle for easy removal and display. Warranty: 15-year; Manufacturers to be KI, or equal.

ROLLING BOOK CART:

All end panels and shelves are 3/4" plywood with Maple veneer laminate and a 1.5 mm solid wood edge banding. Shelves are attached to the end panels using cam lock fasteners and solid wood dowels. Bottom shelf is reinforced with wood cleats screwed into the shelf and end panels. Casters are two (2) swivel and two (2) stationary. Warranty: 15-year and 15-year on casters; Manufacturers to be KI, or equal.

TABLES AND CHAIRS:

Study tabletop is 1¼” thick, particleboard core construction, with .05” high-pressure laminate facer and .026” backer on the underside. All four (4) edges are banded with a 1¼” thick by 2” wide solid Maple. The edge is beveled to a ¼” radiused bullnose at the top. Legs are attached to the apron using dovetail joinery and heavy-gauge metal plate with two (2) heavy-duty anchoring bolts. The legs are 2¼” square glued up face-to-face. A ¾” thick solid Maple apron rail is fit between the legs on all four (4) sides of the table. Apron has a full-length arc that is 3⅞” H at the ends and 2” at the center. Each leg has a 2” diameter nylon-based adjustable leveling glide with a 1½” threaded stem. Standard height is 29”. Manufacturers to be KI, or equal. Unupholstered, armless, 18” H wood chair with five (5) 4” back posts, steam bent to shape and 1” thickness. Seat is ganged into bottom slat and fastened to each back post by one #12 x 2¼” tapping screw concealed by a wood button. Two (2) #12 x 2” tapping screws secure the seat to the front rail and one #12 x 2” tapping screw to secure the seat to each side rail. Bottom slat is made of four 4” stock, bent to a 24” radius, 13/16” thickness by 3⅜” W and double doweled to the back posts using ⅜” x 1½” dowels. Chair glides are ⅞” diameter rubber cushion chrome-plated. Chair glue used in final assembly shall be polyvinyl alcohol ester blend with polyvinyl acetate. Warranty: 15-year and 15-year on Glides; Manufacturers to be KI, or equal.

1. Five (5) ranges to consist of three (3) book stack units, double faced 42” H wood shelving units with CrossRoads book stop shelf per unit, or equal, no back panel. Metal shelf color to be Sand. There are to be four (4) adjustable metal shelves and two (2) wood bottom base shelf. (TAG BC-2 & BC-1 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
BC-1	5	CRSSD4224S-M	D/F Starter, Straight panel, metal shelves, 42”H X 24”D X 37½”W.
BC-2	10	CRSSD4224A-M	D/F Adder, straight end panel, metal shelves, 42”H X 24”D X 36¼”W.

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

2. One (1) range to consist of two (2) book stack units, double faced 42” H wood shelving units with CrossRoads book stop shelf per unit, or equal, no back panel. Metal shelf color to be Sand. There are to be four (4) adjustable metal shelves and two (2) wood bottom base shelf. (TAG BC-2 & BC-1 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
BC-1	1	CRSSD4224S-M	D/F Starter, Straight panel, metal shelves, 42”H X 24”D X 37½”W.
BC-2	1	CRSSD4224A-M	D/F Adder, straight end panel, metal shelves, 42”H X 24”D X 36¼”W.

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

3. One (1) range to consist of four (4) book stack units, double faced 42" H wood shelving units with CrossRoads book stop shelf per unit, or equal, no back panel. Metal shelf color to be Sand. There are to be four (4) adjustable metal shelves and two (2) wood bottom base shelf. (TAG BC-2 & BC-1 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
BC-1	1	CRSSD4224S-M	D/F Starter, Straight panel, metal shelves, 42"H X 24"D X 37½"W.
BC-2	3	CRSSD4224A-M	D/F Adder, straight end panel, metal shelves, 42"H X 24"D X 36¼"W.

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

4. Perimeter/Wall shelving One (1) range to consist of four (4) book stack units, single faced 60" H x 12" D wood shelving unit with CrossRoads bookstop metal shelves, or equal, no back panel and non-finished backside. There are to be four (4) adjustable book stop shelves and one (1) wood bottom base shelf. (TAG BC-3 & BC-4 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
BC-3	1	CRSSS6012S-M	S/F Starter, Straight panel, metal shelves, 60"H X 12"D X 37½"W
BC-4	3	CRSSS6012A-M	S/F Adder, straight panel, metal shelves, 60"H X 12"D X 36¼"W.

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

5. Perimeter/Wall shelving One (1) range to consist of nine (9) single faced 60" H x 12" D wood shelving unit with CrossRoads book stop metal shelves, or equal, no back panel and non-finished backside. There are to be four (4) adjustable book stop shelves and one (1) wood bottom base shelf. (TAG BC-3 & BC-4 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
BC-3	1	CRSSS6012S-M	S/F Starter, Straight panel, metal shelves, 60"H X 12"D X 37½"W
BC-4	8	CRSSS6012A-M	S/F Adder, straight end panel, metal shelves, 60"H X12"D X36¼"W

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

6. Perimeter/Wall shelving One (1) range to consist of three (3) book stack units, single faced 60" H x 12" D wood shelving unit with CrossRoads bookstop metal shelves, or equal, no back panel and non-finished backside. There are to be four (4) adjustable book stop shelves and one (1) wood bottom base shelf. (TAG BC-3 & BC-4 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
BC-3	2	CRSSS6012S-M	S/F Starter, Straight panel, metal shelves, 60"H X 12"D X 37½"W.
BC-4	1	CRSSS6012A-M	S/F Adder, straight end panel, metal shelves, 60"H X12"DX 36¼"W

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

7. Perimeter/Wall shelving One (1) range to consist of two (2) CrossRoads Periodical book stack units or equal, single faced 60" H x 12" D wood shelving unit with back panel and non-finished backside. Three (3) adjustable pivoted shelves, (TAG BC-5 & BC-6 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
BC-5	1	CRPERS6012S-M	S/F Starter, Straight panel, metal shelves, 60"HX12"DX 37½"W
BC-6	1	CRPERS6012A-M	S/F Periodical Adder, straight end panel, metal shelves, 60"HX 12"D X 36¼"W.

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

8. CrossRoads Rolling Book Cart with slanted shelves or equal, 41" H, two (2) double-face slanted shelves and one (1) flat shelf, River Cherry on Maple. (TAG RC-1 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
RC-1	1	CRTRK4140SL-M	Rolling Book Cart with casters, 2- double-face slanted shelves, 44-51/64"H X 14¼"D X 39⅞"W.

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

9. CrossRoads wood chair or equal, Maple wood and wood finish to be Monticello Maple on Maple. (TAG C-1 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
C-1	36	CRCHR18	Wood chair, armless, unupholstered, 18"H seat.

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

10. CrossRoads Study Table or equal, Rectangle, 29"H, Maple wood, wood finish to be Monticello Maple on Maple, Black (1595-60) laminate, No Grommets/Powerup. (TAG T-1 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
T-1	4	CRT3672-M	Study table, straight apron, 36"D x 72"

NAME BRAND: _____

MODEL NUMBER: _____

TOTAL PRICE: _____

WARRANTY TERMS: _____

11. CrossRoads Study Table or equal, Round, 29"H, Maple wood, wood finish to be Monticello Maple on Maple, Black (1595-60) laminate, No Grommets/Powerup. (TAG T-2 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
T-2	3	CRT48R-M	Study table, straight apron, 50"D

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

12. Perimeter/wall computer station, Intellect Wave 4-leg large chair or equal, frame consist of 3/4" x 1 1/2" O.D. 14-gauge elliptical steel tubing welded to a 14-gauge steel plate, no fire retardant, frame color to be STARLIGHT SILVER METALLIC; and a Ruckus, 20-33" sit height adjustable activity table or equal, all adjustable-height table legs adjust with screws in 1" increments. Rectangle (round corner) top has a 2 mm bonded edge band for tamper and moisture resistance as a 74P edge, 1 1/4" thickness with .030" thick high-pressure laminate top surface and .028" phenolic backer (bottom surface), Casters are shipped assembled to the legs, casters are 50 mm O.D. double-wheel, molded nylon, black, unhooded, with brake and use a 5/16" – 18 threaded steel stem for mounting, base finish to be STARLIGHT SILVER METALLIC, FROSTY WHITE (1573-60) laminate. Warranty: 15-year on Glides; 15-year on Intellect wave classroom seating; 15-year on casters; 15-year on all HPL & LPL laminate material on Ruckus tables. Manufacturers to be KI, or equal. (TAG C-2 & T-3 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
C-2	3	IW418	4-leg chair, nylon glides, racked, Cool Grey
T-3	3	RTEEA2048-74P	Activity table, 20"Dx48"W, casters, Ultra Blue edge color

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

13. Ruckus, single post Pneumatic adjustable mobile lectern w/modesty panel or equal, top worksurface adjusts between 28 3/4" and 42 3/4" from the floor by using a pneumatic cylinder with a locking feature to prevent vertical movement when any force is applied to the worksurface, the total amount of weight the cylinder can lift without assistance is 20lbs., the lower frame is constructed with 2" and 1 1/4" by 14-gauge steel tubing and can be nickel-chrome plated or finished in power-coat paint after all welding processes are complete, the 1 1/4" horizontal tubing is capped with a plastic plug (offered in black only), adjustable upper column assembly is constructed of a 3" diameter aluminum extrusion and is capped using black cast zinc flange attached by six, 1/4" x

20 x 1½” screws, assembly is finished in power-coat paint, top consists of high-density particleboard core covered with .030” high-pressure laminate top to be RIVER CHERRY (7937-38) and a .020” phenolic backing sheet and 73P polypropylene edge with a finished top thickness of 13/16”, 20” x 30” laminate worksurface includes a curved front comfort curve on user side and 2¾” radius corners, black, hard floor casters are single wheel with a 40mm outside dimension, modesty panel cover is CLOUD ACRYLIC and is 20” x 20” with 2.31” radius corners constructed of ¼” Acrylite Satinice material with a velvet texture and satin surface on both sides, panels are located on the underside of the worksurface and held in place using six #10-24 x ¾” knurled thumb-screws and two 14-gauge steel rackets, frame color CHAMPAGNE METALLIC, Code compliance: ANSI/BIFMA, Warranty: 15-year; 15-year on casters; 15-year on all HPL & LPL laminate material on Ruckus lectern. Manufacturer to be KI, or equal. (TAG L-1 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
L-1	1	CRT48R-M	Mobile lectern, no book storage, River Cherry edge color

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

14. Aristotle Classic Main Circulation Desk or equal, all worksurfaces, tops and end panels are 1” thick, bookcases have 1” thick top and shelves, edge banding is 2.5 mm thick, full height end and back panels, grommets have a 2¾” diameter opening, WHITE laminate, COPACABANA base laminate; and an Oath Task arm chair with self-weighting (weight-activated) mechanism or equal, height-adjustable arms mounted directly to the seat board, plywood seat board with molded urethane foam is upholstered using a drawstring method and finished with a black plastic under-shroud, BLACK mesh backrest, BLACK nylon base, upholstery fabric grade 1, 1K SKYLINE, Code compliance: BIFMA & TB 117-2013; Oath Warranty: 15-year and 15-year on casters; Aristotle Warranty: Lifetime, 15-year all HPL & LPL laminate material; Manufacturer to be KI or equal, (TAG D-1 & C-3 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
D-1	2	KDA9630.H	Classic Desk Shell, two (2) full end panels, full back panel height with grommet center rear, 29”H x 30”D x 96”W
D-1	1	KDA3030.HS22334866	Classic Desk Shell, two (2) full end panels, full back panel height with grommet center rear, 29”H x 30”D x 30”W
D-1	1	KDA9624.H	Classic Desk Shell, two (2) full end panels, full back panel height with grommet center rear, 29”H x 24”D x 96”W
D-1	1	KOSG48.H	Reception Gallery, White, Copacabana, clearance above desk is 14”; 15”H x 12”D x 48”W
D-1	1	KOSG96.H	Reception Gallery, White, Copacabana, clearance above desk is 14”; 15”H x 12”D x 96”W
D-1	1	KQRB2465L.HS22334867	Quarter-Round Bookcase, Left, White, Copacabana, four white, fixed shelves, 65”H x 24”D X 24”W
C-3	3	OH84QB	Task arm chair, hard floor casters, 300 lb. weight rating

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

15. Sway lounge chair or equal, non-contrast, seat shell and 4-leg base shall be COOL GREY and is constructed of rotationally molded polyethylene, 12-gauge steel rotating contact surface is attached to the bottom of the seat shell, felt glides, Fabric grade 2, 2N NEEDLEPNT CREWEL, Code compliance: TB 117-2013; and a Sway table or equal, 12-gauge steel apron and 4-leg base to be COOL GREY, Felt glides, table top has high-pressure laminate to be MONTICELLO MAPLE (7925-38) overlaying the sides and top of a particle board structure; Warranty: Lifetime and 15-year on foam and 1-year on Felt – Glides; Manufacturer to be KI or equal, (TAG C-4 & T-4 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
C-4	4	SYCNC	Lounge chair, 33"W x 32½"D x 41¾"H
T-4	2	SYTB	Table, no power, 27"W x 27"D x 14.5"H

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

16. MyPlace curve lounge units or equal, range to consist of three (3) inside back, 30° curve, concealed glide, 32" low-back, contrast, base fabric grade L, ARC, BLUEPRINT, seat fabric grade C, 1K SKYLINE, BERMUDA, back fabric grade L, ARC, BLUEPRINT; and two (2) backless 30° curve, concealed glide, contrast, base fabric grade L, ARC, BLUEPRINT, seat fabric grade C, 1K SKYLINE, BERMUDA; and three (3) inside back 45° curve, concealed glide, 32" low-back, contrast, base fabric grade L, ARC, BLUEPRINT, seat fabric grade C, 1K SKYLINE, BERMUDA, back fabric grade L, ARC, BLUEPRINT; all seats and back frames are constructed of ¾" laminated hardwood plywood, all main frame joints are nailed and glued in addition to interlocking joinery across all stress points, foam is 2.5 density, 45 lb. compression with 2.5" thick seat, topped with .5" of 2.6 density 80 lb. compression foam, backs are 1.5" total thickness consisting of 1" thick 2.5 density – 45 lb. and a .5" topper of 2.6 density – 80 lb. compression foam, ¾" of 2.6 density, 80 lb. compression foam covers all exposed sides, all units are double-needle stitched at all primary seams, concealed glides are .38"H, of nail-in molded white nylon, gangers are made from 7-gauge steel (.179" thick), powder-coated black and mounted to the underside of any lounge using ¼" x 1" wood screws, Warranty: life-time, 15-year on Foam; 15-year on Glides; Code compliance: BIFMA & TB 117-2013; Manufacturer to be KI or equal, (TAG O-2, O-1 & O-3 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
O-2	3	MPCI30/CGL/FC	30° curve, 32" Low-back, no moisture barrier, 28"W x 26"D
O-1	2	MPC30/CGL/FC	30° curve, backless, no moisture barrier, 28"Wx26"Dx18"H
O-3	3	MPCI45/CGL/FC	45° curve, 32" Low-back, no moisture barrier, 41.5"Wx26"D

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

OPTIONAL OUTDOOR FURNITURE:

17. Outdoor balcony furniture, Promenade 6' square umbrella or equal, two piece threaded aluminum pole with fiberglass rib umbrella frame, 1.5" diameter pole, black aluminum pole, stainless steel attached locking pin; 75 lb., freestanding umbrella base or equal, 24" x 24", square steel base with wheels; 100% marine grade Recacril fabric or equal, solution dyed acrylic material; Manufacturer to be Plantation Prestige or equal; Sid cluster seating with umbrella hole or equal, 30"H x 75"W x 75"D, 75 lbs., aluminum frame, square aluminum legs, bolt down bracket included; Manufacturer to be EMU Americas or equal; Warranty: 3-year on EMU seating; Warranty: 1-year on Promenade umbrella frame, 7-year on Recacril fabric, (TAG U-1A, U-1B & T-5 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
U-1A	2	9602-01	6' square, manual lift, black pole, Grade A fabric: Capri Blue
U-1B	2	2239875-01	Square with wheels, Black painted steel plate
T-5	2	1830	35" square table, Antique Iron (22), Walnut (404)

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

18. Essen outdoor bench or equal, epoxy primer, Ferrus treatment & powder coat finish, cast iron frame, solid steel seat/back; Manufacturer to be EMU Americas or equal; Warranty: 3-year on EMU seating, (TAG B-1 on attachment)

Tag #	Quantity	Part Number	Part Description & Modifications (if applicable)
B-1	2	U397M	32"H x 65.5"W x 24.5"D, textured steel grey

NAME BRAND: _____

MODEL NUMBER: _____

UNIT PRICE: _____ TOTAL PRICE: _____

WARRANTY TERMS: _____

* * * * *

BID SUBMITTED BY:

Name of Company

Date of Bid

Mailing Address

Discount (If Applicable)

City, State, Zip Code


Length of Time Prices are Valid

Telephone Number

Typed Name of Representative

Email Address of Representative

Signature of Representative



Scale 3/16" = 1'

1 FURNITURE PLAN

ST. TAMMANY PARISH SCHOOL BOARD
 ABITA MIDDLE SCHOOL LIBRARY
 72079 Maple St
 Abita Springs, LA 70420

ISSUE / REVISIONS		
NO.	DESCRIPTION	DATE
1.	PRELIMINARY PLAN FOR DISCUSSION	06.21.22
2.	FINAL QUOTE & FURNITURE PLAN REVIEW	08.08.22

FURNITURE PLANS
 Project Number: 22-158
 Date: 08.08.22
 Drawn by: PW Checked by: ME

FFE-1

Scale as indicated