



**ARBORBROOK  
CHRISTIAN  
ACADEMY**

4823 Waxhaw Indian Trail Rd  
Matthews, NC 28104

**CLASSROOM  
BUILDING**

CONSTRUCTION SERVICES SINCE 1953

**Myers & Chapman**

Your Building Partner™

**DD PACKAGE**  
04-22-2022

REV.	DATE	DESCRIPTION

DATE:

APRIL 22, 2022

PROJECT NO.:

18110.01

TITLE:

**BUILDING  
ELEVATIONS**

DRAWING NO.

**A-2.1**

1 2 3 4 5 6 7

- 2.25" WIDE SHINGLE MOULD
- .75" THICK X 7.25" WIDE FIBER CEMENT SMOOTH TRIM
- .75" THICK X 4.5" WIDE FIBER CEMENT SMOOTH TRIM
- FIBER CEMENT SHINGLE SIDING W/ 7" EXPOSURE
- .75" THICK X 9.25" WIDE FIBER CEMENT SMOOTH TRIM
- .75" THICK X 3.5" WIDE FIBER CEMENT SMOOTH TRIM
- PREFINISHED ALUMINUM GUTTER W/ GUARD AND DOWNSPOUTS- TYP
- CEDAR TEXTURE VERTICAL SIDING FIBER CEMENT PANELS W/ 2" WIDE SMOOTH VERTICALS- TYP ABOVE STONE BASE
- PREMANUFACTURED STONE WALL CAP

FIRST FLOOR  
ELEV.: 11'-0"

BASEMENT  
ELEV.: 0'-0"

**2 SIDE ELEVATION**  
SCALE: 1/4" = 1'-0"

A B C C.1 D E E.2 F G H

- 2.25" WIDE SHINGLE MOULD
- .75" THICK X 7.25" WIDE FIBER CEMENT SMOOTH TRIM

- CONTINUOUS RIDGE VENT
- ASPHALT SHINGLE ROOF
- 2.25" WIDE SHINGLE MOULD
- .75" THICK X 7.25" WIDE FIBER CEMENT SMOOTH TRIM
- .75" THICK X 5.5" WIDE FIBER CEMENT SMOOTH TRIM
- .75" THICK X 3.5" WIDE FIBER CEMENT SMOOTH TRIM
- PREFINISHED ALUMINUM GUTTER W/ GUARD AND DOWNSPOUTS- TYP
- 9.5" X 9.5" COLUMN
- .75" THICK X 3.5" WIDE FIBER CEMENT SMOOTH TRIM
- PREMANUFACTURED STONE WALL CAP
- PREMANUFACTURED STONE VENEER
- PAINTED METAL HAND RAIL

FIRST FLOOR  
ELEV.: 11'-0"

BASEMENT  
ELEV.: 0'-0"

- CEDAR TEXTURE VERTICAL SIDING FIBER CEMENT PANELS W/ 2" WIDE SMOOTH VERTICALS- TYP ABOVE STONE BASE

**1 FRONT ELEVATION**  
SCALE: 1/4" = 1'-0"