

3-YEAR ASBESTOS RE-INSPECTION REPORT

.....

MEMORIAL STADIUM SCRANTON, PA

prepared for:

**SCRANTON SCHOOL DISTRICT
425 North Washington Avenue
Scranton, Pa. 18505**

CONSULTANTS:

Guzek Associates, Inc.
401 Davis Street
Clarks Summit, PA 18411

PROJECT: #SSD.19_751

Updated:

July 2019

TABLE OF CONTENTS

SECTION 1	EXECUTIVE SUMMARY
SECTION 2	INTRODUCTION
SECTION 3	BUILDING DISCRIPTION
SECTION 4	METHODS
SECTION 5	RE-INSPECTION FINDINGS
SECTION 6	RE-INSPECTION RESULTS
SECTION 7	RECOMMENDATIONS
SECTION 8	ASBESTOS INSPECTOR ACCREDIDATION
APPENDIX A	HOMOGENEOUS SAMPLING CHART, RESPONSE ACTION BASED ON HAZARD RANK, & ASBESTOS CONTAINING BUILDING MATERIAL (ACBM) LOCATION DRAWINGS
APPENDIX B	PLM SAMPLE ANALYSIS RESULTS & CHAIN-OF-CUSDOTY

ASBESTOS INSPECTION

For the property known as:

MEMORIAL STADIUM

SECTION 1 EXECUTIVE SUMMARY

An Asbestos Materials Inspection Survey was conducted on July 12, 2019 at the above-listed location. The purpose of the survey was to visually locate, identify, and quantify asbestos-containing building materials. The survey was conducted by Certified Asbestos Inspector Chris Notari (DLI Asbestos Inspector Certification #027028)

All accessible rooms and areas of the complex were entered for inspection of suspected asbestos materials. Suspected asbestos materials not previously sampled (if applicable) were sampled and sent to a laboratory for analyses to confirm or negate the suspicion of asbestos content. Other suspect materials were assumed to contain asbestos.

The results are summarized as follows:

A. Asbestos-containing Materials

1. All confirmed or assumed (roofing materials, chalkboard mastic, etc.) asbestos-containing materials are listed in Appendix A. Materials that were tested and found not to contain asbestos are also listed in Section 6.
2. Recommendations

Recommendations are given in relation to renovation activities for the school building in Section 7.

SECTION 2 INTRODUCTION

An Asbestos Materials Inspection of the Memorial Stadium was performed at the request Scranton School District, Scranton, PA. The purpose of the inspection was to determine the types, quantities, and conditions of confirmed or assumed asbestos-containing materials, if not previously tested.

Once suspected asbestos materials were identified, they were sampled to verify or negate the suspicion of asbestos content (roofs were not tested and were assumed to contain asbestos). All materials sampled were analyzed via EPA Method 600/R-93/116 utilizing Polarized Light Microscopy by *EMSL Analytical, Inc., a NVLAP- accredited laboratory.*

The friability of these materials was also determined. Friable materials, such as cementitious pipe insulation, are those that can be crumbled, pulverized, or reduced to powder by hand or finger pressure. Non-friable materials, such as floor tiles in good condition, are those that cannot be crumbled, pulverized, or reduced to powder by hand or finger pressure. It is possible for normally non-friable materials to be considered as friable if they are in poor or damaged condition or will be rendered friable by construction or other activities, such as drilling, sanding, crushing by heavy equipment, etc.

The Initial Asbestos Hazard Emergency Response Act (AHERA) Building Inspection Report and Management Plan which was prepared and filed in accordance with the United States Environmental Protection Agency's (EPA) Regulation 40 CFR Part 763, Subpart E – Asbestos-Containing Materials in Schools is on file and available for review at the Scranton School District Administration Offices and the Memorial Stadium Administration Office.

SECTION 3 BUILDING DISCRIPTION

Memorial Stadium, located at 825 Providence Road, Scranton, PA is a steel and masonry constructed complex built in 1950. The complex consists of an east and west grandstand areas, press boxes, and various rooms, and contains approximately 21,430 square feet (original complex) plus an additional 6,949 square feet (2004 Renovation Project) for a total of approximately 28,379 square feet.

SECTION 4 METHODS

Prior to re-inspection the following documents were reviewed by Guzek Associates, Inc.

1. Original inspection report
2. 2016 3-Year Re-inspection Report
3. AHERA 6-month Periodic Surveillance Inspection Reports

Upon completion of reviewing the above referenced documentation, Guzek Associates, Inc. conducted a room-by-room and area-by-area inspection of the building to verify the locations of Asbestos Containing Materials listed in the above documents and to determined the conditions (Good, Damaged, or Significantly Damaged) of these materials. In addition, suspect materials not listed in the above documents were identified and either assumed to contain asbestos or collected and analyzed to determined asbestos content.

The asbestos inspection survey was conducted by inspectors qualified by experience, education, and training in the recognition of suspected asbestos-containing materials. Sampling was limited to only areas that were easily accessible (above ceiling tiles, operable hatches, and open areas.) No walls, chases or ceilings, etc. were penetrated during this inspection.

For those materials analyzed for asbestos content during this inspection, representative samples of "suspected" asbestos-containing materials were collected utilizing approved federal and state methods.

All Samples collected were analyzed by EMSL Analytical, Inc., Cinnaminson, NJ. Using EPA 600/R-93/116 Method using Polarized Light Microscopy

SECTION 5 REINSPECTION FINDINGS

The attached inspection forms in Appendix A indicate both the locations and assessed conditions of confirmed or assumed asbestos containing materials as identified in the complex by the 2019 Re-inspection conducted by Guzek Associates, Inc.

The Scranton School District intends to continue implementation of the Operations & Maintenance Program recommendations as contained in the original AHERA Management Plan and to maintain its stringent occupational and environmental protection standards for the on-going control of the identified ACBM's within the building.

SECTION 6 INSPECTION RESULTS

A. Asbestos-containing Materials

Appendix A contains a list and drawings of all confirmed and assumed asbestos-containing materials identified in the 3-year re-inspection report for Memorial Stadium conducted by Guzek Associates, Inc.. This table also includes locations and condition assessments (Good, Damaged, or Significantly Damaged).

Finally all Chain of Custody and Analytical Laboratory Reports from the 2016 3-Year Re-inspection Report are including in Appendix B.

Note: In addition to those materials listed in the Homogeneous Sampling Chart in Appendix A, the following suspected asbestos-containing materials may be present:

1. Pipe and/or pipe fitting insulation (friable materials) in wall cavities in the vicinities of bathroom and shower fixtures, sinks, and drinking water fountains – no access at time of inspection.
2. Glue pucks behind chalkboards, wallboards, etc. (Category 1 non-friable material) – no access at time of inspection.
3. Fire Doors
4. Roofing Materials (including Flashing and Tar)
5. Electrical wiring insulation maybe present

Materials That Were Tested and Found Not to Contain Asbestos

- Mastic on fiberglass ends
- Joint compound
- Sheetrock
- Tar paper behind wood walls (West stands maintenance area)
- Boiler Room in East Stands – Water Storage cementitious tank coating
- Machine Room, 2nd Floor weight room – cementitious tank coating
- Door Caulking
- Duct Sealant

SECTION 7 RECOMMENDATIONS

- A. Any Materials listed as Presumed Asbestos Containing Materials (PACM) in Appendix A shall either be assumed to contain asbestos or should be analyzed to determine asbestos content at time of disturbance
- B. All Asbestos Containing Materials in the building that are to remain in place shall be treated according to Operation and Maintenance (O&M) procedures for each specific material and as listed in the O&M plan for the Memorial Stadium.
- C. All Presumed or Confirmed Asbestos Containing Materials that will be potentially damaged by any activity (renovation, demolition, maintenance, etc.) shall be:
 - 1. Removed by a Pennsylvania Department of Labor and Industry (PaDLI) Certified asbestos abatement contractor prior to renovation. Final clearance air monitoring should be performed by an independent third party contracted to the school district.

Or

- 2. The Activity that will potentially disturb Asbestos Containing Materials shall be designed to avoid said disturbance.

SECTION 8 ASBESTOS INSPECTOR ACCREDITATION

Certified PA Asbestos Inspectors, Chris Notari (DLI Asbestos Inspector Certification #027028) and Brent Tripp (DLI Asbestos Inspector Certification #053975). Copies of their certificates are included in this report on the following pages.

Certificate of Completion

awarded to

Chris Notari

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.

7921 River Road, Pennsauken, NJ 08110

(856) 665-3449

7/11/19

Course Date

N/A

Exam Date

7/11/20


Expiration Date

Not Provided

Social Security Number

ACC-0719-6-005

Certificate Number



**Mark K. Schlager
Training Director**

Certificate of Completion

awarded to

Brent M. Tripp

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.

7921 River Road, Pennsauken, NJ 08110

(856) 665-3449

7/11/19

Course Date

N/A

Exam Date

7/11/20

Expiration Date

Not Provided

Social Security Number

ACC-0719-6-006

Certificate Number



Mark K. Schlager
Training Director

APPENDIX A

REINSPECTION FINDINGS:

HOMOGENEOUS SAMPLING CHART

RESPONSE ACTION BASED ON HAZARD RANK

ASBESTOS CONTAINING BUILDING MATERIAL (ACBM) LOCATION DRAWINGS

HOMOGENEOUS SAMPLING CHART

Scranton School District

Building: Memorial Stadium

Dates of Original AHERA Inspection: July, 1988

Page 1 of 1

HOMOGENEOUS SAMPLING MATERIAL		MATERIAL CATEGORY	ASBESTOS CONTENT	FRIABILITY	AHERA ASSESSMENT	AHERA HAZARD	AHERA REMOVAL PRIORITY	NOTES
MATERIAL LOCATION	MATERIAL DESCRIPTION							
West Stands, Press Boxes #1, #2, #3, and #4	Roof Lining Material (Galbesots)	TSI SURFACE	Assumed or Analyzed	F NF-1 NF-2	G D SD	2	6	- This material exists on the metal panel roof surface
	(Approx. 1,425 sq ft)	Misc.	Analyzed					
West Stands, Press Boxes #1, #2, #3, and #4	Interior/Exterior Panel caulk (undetermined amount)	TSI SURFACE	Assumed or Analyzed	F NF-1 NF-2	G D SD	2	6	- Damaged and loose caulk to be removed
		Misc.	Analyzed					
East Stands, Boiler Room	Fittings (Approx. 10 - 15 Fittings)	TSI SURFACE	Assumed or Analyzed	F NF-1 NF-2	G D SD	4	4	
		Misc.	Analyzed					
East Stands, Boiler Room	Pipe Insulation (Approx. 50 - 60 LF)	TSI SURFACE	Assumed or Analyzed	F NF-1 NF-2	G D SD	2	6	
		Misc.	Analyzed					
Throughout Facility	Ductwork Flex Connections	TSI SURFACE	Assumed or Analyzed	F NF-1 NF-2	G D SD	2	6	
		Misc.	Analyzed					
	Mastic Behind Chalkboards, panels, and wallboards, etc.	TSI SURFACE	Assumed or Analyzed	F NF-1 NF-2	G D SD	1	7	
		Misc.	Analyzed					
	Gasketing Material (Indeterminate)	TSI SURFACE	Assumed or Analyzed	F NF-1 NF-2	G D SD	1	7	
		Misc.	Analyzed					

Information abstracted by: Christopher Notari in July, 2019

Friability: F = Friable, NF-1 = Non-Friable, NF-2 = Non-Friable


AHERA Assessment / Hazard Rank / Removal Priority = See Attached Document, "RESPONSE ACTIONS BASED ON HAZARD RANKING"


Building Inspector's Certification No.: 027028-PA


Assessment: G = Good, D = Damaged, SD = Significantly Damaged

RESPONSE ACTIONS BASED ON HAZARD RANK

HAZARD RANK	REMOVAL PRIORITY	AHERA CATEGORIES	RESPONSE ACTIONS REQUIRED BY AHERA
7	1	Significantly Damaged	Evacuate or restrict the area if needed. Remove the ACBM (or enclose or encapsulate it if sufficient to contain fibers). Repair of T.S.I. allowed if feasible and safe. O&M required for all ACBM.
6	2	Damaged with Potential for Significant Damaged	Evacuate or restrict the area if needed. Remove, enclose, encapsulate, or repair to correct damage. Take steps to reduce potential for disturbance. O&M required for all ACBM.
5	3	Damaged with Potential for Damage	Remove, enclose, encapsulate, or repair to correct damage. O&M required for all ACBM.
4	4	Damaged with Low Potential for Damage	Remove, enclose, encapsulate, or repair to correct damage. O&M required for all ACBM.
3	5	Good with Potential for Significant Damage	Evacuate or restrict the area if needed. Take steps to reduce potential for disturbance. O&M required for all ACBM.
2	6	Good with Potential For Damage	O&M required for all ACBM. Take steps to reduce potential for damage.
1	7	Good with Low Potential for Disturbance	O&M required for all ACBM







APPENDIX B

TEST RESULTS FOR SUSPECTED ASBESTOS-CONTAINING MATERIALS:

2016 LABORATORY REPORT

2016 CHAIN OF CUSTODY

**EMSL Analytical, Inc.**

200 Route 130 North Cinnaminson, NJ 08077

Tel/Fax: (800) 220-3675 / (856) 786-5974

http://www.EMSL.com / cinnaslab@EMSL.com

EMSL Order: 041624245**Customer ID:** CLAG50**Customer PO:** 082416**Project ID:**

Attention: Joseph Guzek
 Guzek Associates, Inc.
 401 Davis Street
 Clarks Summit, PA 18411

Phone: (570) 586-9700
Fax: (570) 586-6728
Received Date: 08/30/2016 10:15 AM
Analysis Date: 09/06/2016 - 09/07/2016
Collected Date: 08/23/2016

Project: Stadium

**Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized
 Light Microscopy**

Sample	Description	Appearance	Non-Asbestos		Asbestos % Type
			% Fibrous	% Non-Fibrous	
01 041624245-0001	East Stands - Mastic over FG Ends	White/Yellow Non-Fibrous Homogeneous	12% Min. Wool	88% Non-fibrous (Other)	None Detected
02 041624245-0002	East Stands - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
03 041624245-0003	East Stands - Sheetrock	White Fibrous Homogeneous	15% Cellulose 5% Glass	80% Non-fibrous (Other)	None Detected
04 041624245-0004	West Stands - Mstic of FG Ends	Gray/Tan/Yellow Fibrous Homogeneous	50% Min. Wool	50% Non-fibrous (Other)	None Detected
05 041624245-0005	West Stands - Mastic over FG Ends	White/Yellow Fibrous Homogeneous	15% Min. Wool	85% Non-fibrous (Other)	None Detected
06 041624245-0006	West Stands- Garage #2 - Tar Paper on Wall Under Wood	Brown/Black Fibrous Homogeneous	80% Cellulose	20% Non-fibrous (Other)	None Detected
07 041624245-0007	West Stands- Press Box #3 - Corrigated Roof Interior Coating	Brown/White/Black Fibrous Homogeneous		93% Non-fibrous (Other)	7% Chrysotile
08 041624245-0008	West Stands- Press Box #3 - Exterior Panel Caulk	Gray/White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
09 041624245-0009	West Stands- Press Box #3 - Corrigated Roof Interior Coating	Black Non-Fibrous Homogeneous		90% Non-fibrous (Other)	10% Chrysotile
10 041624245-0010	East Stands- Boiler Room Storage Tank - TSI	White Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected
11 041624245-0011	East Stands- Boiler Room Storage Tank - TSI	Gray Non-Fibrous Homogeneous	4% Min. Wool	96% Non-fibrous (Other)	None Detected
12 041624245-0012	East Stands- Boiler Room Storage Tank - TSI	Gray Fibrous Homogeneous	30% Min. Wool	70% Non-fibrous (Other)	None Detected
13 041624245-0013	East Stands- Exterior Boiler Room - Door Caulk	Gray/White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
14 041624245-0014	East Stands- Electrical Building - Door Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
15 041624245-0015	East Stands- Tool Room - Door Caulk (under bleachers)	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
16 041624245-0016	East Stands- Concession Stand #1 - Mastic over FG Ends	White/Yellow Fibrous Homogeneous	10% Min. Wool	90% Non-fibrous (Other)	None Detected

Initial report from: 09/07/2016 08:50:16

**EMSL Analytical, Inc.**

200 Route 130 North Cinnaminson, NJ 08077

Tel/Fax: (800) 220-3675 / (856) 786-5974

http://www.EMSL.com / cinnasblab@EMSL.com

EMSL Order: 041624245**Customer ID:** CLAG50**Customer PO:** 082416**Project ID:****Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy**

Sample	Description	Appearance	Non-Asbestos		Asbestos % Type
			% Fibrous	% Non-Fibrous	
17 041624245-0017	East Stands- Ticket Booth - Sheetrock	Brown/White Fibrous Homogeneous	12% Cellulose 3% Glass	85% Non-fibrous (Other)	None Detected
18 041624245-0018	East Stands- Ticket Booth - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
19 041624245-0019	East Stands- Girls Room - Duct Sealant	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
20 041624245-0020	East Stands- Men's Locker Room - Mastic over FG Ends	White/Yellow Non-Fibrous Homogeneous	15% Min. Wool	85% Non-fibrous (Other)	None Detected
21 041624245-0021	East Stands- Concession #2 - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
22 041624245-0022	East Stands- Concession #2 - Sheetrock	Brown/White Fibrous Homogeneous	4% Glass	96% Non-fibrous (Other)	None Detected
23 041624245-0023	West Stands- Men's Locker Room - Interior Door Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
24 041624245-0024	West Stands- 2nd Floor Weight/ Mech Room - Fabric over Tank	White Non-Fibrous Homogeneous	98% Synthetic	2% Non-fibrous (Other)	None Detected
25 041624245-0025	West Stands- 2nd Floor Weight/ Mech Room - Mastic over FG	Tan/Yellow Fibrous Homogeneous	50% Min. Wool	50% Non-fibrous (Other)	None Detected
26 041624245-0026	West Stands- Press Box #1 - Caulk b/w Metal Panels	Gray/Silver Fibrous Homogeneous		85% Non-fibrous (Other)	15% Chrysotile
27 041624245-0027	West Stands- Exterior Storage "C" - Door Caulk	Gray/White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
28 041624245-0028	Ticket Booth #2 - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
29 041624245-0029	Ticket Booth #2 - Sheetrock	Brown/White Fibrous Homogeneous	15% Cellulose 4% Glass	81% Non-fibrous (Other)	None Detected
30 041624245-0030	Ticket Booth #4 - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
31 041624245-0031	Ticket Booth #4 - Sheetrock	Gray Fibrous Homogeneous	15% Cellulose 5% Glass	80% Non-fibrous (Other)	None Detected

Initial report from: 09/07/2016 08:50:16



EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077

Tel/Fax: (800) 220-3675 / (856) 786-5974

<http://www.EMSL.com> / cinnasblab@EMSL.com

EMSL Order: 041624245

Customer ID: CLAG50

Customer PO: 082416

Project ID:

Analyst(s)

Christina Shriver (12)

Seri Smith (6)

Will DiBella (13)

Benjamin Ellis, Laboratory Manager
or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%

Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367

Initial report from: 09/07/2016 08:50:16



EMSL ANALYTICAL, INC.
LABORATORY, PROJECT, TRAINING

Asbestos Chain of Custody

EMSL Order Number (Lab Use Only):

041624245

200 Route 130 North

Cinnaminson, NJ 08077

PHONE: 1-800-220-3675

FAX: (856) 786 5974

Company Name: Guzek Associates, Inc.		EMSL Customer ID:	
Street: 401 Davis Street		City: Clarks Summit	State/Province: PA
Zip/Postal Code: 18411	Country: US	Telephone #: 570-586-9700	Fax #: 570-586-6728
Report To (Name): Joseph Guzek		Please Provide Results: ☐ Fax ☒ Email	
Email Address: guzekassoc@aol.com		Purchase Order: 082416	
Project Name/Number: Stadium		EMSL Project ID (Internal Use Only):	
U.S. State Samples Taken: PA		CT Samples: ☐ Commercial/Taxable ☐ Residential/Tax Exempt	
EMSL-Bill to: ☐ Same ☒ Different - If Bill to is Different note instructions in Comments**			
Third Party Billing requires written authorization from third party			
Turnaround Time (TAT) Options* - Please Check			
☐ 3 Hour	☐ 6 Hour	☐ 24 Hour	☐ 48 Hour ☐ 72 Hour ☐ 96 Hour ☒ 1 Week ☐ 2 Week
*For TEM Air 3 hr through 6 hr, please call ahead to schedule. There is a premium charge for 3 Hour TEM AHERA or EPA Level II TAT. You will be asked to sign an authorization form for this service. Analysis completed in accordance with EMSL's Terms and Conditions located in the Analytical Price Guide.			
PCM - Air ☐ Check if samples are from NY ☐ NIOSH 7400 ☐ w/ OSHA 8hr. TWA		TEM - Air ☐ 4-4.5hr TAT (AHERA only) ☐ AHERA 40 CFR, Part 763 ☐ NIOSH 7402 ☐ EPA Level II ☐ ISO 10312	
PLM - Bulk (reporting limit) ☒ PLM EPA 600/R-93/116 (<1%) ☐ PLM EPA NOB (<1%) Point Count ☐ 400 (<0.25%) ☐ 1000 (<0.1%) Point Count w/Gravimetric ☐ 400 (<0.25%) ☐ 1000 (<0.1%) ☐ NYS 198.1 (friable in NY) ☐ NYS 198.6 NOB (non-friable-NY) ☐ NYS 198.8 SOF-V ☐ NIOSH 9002 (<1%)		TEM - Bulk ☐ TEM EPA NOB ☐ NYS NOB 198.4 (non-friable-NY) ☐ Chatfield SOP ☐ TEM Mass Analysis-EPA 600 sec. 2.5 TEM - Water: EPA 100.2 Fibers >10µm ☐ Waste ☐ Drinking All Fiber Sizes ☐ Waste ☐ Drinking	
TEM - Dust ☐ Microvac - ASTM D 5755 ☐ Wipe - ASTM D6480 ☐ Carpet Sonication (EPA 600/J-93/16)		Soil/Rock/Vermiculite ☐ PLM EPA 600/R-93/116 with milling prep (<1%) ☐ PLM EPA 600/R-93/116 with milling prep (<0.25%) ☐ TEM EPA 600/R-93/116 with milling prep (<0.1%) ☐ TEM Qualitative via Filtration Prep ☐ TEM Qualitative via Drop Mount Prep ☐ Cincinnati Method EPA 600/R-04/004 - PLM/TEM (BC only)	
☐ Check For Positive Stop - Clearly Identify Homogenous Group		Filter Pore Size (Air Samples): ☐ 0.8µm ☐ 0.45µm	
Samplers Name: Chris Notari		Samplers Signature:	
Sample #	Sample Description	Volume/Area (Air) HA # (Bulk)	Date/Time Sampled
01	East Stands (ES) - Mastic over FG ends	Bulk	08/23/16
02	ES - joint compound		
03	ES - sheetrock		
04	West Stands (WS) - Mastic of FG ends		
05	WS - Mastic over FG ends		
Client Sample # (s): 01 - 31		Total # of Samples: 31	
Relinquished (Client): <i>Chris Notari</i>		Date: 8/24/16 Time:	
Received (Lab): <i>Bob EMSL</i>		Date: 8/30/16 Time: 1015	
Comments/Special Instructions: Bill To: Guzek Associates, Inc., 401 Davis Street, Clarks Summit, PA, 18411, US Attention: Chris Notari Phone: 570-586-9700 Email: guzekassoc@aol.com Purchase Order:			



EMSL ANALYTICAL, INC.
ENVIRONMENTAL
LABORATORY • PRODUCTS • TRAINING

Asbestos Chain of Custody

EMSL Order Number (Lab Use Only):

041624245

200 Route 130 North

Cinnaminson, NJ 08077

PHONE: 1-800-220-3675

FAX: (856) 786-5974

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	Sample Description	Volume/Area (Air) HA # (Bulk)	Date/Time Sampled
06	WS - Garage #2 Tar paper on wall under wood	Bulk	08/23/16
07	WS - Press Box #3 Corrugated roof Interior coating		
08	WS - Press Box #3 Exterior Panel caulk		
09	WS - Press Box #3 Corrugated roof interior coating		
10	ES - Boiler Rm Storage Tank TSI		
11	ES - Boiler Rm Storage Tank TSI		
12	ES - Boiler Rm Storage Tank TSI		
13	ES - Exterior Boiler Rm door caulk		
14	ES - Electrical Building Door caulk		
15	ES - Tool Rm Door caulk (under bleachers)		
16	ES - Concession Stand #1 mastic over FG ends		08/24/16
17	ES - Ticket Booth Sheetrock		
18	ES - Ticket Booth joint compound		
19	ES - Gilrs Rm Duct sealant		
20	ES Men's Locker Rm mastic over FG ends		
21	ES - Concession #2 - joint compound		
22	ES - Concession #2 - sheetrock		
23	WS - Men's Locker Rm - Interior Door caulk		
24	WS - 2nd Fl. Weight/Mech Rm Fabric over Tank		
25	WS - 2nd Fl. Weight/Mech Rm mastic over FG		
26	WS - Press Box #1 - Caulk between metal panels		
27	WS - Exterior Door caulk Storage "C"		
28	Ticket Booth #2 joint compound		

*Comments/Special Instructions:

[illegible]

RECEIVED
ENSL
CINNAMINSON, NJ
16 AUG 30 AM 11:10