



**ROCKFORD BOARD OF EDUCATION
INVITATION FOR BID ON SUPPLIES, MATERIALS, EQUIPMENT OR SERVICES
FOR SCHOOL DISTRICT NO. 205
ROCKFORD, ILLINOIS**

IFB No. IFB No. 23-16 HVAC Upgrades at Whitehead, Welsh, Montessori, Brookview, Jefferson, Rolling Green and Summerdale Schools

DATE: January 6, 2023

RE: ADDENDUM NO. 3

To All Bidders:

Included are modifications, clarifications and/or corrections for the Project Manual and are hereby made a part of the contract documents. Please attach this addendum to the Project Manual(s) in your possession. Please note the receipt of this addendum on the bid form. Bidders shall review changes to all portions of this work as changes to one portion may affect the work of another.

If you plan to hand deliver your IFB submission on the due date, please note you must check in on the 1st floor prior to coming to the bid opening. Please allow time for this as late submission will not be accepted.

Refer all questions relative to the business aspect, Instructions to Bidders, Special Conditions, and questions concerning the technical aspect of the documents to the Director of Purchasing by email at purchasingdeptstaff@rps205.com.

ROCKFORD BOARD OF EDUCATION

By: Dane Youngblood
Director of Purchasing



ADDENDUM #3

DATE: January 6, 2023

PROJECT: IFB #23-16
RPS 205 HVAC Improvements:
2303 Whitehead Elementary School
2304 Welsh Elementary School
2305 Maria Montessori at Marsh
2306 Brookview Elementary School
2403 Jefferson High School
2404 Rolling Green Elementary School
2406 Summerdale Early Childhood Center
IMEG #21002885.07, .08, .09, .10, .11, .12, .14

BID DUE DATE: January 12, 2023

ARCHITECT: IMEG Corp.
623 26th Avenue
Rock Island, IL 61201
Phone: 309-788-0673
Fax: 309-786-5967

TO: All Contract Document Holders of Record.

This Addendum forms a part of the bidding and construction documents. This Addendum supersedes and supplements all portions of the original bidding and construction documents dated November 3, 2022 with which it conflicts. Please attach this Addendum to the Project Manual(s) in your possession.

**ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED ON THE BID FORM.
FAILURE TO DO SO MAY SUBJECT BIDDER TO DISQUALIFICATION.**

A. PROCUREMENT AND CONTRACTING REQUIREMENTS

No changes this Addendum.

B. SPECIFICATIONS

No changes this Addendum.

C. DRAWINGS

Summerdale Early Childhood Center

1. Drawing E101B – FIRST FLOOR DEMOLITION – ELECTRICAL – AREA B
 - a. Disconnect and remove existing 200A-3P rated circuit breaker enclosure located on the west wall being removed. Remove associated feeder run (wiring and conduit) close to the ceiling space (field verify the exact location) and prepare it to reconnect to the new power distribution ('MDP-NEW' distribution panel).

2. Drawing E201B – FIRST FLOOR – ELECTRICAL – AREA B
 - a. Provide new J-box to splice the existing remaining feeder wiring section, saved during the demolition work as noted above, with the new feeder wiring section to reconnect it from the new distribution. Field verify the J-box final location in coordination with the existing and new power distribution installation in the room. J-box size shall be per NEC.
3. Drawing E700 – ELECTRICAL PANEL SCHEDULES – AREA B
 - a. Provide one (1) additional 200A-3P rated breaker. Extend existing feeder circuit, saved during the demolition work as noted above, to reconnect to this breaker. Provide new feeder wiring in conduit (4#4/0 & 1#4 GND. in 2-1/2" C) as required. Label the breaker for the existing load that it serves.

END OF ADDENDUM #3

BWP/dks

\\files\Active\Projects\2021\21002885.00\BidPhase\AddendaSupportDocs\Phase 2\20230106 Adden3\20230106 Adden3.docx