

**Specifications/Clarifications:**

The project due date will be extended from **February 8th, 2023, to February 21st, 2023, no later than 12:00 A.M. NO Proposals will be accepted after 12:00 A.M. (PST)**

TechNet

Question #1: Are building plans available indicating drop locations detailed in the RFP? If not, please indicate on each site plan the location of the (31) Classrooms, Library, Office Area, Janitors Office, and Kitchen.

Note: Library for El Morro is shown

**[https://drive.google.com/file/d/1nkJhF76P8iQGrkb\\_bDog8-ym4DWGfQ2R/view?usp=sharing](https://drive.google.com/file/d/1nkJhF76P8iQGrkb_bDog8-ym4DWGfQ2R/view?usp=sharing)**

Question #2: How many drop locations will need raceway installed at each site? If unknown, please provide a baseline quantity of drop locations needing raceway that can be used for bid leveling purposes.

***Potentially 20% of the drops could require raceway.***

Question #3: Will raceway be required for any horizontal pathways? If so, please provide a baseline length and size of horizontal pathways needing raceway for bid leveling purposes.

***No horizontal raceway.***

Question #4: Will any conduit besides fire-stopping sleeves be required on this project? If so, please provide size and length required for bid leveling purposes.

**No.**

Question #5: What is the calendar schedule for this project?

***Work may begin after July 1, 2023. Details are to be determined at a later date.***

Question #6: Will demo of existing cables required in the RFP be performed before or after installation of new cables is complete?

***Before, in order to free up space in pathways.***

Question #7: Is there a specific quantity of cables & drop locations to be demoed as part of this project? If not, please provide baseline quantities for bid leveling purposes.

***1.5-inch diameter raceway, 200 feet total length.***

Question #8: Is any mounting hardware required to be provided by the contractor for installation of the district provided APs?

**No, the existing mounting bracket may be re-used.**

Question #9: Are the STI FS-Series Ready Firestop Pathway Kits acceptable for use on this project? If not, please provide specific part numbers for firestop sleeve system required.

**Yes.**

Question #10: Are the locations of full-height walls requiring firestopping known? If not, please provide baseline quantity of wall locations where firestopping will be required.

**100.**

#### Team Extenda

- During the job walk it was mentioned that the district would like everything in the conduit. Can you please elaborate on that requirement, e.g. does the district want the home run conduit from Work Station Outlet to MDF/IDF room? Or did you mean that district does not want more than 5' of exposed cables in MDF/IDF room.

***Please refer to page 11 of the RFP. Step 'F' under Project Scope Summary lists further details.***

***Also relevant is the section on BARRIER MANAGEMENT on page 42.***

- Will district entertain the contingency in the bid price if the new conduit pathway is required? If contingency is entertained then where do you put in the bid form so that it is fair and comparable for all the bidders. Currently bid form shows one single price.

***The district will review and consider any contingency fees submitted with the proposal.***

#### Construct Connect

What is the estimated cost of this project?

**\$150,000**