

APPENDIX A
Summary of Work to be Performed

Town of Vernon Water Pollution Control Authority

Sewer Rehabilitation, Contract No. 2118

Cured In Place Pipe Lining and Cured In Place Lateral Lining Summary

Sewershed Area V5 - Cured In Place Pipe Lining						
Street Name	Upstream MH	Downstream MH	Pipe Material	Pipe Dia . (in)	Length (ft)	# Active Services
Chestnut Street	2419	367	VC	8	105	3
Chestnut Street	367	366	VC	8	262	5
Cottage Street	1958	1526	VC	8	157	1
Cottage Street	1526	1527	VC	8	193	3
East Main Street	1494	151	VC	15	206	0
East Main Street	151	887	VC	15	207	0
East Main Street*	887	1750	VC	15	254	1
East Main Street	1750	1749	VC	15	267	0
West Main Street	1749	894	VC	15	167	1
West Main Street	894	893	VC	15	181	0
West Main Street	893	892	VC	15	131	0
West Main Street	892	891	VC	15	177	4
West Main Street	891	2655	VC	15	275	9
West Main Street	2654	2653	VC	15	271	6
West Main Street	2653	1756	VC	15	276	2
Elm Street	601	1955	VC	8	304	3
Elm Street	1955	1954	VC	8	305	7
Elm Street	1954	1953	VC	8	202	5
Lawrence Street	1524	610	VC	8	247	6
Lawrence Street	610	611	VC	8	226	3
Lawrence Street	611	612	VC	8	231	7
Webster Street	612	1523	VC	8	200	3
Webster Street	1523	1521	VC	8	260	5
Mountain Street	1522	1521	VC	8	370	9
Mountain Street	1521	609	VC	8	171	3
Mountain Street	609	608	VC	8	115	1
Mountain Street	608	607	VC	8	318	8
Prospect Street	2157	1525	VC	8	308	6

* Spot liner required at 143' over existing dropped joint prior to lining

Town of Vernon Water Pollution Control Authority

Sewer Rehabilitation, Contract No. 2118

Cured In Place Pipe Lining and Cured In Place Lateral Lining Summary

Sewershed Area V5 - Cured In Place Pipe Lining

Street Name	Upstream MH	Downstream MH	Pipe Material	Pipe Dia . (in)	Length (ft)	# Active Services
Prospect Street	1525	120	VC	8	161	0
Prospect Street	3057	3056	VC	8	149	0
Prospect Street	3056	605	VC	8	88	1
Park Street	605	604	VC	8	141	1
Park Street	604	2160	VC	8	142	2
Park Street	2160	1518	VC	8	206	5
Park Street	1518	2831	VC	8	199	3
Park Street	2831	1517	VC	8	206	5
School Street	1212	1211	VC	8	202	3
School Street	1211	2832	VC	8	226	3
School Street	2832	1518	VC	8	299	5

Sewershed Area V5 - Cured In Place Lateral Lining

Street Name	Upstream MH	Downstream MH	Pipe Material	Lateral Dia. (in)	Repair Location from Upstream MH (ft)
Mountain Street	608	607	VC	6	149.5
Mountain Street	608	607	VC	6	155.5
Park Street	2831	1517	VC	6	136.7

Sewershed Area V10 - Cured In Place Pipe Lining

Street Name	Upstream MH	Downstream MH	Pipe Material	Pipe Dia . (in)	Length (ft)	# Active Services
Legion Drive	418	2518	VC	8	302	4
Legion Drive	1273	1274	VC	8	262	4
Mary Lane	750	1627	VC	8	245	3
Rails to Trails	2678	2677	RCP	12	197	0
Rails to Trails	2677	2676	RCP	12	108	0
Rails to Trails	2676	926	AC	12	203	0
Rails to Trails	926	925	AC	12	296	0
Rails to Trails	925	1262	AC	12	295	0
Regan Road	1632	1633	VC	10	279	3

Town of Vernon Water Pollution Control Authority

Sewer Rehabilitation, Contract No. 2118

Cured In Place Pipe Lining and Cured In Place Lateral Lining Summary

Sewershed Area V19 - Cured In Place Pipe Lining						
Street Name	Upstream MH	Downstream MH	Pipe Material	Pipe Dia . (in)	Length (ft)	# Active Services
Hansen Drive	2581	1743	VC	12	174	2
Scott Drive	1328	2138	VC	8	193	3
Vine Drive	2140	2139	VC	8	125	3
