

## Civic Auditorium Soft Goods & Repairs

### Scope of Work

The Lakewood City Schools is seeking bids for the repair and replacement of the curtains, riggings, and necessary equipment for the Lakewood Civic Auditorium.

#### 1. Front Setting

Remove and replace the following curtains with inherently flame retardant 25 oz. Charisma, with 50% fullness, in a stock color to be selected. The top hem shall contain nylon webbing with box pleats and grommets in the middle of each pleat on approximately 1'0" centers with "S hooks" for attachment. The bottom hem shall contain chain weighting within a separate pocket.

- Valance, one (1) required
  - According to Label (16'0 X 65')
  - According to Label 50 percent fullness
  - According to Label Color # 1072 Eggplant
  
- Main Curtain, one (1) required in four (4) equal sections
  - Main Curtain Per Panel (On a motorized track opening stage right and left)
  - According to the Label (27'0"x19'0")
  - According to the Label 50 percent fullness
  - According to the Label Color #1072 Eggplant

Quoted price for above: \_\_\_\_\_

#### 2. Masking Drapery

Remove and replace the following drapery of inherently flame retardant 14 oz. Prism, with 50 percent fullness, in a stock color black. The top hem shall contain nylon webbing with box pleats and grommets in the middle of each pleat on approximately 1'0" centers with "S hooks" for attachment. The bottom hem shall contain chain weighting within a separate pocket.

- Traveler, five (5) required in two (2) equal sections
  - Travelers (5 Sets of 2) and an additional Manual Track for the 5th traveler to be installed on the current cyc pipe see below for further description
  - According to the Label (21'9"x36'0")
  
- Borders, four (5) required
  - Borders (5 total) ( Hung on Pipe) 5th border to be installed on existing
  - According to the Label (9'9" x 74'0")

Quoted price for above: \_\_\_\_\_

### 3. Repairs to rigging system

#### Equipment

- Manual 5th track rope operated track, drapery (see above) and all connecting hardware for a complete installation to match existing stage rigging.
- Repair or replace any missing stopper roll pins on rope locks.
- Purchase lines trimmed to 6" tails above two half hitch rope terminations. The ends taped, trimmed and zip tied.
- Spreader plates added to each arbor and properly located and marked.
- Remove and replace existing lift lines.
- Replace trim chains with ¼" proof coil chain and two (2) 5/16" forged, rated, anchor shackles, and moused.
- Install brackets and pipe clamp connections to the Traveler Track
- Relocation of a first mule block and adjusted or replaced
- Installation of a sag bar
- Replace missing electrical bracket clamp.
- Modify the opening in the floor to keep the operating line from contacting the concrete.

Quoted price for above: \_\_\_\_\_

### 4. Fire Curtain System

- Update current Braille lift style fire curtain with motorized winch, pull stations and other items needed to complete the system.

Quoted price for above: \_\_\_\_\_

Total quoted price for all four projects above: \_\_\_\_\_