

# Spurwink Road Improvements Phase 1

RPF# 182023

Town of Scarborough Planning & Public Works  
Scarborough, Maine

St.Germain  
Westbrook, Maine

## Addendum #1 – May 19, 2023

TO: ALL HOLDERS OF RECORD OF CONTRACT DOCUMENTS

Acknowledge receipt of this addendum by inserting its number and date in the Bid Form (C-410 5.03). Failure to do so may subject the bidder to disqualification. This addendum forms a part of the Contract Documents. It modifies them as follows:

**BID DUE DATE:** There are no changes to the BID DUE DATE with this addendum.

Contract Documents:

1. There are no modifications to the Contract Documents with this addendum.

Technical Specifications:

1. There are no modifications to the Technical Specifications with this addendum.

Planset:

1. There are no modifications to the planset with this addendum.

General Comments and Questions:

1. Request to provide clarification on modular block retaining wall extents (stationing).
  - a. There are two sections of modular block retaining wall, shown on sheet C-203 of the planset.
    - i. One wall is approximately 120ft long, STA 17+10 – STA 18+30.
    - ii. The second wall is approximately 154ft in length, STA 18+60 -STA 20+14.
2. Request to provide clarification on modular block retaining wall specifications.
  - a. Wall shall be per detail shown on Sheet C-503 of the planset and Maine DOT Section 674 – Prefabricated Concrete Modular Gravity Wall as found online at:  
<https://www.maine.gov/mdot/contractors/publications/standardspec/>

3. Request to provide clarification on the Full Depth Reclamation depth and Portland Cement Mixture.
  - a. The total depth of the reclamation is 12 inches. The Design Mix will be field tested using 3%, 5%, and 7% cement content to determine the appropriate mixture for the site. For the purposes of the bid, Bidders should have their bids reflect the use of 5% cement content. If a different mix design is ultimately selected, compensation will be adjusted accordingly.

Attachments

None

