

# JAESC BOILER REPLACEMENT PROJECT RFP

---

scuhna@lodiused.net-mkarim@lodiused.net

## Scope of work:

REMOVE THE EXISTING CLEAVER BROOKS BOILER AND PROPERLY DISPOSE OF

SAVE ALL THE EXISTING ALLERTON MONITORING AND CONTROL DEVICES

INSTALL PROPANE TO NATURAL GAS CONVERSION KIT

PROVIDE NEW ELECTRICAL DISCONNECT AND FLEX CONNECTIONS

INSTALL 3 WAY MIXING VALVE-PROVIDED BY LUSD

INSULATE ANY NEW PIPING

INSTALL THE NEW RBI FB FUTERA II HYDRONIC HOT WATER BOILER-TO BE PROVIDED BY LUSD

PROVIDE ALL CRANE SERVICES

PROVIDE ALL MOUNTING AND MISC PARTS

REINSTALL ALL MONITORING AND CONTROL DEVICES AND CONFIRM WORKING ORDER OF THE MONITORING AND CONTROL DEVICES AND THE BOILER

Provide a 1-year labor warranty

Bid date will be