

1 PARTIAL FOUNDATION PLAN - WEST
S101 1/8" = 1'-0"

LEGEND

- FOOTING TYPE - SEE SCHEDULE
- TOP OF FOOTING ELEVATION
- COLUMN DESIGNATION
- PER MARK - SEE SCHEDULE
- STEP IN FOOTING - SEE B / S301

FOUNDATION PLAN NOTES

- SEE SHEET 6001 FOR GENERAL NOTES & DESIGN CRITERIA.
- ELEVATIONS GIVEN ARE SET FROM REFERENCE ELEVATION. REFERENCE ELEVATION (+5.0') IS SET AT FINISHED FLOOR ELEV. SEE CIVIL DRAWINGS FOR ADDITIONAL INFORMATION.
- REFER TO ARCHITECTURAL, MECHANICAL, ELECTRICAL, PLUMBING, AND DRAWINGS OF OTHER DISCIPLINES FOR LOCATIONS AND DIMENSIONS OF OPENINGS, DIMENSIONAL AND OTHER NON-STRUCTURAL ITEMS.
- TYPICAL SLAB ON GRADE IS 4" NORMAL WEIGHT CONCRETE REINFORCED W/ #4 - W/ 4W14 WWF OVER 10 ML VAPOR BARRIER, OVER APPROVED SUBGRADE OVER APPROVED SUBGRADE. EXTERIOR SLAB ON GRADE IS 4" NORMAL WEIGHT CONCRETE REINFORCED W/ #3 @ 12" O.C. (EA. WAY). LOCATE REINFORCING 1-1/2" CLR FROM TIE-UP.
- PROVIDE (2) #4 @ 6" IN TOP OF SLAB @ ALL RE-ENTRANT CORNERS NOT INTERSECTING SLAB JOINT.
- LOCATE SLAB JOINTS @ 30' OF O.C. MAX. SLAB JOINTS SHALL BE LOCATED TO MAINTAIN A MAXIMUM PANEL ASPECT RATIO OF 1.5 TO 1.6. SLAB JOINTS SHALL BE CONSTRUCTED PER DETAIL.
- FOOTING STEPS IF APPLICABLE ARE SHOWN IN APPROXIMATE LOCATIONS ON PLAN. SEE B / S301 FOR FOOTING STEP DETAIL. CONTRACTOR SHALL FIELD VERIFY LOCATIONS & COORDINATE WITH CIVIL PLANS TO MAINTAIN MINIMUM 1'-0" SOIL COVER OVER FOOTING.
- SEE F / S301 FOR COLUMN BASE PLATE AND ANCHORAGE DETAILS.
- THICKEN SLAB AT LOCATIONS OF STAIR POSTS AND STRINGERS. TYP. - SEE E / S301
- TYPICAL TOP OF FOOTING ELEVATION IS 2'-0" BELOW FINISHED FLOOR ELEVATION UNLESS NOTED OTHERWISE.
- STEEL STAIRS BY OTHERS. SEE NOTES ON 601. SUPPORT FOR STAIRS TO BE ANCHORED DIRECTLY TO TILT-UP CONCRETE WALLS VIA POST-INSTALLED ANCHORAGE UNLESS NOTED OTHERWISE.
- ALL COLUMNS TO HAVE BASE PLATE TYPE BPI UNL.O.
- REFER TO ARCH AND MEP DRAWINGS FOR FLOOR DRAIN LOCATIONS.

FOOTING SCHEDULE


TYPE	SIZE	THICKNESS	REINFORCING
S301	8'-0" x 8'-0"	1'-0"	(1) #6 EACH WAY

WALL FOOTING SCHEDULE

TYPE	SIZE	THICKNESS	REINFORCING
WF1	2'-0" WIDE	1'-4"	(2) #6 T&B CONT.
WF2	2'-0" WIDE	1'-4"	(3) #6 T&B CONT.
WF3	2'-0" WIDE	1'-4"	(3) #6 T&B CONT.
WF4	3'-0" WIDE	1'-4"	(4) #6 T&B CONT.

PIER SCHEDULE

MARK	SIZE	VERTICAL REINFORCING	TES
P1	18x18	(8) #5	(3) @ 12"



Mark A. Hudson
Professional Engineer
1505 C. Cleveland St., Greenville, SC 29607
P: 864.231.3005 F: 864.231.3177
PROJECT # 17-005



TCCA HIGH SCHOOL BUILDING
1400 SE COVE RD
STUART FLORIDA 34997

SHEET ISSUE: NO. DATE DESCRIPTION BY

PRINCIPAL IN CHARGE: RMT
PROJECT ARCHITECT: RMT
DRAWN BY: RMT

SHEET TITLE:
PARTIAL FOUNDATION PLAN - WEST

SHEET NO. PROJ. NO. 022004

S101