PROJECT MANUAL



MAYO HIGH SCHOOL TOILET RENOVATION

DARLINGTON, SOUTH CAROLINA

ARCHITECT'S PROJECT NO.: 624003 DCSD SOLICITATION NO.: FAC2223-03



ARCHITECT/ENGINEER

CHARLESTON, SOUTH CAROLINA

VOLUME 1 OF 1

MARCH 28, 2023

SPECIFICATIONS For The MAYO HIGH SCHOOL TOILET RENOVATION

DARLINGTON, SC



DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

TABLE OF CONTENTS

DIVISION 00 PROCUREMENT AND CONTRACTING REQUIREMENTS

Seals Page Invitation For Bid

Additional Bid & Contract Conditions – Required Insurance Limits

Vendor Application Form

Bidding Schedule

004316 Prebid Question Form

*AIA documents to be issued with first Addendum.

SPECIFICATIONS

DIVISION 1 – GENERAL REQUIREMENTS

011000	Summary
012000	Price and Payment Procedures
012500	Substitution Procedures
	Substitution Request Form (Prior to Receipt of Bids)
013000	Administrative Requirements
013216	Construction Progress Schedule
014000	Quality Requirements
014200	Definitions and Reference Standards
014520	Testing, Adjusting, and Balancing for HVAC
015000	Temporary Facilities and Controls
016000	Product Requirements
017000	Execution and Closeout Requirements
017419	Construction Waste Management and Disposal
017800	Closeout Submittals
017900	Demonstration and Training
018119	Indoor Air Quality Requirements

DIVISION 2 – EXISTING CONDITIONS

024100 Demolition

DIVISION 3 – CONCRETE

033000 Cast-In-Place Concrete

DIVISION 4 – MASONRY

042000 Unit Masonry

DIVISION 5 – METALS

051200	Structural Steel Framing
052100	Steel Joist Framing
053100	Steel Decking
055000	Metal Fabrications

DIVISION 6 - WOOD PLASTICS AND COMPOSITES - NOT USED

<u>DIVISION 7 – THERMAL AND MOISTURE PROTECTION</u>

075423 TPO Membrane Roofing

TABLE OF CONTENTS TOC - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

DCS	5D Solicitation No.: FAC2223-03 / Architect's Project No: 62400					
079200	Joint Sealants					
079513	Expansion Joint Cover Assemblies					
DIVISION 8 – OPENINGS						
081113 Steel Doors and Frames						
081416	Flush Wood Doors					
083100	Access Doors and Panels					
084313	Aluminum-Framed Storefronts					
087100	Door Hardware					
088000	Glazing					
DIVISION 9 - FINISHE	S					
092900	 Gypsum Board					
093000	Tiling					
095100	Acoustical Ceilings					
096500	Resilient Flooring					
096513	Resilient Base and Accessories					
096700	Fluid-Applied Flooring					
099100	Painting					
DIVISION 10 - SPECIA	ALTIES					
102113.19	Plastic Toilet Compartments					
102600	Wall and Door Protection					
102800	Toilet and Bath Accessories					
104400	Fire Protection Specialties					
107300	Protective Covers					
DIVISION 11 – EQUIPI	MENT - NOT USED					
DIVISION 12 – FURNIS	SHINGS					
122400	Window Shades					
DIVISION 13 - SPECIA	AL CONSTRUCTION – NOT USED					
DIVISION 14 – CONVE	EYING SYSTEMS – NOT USED					
	UPPRESSION – NOT USED					
DIVISION 22 – PLUME						
220500	Common Work Results for Plumbing					
220513	Motors for Plumbing Equipment					
220517	Sleeves and Sleeve Seals for Plumbing Piping					
220519	Meters and Gages for Plumbing Piping					
220523	General-Duty Valves for Plumbing Piping					
220529	Hangers and Supports for Plumbing Piping and Equipment					
220553	Identification for Plumbing Piping and Equipment					
220700	Plumbing Insulation					
221116	Domestic Water Piping					
221119	Domestic Water Piping Specialties					
221316	Sanitary Waste and Vent Piping					

TABLE OF CONTENTS TOC - 2

Sanitary Waste Piping Specialties

221319

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

224000	Plumbing Fixtures					
DIVISION 23 – MECHANICAL						
230500 Common Work Results for HVAC						
230513	Motors for HVAC Equipment					
230529	Hangers and Supports for HVAC Piping and Equipment					
230548	Vibration and Seismic Control for HVAC					
230553	Identification for HVAC Piping and Equipment					
230700	HVAC Insulation					
230900	Building Automation System					
230993	Sequence of Operations for HVAC Controls					
232113	Hydronic Piping					
232300	Refrigerant Piping					
233113	Metal Ducts					
233300	Air Duct Accessories					
233423	HVAC Power Ventilators					
233713	Diffusers, Registers, and Grilles					
234100	Particulate Air Filtration					
238113	Wall Mounted Heat Pumps					
238239	Unit Heaters					
DIVISION 25 - INTE	GRATED AUTOMATION - NOT USED					
DIVISION 26 - ELEC	CTRICAL					
260500	Common Work Results for Electrical					
260519	Low-Voltage Electrical Power Conductors and Cables					
260526	Grounding and Bonding for Electrical Systems					
260529	Hangers and Supports for Electrical Systems					
260533	Raceways and Boxes for Electrical Systems					
260553	Identification for Electrical Systems					
260923	Lighting Control Devices					
262726	Wiring Devices					
262813	Fuses					
262816	Enclosed Switches and Circuit Breakers					
262913	Enclosed Controllers					
265119	LED Interior Lighting					
265619	LED Exterior Lighting					

<u>DIVISION 27 – COMMUNICATIONS</u> – NOT USED

<u>DIVISION 28 – ELECTRONIC SAFETY AND SECURITY</u>

280500	Common Work Results for Electronic Safety and Security
283111	Digital, Addressable Fire-Alarm System

TABLE OF CONTENTS TOC - 3

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

<u>DIVISION 31 – EARTHWORK</u> – NOT USED

<u>DIVISION 32 – EXTERIOR IMPROVEMENTS</u> – NOT USED

DIVISION 33 – UTILITIES – NOT USED

<u>DIVISION 34 – TRANSPORTATION – NOT USED</u>

END OF SPECIFICATIONS

APPENDICES

2018 AHERA REINSPECTION REPORT DATED FEBRUARY 13, 2018

END OF TABLE OF CONTENTS

TABLE OF CONTENTS TOC - 4



Solicitation: FAC2223-03 Issue Date: March 28, 2023 Buyer: Laurie O Lane Phone: (843) 398-2249

Number

Email: laurie.lane@darlington.k12.sc.us

Amendment Amendment Amendment Amendment

Number

Number

Invitation For Bid

DESCRIPTION: Mayo High School Toilet Renovation

Acknowledgment of Amendments offerors acknowledges receipt of amendments

SUBMIT OFFER BY (Opening Date/Time): April 26, 2023 @ 11:00 am "Submission Of Offer"

NUMBER OF COPIES TO BE SUBMITTED: 1

QUESTIONS MUST BE RECEIVED BY: April 17, 2023 @ 3:00 pm "Questions From Offerors"

by indicating amendi	nent number, date of issue and initials of Offeror.						
Date of Amendment							
Initials of Offeror							
AWARD & AMENDMENTS It is anticipated that a "Notice of Intent to Award" or "Contract Award" will be posted in the Darlington County School District Office, 2308 N Governor Williams Hwy., Darlington, SC, sent to all Bidders and posted on the District's website at http://www.darlington.k12.sc.us click "Departments" click "Finance & Procurement" click "Solicitation Awards" click "2022-23 Operations Solicitation Awards" within thirty (30) days following the bid opening date and time. Any resulting contract from this solicitation will incorporate the terms, conditions, provisions, specifications and/or scope of work described herein except as may be amended by any amendment, "Notice of Intent to Award," or "Contract Award." This solicitation and any amendments will also be posted on the District's website. You must submit a signed copy of this form with Your Offer. By submitting a bid or proposal, You agree to be bound by the terms of the Solicitation. You agree to hold Your Offer open for a minimum of forty-five (45) calendar days after the Opening Date.							
NAME OF OFFER	OR (Full legal name of business submitting	g the offer))FFEROR'S 1	TYPE OF EN	TITY:	
ALITHODIZED 016	NATURE.			(Che	eck one)		
AUTHORIZED SIGNATURE (Offeror named Person signing must be authorized to submit binding offer to enter contract on behalf of above.)				□ Sole Proprietorship SSN □ Corporation Federal ID # □ S. C. Minority Vendor Minority Vendor # □ Other (See provision entitled "Signing Your Offer".)			
AUTHORIZED PERSON'S NAME PRINTED							
TITLE (Business	ess title of person signing above) DATE CITY S1				STATE		
MAILING ADDRES	SS	CITY		STA	TE	ZIP	
STREET ADDRESS CITY				STA	TE	ZIP	

E-MAIL TELEPHONE FAX

Solicitation Outline

I.	Scope of Solicitation
II.	Instructions to Offerors
	A. General Instructions
	B. Special Instructions
III.	Scope of Work / Specifications
	May be blank if Bidding Schedule / Cost Proposal attached
IV.	Information for Offerors to Submit
V.	Qualifications
VI.	Award Criteria
VII.	Terms and Conditions
	A. General
	B. Special
VIII.	Bidding Schedule

I. SCOPE OF SOLICITATION – It is the intent of DCSD to solicit bids for renovations on four (4) restrooms at Mayo High School Cafeteria. Mayo High School, 405 Chestnut St, Darlington SC 29532

II. INSTRUCTIONS TO OFFERORS

A. GENERAL INSTRUCTIONS

AMENDMENTS TO SOLICITATION a) The Solicitation may be amended at any time prior to opening. All actual and prospective Offerors should monitor the following web site for the issuance of Amendments: http://www.darlington.k12.sc.us Click Departments, Click Finance & Procurement, Click Solicitations, Click 2022-23 Operations Solicitations, (b) Bidders shall acknowledge receipt of any Amendment to this solicitation (1) by signing and returning the Amendment, (2) by letter, or (3) by submitting a bid that indicates in some way that the bidder received the amendment.

AWARD NOTIFICATION Notice regarding the District's intent to award a contract will be posted at the location specified on the Cover Page. The date and location of posting will be announced at opening. If the contract resulting from this Solicitation has a total or potential value in excess of fifty thousand dollars, such notice will be sent to all Offerors responding to the Solicitation and any award will not be effective until the eleventh day after such notice is given.

BID / PROPOSAL AS OFFER TO CONTRACT By submitting Your Bid or Proposal, You are offering to enter into a contract with Darlington County School District. Without further action by either party, a binding contract shall result upon final award. Any award issued will be issued to, and the contract will be formed with, the entity identified as the Offeror on the Cover Page. An Offer may be submitted by only one legal entity; "joint bids" are not allowed.

PROCUREMENT OFFICER AS PROCUREMENT AGENT (a) Authorized Agent. All authority regarding the conduct of this procurement is vested solely with the responsible Procurement Officer or designee. Unless specifically delegated in writing, the Procurement Officer is the only official authorized to bind the District with regard to this procurement. (b) Purchasing Liability. The Procurement Officer is an employee of Darlington County School District acting on behalf of Darlington County School District pursuant to the Consolidated Procurement Code. Any contracts awarded as a result of this procurement are between the Contractor and Darlington County School District. The Procurement Officer is not a party to such contracts and bears no liability for any party's losses arising out of or relating in any way to the contract.

DEADLINE FOR SUBMISSION OF OFFER Any offer received after the procurement officer of Darlington County School District or his designee has declared that the time set for opening has arrived, shall be rejected unless the offer has been delivered to the designated purchasing office for Darlington County School prior to the bid opening.

DEFINITIONS Except as otherwise provided herein, the following definitions are applicable to all parts of the solicitation. For additional definitions, see the terms and conditions below.

- (1) AMENDMENT means a document issued to supplement the original solicitation document.
- (2) BOARD means the Darlington County School District Board of Education.
- (3) BUYER means the Procurement Officer.
- (4) CHIEF PROCUREMENT OFFICER means the Director of Purchasing or designee.
- (5) COVER PAGE means the top page of the original solicitation on which the solicitation is identified by number. Offerors are cautioned that Amendments may modify information provided on the Cover Page.
- (6) DISTRICT means Darlington County School District.
- (7) OFFER means the bid or proposal submitted in response to this solicitation. The terms "Bid" and "Proposal" are used interchangeably with the term "Offer."
- (8) OFFEROR means the single legal entity submitting the offer. The term "Bidder" is used interchangeably with the term "Offeror." See bidding provisions entitled "Signing Your Offer" and "Bid/Proposal As Offer To Contract."
- (9) PROCUREMENT OFFICER means the person, or his successor, identified as such on the Cover Page.
- (10) SOLICITATION means this document, including all its parts, attachments, and any Amendments.
- (11) SUCCESSFUL BIDDER The Bidder chosen by the District for award of a contract. (Also known as the "Contractor" upon commencement of the contract)
- (12) SUBCONTRACTOR means an individual or entity having a contract to perform work or render service to Contractor as a part of the Contractor's agreement arising from this solicitation.
- (13) YOU and YOUR means Offeror.
- (14) CHANGE ORDER means any written alteration in specifications, delivery point, rate of delivery, period of performance, price, quantity, or other provisions of any contract accomplished by mutual agreement of the parties to the contract.

- (15) CONTRACT See clause entitled Contract Documents & Order of Precedence.
- (16) WORK means all labor, materials, equipment and services provided or to be provided by the Contractor to fulfill the Contractor's obligations under the Contract

DUTY TO INQUIRE Offeror, by submitting an Offer, represents that it has read and understands the Solicitation and that its Offer is made in compliance with the Solicitation. Offerors are expected to examine the Solicitation thoroughly and should request an explanation of any ambiguities, discrepancies, errors, omissions, or conflicting statements in the Solicitation. Failure to do so will be at the Offeror's risk. Offeror assumes responsibility for any patent ambiguity in the Solicitation that Offeror does not bring to the District's attention.

TAXES OMIT FROM PRICE Do not include any taxes in your price that Darlington County School District may be required to pay.

PROTESTS Any prospective bidder, offeror, contractor, or subcontractor who is aggrieved in connection with the solicitation of a contract shall protest within fifteen (15) days of the date of issuance of the applicable solicitation document at issue. Any actual bidder, offeror, contractor, or subcontractor who is aggrieved in connection with the intended award or award of a contract shall protest within ten (7) days of the date notification of award is posted in accordance with the District's Procurement Code. A protest shall be in writing, submitted to the Chief Procurement Officer, 120 East Smith Avenue, Darlington, SC 29540 and shall set forth the grounds of the protest and the relief requested with enough particularity to give notice of the issues to be decided.

PUBLIC OPENING Offers will be publicly opened at the date / time and at the location identified on the Cover Page, or last Amendment, whichever is applicable. Prices will not be divulged at this time.

QUESTIONS FROM OFFERORS (a) Any prospective offeror desiring an explanation or interpretation of the solicitation, drawings, specifications, etc., must request it in writing. Questions must be received by the Procurement Officer no later than five (5) days prior to opening unless otherwise stated on the Cover Page. Oral explanations or instructions will not be binding. Any information given a prospective offeror concerning a solicitation will be furnished promptly to all other prospective offerors as an Amendment to the solicitation, if that information is necessary for submitting offers or if the lack of it would be prejudicial to other prospective offerors. (b) Darlington County School District seeks to permit maximum practicable competition. Offerors are urged to advise the Procurement Officer - as soon as possible - regarding any aspect of this procurement, including any aspect of the Solicitation that unnecessarily or inappropriately limits full and open competition.

RESPONSIVENESS / IMPROPER OFFERS

- (A) <u>Bid as Specified</u>. Offers for supplies or services other than those specified will not be considered unless authorized by the Solicitation.
- (b) <u>Multiple Offers</u>. Offerors may submit more than one Offer, provided that each Offer has significant differences other than price. Each separate Offer must satisfy all Solicitation requirements. While multiple Offers may be submitted as one document, Offeror is responsible for clearly differentiating between each separate Offer. If this solicitation is a Request for Proposals, each separate Offer must include a separate cost proposal.
- (c) <u>Responsiveness</u>. Any Offer which fails to conform to the material requirements of the Solicitation may be rejected as nonresponsive. Offers which impose conditions that modify material requirements of the Solicitation may be rejected. If a fixed price is required, an Offer will be rejected if the total possible cost to Darlington County School District cannot be determined. Offerors will not be given an opportunity to correct any material nonconformity. Any deficiency resulting from a minor informality may be cured or waived at the sole discretion of the Procurement Officer.
- (d) <u>Unbalanced Bidding</u>. Darlington County School District may reject an Offer as nonresponsive if the prices bid are materially unbalanced between line items or subline items. A bid is materially unbalanced when it is based on prices significantly less than cost for some work and prices which are significantly overstated in relation to cost for other work, and if there is a reasonable doubt that the bid will result in the lowest overall cost to Darlington County School District even though it may be the low evaluated bid, or if it is so unbalanced as to be tantamount to allowing an advance payment.

RESTRICTIONS APPLICABLE TO OFFERORS By submitting an Offer, You agree not to discuss this procurement activity in any way with any Darlington County School District employees, agents or officials. All communications must be solely with the Procurement Officer. This restriction expires once a contract has been formed and may be lifted by express written permission from the Procurement Officer.

SIGNING YOUR OFFER Every Offer must be signed by an individual with actual authority to bind the Offeror. (a) If the Offeror is an individual, the Offer must be signed by that individual. If the Offeror is an individual doing business as a firm, the Offer must be

submitted in the firm name, signed by the individual, and state that the individual is doing business as a firm. (b) If the Offeror is a partnership, the Offer must be submitted in the partnership name, followed by the words "by its Partner," and signed by a general partner. (c) If the Offeror is a corporation, the Offer must be submitted in the corporate name, followed by the signature and title of the person authorized to sign. (d) An Offer may be submitted by a joint venturer involving any combination of individuals, partnerships, or corporations. If the Offeror is a joint venture, the Offer must be submitted in the name of the Joint Venture and signed by every participant in the joint venture in the manner prescribed in paragraphs (a) through (c) above for each type of participant. (e) If an Offer is signed by an agent, other than as stated in subparagraphs (a) through (d) above, the Offer must state that is has been signed by an Agent. Upon request, Offeror must provide proof of the agent's authorization to bind the principal.

DISCUSSION WITH RESPONSIVE OFFERORS Discussions may be conducted with responsive offerors who submit proposals for the purpose of clarification to assure full understanding of the requirements of the Invitation for Bid. All offerors, whose proposals, in Darlington County School District's sole judgment, needing clarification shall be accorded such an opportunity.

SUBMITTING CONFIDENTIAL INFORMATION For every document Offeror submits in response to or with regard to this solicitation or request, Offeror must separately mark with the word "CONFIDENTIAL" every page, or portion thereof, that Offeror contend contains information that is exempt from public disclosure because it is either (a) a trade secret as defined in Section 30-4-40(a)(1), or (b) privileged and confidential, as that phrase is used in Section 11-35-410. For every document Offeror submits in response to or with regard to this solicitation or request, Offeror must separately mark with the words "TRADE SECRET" every page, or portion thereof, that Offeror contends contains a trade secret as that term is defined by Section 39-8-20 of the Trade Secrets Act.

For every document Offeror submits in response to or with regard to this solicitation or request, Offeror must separately mark with the word "PROTECTED" every page, or portion thereof, that Offeror contends is protected by Section 11-35-1810. All markings must be conspicuous; use color, bold, underlining, or some other method in order to conspicuously distinguish the mark from the other text.

Do not mark your entire response (bid, proposal, quote, etc.) as confidential, trade secret, or protected! If your response, or any part thereof, is improperly marked as confidential or trade secret or protected, the District may, in its sole discretion, determine it nonresponsive. If only portions of a page are subject to some protection, do not mark the entire page. By submitting a response to this solicitation or request, Offeror (1) agrees to the public disclosure of every page of every document regarding this solicitation or request that was submitted at any time prior to entering into a contract (including, but not limited to, documents contained in a response, documents submitted to clarify a response, and documents submitted during negotiations), unless the page is conspicuously marked "TRADE SECRET" or "CONFIDENTIAL" or "PROTECTED", (2) agrees that any information not marked, as required by these bidding instructions, as a "Trade Secret" is not a trade secret as defined by the Trade Secrets Act, and (3) agrees that, notwithstanding any claims or markings otherwise, any prices, commissions, discounts, or other financial figures used to determine the award, as well as the final contract amount, are subject to public disclosure. In determining whether to release documents, the District will detrimentally rely on Offeror's marking of documents, as required by these bidding instructions, as being either "Confidential" or "Trade Secret" or "PROTECTED". By submitting a response, Offeror agrees to defend, indemnify and hold harmless Darlington County School District, its officers and employees, from every claim, demand, loss, expense, cost, damage or injury, including attorney's fees, arising out of or resulting from the District withholding information that Offeror marked as "confidential" or "trade secret" or "PROTECTED". (All references to S.C. Code of Laws.)

SUBMITTING YOUR OFFER OR MODIFICATION (a) Offers and offer modifications shall be submitted in sealed envelopes or packages (unless submitted by approved electronic means) - (1) Addressed to the office specified in the Solicitation; and (2) Showing the time and date specified for opening, the solicitation number, and the name and address of the bidder. (b) Each Offeror must submit the number of copies indicated on the Cover Page. (c) Offerors using commercial carrier services shall ensure that the Offer is addressed and marked on the outermost envelope or wrapper for clear identification when delivered to the office specified in the Solicitation. (d) Facsimile Offers, modifications, or withdrawals, will not be considered unless authorized by the Solicitation. (e) Offers submitted by electronic commerce shall be considered only if the electronic commerce method was specifically stipulated or permitted by the solicitation.

BID ACCEPTANCE PERIOD In order to withdraw your Offer after the minimum period specified on the Cover Page, you must notify the Procurement Officer in writing.

BID IN ENGLISH & DOLLARS Offers submitted in response to this solicitation shall be in the English language and in US dollars, unless otherwise permitted by the solicitation.

REJECTION/CANCELLATION The District may cancel this solicitation in whole or in part. The District may reject any or all proposals in whole or part.

WITHDRAWL OR CORRECTION OF OFFER Offers may be withdrawn by written notice received at any time before the exact time set for opening. If the solicitation authorizes facsimile offers, offers may be withdrawn via facsimile received at any time before the exact time set for opening. A bid may be withdrawn in person by a bidder or its authorized representative if, before the exact time set for opening, the identity of the person requesting withdrawal is established and the person signs a receipt for the bid.

ETHICS ACT By submitting an Offer, you certify that you are in compliance with South Carolina's Ethics, Government Accountability, and Campaign Reform Act of 1991, as amended. The following statutes require special attention: (a) Offering, giving, soliciting, or receiving anything of value to influence action of public employee-Section 8-13-790, (b) Recovery of Kickbacks-Section 8-13-790m (c) Offering, soliciting, ore receiving money for advice or assistance of public official – Section 8-13-720, (d) Use or disclosure of confidential information –Section 8-13-725, and (e) Persons hired to assist in the preparation of specifications or evaluation of bids. Section 8-13-1150.

DRUG FREE WORK PLACE CERTIFICATION By submitting an Offer, Contractor certifies that, if awarded a contract, Contractor will comply with all applicable provisions of the Drug-Free Workplace Act, Title 44, Chapter 107 of the South Carolina Code of Laws, as amended.

OFFICE CLOSING If an emergency or unanticipated event interrupts normal District processes so that offers cannot be received at the District office designated for receipt of bids by the exact time specified in the solicitation, the time specified for receipt of offers will be deemed to be extended to the same time of day specified in the solicitation on the first work day on which normal District's processes resume. In lieu of an automatic extension, an amendment may be issued to reschedule bid opening. If District offices are closed at the time a pre-bid or pre-proposal conference is scheduled, an amendment will be issued to reschedule the conference.

IRAN DIVESTMENT ACT By submission of this bid, each bidder and each person signing on behalf of any bidder certifies, that to the best of its knowledge and belief that each bidder is not on the list created pursuant to Section 11-57-310.

SORT By submission of this bid, the bidder is signing on behalf of himself and any workers employed, that they are in compliance with all of the State SORT laws, South Carolina Code of Laws 23-3-535.

B. SPECIAL INSTRUCTIONS

Questions Relating to this Invitation For Bid

Questions for the purpose of clarifying any part of this IFB must be in writing and can be delivered, or e-mailed to: Laurie Lane, Darlington County School District, Operations/Facilities Procurement Office, 2308 N Governor Williams Hwy, Darlington, SC 29540.

Pre-bid Meeting – A non-mandatory Pre-bid meeting will be held on Tuesday, April 4, 2023 at 10:00 am. The meeting will begin at 2308 N Governor Williams Hwy, Darlington SC 29540 (Operations Building)

E-mail: <u>laurie.lane@darlington.k12.sc.us</u> The solicitation number and name must be clearly noted on all correspondence. For correspondence via e-mail, put it in the 'Subject' field.

Questions for the purpose of clarifying any part of this IFB will be responded to and will be posted at the following web address: http://www.darlington.k12.sc.us Click Departments, Click Finance & Procurement, Click Solicitations, Click 2022-23 Operations Solicitations.

Bid Submittal

The District shall receive all bids no later than the date and time specified on the cover page. The District will accept bids via email if you choose to do so. When they are received, they will be printed and put in an envelope and sealed for specified bid opening time. It will be the bidder's responsibility to check with the Procurement Officer to make sure the bid was received before the opening date/time. The District will not accept any responsibility for bids that were not received or followed up on in a timely manner.

Faxed bids are not acceptable.

Required: Clearly mark the outside of the sealed envelope, box, or package containing the bid <u>and</u> the FEDEX or UPS package with the solicitation # and solicitation description found on the cover page.

Hand delivery/Mail/ Courier service to: Laurie Lane Darlington County School District Operations/Facilities Procurement Office 2308 N Governor Williams Hwy, Darlington, SC 29540

Bidder is solely responsible for ensuring that its courier service provider makes inside deliveries to our physical location. The District is not responsible for any delays caused by the Bidder's chosen means of proposal delivery. **Bidder failure to meet the proposal due date and time shall result in rejection of the bid.**

III. SCOPE OF WORK

Darlington County School District is seeking contractors to provide construction for the minor renovation of four (4) toilet rooms at Mayo High School. The existing four (4) bathrooms shall be reconfigured to 2 group bathrooms, that are accessible. An approximately 540 square foot vestibule addition shall be added to the cafeteria building to allow for enclosed access to the new bathrooms. The renovation of the toilet rooms includes selective demolition, new interior partition construction, interior finish alterations, mechanical grilles replacements, light fixture replacements, and plumbing fixture replacements. Existing interior finishes shall be removed and replaced including floor tile, wall tile, ceiling tile, and paint. Existing interior doors shall be removed and replaced. The addition to enclose entrances to bathrooms include steel structure and CMU masonry walls with brick exterior. New aluminum storefront windows at addition and replacement of existing steel frame doors to match new work completed at Mayo HS. Refer to drawings and specifications for complete scope of work. All contractors are required to work according to OSHA regulations and all care should be taken to ensure the safety of all students, staff, visitors, and other employees. All contractors shall conduct themselves and their work in a professional manner. This is a turnkey job and the contractor is responsible for all the material, labor, equipment, tools, and anything else required to complete this work according to the details specified herein. Iob is expected to be substantially completed no later than August 1, 2023.

IV. INFORMATION FOR OFFERORS TO SUBMIT

- 1. Offeror is to provide Signature Sheet (Page 1)
- 2. Bidding Schedule (Pages 12)
- 3. Vendor Application Form (Page 11)
- 4. All bids should be complete and should convey all of the information requested by the District. If significant errors are found in the Offeror's bid, or if the bid fails to conform to the essential requirements of the IFB, the District and the District alone, will be the judge as to whether the variance is significant enough to reject the bid. Bids which included either modifications to any of the contractual requirements of the IFB or an Offeror's standard terms and conditions may be deemed non-responsive and therefore not considered for award.
- 5. Certificate of Insurance with DSCD named as Certificate holder (Must be provided if awarded bid).

Failure to provide all requested information will be reason for rejection of bid.

V. **QUALIFICATIONS**

Offeror must, upon request of the District, furnish satisfactory evidence of its ability to furnish the goods or services requested in accordance with the terms and conditions set forth in this bid. The District reserves the right to make the final determination as to the Offeror's ability to provide the goods/services requested herein.

A SC General or Mechanical Contractors license is required for anyone performing commercial construction over 5,000 in the regulated classifications listed in Title 40, Chapter 11, Section 40-11-410. Commercial contractors will be required to include their SC License # on the bidding schedule. (If applicable)

VI. <u>AWARD CRITERIA</u>

Award will be made to the lowest responsive and responsible bidder.

The District reserves the right to accept the bid that is in the best interest of the District.

VII. Terms and Conditions

A. General

AFFIRMATIVE ACTION: The contractor will take affirmative action in complying with all Federal and State requirements concerning fair employment and employment of the handicapped, and concerning the treatment of all employees, without regard or discrimination by reason of race, color, religion, sex, national origin or physical handicap. The following are incorporated herein by reference: 41 C.F.R. 60-1.4, 60-250.4 and 60-741-4.

ASSIGNMENT: No contract or its provisions may be assigned, sublet, or transferred without the written consent of the Darlington County School District.

CONTRACT AMENDMENTS, MODIFICATIONS & CHANGE ORDERS: Any change orders, alterations, amendments or other modifications hereunder shall not be effective unless reduced to writing and approved by the Procurement Officer responsible for this solicitation and the contractor. All questions, problems or changes arising after award of this contract shall be directed to the Procurement Officer responsible for this solicitation, Laurie Lane, Operations/Facilities Procurement Office, 2308 N Governor Williams Hwy, Darlington, South Carolina 29540.

FORCE MAJEURE: The Contractor shall not be liable for any excess costs if the failure to perform the contract arises out of causes beyond the control and without the fault or negligence of the contractor. Such causes may include, but are not restricted to acts of God or of the public enemy, acts of the Governments in either its sovereign or contractual capacity, fires, floods, epidemics, quarantine restrictions, strikes, freight embargoes, and unusually severe weather; but in every case the failure to perform must be beyond the control and without the fault or negligence of the contractor. If the failure to perform is caused by the default of a subcontractor, and if such default arises out of causes beyond the control of both the contractor and subcontractor, and without the fault or negligence of either of them, the contractor shall not be liable for any excess costs for failure to perform, unless the supplies or services to be furnished by the subcontractor were obtainable from other sources in sufficient time to permit the contractor to meet the required delivery schedule.

INDEMNIFICATION: Darlington County School District, its officers, agents, and employees, shall be held harmless from liability from any claims, damages and actions of any nature arising from a resultant contract, provided that such liability is not attributable to negligence on the part of the using agency or failure of the using agency to comply with the offer as outlined in the offeror's proposal.

PAYMENT FOR GOODS & SERVICES: Payment for goods & services received by the District shall be processed in accordance with Darlington County School District Procurement Code.

PRIME CONTRACTOR RESPONSIBILITIES: The contractor will be required to assume sole responsibility for the complete effort as required by this IFB. The District will consider the contractor to be the sole point of contact with regard to contractual matters.

SOUTH CAROLINA GOVERNING LAW CLAUSE: The Agreement and any dispute, claim, or controversy relating to the Agreement shall, in all respects, be interpreted, construed, enforced and governed by and under the laws of the State of South Carolina. All disputes, claims, or controversies relating to the Agreement shall be resolved exclusively by the appropriate Chief Procurement Officer in accordance with the District Procurement Code, or in the absence of jurisdiction, only in the Court of Common Pleas for, or a federal court located in, Darlington County, State of South Carolina. Contractor agrees that any act by the District regarding the

Agreement is not a waiver of either the District's sovereign immunity or the District's immunity under the Eleventh Amendment of the United State's Constitution. As used in this paragraph, the term "Agreement" means any transaction or agreement arising out of, relating to, or contemplated by the solicitation.

SUBCONTRACTING: If any part of the work covered by this IFB is to be subcontracted, the offeror shall identify the subcontracting organization and the contractual arrangements made therewith. All subcontractors must be approved by the District. The offeror will also furnish the corporate or company name and the names of the officers of any subcontractors engaged by the offeror.

TERMINATION: Subject to the Provisions below, any contract resulting from this proposal may be terminated by the Director of Procurement, provided a thirty (30) days advance notice in writing is given to the contractor.

<u>Convenience</u>: In the event that this contract is terminated or canceled upon request and for the convenience of the District without the required thirty (30) days advance written notice, then the District shall negotiate reasonable termination costs, if applicable.

<u>Cause</u>: Termination by the District for cause, default or negligence on the part of the contractor shall be excluded from the foregoing provisions; termination costs, if any, shall not apply. The thirty (30) days advance notice requirement is waived and the default provision in the bid shall apply.

Default: In case of default, the District reserves the right to purchase any or all items/services in default in open market, charging the Contractor with any excessive costs. SHOULD SUCH CHARGE BE ASSESSED, NO SUBSEQUENT PROPOSALS OF THE DEFAULTING CONTRACTOR WILL BE CONSIDERED UNTIL THE ASSESSED CHARGE HAS BEEN SATISFIED.

OFFEROR RESPONSIBILITY: Each offeror shall fully acquaint himself with conditions relating to the scope and restrictions attending the execution of the work under the conditions of this proposal. It is expected that this will sometimes require on-site observation. The failure or omission of an offeror to acquaint himself with existing conditions shall in no way relieve him of any obligation with respect to this proposal or to the contract.

OWNERSHIP OF MATERIAL: Ownership of all data, material and documentation originated and prepared for the District pursuant to this contract shall belong exclusively to the District.

B. Special

CHANGES: Any changes, additions, or deletions must first be authorized by the Darlington County School District Procurement Department.

INSPECTION RIGHTS:

Darlington County School District reserves the right to inspect and approve the services/equipment offered under the specifications of this solicitation.

INSURANCE REQUIREMENTS: The successful contractor must furnish within ten (10) days after written acceptance of bid a copy of his Worker's Compensation and/or General Liability insurance certificate to the District. Worker's Compensation coverage shall meet the requirements of South Carolina law. It is agreed that the coverage, as stated, shall not be cancelled or altered until ten (10) days after written notice of any change has been sent by registered mail to the Purchasing Department of Darlington County School District.

WARRANTY:

The contractor warrants to Darlington County School District that all services performed as a result of this bid and specifications will be performed in a professional manner consistent with industry practices.

FEES, LICENSES, PERMITS AND RESPONSIBILITIES:

The contractor, at his own expense, is responsible for obtaining any necessary licenses, fees, or permits and for complying with all applicable Federal, State, and local laws and regulations in connection with the performance of this service. Contractor shall be responsible for all damages to persons or property that occurs as a result of his or employees' fault or negligence. Contractor should complete project within thirty (30) days of the award being issued by the District.

DEBARMENT/SUSPENSION:

By submission of a response to this solicitation, bidders are certifying that they are not debarred or suspended from doing business with any other School District.

Darlington County School District reserves the right:

- to award bids based on individual items, group items, or the entire list of items;
- to reject any or all bids, or any part thereof;
- to waive any informality in bids;
- to accept the bid that is most advantageous to the District.

Additional Bid & Contract Conditions

REQUIRED INSURANCE LIMITS:

Automobile Liability to include all vehicles owned, leased, used by the Contractor and written on an occurrence basis with the same insurer that covers the commercial general liability.

Bodily injury minimum limit of \$500,000

Property damage minimum limit of \$50,000

With the District named as an additional insured.

Commercial General Liability written as a combined single limit for bodily injury and property damage and written on a per occurrence basis with the same insurer that covers the automobile liability.

Bodily injury and property damage combined minimum limit of \$500,000 with general aggregate of \$1,000,000 with the aggregate limit applying in total to this contract only.

Products and completed operations minimum limit of \$300,000 maintained for up to two (2) additional years following final completion or termination of the contract.

Personal and advertising injury minimum limit of \$300,000

Contractual liability minimum limit of \$300,000

With the District named as an additional insured.

Worker's Compensation as required by law and including disease benefit.



VENDOR APPLICATION FORM

Procurement Office Use Only Vendor ID # Initials

BUSINESS <u>FULL LEGAL</u> NAME & ADDRESS:	REMITTANCE ADDRESS (IF DIFFERENT):
PHONE: FAX:	PHONE: FAX:
WATTS: CELL:	WATTS: CELL:
→ WEBSITE ADDRESS:	
NAMES OF OWNERS, OFFICERS, PARTNERS AUTHORIZED TO BE OWNER / PRESIDENT: → EMAIL ADDRESS FOR OWNER / PRESIDENT:	PHONE: FAX:
PARTNER 1:	PHONE: FAX:
PARTNER 2:	PHONE: FAX:
VICE-PRESIDENT:	PHONE: FAX:
TREASURER:	PHONE: FAX:
DISTRICT MANAGER:	PHONE: FAX:
SALES REPRESENTATIVE:	PHONE: FAX:
→ EMAIL ADDRESS FOR MAIN SALES CONTACT:	
INFORMATION ABOUT TYPE OF BUSINESS: TYPE:	INFORMATION ABOUT PRODUCTS / SERVICES: (Find "best fit" category(ies). Check all that apply.) Books & Similar Materials Landscaping / Lawn Maint. Computer Hdw / Software Printing Construction (Specify Below) Rentals (specify) Electrical Masonry Repairs (specify) Mechanical / HVAC Painting Services (specify) Plumbing Supplies (specify) Roofing Supplies (specify) Equipment Food Products Telecommunications Furniture Vehicles / Trucks Other (specify)
IDENTIFICATION AND CERTIFICATION: In compliance with Internal Revenue Service and State of South Carolina regulare required by law to obtain this information when making a reportable payme 31% backup withholding and \$50 penalty. ** This serves as a substitute Feder For Individuals, enter social security number (SSN):	
For sole proprietors, enter owner's SSN or Federal Employer's Id	entification Number (FFIN):
For partnerships, corporations or others, enter FEIN:	Citational Indinoci (i Elity).
	Calas Tay Lisanes Number
For verification of sales tax collection authority, enter State of SC	
For certified minority/disadvantaged businesses, enter State of S	
Under penalties of perjury, I certify that the numbers provided above are true as am exempt, or (b) I have not been notified by the IRS that I am subject to back or (c) the IRS has notified me that I am no longer subject to backup withholding applicant nor anyone in connection with the applicant as a principal or officer, sineligible to do business with any agency of the State of South Carolina, the Fe	up withholding as a result of failure to report all interest or dividends, g. I further certify that all information supplied herein is correct and the to far as is known, is now debarred, suspended or otherwise declared
Authorized Signatory Print Name & Title	Date Completed

BIDDING SCHEDULE FAC2223-03 Mayo High School Toilet Renovation

Total Bid	\$		
SIGNATURE			
<u>JANATORE</u>			
(Legal Name of Person, Firm or Corporat	 tion Submitting Bid)	(Phone Number)	_
(Mailing Address for the above)		(Email Address)	_
(Printed Name of Person Authorized to b	oid)	(Title)	
(Signature of Person Authorized to bid)		(Date)	
SC CONTRACTOR LICENSE #			

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PREBID QUESTION FORM

Only questions requiring a modification or interpretation to the Bidding Documents by an addition, deletion, clarification, or correction, will be made by written Addendum, and transmitted to Planholders of Record on the school district website. To obtain the information: http://www.darlington.k12.sc.us Click Departments, Click Finance & Procurement, Click Solicitations, Click 2022-23 Operations Solicitations.

Questions that do not require a modification or interpretation to the Bidding Documents will not be responded to and will not be included in an Addendum.

The Architect and Owner shall not be responsible for oral modifications and interpretations. Bidders and Sub-bidders requesting a modification or interpretation by addition, deletion, clarification, or correction of the Bidding Documents shall complete and submit this form no later than **April 17, 2023 at 3:00pm** standard time. Use a separate form for each question submitted.

DATE:					
	The following question concerns Drawing (number):				
paragraph					
_					
-	Name	Organization			
Telephone No. ()	e-mail Address:				

Submit via email PDF version of form to: Laurie Lane

laurie.lane@darlington.k12.sc.us

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 011000 SUMMARY

PART 1 GENERAL

1.01 PROJECT

- A. Project Name: Mayo High School Toilet Renovation.
- B. Owner's Name: Darlington County School District.
- C. Architect's Name: Moseley Architects of Charleston, SC.
- D. Owner's Solicitation No.: FAC2223-03.

1.02 CONTRACT DESCRIPTION

A. Contract Type: A single prime contract based on a Stipulated Price (Fixed Sum) as described in the Bidding and Contractual Requirements (Division 00) included in this Project Manual.

1.03 PROFESSIONAL SEALS

- A. Use of Professional Seals on Bidding, Procurement, and Contract Documents: For the purposes of this paragraph, the term "Regulant" refers to the individual who signs and seals parts of the Contract Documents (e.g. the Drawings and Specifications). Certain information has been excerpted verbatim from a source or sources (e.g., UL Assemblies, SMACNA details, IBC code text) which was considered or used by Regulant in preparing parts of the Contract Documents, as follows:
 - The excerpted information was neither prepared under the direct control nor personal supervision nor created by the Regulant, as it was prepared by the source and owner of the excerpted information.
 - For purposes of bidding, procuring, and performance of the Work, and in any event of
 conflicts or ambiguities between the excerpted information in the Contract Documents and
 the requirements of applicable codes and standards, provide the better quality or greater
 quantity of Work which, at a minimum, complies with the requirements of the applicable
 codes and standards.
 - Advise Architect immediately upon becoming aware of requirements of the Work which are not consistent with the requirements of the excerpted information.
 - Attribution is acknowledged for information obtained and included herein verbatim from other source or sources.
 - 5. Regulant has taken into consideration and used certain excerpted information from other sources which are applicable to the Contract Documents, and the Regulant indicates by its seal that it is assuming responsibility for its services in use and application of the excerpted information to the requirements of Work, but not for the excerpted information itself which was prepared by others. Regulant does not indicate by its seal that it is responsible for use or application of other information in such source or sources which was not included herein.

1.04 OWNER OCCUPANCY

- A. Owner intends to continue to occupy adjacent portions of the existing building during the entire construction period.
- B. Owner intends to occupy the Project upon Substantial Completion.
- C. Cooperate with Owner to minimize conflict and to facilitate Owner's operations.

Summary 011000 - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- D. Schedule the Work to accommodate Owner occupancy.
 - Maintain routes of egress and life safety systems for Owner and occupants at all times.

1.05 CONTRACTOR USE OF SITE AND PREMISES

- A. Construction Operations: Limited to areas noted on Drawings.
 - 1. Locate and conduct construction activities in ways that will limit disturbance to site.
- B. Provide access to and from site as required by law and by Owner:
 - Emergency Building Exits During Construction: Keep all exits required by code open during construction period; provide temporary exit signs if exit routes are temporarily altered.
 - 2. Do not obstruct roadways, sidewalks, or other public ways without permit.
- C. Existing building spaces may not be used for storage.
- D. Existing building shall be maintained weathertight. Do not modify elements of the existing building except as indicated on the Construction Documents. Repair damage to the existing building due to construction activity.
- E. Time Restrictions:
 - Comply with local regulations for hours of work, noise ordinances, and similar requirements.
 - Limit conduct of especially noisy, malodorous, and dusty work to the hours of 7 AM to 5 PM.
- F. Utility Outages and Shutdown:
 - 1. Limit disruption of utility services to hours the building is unoccupied.
 - 2. Do not disrupt or shut down life safety systems, including but not limited to fire sprinklers and fire alarm system, without 7 days notice to Owner and authorities having jurisdiction.
 - 3. Prevent accidental disruption of utility services to other facilities.
- G. Controlled Substances: The use of alcohol and drugs is not permitted on the Project site. Provide a designated outdoor smoking area for construction personnel that is at least 30 feet away from the building.

1.06 SPECIFICATION SECTIONS APPLICABLE TO ALL WORK

A. The provisions of the Owner/Contractor agreement, General Conditions of the Contract, Supplementary Conditions (if any), and all Division 01 sections shall apply to all sections of the Project Manual.

1.07 SECURITY PROVISIONS

- A. Background Check: The Owner requires that a background check be performed on all personnel working on the site. Comply with Owner's requirements for screening service to be used. Maintain a list of all accredited persons, submit a copy to Owner on request.
- B. Identification Badges: Provide identification badges to each person authorized to enter premises. Badge shall include personal photograph, name, employer, expiration date, and an assigned number. Have personnel return badges to Contractor after completion of their portion of the Work.

Summary 011000 - 2

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION 011000

Summary 011000 - 3

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 012000 PRICE AND PAYMENT PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Procedures for preparation and submittal of applications for progress payments.

1.02 SCHEDULE OF VALUES

- A. Use Schedule of Values Form: AIA G703, unless otherwise agreed to by Owner in writing.
- B. Forms filled out by hand will not be accepted.
- C. Format: Utilize the Table of Contents of this Project Manual. Identify each line item with number and title of the specification section. Identify site mobilization.
- D. Include in each line item, the amount of Allowances specified in this section. For unit cost Allowances, identify quantities taken from Contract Documents multiplied by the unit cost to achieve the total for the item.
- E. Include separately from each line item, a direct proportional amount of Contractor's overhead and profit.
- F. Revise schedule to list approved Change Orders, with each Application For Payment.
 - 1. When a Change Order includes multiple PCOs, break down the total Change Order to include each PCO as an individual line item.

1.03 APPLICATIONS FOR PROGRESS PAYMENTS

- A. Payment Period: Submit at intervals stipulated in the Agreement.
- B. Use Form AIA G702 and Form AIA G703.
- C. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit sample to Architect for approval.
- D. Forms filled out by hand will not be accepted.
- E. For each item, provide a column for listing each of the following:
 - 1. Item Number.
 - Description of work.
 - 3. Scheduled Values.
 - 4. Previous Applications.
 - 5. Work in Place and Stored Materials under this Application.
 - 6. Authorized Change Orders.
 - 7. Total Completed and Stored to Date of Application.
 - 8. Balance to Finish.
 - 9. Retainage.
- F. Execute certification by signature of authorized officer.
- G. Use data from approved Schedule of Values. Provide dollar value in each column for each line item for portion of work performed and for stored products.
- H. List each authorized Change Order as a separate line item, listing Change Order number and dollar amount as for an original item of work.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- When a Change Order includes multiple PCOs, break down the total Change Order to include each PCO as an individual line item.
- I. Submit one electronic and three hard-copies of each Application for Payment.
- J. Include the following with the application:
 - 1. Transmittal letter as specified for submittals in Section 013000.
 - 2. Construction progress schedule, revised and current as specified in Section 013000.
 - 3. Partial release of liens from major subcontractors and vendors.
 - 4. Affidavits attesting to off-site stored products.

1.04 MODIFICATION PROCEDURES

- A. For minor changes not involving an adjustment to the Contract Sum or Contract Time, Architect will issue instructions directly to Contractor on AIA Document G710 "Architect's Supplemental Instructions."
- B. For changes for which advance pricing is desired, Architect will issue a document that includes a detailed description of a proposed change with supplementary or revised drawings and specifications, a change in Contract Time for executing the change with a stipulation of any overtime work required and the period of time during which the requested price will be considered valid. Contractor shall prepare and submit a fixed price quotation within 14 days, unless otherwise indicated in Proposal Request.
- C. Contractor may propose a change by submitting a request for change to Architect, describing the proposed change and its full effect on the work, with a statement describing the reason for the change, and the effect on the Contract Sum and Contract Time with full documentation.
- D. For other required changes, Architect will issue a Construction Change Directive, on AIA Document G714, signed by Owner instructing Contractor to proceed with the change, for subsequent inclusion in a Change Order.
 - The document will describe the required changes and will designate method of determining any change in Contract Sum or Contract Time.
 - 2. Promptly execute the change.
- E. Computation of Change in Contract Amount: As specified in the Agreement and Conditions of the Contract.
 - 1. For change requested by Architect for work falling under a fixed price contract, the amount will be based on Contractor's price quotation.
 - 2. For change requested by Contractor, the amount will be based on the Contractor's request for a Change Order as approved by Architect.
 - 3. For pre-determined unit prices and quantities, the amount will based on the fixed unit prices.
- F. Substantiation of Costs: Provide full information required for evaluation.
 - Provide the following data:
 - a. Quantities of products, labor, and equipment.
 - b. Taxes, insurance, and bonds.
 - c. Overhead and profit.
 - d. Justification for any change in Contract Time.
 - e. Credit for deletions from Contract, similarly documented.
 - 2. Support each claim for additional costs with additional information:
 - a. Origin and date of claim.
 - b. Dates and times work was performed, and by whom.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- c. Time records and wage rates paid.
- d. Invoices and receipts for products, equipment, and subcontracts, similarly documented.
- G. Execution of Change Orders: Architect will issue Change Orders on AIA Document G701 for signatures of parties as provided in the Conditions of the Contract.
- H. After execution of Change Order, promptly revise Schedule of Values and Application for Payment forms to record each authorized Change Order as a separate line item and adjust the Contract Sum.
- Promptly revise progress schedules to reflect any change in Contract Time, revise subschedules to adjust times for other items of work affected by the change, and resubmit.

1.05 APPLICATION FOR FINAL PAYMENT

- A. Prepare Application for Final Payment as specified for progress payments, identifying total adjusted Contract Sum, previous payments, and sum remaining due.
- B. Application for Final Payment will not be considered until the following have been accomplished:
 - 1. All closeout procedures specified in Section 017000.
- C. Provide evidence and supporting data for the following, as attachments to the Application for Final Payment:
 - 1. AIA G706, "Contractor's Affidavit of Payment of Debts and Claims."
 - 2. AIA G707, "Consent of Surety to Final Payment."
 - 3. Settlement of all debts and claims, including liquidated damages, taxes, and fees.
 - 4. Utility meter readings, fuel levels, and similar measurements, as of the date of turn over to the Owner.
 - 5. Certificates for insured products.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION 012000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 012500 SUBSTITUTION PROCEDURES

PART 1 GENERAL

1.01 DEFINITIONS

- A. Substitutions: Changes from Contract Documents requirements proposed by Contractor to materials, products, assemblies, and equipment.
 - 1. Substitutions for Cause: Proposed due to changed Project circumstances beyond Contractor's control, such as unavailability, regulatory changes, or unobtainable warranty terms.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 GENERAL REQUIREMENTS

- A. A Substitution Request for products, assemblies, materials, and equipment constitutes a representation that the submitter:
 - 1. Has investigated proposed product and determined that it meets or exceeds the quality level of the specified product, equipment, assembly, or system.
 - 2. Agrees to provide the same warranty for the substitution as for the specified product.
 - 3. Agrees to provide same or equivalent maintenance service and source of replacement parts, as applicable.
 - 4. Agrees to coordinate installation and make changes to other work that may be required for the work to be complete, with no additional cost to Owner.
 - 5. Waives claims for additional costs or time extension that may subsequently become apparent.
 - 6. Agrees to reimburse Owner and Architect for review or redesign services associated with re-approval by authorities.
- B. Document each request with complete data substantiating compliance of proposed substitution with Contract Documents. Burden of proof is on proposer.
 - 1. Note explicitly any non-compliant characteristics.
- C. Content: Include information necessary for tracking the status of each Substitution Request, and information necessary to provide an actionable response.
 - A copy of the Substitution Request Form that shall be used is included at the end of this Section for informational purposes. Request a Word or editable PDF version of the form from the Architect and complete the form digitally; do not complete the form by hand.
 - 2. Contractor's Substitution Request documentation must include the following:
 - Substitution Request Information:
 - 1) Indication of whether the substitution is for cause or convenience.
 - 2) Issue date.
 - 3) Reference to particular Contract Document(s) specification section number, title, and article/paragraph(s).
 - 4) Description of Substitution.
 - 5) Reason why the specified item cannot be provided.
 - 6) Description of how proposed substitution affects other parts of work.

Substitution Procedures 012500 - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- b. Attached Comparative Data: Provide point-by-point, side-by-side comparison addressing essential attributes specified, as appropriate and relevant for the item:
 - 1) Physical characteristics.
 - 2) In-service performance.
 - Expected durability.
 - 4) Visual effect.
 - 5) Sustainable design features.
 - 6) Warranties.
 - 7) Other salient features and requirements.
 - 8) Include, as appropriate or requested, the following types of documentation:
 - (a) Product Data:
 - (b) Samples.
 - (c) Certificates, test, reports or similar qualification data.
 - (d) Drawings, when required to show impact on adjacent construction elements.
- c. Impact of Substitution: Provide data indicating cost savings to Owner and change in Contract Time due to accepting substitution.
- D. Limit each request to a single proposed substitution item.
 - 1. Submit an electronic document, combining the request form with supporting data into single document.

3.02 SUBSTITUTION PROCEDURES DURING CONSTRUCTION

- A. Architect will consider requests for substitutions for convenience only within 30 days after date of Agreement.
 - 1. Substitutions for convenience submitted after this time period may or may not be considered, at the Architect's discretion.
- B. Submit request for Substitution for Cause immediately upon discovery of need for substitution, but not later than 14 days prior to time required for review and approval by Architect, in order to stay on approved project schedule.
- C. Substitutions will not be considered under one or more of the following circumstances:
 - 1. When they are indicated or implied on shop drawing or product data submittals, without having received prior approval.
 - 2. Without a separate written request.

3.03 RESOLUTION

- A. Architect may request additional information and documentation prior to rendering a decision. Provide this data in an expeditious manner.
- B. Architect will notify Contractor in writing of decision to accept or reject request.

3.04 ACCEPTANCE

A. Accepted substitutions change the work of the Project. They will be documented and incorporated into work of the project by Change Order, Construction Change Directive, Architectural Supplementary Instructions, or similar instruments provided for in the Conditions of the Contract.

Substitution Procedures 012500 - 2

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.05 CLOSEOUT ACTIVITIES

A. See Section 017800 - Closeout Submittals, for closeout submittals.

END OF SECTION 012500

Substitution Procedures 012500 - 3



Substitution Request Form – Prior to Receipt of Bids

General Information				
Project Name	Mayo High School - Toilet Renovation			
A/E Project Number	624003			
Specifie	ed Product/Iter	n Information		
Specification Title				
Section				
Page				
Article / Paragraph				
Description				
Propos	ed Substitution	n Information		
Proposed Substitution				
Reason for not providing specified product/item				
Comparative Data	Attach a point-by-point comparative data list. Include all differences between the proposed substitution and the specified product/item. If not provided, this Request will be rejected.			
Manufacturer				
Manufacturer Address				
Manufacturer Phone				
Manufacturer Representative Email address				
Trade / Model Name				
Model Number				
Installer (if known)				
Installer Address				
Installer Phone				
History	New product	2-5 years	5-10 yrs	10 yrs or longer
Proposed substitution affects other parts of the Work	☐ Yes		☐ No	
If yes, explain				
Proposed Substitution Similar Installation				
Have you used this product/item on any other projects	☐ Yes		☐ No	
Project				
Project Address				
Architect/Engineer				
A/E Phone				

MOSELEYARCHITECTS

Owner					
Owner Phone					
Date installed					
At	tached Su	pporting l	Data		
☐ Drawings ☐ Product Data/Specs ☐ Samples ☐ Tests ☐ Reports ☐					
Entity submitting this Su	bstitution	Request o	ertifies all	of the following:	
 Proposed substitution has been fully investigated and determined to be equivalent or superior in all respects to the specified product, except as may otherwise be specifically and clearly indicated herein. If applicable, proposed substitution shall not adversely affect LEED requirements nor shall it prevent achieving the relative number of applicable LEED point[s] the specified product would have received. Proposed substitution's function, appearance, and quality are equal or superior in all respects to the specified product, except as may otherwise be specifically and clearly indicated herein. Same or superior warranty and/or guarantees shall be furnished for proposed substitution as is required for the specified product/item. Same maintenance service and source replacement parts, as applicable, are available; including local availability. Proposed substitution shall have no adverse effect on other trades. Proposed substitution shall not affect dimensions and functional clearances. Coordination, installation, and changes to the Work as necessary for the accepted proposed substitution shall 					
be complete in all respects.	Entity's I	nformatio	n		
Submitted by					
Signed By	Signed By				
Date					
Email address of Signee above					
Company Name					
Address					
Phone					
Architect	/ Engine	er Review	and Action		
If this Substitution request is acceptable, it shall be included in an Addendum. If the proposed substitution is not included in an Addendum, then the proposed substitution was rejected; was not submitted in accordance with the Bidding/Procurement Documents; and/or this Form was not complete. This Form shall be completely filled in to be considered for acceptance.					

responsibility of the submitting entity and the Contractor (if not the submitting entity).

END OF SUBSTITUTION REQUEST FORM

Acceptance of this Substitution request is an acceptance of the manufacturer and product/item only for general conformance with the design concept reflected in the Bidding/Procurement Documents. The A/E has made no attempt to verify specific performance data, or to check details of the proposed substitution as to special features, capacities, physical dimensions, or code and/or regulatory compliance – all of which remain the

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 013000 ADMINISTRATIVE REQUIREMENTS

PART 1 GENERAL

1.01 RELATED REQUIREMENTS

A. Section 016000 - Product Requirements: General product requirements.

1.02 GENERAL ADMINISTRATIVE REQUIREMENTS

- A. Comply with requirements of Section 017000 Execution and Closeout Requirements for coordination of execution of administrative tasks with timing of construction activities.
- B. Electronic File Distribution: Upon request, Contractor may be provided electronic files for use in coordination of the Work and preparation of submittals. Contractor shall submit a signed Request Form for Electronic Files, provided by the Architect.
 - 1. Electronic files do not contain all of the information of the Bid Documents or Contract Documents for construction of the Project, and the Architect shall not be responsible for differences between electronic files, Bid Documents, and Contract Documents.

1.03 SUBMITTALS

- A. General Contractor Personnel: Within 15 days after award of Contract, provide a summary of General Contractor's on site personnel. Identify each individual, beginning with project superintendent. List project responsibilities, cell phone number, and email address.
- B. Subcontractors: Within 15 days after award of Contract, provide a summary of all companies and individuals engaged as subcontractors for any part of the Project. Include a contact name, company address, phone number, and email address, and identify what part of the Work shall be completed by each subcontractor.
- C. Coordination Drawings: Submit completed Coordination Drawings for Architect's information.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 ELECTRONIC DOCUMENT SUBMITTAL SERVICE

- A. All documents transmitted for purposes of administration of the contract are to be in electronic (PDF, MS Word, or MS Excel) format, as appropriate to the document, and transmitted via an Internet-based submittal service that receives, logs and stores documents, provides electronic stamping and signatures, and notifies addressees via email.
 - Besides submittals for review, information, and closeout, this procedure applies to Requests for Interpretation (RFIs), progress documentation, contract modification documents (e.g. supplementary instructions, change proposals, change orders), applications for payment, field reports and meeting minutes, Contractor's correction punchlist, and any other document any participant wishes to make part of the project record.
 - 2. It is Contractor's responsibility to submit documents in allowable format.
 - Subcontractors, suppliers, and Architect's consultants will be permitted to use the service at no extra charge.
 - Paper document transmittals will not be reviewed unless previously approved; emailed electronic documents will not be reviewed.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 5. All other specified submittal and document transmission procedures apply, except that electronic document requirements do not apply to samples or color selection charts.
- B. Submittal Service: Coordinate method for exchanging files no later than the Preconstruction Meeting. The Architect's "Newforma InfoExchange" website and procedures can be used at no charge. If the Contractor chooses to use a different platform and methodology:
 - 1. The Architect may reject the methodology or platform proposed and:
 - a. use the Architect's Newforma InfoExchange website, or
 - b. the project team will revert to traditional hard-copy exchange;
 - 2. or the Contractor shall bear the cost of software, licensing, training, etc., for the project team to participate.
- C. Project Closeout: Architect will determine when to terminate the service for the project and is responsible for obtaining archive/record copies of files for Owner. If the Project Team uses an alternate platform preferred by the Contractor, the Contractor shall be responsible for distributing archive/record copies of files to Owner and Architect.

3.02 PRECONSTRUCTION MEETING

- A. Architect will schedule a meeting after Notice of Award.
- B. Attendance Required:
 - 1. Owner.
 - 2. Architect.
 - Contractor.
 - 4. Major subcontractors, consultants, and others as necessary and appropriate.
- C. Agenda:
 - 1. Execution of Owner-Contractor Agreement.
 - 2. Submission of executed bonds and insurance certificates.
 - Distribution of Contract Documents.
 - Submission of list of subcontractors, list of products, schedule of values, and progress schedule.
 - Designation of personnel representing the parties to Contract and Architect.
 - 6. Procedures and processing of field decisions, submittals, substitutions, applications for payments, proposal request, Change Orders, and Contract closeout procedures.
 - 7. Scheduling.
 - 8. Site mobilization and utilization.
 - 9. Other project-specific items on pre-distributed agenda.
- D. Architect shall record minutes and distribute digital copies to Owner, Contractor, and other attendees. Contractor shall be responsible for distribution to subcontractors and other personnel affected by decisions made.

3.03 INDOOR AIR QUALITY (IAQ) MANAGEMENT PLAN DEVELOPMENT SESSION

- A. Architect will schedule a meeting after Notice of Award.
- B. Attendance Required:
 - 1. Owner.
 - Architect.
 - 3. Mechanical engineer.
 - 4. Contractor.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- HVAC subcontractor.
- 6. Other major subcontractors, consultants, and others as necessary and appropriate.

C. Agenda:

- 1. Protection of Materials: Discussion of how and where materials that could impact IAQ will be stored, including but not limited to, the following:
 - a. Insulation.
 - b. Gypsum board.
 - c. Flooring materials.
 - d. Ceiling panels.
 - e. Furnishings.
 - f. Odorous chemicals.
- 2. Protection of HVAC: Discussion of how HVAC equipment will be stored installed, and operated during construction.
- 3. Pathway Interruption: Discussion of how airflow between construction zones will be limited to prevent the spreading of pollutants from one part of the building to another.
- 4. Housekeeping: Discussion of how the building will be kept clean and dry.
- Materials Installation Scheduling: Discussion of what wet (odor emitting) materials will be used on the project, in order to schedule their installation before fuzzy (odor absorbing) materials.

3.04 PREINSTALLATION MEETINGS

- A. When required in individual specification sections, convene a preinstallation meeting at the site prior to commencing work of the section. Do not allow installation of affected work to proceed until preinstallation meeting can be held.
 - 1. Include all preinstallation meetings on the Project Schedule.
- B. Require attendance of parties directly affecting, or affected by, work of the specific section.
- C. Notify Architect and Owner in advance of meeting date.
- D. Prepare agenda and preside at meeting:
 - 1. Review conditions of examination, preparation and installation procedures.
 - 2. Review coordination with related work.
- E. Record minutes and distribute copies within two days after meeting to participants, with copies to Architect, Owner, participants, and those affected by decisions made.

3.05 PROGRESS MEETINGS

- A. Architect will make arrangements for meetings, prepare agenda with copies for participants, preside at meetings.
- B. Attendance Required:
 - 1. Owner.
 - 2. Architect.
 - 3. Contractor's superintendent.
 - Other subcontractors or consultants as required for the specific parts of the Work to be discussed.

C. Agenda:

- 1. Review minutes of previous meetings.
- Review of work progress.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 3. Field observations, problems, and decisions.
- 4. Identification of problems that impede, or will impede, planned progress.
- 5. Review of submittals schedule and status of submittals.
- 6. Review of RFIs log and status of responses.
- 7. Maintenance of progress schedule.
- 8. Corrective measures to regain projected schedules.
- 9. Planned progress during succeeding work period.
- 10. Maintenance of quality and work standards.
- 11. Effect of proposed changes on progress schedule and coordination.
- 12. Other business relating to the work.
- D. Architect shall record minutes and distribute copies to the Owner, Contractor, and other consultants, Owner's representatives, or other third party attendees. The Contractor shall be responsible for distributing to any affected subcontractors and other personnel.

3.06 CLOSEOUT MEETING

- A. Schedule and administer closeout meeting no later than 30 days before the scheduled Date of Substantial Completion.
- B. Make arrangements for the meeting, prepare agenda with copies for participants, and preside at the meeting.
- C. Attendance Required:
 - 1. Owner.
 - 2. Architect.
 - 3. Contractor's superintendent.
 - 4. Major subcontractors.
 - 5. Other subcontractors or consultants as required.

D. Agenda:

- Review closeout requirements and procedures in Division 1 Section "Execution and Closeout Requirements."
- 2. Review startup, testing, and adjusting of all systems.
- 3. Coordination of inspections by local authorities having jurisdiction and third party Special Inspectors as required to obtain Certificate of Occupancy.
- 4. Coordination of Owner's occupancy and changeover of utilities, insurance, and building keying/lock system.
- 5. Procedures for Contractor's Correction Punch List, Architect's Substantial Completion inspection, and Final Correction Punch List.
- Delivery, turnover, and storage of maintenance materials, attic stock, special tools, and other non-installed materials.
- 7. Coordination of closeout documentation, including demonstration and training materials and videos, as built/record documents, operation and maintenance binders, and warranty binders.
- 8. Removal of temporary facilities, construction equipment, and tools.
- 9. Final cleaning, touchup, restoration, and preventive maintenance.
- 10. Coordination of final Applications for Payment.
- E. Record minutes and distribute copies within two days after meeting to participants, with copies to Architect, Owner, participants, and those affected by decisions made.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.07 DAILY CONSTRUCTION REPORTS

- A. Include only factual information. Do not include personal remarks or opinions regarding operations and/or personnel.
- B. Prepare a daily construction report recording the following information concerning events at Project site and project progress:
 - 1. Date.
 - 2. High and low temperatures, and general weather conditions.
 - 3. List of subcontractors at Project site.
 - 4. Approximate count of personnel at Project site.
 - 5. Major equipment at Project site.
 - 6. Material deliveries.
 - 7. Safety, environmental, or industrial relations incidents.
 - 8. Meetings and significant decisions.
 - 9. Unusual events (submit a separate special report).
 - 10. Stoppages, delays, shortages, and losses. Include comparison between scheduled work activities (in Contractor's most recently updated and published schedule) and actual activities. Explain differences, if any. Note days or periods when no work was in progress and explain the reasons why.
 - 11. Directives and requests of Authority(s) Having Jurisdiction (AHJ).
 - 12. Testing and/or inspections performed.
 - 13. Signature of Contractor's authorized representative.

3.08 COORDINATION DRAWINGS AND COORDINATION CONFERENCE

- A. Coordination Drawings: The Contractor shall prepare coordination drawings of all spaces where utilities, systems, and other components converge or intersect and efficient installation is required to accommodate all components.
 - 1. Prepare coordination drawings of the following spaces, at minimum. Supplement with additional spaces as required by project-specific conditions.
 - a. Above ceilings.
 - b. Vertical chases, shafts, and wall cavities.
 - c. Mechanical and electrical rooms, fire pump room, and other major utility spaces.
 - Provide accurate overall dimensions of components (for example, outside diameters of pipe and conduit, or overall ductwork dimensions including insulation and enclosure thickness).
 - 3. Include accessory components of systems that could cause potential conflicts, such as bracing, slotted channel framing, hangers, and other supports, valve handles, flanges, fittings, cable/wire management trays, and other similar components.
 - 4. Include sequence of installation of all components, materials, and systems.
 - Include means of access to each component, material, or system, for maintenance and repairs.
 - 6. Provide additional coordination drawings as required by individual specification sections.
 - 7. Prepare Coordination Drawings using project-specific information. Do not use photocopies or reproductions of Contract Documents, and do not use standard details or data from manufacturers, suppliers, or other outside parties.
 - 8. Drawing Files: The Contractor may develop coordination drawings using 2D CAD software or with 3D BIM software with clash-detection functionality.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- a. The Architect will furnish original 3D BIM model or 2D DWG files for Contractor's use upon receipt of Architect's "Request Form for Electronic Files". A copy of this form shall be provided to the Contractor upon request.
 - The Architect makes no guarantee to the accuracy of components in electronic files. The Contractor shall coordinate electronic data with the Contract Documents in order to provide final Coordination Drawings.
 - 2) If using 2D files, the Contractor shall prepare drawings in multiple views (for example, RCP and section) to fully represent 3D space, for example plenum heights, wall assembly thicknesses, etc.
- Submittal: Submit Coordination Drawings as a "Submittal for Information." Architect will
 not approve Coordination Drawings, but will keep on file for use in subsequent
 coordination and conflict resolution.
- B. Coordination Conference: Schedule and conduct a Coordination Conference prior to beginning construction or rough-in of affected work. Require attendance by all affected trades and installers.
 - 1. Identify the Coordination Conference as a "milestone" date on the Construction Progress Schedule.
 - 2. Advise the Architect of all potential conflicts identified in the Coordination Drawings and at the Coordination Conference.
 - 3. Do not proceed with construction or installation of components, materials, or systems until potential conflicts have been resolved and affected parties have agreed to a remedy.
 - 4. Remedies to address conflicts not identified in the Coordination Drawings, at the Coordination Conference, or otherwise addressed prior to construction or installation of affected components, materials, and systems, or discovery of a non-workable situation not identified or addressed, will not be considered as a basis for delay, time extension, or additional cost to the Contract.

3.09 REQUESTS FOR INFORMATION (RFI)

- A. Definition: A request seeking one of the following:
 - An interpretation, amplification, or clarification of some requirement of Contract
 Documents arising from inability to determine from them the exact material, process, or
 system to be installed; or when the elements of construction are required to occupy the
 same space (interference); or when an item of work is described differently at more than
 one place in Contract Documents.
 - 2. A resolution to an issue which has arisen due to field conditions and affects design intent.
- B. Preparation: Prepare an RFI immediately upon discovery of a need for interpretation of Contract Documents. Failure to submit a RFI in a timely manner is not a legitimate cause for claiming additional costs or delays in execution of the work.
 - 1. Prepare a separate RFI for each specific item.
 - Review, coordinate, and comment on requests originating with subcontractors and/or materials suppliers.
 - b. Do not forward requests which solely require internal coordination between subcontractors.
 - 2. Prepare in a format and with content acceptable to Owner.
 - 3. Prepare using software provided by the Electronic Document Submittal Service.
 - 4. Combine RFI and its attachments into a single electronic file. PDF format is preferred.
- C. Reason for the RFI: Prior to initiation of an RFI, carefully study all Contract Documents to confirm that information sufficient for their interpretation is not included.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 1. Include in each request Contractor's signature attesting to good faith effort to determine from Contract Documents information requiring interpretation.
- 2. Unacceptable Uses for RFIs: Do not use RFIs to request the following:
 - a. Approval of submittals (use procedures specified elsewhere in this section).
 - b. Approval of substitutions (see Section 016000 Product Requirements)
 - c. Changes that entail change in Contract Time and Contract Sum (comply with provisions of the Conditions of the Contract).
 - d. Different methods of performing work than those indicated in the Contract Drawings and Specifications (comply with provisions of the Conditions of the Contract).
- 3. Improper RFIs: Requests not prepared in compliance with requirements of this section, and/or missing key information required to render an actionable response. They will be returned without a response.
- 4. Frivolous RFIs: Requests regarding information that is clearly indicated on, or reasonably inferable from, Contract Documents, with no additional input required to clarify the question. They will be returned without a response.
 - a. The Owner reserves the right to assess the Contractor for the costs (on time-and-materials basis) incurred by the Architect, and any of its consultants, due to processing of such RFIs.
- D. Content: Include identifiers necessary for tracking the status of each RFI, and information necessary to provide an actionable response.
 - Official Project name and number, and any additional required identifiers established in Contract Documents.
 - 2. Owner's, Architect's, and Contractor's names.
 - 3. Discrete and consecutive RFI number, and descriptive subject/title.
 - 4. Issue date and requested reply date.
 - 5. Reference to particular Contract Document(s) requiring additional information/interpretation. Identify pertinent drawing and detail number and/or specification section number, title, and paragraph(s).
 - 6. Annotations: Field dimensions and/or description of conditions which have engendered the request.
 - 7. Contractor's suggested resolution: A written and/or a graphic solution, to scale, is required in cases where clarification of coordination issues is involved, for example; routing, clearances, and/or specific locations of work shown diagrammatically in Contract Documents. If applicable, state the likely impact of the suggested resolution on Contract Time or the Contract Sum.
- E. Attachments: Include sketches, coordination drawings, descriptions, photos, submittals, and other information necessary to substantiate the reason for the request.
- F. RFI Log: Prepare and maintain a tabular log of RFIs for the duration of the project.
 - 1. Indicate current status of every RFI. Update log promptly and on a regular basis.
 - 2. Note dates of when each request is made, and when a response is received.
- G. Review Time: Architect will respond and return RFIs to Contractor within seven calendar days of receipt. For the purpose of establishing the start of the mandated response period, RFIs received after 12:00 noon will be considered as having been received on the following regular working day.
 - 1. Response period may be shortened or lengthened for specific items, subject to mutual agreement.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- H. Responses: Content of answered RFIs will not constitute in any manner a directive or authorization to perform extra work or delay the project. If in Contractor's belief it is likely to lead to a change to Contract Sum or Contract Time, promptly issue a notice to this effect, and follow up with an appropriate Change Order request to Owner.
 - 1. When the Architect provides a response to an RFI, that RFI shall be closed. If there is additional information required, or a question about the response itself, then another RFI with a new number shall be generated by the Contractor. At no time shall an RFI be "reopened" or remain open after the Architect has formally responded.
 - 2. Do not extend applicability of a response to specific item to encompass other similar conditions, unless specifically so noted in the response.
 - Upon receipt of a response, promptly review and distribute it to all affected parties, and update the RFI Log.
 - 4. Notify Architect within seven calendar days if an additional or corrected response is required by submitting an amended version of the original RFI, identified as specified above.

3.10 SUBMITTAL SCHEDULE

- A. Submit to Architect for review a schedule for submittals in tabular format.
 - 1. Coordinate with Contractor's construction schedule and schedule of values.
 - Format schedule to allow tracking of status of submittals throughout duration of construction.
 - 3. Arrange information to include scheduled date for initial submittal, specification number and title, submittal category (for review or for information), description of item of work covered, and role and name of subcontractor.
 - 4. Account for time required for preparation, review, manufacturing, fabrication and delivery when establishing submittal delivery and review deadline dates.
 - a. For assemblies, equipment, systems comprised of multiple components and/or requiring detailed coordination with other work, allow for additional time to make corrections or revisions to initial submittals, and time for their review.
 - b. Account for a reasonable duration of time to allow for final color selections, approvals, and preparation of final finish schedules (one finish schedule for interior color selections, and one for exterior color selections). This period shall begin upon receipt of all submittals requiring color selection.

3.11 SUBMITTALS FOR REVIEW

- A. When the following are specified in individual sections, submit them for review:
 - 1. Product data.
 - 2. Design data.
 - 3. Shop drawings.
 - 4. Samples for selection.
 - 5. Samples for verification.
- B. Submit to Architect for review for the limited purpose of checking for compliance with information given and the design concept expressed in Contract Documents.
- C. Samples will be reviewed for aesthetic, color, or finish selection.
- D. Color Selection: In individual specification sections, specific items are identified which require color/finish selections to be made by the Architect from color chart or sample submittals. The Submittal Schedule, prepared according to "Submittal Schedule" paragraph above, shall identify these required color/finish submittals.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- Submittals requiring color selection must be submitted by Contractor and approved by Architect for conformance with Contract Documents prior to the start of the color selection process. When the submittals have been approved for conformance with Contract Documents, the process for color selection, presentation of color concepts, Owner approval, and Color Schedule preparation will begin.
- 2. Interior Color Selections: The Architect will make coordinated selections of colors/finishes for the building interior, present the resulting color concepts to the Owner for approval, and prepare the actual Interior Color Schedule for the Work.
- 3. Exterior Color Selections: The Architect will make coordinated selections of colors/finishes for the building exterior and prepare Exterior Color Schedule.
- E. After review, provide copies and distribute in accordance with SUBMITTAL PROCEDURES article below.

3.12 SUBMITTALS FOR INFORMATION

- A. When the following are specified in individual sections, submit them for information:
 - 1. Certificates.
 - 2. Test reports.
 - 3. Inspection reports.
 - 4. Manufacturer's instructions.
 - 5. Manufacturer's field reports.
 - 6. Other types indicated.
- B. Submit for Architect's knowledge as contract administrator or for Owner.

3.13 SUBMITTALS FOR PROJECT CLOSEOUT

- A. Submit Correction Punch List for Substantial Completion.
- B. Submit Final Correction Punch List for Substantial Completion.
- C. When the following are specified in individual sections, submit them at project closeout in compliance with requirements of Section 017800 Closeout Submittals:
 - 1. Project record documents.
 - 2. Operation and maintenance data.
 - 3. Warranties.
 - 4. Bonds.
 - 5. Other types as indicated.

3.14 NUMBER OF COPIES OF SUBMITTALS

- A. Electronic Documents: Submit one electronic copy in PDF format; an electronically-marked up file will be returned. Create PDFs at native size and right-side up; illegible files will be rejected.
- B. Selection Samples: Submit one set of manufacturer's charts indicating full range of available colors, textures, patterns, and other aesthetic qualities.
- C. Verification Samples: Submit three sets of physical samples. Two sets will be retained by Architect, the third will be returned to the Contractor. Maintain approved sample at the Project site for use in comparing to installed Work.
 - 1. Where a full-size assembly of multiple components is required as a sample (for example, railing section or full-size cabinet), only one sample is required for those items.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.15 SUBMITTAL PROCEDURES

- A. General Requirements:
 - Use a single transmittal for all submittals required by each individual specification section, unless otherwise indicated.
 - a. Verification samples and large shop drawing submittals may be submitted under separate cover when approved by Architect.
 - 2. Transmit using AIA G810 or other approved form.
 - 3. Sequentially identify each item. For revised submittals use original number and a sequential numerical suffix.
 - 4. Identify: Project; Contractor; subcontractor or supplier; pertinent drawing and detail number; and specification section number and article/paragraph, as appropriate on each copy.
 - 5. Apply Contractor's stamp, signed or initialed certifying that review, approval, verification of products required, field dimensions, adjacent construction work, and coordination of information is in accordance with the requirements of the work and Contract Documents.
 - a. Submittals from sources other than the Contractor, or without Contractor's stamp will not be acknowledged, reviewed, or returned.
 - 6. Deliver each submittal on date noted in submittal schedule, unless an earlier date has been agreed to by all affected parties, and is of the benefit to the project.
 - Upload submittals in electronic form to Electronic Document Submittal Service website.
 - 7. Schedule submittals to expedite the Project, and coordinate submission of related items.
 - Allow sufficient time for administrative processing, Architect's initial review, and potential resubmittals.
 - 1) Large submittals may require longer review durations. Large or multi-part submittals (such as structural steel or aluminum storefront and curtainwall) may be submitted by building area, building level, or otherwise subdivided "packages" with the approval of the Architect. Subdivided "packages" will be reviewed one at a time in the order received. If large submittals are submitted in their entirety as a single package, the Architect may elect to review and return portions of the submittal individually, and will coordinate the schedule for return of these partial reviews with the Contractor for sequencing in the Work.
 - b. Allow additional time for submittals requiring sequential reviews involving Architect's consultants, Owner, or another affected party.
 - c. Allow additional time for submittals requiring sequential reviews involving approval from authorities having jurisdiction (AHJ), in addition to Architect's approval.
 - d. No extensions to the project schedule shall be granted due to delays that can be attributed to submittal processing or failure to allow for sequential reviews or resubmittals.
 - 8. Identify variations from Contract Documents and product or system limitations that may be detrimental to successful performance of the completed work.
 - 9. When revised for resubmission, identify all changes made since previous submission.
 - 10. Distribute reviewed submittals. Instruct parties to promptly report inability to comply with requirements.
 - 11. Incomplete submittals may not be reviewed, unless they are partial submittals for distinct portion(s) of the work, and have received prior approval for their use.
 - 12. Submittals not requested will be recognized, and will be returned "Not Reviewed".
- B. Product Data Procedures:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 1. Submit only information required by individual specification sections.
- 2. Collect required information into a single submittal.
- 3. Submit concurrently with related shop drawing submittal.
- 4. Do not submit (Material) Safety Data Sheets for materials or products.

C. Shop Drawing Procedures:

- Prepare accurate, drawn-to-scale, original shop drawing documentation by interpreting Contract Documents and coordinating related work.
- 2. Do not reproduce Contract Documents to create shop drawings.
- 3. Generic, non-project-specific information submitted as shop drawings do not meet the requirements for shop drawings.

D. Samples Procedures:

- 1. Transmit related items together as single package.
- 2. Identify each item to allow review for applicability in relation to shop drawings showing installation locations.
- 3. Selection Samples: Provide color charts that accurately relay color, pattern, and texture information. Photographs or photocopies of color charts are unacceptable and subject to rejection.
- 4. Verification Samples: Provide physical samples of each color selected by Architect from Selection Samples. Verification samples shall be manufactured and prepared identically to the material that shall be used in the installed Work. Label each sample clearly with manufacturer, product name, and color, texture, and/or pattern name as applicable. Photographs of physical samples are unacceptable and subject to rejection.

3.16 SUBMITTAL REVIEW

- A. Submittals for Review: Architect will review each submittal, and approve, or take other appropriate action.
- B. Submittals for Information: Architect will acknowledge receipt, but will take no other action.
- C. Architect's actions will be reflected by marking each returned submittal using virtual stamp on electronic submittals.
 - 1. Notations may be made directly on submitted items and/or listed on appended Submittal Review cover sheet.
- D. Architect's actions on items submitted for review:
 - 1. Authorizing purchasing, fabrication, delivery, and installation:
 - a. "Approved as Noted":
 - Where review notations indicate revisions are necessary, submit corrected item, with review notations acknowledged and incorporated.
 - 2. Not Authorizing fabrication, delivery, and installation:
 - a. "Revise and Resubmit":
 - 1) Resubmit revised item, with review notations acknowledged and incorporated.
 - b. "Rejected/Resubmit":
 - New submittal required, with item complying with requirements of Contract Documents.
 - c. "Color Selection Required":
 - 1) Color selections for the entire project, or portion thereof, will be provided after receipt of all color charts and samples required for the Project.
 - d. "Not Submitted":

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- Additional submittal items are required that were not provided in the original submittal.
- E. Architect's actions on items submitted for information:
 - 1. Items for which no action was taken:
 - a. "Not Reviewed": To notify the Contractor that the submittal has been received for record only.

END OF SECTION 013000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 013216 CONSTRUCTION PROGRESS SCHEDULE

PART 1 GENERAL

1.01 SUBMITTALS

- A. Within 10 days after date of Agreement, submit preliminary schedule defining planned operations for the first 60 days of Work, with a general outline for remainder of Work.
- B. If preliminary schedule requires revision after review, submit revised schedule within 10 days.
- C. Within 20 days after review of preliminary schedule, submit draft of proposed complete schedule for review.
 - Include written certification that major contractors have reviewed and accepted proposed schedule.
- D. Within 10 days after joint review, submit complete schedule.
- E. Submit updated schedule with each Application for Payment.
- F. Submit in PDF format.

1.02 QUALITY ASSURANCE

A. Scheduler: Contractor's personnel or specialist Consultant specializing in CPM scheduling with experience in scheduling construction work of a complexity comparable to this Project, and having use of computer facilities capable of delivering a detailed graphic printout within 48 hours of request.

1.03 SCHEDULE FORMAT

A. Listings: In chronological order according to the start date for each activity. Identify each activity with the applicable specification section number.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PRELIMINARY SCHEDULE

A. Prepare preliminary schedule in the form of a horizontal bar chart.

3.02 CONTENT

- A. Show complete sequence of construction by activity, with dates for beginning and completion of each element of construction.
- B. Identify work of separate phases and other logically grouped activities.
- C. Identify all major milestone dates, including, but not limited to, Notice to Proceed and Substantial and Final Completion dates.
- D. Identify duration of each activity, in maximum 15 day intervals.
- E. Incorporate work restrictions indicated in Section 011000 Summary, if any.
- F. Show accumulated percentage of completion of each item, and total percentage of Work completed, as of the first day of each month.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- G. Provide separate schedule of submittal dates for shop drawings, product data, and samples, owner-furnished products, products identified under Allowances, and dates reviewed submittals will be required from Architect. Indicate decision dates for selection of finishes.
- H. Indicate procurement duration and delivery dates for long-lead time items.
- Coordinate submittal approval process with procurement and delivery requirements. Submittals
 requiring resubmission or revision for approval will not be allowed as a basis for schedule
 impacts.
- J. Indicate delivery dates for owner-furnished products and products identified under Allowances.
- K. Indicate the time period for color selection activity and approval by Owner and Architect, as required per Section 013000 - Administrative Requirements.
- L. Indicate date of changeover from temporary to permanent utilities.
- M. Provide a reasonable time period prior to the date of Substantial Completion for administrative activities and procedures.
- N. Provide legend for symbols and abbreviations used.

3.03 BAR CHARTS

- A. Include a separate bar for each major portion of Work or operation.
- B. Identify critical path activities.
- C. Identify the first work day of each week.

3.04 NETWORK ANALYSIS (CPM)

- A. Prepare network analysis diagrams and supporting mathematical analyses using the Critical Path Method.
- B. Illustrate order and interdependence of activities and sequence of work; how start of a given activity depends on completion of preceding activities, and how completion of the activity may restrain start of subsequent activities.
- C. Mathematical Analysis: Tabulate each activity of detailed network diagrams, using calendar dates, and identify for each activity:
 - Preceding and following event numbers.
 - 2. Activity description.
 - 3. Estimated duration of activity, in maximum 15 day intervals.
 - Earliest start date.
 - 5. Earliest finish date.
 - 6. Actual start date.
 - 7. Actual finish date.
 - Latest start date.
 - 9. Latest finish date.
 - 10. Total and free float; float time shall accrue to Owner and to Owner's benefit.
 - 11. Percentage of activity completed.
 - 12. Responsibility.
- D. Analysis Program: Capable of accepting revised completion dates, and recomputation of all dates and float.
- E. Required Reports: List activities in sorts or groups:
 - 1. By preceding work item or event number from lowest to highest.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 2. By amount of float, then in order of early start.
- 3. In order of latest allowable finish dates.
- 4. Listing of activities on the critical path.

3.05 REVIEW AND EVALUATION OF SCHEDULE

- A. Participate in joint review and evaluation of schedule with Architect at each submittal.
- B. Evaluate project status to determine work behind schedule and work ahead of schedule.
- C. After review, revise as necessary as result of review, and resubmit within 10 days.

3.06 UPDATING SCHEDULE

- A. Maintain schedules to record actual start and finish dates of completed activities.
- B. Indicate progress of each activity to date of revision, with projected completion date of each activity.
- C. Annotate diagrams to graphically depict current status of Work.
- D. Identify activities modified since previous submittal, major changes in Work, and other identifiable changes.
- E. Indicate changes required to maintain Date of Substantial Completion.
- F. Schedule revisions shall not modify any Contract Dates or the Contract Sum, unless specifically approved and documented via Change Order.
- G. Submit reports required to support recommended changes.
- H. Provide narrative report to define problem areas, anticipated delays, and impact on the schedule. Report corrective action taken or proposed and its effect.
- I. Recovery Schedule: If the Contractor is 14 or more days behind schedule, in the opinion of the Owner, the Contractor shall prepare a Recovery Schedule, incorporating a reasonable, mutually agreed upon length of time to return the Work to the approved Schedule. The Recovery Schedule shall be prepared to the same level of detail as the original construction progress schedule. Submit the recovery schedule for Owner review; do not proceed until the Owner has approved.
 - At the end of the recovery period, Owner shall reevaluate construction progress and determine if the Recovery Schedule has been successfully completed. If completed, Owner shall direct the Contractor to proceed with the latest approved Construction Schedule.
 - a. If the Contractor is still behind schedule at the end of the recovery period, the Owner shall direct the Contractor to provide additional schedule revisions to complete the recovery, or may at its option pursue other means of resolution as provided for by the Contract Documents.
 - Need for and preparation of a Recovery Plan shall not be the basis of additional cost to the Owner or extension of Project Schedule, unless the Contractor can demonstrate that the reason for being behind schedule is no fault of their own.

3.07 DISTRIBUTION OF SCHEDULE

A. Distribute copies of updated schedules to Contractor's project site file, to subcontractors, suppliers, Architect, Owner, and other concerned parties.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

B. Instruct recipients to promptly report, in writing, problems anticipated by projections indicated in schedules.

END OF SECTION 013216

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 014000 QUALITY REQUIREMENTS

PART 1 GENERAL

1.01 RELATED REQUIREMENTS

A. Section 014200 - Definitions and Reference Standards.

1.02 DEFINITIONS

- A. Contractor's Quality Control Plan: Contractor's management plan for executing the Contract for Construction.
- B. Contractor's Professional Design Services/Delegated Design: Design of some aspect or portion of the project by party other than the design professional of record. Provide these services as part of the Contract for Construction.
 - Design Services Types Required:
 - Construction-Related: Services Contractor needs to provide in order to carry out the Contractor's sole responsibilities for construction means, methods, techniques, sequences, and procedures.
 - b. Design-Related: Design services explicitly required to be performed by another design professional due to highly-technical and/or specialized nature of a portion of the project. Services primarily involve engineering analysis, calculations, and design, and are not intended to alter the aesthetic aspects of the design.
- C. Design Data: Design-related, signed and sealed drawings, calculations, specifications, certifications, shop drawings and other submittals provided by Contractor, and prepared directly by, or under direct supervision of, appropriately licensed design professional.

1.03 CONTRACTOR'S CONSTRUCTION-RELATED PROFESSIONAL DESIGN SERVICES

- A. Coordination: Contractor's professional design services are subject to requirements of project's Conditions for Construction Contract.
- B. Provide such engineering design services as may be necessary to plan and safely conduct certain construction operations, pertaining to, but not limited to the following:
 - 1. Temporary sheeting, shoring, or supports.
 - 2. Temporary scaffolding.
 - 3. Temporary bracing.
 - 4. Temporary falsework for support of spanning or arched structures.
 - 5. Temporary foundation underpinning.
 - 6. Temporary stairs or steps required for construction access only.
 - 7. Temporary hoist(s) and rigging.
 - 8. Investigation of soil conditions and design of temporary foundations to support construction equipment.
 - 9. Additional temporary controls as required.

1.04 CONTRACTOR'S DESIGN-RELATED PROFESSIONAL DESIGN SERVICES

- A. Coordination: Contractor's professional design services are subject to requirements of project's Conditions for Construction Contract.
- B. Base design on performance and/or design criteria indicated in individual specification sections.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 1. Submit a Request for Information to Architect if the criteria indicated are not sufficient to perform required design services.
- C. Scope of Design Services/Delegated Design: As required by individual specification sections.

1.05 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Designer's Qualification Statement: Submit for Architect's knowledge as contract administrator, or for Owner's information.
 - Include information for each individual professional responsible for producing, or supervising production of, design-related professional services provided by Contractor.
 - a. Full name.
 - b. Professional licensure information.
 - c. Statement addressing extent and depth of experience specifically relevant to design of items assigned to Contractor.
- C. Design Data: Submit for Architect's knowledge as contract administrator for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents, or for Owner's information.
 - 1. Include calculations that have been used to demonstrate compliance to performance and regulatory criteria provided, and to determine design solutions.
 - 2. Include required product data and shop drawings.
 - 3. Include a statement or certification attesting that design data complies with criteria indicated, such as building codes, loads, functional, and similar engineering requirements.
 - 4. Include signature and seal of design professional responsible for allocated design services on calculations and drawings.
- D. Test Reports: After each test/inspection, require testing agency to promptly distribute digital copy of report to Architect, Owner, Contractor, and others as required.
 - 1. Include:
 - a. Date issued.
 - b. Project title and number.
 - c. Name of inspector.
 - d. Date and time of sampling or inspection.
 - e. Identification of product and specifications section.
 - f. Location in the Project.
 - g. Type of test/inspection.
 - h. Date of test/inspection.
 - i. Results of test/inspection.
 - j. Compliance with Contract Documents.
 - k. When requested by Architect, provide interpretation of results.
- E. Certificates: When specified in individual specification sections, submit certification by the manufacturer and Contractor to Architect, in quantities specified for Product Data.
 - 1. Indicate material or product complies with or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
 - 2. Certificates may be recent or previous test results on material or product, but must be acceptable to Architect.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- F. Manufacturer's Instructions: When specified in individual specification sections, submit printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, for the Owner's information. Indicate special procedures, perimeter conditions requiring special attention, and special environmental criteria required for application or installation.
- G. Manufacturer's Field Reports:
 - 1. Submit report promptly to Architect for information.
 - Submit for information for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents.

1.06 QUALITY ASSURANCE

- A. Testing Agency Qualifications:
 - Prior to start of work, submit agency name, address, and telephone number, and names of full time registered Engineer and responsible officer.
 - Submit copy of report of laboratory facilities inspection made by NIST Construction Materials Reference Laboratory during most recent inspection, with memorandum of remedies of any deficiencies reported by the inspection.
 - Qualification Statement: Provide documentation showing testing laboratory is accredited under OSHA's Nationally Recognized Testing Laboratory (NRTL) program or through the National Institute of Standards and Technology's (NIST's) National Voluntary Laboratory Accreditation Program (NVLAP).
- B. Designer Qualifications: Where professional engineering design services and design data submittals are specifically required of Contractor by Contract Documents, provide services of a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.
- C. Contractor's Quality Control (CQC) Plan:
 - Prior to start of work, submit a comprehensive plan describing how contract deliverables will be produced. Tailor CQC plan to specific requirements of the project. Include the following information:
 - a. Management Structure: Identify personnel responsible for quality. Include a chart showing lines of authority.
 - Include qualifications (in resume form), duties, responsibilities of each person assigned to CQC function.
 - Management Approach: Define, describe, and include in the plan specific methodologies used in executing the work.
 - 1) Management and control of documents and records relating to quality.
 - 2) Communications.
 - 3) Coordination procedures.
 - Resource management.
 - 5) Process control.
 - 6) Inspection and testing procedures and scheduling, including inspections by authorities having jurisdiction and special inspections.
 - 7) Control of noncomplying work.
 - Tracking deficiencies from identification, through acceptable corrective action, and verification.
 - 9) Control of testing and measuring equipment.
 - 10) Project materials certification.
 - 11) Managerial continuity and flexibility.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

c. Acceptance of the plan is required prior to start of construction activities not including mobilization work. Owner's acceptance of the plan will be conditional and predicated on continuing satisfactory adherence to the plan. Owner reserves the right to require Contractor to make changes to the plan and operations, including removal of personnel, as necessary, to obtain specified quality of work results.

1.07 REFERENCES AND STANDARDS

- A. For products and workmanship specified by reference to a document or documents not included in the Project Manual, also referred to as reference standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. Comply with reference standard of date of issue current on date of Contract Documents, except where a specific date is established by applicable code.
- C. Obtain copies of standards where required by product specification sections.
- D. Maintain copy at project site during submittals, planning, and progress of the specific work, until Substantial Completion.
- E. Should specified reference standards conflict with Contract Documents, comply with the higher quality or quantity, and provide documentation of the conflict to the Architect.
- F. Neither the contractual relationships, duties, or responsibilities of the parties in Contract nor those of Architect shall be altered from Contract Documents by mention or inference otherwise in any reference document.

1.08 TESTING AND INSPECTION AGENCIES AND SERVICES

- A. Owner will employ and pay for services of an independent testing agency to perform Special Inspections and other specified testing indicated in individual specification sections.
- B. Where indicated in individual specification sections, Contractor shall employ and pay for services of an independent testing agency to perform other specified testing.
- C. Employment of agency in no way relieves Contractor of obligation to perform Work in accordance with requirements of Contract Documents.
- D. Contractor Employed Agency: Testing agency shall comply with requirements of ASTM E 329, and shall be certified through OSHA's Nationally Recognized Testing Laboratory (NRTL) program or through the National Institute of Standards and Technology's (NIST's) National Voluntary Laboratory Accreditation Program (NVLAP).
 - Testing Equipment: Calibrated at reasonable intervals either by NIST or using an NIST established Measurement Assurance Program, under a laboratory measurement quality assurance program.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce work of specified quality.
- B. Comply with manufacturers' instructions, including each step in sequence.
- Should manufacturers' instructions conflict with Contract Documents, request clarification from Architect before proceeding.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- D. Comply with specified standards as minimum quality for the work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- E. Have work performed by persons qualified to produce required and specified quality.
- F. Verify that field measurements are as indicated on shop drawings or as instructed by the manufacturer.
- G. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, and disfigurement.

3.02 MOCK-UPS

- A. Before installing portions of the Work where mock-ups are required, construct mock-ups in location and size indicated for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work. The purpose of mock-up is to demonstrate the proposed range of aesthetic effects and workmanship.
- B. Accepted mock-ups establish the standard of quality the Architect will use to judge the Work.
- C. Tests shall be performed under provisions identified in this section and identified in the respective product specification sections.
- D. Assemble and erect specified items with specified attachment and anchorage devices, flashings, seals, and finishes.
- E. Obtain Architect's approval of mock-ups before starting work, fabrication, or construction.
 - 1. Architect will issue written comments within seven (7) working days of initial review and each subsequent follow up review of each mock-up.
 - 2. Make corrections as necessary until Architect's approval is issued.
- F. Architect will use accepted mock-ups as a comparison standard for the remaining Work.
- G. Where mock-up has been accepted by Architect and is specified in product specification sections to be removed, protect mock-up throughout construction, remove mock-up and clear area when directed to do so by Architect.

3.03 TOLERANCES

- A. Monitor fabrication and installation tolerance control of products to produce acceptable Work. Do not permit tolerances to accumulate.
- B. Comply with manufacturers' tolerances. Should manufacturers' tolerances conflict with Contract Documents, request clarification from Architect before proceeding.
- C. Adjust products to appropriate dimensions; position before securing products in place.

3.04 TESTING AND INSPECTION

- A. See individual specification sections for testing and inspection required.
- B. Testing Agency Duties for Contractor-employed Testing and Inspection Agencies:
 - 1. Test samples of mixes submitted by Contractor.
 - 2. Provide qualified personnel at site. Cooperate with Architect and Contractor in performance of services.
 - 3. Perform specified sampling and testing of products in accordance with specified standards.
 - 4. Ascertain compliance of materials and mixes with requirements of Contract Documents.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 5. Promptly notify Architect and Contractor of observed irregularities or non-compliance of Work or products.
- 6. Perform additional tests and inspections required by Architect.
- 7. Attend preconstruction meetings and progress meetings.
- 8. Submit reports of all tests/inspections specified.
- C. Limits on Testing/Inspection Agency Authority:
 - Agency may not release, revoke, alter, or enlarge on requirements of Contract Documents.
 - 2. Agency may not approve or accept any portion of the Work.
 - 3. Agency may not assume any duties of Contractor.
 - 4. Agency has no authority to stop the Work.

D. Contractor Responsibilities:

- 1. Deliver to agency at designated location, adequate samples of materials proposed to be used that require testing, along with proposed mix designs.
- Cooperate with laboratory personnel, and provide access to the Work and to manufacturers' facilities.
- 3. Provide incidental labor and facilities:
 - a. To provide access to Work to be tested/inspected.
 - b. To obtain and handle samples at the site or at source of Products to be tested/inspected.
 - c. To facilitate tests/inspections.
 - d. To provide storage and curing of test samples.
- 4. Notify Architect and laboratory 24 hours prior to expected time for operations requiring testing/inspection services.
- 5. Employ services of an independent qualified testing laboratory and pay for additional samples, tests, and inspections required by Contractor beyond specified requirements.
- 6. Arrange with Owner's agency and pay for additional samples, tests, and inspections required by Contractor beyond specified requirements.
- 7. Coordinate repairs where testing and inspection has damaged the Work.
- E. Re-testing and/or re-inspections required because of non-compliance with specified requirements shall be performed by the same agency. Do not proceed with construction activities that would conceal or cover work needing re-testing or re-inspection.
- F. Re-testing and/or re-inspections required because of non-compliance with specified requirements shall be paid for by Contractor.

3.05 MANUFACTURERS' FIELD SERVICES

- A. When specified in individual specification sections, require material or product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, and field quality control requirements as applicable, and to initiate instructions when necessary.
- B. Provide a written report of observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions or Contract Documents. Obtain Owner's approval prior to proceeding with any modifications.

3.06 DEFECT ASSESSMENT

Replace Work or portions of the Work not complying with specified requirements.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. Contractor may request to restore defective Work or portions of the Work to comply with specified requirements in lieu of replacement. Obtain Owner's approval prior to proceeding with restoration.
- C. If, in the opinion of Owner, it is not practical to restore or remove and replace the work, Owner will direct an appropriate remedy or adjust payment.

END OF SECTION 014000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 014200 DEFINITIONS AND REFERENCE STANDARDS

PART 1 GENERAL

1.01 SUMMARY

- A. The definitions include in this section supplement, but do not replace, the definitions contained in the General Conditions. In the event of duplication, the General Conditions shall govern.
- B. Other definitions are included in individual specification sections.

1.02 DEFINITIONS

- A. Furnish: To supply, deliver, unload, and inspect for damage.
- B. Install: To unpack, assemble, erect, apply, place, finish, cure, protect, clean, start up, and make ready for use.
- C. Product: Material, machinery, components, equipment, fixtures, and systems forming the work result. Not materials or equipment used for preparation, fabrication, conveying, or erection and not incorporated into the work result. Products may be new, never before used, or re-used materials or equipment.
- D. Provide: To furnish and install.
- E. Supply: Same as Furnish.
- F. Installer: A Contractor or other entity engaged by Contractor, as an employee, subcontractor, or contractor of lower tier, to perform a particular construction operation, including installation, erection, application, and similar operations.
 - 1. Using a term such as "carpentry" does not imply that certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name, such as "carpenter." It also does not imply that specified requirements apply exclusively to tradespeople of the corresponding generic name.
- G. Experienced: When used with the term "Installer," this term means having successfully completed previous work similar in size and scope to this Project; being familiar with the special requirements indicated; and having complied with the requirements of local authorities having jurisdiction.
- H. Replace: Provide an acceptable like product or material in place of a missing or unacceptable (rejected) product or material. To "replace" an unacceptable product or material includes its removal and disposal.
- Punch List: A written list of unfinished Work and defective Work resulting from inspection and testing to determine whether Substantial Completion has been accomplished. The unfinished Work and defective Work must be finished and corrected to obtain Substantial or Final Completion, in accordance with the General Conditions.
- J. Written or Printed: When used in conjunction with manufacturer's product data or installation requirements, either of these terms may be used to require compliance with manufacturer's current printed and published information.

1.03 REFERENCE STANDARDS

A. For products or workmanship specified by reference to a document or documents not included in the Project Manual, also referred to as reference standards, comply with requirements of the standard, except when more rigid requirements are specified, or are required by applicable codes or local authorities having jurisdiction.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. Should specified reference standards conflict with Contract Documents, request clarification from the Architect before proceeding.
- C. Neither the contractual relationships, duties, or responsibilities of the parties in Contract nor those of the Architect shall be altered by Contract Documents by mention or inference otherwise in any reference document.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION 014200

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 014520 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Balancing Air Systems:
 - a. Constant-volume air systems.
 - 2. Testing, Adjusting, and Balancing Equipment:
 - a. Motors.
 - b. Condensing units.
 - c. Heat-transfer coils.
 - 3. Testing, adjusting, and balancing existing systems and equipment.

1.3 DEFINITIONS

- A. AABC: Associated Air Balance Council.
- B. BAS: Building automation system.
- C. NEBB: National Environmental Balancing Bureau.
- D. TAB: Testing, adjusting, and balancing.
- E. TAB Specialist: An independent entity meeting qualifications to perform TAB work.

1.4 PREINSTALLATION MEETINGS

- A. TAB Conference: If requested by the Owner or Architect, conduct a TAB conference at Project site after approval of the TAB strategies and procedures plan to develop a mutual understanding of the details. Provide a minimum of 14 days' notice of scheduled meeting time and location.
 - 1. Minimum Agenda Items:
 - a. The Contract Documents examination report.
 - b. The TAB plan.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Needs for coordination and cooperation of trades and subcontractors.
- d. Proposed procedures for documentation and communication flow.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: Within 30 days of Contractor's Notice to Proceed, submit documentation that the TAB agent and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article.
- B. Contract Documents Examination Report: Within 60 days of Contractor's Notice to Proceed, submit the Contract Documents review report as specified in Part 3.
- C. Strategies and Procedures Plan: Within 90 days of Contractor's Notice to Proceed, submit TAB strategies and step-by-step procedures as specified in "Preparation" Article.
- D. System Readiness Checklists: Within 90 days of Contractor's Notice to Proceed, submit system readiness checklists as specified in "Preparation" Article.
- E. Examination Report: Submit a summary report of the examination review required in "Examination" Article.
- F. Certified TAB reports: Within 14 days of completion of balancing work, submit testing and balancing report.
- G. Sample report forms.

1.6 QUALITY ASSURANCE

- A. TAB Specialists Qualifications: Certified by AABC or NEBB. TAB provider shall be an independent company from the contractors performing the work.
 - 1. TAB Field Supervisor: Employee of the TAB specialist and certified by AABC or NEBB.
 - 2. TAB Technician: Employee of the TAB specialist and certified by AABC or NEBB as a TAB technician.
- B. Instrumentation Type, Quantity, Accuracy, and Calibration: Comply with requirements in ASHRAE 111, Section 4, "Instrumentation."
- C. The following information shall be submitted as part of the Quality Assurance Submittal:
 - 1. Provide evidence of satisfactory completion of at least two projects of similar size and scope. Submit the following for each project:
 - a. Completed testing and balancing reports for each project.
 - b. If not included in the testing and balancing report, provide equipment startup checklists for each project.
 - c. Owner contact for each project.
 - d. Design engineer contact for each project.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- e. Architect contact for each project.
- 2. The Architect shall determine whether the agent is qualified and the decision shall be final. Re-submittals on behalf of the same company shall not be considered.
- D. TAB Conference: After approval of the TAB submittals, the TAB specialist shall arrange a meeting with the Owner's and the Architect's representatives to develop a mutual understanding of the details and review the TAB strategies and procedures plan. Ensure the participation of TAB team members, equipment manufacturers' authorized service representatives, HVAC controls installer, and other support personnel. Provide 14 days' notice of scheduled meeting time and location.

1. Minimum Agenda:

- a. Submittal distribution requirements.
- b. Contract documents examination report.
- c. TAB strategies and procedures plan.
- d. Work schedule and project site access requirements.
- e. Coordination and cooperation of trades and subcontractors.
- f. Coordination of documentation and communication flow.
- g. Systems readiness checklists.
- E. TAB Reports: Use standard forms from AABC's "National Standards for TAB" or NEBB's "Procedural Standards for TAB of Environmental Systems."
- F. Instrumentation Type, Quantity, and Accuracy: As described in the "AABC National Standards for Total System Balance" or NEBB's "Procedural Standards for TAB of Environmental Systems," Section II, "Required Instrumentation for NEBB Certification."

1.7 FIELD CONDITIONS

A. Partial Owner Occupancy: Owner may occupy completed areas of building before Substantial Completion. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.

1.8 COORDINATION

- A. Coordinate the efforts of work performed under other sections for operation of systems and equipment to support and assist TAB activities.
- B. Notice: Provide 7 days' notice to the Contractor and Architect for each test. Include scheduled test dates and times.
- C. Perform TAB after any required leakage and pressure tests on air and water distribution systems have been satisfactorily completed.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.9 WARRANTY

- A. General Warranty: The national project performance guarantee indicated in this Article shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by the Contractor under requirements of the Contract Documents.
- B. Special Guarantee: Provide a guarantee on NEBB or AABC forms stating that NEBB or AABC will assist in completing the requirements of the Contract Documents if the TAB Agent fails to comply with the Contract Documents. Guarantee includes the following provisions:
 - 1. The certified Agent has tested and balanced systems according to the Contract Documents.
 - 2. Systems are balanced to optimum performance capabilities within design and installation limits

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems designs that may preclude proper TAB of systems and equipment.
- B. Examine installed systems for balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are applicable for intended purpose and are accessible.
- C. Examine the approved submittals for HVAC systems and equipment.
- D. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- E. Examine ceiling plenums and underfloor air plenums used for supply, return, or relief air to verify that they are properly separated from adjacent areas. Verify that penetrations in plenum walls are sealed and fire-stopped if required.
- F. Examine equipment performance data including fan and pump curves.
 - 1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
 - 2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems - Duct Design." Compare results with the design data and installed conditions.

- G. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.
- H. Examine test reports specified in individual system and equipment Sections.
- I. Examine HVAC equipment and verify that bearings are greased, belts are aligned and tight, filters are clean, and equipment with functioning controls is ready for operation.
- J. Examine terminal units, such as variable-air-volume boxes, and verify that they are accessible and their controls are connected and functioning.
- K. Examine strainers. Verify that startup screens have been replaced by permanent screens with indicated perforations.
- L. Examine control valves for proper installation for their intended function of throttling, diverting, or mixing fluid flows.
- M. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- N. Examine system pumps to ensure absence of entrained air in the suction piping.
- O. Examine operating safety interlocks and controls on HVAC equipment.
- P. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.2 PREPARATION

- A. Prepare a TAB plan that includes the following:
 - 1. Equipment and systems to be tested.
 - 2. Strategies and step-by-step procedures for balancing the systems.
 - 3. Instrumentation to be used.
 - 4. Sample forms with specific identification for all equipment.
- B. Perform system-readiness checks of HVAC systems and equipment to verify system readiness for TAB work. Include, at a minimum, the following:
 - 1. Airside:
 - a. Verify that leakage and pressure tests on air distribution systems have been satisfactorily completed.
 - b. Duct systems are complete with terminals installed.
 - c. Volume, smoke, and fire dampers are open and functional.
 - d. Clean filters are installed.
 - e. Fans are operating, free of vibration, and rotating in correct direction.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- f. Variable-frequency controllers' startup is complete and safeties are verified.
- g. Automatic temperature-control systems are operational.
- h. Ceilings are installed.
- i. Windows and doors are installed.
- j. Suitable access to balancing devices and equipment is provided.

3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary for TAB procedures.
 - 1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
 - Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish according to Section 230713 "Duct Insulation," Section 230716 "HVAC Equipment Insulation," and Section 230719 "HVAC Piping Insulation."
- B. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.
- C. Take and report testing and balancing measurements in inch-pound (IP) units.

3.4 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

- A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Cross-check the summation of required outlet volumes with required fan volumes.
- B. Prepare schematic diagrams of systems' "as-built" duct layouts.
- C. For variable-air-volume systems, develop a plan to simulate diversity.
- D. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.
- E. Check airflow patterns from the outdoor-air louvers and dampers and the return- and exhaust-air dampers through the supply-fan discharge and mixing dampers.
- F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- G. Verify that motor starters are equipped with properly sized thermal protection.
- H. Check dampers for proper position to achieve desired airflow path.
- I. Check for airflow blockages.
- J. Check condensate drains for proper connections and functioning.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- K. Check for proper sealing of air-handling-unit components.
- L. Verify that air duct system is sealed as specified in Section 233113 "Metal Ducts."

3.5 PROCEDURES FOR CONSTANT-VOLUME AIR SYSTEMS

- A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.
 - 1. Measure total airflow.
 - a. Set outside-air, return-air, and relief-air dampers for proper position that simulates minimum outdoor-air conditions.
 - b. Where duct conditions allow, measure airflow by Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses to obtain total airflow.
 - c. Where duct conditions are not suitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
 - d. If a reliable Pitot-tube traverse or coil traverse is not possible, measure airflow at terminals and calculate the total airflow.
 - 2. Measure fan static pressures as follows:
 - a. Measure static pressure directly at the fan outlet or through the flexible connection.
 - b. Measure static pressure directly at the fan inlet or through the flexible connection.
 - c. Measure static pressure across each component that makes up the air-handling system.
 - d. Report artificial loading of filters at the time static pressures are measured.
 - 3. Review Record Documents to determine variations in design static pressures versus actual static pressures. Calculate actual system-effect factors. Recommend adjustments to accommodate actual conditions.
 - 4. Obtain approval from Architect for adjustment of fan speed higher or lower than indicated speed. Comply with requirements in HVAC sections for air-handling units for adjustment of fans, belts, and pulley sizes to achieve indicated air-handling-unit performance.
 - 5. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload occurs. Measure amperage in full-cooling, full-heating, economizer, and any other operating mode to determine the maximum required brake horsepower.
- B. Adjust volume dampers for main duct, submain ducts, and major branch ducts to indicated airflows.
 - 1. Measure airflow of submain and branch ducts.
 - 2. Adjust submain and branch duct volume dampers for specified airflow.
 - 3. Re-measure each submain and branch duct after all have been adjusted.
- C. Adjust air inlets and outlets for each space to indicated airflows.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Set airflow patterns of adjustable outlets for proper distribution without drafts.
- 2. Measure inlets and outlets airflow.
- 3. Adjust each inlet and outlet for specified airflow.
- 4. Re-measure each inlet and outlet after they have been adjusted.

D. Verify final system conditions.

- 1. Re-measure and confirm that minimum outdoor, return, and relief airflows are within design. Readjust to design if necessary.
- 2. Re-measure and confirm that total airflow is within design.
- 3. Re-measure all final fan operating data, rpms, volts, amps, and static profile.
- 4. Mark all final settings.
- 5. Test system in economizer mode. Verify proper operation and adjust if necessary.
- 6. Measure and record all operating data.
- 7. Record final fan-performance data.

3.6 PROCEDURES FOR MOTORS

- A. Motors 1/2 HP and Larger: Test at final balanced conditions and record the following data:
 - 1. Manufacturer's name, model number, and serial number.
 - 2. Motor horsepower rating.
 - 3. Motor rpm.
 - 4. Phase and hertz.
 - 5. Nameplate and measured voltage, each phase.
 - 6. Nameplate and measured amperage, each phase.
 - 7. Starter size and thermal-protection-element rating.
 - 8. Service factor and frame size.
- B. Motors Driven by Variable-Frequency Controllers: Test manual bypass of controller to prove proper operation.

3.7 PROCEDURES FOR CONDENSING UNITS

- A. Verify proper rotation of fans.
- B. Measure entering- and leaving-air temperatures.
- C. Record fan and motor operating data.

3.8 PROCEDURES FOR HEAT-TRANSFER COILS

- A. Measure, adjust, and record the following data for each water coil:
 - 1. Entering- and leaving-water temperature.
 - 2. Water flow rate.
 - 3. Water pressure drop for major (more than 20 gpm) equipment coils, excluding unitary equipment such as reheat coils, unit heaters, and fan-coil units.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Dry-bulb temperature of entering and leaving air.
- 5. Wet-bulb temperature of entering and leaving air for cooling coils.
- 6. Airflow.
- B. Measure, adjust, and record the following data for each electric heating coil:
 - 1. Nameplate data.
 - 2. Airflow.
 - 3. Entering- and leaving-air temperature at full load.
 - 4. Voltage and amperage input of each phase at full load.
 - 5. Calculated kilowatt at full load.
 - 6. Fuse or circuit-breaker rating for overload protection.
- C. Measure, adjust, and record the following data for each steam coil:
 - 1. Dry-bulb temperature of entering and leaving air.
 - 2. Airflow.
 - 3. Inlet steam pressure.
- D. Measure, adjust, and record the following data for each refrigerant coil:
 - 1. Dry-bulb temperature of entering and leaving air.
 - 2. Wet-bulb temperature of entering and leaving air.
 - 3. Airflow.

3.9 TOLERANCES

- A. Set HVAC system's airflow rates and water flow rates within the following tolerances:
 - 1. Supply, Return, and Exhaust Fans and Equipment with Fans: 0 to plus 10 percent.
 - 2. Air Outlets: Plus or minus 10 percent.
 - 3. Return Inlets: Plus or minus 10 percent.
 - 4. Exhaust Inlets: 0 to plus 10 percent.
 - 5. Unless indicated otherwise: Plus or minus 10 percent.
- B. Maintaining pressure relationships as designed shall have priority over the tolerances specified above.

3.10 PROGRESS REPORTING

A. Initial Construction-Phase Report: Based on examination of the Contract Documents as specified in "Examination" Article, prepare a report on the adequacy of design for systems balancing devices. Recommend changes and additions to systems balancing devices to facilitate proper performance measuring and balancing. Recommend changes and additions to HVAC systems and general construction to allow access for performance measuring and balancing devices.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

B. Status Reports: Prepare biweekly progress reports to describe completed procedures, procedures in progress, and scheduled procedures. Include a list of deficiencies and problems found in systems being tested and balanced. Prepare a separate report for each system and each building floor for systems serving multiple floors.

3.11 FINAL REPORT

- A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.
 - 1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
 - 2. Include a list of instruments used for procedures, along with proof of calibration.
 - 3. Certify validity and accuracy of field data.
- B. Final Report Contents: In addition to certified field-report data, include the following:
 - 1. Fan curves.
 - 2. Manufacturers' test data.
 - 3. Field test reports prepared by system and equipment installers.
 - 4. Other information relative to equipment performance; do not include Shop Drawings and Product Data.
- C. General Report Data: In addition to form titles and entries, include the following data:
 - 1. Title page.
 - 2. Name and address of the TAB specialist.
 - 3. Project name.
 - 4. Project location.
 - 5. Architect's name and address.
 - 6. Engineer's name and address.
 - 7. Contractor's name and address.
 - 8. Report date.
 - 9. Signature of TAB supervisor who certifies the report.
 - 10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
 - 11. Summary of contents including the following:
 - a. Indicated versus final performance.
 - b. Notable characteristics of systems.
 - c. Description of system operation sequence if it varies from the Contract Documents.
 - 12. Nomenclature sheets for each item of equipment.
 - 13. Data for terminal units, including manufacturer's name, type, size, and fittings.
 - 14. Notes to explain why certain final data in the body of reports vary from indicated values.
 - 15. Test conditions for fans and pump performance forms including the following:
 - a. Settings for outdoor-, return-, and exhaust-air dampers.
 - b. Conditions of filters.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Cooling coil, wet- and dry-bulb conditions.
- d. Face and bypass damper settings at coils.
- e. Fan drive settings including settings and percentage of maximum pitch diameter.
- f. Inlet vane settings for variable-air-volume systems.
- g. Settings for supply-air, static-pressure controller.
- h. Other system operating conditions that affect performance.
- D. System Diagrams: Include schematic layouts of air and hydronic distribution systems. Present each system with single-line diagram and include the following:
 - 1. Quantities of outdoor, supply, return, and exhaust airflows.
 - 2. Duct, outlet, and inlet sizes.
 - 3. Balancing stations.
 - 4. Position of balancing devices.
- E. Air-Handling-Unit Test Reports: For air-handling units with coils, include the following:
 - 1. Unit Data:
 - a. Unit identification.
 - b. Location.
 - c. Make and type.
 - d. Model number and unit size.
 - e. Manufacturer's serial number.
 - f. Unit arrangement and class.
 - g. Discharge arrangement.
 - h. Sheave make, size in inches, and bore.
 - i. Center-to-center dimensions of sheave and amount of adjustments in inches.
 - j. Number, make, and size of belts.
 - k. Number, type, and size of filters.
 - 2. Motor Data:
 - a. Motor make, and frame type and size.
 - b. Horsepower and rpm.
 - c. Volts, phase, and hertz.
 - d. Full-load amperage and service factor.
 - e. Sheave make, size in inches, and bore.
 - f. Center-to-center dimensions of sheave and amount of adjustments in inches.
 - 3. Test Data (Indicated and Actual Values):
 - a. Total airflow rate in cfm.
 - b. Total system static pressure in inches wg.
 - c. Fan rpm.
 - d. Discharge static pressure in inches wg.
 - e. Filter static-pressure differential in inches wg.
 - f. Preheat-coil static-pressure differential in inches wg.
 - g. Cooling-coil static-pressure differential in inches wg.
 - h. Heating-coil static-pressure differential in inches wg.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- i. Outdoor airflow in cfm.
- j. Return airflow in cfm.
- k. Outdoor-air damper position.
- 1. Return-air damper position.
- m. Vortex damper position.
- F. Apparatus-Coil Test Reports:
 - 1. Coil Data:
 - a. System identification.
 - b. Location.
 - c. Coil type.
 - d. Number of rows.
 - e. Fin spacing in fins per inch.
 - f. Make and model number.
 - g. Face area in square feet.
 - h. Tube size in NPS.
 - i. Tube and fin materials.
 - j. Circuiting arrangement.
 - 2. Test Data (Indicated and Actual Values):
 - a. Airflow rate in cfm.
 - b. Average face velocity in fpm.
 - c. Air pressure drop in inches wg.
 - d. Outdoor-air, wet- and dry-bulb temperatures in deg F.
 - e. Return-air, wet- and dry-bulb temperatures in deg F.
 - f. Entering-air, wet- and dry-bulb temperatures in deg F.
 - g. Leaving-air, wet- and dry-bulb temperatures in deg F.
 - h. Water flow rate in gpm.
 - i. Water pressure differential in feet of head or psig.
 - j. Entering-water temperature in deg F.
 - k. Leaving-water temperature in deg F.
 - 1. Refrigerant expansion valve and refrigerant types.
 - m. Refrigerant suction pressure in psig.
 - n. Refrigerant suction temperature in deg F.
 - o. Inlet steam pressure in psig.
- G. Electric-Coil Test Reports: For electric furnaces, duct coils, and electric coils installed in central-station air-handling units, include the following:
 - 1. Unit Data:
 - a. System identification.
 - b. Location.
 - c. Coil identification.
 - d. Capacity in Btu/h.
 - e. Number of stages.
 - f. Connected volts, phase, and hertz.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- g. Rated amperage.
- h. Airflow rate in cfm.
- i. Face area in square feet.
- j. Minimum face velocity in fpm.
- 2. Test Data (Indicated and Actual Values):
 - a. Heat output in Btu/h.
 - b. Airflow rate in cfm.
 - c. Air velocity in fpm.
 - d. Entering-air temperature in deg F.
 - e. Leaving-air temperature in deg F.
 - f. Voltage at each connection.
 - g. Amperage for each phase.
- H. Fan Test Reports: For supply, return, and exhaust fans, include the following:
 - 1. Fan Data:
 - a. System identification.
 - b. Location.
 - c. Make and type.
 - d. Model number and size.
 - e. Manufacturer's serial number.
 - f. Arrangement and class.
 - g. Sheave make, size in inches, and bore.
 - h. Center-to-center dimensions of sheave and amount of adjustments in inches.
 - 2. Motor Data:
 - a. Motor make, and frame type and size.
 - b. Horsepower and rpm.
 - c. Volts, phase, and hertz.
 - d. Full-load amperage and service factor.
 - e. Sheave make, size in inches, and bore.
 - f. Center-to-center dimensions of sheave, and amount of adjustments in inches.
 - g. Number, make, and size of belts.
 - 3. Test Data (Indicated and Actual Values):
 - a. Total airflow rate in cfm.
 - b. Total system static pressure in inches wg.
 - c. Fan rpm.
 - d. Discharge static pressure in inches wg.
 - e. Suction static pressure in inches wg.
- I. Round, Flat-Oval, and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:
 - 1. Report Data:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. System and air-handling-unit number.
- b. Location and zone.
- c. Traverse air temperature in deg F.
- d. Duct static pressure in inches wg.
- e. Duct size in inches.
- f. Duct area in square feet.
- g. Indicated airflow rate in cfm.
- h. Indicated velocity in fpm.
- i. Actual airflow rate in cfm.
- j. Actual average velocity in fpm.
- k. Barometric pressure in psig.

J. Instrument Calibration Reports:

1. Report Data:

- a. Instrument type and make.
- b. Serial number.
- c. Application.
- d. Dates of use.
- e. Dates of calibration.

3.12 VERIFICATION OF TAB REPORT

- A. The TAB specialist's test and balance engineer shall conduct the inspection in the presence of Owner.
- B. Owner shall randomly select measurements, documented in the final report, to be rechecked. Rechecking shall be limited to either 10 percent of the total measurements recorded or the extent of measurements that can be accomplished in a normal 8-hour business day.
- C. If rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."
- D. If the number of "FAILED" measurements is greater than 10 percent of the total measurements checked during the final inspection, the testing and balancing shall be considered incomplete and shall be rejected.
- E. If TAB work fails, proceed as follows:
 - 1. TAB specialists shall recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes; resubmit the final report and request a second final inspection.
 - 2. If the second final inspection also fails, Owner may contract the services of another TAB specialist to complete TAB work according to the Contract Documents and deduct the cost of the services from the original TAB specialist's final payment.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. If the second verification also fails, design professional may contact AABC Headquarters regarding the AABC National Performance Guaranty.
- F. Prepare test and inspection reports.

3.13 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional TAB to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional TAB during near-peak summer and winter conditions.
- C. When requested, provide up to 32 hours by the technician that provided services under this Section to support commissioning.

END OF SECTION 014520

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 015000 TEMPORARY FACILITIES AND CONTROLS

PART 1 GENERAL

1.01 DEWATERING

- A. Provide temporary means and methods for dewatering all temporary facilities and controls, in compliance with local authority having jurisdiction.
- B. Maintain temporary facilities in operable condition.

1.02 TEMPORARY UTILITIES

- A. Provide and pay for all electrical power, lighting, water, heating and cooling, and ventilation required for construction purposes.
- B. New permanent facilities may be used, with prior Owner authorization.
 - 1. Use of permanent facilities shall not impact specified warranties. Equipment shall be maintained during temporary usage.
- C. Temporary Lighting: Provide temporary lighting of type and producing lighting levels necessary for proper installation of the Work.
- D. Temporary Heating, Cooling, and Ventilation: Provide temporary measures and equipment as required for curing, drying, and humidity control. Comply with manufacturer's installation instructions for specific product requirements.
 - 1. Provide measures and equipment to meet warranty requirements of interior woodwork specified in Division 6 and/or Division 12 sections.
 - 2. Use of Permanent HVAC Facilities and Equipment: Use of HVAC equipment shall be subject to Owner approval.
 - a. Protect new and existing HVAC equipment from intrusion of dust, silica, dirt and debris during construction operations.
 - b. Cover all openings in new and existing inactive ductwork during construction operation with minimum 6 mil polyethylene sheet.
 - c. Where use of existing HVAC equipment is approved by Owner, provide temporary filters with a minimum MERV of 8. Change the filters every two weeks while construction is ongoing. Provide new filters at Substantial Completion; do not change out temporary filter until approved by Architect.
 - d. Do not perform testing and balancing of HVAC equipment until dust, silica, dirt and debris producing activities are complete.
- E. Temporary Water: For the duration of construction or until permanent water service is available at the site, the Contractor shall provide a temporary water source, as part of the Contract Price.
- F. Temporary Electric Service: Until electric utility provides permanent service at the site, the Contractor shall provide temporary electrical power, as part of the Contract Price.
- G. Temporary Sewer and Drainage: Comply with requirements of local authority having jurisdiction for connection of temporary sewer to public system.

1.03 TELECOMMUNICATIONS SERVICES

- A. Provide, maintain, and pay for telecommunications services to field office at time of project mobilization.
- B. Telecommunications services shall include:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- Telephone Service: Contractor shall ensure that all of its forces, including on-site managers/supervisors of each Subcontractor, have mobile devices and adequate voice and data coverage for on-site operations
- 2. Internet Connections: Minimum of one; DSL modem or faster.
- Video Conferencing and Video Site Visit/Walkthrough Infrastructure: Maintain personal computer/laptop with large format display screen and video conferencing software in the common-use field office.
 - a. Maintain equipment in common-use field office for site visits and walkthroughs, including a portable, high quality digital video camera, audio headset with microphone for walkthrough commentary/narration, and accessories including connection cables and battery packs.

1.04 TEMPORARY SANITARY FACILITIES

- A. Provide and maintain required facilities and enclosures. Provide at time of project mobilization.
 - 1. Provide temporary unisex toilet units and all required disposable supplies.
 - Provide handwash stations and hand sanitizer at each toilet unit.
 - 3. Provide regular servicing of portable facilities by professional servicing company; including draining, cleaning, and disinfecting.
- B. New permanent facilities may not be used during construction operations.
- C. Maintain daily in clean and sanitary condition.

1.05 BARRIERS

- A. Provide barriers to prevent unauthorized entry to construction areas, to prevent access to areas that could be hazardous to workers or the public, to allow for owner's use of site and to protect existing facilities and adjacent properties from damage from construction operations and demolition.
- B. Provide barricades and covered walkways required by governing authorities for public rights-ofway and for public access to existing building, and for emergency egress.
- C. Provide protection for plants designated to remain. Replace damaged plants.
- D. Protect vehicular traffic, stored materials, site, and structures from damage.

1.06 FENCING

- A. Barrier Mesh Fence: Provide minimum 6-foot height open-mesh polypropylene barrier fabric mounted on lumber or galvanized steel posts to isolate and define construction area and prevent accidental public access.
- B. Construction: Commercial grade chain link fence.
 - Contractor may provide either fixed or portable fencing to suit conditions. For portable fencing, provide concrete or galvanized steel bases for supporting posts. Bases for portable fencing shall not obstruct sidewalks or other pathways used by pedestrians.
- C. Provide 6 foot high fence around construction site; equip with vehicular and pedestrian gates with locks.
- D. Unless otherwise indicated, provide barrier mesh fencing to enclose the approximate extent of the entire construction site. Chain link fencing shall be used to enclose Contractor's field office and laydown/storage areas, areas of the site actively in construction, and as deemed necessary by Contractor.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.07 EXTERIOR ENCLOSURES

A. Provide temporary weather tight closure of exterior openings to accommodate acceptable working conditions and protection for Products, to allow for temporary heating and maintenance of required ambient temperatures identified in individual specification sections, and to prevent entry of unauthorized persons. Provide access doors with self-closing hardware and locks.

1.08 INTERIOR ENCLOSURES

- A. Provide temporary partitions to separate work areas from Owner-occupied areas, to prevent penetration of dust and moisture into Owner-occupied areas, and to prevent damage to existing materials and equipment.
- B. Construction: Framing and gypsum board sheet materials with closed joints and sealed edges at intersections with existing surfaces:

1.09 SECURITY

- A. Provide security and facilities to protect Work, existing facilities, and Owner's operations from unauthorized entry, vandalism, or theft.
 - 1. Contractor shall repair damage to existing facilities caused by Construction operations.
- B. Coordinate with Owner's security program.
- C. Environmental Protection: Comply with EPA, OSHA and other regulatory requirements to prevent contamination of site, air, and public sewer/runoff.
 - 1. Provide additional work restrictions and protective measures as indicated on Civil/Site Drawings and as specified in Section 011000 Summary.

1.10 VEHICULAR ACCESS AND PARKING

- A. Comply with regulations relating to use of streets and sidewalks, access to emergency facilities, and access for emergency vehicles.
- B. Coordinate access and haul routes with governing authorities and Owner.
- C. Provide and maintain access to fire hydrants, free of obstructions.
- D. Provide means of removing mud from vehicle wheels before entering streets.
- E. Designated existing on-site roads may be used for construction traffic.
- F. Provide temporary parking areas to accommodate construction personnel. When site space is not adequate, provide additional off-site parking.

1.11 WASTE REMOVAL

- A. See Section 017419 Construction Waste Management and Disposal, for additional requirements.
- B. Provide waste removal facilities and services as required to maintain the site in clean and orderly condition.
- C. Provide containers with lids. Remove trash from site periodically.
- D. If materials to be recycled or re-used on the project must be stored on-site, provide suitable non-combustible containers; locate containers holding flammable material outside the structure unless otherwise approved by the authorities having jurisdiction.
- E. Open free-fall chutes are not permitted. Terminate closed chutes into appropriate containers with lids.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.12 PROJECT IDENTIFICATION

- A. Provide project identification sign of design and construction indicated on drawings.
 - 1. Obtain and pay for any permits required for temporary signage by local authority having jurisdiction.
- B. Erect on site at location(s) established by Architect.
- C. Provide temporary directional signage as directed to facilitate site access for visitors and other construction personnel.
- D. No other signs are allowed without Owner permission except those required by law.

1.13 FIELD OFFICES

- A. Field Office: Weathertight, with lighting, electrical outlets, heating, cooling equipment, and equipped with sturdy furniture and drawing display table.
 - 1. Provide space for Project meetings, with table and chairs to accommodate 10 persons.
 - 2. Provide drinking water/water cooler and a private bathroom.
 - 3. Maintain the following materials in the field office, available to Architect and Owner's representative at all times:
 - A complete, up-to-date set of all Contract Documents, including FCs, RFIs, PCOs, and COs.
 - b. A complete, up-to-date set of all reviewed final shop drawings.
 - c. The most recent, up-to-date version of Contractor's Progress Schedule.
- B. Locate offices a minimum distance of 30 feet from other structures.

1.14 REMOVAL OF UTILITIES, FACILITIES, AND CONTROLS

- A. Remove temporary utilities, equipment, facilities, materials, prior to Date of Substantial Completion inspection.
- B. Remove temporary underground installations.
- C. Clean and repair damage caused by installation or use of temporary work.
- D. Restore existing facilities used during construction to original condition.
- E. Restore new permanent facilities used during construction to specified condition.

PART 2 PRODUCTS

2.01 MATERIALS

- A. Rough Carpentry: 2x lumber, in length and depth required for floor to ceiling partitions. Partitions shall not be fastened to existing ceilings or flooring to remain. Provide additional bracing and concealed attachments to building structure.
- B. Gypsum Board: 1/2-inch gypsum wallboard; ASTM C 1396.
- C. Insulation: Mineral-wool fiber blankets; with maximum flame-spread and smoke-developed ratings of 25 and 50 when tested per ASTM E 84.
- D. Polyethylene Sheet: Minimum 10 mil reinforced sheeting; achieving a passing rating when tested per NFPA 701, and a maximum flame-spread rating of 15 when tested per ASTM E 84.
- E. Walk-Off Mats: Dust-, dirt- and silica-control walk-off mats at each entrance into the enclosed construction area and each entrance through temporary partitions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

F. Hardware: Provide temporary hinges, latch, and lock at doors in temporary partitions. Where doors in temporary partitions are also indicated to serve as egress, provide ADA-compliant exit device and closer.

2.02 EQUIPMENT

A. Fire Extinguishers: Provide portable UL rated extinguishers. Provide extinguisher types rated for potential classes of fire expected for construction work indicated.

PART 3 EXECUTION

3.01 ELEVATOR AND STAIR USAGE

- A. Use of new or existing elevator(s) is not permitted.
- B. Use of existing stairs is permitted. Cover existing finishes and maintain stairs without damage. Clean and restore stairs to Owner's approval at Substantial Completion.
- C. Use of new stairs is permitted. To prevent wear on finishes, do not install finishes on stairs until construction foot traffic can be minimized. Clean and prepare stair substrate thoroughly prior to installation of finishes. Cover finishes after installation, and clean and restore to Owner's approval at Substantial Completion.
 - 1. Provide temporary stairs until new stairs are available.

3.02 PEST CONTROL

- A. Provide pest-control services at regular intervals, performed in compliance with regulations of state regulations, and by a pest-control firm licensed in the state where the project is located. Any chemicals and pesticides used shall be approved by EPA and local authority having jurisdiction. Contractor's pest control plan shall ensure the facility is free of termites, roaches, rodents, and other pests at time of Substantial Completion.
 - 1. Coordinate with Owner's Integrated Pest Management (IPM) plan where applicable.
 - 2. Provide Owner with a minimum 72 hours pre-notification for pest-control treatments.

3.03 TEMPORARY FIRE PROTECTION

- A. Comply with International Fire Code, Chapter 33 "Fire Safety During Construction and Demolition" for preventing damage to structures under construction.
 - 1. Comply with NFPA 241 "Standard for Safeguarding Construction, Alteration, and Demolition Operations" for additional provisions and conditions that are not covered by Chapter 33 of the International Fire Code.
- B. Provide a fire-prevention program, review with all personnel on site, and post fire-prevention information in clearly visible area. Coordinate fire-prevention program with local fire department.
- C. Provide clearly labeled portable fire extinguishers.
- D. Provide fire watch in compliance with OSHA requirements during and after use of all potential ignition sources, including but not limited to, welders, grinders, cutting torches, heating and electrical equipment, and lighting.
- E. Do not allow smoking in areas under construction.

3.04 MOISTURE CONTROL

- A. Prevent the absorption of moisture and humidity by:
 - 1. Sequencing the delivery of such materials so that they are not present in the building until wet work is completed and dry.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 2. Delivery and storage of such materials in fully sealed moisture-impermeable packaging.
- 3. Provide sufficient ventilation for drying within reasonable time frame.
- B. Prior to building dry-in, store porous materials in a separate enclosed storage building. Keep all surfaces clear of standing water, and cover or otherwise protect all materials from water infiltration and damage. Do not enclose interior spaces until dry-in is complete and ventilation can remove excess moisture.
- C. After building dry-in, provide temporary mechanical ventilation for humidity and moisture control until the building HVAC system is operational. Do not store or install material in the building until ambient temperature and humidity is within manufacturer's acceptable range. Do not install wet materials, and ensure that substrates are fully dry prior to installing other materials over them.
- D. Provide continuous monitoring of installed materials. Remove gypsum board, wood products, and other mold-supporting products, if they become and remain wet for 48 hours. Remove and replace any materials showing visible signs of mold or mildew.

3.05 TEMPORARY FACILITY USAGE AND REMOVAL

- A. Maintenance and Usage: Keep temporary facilities clean and in well-maintained condition for the duration of the Project. Prevent misuse of or damage to facilities by construction personnel. Make repairs to temporary facilities or replace facilities as required to keep them in good operating condition and in compliance with applicable OSHA, local permitting, and other applicable regulations.
- B. Changeover: Coordinate changeover from temporary facilities to permanent facilities at Substantial Completion, unless an alternate arrangement for changeover has been agreed upon in writing by Owner.
 - 1. Contractor shall be responsible for repair, restoration, and cleaning of permanent facilities that are used for construction purposes after changeover.
- C. Removal: Unless otherwise indicated, temporary facilities and controls are the property of the Contractor, and shall be removed upon Architect's approval when Contractor can demonstrate that they are no longer needed.
 - 1. Comply with construction waste management and recycling requirements for temporary facilities and materials that are not able to be reused.
 - 2. After removal of temporary facilities and controls, complete all permanent construction that was not accessible due to the presence of temporary facilities.
 - 3. Remove materials that have become soiled or contaminated due to construction vehicle traffic, parking, temporary field offices, oil or other chemical spillage, and other temporary usage, and replace with clean material. Complete grading, landscaping, paving, and other site improvements, and repair or restore all damage to existing or previously completed site improvements.

END OF SECTION 015000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 016000 PRODUCT REQUIREMENTS

PART 1 GENERAL

1.01 RELATED REQUIREMENTS

- A. Section 011000 Summary: Identification of Owner-supplied products.
- B. Section 012500 Substitution Procedures: Substitutions made during procurement and/or construction phases.
- C. Section 014000 Quality Requirements: Product quality monitoring.
- D. Section 017419 Construction Waste Management and Disposal: Waste disposal requirements potentially affecting product selection, packaging and substitutions.

1.02 DEFINITIONS

- Comparable Product: An unnamed product that is similar in quality and performance to named product(s).
- B. Basis-of-Design Product: A specific product selected by the Architect for use in the design process; based on certain performance characteristics, physical qualities or details, a specialized finish type, pattern, or color, or other indicated characteristics.

1.03 WARRANTIES

- A. Product warranties shall be provided in addition to and run concurrently to Contractor's general warranty/guarantee.
 - 1. Unless otherwise indicated, all warranty terms shall start on the date of Substantial Completion.
- B. Manufacturer's Warranty: A standard warranty issued by the product manufacturer, covering production and material defects.
- C. Special Warranties: Warranties in addition to standard manufacturer's warranty, covering fabrication, installation, or specific performance items such as weathertightness
- D. Warranty Form: Warranty shall be provided on either manufacturer's standard form or on specified form. When a sample warranty form is not included in the Project Manual, the warranty shall be on mutually agreed form.

PART 2 PRODUCTS

2.01 EXISTING PRODUCTS

- A. Do not use materials and equipment removed from existing premises unless specifically required or permitted by Contract Documents.
- B. Unforeseen historic items encountered remain the property of the Owner; notify Owner promptly upon discovery; protect, remove, handle, and store as directed by Owner.
- C. Existing materials and equipment indicated to be removed, but not to be re-used, relocated, reinstalled, delivered to the Owner, or otherwise indicated as to remain the property of the Owner, become the property of the Contractor; remove from site.

2.02 NEW PRODUCTS

A. Provide new products unless specifically required or permitted by Contract Documents.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. See Section 014000 Quality Requirements, for additional source quality control requirements.
- C. Use of products having any of the following characteristics is not permitted:
 - Made using or containing CFC's or HCFC's.
 - 2. Containing lead, cadmium, or asbestos.

2.03 PRODUCT OPTIONS

- A. Products Specified with a Single Named Product: Where required by Owner due to facility standards, provide the named product; no options or substitutions allowed.
- B. Products Specified by Reference Standards or by Description Only: Use any product meeting those standards or description.
- C. Products Specified by Naming One or More Manufacturers: Use a product of one of the manufacturers named and meeting specifications, no options or substitutions allowed.
- D. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named.
- E. Products Specified by Naming One or More Manufacturers with a Provision for Comparable Products: Unnamed comparable product may be submitted after award of Contract. Comply with requirements in "Comparable Products" article below.

2.04 BASIS-OF-DESIGN PRODUCTS

- A. Where a product is specified by naming a Basis-of-Design, comply with the following:
 - Where a list of additional manufacturers is provided, provide the Basis-of-Design product or a comparable product by one of the listed manufacturers, in compliance with "Comparable Products" article below.
 - Where a list of additional manufacturers is not provided, provide the Basis-of-Design product, or submit a substitution request in compliance with Section 012500 - Substitution Procedures.
 - 3. Basis-of-Design characteristics shall include requirements in the Specifications and on the Drawings.
 - 4. Where the Basis-of-Design lists a specific finish, manufacturers wishing to submit as a Comparable Product or as a substitution shall certify that they are able to provide an exact match to the specified finish, or that they will provide a custom finish to match.

2.05 COMPARABLE PRODUCTS

- A. Where a product is specified with a provision for comparable products, Contractors submitting a Comparable Product shall comply with the following:
 - 1. The submitted product shall not require changes to the Work, unless specifically approved by Architect. If changes are required, the Contractor shall resubmit the product as a substitution request, and the Contractor shall bear the cost of the changes, coordinate with other impacted contractors, and provide appropriate notations on record documents.
 - 2. Contractor shall provide, with the submittal, a detailed breakdown comparing the submitted product to at least one of the other listed products; list specified performance qualities, test results, dimensions, finish, and other critical properties.
 - 3. Contractor shall provide warranty data indicating that submitted Comparable Product complies with indicated warranty term(s).
- B. Comparable product submittals are subject to Architect's final approval. If a proposed product is found to be unacceptable, Contractor shall revert to one of the named products.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.06 COLOR/FINISH OPTIONS

- A. Preselected Color/Finish: Where a specific manufacturer's premium or custom finish or color is indicated as the basis-of-design, other listed manufacturers shall certify that they can provide an exact match, or that they will provide pricing under the assumption that a custom finish or color will be required.
- B. Color/Finish Selection: Unless specifically indicated to either be a custom color or to be selected from manufacturer's standard range, color and finish selections shall be made from manufacturer's full range of options, including premiums, metallics, wood grains, etc.

2.07 MAINTENANCE MATERIALS

- A. Furnish extra materials, spare parts, tools, and software of types and in quantities specified in individual specification sections.
- B. Deliver to location designated by Owner; obtain receipt prior to final payment.

PART 3 EXECUTION

3.01 SUBSTITUTION LIMITATIONS

A. See Section 012500 - Substitution Procedures.

3.02 OWNER-SUPPLIED PRODUCTS

- A. See Section 011000 Summary for identification of Owner-supplied products.
- B. Owner's Responsibilities:
 - Arrange for and deliver Owner reviewed shop drawings, product data, and samples, to Contractor.
 - 2. Arrange and pay for product delivery to site.
 - 3. On delivery, inspect products jointly with Contractor.
 - Submit claims for transportation damage and replace damaged, defective, or deficient items.
 - 5. Arrange for manufacturers' warranties, inspections, and service.
- C. Contractor's Responsibilities:
 - 1. Review Owner reviewed shop drawings, product data, and samples.
 - Receive and unload products at site; inspect for completeness or damage jointly with Owner.
 - 3. Handle, store, install and finish products.
 - 4. Repair or replace items damaged after receipt.

3.03 TRANSPORTATION AND HANDLING

- A. Package products for shipment in manner to prevent damage; for equipment, package to avoid loss of factory calibration.
- B. If special precautions are required, attach instructions prominently and legibly on outside of packaging.
- C. Coordinate schedule of product delivery to designated prepared areas in order to minimize site storage time and potential damage to stored materials.
- D. Transport and handle products in accordance with manufacturer's instructions.
- E. Transport materials in covered trucks to prevent contamination of product and littering of surrounding areas.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- F. Promptly inspect shipments to ensure that products comply with requirements, quantities are correct, and products are undamaged.
- G. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage, and to minimize handling.
- H. Arrange for the return of packing materials, such as wood pallets, where economically feasible.

3.04 STORAGE AND PROTECTION

- Provide protection of stored materials and products against theft, casualty, or deterioration.
- B. Designate receiving/storage areas for incoming products so that they are delivered according to installation schedule and placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication. See Section 017419.
 - 1. Structural Loading Limitations: Handle and store products and materials so as not to exceed static and dynamic load-bearing capacities of project floor and roof areas.
- C. Store and protect products in accordance with manufacturers' instructions.
- D. Store with seals and labels intact and legible.
- E. Arrange storage of materials and products to allow for visual inspection for the purpose of determination of quantities, amounts, and unit counts.
- F. Store sensitive products in weathertight, climate-controlled enclosures in an environment favorable to product.
- G. For exterior storage of fabricated products, place on sloped supports above ground.
- H. Provide off-site storage and protection when site does not permit on-site storage or protection.
- Protect products from damage or deterioration due to construction operations, weather, precipitation, humidity, temperature, sunlight and ultraviolet light, dirt, dust, and other contaminants.
- J. Comply with manufacturer's warranty conditions, if any.
- K. Do not store products directly on the ground.
- L. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.
- M. Prevent contact with material that may cause corrosion, discoloration, or staining.
- N. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
- O. Arrange storage of products to permit access for inspection. Periodically inspect to verify products are undamaged and are maintained in acceptable condition.

END OF SECTION 016000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 017000 EXECUTION AND CLOSEOUT REQUIREMENTS

PART 1 GENERAL

1.01 SUBMITTALS

A. Project Record Documents: Accurately record actual locations of capped and active utilities.

1.02 QUALIFICATIONS

A. For design of temporary shoring and bracing, employ a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.

1.03 PROJECT CONDITIONS

- A. Use of explosives is not permitted.
- B. Protect site from puddling or running water. Provide water barriers as required to protect site from soil erosion.
- C. Perform dewatering activities, as required, for the duration of the project.
- D. Ventilate enclosed areas to assist cure of materials, to dissipate humidity, and to prevent accumulation of dust, fumes, vapors, or gases.
- E. Dust and Silica Control: Execute work by methods to minimize raising dust and silica from construction operations. Provide positive means to prevent air-borne dust and silica from dispersing into atmosphere and over adjacent property.
 - Provide dust-proof enclosures to prevent entry of dust and silica that is generated outdoors.
 - 2. Provide dust-proof barriers between construction areas and areas continuing to be occupied by Owner.
- F. Erosion and Sediment Control: Plan and execute work by methods to control surface drainage from cuts and fills, from borrow and waste disposal areas. Prevent erosion and sedimentation.
 - 1. Minimize amount of bare soil exposed at one time.
 - 2. Provide temporary measures such as berms, dikes, and drains, to prevent water flow.
 - 3. Construct fill and waste areas by selective placement to avoid erosive surface silts or clays.
 - 4. Periodically inspect earthwork to detect evidence of erosion and sedimentation; promptly apply corrective measures.
- G. Noise Control: Provide methods, means, and facilities to minimize noise produced by construction operations.
- H. Pest and Rodent Control: Provide methods, means, and facilities to prevent pests and insects from damaging the work.
- I. Pollution Control: Provide methods, means, and facilities to prevent contamination of soil, water, and atmosphere from discharge of noxious, toxic substances, and pollutants produced by construction operations. Comply with federal, state, and local regulations.
- J. Hazardous Materials: Do not use materials or products that contain hazardous substances, for permanently installed products and materials, installation materials, or for cleaning or other construction use.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.04 COORDINATION

- A. See Section 011000 for occupancy-related requirements.
- B. Coordinate scheduling, submittals, and work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of interdependent construction elements, with provisions for accommodating items installed later.
- C. Notify affected utility companies and comply with their requirements.
- D. Verify that utility requirements and characteristics of new operating equipment are compatible with building utilities. Coordinate work of various sections having interdependent responsibilities for installing, connecting to, and placing in service, such equipment.
- E. Coordinate space requirements, supports, and installation of mechanical and electrical work that are indicated diagrammatically on drawings. Follow routing indicated for pipes, ducts, and conduit, as closely as practicable; place runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for maintenance, and for repairs.
- F. In finished areas except as otherwise indicated, conceal pipes, ducts, and wiring within the construction. Coordinate locations of fixtures and outlets with finish elements.
- G. Coordinate completion and clean-up of work of separate sections.
- H. After Owner occupancy of premises, coordinate access to site for correction of defective work and work not in accordance with Contract Documents, to minimize disruption of Owner's activities.

PART 2 PRODUCTS

2.01 PATCHING MATERIALS

- A. New Materials: As specified in product sections; match existing products and work for patching and extending work.
- B. Type and Quality of Existing Products: Determine by inspecting and testing products where necessary, referring to existing work as a standard.
- C. Product Substitution: For any proposed change in materials, submit request for substitution described in Section 016000 Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent work. Start of work means acceptance of existing conditions.
- B. Verify that existing substrate is capable of structural support or attachment of new work being applied or attached.
- C. Examine and verify specific conditions described in individual specification sections.
- D. Take field measurements before confirming product orders or beginning fabrication, to minimize waste due to over-ordering or misfabrication.
- E. Verify that utility services are available, of the correct characteristics, and in the correct locations.
- F. Prior to Cutting: Examine existing conditions prior to commencing work, including elements subject to damage or movement during cutting and patching. After uncovering existing work,

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

assess conditions affecting performance of work. Beginning of cutting or patching means acceptance of existing conditions.

3.02 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.
- C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.

3.03 LAYING OUT THE WORK

- A. Verify locations of survey control points prior to starting work.
- B. Promptly notify Architect of any discrepancies discovered.
- C. Contractor shall locate and protect survey control and reference points.
- D. Protect survey control points prior to starting site work; preserve permanent reference points during construction.
- E. Promptly report to Architect the loss or destruction of any reference point or relocation required because of changes in grades or other reasons.
- F. Replace dislocated survey control points based on original survey control. Make no changes without prior written notice to Architect.
- G. Utilize recognized engineering survey practices.
- H. Establish a minimum of two permanent bench marks on site, referenced to established control points. Record locations, with horizontal and vertical data, on project record documents.
- I. Establish elevations, lines and levels. Locate and lay out by instrumentation and similar appropriate means:
 - 1. Site improvements including pavements; stakes for grading, fill and topsoil placement; utility locations, slopes, and invert elevations.
 - 2. Grid or axis for structures.
 - 3. Building foundation, column locations, ground floor elevations.
- J. Periodically verify layouts by same means.
- K. Maintain a complete and accurate log of control and survey work as it progresses.

3.04 GENERAL INSTALLATION REQUIREMENTS

- A. Fire Safety: Comply with provisions of 2018 International Fire Code, Chapter 33; "Fire Safety During Construction and Demolition" for preventing damage to structures under construction.
 - 1. In addition to compliance with regulatory requirements, conduct construction operations in compliance with NFPA 241, including applicable recommendations in Appendix A.
- B. Install products as specified in individual sections, in accordance with manufacturer's instructions and recommendations, and so as to avoid waste due to necessity for replacement.
- C. Make vertical elements plumb and horizontal elements level, unless otherwise indicated.
- D. Install equipment and fittings plumb and level, neatly aligned with adjacent vertical and horizontal lines, unless otherwise indicated.
- E. Make consistent texture on surfaces, with seamless transitions, unless otherwise indicated.
- F. Make neat transitions between different surfaces, maintaining texture and appearance.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.05 ALTERATIONS

- A. Drawings showing existing construction and utilities are based on casual field observation and existing record documents only.
 - 1. Verify that construction and utility arrangements are as indicated.
 - 2. Report discrepancies to Architect before disturbing existing installation.
 - 3. Beginning of alterations work constitutes acceptance of existing conditions.
- B. Keep areas in which alterations are being conducted separated from other areas that are still occupied.
 - Provide, erect, and maintain temporary dustproof partitions of construction specified in Section 015000.
- C. Maintain weatherproof exterior building enclosure except for interruptions required for replacement or modifications; take care to prevent water and humidity damage.
 - Where openings in exterior enclosure exist, provide construction to make exterior enclosure weatherproof.
 - Insulate existing ducts or pipes that are exposed to outdoor ambient temperatures by alterations work.
- D. Remove existing work as indicated and as required to accomplish new work.
 - 1. Remove items indicated on drawings.
 - 2. Relocate items indicated on drawings.
 - 3. Remove miscellaneous hangers, exposed nails not serving as fasteners, and similar protrusions; remove adhesive residue and tape; fill anchorage holes; and otherwise patch and restore surface to be a uniform substrate.
 - 4. Where new surface finishes are to be applied to existing work, perform removals, patch, and prepare existing surfaces as required to receive new finish; prepare substrate per manufacturer's requirements for successful application of new finish.
 - 5. Where new surface finishes are not specified or indicated, patch holes and damaged surfaces to match adjacent finished surfaces.
- E. Services (Including but not limited to HVAC, Plumbing, Fire Protection, Electrical, and Telecommunications): Remove, relocate, and extend existing systems to accommodate new construction.
 - 1. Maintain existing active systems that are to remain in operation; maintain access to equipment and operational components; if necessary, modify installation to allow access or provide access panel.
 - 2. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
 - a. Disable existing systems only to make switchovers and connections; minimize duration of outages.
 - b. See Section 011000 for other limitations on outages and required notifications.
 - c. Provide temporary connections as required to maintain existing systems in service.
 - 3. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings; remove back to source of supply where possible, otherwise cap stub and tag with identification; patch holes left by removal using materials specified for new construction.
- F. Protect existing work to remain.
 - Prevent movement of structure; provide shoring and bracing if necessary.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
 - Use cutting methods such as sawing, drilling, and grinding that do not create impact stresses on existing construction. Do not use striking methods such as chopping or hammering.
- 3. Repair adjacent construction and finishes damaged during removal work.
- G. Adapt existing work to fit new work: Make as neat and smooth transition as possible.
 - When existing finished surfaces are cut so that a smooth transition with new work is not possible, terminate existing surface along a straight line at a natural line of division and make recommendation to Architect.
 - 2. Where removal of partitions or walls results in adjacent spaces becoming one, rework floors, walls, and ceilings to a smooth plane without breaks, steps, or bulkheads.
- H. Patching: Where the existing surface is not indicated to be refinished, patch to match the surface finish that existed prior to cutting. Where the surface is indicated to be refinished, patch so that the substrate is ready for the new finish.
- I. Refinish existing surfaces as indicated:
 - Where rooms or spaces are indicated to be refinished, refinish all visible existing surfaces
 to remain to the specified condition for each material, with a neat transition to adjacent
 finishes.
- J. Clean existing systems and equipment in all spaces impacted by alteration work.
- K. Remove demolition debris and abandoned items from alterations areas and dispose of off-site; do not burn or bury.
- L. Do not begin new construction in alterations areas before demolition is complete.

3.06 CUTTING AND PATCHING

- A. Refer to Alterations article above for additional requirements related to cutting and patching of existing construction.
- B. Perform cutting and patching to:
 - 1. Complete the work.
 - 2. Fit products together to integrate with other work.
 - 3. Provide openings for penetration of mechanical, electrical, and other services.
 - 4. Match work that has been cut to adjacent work.
 - 5. Repair areas adjacent to cuts to required condition.
 - 6. Repair new work damaged by subsequent work.
 - 7. Remove samples of installed work for testing when requested.
 - 8. Remove and replace defective and non-complying work.
- C. Execute work by methods that avoid damage to other work and that will provide appropriate surfaces to receive patching and finishing. In existing work, minimize damage and restore to specified condition.
- Employ skilled and experienced installer to perform cutting and patching.
- E. Restore work with new products in accordance with requirements of Contract Documents.
- F. Fit work to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- G. At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with fire rated material to maintain existing fire ratings, to full thickness of the penetrated element.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

H. Patching:

- Finish patched surfaces to match finish that existed prior to patching. On continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.
- 2. Match color, texture, and appearance.
- Repair patched surfaces that are damaged, lifted, discolored, or showing other imperfections due to patching work. If defects are due to condition of substrate, repair substrate prior to repairing finish.

3.07 PROGRESS CLEANING

- A. Maintain areas free of waste materials, debris, and rubbish. Maintain site in a clean and orderly condition.
- B. Remove debris and rubbish from pipe chases, plenums, attics, crawl spaces, and other closed or remote spaces, prior to enclosing the space.
- C. Broom and vacuum clean interior areas prior to start of surface finishing, and continue cleaning to eliminate dust and silica.
- D. Collect and remove waste materials, debris, and trash/rubbish from site periodically and dispose off-site; do not burn or bury.

3.08 PROTECTION OF INSTALLED WORK

- A. Protect installed work from damage by construction operations.
- B. Provide special protection where specified in individual specification sections.
- C. Provide temporary and removable protection for installed products. Control activity in immediate work area to prevent damage.
- D. Provide protective coverings at walls, projections, jambs, sills, and soffits of openings.
- E. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage, or movement of heavy objects, by protecting with durable sheet materials.
- F. Protect work from spilled liquids. If work is exposed to spilled liquids, immediately remove protective coverings, dry out work, and replace protective coverings.
- G. Prohibit traffic or storage upon waterproofed or roofed surfaces. If traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.
- H. Prohibit traffic from landscaped areas.
- I. Remove protective coverings when no longer needed; reuse or recycle coverings if possible.

3.09 SYSTEM STARTUP AND ADJUSTING

- A. Coordinate schedule for start-up of various equipment and systems.
- B. Notify Architect and Owner seven days prior to start-up of each item.
- C. Verify that each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, control sequence, and for conditions that may cause damage.
- D. Verify tests, meter readings, and specified electrical characteristics agree with those required by the equipment or system manufacturer.
- E. Verify that wiring and support components for equipment are complete and tested.
- F. Execute start-up under supervision of applicable Contractor personnel and manufacturer's representative in accordance with manufacturers' instructions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- G. When specified in individual specification Sections, require manufacturer to provide authorized representative to be present at site to inspect, check, and approve equipment or system installation prior to start-up, and to supervise placing equipment or system in operation.
- H. Adjust operating products and equipment to ensure smooth and unhindered operation.
- I. Submit a written report that equipment or system has been properly installed and is functioning correctly.

3.10 DEMONSTRATION AND INSTRUCTION

A. See Section 017900 - Demonstration and Training.

3.11 FINAL CLEANING

- A. Execute final cleaning prior to Substantial Completion.
 - 1. Clean areas to be occupied by Owner prior to final completion before Owner occupancy.
- B. Use cleaning materials that are nonhazardous.
- C. Clean interior and exterior glass, surfaces exposed to view; remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, vacuum carpeted and soft surfaces.
- D. Remove all labels that are not permanent. Do not paint or otherwise cover fire test labels or nameplates on mechanical and electrical equipment.
- E. Clean equipment and fixtures to a sanitary condition with cleaning materials appropriate to the surface and material being cleaned.
- F. Replace filters of operating equipment.
- G. Clean debris from roofs, gutters, downspouts, scuppers, overflow drains, area drains, and drainage systems.
- H. Clean site; sweep paved areas, rake clean landscaped surfaces.
- I. Remove waste, surplus materials, trash/rubbish, and construction facilities from the site; dispose of in legal manner; do not burn or bury.
- J. All outdoor grass areas disturbed by construction during the project, Contractor shall provide seed, topsoil, and fine grading if necessary to restore to original state of grassing.

3.12 CLOSEOUT PROCEDURES

- A. Prior to Substantial Completion, complete the following:
 - 1. Provide startup, testing, and adjusting of all systems and equipment.
 - a. Demonstrate that air and water systems are balanced and that automatic temperature control system is in control of all equipment. This may require separate demonstrations if controls cannot be tested for applicable seasons of the year.
 - b. Submit written certification that testing/adjusting/balancing operations have been completed, and that systems are operation and under control in conformance with applicable specification section(s).
 - 2. Provide all inspections required by local authorities having jurisdiction to obtain Certificate of Occupancy, and provide written certification of completion of Special Inspections.
 - 3. Provide preventive maintenance services for all equipment used prior to Substantial Completion, and provide initial maintenance servicing for all products and equipment that will be subject to ongoing maintenance/service contracts.
 - 4. Provide final cleaning of all products, materials, and equipment, and provide touch up and restoration of exposed materials and finishes.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 5. Provide fresh batteries in all battery-powered products and equipment.
- 6. Provide demonstration and training for Owner's personnel on all required systems and equipment.
- 7. Coordinate a walkthrough with the Owner and the local fire department and other emergency services.
- 8. To the maximum extent possible, remove temporary facilities and controls, construction equipment and tools, and similar items that are not part of the finished Work.
- 9. Coordinate changeover with the Owner of permanent utilities, insurance requirements, and building's permanent keying and lock system.
- B. Notify Architect when work is considered ready for Architect's Substantial Completion inspection.
- C. Submit written certification containing Contractor's Correction Punch List, that Contract Documents have been reviewed, work has been inspected, and that work is complete in accordance with Contract Documents and ready for Architect's Substantial Completion inspection.
- D. Owner will occupy the building after Substantial Completion as specified in Section 011000.
- E. Conduct Substantial Completion inspection and create Final Correction Punch List containing Architect's and Contractor's comprehensive list of items identified to be completed or corrected and submit to Architect.
- F. Correct items of work listed in Final Correction Punch List and comply with requirements for access to Owner-occupied areas.
- G. Notify Architect when work is considered finally complete and ready for Architect's Substantial Completion final inspection.
- H. Prior to final completion, complete the following:
 - Complete items of work determined by Architect listed in executed Certificate of Substantial Completion.
 - 2. Provide final pest and rodent control treatments and inspections.
 - 3. Remove any remaining construction equipment, tools, and materials; perform additional cleaning required due to construction activities following Substantial Completion, and leave the site prepared for Owner occupancy.
 - 4. Submit final demonstration and training materials and videos, as built/record documents, operation and maintenance binders, and warranty binders.
 - 5. Submit final application for payment.

3.13 MAINTENANCE

- A. Provide service and maintenance of components indicated in specification sections.
 - 1. Contractor's maintenance responsibility shall be through Substantial Completion, unless a longer term is required by individual specification section.
- B. Maintenance service shall not be assigned or transferred to any agent or third party without prior written consent of the Owner.

END OF SECTION 017000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 017419 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 GENERAL

1.01 WASTE MANAGEMENT REQUIREMENTS

- A. Owner requires that this project generate the least amount of trash and waste possible.
- B. Employ processes that ensure the generation of as little waste as possible due to error, poor planning, breakage, mishandling, contamination, or other factors.
- C. Minimize trash/waste disposal in landfills; reuse, salvage, or recycle as much waste as economically feasible.
- D. Contractor shall submit periodic Waste Disposal Reports; all landfill disposal, incineration, recycling, salvage, and reuse must be reported regardless of to whom the cost or savings accrues; use the same units of measure on all reports.
- E. Methods of trash/waste disposal that are not acceptable are:
 - Burning on the project site.
 - 2. Burying on the project site.
 - 3. Dumping or burying on other property, public or private.
 - 4. Other illegal dumping or burying.
- F. Regulatory Requirements: Contractor is responsible for knowing and complying with regulatory requirements, including but not limited to Federal, state and local requirements, pertaining to legal disposal of all construction and demolition waste materials.
 - Fire Safety: Comply with International Fire Code, Chapter 33 "Fire Safety During Construction and Demolition" and with NFPA 241 for provisions relating to accumulation and removal of combustible debris and waste.

1.02 DEFINITIONS

- A. Clean: Untreated and unpainted; not contaminated with oils, solvents, caulk, or the like.
- B. Construction and Demolition Waste: Solid wastes typically including building materials, packaging, trash, debris, and rubble resulting from construction, remodeling, repair and demolition operations.
- C. Hazardous: Exhibiting the characteristics of hazardous substances, i.e., ignitibility, corrosivity, toxicity or reactivity.
- D. Nonhazardous: Exhibiting none of the characteristics of hazardous substances, i.e., ignitibility, corrosivity, toxicity, or reactivity.
- E. Nontoxic: Neither immediately poisonous to humans nor poisonous after a long period of exposure.
- F. Recyclable: The ability of a product or material to be recovered at the end of its life cycle and remanufactured into a new product for reuse by others.
- G. Recycle: To remove a waste material from the project site to another site for remanufacture into a new product for reuse by others.
- H. Recycling: The process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for the purpose of using the altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- I. Return: To give back reusable items or unused products to vendors for credit.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- Reuse: To reuse a construction waste material in some manner on the project site.
- K. Salvage: To remove a waste material from the project site to another site for resale or reuse by others.
- L. Sediment: Soil and other debris that has been eroded and transported by storm or well production run-off water.
- M. Source Separation: The act of keeping different types of waste materials separate beginning from the first time they become waste.
- N. Toxic: Poisonous to humans either immediately or after a long period of exposure.
- O. Trash: Any product or material unable to be reused, returned, recycled, or salvaged.
- P. Waste: Extra material or material that has reached the end of its useful life in its intended use. Waste includes salvageable, returnable, recyclable, and reusable material.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Waste Disposal Reports: Submit at specified intervals, with details of quantities of trash and waste, means of disposal or reuse, and costs; show both totals to date and since last report.
 - 1. Submit updated Report with each Application for Progress Payment; failure to submit Report will delay payment.
 - 2. Submit Report on a form acceptable to Owner.
 - 3. Landfill Disposal: Include the following information:
 - a. Identification of material.
 - Amount, in tons or cubic yards, of trash/waste material from the project disposed of in landfills.
 - State the identity of landfills, total amount of tipping fees paid to landfill, and total disposal cost.
 - Include manifests, weight tickets, receipts, and invoices as evidence of quantity and cost
 - 4. Incinerator Disposal: Include the following information:
 - a. Identification of material.
 - b. Amount, in tons or cubic yards, of trash/waste material from the project delivered to incinerators.
 - c. State the identity of incinerators, total amount of fees paid to incinerator, and total disposal cost.
 - Include manifests, weight tickets, receipts, and invoices as evidence of quantity and cost.
 - 5. Recycled and Salvaged Materials: Include the following information for each:
 - a. Identification of material, including those retrieved by installer for use on other projects.
 - b. Amount, in tons or cubic yards, date removed from the project site, and receiving party.
 - c. Transportation cost, amount paid or received for the material, and the net total cost or savings of salvage or recycling each material.
 - d. Include manifests, weight tickets, receipts, and invoices as evidence of quantity and cost.
 - e. Certification by receiving party that materials will not be disposed of in landfills or by incineration.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 6. Material Reused on Project: Include the following information for each:
 - a. Identification of material and how it was used in the project.
 - b. Amount, in tons or cubic yards.
 - c. Include weight tickets as evidence of quantity.
- 7. Other Disposal Methods: Include information similar to that described above, as appropriate to disposal method.

PART 3 EXECUTION

2.01 WASTE MANAGEMENT PROCEDURES

- A. See Section 013000 for additional requirements for project meetings, reports, submittal procedures, and project documentation.
- B. See Section 015000 for additional requirements related to trash/waste collection and removal facilities and services.
- C. See Section 016000 for waste prevention requirements related to delivery, storage, and handling.
- D. See Section 017000 for trash/waste prevention procedures related to demolition, cutting and patching, installation, protection, and cleaning.

2.02 WASTE MANAGEMENT PLAN IMPLEMENTATION

- A. Manager: Designate an on-site person or persons responsible for instructing workers and overseeing and documenting results of the Waste Management Plan.
- B. Communication: Distribute copies of the Waste Management Plan to Contractor's site superintendent, each subcontractor, Owner, and Architect.
- C. Instruction: Provide on-site instruction of appropriate separation, handling, and recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the project.
- D. Meetings: Discuss trash/waste management goals and issues at project meetings.
 - 1. Prebid meeting.
 - Preconstruction meeting.
 - 3. Regular job-site meetings.
- E. Facilities: Provide specific facilities for separation and storage of materials for recycling, salvage, reuse, return, and trash disposal, for use by all contractors and installers.
 - 1. Provide containers as required.
 - 2. Provide adequate space for pick-up and delivery and convenience to subcontractors.
 - 3. Keep recycling and trash/waste bin areas neat and clean and clearly marked in order to avoid contamination of materials.
- F. Hazardous Wastes: Separate, store, and dispose of hazardous wastes according to applicable regulations.
- G. Recycling: Separate, store, protect, and handle at the site identified recyclable waste products in order to prevent contamination of materials and to maximize recyclability of identified materials. Arrange for timely pickups from the site or deliveries to recycling facility in order to prevent contamination of recyclable materials.
- H. Reuse of Materials On-Site: Set aside, sort, and protect separated products in preparation for reuse.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

I. Salvage: Set aside, sort, and protect products to be salvaged for reuse off-site.

END OF SECTION 017419

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 017800 CLOSEOUT SUBMITTALS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Project record documents.
- B. Operation and maintenance data.
- C. Warranties and bonds.

1.02 RELATED REQUIREMENTS

- A. Section 013000 Administrative Requirements: Submittal procedures, shop drawings, product data, and samples.
- B. Individual Product Sections: Specific requirements for operation and maintenance data.
- C. Individual Product Sections: Warranties required for specific products or Work.

1.03 SUBMITTALS

- A. Project Record Documents: Submit documents to Architect within 15 days after the date of Substantial Completion.
- B. Operation and Maintenance Data:
 - 1. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit completed documents within 15 days after acceptance.
 - 2. Submit one PDF draft copy of completed documents within 15 days after the Closeout Conference. This copy will be reviewed and returned, with Architect comments. Revise content of all document sets as required prior to final submission.
 - 3. After revisions are complete, submit one bound hard copy and PDF electronic file of revised final documents in final form within 15 days after Substantial Completion.

C. Warranties and Bonds:

- 1. For equipment or component parts of equipment put into service during construction with Owner's permission, submit documents within 15 days after acceptance.
- 2. Make other submittals within 15 days after Date of Substantial Completion, prior to final Application for Payment.
- For items of Work for which acceptance is delayed beyond Date of Substantial Completion, submit within 15 days after acceptance, listing the date of acceptance as the beginning of the warranty period.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PROJECT RECORD DOCUMENTS

- A. Maintain on site one set of the following record documents; record actual revisions to the Work:
 - 1. Drawings.
 - 2. Addenda.
 - 3. Change Orders and other modifications to the Contract.
 - 4. Miscellaneous record submittals.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. Ensure entries are complete and accurate, enabling future reference by Owner.
 - 1. Include revised Drawings reissued during Bidding and Construction.
- C. Store record documents separate from documents used for construction.
 - Keep record documents in a location accessible to Architect for periodic review and reference.
 - 2. Maintain in legible condition. If record document set becomes damaged or excessively dirty, transfer comments to clean set prior to submittal to Architect.
- D. Record information concurrent with construction progress.
- E. Record Drawings: Legibly mark each item to record actual construction including:
 - 1. Measured depths of foundations in relation to finish first floor datum.
 - 2. Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - 3. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
 - 4. Field changes of dimension and detail.
 - Details not on original Contract drawings.
- F. Miscellaneous Record Submittals: Where other specification sections require completion certifications, or closeout or record submittals, submit in a single binder organized by specification section.

3.02 ASSEMBLY OF RECORD DOCUMENTS

- A. Submittal for Architect's Review:
 - 1. Submit PDF scanned copy of marked up prints.
 - 2. Architect shall review and provide comment on completeness
- B. Submittal for Distribution to Owner:
 - 1. After Architect has approved for content and completeness, submit PDF scanned copy of final marked up prints, and submit hard copy originals.
 - 2. Submit full set of Drawings, regardless of whether any modification or markings are on each sheet.

3.03 OPERATION AND MAINTENANCE DATA

- A. Product Data: Mark each sheet to clearly identify specific products and component parts, and data applicable to installation. Delete inapplicable information.
- B. Drawings: Supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams. Do not use Project Record Documents as maintenance drawings.
- C. Typed Text: As required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions.

3.04 OPERATION AND MAINTENANCE DATA FOR MATERIALS AND FINISHES

- A. For Each Product, Applied Material, and Finish:
 - 1. Product data, with catalog number, size, composition, and color and texture designations.
 - 2. Information for re-ordering custom manufactured products.
- B. Instructions for Care and Maintenance: Manufacturer's recommendations for cleaning agents and methods, precautions against detrimental cleaning agents and methods, and recommended schedule for cleaning and maintenance.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- C. Moisture protection and weather-exposed products: Include product data listing applicable reference standards, chemical composition, and details of installation. Provide recommendations for inspections, maintenance, and repair.
- D. Additional information as specified in individual product specification sections.
- E. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.

3.05 OPERATION AND MAINTENANCE DATA FOR EQUIPMENT AND SYSTEMS

- A. For Each Item of Equipment and Each System:
 - 1. Description of unit or system, and component parts.
 - 2. Identify function, normal operating characteristics, and limiting conditions.
 - 3. Include performance curves, with engineering data and tests.
 - 4. Complete nomenclature and model number of replaceable parts.
- B. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.
- C. Panelboard Circuit Directories: Provide electrical service characteristics, controls, and communications; typed.
- D. Include color coded wiring diagrams as installed.
- E. Operating Procedures: Include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
- F. Maintenance Requirements: Include routine procedures and guide for preventative maintenance and troubleshooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- G. Provide servicing and lubrication schedule, and list of lubricants required.
- H. Include manufacturer's printed operation and maintenance instructions.
- I. Include sequence of operation by controls manufacturer.
- J. Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- K. Provide control diagrams by controls manufacturer as installed.
- Provide Contractor's coordination drawings, with color coded piping diagrams as installed.
- M. Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- N. Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- O. Include test and balancing reports.
- P. Additional Requirements: As specified in individual product specification sections.

3.06 ASSEMBLY OF OPERATION AND MAINTENANCE MANUALS

A. Assemble operation and maintenance data into durable manuals for Owner's personnel use, with data arranged in the same sequence as, and identified by, the specification sections.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. Where systems involve more than one specification section, provide separate tabbed divider for each system.
- C. Binders: Commercial quality, 8-1/2 by 11 inch three D side ring binders with durable plastic covers; 2 inch maximum ring size. When multiple binders are used, correlate data into related consistent groupings.
- D. Cover: Identify each binder on front and spine with typed or printed title OPERATION AND MAINTENANCE INSTRUCTIONS; identify title of Project; identify subject matter of contents.
- E. Project Directory: Title and address of Project; names, addresses, and telephone numbers of Architect, Consultants, Contractor and subcontractors, with names of responsible parties.
- F. Tables of Contents: List every item separated by a divider, using the same identification as on the divider tab; where multiple volumes are required, include all volumes Tables of Contents in each volume, with the current volume clearly identified.
- G. Dividers: Provide tabbed dividers for each separate product and system; identify the contents on the divider tab; immediately following the divider tab include a description of product and major component parts of equipment.
- H. Text: Manufacturer's printed data, or typewritten data on 20 pound paper.
- I. Drawings: Provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.
- J. Arrangement of Contents: Organize each volume in parts as follows:
 - 1. Project Directory.
 - 2. Table of Contents, of all volumes, and of this volume.
 - 3. Operation and Maintenance Data: Arranged by system, then by product category.
 - a. Source data.
 - b. Product data.
 - c. Operation and maintenance data.
 - d. Field quality control data.
 - e. Photocopies of warranties and bonds.

3.07 WARRANTIES AND BONDS

- A. Obtain warranties and bonds, executed in duplicate by responsible Subcontractors, suppliers, and manufacturers, within 15 days after completion of the applicable item of work. Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial completion is determined.
- B. Verify that documents are in proper form, contain full information, and are notarized.
- C. Retain warranties and bonds until time specified for submittal.
- D. Manual: Bind in commercial quality 8-1/2 by 11 inch three D side ring binders with durable plastic covers.
- E. Cover: Identify each binder on front and spine with typed or printed title WARRANTIES AND BONDS, with title of Project; name, address and telephone number of Contractor and equipment supplier; and name of responsible company principal.
- F. Table of Contents: Neatly typed, in the sequence of the Table of Contents of the Project Manual, with each item identified with the number and title of the specification section in which specified, and the name of product or work item.
- G. Separate each warranty or bond with index tab sheets keyed to the Table of Contents listing. Provide full information, using separate typed sheets as necessary. List Subcontractor,

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- supplier, and manufacturer, with name, address, and telephone number of responsible principal.
- H. Provide photocopy of each warranty in operation and maintenance manuals; locate each warranty with applicable O&M data for product or equipment.

END OF SECTION 017800

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 017900 DEMONSTRATION AND TRAINING

PART 1 GENERAL

1.01 SUMMARY

- A. Demonstration of products, systems, equipment, and other items where indicated in specific specification sections.
- B. Training of Owner personnel in operation and maintenance of products, systems, equipment, and as otherwise indicated in specific specification sections.

1.02 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Draft Training Plans: Owner will designate personnel to be trained; tailor training to needs and skill-level of attendees.
 - 1. Submit not less than four weeks prior to start of training.
 - 2. Revise and resubmit until acceptable.
 - 3. Provide an overall schedule showing all training sessions.
 - 4. Include at least the following for each training session:
 - a. Identification, date, time, and duration.
 - b. Description of products and/or systems to be covered.
 - c. Name of firm and person conducting training; include qualifications.
 - d. Intended audience, such as job description.
 - e. Objectives of training and suggested methods of ensuring adequate training.
 - f. Methods to be used, such as classroom lecture, live demonstrations, hands-on, etc.
 - g. Media to be used, such as slides, hand-outs, etc.
 - h. Training equipment required, such as projector, projection screen, etc., to be provided by Contractor.
- C. Training Manuals: Provide training manual for each attendee.
 - 1. Include applicable portion of O&M manuals.
 - 2. Include copies of all hand-outs, slides, overheads, video presentations, etc., that are not included in O&M manuals.
 - Provide one extra copy of each training manual to be included with operation and maintenance data.

D. Training Reports:

- 1. Identification of each training session, date, time, and duration.
- 2. Sign-in sheet showing names and job titles of attendees.
- 3. List of attendee questions and written answers given, including copies of and references to supporting documentation required for clarification; include answers to questions that could not be answered in original training session.
- E. Video Recordings: Submit digital video recording of each demonstration and training session for Owner's subsequent use.
 - 1. Format: DVD Disc.
 - 2. Label each disc and container with session identification and date.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3. Where available, provide manufacturer's pre-produced training videos in conjunction with live demonstration and training video.

1.03 QUALITY ASSURANCE

- A. Instructor Qualifications: Familiar with design, operation, maintenance and troubleshooting of the relevant products and systems.
 - Instructor shall be certified by the manufacturer or fabricator of system.
 - 2. Where a single person is not familiar with all aspects, provide specialists with necessary qualifications.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 DEMONSTRATION - GENERAL

- A. Demonstrations conducted during system start-up do not qualify as demonstrations for the purposes of this section, unless approved in advance by Owner.
- B. Demonstrations conducted during Functional Testing need not be repeated unless Owner personnel training is specified.
- C. Demonstration may be combined with Owner personnel training if applicable, and if acceptable to Owner.
- D. Operating Equipment and Systems: Demonstrate operation in all modes, including start-up, shut-down, seasonal changeover, emergency conditions, and troubleshooting, and maintenance procedures, including scheduled and preventive maintenance.
 - 1. Complete demonstrations within two weeks after the date of Substantial Completion.
 - 2. For equipment or systems requiring seasonal operation, perform demonstration for other season within six months.
- E. Non-Operating Products: Demonstrate cleaning, scheduled and preventive maintenance, and repair procedures.
 - 1. Complete demonstrations within two weeks after the date of Substantial Completion.

3.02 TRAINING - GENERAL

- Conduct training on-site, utilizing installed products and equipment, unless otherwise indicated.
- B. Provide training in minimum two hour segments.
- C. Training schedule will be subject to availability of Owner's personnel to be trained; re-schedule training sessions as required by Owner; once schedule has been approved by Owner failure to conduct sessions according to schedule will be cause for Owner to charge Contractor for personnel "show-up" time.
- D. Review of Facility Policy on Operation and Maintenance Data: During training discuss:
 - 1. Typical contents and organization of all manuals, including explanatory information, system narratives, and product specific information.
 - 2. Typical uses of the O&M manuals.
- E. Product- and System-Specific Training:
 - 1. Review the applicable O&M manuals.
 - 2. For systems, provide an overview of system operation, design parameters and constraints, and operational strategies.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 3. Review instructions for proper operation in all modes, including start-up, shut-down, seasonal changeover and emergency procedures, and for maintenance, including preventative maintenance.
- 4. Discuss cleaning products and procedures, including recommended cleaning products and products that are detrimental to equipment operation or finishes.
- 5. Provide hands-on training on all operational modes possible and preventive maintenance.
- 6. Emphasize safe and proper operating requirements; discuss relevant health and safety issues, warning or error indications, and emergency procedures and shutdown.
- 7. Discuss common troubleshooting problems and solutions. Include minor adjustments for resolving noise, vibration, and improving system efficiency.
- 8. Discuss any peculiarities of equipment installation or operation.
- 9. Discuss warranties and guarantees, including procedures necessary to avoid voiding coverage. Include discussion of continuing maintenance agreements and procedures.
- 10. Review recommended tools and spare parts inventory suggestions of manufacturers.
- 11. Review spare parts and tools required to be furnished by Contractor.
- 12. Review spare parts suppliers and sources and procurement procedures.
- F. Be prepared to answer questions raised by training attendees; if unable to answer during training session, provide written response within three days.

END OF SECTION 017900

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 018119 INDOOR AIR QUALITY REQUIREMENTS

PART 1 GENERAL

1.01 SUMMARY

- A. Provide Indoor Air Quality (IAQ) Management Plan to remain in force during the construction period.
- B. Chapter 3 of the Sheet Metal and Air Conditioning National Contractors' Association (SMACNA) IAQ Guideline for Occupied Buildings Under Construction, 2nd Edition 2007, available from SMACNA (703-803-2980 or www.smacna.org).

1.02 SUBMITTAL

A. Construction Indoor Air Quality Management Plan (CIAQM Plan).

PART 2 OBJECTIVES DURING CONSTRUCTION

2.01 PROTECTION

- A. Store all materials and equipment in a protected area (inside warehouse or storage trailer). Protect materials and equipment that are too large or heavy to store in a trailer from water and dirt/dust/debris.
 - OPTION: When stored outside, provide two layers of minimum 8-mil poly on the ground and elevate equipment or material a minimum of 4 inches to allow water to run off. Secure top and sides with two layers of 8-mil poly to prevent water penetration and dust/dirt accumulation.
- B. Protect HVAC equipment from dust and odors. Do not store equipment in areas near painting, pressure washing, or excavation. Do not operate equipment during cutting or grinding of masonry or concrete.
 - 1. Refer to Division 23 for construction filter requirements for protection of mechanical duct systems during construction.
 - 2. Clean ductwork when installed. Cap ends with poly during construction to prevent contamination.
 - 3. Do not operate HVAC system until the exterior walls, roof, glass, doors and building filters are properly installed.
 - 4. If air handlers must be used during construction, provide filtration media with a Minimum Efficiency Reporting Value (MERV) of 8 at each air-handling unit. Provide specified prefilters and final filters for operation during construction or install temporary 4-inch MERV 8 filters at each return air grille for operation during construction.
 - 5. Replace all filtration media immediately prior to Substantial Completion.
 - Filtration media installed in air-handling units shall have a Minimum Efficiency Reporting Value (MERV) of 8.
 - 6. Do not perform Testing and Balancing until dust or odor generating activities are completed.

2.02 SOURCE CONTROL

- A. Minimize IAQ contaminants introduced by construction materials.
- B. Store waste construction materials a minimum of 30 feet away from the building.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

C. Do not smoke within 30 feet of the exterior building perimeter.

2.03 PATHWAY INTERRUPTION

- A. Provide barriers to contain construction areas to allow a portion of the building to be cleaned and then operate the HVAC system in that cleaned area. Acceptable barriers include dust curtains and temporary walls.
 - 1. Protect areas of the building in which HVAC is operational by physical barriers from areas of the building not acceptable for operation of the HVAC system.
- B. Maintain areas within 30 feet of outdoor air intakes free of dust, dirt, debris, and volatile materials while the HVAC system is in operation.

2.04 HOUSEKEEPING

- A. As dust accumulates at the Site, it can become airborne when disturbed by nearby activity. Similarly, spills or excess applications of products containing solvents will increase odors at the Site. Leaving the Site wet or damp for more than a day could result in the growth of mold and bacteria. Therefore, Site cleanup and maintenance is important to maintaining good IAQ during construction.
- B. Perform the following to control contaminants at the Site:
 - 1. Suppress dust with wetting agents or sweeping compounds
 - 2. Provide an efficient dust collection method (e.g. a damp rag, wet mop, or vacuum equipped with a high efficiency particulate arrester (HEPA) filter or wet scrubber).
 - 3. Remove spills or excess applications of solvent-containing products immediately. Provide low-VOC emitting spot removers and cleaning agents near occupied areas.
 - 4. Remove accumulated water and keep work areas as dry as possible, including the use of dehumidification, if necessary.
 - 5. Once building is enclosed, vacuum with HEPA filtered vacuum cleaners to prevent settled dust from becoming airborne again.
 - Protect porous materials from exposure to moisture. Replace items that remain damp for more than four hours.

END OF SECTION 018119

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 024100 DEMOLITION

PART 1 GENERAL

1.01 DEFINITIONS

- A. "Remove": Carefully detach or dismantle items from existing construction and properly dispose of or recycle off site, unless items are indicated to be salvaged or reinstalled.
- B. "Salvage" or "Remove and Salvage": Carefully detach or dismantle items from existing construction in a manner to prevent damage. Clean, package, label and deliver salvaged items to Owner in ready-for-reuse condition. If indicated to be reinstalled, store in a secure area until ready for reinstallation.
- C. "Reinstall" or "Remove and Reinstall": Carefully detach or dismantle items from existing construction in a manner to prevent damage. Clean and prepare for reuse and reinstall where indicated.
- D. "Existing", "Existing to Remain" or "ETR": Designation for existing items that are not to be removed and that are not otherwise indicated to be salvaged or reinstalled.
 - Not all existing construction to remain shall be noted with one of these terms on the Drawings; the intent is to assist the Contractor in areas where it may be difficult to determine. Existing construction shall be assumed to remain unless specifically noted to be removed - either when noted with "remove", "salvage", or "reinstall" terminology per above, or when indicated graphically in accordance with the Demolition Legend on the Demolition Drawings.

1.02 REFERENCE STANDARDS

A. NFPA 241 - Standard for Safeguarding Construction, Alteration, and Demolition Operations 2022, with Errata (2021).

1.03 SUBMITTALS

- A. Photographic Documentation: Submit photographic record of the existing conditions, either as still photographs or as a video-recorded walkthrough. Contractor shall perform walkthrough of existing conditions with Owner's representative prior to site mobilization.
 - Photographic documentation shall clearly show existing damage and wear on existing surfaces that may be interpreted as being caused by subsequent demolition and construction operations.
 - 2. For still photographs, submit marked-up plan(s) indicating locations where photographs were taken and direction photograph is facing. Include a written narrative to describe existing damage and other conditions as deemed necessary.
 - 3. For video recordings, include a spoken narrative to describe locations and existing conditions, or provide a supplementary written narrative.
 - 4. Submit all photographic documentation as digital photo / video files, and supplementary narratives and plans as PDF files. Submit as part of the initial submittal package required prior to release of the first request for payment.
- B. Site Plan: Indicate:
 - 1. Areas for temporary construction and field offices.
- C. Project Record Documents: Accurately record actual locations of capped and active utilities and subsurface construction.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 2 PRODUCTS -- NOT USED

PART 3 EXECUTION

3.01 GENERAL PROCEDURES AND PROJECT CONDITIONS

- A. All demolition work shall be considered unclassified. Barring discovery of hazardous materials or undocumented structural components, where elements are indicated to be demolished, the bid price shall be for complete demolition of the element, regardless of the individual component makeup of that element.
- B. Comply with applicable codes and regulations for demolition operations and safety of adjacent structures and the public.
 - 1. Obtain required permits.
 - 2. Fire Safety: Comply with applicable requirements of the International Fire Code; Chapter 33, and with NFPA 241.
 - a. Use of explosives is not permitted.
 - b. Hot Work: Remove all combustibles from areas where hot work is required, including use of cutting torches, welding, or heating equipment. Maintain fire watch for entire duration of hot work and for a minimum 30 minutes after completion of hot work.
 - 1) Keep portable fire extinguishers within 30 feet of locations where hot work is being performed for entire duration.
 - c. Maintain egress routes and emergency access routes at all times; do not allow demolished materials to accumulate and block routes.
 - d. Remove combustible demolished materials from the building by the end of each work day. Temporarily store combustible materials in noncombustible containers with selfclosing lids until they can be removed from the building.
 - e. Do not burn demolished material on site.
 - Take precautions to prevent catastrophic or uncontrolled collapse of structures to be removed; do not allow worker or public access within range of potential collapse of unstable structures.
 - 4. Provide, erect, and maintain temporary barriers and security devices.
 - 5. Conduct operations to minimize effects on and interference with adjacent structures and occupants.
 - 6. Do not close or obstruct roadways or sidewalks without permits from authority having jurisdiction.
 - Conduct operations to minimize obstruction of public and private entrances and exits. Do
 not obstruct required exits at any time. Protect persons using entrances and exits from
 removal operations.
 - 8. Obtain written permission from owners of adjacent properties when demolition equipment will traverse, infringe upon, or limit access to their property.
- C. Do not begin removal until receipt of notification to proceed from Owner.
- D. Do not begin removal until built elements to be salvaged, relocated, or reinstalled have been removed.
- E. Protect existing structures and other elements to remain in place and not removed.
 - 1. Provide bracing and shoring.
 - 2. Prevent movement or settlement of adjacent structures.
 - 3. Stop work immediately if adjacent structures appear to be in danger.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- F. Minimize production of dust due to demolition operations. Do not use water if that will result in ice, flooding, sedimentation of public waterways or storm sewers, or other pollution.
- G. Hazardous Materials: It is not expected that hazardous materials will be encountered during performance of the Work.
 - If hazardous materials are discovered during removal operations, stop work and notify Architect and Owner; hazardous materials include regulated asbestos containing materials, lead, PCBs, and mercury.
- H. Perform demolition in a manner that maximizes salvage and recycling of materials.
 - 1. Dismantle existing construction and separate materials.
 - 2. Set aside reusable, recyclable, and salvageable materials; store and deliver to collection point or point of reuse.

3.02 EXISTING UTILITIES

- Coordinate work with utility companies. Notify utilities before starting work, comply with their requirements, and obtain required permits.
- B. Protect existing utilities to remain from damage.
- C. Do not disrupt public utilities without permit from authority having jurisdiction.
- D. Do not close, shut off, or disrupt existing life safety systems that are in use without at least 7 days prior written notification to Owner.
- E. Do not close, shut off, or disrupt existing utility branches or take-offs that are in use without at least 3 days prior written notification to Owner.
- F. Locate and mark utilities to remain; mark using highly visible tags or flags, with identification of utility type; protect from damage due to subsequent construction, using substantial barricades if necessary.
- G. Remove exposed piping, valves, meters, equipment, supports, and foundations of disconnected and abandoned utilities.

3.03 SELECTIVE DEMOLITION FOR ALTERATIONS

- A. Existing construction and utilities indicated on drawings are based on casual field observation and existing record documents only.
 - 1. Verify construction and utility arrangements are as indicated.
 - 2. Report discrepancies to Architect before disturbing existing installation.
 - 3. Beginning of demolition work constitutes acceptance of existing conditions that would be apparent upon examination prior to starting demolition.
- Separate areas in which demolition is being conducted from areas that remain occupied.
 - 1. Provide, erect, and maintain temporary dustproof partitions of construction specified in Section 015000 in locations indicated on drawings.
- C. Maintain weatherproof exterior building enclosure, except for interruptions required for replacement or modifications; prevent water and humidity damage.
- D. Remove existing work as indicated and required to accomplish new work.
 - 1. Remove items indicated on drawings.
- E. Services (Including but not limited to HVAC, Plumbing, Fire Protection, Electrical, and Telecommunications): Remove existing systems and equipment as indicated.
 - 1. Maintain existing active systems to remain in operation, and maintain access to equipment and operational components.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 2. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
- 3. Verify that abandoned services serve only abandoned facilities before removal.
- 4. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings. Remove back to source of supply where possible, otherwise cap stub and tag with identification.
- F. Floor Finishes: After removal of existing floor finishes including backings, underlayments, and thick set mortar beds, remove all residual adhesives and glue. Provide grinding, sanding, or shot-blasting of existing concrete floor slab to achieve the proper surface to receive new indicated floor finish. Coordinate slab surface preparations required for each new indicated floor finish with appropriate subcontractor.
- G. Concrete: Cut neatly in straight lines with power-driven saw with diamond-tooth blade or other type specifically intended for concrete and masonry. Break up and remove carefully, avoiding damage to adjacent flooring that will remain exposed in the finished work.
- H. Masonry: Remove masonry in whole units at exposed surfaces, new openings, and unless otherwise indicated, to allow for toothing-in of new masonry.
 - 1. Solid masonry may be cut with power saw where masonry edges will be concealed by the finished work. Do not cut hollow masonry.
- I. Existing Surfaces to Receive Finishes: Remove miscellaneous hangers, exposed nails not serving as fasteners, and similar protrusions; remove adhesive residue and tape; fill anchorage holes; and otherwise patch and restore surface to be a uniform substrate suitable for applied finishes.
- J. Protect existing work to remain.
 - 1. Prevent movement of structure. Provide shoring and bracing as required.
 - 2. Perform cutting to accomplish removal work neatly and as specified for cutting new work.
 - 3. Repair adjacent construction and finishes damaged during removal work.
 - Patch to match new work.

3.04 DEBRIS AND WASTE REMOVAL

- A. Remove debris, junk, and trash from site.
- B. Leave site in clean condition, ready for subsequent work.
- C. Clean up spillage and wind-blown debris from public and private lands.

END OF SECTION 024100

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 033000 - CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Cast-in-place concrete, including concrete materials, mixture design, placement procedures, and finishes.

1.3 DEFINITIONS

- A. Cementitious Materials: Portland cement alone or in combination with one or more of the following: fly ash, slag cement, other pozzolans, and silica fume; materials subject to compliance with requirements.
- B. Water/Cement Ratio (w/cm): The ratio by weight of water to cementitious materials.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at the project site.
 - 1. Require representatives of each entity directly concerned with cast-in-place concrete to attend, including the following:
 - a. Contractor's superintendent.
 - b. Independent testing agency responsible for concrete design mixtures.
 - c. Ready-mix concrete manufacturer.
 - d. Concrete Subcontractor.
 - e. Special concrete finish Subcontractor.

1.5 ACTION SUBMITTALS

- A. Product Data: For each of the following.
 - 1. Portland cement.
 - 2. Fly ash.
 - 3. Slag cement.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Silica fume.
- 5. Aggregates.
- 6. Admixtures:
 - a. Include limitations of use, including restrictions on cementitious materials, supplementary cementitious materials, air entrainment, aggregates, temperature at time of concrete placement, relative humidity at time of concrete placement, curing conditions, and use of other admixtures.
- 7. Vapor barriers.
- 8. Floor and slab treatments.
- 9. Liquid floor treatments.
- 10. Curing materials.
- 11. Joint fillers.
- 12. Repair materials
- 13. Steel reinforcement and accessories.
- B. Design Mixtures: For each concrete mixture, include the following:
 - 1. Mixture identification.
 - 2. Minimum 28-day compressive strength.
 - 3. Durability exposure class.
 - 4. Maximum w/cm.
 - 5. Calculated equilibrium unit weight, for lightweight concrete.
 - 6. Slump limit.
 - 7. Air content.
 - 8. Nominal maximum aggregate size.
 - 9. Indicate amounts of mixing water to be withheld for later addition at Project site if permitted.
 - 10. Include manufacturer's certification that permeability-reducing admixture is compatible with mix design.
 - 11. Include certification that dosage rate for permeability-reducing admixture matches dosage rate used in performance compliance test.
 - 12. Intended placement method.
 - 13. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.

C. Shop Drawings:

- 1. Construction Joint Layout: Indicate proposed construction joints required to construct the structure.
 - a. Location of construction joints is subject to approval of the Architect.
- 2. Steel Reinforcement Shop Drawings: Placing drawings that detail fabrication, bending, and placement. Include bar sizes, lengths, material, grade, bar schedules, stirrup spacing, bent bar diagrams, bar arrangement, splices and laps, mechanical connections, tie spacing, hoop spacing, and supports for concrete reinforcement.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Formwork Shop Drawings: Prepared by or under the supervision of a licensed professional engineer detailing fabrication, assembly, and support of formwork.
- D. Concrete Schedule: For each location of each Class of concrete indicated on the drawings, including the following:
 - 1. Concrete Class designation.
 - 2. Location within Project.
 - 3. Exposure Class designation.
 - 4. Formed Surface Finish designation and final finish.
 - 5. Final finish for floors.
 - 6. Curing process.
 - 7. Floor treatment if any.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For the following:
 - 1. Installer: Include copies of applicable ACI certificates.
 - 2. Ready-mixed concrete manufacturer.
 - 3. Testing agency: Include copies of applicable ACI certificates.
- B. Material Certificates: For each of the following, signed by manufacturers:
 - 1. Cementitious materials.
 - 2. Admixtures.
 - 3. Form materials and form-release agents.
 - 4. Steel reinforcement and accessories.
 - 5. Waterstops.
 - 6. Curing compounds.
 - 7. Floor and slab treatments.
 - 8. Bonding agents.
 - 9. Adhesives.
 - 10. Vapor barriers.
 - 11. Joint-filler strips.
 - 12. Repair materials.
- C. Material Test Reports: For the following, from a qualified testing agency:
 - 1. Portland cement.
 - 2. Fly ash.
 - 3. Slag cement.
 - 4. Silica fume.
 - 5. Aggregates.
 - 6. Admixtures:
 - a. Permeability-Reducing Admixture: Include independent test reports, indicating compliance with specified requirements, including dosage rate used in test.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. Floor surface flatness and levelness measurements report, indicating compliance with specified tolerances.
- E. Preconstruction Test Reports: For each mix design.
- F. Field quality-control reports.
- G. Minutes of preinstallation conference.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs Project personnel qualified as an ACI-certified Flatwork Technician and Finisher and a supervisor who is a certified ACI Flatwork Concrete Finisher/Technician or an ACI Concrete Flatwork Technician.
 - Post-Installed Concrete Anchors Installers: ACI-certified Adhesive Anchor Installer.
- B. Ready-Mixed Concrete Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C94/C94M requirements for production facilities and equipment.
 - 1. Manufacturer certified in accordance with NRMCA's "Certification of Ready Mixed Concrete Production Facilities."
- C. Laboratory Testing Agency Qualifications: A testing agency qualified in accordance with ASTM C1077 and ASTM E329 for testing indicated and employing an ACI-certified Concrete Quality Control Technical Manager.
 - 1. Personnel performing laboratory tests shall be an ACI-certified Concrete Strength Testing Technician and Concrete Laboratory Testing Technician, Grade I. Testing agency laboratory supervisor shall be an ACI-certified Concrete Laboratory Testing Technician, Grade II.
- D. Field Quality Control Testing Agency Qualifications: An independent agency, acceptable to authorities having jurisdiction, qualified in accordance with ASTM C1077 and ASTM E329 for testing indicated.
 - 1. Personnel conducting field tests shall be qualified as an ACI Concrete Field-Testing Technician, Grade 1, in accordance with ACI CP-1 or an equivalent certification program.
- E. Welding Qualifications: Qualify procedures and personnel according to AWS D1.4, "Structural Welding Code Reinforcing Steel."

1.8 PRECONSTRUCTION TESTING

A. Preconstruction Testing Service: Engage a qualified testing agency to perform preconstruction testing on each concrete mixture.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Include the following information in each test report:
 - a. Admixture dosage rates.
 - b. Slump.
 - c. Air content.
 - d. Seven-day compressive strength.
 - e. 28-day compressive strength.
 - f. Permeability.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Comply with ASTM C94/C94M and ACI 301 (ACI 301M).
- B. Steel Reinforcement: Deliver, store, and handle steel reinforcement to prevent bending and damage.
- C. Waterstops: Store waterstops under cover to protect from moisture, sunlight, dirt, oil, and other contaminants.

1.10 FIELD CONDITIONS

- A. Cold-Weather Placement: Comply with ACI 301 and ACI 306.1 and as follows.
 - 1. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
 - 2. When average high and low temperature is expected to fall below 40 deg F for three successive days, maintain delivered concrete mixture temperature within the temperature range required by ACI 301.
 - 3. Do not use frozen materials or materials containing ice or snow.
 - 4. Do not place concrete in contact with surfaces less than 35 deg F, other than reinforcing steel.
 - 5. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in mixture designs.
- B. Hot-Weather Placement: Comply with ACI 301 and ACI 305.1, and as follows:
 - 1. Maintain concrete temperature at time of placement to not exceed 90 deg F. Chilled mixing water or chopped ice may be used to control temperature, provided water equivalent of ice is calculated to total amount of mixing water.
 - 2. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade uniformly moist without standing water, soft spots, or dry areas.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 2 - PRODUCTS

2.1 CONCRETE, GENERAL

A. ACI Publications: Comply with ACI 301 unless modified by requirements in the Contract Documents.

2.2 CONCRETE MATERIALS

A. Source Limitations:

- 1. Obtain all concrete mixtures from a single ready-mixed concrete manufacturer for entire Project.
- 2. Obtain each type or class of cementitious material of the same brand from the same manufacturer's plant.
- 3. Obtain aggregate from single source.
- 4. Obtain each type of admixture from single source from single manufacturer.

B. Cementitious Materials:

- 1. Portland Cement: ASTM C150/C150M, Type I Type II or Type I/II. Supplement with the following:
- 2. Fly Ash: ASTM C618, Class F.
- 3. Slag Cement: ASTM C989/C989M, Grade 100 or 120.
- 4. Silica Fume: ASTM C1240 amorphous silica.
- C. Normal-Weight Aggregates: ASTM C33, Class 3M coarse aggregate or better, graded. Provide aggregates from a single source.
 - 1. Alkali-Silica Reaction: Comply with one of the following:
 - a. Expansion Result of Aggregate: Not more than 0.04 percent at one-year when tested in accordance with ASTM C1293.
 - b. Expansion Results of Aggregate and Cementitious Materials in Combination: Not more than 0.10 percent at an age of 16 days when tested in accordance with ASTM C1567.
 - c. Alkali Content in Concrete: Not more than 4 lb./cu. yd. for moderately reactive aggregate or 3 lb./cu. yd. for highly reactive aggregate, when tested in accordance with ASTM C1293 and categorized in accordance with ASTM C1778, based on alkali content being calculated in accordance with ACI 301.
 - 2. Maximum Coarse-Aggregate Size: As indicated.
 - 3. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement.
- D. Lightweight Aggregate: ASTM C330/C330M, maximum aggregate size as indicated.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- E. Air-Entraining Admixture: ASTM C260/C260M.
- F. Chemical Admixtures: Certified by manufacturer to be compatible with other admixtures that do not contribute water-soluble chloride ions exceeding those permitted in hardened concrete. Do not use calcium chloride or admixtures containing calcium.
 - 1. Water-Reducing Admixture: ASTM C494/C494M, Type A.
 - 2. Retarding Admixture: ASTM C494/C494M, Type B.
 - 3. Water-Reducing and -Retarding Admixture: ASTM C494/C494M, Type D.
 - 4. High-Range, Water-Reducing Admixture: ASTM C494/C494M, Type F.
 - 5. High-Range, Water-Reducing and -Retarding Admixture: ASTM C494/C494M, Type G.
 - 6. Plasticizing and Retarding Admixture: ASTM C1017/C1017M, Type II.
 - 7. Permeability-Reducing Admixture: ASTM C494/C494M, Type S, hydrophilic, permeability-reducing crystalline admixture, capable of reducing water absorption of concrete exposed to hydrostatic pressure (PRAH).
 - a. Permeability: No leakage when tested in accordance with U.S. Army Corps of Engineers CRC C48 at a hydraulic pressure of 200 psi for 14 days.
- G. Water and Water Used to Make Ice: ASTM C94/C94M, potable.

2.3 VAPOR BARRIERS

A. Sheet Vapor Barrier: ASTM E1745, Class A with a water-vapor permeance of less than 0.01 perms after mandatory conditioning (ASTM E1745, Section 7.1); not less than 15 mils thick. Include manufacturer's recommended adhesive or pressure-sensitive tape.

2.4 LIQUID FLOOR TREATMENTS

- A. VOC Content: Liquid floor treatments shall have a VOC content of 200g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- B. Penetrating Liquid Floor Treatment: Clear, chemically reactive, waterborne solution of inorganic silicate or siliconate materials and proprietary components; odorless; that penetrates, hardens, and densifies concrete surfaces.

2.5 CURING MATERIALS

- A. Evaporation Retarder: Waterborne, monomolecular film forming, manufactured for application to fresh concrete.
- B. Absorptive Cover: AASHTO M 182, Class 2, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. when dry.
- C. Moisture-Retaining Cover: ASTM C171, polyethylene film burlap-polyethylene sheet.
- D. Water: Potable.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

E. Clear, Waterborne, Membrane-Forming, Dissipating Curing Compound: ASTM C309, Type 1, Class B.

2.6 RELATED MATERIALS

- A. Expansion- and Isolation-Joint-Filler Strips: ASTM D1751, asphalt-saturated cellulosic fiber.
- B. Bonding Agent: ASTM C1059/C1059M, Type II, nonredispersible, acrylic emulsion or styrene butadiene.
- C. Epoxy Bonding Adhesive: ASTM C881, two-component epoxy resin, capable of humid curing and bonding to damp surfaces, of class suitable for application temperature and of grade and class to suit requirements, and as follows:
 - 1. Types IV and V, load bearing, for bonding hardened or freshly mixed concrete to hardened concrete.
- D. Floor Slab Protective Covering: Eight-feet- wide cellulose fabric.

2.7 REPAIR MATERIALS

- A. Repair Underlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/8 inch and that can be feathered at edges to match adjacent floor elevations.
 - 1. Cement Binder: ASTM C150/C150M portland cement or hydraulic or blended hydraulic cement, as defined in ASTM C219.
 - 2. Primer: Product of underlayment manufacturer recommended for substrate, conditions, and application.
 - 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch or coarse sand, as recommended by underlayment manufacturer.
 - 4. Compressive Strength: Not less than 5000 psi at 28 days when tested in accordance with ASTM C109/C109M.
- B. Repair Overlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/4 inch and that can be filled in over a scarified surface to match adjacent floor elevations.
 - 1. Cement Binder: ASTM C150/C150M portland cement or hydraulic or blended hydraulic cement, as defined in ASTM C219.
 - 2. Primer: Product of topping manufacturer recommended for substrate, conditions, and application.
 - 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch or coarse sand as recommended by topping manufacturer.
 - 4. Compressive Strength: Not less than 5000 psi at 28 days when tested in accordance with ASTM C109/C109M.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.8 CONCRETE MIXTURES, GENERAL

- A. Prepare design mixtures for each type and strength of concrete, proportioned on the basis of laboratory trial mixture or field test data, or both, in accordance with ACI 301.
 - 1. Use a qualified testing agency for preparing and reporting proposed mixture designs, based on laboratory trial mixtures.
- B. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland cement in concrete as follows:
 - 1. Fly Ash or Other Pozzolans: As indicated.
 - 2. Slag Cement: As indicated.
 - 3. Silica Fume: As indicated.
 - 4. Total of Fly Ash or Other Pozzolans, Slag Cement, and Silica Fume: As indicated.
 - 5. Total of Fly Ash or Other Pozzolans and Silica Fume: As indicated.
- C. Admixtures: Use admixtures in accordance with manufacturer's written instructions.
 - 1. Use high-range water-reducing admixture in concrete, as required, for placement and workability.
 - 2. Use water-reducing and -retarding admixture when required by high temperatures, low humidity, or other adverse placement conditions.
 - 3. Use water-reducing admixture in pumped concrete, concrete for heavy-use industrial slabs, concrete for parking structure slabs, and concrete with a w/cm below 0.50.
 - 4. Use permeability-reducing admixture in concrete mixtures where indicated.

2.9 CONCRETE MIXTURES

- A. Class Footings: Structural concrete used for footings.
 - 1. Exposure Class: As indicated.
 - 2. Minimum Compressive Strength: As indicated at 28 days.
 - 3. Maximum w/cm: As indicated.
 - 4. Slump Limit: 4 inches, plus or minus 1 inch; or 8 inches, plus or minus 1 inch for concrete with verified slump of 3 inches, plus or minus 1 inch before adding high-range water-reducing admixture or plasticizing admixture.
 - 5. Limit water-soluble, chloride-ion content in hardened concrete as indicated.
- B. Class Exterior Walls, Columns, and Piers: Structural concrete used for exterior walls, columns, and piers.
 - 1. Exposure Class: As indicated.
 - 2. Minimum Compressive Strength: As indicated at 28 days.
 - 3. Maximum w/cm: As indicated.
 - 4. Slump Limit: 4 inches, plus or minus 1 inch; or 8 inches, plus or minus 1 inch for concrete with verified slump of 3 inches, plus or minus 1 inch, before adding high-range water-reducing admixture or plasticizing admixture.
 - 5. Air Content: As indicated.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 6. Limit water-soluble, chloride-ion content in hardened concrete as indicated.
- C. Class Interior Slab-on-Grade: Structural concrete used for interior slabs-on-ground.
 - 1. Exposure Class: As indicated.
 - 2. Minimum Compressive Strength: As indicated at 28 days.
 - 3. Maximum w/cm: As indicated.
 - 4. Minimum Cementitious Materials Content: 470 lb/cu. yd..
 - 5. Slump Limit: 4 inches, plus or minus 1.
 - 6. Air Content:
 - a. Do not use an air-entraining admixture or allow total air content to exceed 3 percent for concrete used in trowel-finished floors.
 - 7. Limit water-soluble, chloride-ion content in hardened concrete as indicated.
- D. Class Interior Slab on Metal Deck Normal Weight: Structural normal weight concrete used for interior suspended slabs on metal deck.
 - 1. Exposure Class: As indicated.
 - 2. Minimum Compressive Strength: As indicated at 28 days.
 - 3. Maximum w/cm: As indicated.
 - 4. Minimum Cementitious Materials Content: 470 lb/cu. yd..
 - 5. Slump Limit: 4 inches, plus or minus 1 inch.
 - 6. Air Content:
 - a. Do not use an air-entraining admixture or allow total air content to exceed 3 percent for concrete used in trowel-finished floors.
 - 7. Limit water-soluble, chloride-ion content in hardened concrete as indicated.
- E. Class Interior Slab on Metal Deck Light Weight: Structural lightweight concrete used for interior suspended slabs on metal deck.
 - 1. Exposure Class: As indicated.
 - 2. Minimum Compressive Strength: As indicated at 28 days.
 - 3. Calculated Equilibrium Unit Weight: As indicated, as determined by ASTM C567/C567M.
 - 4. Slump Limit: 4 inches, plus or minus 1 inch.
 - 5. Air Content:
 - a. Do not use an air-entraining admixture or allow total air content to exceed 3 percent for concrete used in trowel-finished floors.
 - 6. Limit water-soluble, chloride-ion content in hardened concrete as indicated.
- F. Class Interior Beams and elevated slabs: Structural concrete used for interior beams and elevated slabs not in contact with soil
 - 1. Exposure Class: As indicated.
 - 2. Minimum Compressive Strength: As indicated at 28 days.
 - 3. Maximum w/cm: As indicated.
 - 4. Slump Limit: 4 inches, plus or minus 1 inch.
 - 5. Air Content:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Do not use an air-entraining admixture or allow total air content to exceed 3 percent for concrete used in trowel-finished floors.
- 6. Limit water-soluble, chloride-ion content in hardened concrete as indicated.
- G. Class Interior Walls, Columns, & Piers: Structural concrete used for interior walls, columns, and piers.
 - 1. Exposure Class: As indicated.
 - 2. Minimum Compressive Strength: As indicated at 28 days.
 - 3. Maximum w/cm: As indicated.
 - 4. Slump Limit: 4 inches, plus or minus 1 inch, or 8 inches, plus or minus 1 inch for concrete with verified slump of 3 inches, plus or minus 1 inch, before adding high-range water-reducing admixture or plasticizing admixture.
 - 5. Air Content: As indicated.
 - 6. Limit water-soluble, chloride-ion content in hardened concrete as indicated.
- H. Class Grade Beams: Structural concrete used for grade beams in contact with soil.
 - 1. Exposure Class: As indicated.
 - 2. Minimum Compressive Strength: As indicated at 28 days.
 - 3. Maximum w/cm: As indicated.
 - 4. Slump Limit: 4 inches, plus or minus 1 inch.
 - 5. Air Content: As indicated.
 - 6. Limit water-soluble, chloride-ion content in hardened concrete as indicated.

2.10 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, mix, and deliver concrete in accordance with ASTM C94, and furnish batch ticket information.
- B. Project-Site Mixing: Measure, batch, and mix concrete materials and concrete in accordance with ASTM C94/C94M. Mix concrete materials in appropriate drum-type batch machine mixer.
 - 1. For mixer capacity of 1 cu. yd. or smaller, continue mixing at least 1-1/2 minutes, but not more than five minutes after ingredients are in mixer, before any part of batch is released.
 - 2. For mixer capacity larger than 1 cu. yd., increase mixing time by 15 seconds for each additional 1 cu. yd..
 - 3. Provide batch ticket for each batch discharged and used in the Work, indicating Project identification name and number, date, mixture type, mixture time, quantity, and amount of water added. Record approximate location of final deposit in structure.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verification of Conditions:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Before placing concrete, verify that installation of concrete forms, accessories, and reinforcement, and embedded items is complete and that required inspections have been performed.
- 2. Do not proceed until unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Provide reasonable auxiliary services to accommodate field testing and inspections, acceptable to testing agency, including the following:
 - 1. Daily access to the Work.
 - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 - 3. Secure space for storage, initial curing, and field curing of test samples, including source of water and continuous electrical power at Project site during site curing period for test samples.
 - 4. Security and protection for test samples and for testing and inspection equipment at Project site.

3.3 INSTALLATION OF EMBEDDED ITEMS

- A. Place and secure anchorage devices and other embedded items required for adjoining Work that is attached to or supported by cast-in-place concrete.
 - 1. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 2. Install anchor rods, accurately located, to elevations required and complying with tolerances in Section 7.5 of ANSI/AISC 303.
 - 3. Install reglets to receive waterproofing and to receive through-wall flashings in outer face of concrete frame at exterior walls, where flashing is shown at lintels, shelf angles, and other conditions.

3.4 INSTALLATION OF VAPOR BARRIER

- A. Sheet Vapor Barriers: Place, protect, and repair sheet vapor barrier in accordance with ASTM E1643 and manufacturer's written instructions.
 - 1. Install vapor barrier with longest dimension parallel with direction of concrete pour.
 - 2. Face laps away from exposed direction of concrete pour.
 - 3. Lap vapor barrier over footings and grade beams not less than 6 inches, sealing vapor retarder to concrete.
 - 4. Lap joints 6 inches and seal with manufacturer's recommended tape.
 - 5. Terminate vapor barrier at the top of floor slabs, grade beams, and pile caps, sealing entire perimeter to floor slabs, grade beams, foundation walls, or pile caps.
 - 6. Seal penetrations in accordance with vapor barrier manufacturer's instructions.
 - 7. Protect vapor barrier during placement of reinforcement and concrete.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

a. Repair damaged areas by patching with vapor barrier material, overlapping damages area by 6 inches on all sides, and sealing to vapor barrier.

3.5 JOINTS

- A. Construct joints true to line, with faces perpendicular to surface plane of concrete.
- B. Construction Joints: Place concrete monolithically. Construction Joints may be permitted only after approval of the Engineer.
- C. Control Joints in Slabs-on-Ground: Form weakened-plane control joints, sectioning concrete into areas as indicated. Construct control joints for a depth equal to at least one-fourth of concrete thickness as follows:
 - 1. Sawed Joints: Form control joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch-wide joints into concrete when cutting action does not tear, abrade, or otherwise damage surface and before concrete develops random cracks.
- D. Isolation Joints in Slabs-on-Ground: After removing formwork, install joint-filler strips at slab junctions with vertical surfaces, such as column pedestals, foundation walls, grade beams, and other locations, as indicated.
 - 1. Extend joint-filler strips full width and depth of joint, terminating flush with finished concrete surface unless otherwise indicated.
 - 2. Terminate full-width joint-filler strips not less than 1/2 inch or more than 1 inch below finished concrete surface, where joint sealants, specified in Division 07 are indicated.
 - 3. Install joint-filler strips in lengths as long as practicable. Where more than one length is required, lace or clip sections together.

E. Doweled Joints:

- 1. Install dowel bars and support assemblies at joints where indicated.
- 2. Lubricate or asphalt coat one-half of dowel bar length to prevent concrete bonding to one side of joint.
- F. Dowel Plates: Install dowel plates at joints, where indicated on Drawings.

3.6 CONCRETE PLACEMENT

- A. Before placing concrete, verify that installation of formwork, reinforcement, embedded items, and vapor barrier is complete and that required inspections are completed.
 - 1. Immediately prior to concrete placement, inspect vapor barrier for damage and deficient installation, and repair defective areas.
 - 2. Provide continuous inspection of vapor barrier during concrete placement and make necessary repairs to damaged areas as Work progresses.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Notify Architect and testing and inspection agencies 24 hours prior to commencement of concrete placement.
- C. Before test sampling and placing concrete, water may be added at Project site, subject to limitations of ACI 301, but not to exceed the amount indicated on the concrete delivery ticket.
 - 1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.
- D. Deposit concrete continuously in one layer or in horizontal layers of such thickness that no new concrete is placed on concrete that has hardened enough to cause seams or planes of weakness.
 - 1. If a section cannot be placed continuously, provide construction joints as indicated.
 - 2. Deposit concrete to avoid segregation.
 - 3. Deposit concrete in horizontal layers of depth not to exceed formwork design pressures and in a manner to avoid inclined construction joints.
 - 4. Consolidate placed concrete with mechanical vibrating equipment in accordance with ACI 301.
 - a. Do not use vibrators to transport concrete inside forms.
 - b. Insert and withdraw vibrators vertically at uniformly spaced locations to rapidly penetrate placed layer and at least 6 inches into preceding layer.
 - c. Do not insert vibrators into lower layers of concrete that have begun to lose plasticity.
 - d. At each insertion, limit duration of vibration to time necessary to consolidate concrete, and complete embedment of reinforcement and other embedded items without causing mixture constituents to segregate.
- E. Deposit and consolidate concrete for floors and slabs in a continuous operation, within limits of construction joints, until placement of a panel or section is complete.
 - 1. Do not place concrete floors and slabs in a checkerboard sequence.
 - 2. Consolidate concrete during placement operations, so concrete is thoroughly worked around reinforcement and other embedded items and into corners.
 - 3. Maintain reinforcement in position on chairs during concrete placement.
 - 4. Screed slab surfaces with a straightedge and strike off to correct elevations.
 - 5. Level concrete, cut high areas, and fill low areas.
 - 6. Slope surfaces uniformly to drains where required.
 - 7. Begin initial floating using bull floats or darbies to form a uniform and open-textured surface plane, before excess bleedwater appears on the surface.
 - 8. Do not further disturb slab surfaces before starting finishing operations.

3.7 FINISHING FORMED SURFACES

- A. As-Cast Surface Finishes:
 - 1. ACI 301 Surface Finish SF-2.0: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams.
 - a. Patch voids larger than 3/4 inch wide or 1/2 inch deep.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- b. Remove projections larger than 1/4 inch.
- c. Patch tie holes.
- d. Surface Tolerance: ACI 117 Class B.
- e. Locations: Apply to concrete surfaces not exposed to public view.

B. Rubbed Finish: Apply the following to as cast surface finishes where indicated:

1. Smooth-Rubbed Finish:

- a. Perform no later than one day after form removal.
- b. Moisten concrete surfaces and rub with carborundum brick or another abrasive until producing a uniform color and texture.

2. Grout-Cleaned Rubbed Finish:

- a. Clean concrete surfaces after contiguous surfaces are completed and accessible.
- b. Do not clean concrete surfaces as Work progresses.
- c. Mix 1-part portland cement to 1-1/2 parts fine sand, complying with ASTM C144 or ASTM C404, by volume, with sufficient water to produce a mixture with the consistency of thick paint. Add white portland cement in amounts determined by trial patches, so color of dry grout matches adjacent surfaces.
- d. Wet concrete surfaces.
- e. Scrub grout into voids and remove excess grout. When grout whitens, rub surface with clean burlap, and keep surface damp by fog spray for at least 36 hours.

C. Related Unformed Surfaces:

- 1. At tops of walls, horizontal offsets, and similar unformed surfaces adjacent to formed surfaces, strike off smooth and finish with a color and texture matching adjacent formed surfaces.
- 2. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces unless otherwise indicated.

3.8 FINISHING FLOORS AND SLABS

A. Comply with ACI 302.1R recommendations for screeding, restraightening, and finishing operations for concrete surfaces. Do not wet concrete surfaces.

B. Scratch Finish:

- 1. While still plastic, texture concrete surface that has been screeded and bull-floated or darbied.
- 2. Use stiff brushes, brooms, or rakes to produce a profile depth of 1/4 inch in one direction.
- 3. Apply scratch finish to surfaces indicated and to receive concrete floor toppings and to receive mortar setting beds for bonded cementitious floor finishes.

C. Float Finish:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. When bleedwater sheen has disappeared and concrete surface has stiffened sufficiently to permit operation of specific float apparatus, consolidate concrete surface with power-driven floats or by hand floating if area is small or inaccessible to power-driven floats.
- 2. Repeat float passes and restraightening until surface is left with a uniform, smooth, granular texture and complies with ACI 117 tolerances for conventional concrete.
- 3. Apply float finish to surfaces indicated, to surfaces to receive trowel finish and to be covered with fluid-applied or sheet waterproofing, built-up or membrane roofing, or sand-bed terrazzo.

D. Trowel Finish:

- 1. After applying float finish, apply first troweling and consolidate concrete by hand or power-driven trowel.
- 2. Continue troweling passes and restraighten until surface is free of trowel marks and uniform in texture and appearance.
- 3. Grind smooth any surface defects that would telegraph through applied coatings or floor coverings.
- 4. Do not add water to concrete surface.
- 5. Do not apply hard-troweled finish to concrete, which has a total air content greater than 3 percent.
- 6. Apply a trowel finish to surfaces indicated and to surfaces exposed to view or to be covered with resilient flooring, carpet, ceramic, or quarry tile set over a cleavage membrane, paint, or another thin-film-finish coating system.
- 7. Finish surfaces to the following tolerances, in accordance with ASTM E1155, for a randomly trafficked floor surface:

a. Slabs on Ground:

- 1) Specified overall values of flatness, F_F 35; and of levelness, F_L 25; with minimum local values of flatness, F_F 24; and of levelness, F_L 17.
- 2) At areas receiving a polished concrete floor finish, specified overall values of flatness, F_F 50; and of levelness, F_L 35; with minimum local values of flatness, F_F 40; and of levelness, F_L 24.

b. Suspended Slabs:

- 1) Specified overall values of flatness, F_F 35; and of levelness, F_L 25; with minimum local values of flatness, F_F 24; and of levelness, F_L 17.
- E. Trowel and Fine-Broom Finish: Apply a first trowel finish to surfaces indicated and to surfaces where ceramic or quarry tile is to be installed by either thickset or thinset method. While concrete is still plastic, slightly scarify surface with a fine broom perpendicular to main traffic route.
 - 1. Coordinate required final finish with Architect before application.
 - 2. Comply with flatness and levelness tolerances for trowel-finished floor surfaces.
- F. Broom Finish: Apply a broom finish to exterior concrete platforms, steps, ramps, and locations indicated on Drawings.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Immediately after float finishing, slightly roughen trafficked surface by brooming with fiber-bristle broom perpendicular to main traffic route.
- 2. Coordinate required final finish with Architect before application.

3.9 INSTALLATION OF MISCELLANEOUS CONCRETE ITEMS

A. Filling In:

- 1. Fill in holes and openings left in concrete structures after Work of other trades is in place unless otherwise indicated.
- 2. Mix, place, and cure concrete, as specified, to blend with in-place construction.
- 3. Provide other miscellaneous concrete filling indicated or required to complete the Work.
- B. Curbs: Provide monolithic finish to interior curbs by stripping forms while concrete is still green and by steel-troweling surfaces to a hard, dense finish with corners, intersections, and terminations slightly rounded.

C. Equipment Bases and Foundations:

- 1. Coordinate sizes and locations of concrete bases with actual equipment provided.
- 2. Minimum Compressive Strength: 3500 psi at 28 days.
- 3. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of concrete base.
- 4. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete substrate.
- 5. Prior to pouring concrete, place and secure anchorage devices.
 - a. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - b. Cast anchor-bolt insert into bases.
 - c. Install anchor bolts to elevations required for proper attachment to supported equipment.

3.10 CONCRETE CURING

- A. Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.
 - 1. Comply with ACI 301 and ACI 306.1 for cold weather protection during curing.
 - 2. Comply with ACI 301 and ACI 305.1 for hot-weather protection during curing.
 - 3. Maintain moisture loss no more than 0.2 lb/sq. ft. x h, calculated in accordance with ACI 305.1, before and during finishing operations.

B. Curing Formed Surfaces: Comply with ACI 308.1 as follows:

- 1. Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces.
- 2. Cure concrete containing color pigments in accordance with color pigment manufacturer's instructions.
- 3. If forms remain during curing period, moist cure after loosening forms.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. If removing forms before end of curing period, continue curing for remainder of curing period, as follows:
 - a. Continuous Fogging: Maintain standing water on concrete surface until final setting of concrete.
 - b. Continuous Sprinkling: Maintain concrete surface continuously wet.
 - c. Absorptive Cover: Pre-dampen absorptive material before application; apply additional water to absorptive material to maintain concrete surface continuously wet.
 - d. Water-Retention Sheeting Materials: Cover exposed concrete surfaces with sheeting material, taping, or lapping seams.
 - e. Membrane-Forming Curing Compound: Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's written instructions.
 - 1) Recoat areas subject to heavy rainfall within three hours after initial application.
 - 2) Maintain continuity of coating and repair damage during curing period.
- C. Curing Unformed Surfaces: Comply with ACI 308.1 as follows:
 - 1. Begin curing immediately after finishing concrete.
 - 2. Interior Concrete Floors:
 - a. Floors to Receive Floor Coverings Specified in Other Sections: Contractor has option of the following:
 - 1) Absorptive Cover: As soon as concrete has sufficient set to permit application without marring concrete surface, install prewetted absorptive cover over entire area of floor.
 - a) Lap edges and ends of absorptive cover not less than 12-inches.
 - b) Maintain absorptive cover water saturated, and in place, for duration of curing period, but not less than seven days.
 - 2) Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches, and sealed by waterproof tape or adhesive.
 - a) Immediately repair any holes or tears during curing period, using cover material and waterproof tape.
 - b) Cure for not less than seven days.
 - 3) Ponding or Continuous Sprinkling of Water: Maintain concrete surfaces continuously wet for not less than seven days, utilizing one, or a combination of, the following:
 - a) Water.
 - b) Continuous water-fog spray.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- b. Floors to Receive Penetrating Liquid Floor Treatments: Contractor has option of the following:
 - 1) Absorptive Cover: As soon as concrete has sufficient set to permit application without marring concrete surface, install prewetted absorptive cover over entire area of floor.
 - a) Lap edges and ends of absorptive cover not less than 12 inches.
 - b) Maintain absorptive cover water saturated, and in place, for duration of curing period, but not less than seven days.
 - 2) Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches, and sealed by waterproof tape or adhesive.
 - a) Immediately repair any holes or tears during curing period, using cover material and waterproof tape.
 - b) Cure for not less than seven days.
 - 3) Ponding or Continuous Sprinkling of Water: Maintain concrete surfaces continuously wet for not less than seven days, utilizing one, or a combination of, the following:
 - a) Water.
 - b) Continuous water-fog spray.
- c. Floors to Receive Polished Finish: Contractor has option of the following:
 - 1) Absorptive Cover: As soon as concrete has sufficient set to permit application without marring concrete surface, install prewetted absorptive cover over entire area of floor.
 - a) Lap edges and ends of absorptive cover not less than 12 inches.
 - b) Maintain absorptive cover water saturated, and in place, for duration of curing period, but not less than seven days.
 - 2) Ponding or Continuous Sprinkling of Water: Maintain concrete surfaces continuously wet for not less than seven days, utilizing one, or a combination of, the following:
 - a) Water
 - b) Continuous water-fog spray.
- d. Floors to Receive Chemical Stain:
 - 1) As soon as concrete has sufficient set to permit application without marring concrete surface, install curing paper over entire area of floor.
 - 2) Install curing paper square to building lines, without wrinkles, and in a single length without end joints.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3) Butt sides of curing paper tight; do not overlap sides of curing paper.
- 4) Leave curing paper in place for duration of curing period, but not less than 28 days.

e. Floors to Receive Urethane Flooring:

- 1) As soon as concrete has sufficient set to permit application without marring concrete surface, install prewetted absorptive cover over entire area of floor.
- 2) Rewet absorptive cover and cover immediately with polyethylene moistureretaining cover with edges lapped 6 inches and sealed in place.
- 3) Secure polyethylene moisture-retaining cover in place to prohibit air from circulating under polyethylene moisture-retaining cover.
- 4) Leave absorptive cover and polyethylene moisture-retaining cover in place for duration of curing period, but not less than 28 days.

f. Floors to Receive Curing Compound:

- 1) Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's written instructions.
- 2) Recoat areas subjected to heavy rainfall within three hours after initial application.
- 3) Maintain continuity of coating, and repair damage during curing period.
- 4) Removal: After curing period has elapsed, remove curing compound without damaging concrete surfaces by method recommended by curing compound manufacturer unless manufacturer certifies curing compound does not interfere with bonding of floor covering used on Project.

g. Floors to Receive Curing and Sealing Compound:

- 1) Apply uniformly to floors and slabs indicated in a continuous operation by power spray or roller in accordance with manufacturer's written instructions.
- 2) Recoat areas subjected to heavy rainfall within three hours after initial application.
- 3) Repeat process 24 hours later and apply a second coat. Maintain continuity of coating, and repair damage during curing period.
- h. Terrazzo Floor Areas: At areas to receive terrazzo flooring, cure concrete for a minimum of 28 days. Do not use curing agents in areas to receive terrazzo flooring.

3.11 TOLERANCES

A. Conform to ACI 117.

3.12 APPLICATION OF LIQUID FLOOR TREATMENTS

A. Penetrating Liquid Floor Treatment: Prepare, apply, and finish penetrating liquid floor treatment in accordance with manufacturer's written instructions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Remove curing compounds, sealers, oil, dirt, laitance, and other contaminants and complete surface repairs.
- 2. Do not apply to concrete that is less than 28 days' old.
- 3. Apply liquid until surface is saturated, scrubbing into surface until a gel forms; rewet; and repeat brooming or scrubbing.
- 4. Rinse with water; remove excess material until surface is dry.
- 5. Apply a second coat in a similar manner if surface is rough or porous.
- B. Sealing Coat: Uniformly apply a continuous sealing coat of curing and sealing compound to hardened concrete by power spray or roller in accordance with manufacturer's written instructions.

3.13 JOINT FILLING

- A. Prepare, clean, and install joint filler in accordance with manufacturer's written instructions.
 - 1. Defer joint filling until concrete has aged at least six month(s).
 - 2. Do not fill joints until construction traffic has permanently ceased.
- B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joints clean and dry.
- C. Install semirigid joint filler full depth in saw-cut joints and at least 2 inches deep in formed joints.
- D. Overfill joint, and trim joint filler flush with top of joint after hardening.

3.14 CONCRETE SURFACE REPAIRS

- A. Defective Concrete:
 - 1. Repair and patch defective areas when approved by Architect.
 - 2. Remove and replace concrete that cannot be repaired and patched to Architect's approval.
- B. Patching Mortar: Mix dry-pack patching mortar, consisting of 1-part portland cement to 2-1/2 parts fine aggregate passing a No. 16 sieve, using only enough water for handling and placing.
- C. Repairing Formed Surfaces: Surface defects include color and texture irregularities, cracks, spalls, air bubbles, honeycombs, rock pockets, fins and other projections on the surface, and stains and other discolorations that cannot be removed by cleaning.
 - 1. Immediately after form removal, cut out honeycombs, rock pockets, and voids more than 1/2 inch in any dimension to solid concrete.
 - a. Limit cut depth to 3/4 inch.
 - b. Make edges of cuts perpendicular to concrete surface.
 - c. Clean, dampen with water, and brush-coat holes and voids with bonding agent.
 - d. Fill and compact with patching mortar before bonding agent has dried.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- e. Fill form-tie voids with patching mortar or cone plugs secured in place with bonding agent.
- 2. Repair defects on surfaces exposed to view by blending white portland cement and standard portland cement, so that, when dry, patching mortar matches surrounding color.
 - a. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching.
 - b. Compact mortar in place and strike off slightly higher than surrounding surface.
- 3. Repair defects on concealed formed surfaces that will affect concrete's durability and structural performance as determined by Architect.

D. Repairing Unformed Surfaces:

- 1. Test unformed surfaces, such as floors and slabs, for finish, and verify surface tolerances specified for each surface.
 - a. Correct low and high areas.
 - b. Test surfaces sloped to drain for trueness of slope and smoothness; use a sloped template.
- 2. Repair finished surfaces containing surface defects, including spalls, popouts, honeycombs, rock pockets, crazing, and cracks in excess of 0.01 inch wide or that penetrate to reinforcement or completely through unreinforced sections regardless of width, and other objectionable conditions.
- 3. After concrete has cured at least 14 days, correct high areas by grinding.
- 4. Correct localized low areas during, or immediately after, completing surface-finishing operations by cutting out low areas and replacing with patching mortar.
 - a. Finish repaired areas to blend into adjacent concrete.
- 5. Correct other low areas scheduled to receive floor coverings with a repair underlayment.
 - a. Prepare, mix, and apply repair underlayment and primer in accordance with manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.
 - b. Feather edges to match adjacent floor elevations.
- 6. Repair defective areas, except random cracks and single holes 1 inch or less in diameter, by cutting out and replacing with fresh concrete.
 - a. Remove defective areas with clean, square cuts, and expose steel reinforcement with at least a 3/4-inch clearance all around.
 - b. Dampen concrete surfaces in contact with patching concrete and apply bonding agent.
 - c. Mix patching concrete of same materials and mixture as original concrete, except without coarse aggregate.
 - d. Place, compact, and finish to blend with adjacent finished concrete.
 - e. Cure in same manner as adjacent concrete.
- 7. Repair random cracks and single holes 1 inch or less in diameter with patching mortar.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Groove top of cracks and cut out holes to sound concrete, and clean off dust, dirt, and loose particles.
- b. Dampen cleaned concrete surfaces and apply bonding agent.
- c. Place patching mortar before bonding agent has dried.
- d. Compact patching mortar and finish to match adjacent concrete.
- e. Keep patched area continuously moist for at least 72 hours.
- E. Perform structural repairs of concrete, subject to Architect's approval, using epoxy adhesive and patching mortar.
- F. Repair materials and installation not specified above may be used, subject to Architect's approval.

3.15 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a special inspector to perform field tests and inspections and prepare testing and inspection reports.
- B. Testing Agency: Owner will engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports.
 - 1. Testing agency shall be responsible for providing curing container for composite samples on Site and verifying that field-cured composite samples are cured in accordance with ASTM C31.
 - 2. Testing agency shall immediately report to Architect, Contractor, and concrete manufacturer any failure of Work to comply with Contract Documents.
 - 3. Testing agency shall report results of tests and inspections, in writing, to Owner, Architect, Contractor, and concrete manufacturer within 48 hours of inspections and tests.
 - a. Test reports shall include reporting requirements of ASTM C31, ASTM C39, and ACI 301, including the following as applicable to each test and inspection:
 - 1) Project name.
 - 2) Name of testing agency.
 - 3) Names and certification numbers of field and laboratory technicians performing inspections and testing.
 - 4) Name of concrete manufacturer.
 - 5) Date and time of inspection, sampling, and field testing.
 - 6) Date and time of concrete placement.
 - 7) Location in Work of concrete represented by samples.
 - 8) Date and time sample was obtained.
 - 9) Truck and batch ticket numbers.
 - 10) Design compressive strength at 28 days.
 - 11) Concrete mixture designation, proportions, and materials.
 - 12) Field test results.
 - 13) Information on storage and curing of samples before testing, including curing method and maximum and minimum temperatures during initial curing period.
 - 14) Type of fracture and compressive break strengths at seven days and 28 days.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

C. Batch Tickets: For each load delivered, submit three copies of batch delivery ticket to testing agency, indicating quantity, mix identification, admixtures, design strength, aggregate size, design air content, design slump at time of batching, and amount of water that can be added at Project site.

D. Inspections:

- 1. Headed bolts and studs.
- 2. Verification of use of required design mixture.
- 3. Concrete placement, including conveying and depositing.
- 4. Curing procedures and maintenance of curing temperature.
- 5. Verification of concrete strength before removal of shores and forms from beams and slabs
- 6. Batch Plant Inspections: On a random basis, as determined by Architect.
- E. Concrete Tests: Testing of composite samples of fresh concrete obtained in accordance with ASTM C 172 shall be performed in accordance with the following requirements:
 - 1. Testing Frequency: Obtain one composite sample for each day's pour of each concrete mixture exceeding 5 cu. yd., but less than 25 cu. yd., plus one set for each additional 50 cu. yd. or fraction thereof.
 - a. When frequency of testing provides fewer than five compressive-strength tests for each concrete mixture, testing shall be conducted from at least five randomly selected batches or from each batch if fewer than five are used.

2. Slump: ASTM C143:

- a. One test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture.
- b. Perform additional tests when concrete consistency appears to change.
- 3. Air Content: ASTM C231 pressure method, for normal-weight concrete; ASTM C173 volumetric method, for structural lightweight concrete.
 - a. One test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
- 4. Concrete Temperature: ASTM C1064:
 - a. One test hourly when air temperature is 40 deg F and below or 80 deg F and above, and one test for each composite sample.
- 5. Unit Weight: ASTM C567 fresh unit weight of structural lightweight concrete.
 - a. One test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
- 6. Compression Test Specimens: ASTM C31:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Cast and laboratory cure one set of five 6-inch by 12-inch or 4-inch by 8-inch cylinder specimens for each composite sample.
- 7. Compressive-Strength Tests: ASTM C39/C39M.
 - a. Test one laboratory-cured specimen at seven days and one set of three specimens at 28 days and hold one specimen for test at 56 days.
 - b. A compressive-strength test shall be the average compressive strength from a set of three specimens obtained from same composite sample and tested at age indicated.
- 8. Strength of each concrete mixture will be satisfactory if every average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength, and no compressive-strength test value falls below specified compressive strength by more than 500 psi if specified compressive strength is 5000 psi, or no compressive strength test value is less than 10 percent of specified compressive strength if specified compressive strength is greater than 5000 psi.
- 9. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
- 10. Additional Tests:
 - a. Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, temperature, placement time, or other requirements have not been met, as directed by Architect.
 - b. Testing and inspecting agency may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C42 or by other methods as directed by Architect.
 - 1) Acceptance criteria for concrete strength shall be in accordance with ACI 301, section 1.6.6.3.
- 11. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.
- 12. Correct deficiencies in the Work that test reports and inspections indicate do not comply with the Contract Documents.
- F. Measure floor and slab flatness and levelness in accordance with ASTM E1155 within 24 hours of completion of floor finishing and promptly report test results to Architect.

3.16 PROTECTION

- A. Protect concrete surfaces as follows:
 - 1. Protect from petroleum stains.
 - 2. Diaper hydraulic equipment used over concrete surfaces.
 - 3. Prohibit vehicles from interior concrete slabs.
 - 4. Prohibit use of pipe-cutting machinery over concrete surfaces.
 - 5. Prohibit placement of steel items on concrete surfaces.
 - 6. Prohibit use of acids or acidic detergents over concrete surfaces.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 7. Protect liquid floor treatment from damage and wear during the remainder of construction period. Use protective methods and materials, including temporary covering, recommended in writing by liquid floor treatments installer.
- 8. Protect concrete surfaces scheduled to receive surface hardener or polished concrete finish using Floor Slab Protective Covering.

END OF SECTION 033000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 042000 UNIT MASONRY

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware 2016a.
- B. ASTM A240/A240M Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications 2022.
- C. ASTM A615/A615M Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement 2020.
- D. ASTM A641/A641M Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire 2019.
- E. ASTM A951/A951M Standard Specification for Steel Wire for Masonry Joint Reinforcement 2016, with Editorial Revision (2018).
- F. ASTM A1064/A1064M Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete 2022.
- G. ASTM C55 Standard Specification for Concrete Building Brick 2017.
- H. ASTM C62 Standard Specification for Building Brick (Solid Masonry Units Made From Clay or Shale) 2017.
- ASTM C90 Standard Specification for Loadbearing Concrete Masonry Units 2021.
- J. ASTM C91/C91M Standard Specification for Masonry Cement 2018.
- K. ASTM C140/C140M Standard Test Methods for Sampling and Testing Concrete Masonry Units and Related Units 2022a.
- L. ASTM C144 Standard Specification for Aggregate for Masonry Mortar 2018.
- M. ASTM C216 Standard Specification for Facing Brick (Solid Masonry Units Made From Clay or Shale) 2021.
- N. ASTM C270 Standard Specification for Mortar for Unit Masonry 2019a, with Editorial Revision.
- O. ASTM C404 Standard Specification for Aggregates for Masonry Grout 2018.
- P. ASTM C476 Standard Specification for Grout for Masonry 2020.
- Q. ASTM C780 Standard Test Method for Preconstruction and Construction Evaluation of Mortars for Plain and Reinforced Unit Masonry 2020.
- R. ASTM C1019 Standard Test Method for Sampling and Testing Grout for Masonry 2020.
- S. ASTM C1072 Standard Test Methods for Measurement of Masonry Flexural Bond Strength 2019.
- T. ASTM C1314 Standard Test Method for Compressive Strength of Masonry Prisms 2021.
- U. ASTM D1227/D1227M Standard Specification for Emulsified Asphalt Used as a Protective Coating for Roofing 2013, with Editorial Revision (2019).
- V. ASTM E154/E154M Standard Test Methods for Water Vapor Retarders Used in Contact with Earth Under Concrete Slabs, on Walls, or as Ground Cover 2008a (Reapproved 2019).
- W. ASTM E514/E514M Standard Test Method for Water Penetration and Leakage Through Masonry 2020.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- X. BIA Technical Notes No. 7 Water Penetration Resistance Design and Detailing 2017.
- Y. BIA Technical Notes No. 13 Ceramic Glazed Brick Exterior Walls 2017.
- Z. BIA Technical Notes No. 28B Brick Veneer/Steel Stud Walls 2005.
- AA. BIA Technical Notes No. 46 Maintenance of Brick Masonry 2017.
- BB. TMS 402/602 Building Code Requirements and Specification for Masonry Structures 2016.

1.02 ADMINISTRATIVE REQUIREMENTS

A. Preinstallation Meeting: Convene a preinstallation meeting at the Project site one week before starting work of this section; require attendance by all relevant installers.

1.03 SUBMITTALS

- A. Product Data: Provide data for masonry units, fabricated wire reinforcement, mortar, and masonry accessories.
- B. Shop Drawings: Indicate pertinent dimensions, materials, anchorage, size and type of fasteners, and accessories for brickwork support system.
- C. Samples: Face brick and mortar selections will be verified in mock-up panel. Provide samples of exposed accessories and trim requiring color selection.
- D. Material Certificates and Test Reports: Provide manufacturer's certificates and test reports for the following:
 - 1. Masonry Units:
 - a. Brick: Size data including fabrication tolerances.
 - b. Brick: Efflorescence test, per ASTM C 67.
 - c. Masonry Units: Compressive strength test data.
 - d. Concrete Masonry: Data indicating aggregates comply with ASTM C 33 (normal weight), ASTM C 331 (lightweight), and ASTM C 618 (fly ash).
 - Mortar and Grout Mixes: Provide description and proportion of materials for each type of mortar and grout.
 - Provide material certificates for each type of metal accessory, including reinforcing bars, joint reinforcement, veneer ties and anchors, and other indicated accessories, indicating compliance with requirements.

1.04 QUALITY ASSURANCE

- A. Comply with provisions of ACI 530.1/ASCE 6/TMS 402/602, except where exceeded by requirements of Contract Documents.
- B. Fire Rated Assemblies: Provide products that comply with fire-resistance ratings indicated as determined by testing according to ASTM E 119, by equivalent testing thickness, or by means acceptable to authorities having jurisdiction.
- C. Aggregate for Concrete Masonry Units: If bottom ash is used as aggregate in the CMU, the Source for the bottom ash shall be a power station that has a minimum of ten (10) years continuous experience as a supplier of quality material as verified by independent certified laboratory testing and no defects in the marketplace.
- D. Pre-Construction Testing: Owner shall engage an independent testing agency to perform field quality control tests, in accordance with Section 014000 Quality Requirements.
 - Concrete Masonry Unit Tests: Testing agency shall test each variety of concrete unit masonry in accordance with ASTM C140/C140M compressive strength requirements.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.05 FIELD CONDITIONS

- A. Wall Cavity Protection: Provide temporary waterproof sheet coverings over masonry walls at top of walls, sills, parapets, and other horizontal projections. Install coverings at end of each workday, when rain or precipitation is expected, and after masonry work is completed.
 - 1. Extend coverings down vertically at least 24 inches on each side of masonry wall. At multiwythe walls where one wythe is more than 24 inches taller than other wythe(s), extend covering as required to fully cover all wythes and cavities.
 - At roof parapets, extend covering on rear side of parapet full height down to roof deck/membrane, until vertical protection/roof membrane is installed.
 - 2. Secure all coverings in place with tape or adhesive that does not leave residue, or other securement method that does not penetrate or damage permanent construction.
 - 3. Provide protective coverings at sills and horizontal projections that can also serve as protection from mortar droppings.
 - 4. Provide protective coverings over tops of foundation walls containing insulation to protect from exposure to sun and from construction traffic damage.
 - 5. Do not remove or allow removal of temporary covers until permanent top of wall protection elements (coping, sill, roof surface, waterproof membrane, etc) are underway.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Deliver, handle, and store masonry units by means that will prevent mechanical damage and contamination by other materials.

PART 2 PRODUCTS

2.01 CONCRETE MASONRY UNITS

- A. Concrete Block: Comply with referenced standards and as follows:
 - 1. Size: Standard units with nominal face dimensions of 16 by 8 inches and nominal depths as indicated on drawings for specific locations.
 - Special Shapes: Provide nonstandard blocks configured for corners.
 - a. Provide bullnose units for outside corners.
 - 3. Concrete Masonry Units: ASTM C90, lightweight.
 - a. Exposed Faces: Manufacturer's standard color and texture.
 - b. Aggregates:
 - Lightweight Aggregates: Lightweight aggregate shall strictly comply with ASTM C 331, ASTM C 151, and ASTM C 641. Drying shrinkage of aggregate shall not exceed 0.10% at 100 days.
 - 2) Waste concrete, scoria, and aglite shall not be permitted.
 - Decorative Concrete Block: ASTM C 90, normal weight.
 - a. Pattern: Manufacturer's standard ground-face pattern.
 - b. Size: Match standard nominal dimensions per "Concrete Block" paragraph above.
 - c. Color: As selected by Architect from manufacturer's full range.
 - d. Provide integral water repellent, mortar additive, and field-applied treatment at all exterior decorative CMU.
 - e. Topcoat: Where recommended by manufacturer of ground-face units, provide clear acrylic top-coat, minimum 20 percent solids content.
 - 5. Units with Integral Water Repellent: Concrete block units as specified in this section with polymeric liquid admixture added to concrete masonry units at the time of manufacture.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- a. Performance of Units with Integral Water Repellent:
 - 1) Water Permeance: When tested per ASTM E514/E514M and for a minimum of 72 hours.
 - (a) No water visible on back of wall above flashing at the end of 24 hours.
 - (b) No flow of water from flashing equal to or greater than 0.032 gallons per hour at the end of 24 hours.
 - (c) No more than 25 percent of wall area above flashing visibly damp at end of test.
 - 2) Flexural Bond Strength: ASTM C1072; minimum 10 percent increase.
 - 3) Compressive Strength: ASTM C1314; maximum 5 percent decrease.
- b. Use only in combination with mortar that also has integral water repellent admixture.
 - 1) Provide manufacturer's companion product for field-applied spray treatment. Provide all three (integral repellent, mortar additive, and field-applied treatment) for all exterior decorative CMU.
- Use water repellent admixtures for masonry units and mortar by a single manufacturer.
- d. Available Products:
 - 1) ACM Chemistries; RainBloc.
 - 2) BASF Aktiengesellschaft; Rheopel Plus.
 - 3) Grace Construction Products (W.R. Grace & Co.); Dry-Block.
- B. Concrete Brick:
 - 1. Actual Size: 3-5/8 inches wide by 2-1/4 inches high by 7-5/8 inches long.
 - 2. Concrete Building Brick: ASTM C55; lightweight, solid, for interior or concealed use.

2.02 BRICK UNITS

- A. Facing Brick: ASTM C216, Type FBS Smooth, Grade SW.
 - 1. Actual Size: 3-5/8 inches wide by 2-1/4 inches high by 7-5/8 inches long (modular).
 - 2. Actual Size: 3-5/8 inches wide by 3-5/8 inches high by 11-5/8 inches long (utility).
 - 3. Special shapes: Molded units as required by conditions indicated, unless standard units can be sawn to produce equivalent effect.
- B. Building (Common) Brick: ASTM C62, Grade SW, except MW may be used in locations indicated acceptable in reference standard; solid units.
 - 1. Actual size: Match face brick.
 - 2. Locations: May be used in concealed locations in lieu of face brick.

2.03 MORTAR AND GROUT MATERIALS

- A. Masonry Cement: ASTM C91/C91M.
 - 1. Colored Mortar: Premixed cement as required to match Architect's color sample.
 - 2. Available Products:
 - a. Argos USA; Magnolia Masonry Cement.
 - b. Holcim (US) Inc.; Rainbow Mortamix Custom Color Masonry Cement.
 - c. Lehigh Hanson; flamingo Colored Cement.
 - d. Roanoke Cement; a division of Titan America; Colored Masonry Cement.
 - e. York Building Products, a Stewart Company; Workrite Colored Masonry Cement.

B. Surface Bonding Mortar (Parge Coat): ASTM C 887.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

C. Mortar Aggregate: ASTM C144.D. Grout Aggregate: ASTM C404.E. Water: Clean and potable.

2.04 DAMPPROOFING

- A. General: Dampproofing may be provided as a Contractor option to parge coat, applied to exterior face of below grade CMU back up wall (prior to insulation or grouting).
- B. Bituminous Dampproofing: Cold-applied water-based emulsion; asphalt with mineral colloid or chemical emulsifying agent; with or without fiber reinforcement; asbestos-free; suitable for application on vertical and horizontal surfaces.
 - Emulsified Asphalt Coating (Brush or Spray Applied): ASTM D1227/D1227M, Type II, Class 1 - Mineral colloid emulsifying agents with non-asbestos fibers or Type III, Class 1 -Mineral colloid emulsifying agents without fibrous reinforcement.
 - 2. Accessory Materials: Provide asphaltic primer, glass fiber reinforcement, and compatible patching compounds as required and as recommended by manufacturer.
 - Manufacturers:
 - a. Henry Company.
 - b. Karnak Corporation.
 - c. Mar-Flex Systems, Inc.
 - d. W. R. Meadows, Inc.

2.05 REINFORCEMENT AND ANCHORAGE

- A. Reinforcing Steel: ASTM A615/A615M, Grade 60 (60,000 psi), deformed billet bars; uncoated.
- B. Single Wythe Joint Reinforcement: ASTM A951/A951M.
 - 1. Type: Ladder.
 - 2. Material: Mill-galvanized steel for interior walls, hot-dip galvanized steel for exterior walls.
 - 3. Size: 0.1483 inch side rods with 0.1483 inch cross rods; width as required to provide not less than 5/8 inch of mortar coverage on each exposure.
- C. Multiple Wythe Joint Reinforcement: ASTM A951/A951M. Provide at composite walls and subgrade walls.
 - 1. Type: Ladder.
 - Material: Mill-galvanized steel for interior walls, hot-dip galvanized steel for exterior walls.
 - 3. Size: 0.1483 inch side rods with 0.1483 inch cross rods; width as required to provide not less than 5/8 inch of mortar coverage on each exposure.
 - a. Provide two side rods for each wythe that is nominal 6" depth or greater, and one side rod for each wythe that is nominal 4" depth.
- D. Adjustable Multiple Wythe Joint Reinforcement: ASTM A951/A951M. Provide at cavity walls/masonry veneer walls.
 - 1. Type: Ladder, with adjustable ties or tabs spaced at 16 in on center.
 - 2. Material: Hot-dip galvanized carbon steel.
 - Size: 0.1483 inch side rods with 0.1483 inch cross rods and adjustable components of 0.1875 inch wire, width of components as required to provide not less than 5/8 inch of mortar coverage from each masonry face.
 - 4. Vertical adjustment: Not more than 1 1/4 inches.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- E. Strap Anchors: Bent steel shapes, 1-1/2 inch width, 0.105 inch thick, 24 inch length, with 2 inch long, 90 degree bend at each end to form a U or Z shape or with cross pins, hot dip galvanized to ASTM A153/A153M Class B.
- F. Flexible Anchors: 2-piece anchors that permit differential movement between masonry and building frame, sized to provide not less than 5/8 inch of mortar coverage from masonry face.
- G. Masonry Veneer Anchors: 2-piece anchors that permit differential movement between masonry veneer and structural backup, hot dip galvanized to ASTM A 153/A 153M, Class B. Provide at masonry veneer walls with metal framing backup. At cavity walls with CMU backup and masonry veneer, masonry veneer anchors may be used in conjunction with standard horizontal joint reinforcing, at Contractor's option, in lieu of adjustable multiple wythe joint reinforcement.
 - 1. Anchor plates: Not less than 0.075 inch thick, designed for fastening to structural backup through sheathing by two fasteners; provide design with legs that penetrate sheathing and insulation to provide positive anchorage.
 - 2. Wire ties: Manufacturer's standard shape, 0.1875 inch thick.
 - 3. Vertical adjustment: Not less than 3-1/2 inches.

2.06 FLASHINGS

- A. Combination Nonasphaltic Flashing Materials Copper:
 - Copper/Polymer Film or Fabric Flashing: 5 oz/sq ft copper sheet laminated between two sheets of polymer film. Minimum Puncture Resistance of 780 psi, when measured in accordance with ASTM E154/E154M.
 - a. Available Products:
 - 1) Advanced Building Products, Inc.; Copper Sealtite 2000.
 - 2) Hohmann & Barnard, Inc; Copper-Fabric NA.
 - 3) STS Coatings, Inc.; Wall Guardian Copper TWF.
 - 4) York Manufacturing, Inc; Multi-Flash 500 Series.
- B. Combination Non-Asphaltic Flashing Materials Stainless Steel:
 - Stainless Steel/Polymer Fabric Flashing: ASTM A240/A240M; 2 mil type 304 stainless steel sheet bonded on one side to one sheet of polymer fabric.
 - a. Manufacturers:
 - 1) Hohmann & Barnard, Inc; Mighty-Flash Stainless Flashing.
 - 2) Prosoco; R-Guard SS ThruWall.
 - 3) STS Coatings; Wall Guardian Stainless Steel TWF.
 - 4) York Manufacturing, Inc; Multi-Flash SS.
- C. Factory-Fabricated Flashing Corners and End Dams: Stainless steel.
- D. Termination Bars: One-inch wide, fabricated of 0.125-inch PVC, 0.090-inch extruded aluminum, or 0.075-inch stainless steel; compatible with membrane and adhesives.
- E. Drip Edge: Stainless steel; angled drip with hemmed edge; compatible with membrane and adhesives.
- F. Flashing Sealant/Adhesive/Liquid Seam Tape: Polyether-based, 100% solids, moisture-curing elastomeric products recommended by flashing manufacturer for bonding flashing sheets to each other and to substrates; and that are compatible with asphalt-free flashing materials and air barrier materials. Traditional mastic is not acceptable.
 - 1. Available Products:
 - a. Master Builders Solutions; MasterSeal NP150.
 - b. STS Coatings; GreatSeal LT-100 Liquid Tape.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

c. York; UniverSeal US-100 Liquid Tape.

2.07 ACCESSORIES

- A. Preformed Control Joints: Rubber material. Provide with corner and tee accessories, fused joints.
 - 1. Provide nominal 2.5-inch "standard" and "tee" configurations to suit application unless indicated otherwise.
- B. Joint Filler: Closed cell polyvinyl chloride; oversized 50 percent to joint width; self expanding; in maximum lengths available.
- C. Cavity Mortar Control: Semi-rigid polyethylene or polyester mesh panels, sized to thickness of wall cavity, and designed to prevent mortar droppings from clogging weeps and cavity vents and allow proper cavity drainage.
 - 1. Mortar Diverter: Semi-rigid mesh designed for installation at flashing locations. Provide in depth matching cavity depth without gap at front or back of mesh. Fabricate approximately 10 inches high with minimum 6 inch high dovetail shape projections.
 - a. Available Products:
 - 1) Advanced Building Products, Inc; Mortar Break DT.
 - Heckmann Building Products; WallDefender.
 - 3) Hohmann & Barnard, Inc.; Mortar Trap.
 - 4) Mortar Net Solutions; MortarNet.
 - 5) Wire-Bond; Cavity Net DT (3611D).
 - b. At cavities with depth greater than 2 inches, provide companion drainage product by one of the manufacturers above; nominal 1/2-inch thickness by 20 inches wide, to be field inserted into cavity in a "U" configuration. Basis-of-Design is "Mortar Catch 352" by Advanced Building Products, Inc.
- D. Weeps/Cavity Vents:
 - 1. Cellular Type: Extruded propylene with honeycomb design.
 - a. Color(s): As selected by Architect from manufacturer's full range.
 - b. Available Products:
 - 1) Advanced Building Products, Inc.; Mortar Break weep mesh.
 - 2) Blok-Lok Limited; Cell-Vent.
 - 3) CavClear/Archovations, Inc.; CavClear Weep Vent.
 - 4) Heckmann Building Products Inc.; No. 85 Cell Vent.
 - 5) Hohmann & Barnard, Inc.; Quadro-Vent.
 - 6) Mortar Net Solutions; WeepVent.
 - Wire-Bond; Cell Vent.
 - 2. Bed Joint Weep System: Corrugated plastic drainage system incorporating continuous drainage strip within cavity portion of wall with integral weephole extensions at 9-1/2 inches on center located above flashing in the bed joint of the veneer masonry. Provide at masonry units over 32 inches long, and as indicated.
 - a. Available Products:
 - 1) Heckmann Building Products; Core/Cavity Vent Weep System #367.
 - 2) Masonry Technology Incorporated (MTI); Cavity Weep CV 5010.
- E. Reinforcing Positioners: Provide wire positioners in bed joints to keep steel reinforcing bars centered in cells, fabricated of 0.1483-inch hot-dip galvanized steel wire.

Available Products:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- a. Heckmann Building Products, Inc.; No. 376 Rebar Positioner.
- b. Hohmann & Barnard, Inc.; #RB or #RB-Twin Rebar Positioner.
- Wire-Bond; O-Ring or Double O-Ring Rebar Positioner.
- F. Protection Board: ASTM D 6506, semi-rigid sheets of fiberglass or mineral-reinforced asphaltic core, pressure laminated between two asphalt-saturated fibrous liners and as follows:
 - Thickness: 1/8-inch, nominal.
 - 2. Adhesive: Rubber-based solvent type recommended by waterproofing manufacturer for type of protection board.
- G. Cleaning Solution: Non-acidic, not harmful to masonry work or adjacent materials.

2.08 LINTELS

- A. Masonry Lintels: Fabricated of bond beam CMUs, with texture matching adjacent standard CMU. Provide reinforcing bars and grout in accordance with structural requirements. Provide temporary supports until cured.
- B. Precast Concrete Lintels: Comply with structural requirements for concrete strength and reinforcing. Precast U-lintels fabricated in accordance with performance standards of PCI MNL-116 with 3500 psi concrete for standard lintels and 6000 psi concrete for prestressed lintels as manufactured by Cast-Crete are acceptable in lieu of rectangular section lintels.
- C. Steel Lintels: Refer to Division 5 "Metal Fabrications."

2.09 MORTAR AND GROUT MIXING

- A. Mortar for Unit Masonry: ASTM C270, using the Proportion Specification.
 - 1. Masonry below grade and in contact with earth: Type S.
 - 2. Reinforced masonry: Type S.
 - 3. Mortar parge coats: Type S.
 - 4. Exterior, loadbearing and non-loadbearing, and interior, loadbearing and non-loadbearing: Type N, except as indicated above.
 - a. Interior, non-loadbearing masonry may use Type O at Contractor's option.
- Colored Mortar: Proportion selected pigments and other ingredients to match Architect's sample, without exceeding manufacturer's recommended pigment-to-cement ratio.
- C. Grout: ASTM C476; consistency required to fill completely volumes indicated for grouting; fine grout for spaces with smallest horizontal dimension of 2 inches or less; coarse grout for spaces with smallest horizontal dimension greater than 2 inches.
- D. Mixing: Use mechanical batch mixer and comply with referenced standards.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field conditions are acceptable and are ready to receive masonry.
- B. Verify that related items provided under other sections are properly sized and located.
- C. Verify that built-in items are in proper location, and ready for roughing into masonry work.

3.02 PREPARATION

A. Direct and coordinate placement of metal anchors supplied for installation under other sections.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

B. Provide temporary bracing during installation of masonry work. Maintain in place until building structure provides permanent bracing.

3.03 COLD AND HOT WEATHER REQUIREMENTS

A. Comply with requirements of TMS 402/602 or applicable building code, whichever is more stringent.

3.04 COURSING

- A. Establish lines, levels, and coursing indicated. Protect from displacement.
- B. Maintain masonry courses to uniform dimension. Form vertical and horizontal joints of uniform thickness.
 - 1. CMU Coursing: One unit and one mortar joint equal 8 inches.
 - 2. Brick Coursing: Either two or three units with accompanying mortar joints shall equal 8 inches, based on basis-of-design brick size(s) indicated above.
- C. Provide running bond for all masonry units unless otherwise indicated.
- D. Tool all mortar joints slightly concave where they will be exposed, unless otherwise indicated.
 - Provide flush joints where they will be concealed by surface-applied treatments or finishes including but not limited to tile, wall coverings, fluid-applied or SPF air barriers, or membranes.

3.05 PLACING AND BONDING

- A. Create a consistent blend for each type of veneer masonry by mixing units from a minimum of three pallets.
- Lay solid masonry units in full bed of mortar, with full head joints, uniformly jointed with other work.
- C. Lay hollow masonry units with face shell bedding on head and bed joints.
- D. Remove excess mortar and mortar smears as work progresses.
- E. Do not shift or tap masonry units after mortar has achieved initial set. Where adjustment must be made, remove mortar and replace.
- F. Perform job site cutting of masonry units with proper tools to provide straight, clean, unchipped edges. Prevent broken masonry unit corners or edges.
- G. Cut mortar joints flush where surface-applied treatment or finish (other than paint) is scheduled, where wall tile is scheduled, cement parging is required, resilient base is scheduled, or bitumen dampproofing is applied.
- H. Keyed Sets: Lay manufactured keyed sets and keystone units in configuration indicated, in accordance with BIA Tech Note 31. Maintain uniform mortar joint widths. Cut adjacent horizontal brick that abuts keyed sets cleanly to match skewback or to match circular radius as condition requires, and to maintain a consistent mortar joint.
 - 1. Provide flashings and end dams at keyed sets in accordance with BIA standard.

3.06 WEEPS/CAVITY VENTS

A. Install weeps in veneer and cavity walls at 24 inches on center horizontally on top of throughwall flashing above shelf angles and lintels and at bottom of walls.

3.07 CAVITY MORTAR CONTROL

A. Do not permit mortar to drop or accumulate into cavity air space or to plug weep/cavity vents.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. For cavity walls, build inner wythe ahead of outer wythe to accommodate accessories.
- C. Install cavity mortar diverter at base of cavity and at other flashing locations as recommended by manufacturer to prevent mortar droppings from blocking weep/cavity vents.

3.08 REINFORCEMENT AND ANCHORAGE - GENERAL, SINGLE WYTHE MASONRY, AND CAVITY WALL MASONRY

- A. Unless otherwise indicated on drawings or specified under specific wall type, install horizontal joint reinforcement 16 inches on center.
- B. Place masonry joint reinforcement in first and second horizontal joints above and below openings. Extend minimum 16 inches each side of opening.
- C. Place continuous joint reinforcement in first and second joint below top of walls.
- D. At parapets and below-grade/foundations, provide joint reinforcement at 8 inches o.c. vertically.
- E. Embed longitudinal wires of joint reinforcement in mortar joint with at least 5/8 inch mortar cover on each side.
- F. Lap joint reinforcement ends minimum 6 inches.
- G. Do not extend reinforcement across control, expansion, and other building movement joints.
- H. Reinforce corners and intersections with prefabricated T- or L-shaped reinforcing.
- I. Fasten anchors to structural framing and embed in masonry joints as masonry is laid. Unless otherwise indicated on drawings or closer spacing is indicated under specific wall type, space anchors at maximum of 36 inches horizontally and 24 inches vertically.

3.09 REINFORCEMENT AND ANCHORAGE - MASONRY VENEER

A. Masonry and/or Metal Framing Back-Up: Embed anchors to bond veneer at maximum 16 inches on center vertically and 24 inches on center horizontally. Place additional anchors at perimeter of openings and ends of panels, so maximum spacing of anchors is 8 inches on center.

3.10 REINFORCEMENT AND ANCHORAGES - COMPOSITE UNIT MASONRY

- A. Install continuous horizontal joint reinforcement at 16 inches o.c. vertically, except at below grade foundation walls install at 8 inches o.c. vertically.
- B. Where concrete foundations are indicated, tie below-grade masonry to concrete with rigid anchors spaced at maximum 8 inches o.c. vertically.
- C. Coordinate with parging/dampproofing and with installation of insulation, where indicated.

3.11 MASONRY FLASHINGS

- A. Whether or not specifically indicated, install masonry flashing to divert water to exterior at all locations where downward flow of water will be interrupted.
 - 1. Remove or cover protrusions or sharp edges that could puncture flashings.
 - 2. Seal lapped ends and penetrations of flashing before covering with mortar.
- Terminate flashing up 8 inches minimum on vertical surface of backing:
 - 1. Anchor vertical leg of flashing into backing with a termination bar and sealant.
- C. Extend metal flashings to within 1/2 inch of exterior face of masonry and adhere to top of stainless steel angled drip with hemmed edge.
 - Notch and hem exterior corners of drip edges to eliminate sharp, exposed cut metal edges at locations below 6'-0" above grade.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- D. Support flexible flashings across gaps and openings.
- E. Lap end joints of flashings at least 6 inches, minimum, and seal watertight with flashing sealant/adhesive.

3.12 LINTELS

- A. Install loose steel or precast lintels over openings, where indicated.
- B. Install reinforced unit masonry lintels over openings where steel or precast concrete lintels are not scheduled.
 - 1. Comply with requirements on Structural Drawings for type of lintel at each opening, additional lintel sizing, reinforcement, and installation requirements.
 - 2. Allow masonry lintels to attain specified strength before removing temporary supports.
- C. Maintain minimum 8 inch bearing on each side of opening.

3.13 GROUTED COMPONENTS

- A. Lap splices minimum 24 bar diameters.
- B. Support and secure reinforcing bars from displacement. Maintain position within 1/2 inch of dimensioned position.
- C. Place and consolidate grout fill without displacing reinforcing.

3.14 CONTROL AND EXPANSION JOINTS

- A. Do not continue horizontal joint reinforcement through control or expansion joints.
- B. Install preformed control joint device in continuous lengths. Seal butt and corner joints in accordance with manufacturer's instructions.
- C. Provide control and expansion joints at locations indicated on Drawings, and as follows:
 - 1. At changes in wall height.
 - 2. At changes in wall thickness
 - 3. At change in support (eq: transition from foundation support to floor slab support).
 - 4. Adjacent to corners of walls within a distance equal to no more than half the maximum control joint spacing.
 - 5. Wall intersections.
 - Do not place control joints closer than 16 inches to edge of wall openings (doors, windows, louvers, ducts).
 - 7. Distance between joints shall not exceed a length to height ratio of 1.5:1.
 - 8. Distance between joints shall not exceed 25 feet where no openings occur between joints.
 - 9. Distance between joints shall not exceed 20 feet where openings occur between joints.

3.15 BUILT-IN WORK

- A. As work progresses, install built-in metal door frames, anchor bolts, and plates and other items to be built into the work and furnished under other sections.
- B. Install built-in items plumb, level, and true to line.
- C. Bed anchors of metal door frames in adjacent mortar joints. Fill frame voids solid with grout.
 - 1. Mix mortar (or grout) to a 4-inch maximum slump consistency and hand trowel into place in accordance with Steel Door Institute (SDI-100).
 - Fill adjacent masonry cores with grout minimum 12 inches from framed openings.
- D. Do not build into masonry construction organic materials that are subject to deterioration.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.16 TOLERANCES

- A. Install masonry within the site tolerances found in TMS 402/602.
- B. Maximum Variation From Unit to Adjacent Unit: 1/16 inch.
- C. Maximum Variation from Plane of Wall: 1/4 inch in 10 ft and 1/2 inch in 20 ft or more.
- Maximum Variation from Plumb: 1/4 inch per story non-cumulative; 1/2 inch in two stories or more.
- E. Maximum Variation from Level Coursing: 1/8 inch in 3 ft and 1/4 inch in 10 ft; 1/2 inch in 30 ft.
- F. Maximum Variation of Mortar Joint Thickness: Head joint, minus 1/4 inch, plus 3/8 inch.
- G. Maximum Variation from Cross Sectional Thickness of Walls: 1/4 inch.

3.17 CUTTING AND FITTING

- A. Cut and fit for chases, pipes, conduit, and other penetrations. Coordinate with other sections of work to provide correct size, shape, and location.
- B. Obtain approval prior to cutting or fitting masonry work not indicated or where appearance or strength of masonry work may be impaired.

3.18 PARGING

- A. Dampen masonry walls prior to parging.
- B. Parge cavity side of CMU below grade back-up wythe with a single coat of surface-bonding mortar to a total thickness of 1/4 inch.
 - 1. In lieu of parging, Contractor may at its option apply bituminous dampproofing, at a minimum rate of 1.25 gal per 100 sq. ft. Apply primer if required by manufacturer and comply with manufacturer's installation requirements.
- C. Steel trowel surface smooth and flat with a maximum surface variation of 1/8 inch per foot.
- D. Strike top edge of parging at 45 degrees.

3.19 FIELD QUALITY CONTROL

- A. An independent testing agency will perform field quality control tests, as specified in Section 014000 Quality Requirements.
- B. Concrete Masonry Unit Tests: Testing agency shall test concrete unit masonry, of each load-bearing size indicated, in accordance with ASTM C140/C140M for compliance with requirements of this specification.
- C. Mortar Tests: Testing agency shall test each type of mortar in accordance with ASTM C780. Mortar shall be tested on each of the first 3 days. Alert testing agency if mortar mix is altered during construction to allow for retesting.
- D. Grout Test: Testing agency shall test each type of grout in accordance with ASTM C1019. Grout shall be tested on each of the first 3 days. Alert testing agency if grout mix is altered during construction to allow for retesting.

3.20 CLEANING

- A. Remove excess mortar and mortar droppings.
- B. Replace defective mortar. Match adjacent work.
- C. Clean soiled surfaces with cleaning solution.
- D. Use non-metallic tools in cleaning operations.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.21 PROTECTION

- A. Provide temporary protective waterproof sheet coverings over tops of walls, parapets, sills, and other horizontal projections as the work progresses, in accordance with "Field Conditions" article above.
- B. Without damaging completed work, provide protective boards at exposed external corners that are subject to damage by construction activities.
- C. Provide protective vertical boards and horizontal sheeting at grade level base of walls to prevent staining or splashing from rain, mud, or mortar droppings.

END OF SECTION 042000

Unit Masonry 042000 - 13

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 051200 - STRUCTURAL STEEL FRAMING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Structural steel.
- 2. Shear stud connectors.
- 3. Shrinkage-resistant grout.

B. Related Requirements:

- 1. Section 053100 "Steel Decking" for field installation of shear stud connectors through deck
- 2. Section 055000 "Metal Fabrications" for miscellaneous steel fabrications and other steel items not defined as structural steel.

1.3 DEFINITIONS

- A. Structural Steel: Elements of the structural frame indicated on Drawings and as described in ANSI/AISC 303.
- B. Lateral-Force-Resisting System: Elements of structural-steel frame designated as "LFRS" or along grid lines designated as "LFRS" on Drawings, including columns, beams, and braces and their connections.
- C. Heavy Sections: Rolled and built-up sections as follows:
 - 1. Shapes included in ASTM A6 with flanges thicker than 1-1/2 inches.
 - 2. Welded built-up members with plates thicker than 2 inches.
 - 3. Column base plates thicker than 2 inches.
- D. Protected Zone: Structural members or portions of structural members indicated as "protected zone" on Drawings. Connections of structural and nonstructural elements to protected zones are limited.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

E. Demand-Critical Welds: Those welds, the failure of which would result in significant degradation of the strength and stiffness of the seismic-load-resisting system, and which are indicated as "demand critical" or "seismic critical" on Drawings.

1.4 COORDINATION

- A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.
- B. Coordinate installation of anchorage items to be embedded in or attached to other construction without delaying the Work. Provide setting diagrams, sheet metal templates, instructions, and directions for installation.

1.5 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at the project site.

1.6 ACTION SUBMITTALS

A. Product Data:

- 1. Structural-steel materials.
- 2. High-strength, bolt-nut-washer assemblies.
- 3. Shear stud connectors.
- 4. Anchor rods.
- 5. Threaded rods.
- 6. Forged-steel hardware.
- 7. Slide bearings.
- 8. Shop primer.
- 9. Galvanized-steel primer.
- 10. Etching cleaner.
- 11. Galvanized repair paint.
- 12. Shrinkage-resistant grout.

B. Shop Drawings: Show fabrication of structural-steel components.

- 1. Include details of cuts, connections, splices, camber, holes, and other pertinent data.
- 2. Include embedment Drawings.
- 3. Indicate welds by standard AWS symbols, distinguishing between shop and field welds, and show size, length, and type of each weld. Show backing bars that are to be removed and supplemental fillet welds where backing bars are to remain.
- 4. Indicate type, size, and length of bolts, distinguishing between shop and field bolts. Identify pretensioned and slip-critical, high-strength bolted connections.
- 5. Identify members and connections of the seismic-load-resisting system.
- 6. Indicate locations and dimensions of protected zones.
- 7. Identify demand-critical welds.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 8. Identify members not to be shop primed.
- C. Welding Procedure Specifications (WPSs) and Procedure Qualification Records (PQRs): Provide in accordance with AWS D1.1 for each welded joint whether prequalified or qualified by testing, including the following:
 - 1. Power source (constant current or constant voltage).
 - 2. Electrode manufacturer and trade name, for demand-critical welds.
- D. Delegated-Design Submittal: For structural-steel connections indicated on Drawings to comply with design loads, include analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.7 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer, fabricator, shop-painting applicators, professional engineer, and testing agency.
- B. Welding certificates.
- C. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.
- D. Mill test reports for structural-steel materials, including chemical and physical properties.
- E. Product Test Reports: For the following:
 - 1. Bolts, nuts, and washers, including mechanical properties and chemical analysis.
 - 2. Direct-tension indicators.
 - 3. Tension-control, high-strength, bolt-nut-washer assemblies.
 - 4. Shear stud connectors.
- F. Survey of existing conditions.
- G. Source quality-control reports.
- H. Field quality-control reports.

1.8 QUALITY ASSURANCE

- A. Fabricator Qualifications: A qualified fabricator that participates in the AISC Quality Certification Program and is designated an AISC-Certified Plant, Category BU or is accredited by the IAS Fabricator Inspection Program for Structural Steel (Acceptance Criteria 172).
- B. Installer Qualifications: A qualified Installer who participates in the AISC Quality Certification Program and is designated an AISC-Certified Erector, Category CSE.
- C. Welding Qualifications: Qualify procedures and personnel in accordance with AWS D1.1.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Store materials to permit easy access for inspection and identification. Keep steel members off ground and spaced by using pallets, dunnage, or other supports and spacers. Protect steel members and packaged materials from corrosion and deterioration.
 - 1. Do not store materials on structure in a manner that might cause distortion, damage, or overload to members or supporting structures. Repair or replace damaged materials or structures as directed.
- B. Store fasteners in a protected place in sealed containers with manufacturer's labels intact.
 - 1. Fasteners may be repackaged provided Owner's testing and inspecting agency observes repackaging and seals containers.
 - 2. Clean and relubricate bolts and nuts that become dry or rusty before use.
 - 3. Comply with manufacturers' written recommendations for cleaning and lubricating ASTM F1852 bolt assemblies and for retesting bolt assemblies after lubrication.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Comply with applicable provisions of the following specifications and documents:
 - 1. ANSI/AISC 303.
 - 2. ANSI/AISC 360.
 - 3. RCSC's "Specification for Structural Joints Using High-Strength Bolts."
- B. Connection Design Information:
 - 1. Option 3 and 3B: Design connections and final configuration of member reinforcement at connections in accordance with ANSI/AISC 303 by fabricator's qualified professional engineer.
 - a. Use Allowable Stress Design; data are given at service-load level.

2.2 STRUCTURAL-STEEL MATERIALS

- A. W-Shapes, Angles: As indicated.
- B. Channels, M-Shapes, S-Shapes: As indicated.
- C. Plate and Bar: As indicated.
- D. Cold-Formed Hollow Structural Sections: As indicated.
- E. Steel Pipe: ASTM A53, Type E or Type S, Grade B.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Weight Class: Standard, unless otherwise indicated.
- 2. Finish: Black except where indicated to be galvanized.
- F. Steel Forgings: ASTM A668/A668M.
- G. Welding Electrodes: Comply with AWS requirements.

2.3 BOLTS AND CONNECTORS

- A. High-Strength Bolts, Nuts, and Washers: ASTM F3125, Grade A325, Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436, Type 1, hardened carbon-steel washers; all with plain finish.
 - 1. Direct-Tension Indicators: ASTM F959, Type 325-1, compressible-washer type with plain finish.
- B. High-Strength Bolts, Nuts, and Washers: ASTM F3125, Grade A490, Type 1, heavy-hex steel structural bolts or ASTM F2280 tension-control, bolt-nut-washer assemblies with splined ends; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436, Type 1, hardened carbon-steel washers; all with plain finish.
 - 1. Direct-Tension Indicators: ASTM F959, Type 490-1, compressible-washer type with plain finish.
- C. Zinc-Coated High-Strength Bolts, Nuts, and Washers: ASTM F3125, Grade A325, Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436, Type 1, hardened carbon-steel washers.
 - 1. Finish: Hot-dip zinc coating.
 - 2. Direct-Tension Indicators: ASTM F959, Type 325-1, compressible-washer type with mechanically deposited zinc coating finish.
- D. Tension-Control, High-Strength Bolt-Nut-Washer Assemblies: ASTM F3125, Grade F1852, Type 1, round head assemblies, consisting of steel structural bolts with splined ends; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers.
 - 1. Finish: Plain.
- E. Shear Stud Connectors: ASTM A108, Grades 1015 through 1020, headed-stud type, cold-finished carbon steel; AWS D1.1, Type B.

2.4 RODS

- A. Unheaded Anchor Rods: ASTM F1554, Grade as indicated.
 - 1. Configuration: Straight.
 - 2. Nuts: ASTM A563 heavy-hex carbon steel.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Plate Washers: ASTM A36 carbon steel.
- 4. Washers: ASTM F436, Type 1, hardened carbon steel.
- 5. Finish: Plain.
- B. Headed Anchor Rods: ASTM F1554, Grade as indicated, straight.
 - 1. Nuts: ASTM A563 heavy-hex carbon steel.
 - 2. Plate Washers: ASTM A36 carbon steel.
 - 3. Washers: ASTM F436, Type 1, hardened carbon steel.
 - 4. Finish: Plain.
- C. Threaded Rods: ASTM A36.
 - 1. Nuts: ASTM A563 heavy-hex carbon steel.
 - 2. Washers: ASTM F436, Type 1, hardened carbon steel.
 - 3. Finish: Plain.

2.5 FORGED-STEEL STRUCTURAL HARDWARE

- A. Clevises and Turnbuckles: Made from cold-finished carbon-steel bars, ASTM A108, Grade 1035.
- B. Eye Bolts and Nuts: Made from cold-finished carbon-steel bars, ASTM A108, Grade 1030.
- C. Sleeve Nuts: Made from cold-finished carbon-steel bars, ASTM A108, Grade 1018.

2.6 PRIMER

- A. Steel Primer:
 - 1. Comply with Division 9.
 - 2. Fabricator's standard lead- and chromate-free, nonasphaltic, rust-inhibiting primer complying with MPI#79 and compatible with topcoat.
- B. Galvanizing Repair Paint:
 - 1. Galvanizing Repair Paint: ASTM A780.

2.7 SHRINKAGE-RESISTANT GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C1107, factory-packaged, nonmetallic aggregate grout, noncorrosive and nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.8 FABRICATION

- A. Structural Steel: Fabricate and assemble in shop to greatest extent possible. Fabricate in accordance with ANSI/AISC 303 and to ANSI/AISC 360.
 - 1. Camber structural-steel members where indicated.
 - 2. Fabricate beams with rolling camber up.
 - 3. Identify high-strength structural steel in accordance with ASTM A6 and maintain markings until structural-steel framing has been erected.
 - 4. Mark and match-mark materials for field assembly.
 - 5. Complete structural-steel assemblies, including welding of units, before starting shop-priming operations.
- B. Thermal Cutting: Perform thermal cutting by machine to greatest extent possible.
 - 1. Plane thermally cut edges to be welded to comply with requirements in AWS D1.1.
- C. Bolt Holes: Cut, drill, or punch standard bolt holes perpendicular to metal surfaces.
- D. Finishing: Accurately finish ends of columns and other members transmitting bearing loads.
- E. Cleaning: Clean and prepare steel surfaces that are to remain unpainted in accordance with SSPC-SP 2.
- F. Shear Stud Connectors: Prepare steel surfaces as recommended by manufacturer of shear connectors. Weld using automatic end welding of headed-stud shear connectors in accordance with AWS D1.1 and manufacturer's written instructions.
- G. Holes: Provide holes required for securing other work to structural steel and for other work to pass through steel members.
 - 1. Cut, drill, or punch holes perpendicular to steel surfaces. Do not thermally cut bolt holes or enlarge holes by burning.
 - 2. Baseplate Holes: Cut, drill, mechanically thermal cut, or punch holes perpendicular to steel surfaces.

2.9 SHOP CONNECTIONS

- A. High-Strength Bolts: Shop install high-strength bolts in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for type of bolt and type of joint specified.
 - 1. Joint Type: As indicated.
- B. Weld Connections: Comply with AWS D1.1 for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.
 - 1. Assemble and weld built-up sections by methods that maintain true alignment of axes without exceeding tolerances in ANSI/AISC 303 for mill material.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.10 GALVANIZING

- A. Hot-Dip Galvanized Finish: Apply zinc coating by the hot-dip process to structural steel in accordance with ASTM A123.
 - 1. Fill vent and drain holes that are exposed in the finished Work unless they function as weep holes, by plugging with zinc solder and filing off smooth.
 - 2. Galvanize lintels and shelf angles attached to structural-steel frame and located in exterior walls.

2.11 SHOP PRIMING

- A. Shop prime steel surfaces, except the following:
 - 1. Surfaces embedded in concrete or mortar. Extend priming of partially embedded members to a depth of 2 inches.
 - 2. Surfaces to be field welded.
 - 3. Surfaces of high-strength bolted, slip-critical connections.
 - 4. Surfaces to receive sprayed fire-resistive materials (applied fireproofing).
 - 5. Galvanized surfaces unless indicated to be painted.
- B. Surface Preparation of Steel: Clean surfaces to be painted. Remove loose rust and mill scale and spatter, slag, or flux deposits. Prepare surfaces in accordance with the following specifications and standards:
 - 1. For Concealed Steel:
 - a. SSPC-SP 2.
 - b. SSPC-SP 3.
 - 2. "For Exposed Steel:
 - a. SSPC-SP 6 (WAB)/NACE WAB-3."SSPC-SP 10 (WAB)/NACE WAB-2"
 Subparagraph below requires that 95 percent of surface area be free of visible residue.
- C. Priming: Immediately after surface preparation, apply primer in accordance with manufacturer's written instructions and at rate recommended by SSPC to provide a minimum dry film thickness of 1.5 mils. Use priming methods that result in full coverage of joints, corners, edges, and exposed surfaces.
 - 1. Stripe paint corners, crevices, bolts, welds, and sharp edges.
 - 2. Apply two coats of shop paint to surfaces that are inaccessible after assembly or erection. Change color of second coat to distinguish it from first.

2.12 SOURCE QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform shop tests and inspections.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Allow testing agency access to places where structural-steel work is being fabricated or produced to perform tests and inspections.
- 2. Bolted Connections: Inspect and test shop-bolted connections in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts."
- 3. Welded Connections: Visually inspect shop-welded connections in accordance with AWS D1.1 and the following inspection procedures, at testing agency's option:
 - a. Liquid Penetrant Inspection: ASTM E165.
 - b. Magnetic Particle Inspection: ASTM E709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration are not accepted.
 - c. Ultrasonic Inspection: ASTM E164.
 - d. Radiographic Inspection: ASTM E94.
- 4. In addition to visual inspection, test and inspect shop-welded shear stud connectors in accordance with requirements in AWS D1.1 for stud welding and as follows:
 - a. Perform bend tests if visual inspections reveal either a less-than-continuous 360-degree flash or welding repairs to any shear stud connector.
 - b. Conduct tests in accordance with requirements in AWS D1.1 on additional shear stud connectors if weld fracture occurs on shear stud connectors already tested.
- 5. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify, with certified steel erector present, elevations of concrete- and masonry-bearing surfaces and locations of anchor rods, bearing plates, and other embedments for compliance with requirements.
 - 1. Prepare a certified survey of existing conditions. Include bearing surfaces, anchor rods, bearing plates, and other embedments showing dimensions, locations, angles, and elevations.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Provide temporary shores, guys, braces, and other supports during erection to keep structural steel secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural steel, connections, and bracing are in place unless otherwise indicated on Drawings.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.3 ERECTION

- A. Set structural steel accurately in locations and to elevations indicated and in accordance with ANSI/AISC 303 and ANSI/AISC 360.
- B. Baseplates, Bearing Plates, and Leveling Plates: Clean concrete- and masonry-bearing surfaces of bond-reducing materials, and roughen surfaces prior to setting plates. Clean bottom surface of plates.
 - 1. Set plates for structural members on wedges, shims, or setting nuts as required.
 - 2. Weld plate washers to top of baseplate.
 - 3. Snug-tighten anchor rods after supported members have been positioned and plumbed. Do not remove wedges or shims but, if protruding, cut off flush with edge of plate before packing with grout.
 - 4. Promptly pack shrinkage-resistant grout solidly between bearing surfaces and plates, so no voids remain. Neatly finish exposed surfaces; protect grout and allow to cure. Comply with manufacturer's written installation instructions for grouting.
- C. Maintain erection tolerances of structural steel within ANSI/AISC 303.
- D. Align and adjust various members that form part of complete frame or structure before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that are in permanent contact with members. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.
 - 1. Level and plumb individual members of structure. Slope roof framing members to slopes indicated on Drawings.
- E. Splice members only where indicated.
- F. Do not use thermal cutting during erection.
- G. Do not enlarge unfair holes in members by burning or using drift pins. Ream holes that must be enlarged to admit bolts.

3.4 FIELD CONNECTIONS

- A. High-Strength Bolts: Install high-strength bolts in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for bolt and joint type specified.
 - 1. Joint Type: As indicated.
- B. Weld Connections: Comply with AWS D1.1 for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.
 - 1. Comply with ANSI/AISC 303 and ANSI/AISC 360 for bearing, alignment, adequacy of temporary connections, and removal of paint on surfaces adjacent to field welds.
 - 2. Assemble and weld built-up sections by methods that maintain true alignment of axes without exceeding tolerances in ANSI/AISC 303 for mill material.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.5 INSTALLATION OF PREFABRICATED BUILDING COLUMNS

A. Install prefabricated building columns to comply with ANSI/AISC 360, manufacturer's written recommendations, and requirements of testing and inspecting agency that apply to the fire-resistance rating indicated.

3.6 REPAIR

A. Galvanized Surfaces: Clean areas where galvanizing is damaged or missing, and repair galvanizing to comply with ASTM A780.

B. Touchup Painting:

- 1. Immediately after erection, clean exposed areas where primer is damaged or missing, and paint with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.
 - a. Clean and prepare surfaces by SSPC-SP 2 hand-tool cleaning or SSPC-SP 3 power-tool cleaning.

3.7 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a special inspector to perform the following special inspections:
 - 1. Verify structural-steel materials and inspect steel frame joint details.
 - 2. Verify weld materials and inspect welds.
 - 3. Verify connection materials and inspect high strength bolted connections.
- B. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
 - 1. Bolted Connections: Inspect and test bolted connections in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts."
 - 2. Welded Connections: Visually inspect field welds in accordance with AWS D1.1.
 - a. In addition to visual inspection, test and inspect field welds in accordance with AWS D1.1 and the following inspection procedures, at testing agency's option:
 - 1) Liquid Penetrant Inspection: ASTM E165.
 - 2) Magnetic Particle Inspection: ASTM E709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration are not accepted.
 - 3) Ultrasonic Inspection: ASTM E164.
 - 4) Radiographic Inspection: ASTM E94.

END OF SECTION 051200

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 052100 - STEEL JOIST FRAMING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. K-series steel joists.
- 2. KCS-type K-series steel joists.
- 3. Steel joist accessories.

B. Related Requirements:

- 1. Section 033000 "Cast-in-Place Concrete" for installing bearing plates in concrete.
- 2. Section 042000 "Unit Masonry" for installing bearing plates in unit masonry.

1.3 DEFINITIONS

- A. SJI's "Specifications": Steel Joist Institute's "Standard Specifications, Load Tables and Weight Tables for Steel Joists and Joist Girders."
- B. Special Joists: Steel joists or joist girders requiring modification by manufacturer to support nonuniform, unequal, or special loading conditions that invalidate load tables in SJI's "Specifications."

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of joist, accessory, and product.
- B. Shop Drawings:
 - 1. Include layout, designation, number, type, location, and spacing of joists.
 - 2. Include joining and anchorage details; bracing, bridging, and joist accessories; splice and connection locations and details; and attachments to other construction.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For manufacturer and professional engineer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Welding certificates.
- C. Manufacturer certificates.
- D. Mill Certificates: For each type of bolt.
- E. Comprehensive engineering analysis of special joists signed and sealed by the qualified professional engineer responsible for its preparation.
- F. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A manufacturer certified by SJI to manufacture joists complying with applicable standard specifications and load tables in SJI's "Specifications."
 - 1. Manufacturer's responsibilities include providing professional engineering services for designing special joists to comply with performance requirements.
- B. Welding Qualifications: Qualify field-welding procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle joists as recommended in SJI's "Specifications."
- B. Protect joists from corrosion, deformation, and other damage during delivery, storage, and handling.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Provide special joists and connections capable of withstanding design loads indicated.
 - 1. Use ASD; data are given at service-load level.
 - 2. Design special joists to withstand design loads with live-load deflections no greater than the following:
 - a. Roof Joists: Vertical deflection of 1/240 of the span.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.2 STEEL JOISTS

- A. K-Series Steel Joist: Manufactured steel joists of type indicated according to "Standard Specification for Open Web Steel Joists, K-Series" in SJI's "Specifications," with steel-angle top- and bottom-chord members, underslung ends, and parallel top chord.
 - 1. Joist Type: K-series steel joists and KCS-type K-series steel joists.
 - 2. K-Series Steel Joist Substitutes: Manufacture according to "Standard Specifications for Open Web Steel Joists, K-Series" in SJI's "Specifications," with steel-angle or -channel members
 - 3. Provide holes in chord members for connecting and securing other construction to joists.
 - 4. Top-Chord Extensions: Extend top chords of joists with SJI's Type S top-chord extensions where indicated, complying with SJI's "Specifications."
 - 5. Extended Ends: Extend bearing ends of joists with SJI's Type R extended ends where indicated, complying with SJI's "Specifications."
 - 6. Do not camber joists.
 - 7. Equip bearing ends of joists with manufacturer's standard beveled ends or sloped shoes if joist slope exceeds 1/4 inch per 12 inches.

2.3 PRIMERS

A. Primer:

- 1. Low-Emitting Materials: Paint and coatings shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- 2. SSPC-Paint 15, or manufacturer's standard shop primer complying with performance requirements in SSPC-Paint 15.
- 3. Provide shop primer that complies with Division 9.

2.4 STEEL JOIST ACCESSORIES

A. Bridging:

- 1. Provide bridging anchors and number of rows of horizontal and/or diagonal bridging of material, size, and type required by SJI's "Specifications for type of joist, chord size, spacing, and span. Furnish additional erection bridging if required for stability.
- B. Steel bearing plates with integral anchorages are specified in Section 055000 "Metal Fabrications."
- C. High-Strength Bolts, Nuts, and Washers: ASTM F3125 Grade A325, Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436, Type 1, hardened carbon-steel washers.
 - 1. Finish: Plain.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. Welding Electrodes: Comply with AWS standards.
- E. Galvanizing Repair Paint: ASTM A780.
- F. Furnish miscellaneous accessories including splice plates and bolts required by joist manufacturer to complete joist assembly.

2.5 CLEANING AND SHOP PAINTING

- A. Clean and remove loose scale, heavy rust, and other foreign materials from fabricated joists and accessories by hand-tool cleaning, SSPC-SP 2 or power-tool cleaning, SSPC-SP 3.
- B. Apply one coat of shop primer to joists and joist accessories to be primed to provide a continuous, dry paint film not less than 1 mil thick.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine supporting substrates, embedded bearing plates, and abutting structural framing for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Do not install joists until supporting construction is in place and secured.
- B. Install joists and accessories plumb, square, and true to line; securely fasten to supporting construction according to SJI's "Specifications, joist manufacturer's written instructions, and requirements in this Section.
 - 1. Before installation, splice joists delivered to Project site in more than one piece.
 - 2. Space, adjust, and align joists accurately in location before permanently fastening.
 - 3. Install temporary bracing and erection bridging, connections, and anchors to ensure that joists are stabilized during construction.
 - 4. Delay rigidly connecting bottom-chord extensions to columns or supports until dead loads are applied.
- C. Field weld joists to supporting steel bearing plates and framework. Coordinate welding sequence and procedure with placement of joists. Comply with AWS requirements and procedures for welding, appearance and quality of welds, and methods used in correcting welding work.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

D. Install and connect bridging concurrently with joist erection, before construction loads are applied. Anchor ends of bridging lines at top and bottom chords if terminating at walls or beams.

3.3 REPAIRS

A. Repair damaged galvanized coatings on galvanized items with galvanized repair paint according to ASTM A780 and manufacturer's written instructions.

B. Touchup Painting:

- 1. Immediately after installation, clean, prepare, and prime or reprime field connections, rust spots, and abraded surfaces of prime-painted joists, bearing plates, abutting structural steel, and accessories.
 - a. Clean and prepare surfaces by SSPC-SP 2 hand-tool cleaning or SSPC-SP 3 power-tool cleaning.
 - b. Apply a compatible primer of same type as primer used on adjacent surfaces.

3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Visually inspect field welds according to AWS D1.1.
 - 1. In addition to visual inspection, test field welds according to AWS D1.1.
- C. Visually inspect bolted connections.
- D. Prepare test and inspection reports.

END OF SECTION 052100

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 053100 - STEEL DECKING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Roof deck.
- B. Related Requirements:
 - 1. Section 055000 "Metal Fabrications" for framing deck openings with miscellaneous steel shapes.

1.3 ACTION SUBMITTALS

- A. Product Data: For the following:
 - 1. Roof deck.
- B. Shop Drawings:
 - 1. Include layout and types of deck panels, anchorage details, reinforcing channels, pans, cut deck openings, special jointing, accessories, and attachments to other construction.

1.4 INFORMATIONAL SUBMITTALS

- A. Welding certificates.
- B. Product Certificates: For each type of steel deck.
- C. Product Test Reports: For tests performed by a qualified testing agency, indicating that each of the following complies with requirements:
 - 1. Power-actuated mechanical fasteners.
- D. Research Reports: For steel deck, from ICC-ES.
- E. Field quality-control reports.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to ASTM E329 for testing indicated.
- B. Welding Qualifications: Qualify procedures and personnel according to AWS D1.3, "Structural Welding Code Sheet Steel."
- C. FM Approvals' RoofNav Listing: Provide steel roof deck evaluated by FM Approvals and listed in its RoofNav for Class 1 fire rating and Class 1-90 windstorm ratings. Identify materials with FM Approvals Certification markings.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Protect steel deck from corrosion, deformation, and other damage during delivery, storage, and handling.
- B. Stack steel deck on platforms or pallets and slope to provide drainage. Protect with a waterproof covering and ventilate to avoid condensation.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. AISI Specifications: Comply with calculated structural characteristics of steel deck according to AISI's "North American Specification for the Design of Cold-Formed Steel Structural Members."
- B. Fire-Resistance Ratings: Comply with ASTM E119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.
- C. Low-Emitting Materials: Paints and coatings shall comply with the testing and product requirements of the California Department of Health Services' Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

2.2 ROOF DECK

- A. Roof Deck: Fabricate panels, without top-flange stiffening grooves, to comply with "SDI Specifications and Commentary for Steel Roof Deck," in SDI Publication No. 31, and with the following:
 - 1. Galvanized-Steel Sheet: ASTM A653, Structural Steel (SS), Grade 50, G60 zinc coating.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Galvanized and Shop-Primed Steel Sheet: ASTM A653, Structural Steel (SS), Grade 40, G60 zinc coating; cleaned, pretreated, and primed with manufacturer's standard baked-on, rust-inhibitive primer.
- 3. Deck Profile: As indicated.
- 4. Profile Depth: As indicated.
- 5. Design Uncoated-Steel Thickness: As indicated.
- 6. Design Uncoated-Steel Thicknesses; Deck Unit/Bottom Plate: As indicated.
- 7. Span Condition: Triple span or more.
- 8. Side Laps: Overlapped or interlocking seam at Contractor's option.

2.3 ACCESSORIES

- A. Provide manufacturer's standard accessory materials for deck that comply with requirements indicated.
- B. Mechanical Fasteners: Corrosion-resistant, low-velocity, power-actuated or pneumatically driven carbon-steel fasteners; or self-drilling, self-threading screws.
- C. Side-Lap Fasteners: Corrosion-resistant, hexagonal washer head; self-drilling, carbon-steel screws, No. 10 minimum diameter, unless otherwise indicated.
- D. Flexible Closure Strips: Vulcanized, closed-cell, synthetic rubber.
- E. Miscellaneous Sheet Metal Deck Accessories: Steel sheet, minimum yield strength of 50,000 psi, not less than 0.0359-inch design uncoated thickness, of same material and finish as deck; of profile indicated or required for application.
- F. Pour Stops and Girder Fillers: Steel sheet, minimum yield strength of 50,000 psi, of same material and finish as deck, and of thickness and profile indicated.
- G. Column Closures, End Closures, Z-Closures, and Cover Plates: Steel sheet, of same material, finish, and thickness as deck unless otherwise indicated.
- H. Flat Sump Plates: Single-piece steel sheet, 0.0747 inch thick, of same material and finish as deck. For drains, cut holes in the field.
- I. Recessed Sump Pans: Single-piece steel sheet, 0.0747 inch thick, of same material and finish as deck, with 3-inch wide flanges and recessed pans of 1-1/2-inch minimum depth. For drains, cut holes in the field.
- J. Galvanizing Repair Paint: ASTM A780.
- K. Repair Paint: Manufacturer's standard rust-inhibitive primer of same color as primer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine supporting frame and field conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

- A. Install deck panels and accessories according to applicable specifications and commentary in SDI Publication No. 31, manufacturer's written instructions, and requirements in this Section.
- B. Install temporary shoring before placing deck panels if required to meet deflection limitations.
- C. Locate deck bundles to prevent overloading of supporting members.
- D. Place deck panels on supporting frame and adjust to final position with ends accurately aligned and bearing on supporting frame before being permanently fastened. Do not stretch or contract side-lap interlocks.
 - 1. Align cellular deck panels over full length of cell runs and align cells at ends of abutting panels.
- E. Place deck panels flat and square and fasten to supporting frame without warp or deflection.
- F. Cut and neatly fit deck panels and accessories around openings and other work projecting through or adjacent to deck.
- G. Provide additional reinforcement and closure pieces at openings as required for strength, continuity of deck, and support of other work.
- H. Comply with AWS requirements and procedures for manual shielded metal arc welding, appearance and quality of welds, and methods used for correcting welding work.
- I. Mechanical fasteners may be used in lieu of welding to fasten deck. Locate mechanical fasteners and install according to deck manufacturer's written instructions.

3.3 INSTALLATION OF ROOF DECK

- A. Fasten roof-deck panels to steel supporting members as indicated.
- B. Side-Lap and Perimeter Edge Fastening: Fasten side laps and perimeter edges of panels between supports as indicated.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- C. End Bearing: Install deck ends over supporting frame with a minimum end bearing of 1-1/2 inches, with end joints as follows:
 - 1. End Joints: Lapped 2 inches minimum.
- D. Roof Sump Pans and Sump Plates: Install over openings provided in roof deck and weld flanges to top of deck. Space welds not more than 12 inches apart with at least one weld at each corner.
- E. Miscellaneous Roof-Deck Accessories: Install ridge and valley plates, finish strips, end closures, and reinforcing channels according to deck manufacturer's written instructions. Weld to substrate to provide a complete deck installation.
 - 1. Weld cover plates at changes in direction of roof-deck panels unless otherwise indicated.
- F. Flexible Closure Strips: Install flexible closure strips over partitions, walls, and where indicated. Install with adhesive according to manufacturer's written instructions to ensure complete closure.

3.4 REPAIR

- A. Galvanizing Repairs: Prepare and repair damaged galvanized coatings on both surfaces of deck with galvanized repair paint according to ASTM A780 and manufacturer's written instructions.
- B. Repair Painting:
 - 1. Wire brush and clean rust spots, welds, and abraded areas on both surfaces of prime-painted deck immediately after installation, and apply repair paint.
 - 2. Apply repair paint, of same color as adjacent shop-primed deck, to bottom surfaces of deck exposed to view.
 - 3. Wire brushing, cleaning, and repair painting of bottom deck surfaces are included in Division 9.
 - 4. Wire brushing, cleaning, and repair painting of rust spots, welds, and abraded areas of both deck surfaces are included in Division 9.

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Field welds will be subject to inspection.
- C. Prepare test and inspection reports.

END OF SECTION 053100

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 055000 METAL FABRICATIONS

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM A36/A36M Standard Specification for Carbon Structural Steel 2019.
- B. ASTM A53/A53M Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless 2022.
- C. ASTM A123/A123M Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products 2017.
- D. ASTM A283/A283M Standard Specification for Low and Intermediate Tensile Strength Carbon Steel Plates 2018.
- E. ASTM A307 Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength 2021.
- F. ASTM A501/A501M Standard Specification for Hot-Formed Welded and Seamless Carbon Steel Structural Tubing 2021.
- G. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process 2022.
- H. ASTM A1011/A1011M Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength 2018a.
- AWS B2.1/B2.1M Specification for Welding Procedure and Performance Qualification 2021.
- J. AWS D1.1/D1.1M Structural Welding Code Steel 2020, with Errata (2022).
- K. AWS D1.2/D1.2M Structural Welding Code Aluminum 2014, with Errata (2020).
- L. SSPC-Paint 15 Steel Joist Shop Primer/Metal Building Primer 2004.
- M. SSPC-Paint 20 Zinc-Rich Coating (Type I Inorganic, and Type II Organic) 2019.

1.02 SUBMITTALS

- A. Product Data: Provide product data for factory fabricated products and accessory materials, including the following:
 - 1. Nonshrink grout.
 - 2. Shop primer paint products.
 - Coordinate with Division 9 Painting topcoat manufacturer and provide compatibility certificates from topcoat manufacturer that shop primers are acceptable substrate for specified topcoats.
- B. Shop Drawings: Indicate profiles, sizes, connection attachments, reinforcing, anchorage, size and type of fasteners, and accessories. Include erection drawings, elevations, and details where applicable.
 - Include field measurements, and indicate where field measurements differ from documents.
- C. Welders' Qualification Statement: Welders' certificates in accordance with AWS B2.1/B2.1M and dated no more than 12 months before start of scheduled welding work.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.03 QUALITY ASSURANCE

- A. Welder Qualifications: Welding processes and welding operators qualified in accordance with AWS D1.1/D1.1M and AWS D1.2/D1.2M and dated no more than 12 months before start of scheduled welding work.
- B. Field Measurements: Take field measurements prior to fabrication and verify that dimensions and tolerances are acceptable for fabricated products to fit the space. Indicate field measurements on shop drawings.

PART 2 PRODUCTS

2.01 MATERIALS - STEEL

- A. Steel Sections: ASTM A36/A36M.
- B. Steel Tubing: ASTM A501/A501M hot-formed structural tubing.
- C. Plates: ASTM A283/A283M.
- D. Pipe: ASTM A53/A53M, Grade B Schedule 40, black finish.
- E. Slotted Channel Fittings: ASTM A1011/A1011M.
- F. Mechanical Fasteners: Same material as or compatible with materials being fastened; type consistent with design and specified quality level.
 - Provide stainless steel fasteners for all exterior construction and for fastening aluminum and stainless steel fabrications.
 - 2. Provide stainless steel fasteners at areas subject to moisture or steam, including mechanical rooms, janitor/custodial rooms with floor sinks, and similar spaces.
 - Provide zinc-plated fasteners for interior construction except where stainless steel is indicated.
- G. Bolts, Nuts, and Washers: ASTM A307, Grade A, plain.
- H. Welding Materials: AWS D1.1/D1.1M; type required for materials being welded.
- Shop and Touch-Up Primer: SSPC-Paint 15, universal shop primer, complying with VOC limitations of authorities having jurisdiction.
- J. Touch-Up Primer for Galvanized Surfaces: SSPC-Paint 20, Type I Inorganic, complying with VOC limitations of authorities having jurisdiction.

2.02 FABRICATION

- A. Fit and shop assemble items in largest practical sections, for delivery to site.
- B. Fabricate items with joints tightly fitted and secured.
- C. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.
- D. Furnish components required for anchorage of fabrications. Fabricate anchors and related components of same material and finish as fabrication, except where specifically noted otherwise.

2.03 FABRICATED ITEMS

- A. Channels and Plates Not Attached to Structural Framing: For support of metal decking and masonry; prime paint finish.
- B. Lintels: As detailed; prime paint finish.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- C. Door Frames for Overhead Door Openings and Wall Openings: Channel or bent plate sections; prime paint finish.
- D. Slotted Channel Framing: Fabricate channels and fittings from structural steel complying with the referenced standards; factory-applied, rust-inhibiting thermoset acrylic enamel finish.
- E. Miscellaneous Steel Shapes: Provide steel shapes for miscellaneous applications indicated on drawings, including but not limited to, reinforcing steel shapes at low partitions/knee walls and concrete slab edge angles.

2.04 FINISHES - STEEL

- A. Prime paint steel items.
 - 1. Exceptions: Galvanize and do not prime items to be embedded in concrete and items to be embedded in masonry. Do not prime items to be embedded in sprayed fireproofing.
- B. Prepare interior items to be primed in accordance with SSPC-SP3 Power Tool Cleaning.
- C. Prepare exterior items to be primed, and interior items to receive specialty protective coating such as zinc-rich primer, in accordance with SSPC-SP 6/NACE No. 3 Commercial Blast Cleaning.
- D. Clean surfaces of rust, scale, grease, and foreign matter prior to finishing.
- E. Prime Painting: One coat.
- F. Galvanizing: Galvanize after fabrication to ASTM A123/A123M requirements.
- G. Slotted Channel Framing: ASTM A653/A653M, Grade 33.

2.05 FABRICATION TOLERANCES

- A. Squareness: 1/8 inch maximum difference in diagonal measurements.
- B. Maximum Offset Between Faces: 1/16 inch.
- C. Maximum Misalignment of Adjacent Members: 1/16 inch.
- D. Maximum Bow: 1/8 inch in 48 inches.
- E. Maximum Deviation From Plane: 1/16 inch in 48 inches.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive work.

3.02 PREPARATION

- A. Clean and strip primed steel items to bare metal where site welding is required.
- B. Furnish setting templates to the appropriate entities for steel items required to be cast into concrete or embedded in masonry.

3.03 INSTALLATION

- A. Install items plumb and level, accurately fitted, free from distortion or defects.
- B. Provide for erection loads, and for sufficient temporary bracing to maintain true alignment until completion of erection and installation of permanent attachments.
- C. Perform field welding in accordance with AWS D1.1/D1.1M.
- D. Obtain approval prior to site cutting or making adjustments not scheduled.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

E. After erection, prime welds, abrasions, and surfaces not shop primed, except surfaces to be in contact with concrete.

3.04 TOLERANCES

- A. Maximum Variation From Plumb: 1/4 inch per story, non-cumulative.
- B. Maximum Offset From True Alignment: 1/4 inch.
- C. Maximum Out-of-Position: 1/4 inch.

END OF SECTION 055000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 075423 TPO MEMBRANE ROOFING

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM C177 Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus 2019.
- B. ASTM C552 Standard Specification for Cellular Glass Thermal Insulation 2022.
- C. ASTM C1177/C1177M Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing 2017.
- D. ASTM C1289 Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board 2022a.
- E. ASTM D6878/D6878M Standard Specification for Thermoplastic Polyolefin-Based Sheet Roofing 2021.
- F. FM (AG) FM Approval Guide current edition.
- G. FM DS 1-28 Wind Design 2015, with Editorial Revision (2022).
- H. NRCA (RM) The NRCA Roofing Manual 2022.
- NRCA (WM) The NRCA Waterproofing Manual 2021.
- J. UL (FRD) Fire Resistance Directory Current Edition.

1.02 ADMINISTRATIVE REQUIREMENTS

- Preinstallation Meeting: Convene at the Project site one week before starting work of this section.
 - 1. Review preparation and installation procedures and coordinating and scheduling required with related work.

1.03 SUBMITTALS

- A. Product Data: Provide data indicating membrane materials, flashing materials, insulation, vapor retarder, surfacing, and fasteners.
- B. Shop Drawings: Submit drawings that indicate joint or termination detail conditions, conditions of interface with other materials, and paver layout.
- C. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.
 - Submit in the form of manufacturer's assembly letter, indicating each component of the roofing assembly as specified, and that assembly meets performance requirements and manufacturer's warranty conditions.
- D. Manufacturer's Field Reports: Indicate procedures followed, ambient temperatures, humidity, wind velocity during application, and supplementary instructions given.
- E. Manufacturer's qualification statement.
- F. Installer's qualification statement.
- G. Warranty Documentation:
 - 1. Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2. Submit installer's written verification that installation complies with warranty conditions for waterproof membrane.

1.04 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacture of products specified, with UL-listed roof assemblies for roof systems indicated.
- B. Installer Qualifications: Company specializing in installation of roof systems indicated, and approved / certified by roofing manufacturer to install products specified.
- C. Insulation Manufacturer Qualifications: Approved by roof membrane manufacturer, and approved and labeled under third party quality program as required by applicable building code.
 - 1. Insulation Labeling: All foam insulation shall bear the label of testing/inspection agency, and shall include manufacturer identification, product identification, and performance characteristics.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials in manufacturer's original containers, dry and undamaged, with seals and labels intact, unless otherwise indicated.
- B. Store materials in weather protected environment, clear of ground and moisture.
- C. Ensure storage and staging of materials does not exceed static and dynamic load-bearing capacities of roof decking.
- D. Protect foam insulation from direct exposure to sunlight.

1.06 FIELD CONDITIONS

- A. Do not install roofing materials during unsuitable weather, or when unsuitable weather is expected. Proceed only when field conditions are in accordance with roofing manufacturer's installation and warranty requirements.
- B. Do not expose materials vulnerable to water or sun damage in quantities greater than can be weatherproofed the same day.
- C. Schedule applications so that no partially completed sections of roof are left exposed at end of workday.

1.07 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Special Warranty Manufacturer: Manufacturer's standard warranty form, customized for project-specific conditions.
 - 1. Manufacturer's warranty shall be a "total system" or "edge-to-edge" warranty; no dollar limit ("NDL").
 - 2. Include all components of roofing system including, but not limited to, roofing membrane, roof insulation, adhesives and fasteners, flashings, edge metals and copings, substrate board, vapor retarder/air barrier, roof insulation, and cover board.
 - 3. Manufacturer's Total System Warranty Period: 20 years, from date of Substantial Completion.
- Special Warranty Installer: Installer shall sign and submit per warranty form attached at end of this section.
 - Installer's warranty shall cover all components of roofing system, matching manufacturer's warranty above.
 - 2. Installer's Warranty Period: 2 years, from date of Substantial Completion.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Thermoplastic Polyolefin (TPO) Membrane Roofing Materials:
 - Carlisle Roofing Systems, Inc.
 - 2. Firestone Building Products, LLC.
 - 3. Johns Manville.

2.02 ROOFING

- A. Thermoplastic Membrane Roofing: One ply membrane, fully adhered, over vapor retarder and insulation.
- B. Roofing Assembly Requirements:
 - 1. Roof Covering External Fire Resistance Classification: UL (FRD) Class A.
 - 2. Assembly Thermal Resistance (R-Value): Roofing assembly shall have a total minimum R-value of 30 in accordance with IECC for Commercial Buildings.

2.03 MEMBRANE ROOFING AND ASSOCIATED MATERIALS

- A. Membrane Roofing Materials:
 - TPO: Thermoplastic polyolefin (TPO) complying with ASTM D6878/D6878M, sheet contains reinforcing fabrics or scrims.
 - a. Thickness: 60 mil, 0.060 inch, minimum.
 - 2. Sheet Width: Factory fabricated into widest possible sheets.
 - 3. Color: White.
- B. Seaming Materials: As recommended by membrane manufacturer.
- C. Flexible Flashing Material: Same material as membrane.

2.04 DECK SHEATHING

- A. Thermal Barrier: Deck sheathing shall serve as an approved thermal barrier, as required by applicable building code, separating foam plastic roof insulation from the interior of the building.
- B. Deck Sheathing: Glass-mat faced gypsum panels complying with ASTM C1177/C1177M.
 - 1. Thickness: 1/2 inch, fire-resistant.
 - 2. Products:
 - a. CertainTeed Corporation; GlasRoc Sheathing.
 - b. Georgia-Pacific; DensDeck Prime.
 - National Gypsum Company; DEXcell Glass Mat Roof Board.
 - d. USG Corporation; Securock Ultralight Glass-Mat Roof Board.

2.05 VAPOR RETARDER / AIR BARRIER

- A. Vapor Retarder / Air Barrier Sheet, Self-Adhered: Composite sheet fabricated of rubberized asphalt factory laminated to polyethylene/polypropylene film with release liner. Product shall be approved by primary roofing manufacturer, and comply with the following:
 - 1. Total Thickness: 30 mils, minimum.
 - 2. Air Permeance: Less than 0.004 cfm/sq.ft. when tested per ASTM E 2178.
 - 3. Vapor Permeance: Less than 0.1 perm when tested per ASTM E 96.
 - 4. Products:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- a. Carlisle; VapAir Seal 725 TR.
- b. Firestone; V-Force Vapor Barrier.
- c. Johns Manville; JM Vapor Barrier SA.

2.06 COVER BOARDS

- A. Cover Board: High compressive strength polyisocyanurate (ISO) board insulation complying with ASTM C1289, and the following characteristics:
 - 1. Classification: Type II, Class 4 Faced with coated or uncoated polymer-bonded glass fiber mat facers on both major surfaces of the core foam.
 - 2. Compressive Strength: Type II, Class 4; Grade 1, 80 psi.
 - 3. Board Thickness: 1/2 inch.
 - 4. Thermal Resistance: R-value of 2.5, minimum, at 1/2 inch thick and 75 degrees F mean temperature.
 - 5. Products:
 - a. Carlisle; SecurShield HD.
 - b. Firestone; Isogard HD Cover Board.
 - c. Johns Manville; ProtectoR.

2.07 INSULATION

- A. Surface Burning Characteristics: Foam plastic insulation shall have a maximum flame spread index of 75, and maximum smoke developed index of 450, when tested in accordance with ASTM E84 at maximum thickness intended for use.
- B. Polyisocyanurate (ISO) Board Insulation: Rigid cellular foam, complying with ASTM C1289.
 - 1. Classifications:
 - a. Type II:
 - Class 1 Faced with glass fiber reinforced cellulosic felt facers on both major surfaces of core foam.
 - 2) Compressive Strength: Classes 1-2-3, Grade 2, 20 psi (138 kPa), minimum.
 - 2. Tapered Board: Slope as indicated, but no lower than 1/4 inch per foot; minimum thickness 1/2 inch; fabricate of fewest layers possible.
 - 3. Preformed Shapes: Provide saddles crickets, tapered edge strips, and other insulation shapes where indicated for sloping to drain. Fabricate to slopes indicated, but no less than 1/4 inch per 12 inches, and no less than 1/8 inch per 12 inches in valleys.

2.08 ACCESSORIES

- A. Stack Boots: Prefabricated flexible boot and collar for pipe stacks through membrane; same material as membrane.
- B. Sheathing Joint Tape: Paper type, self adhering.
- C. Insulation Joint Tape: Glass fiber reinforced type as recommended by insulation manufacturer, compatible with roofing materials; 6 inches wide; self adhering.
- D. Insulation Fasteners: Appropriate for purpose intended and approved by roofing manufacturer.
 - Length as required for thickness of insulation material and penetration of deck substrate, with metal washers.
- E. Membrane Adhesive: As recommended by membrane manufacturer.
- F. Insulation Adhesive: As recommended by insulation manufacturer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- G. Sealants: As recommended by membrane manufacturer.
- H. Walkway Pads: Suitable for maintenance traffic, contrasting color or otherwise visually distinctive from roof membrane.
 - 1. Composition: Roofing membrane manufacturer's standard.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces and site conditions are ready to receive work.
- B. Verify deck is supported and secure.
- C. Verify deck is clean and smooth, flat, free of depressions, waves, or projections, properly sloped and suitable for installation of roof system.
- D. Verify deck surfaces are dry and free of snow or ice.
- E. Verify that roof openings, curbs, and penetrations through roof are solidly set, and other accessories are in place.

3.02 PREPARATION - METAL DECK

- A. Install deck sheathing on metal deck:
 - 1. Lay with long side at right angle to flutes; stagger end joints; provide support at ends.
 - 2. Cut sheathing cleanly and accurately at roof breaks and protrusions to provide smooth surface.
 - 3. Tape joints.
 - Mechanically fasten sheathing to roof deck, in accordance with Factory Mutual recommendations and roofing manufacturer's instructions.
 - a. At locations where metal roof deck will be exposed from below in the finished work, carefully coordinate fastener attachment such that fasteners do not penetrate the bottom flanges of the metal deck. Remove fasteners that penetrate the bottom flanges and replace with properly located fasteners, and restore metal deck to Owner's satisfaction.

3.03 INSTALLATION, GENERAL

- A. Perform work in accordance with manufacturer's instructions, NRCA (RM), and NRCA (WM) applicable requirements.
- B. Do not apply roofing membrane during cold or wet weather conditions.
- C. Do not apply roofing membrane when ambient temperature is outside the temperature range recommended by manufacturer.
- D. Do not apply roofing membrane to damp or frozen deck surface or when precipitation is expected or occurring.
- E. Do not expose materials vulnerable to water or sun damage in quantities greater than can be weatherproofed the same day.

3.04 INSTALLATION - VAPOR RETARDER AND INSULATION, UNDER MEMBRANE

- Install vapor retarder over sheathing surface in accordance with manufacturer's instructions.
 - 1. Extend vapor retarder under blocking to deck edge.
 - 2. Install flexible flashing from vapor retarder to air seal material of wall construction, lap and seal to provide continuity of the air barrier plane.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. Ensure vapor retarder is clean and dry, continuous, and ready for application of insulation.
- C. Attachment of Insulation:
 - Mechanically fasten first layer of insulation to deck in accordance with roofing manufacturer's instructions and FM DS 1-28 Factory Mutual requirements.
 - a. At locations where metal roof deck will be exposed from below in the finished work, carefully coordinate fastener attachment such that fasteners do not penetrate the bottom flanges of the metal deck. Remove fasteners that penetrate the bottom flanges and replace with properly located fasteners, and restore metal deck to Owner's satisfaction.
 - 2. Embed subsequent layer(s) of insulation into full bed of adhesive in accordance with roofing and insulation manufacturers' instructions.
 - 3. Install a minimum of two layers of insulation, with a minimum total thickness of 5 inches, to achieve a cumulative Long Term Thermal Resistance (LTTR) value of 28.5 per ASTM C 1289, followed by a cover board.
- D. Lay subsequent layers of insulation with joints staggered minimum 6 inches from joints of preceding layer.
- E. Place tapered insulation to the required slope pattern in accordance with manufacturer's instructions.
- F. On metal deck, place boards parallel to flutes with insulation board edges bearing on deck flutes.
- G. Lay boards with edges in moderate contact without forcing. Cut insulation to fit neatly to perimeter blocking and around penetrations through roof.
- H. Tape joints of insulation in accordance with roofing and insulation manufacturers' instructions.
- At roof drains, use factory-tapered boards to slope down to roof drains over a distance of 18 inches.
- J. Do not install more insulation than can be covered with membrane in same day.
- K. Cover Boards: Secure cover boards in accordance with roofing manufacturer's instructions with manufacturer's insulation adhesive. Install cover boards with joints staggered minimum 6 inches from joints of preceding insulation layer.

3.05 INSTALLATION - MEMBRANE

- A. Roll out membrane, free from wrinkles or tears. Place sheet into place without stretching.
- B. Shingle joints on sloped substrate in direction of drainage.
- C. Fully Adhered Application: Apply adhesive to substrate per manufacturer's instruction. Fully embed membrane in adhesive except in areas directly over or within 3 inches of expansion joints. Fully adhere one roll before proceeding to adjacent rolls.
- D. Overlap edges and ends and seal seams by contact adhesive, minimum 3 inches. Seal permanently waterproof. Apply uniform bead of sealant to joint edge.
- E. At intersections with vertical surfaces:
 - 1. Extend membrane over cant strips and up a minimum of 4 inches onto vertical surfaces.
 - Fully adhere flexible flashing over membrane and up to nailing strips.
- F. Around roof penetrations, seal flanges and flashings with flexible flashing.
- G. Install roofing expansion joints where indicated. Make joints watertight.
- H. Coordinate installation of roof drains and sumps and related flashings.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

 Install walkway pads in layout indicated. If not indicated, provide from roof access hatch/door to each major piece of rooftop equipment and fully around perimeter of equipment. Space pad joints to permit drainage.

3.06 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Provide on-site inspection by roofing manufacturer's technical representative at least three times (deck/substrate examination, in-progress, and warranty inspection) during installation of this work.
- C. Repair or replace roofing components where inspection determines they are defective.
 - 1. Repair or replace roofing system where ponding occurs in excess of specified requirement.

3.07 CLEANING

- A. See Section 017000 Execution and Closeout Requirements for additional requirements.
- B. In areas where finished surfaces are soiled by work of this section, consult manufacturer of surfaces for cleaning advice and comply with their documented instructions.
- C. Repair or replace defaced or damaged finishes caused by work of this section.
- D. Provide a final cleaning of the roof membrane immediately prior to Substantial Completion to remove dirt, clay and other soiling.

3.08 PROTECTION

- A. Protect installed roofing and flashings from construction operations.
- B. Where traffic must continue over finished roof membrane, protect surfaces using durable materials.

END OF SECTION 075423

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 079200 JOINT SEALANTS

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM C794 Standard Test Method for Adhesion-in-Peel of Elastomeric Joint Sealants 2018 (Reapproved 2022).
- B. ASTM C834 Standard Specification for Latex Sealants 2017.
- C. ASTM C919 Standard Practice for Use of Sealants in Acoustical Applications 2022.
- D. ASTM C920 Standard Specification for Elastomeric Joint Sealants 2018.
- E. ASTM C1087 Standard Test Method for Determining Compatibility of Liquid-Applied Sealants with Accessories Used in Structural Glazing Systems 2016.
- F. ASTM C1193 Standard Guide for Use of Joint Sealants 2016.
- G. ASTM C1248 Standard Test Method for Staining of Porous Substrate by Joint Sealants 2022.
- H. ASTM C1311 Standard Specification for Solvent Release Sealants 2022.
- I. ASTM C1521 Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints 2019 (Reapproved 2020).

1.02 SUBMITTALS

- A. Product Data for Sealants: Submit manufacturer's technical data sheets for each product to be used, that includes the following.
 - Physical characteristics, including movement capability, VOC content, hardness, cure time, and color availability.
 - 2. List of backing materials approved for use with the specific product.
 - 3. Substrates that product is known to satisfactorily adhere to and with which it is compatible.
 - 4. Substrates the product should not be used on.
- B. Product Data for Accessory Products: Submit manufacturer's technical data sheet for each product to be used, including physical characteristics, installation instructions, and recommended tools.
- C. Color Cards for Selection: Where sealant color is not specified, submit manufacturer's color cards showing standard colors available for selection.
- D. Preconstruction Laboratory Test Reports: Submit at least four weeks prior to start of installation.
- E. Preinstallation Field Adhesion Test Plan: Submit at least two weeks prior to start of installation.
- F. Preinstallation Field Adhesion Test Reports: Submit filled out Preinstallation Field Adhesion Test Reports log within 10 days after completion of tests; include bagged test samples and photographic records.

1.03 QUALITY ASSURANCE

- A. Installer Qualifications: Company specializing in performing the work of this section, and is approved and/or certified by manufacturer.
- B. Preconstruction Laboratory Testing: Arrange for sealant manufacturer(s) to test each combination of sealant, substrate, backing, and accessories.

Joint Sealants 079200 - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 1. Adhesion Testing: In accordance with ASTM C794.
- 2. Compatibility Testing: In accordance with ASTM C1087.
- 3. Allow sufficient time for testing to avoid delaying the work.
- 4. Deliver to manufacturer sufficient samples for testing.
- 5. Report manufacturer's recommended corrective measures, if any, including primers or techniques not indicated in product data submittals.
- 6. Testing is not required if sealant manufacturer provides data showing previous testing, not older than 24 months, that shows satisfactory adhesion, lack of staining, and compatibility.
- C. Preinstallation Field Adhesion Test Plan: Include destructive field adhesion testing of one sample of each combination of sealant type and substrate, except interior acrylic latex sealants, and include the following for each tested sample.
 - 1. Identification of testing agency.
 - 2. Preinstallation Field Adhesion Test Log Form: Include the following data fields, with known information filled out.
 - a. Test date.
 - b. Copy of test method documents.
 - c. Age of sealant upon date of testing.
 - d. Test results, modeled after the sample form in the test method document.
 - e. Indicate use of photographic record of test.
- D. Field Adhesion Test Procedures:
 - 1. Allow sealants to fully cure as recommended by manufacturer before testing.
 - 2. Have a copy of the test method document available during tests.
 - 3. Record the type of failure that occurred, other information required by test method, and the information required on the Field Quality Control Log.
 - 4. When performing destructive tests, also inspect the opened joint for proper installation characteristics recommended by manufacturer, and report any deficiencies.
 - 5. Deliver the samples removed during destructive tests in separate sealed plastic bags, identified with project, location, test date, and test results, to Owner.
 - 6. If any combination of sealant type and substrate does not show evidence of minimum adhesion or shows cohesion failure before minimum adhesion, report results to Architect.
- E. Destructive Field Adhesion Test: Test for adhesion in accordance with ASTM C1521, using Destructive Tail Procedure.
 - Sample: At least 18 inches long.
 - 2. Minimum Elongation Without Adhesive Failure: Consider the tail at rest, not under any elongation stress; multiply the stated movement capability of the sealant in percent by two; then multiply 1 inch by that percentage; if adhesion failure occurs before the "1 inch mark" is that distance from the substrate, the test has failed.
 - If either adhesive or cohesive failure occurs prior to minimum elongation, take necessary
 measures to correct conditions and re-test; record each modification to products or
 installation procedures.

1.04 WARRANTY

- A. See Section 017800 Closeout Submittals, for additional warranty requirements.
- B. Correct defective work within a five year period after Date of Substantial Completion.
- C. Warranty: Include coverage for installed sealants and accessories that fail to achieve watertight seal, exhibit loss of adhesion or cohesion, or do not cure.

Joint Sealants 079200 - 2

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 2 PRODUCTS

2.01 JOINT SEALANT APPLICATIONS

A. Scope:

- 1. Exterior Joints: Seal open joints, whether or not the joint is indicated on drawings, unless specifically indicated not to be sealed. Exterior joints to be sealed include, but are not limited to, the following items.
 - a. Wall expansion and control joints.
 - b. Joints between door, window, and other frames and adjacent construction.
 - c. Joints between different exposed materials.
 - d. Openings below ledge angles in masonry.
 - e. Other joints indicated below.
- 2. Interior Joints: Do not seal interior joints unless specifically indicated to be sealed. Interior joints to be sealed include, but are not limited to, the following items.
 - a. Joints between door, window, and other frames and adjacent construction.
 - b. Wall and ceiling joints.
 - c. Joints between plumbing fixtures and floor or wall construction.
 - Other joints indicated below.
- 3. Do not seal the following types of joints.
 - a. Intentional weepholes in masonry.
 - b. Joints indicated to be treated with manufactured expansion joint cover or some other type of sealing device.
 - Joints where sealant is specified to be provided by manufacturer of product to be sealed
 - d. Joints where installation of sealant is specified in another section.
 - e. Joints between suspended panel ceilings/grid and walls.
- B. Exterior Joints: Use non-sag non-staining silicone sealant (ES-1), unless otherwise indicated.
 - Type ES-5 Control and Expansion Joints in Concrete Paving: Self-leveling polyurethane "traffic-grade" sealant.
 - 2. Type ES-1 or ES-2 Joints between walls and frames of doors, windows, and louvers.
 - 3. Type SRS-1 Bedding joints.
- C. Interior Joints: Use non-sag polyurethane sealant (ES-4), unless otherwise indicated.
 - 1. Type ES-3 Joints between Fixtures in Wet Areas and Floors, Walls, and Ceilings: Mildew-resistant silicone sealant; white.
 - 2. Type ES-5 Floor Joints: Self-leveling polyurethane "traffic-grade" sealant.
 - 3. Type AS-1 Joints at sound-rated or acoustic assemblies, and at full-height panel wall and partition assemblies indicated to have sound attenuation batts.
 - 4. Type LS-1 Joints around perimeters of interior doors, windows, elevator entrances, and similar framed openings.
- D. Interior Wet Areas: Bathrooms, restrooms, and kitchens; fixtures in wet areas include plumbing fixtures, countertops, cabinets, and other similar items.
- E. Sound-Rated Assemblies: Walls and ceilings identified as "STC-rated", "sound-rated", or "acoustical".

Joint Sealants 079200 - 3

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.02 NONSAG JOINT SEALANTS

- A. Type ES-1 Low-Modulus Non-Staining Silicone Sealant: ASTM C920, Grade NS, Uses M and A; not expected to withstand continuous water immersion or traffic.
 - 1. Movement Capability: Plus and minus 50 percent, minimum.
 - 2. Non-Staining To Porous Stone: Non-staining to light-colored natural stone when tested in accordance with ASTM C1248.
 - 3. Dirt Pick-Up: Reduced dirt pick-up compared to other silicone sealants.
 - 4. Color: To be selected by Architect from manufacturer's standard range.
 - Manufacturers:
 - a. Master Builders Solutions; MasterSeal NP 100.
 - b. Momentive Performance Materials, Inc/GE Silicones; SCS 2000 SilPruf.
 - c. Pecora Corporation; Pecora 890 NST (Non-Staining Technology) or 890 FST (Field Tint).
 - d. Polymeric Systems, Inc.; PSI-641.
 - e. Tremco Commercial Sealants & Waterproofing; Spectrem 3 or Spectrem 4-TS (Field Tint).
 - f. Substitutions: See Section 016000 Product Requirements.
- B. Type ES-2 Medium-Modulus Non-Staining Silicone Sealant: ASTM C920, Grade NS, Uses M and A; not expected to withstand continuous water immersion or traffic.
 - 1. Movement Capability: Plus and minus 50 percent, minimum.
 - 2. Non-Staining To Porous Stone: Non-staining to light-colored natural stone when tested in accordance with ASTM C1248.
 - 3. Dirt Pick-Up: Reduced dirt pick-up compared to other silicone sealants.
 - 4. Color: To be selected by Architect from manufacturer's standard range.
 - 5. Manufacturers:
 - a. Dow Chemical Company; DOWSIL 795 Silicone Building Sealant.
 - Momentive Performance Materials, Inc/GE Silicones; SCS9000 SilPruf NB Non-Staining Silicone Weatherproofing Sealant.
 - c. Pecora Corporation; Pecora 895 NST (Non-Staining Technology).
 - d. Tremco Commercial Sealants & Waterproofing; Spectrem 2.
 - e. Substitutions: See Section 016000 Product Requirements.
- C. Type ES-3 Mildew-Resistant Silicone Sealant: ASTM C920, Grade NS, Uses M and A; single component, mildew resistant; not expected to withstand continuous water immersion or traffic. Neutral- or acid-curing per manufacturer standard.
 - 1. Color: White.
 - 2. Manufacturers:
 - a. Dow; DOWSIL 786 Mildew Resistant.
 - b. Pecora Corporation; Pecora 898 NST (Non-Staining Technology).
 - c. Tremco Commercial Sealants & Waterproofing; Tremsil 600 or Tremsil 200.
 - d. Substitutions: See Section 016000 Product Requirements.
- D. Type ES-4 Polyurethane Sealant: ASTM C920, Grade NS, Uses M and A; multi-component; not expected to withstand continuous water immersion or traffic.
 - 1. Movement Capability: Plus and minus 25 percent, minimum.
 - 2. Color: To be selected by Architect from manufacturer's standard range.
 - Manufacturers:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- a. ITW Polymers Sealants; Permathane SM 7200.
- b. Master Builders Solutions by BASF; MasterSeal NP2.
- c. Pecora Corporation; DynaTrol II.
- d. Sika Corporation; Sikaflex-2c NS.
- e. Tremco Commercial Sealants & Waterproofing; Dymeric 240 FC or Vulkem 227.
- f. Substitutions: See Section 016000 Product Requirements.
- E. Type LS-1 Acrylic Emulsion Latex: Water-based; ASTM C834, single component, non-staining, non-bleeding, non-sagging; not intended for exterior use.
 - 1. Color: To be selected by Architect from manufacturer's standard range.
 - 2. Grade: ASTM C834; Grade NF.
 - 3. Manufacturers:
 - Bostik, Inc; Chem-Calk 600.
 - b. ITW Polymers Sealants; SM 8200.
 - c. Master Builders Solutions; MasterSeal NP 520.
 - d. Pecora Corporation; AC-20 +Silicone.
 - e. Tremco Commercial Sealants & Waterproofing; Tremflex 834.
 - f. Substitutions: See Section 016000 Product Requirements.
- F. Type AS-1 Acrylic Emulsion Latex: Water-based; ASTM C834, single component, non-staining, non-bleeding, non-sagging acoustical sealant.
 - 1. Color: Standard colors matching finished surfaces, Type OP (opaque).
 - 2. Grade: ASTM C834; Grade NF.
 - 3. Manufacturers:
 - a. Accumetric LLC: BOSS 826 Acoustical Sound Sealant.
 - Franklin International, Inc; Titebond GREENchoice Acoustical Smoke & Sound Sealant.
 - c. Hilti, Inc; CP 506 Smoke and Acoustical Sealant.
 - d. Master Builders Solutions; MasterSeal NP 520.
 - e. Momentive Performance Materials, Inc/GE Silicones; RCS20 Acoustical.
 - f. Pecora Corporation; AC-20 FTR or AIS-919.
 - g. Specified Technologies Inc; Smoke N' Sound Acoustical Sealant.
 - h. Tremco Commercial Sealants & Waterproofing; Tremstop Smoke and Sound.
 - i. Substitutions: See Section 016000 Product Requirements.
- G. Type SRS-1 Butyl Sealant: Solvent-based; ASTM C1311; single component, nonsag; not expected to withstand continuous water immersion or traffic.
 - 1. Manufacturers:
 - a. Bostik, Inc; Chem-Calk 300.
 - b. Pecora Corporation; Pecora BC-158 Butyl Rubber Sealant.
 - c. Tremco Inc.; Tremco Butyl Sealant.
 - d. Substitutions: See Section 016000 Product Requirements.

2.03 SELF-LEVELING SEALANTS

- A. Type ES-5 Self-Leveling Polyurethane Sealant for Traffic: Polyurethane; ASTM C920, Grade P, Uses M and A; single or multi-component; explicitly approved by manufacturer for traffic exposure.
 - 1. Movement Capability: Plus and minus 25 percent, minimum.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

Manufacturers:

- a. Bostik, Inc.; Chem-Calk 550.
- b. ITW Polymers Sealants; Permathane SM 7201.
- c. Pacific Polymers, Inc; Elast-Thane 227 Type 1 (Self-Leveling).
- d. Polymeric Systems, Inc; PSI-270SL.
- e. Tremco Commercial Sealants & Waterproofing; THC-901 or THC-900.
- f. W. R. MEADOWS, Inc; POURTHANE SL.
- g. Substitutions: See Section 016000 Product Requirements.

2.04 ACCESSORIES

- A. Backer Rod: Cylindrical cellular foam rod with surface that sealant will not adhere to, compatible with specific sealant used, and recommended by backing and sealant manufacturers for specific application.
- B. Backing Tape: Self-adhesive polyethylene tape with surface that sealant will not adhere to and recommended by tape and sealant manufacturers for specific application.
- C. Masking Tape: Self-adhesive, nonabsorbent, non-staining, removable without adhesive residue, and compatible with surfaces adjacent to joints and sealants.
- D. Joint Cleaner: Non-corrosive and non-staining type, type recommended by sealant manufacturer; compatible with joint forming materials.
- E. Primers: Type recommended by sealant manufacturer to suit application; non-staining.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that joints are ready to receive work.
- B. Verify that backing materials are compatible with sealants.
- C. Verify that backer rods are of the correct size.
- D. Preinstallation Adhesion Testing: Install a sample for each test location indicated in the test plan.
 - 1. Test each sample as specified in PART 1 under QUALITY ASSURANCE article.
 - 2. Notify Architect of date and time that tests will be performed, at least seven days in advance.
 - 3. Record each test on Preinstallation Adhesion Test Log as indicated.
 - 4. If any sample fails, review products and installation procedures, consult manufacturer, or take whatever other measures are necessary to ensure adhesion; re-test in a different location; if unable to obtain satisfactory adhesion, report to Architect.
 - 5. After completion of tests, remove remaining sample material and prepare joint for new sealant installation.

3.02 PREPARATION

- A. Remove loose materials and foreign matter that could impair adhesion of sealant.
- B. Clean joints, and prime as necessary, in accordance with manufacturer's instructions.
- C. Perform preparation in accordance with manufacturer's instructions and ASTM C1193.
- D. Mask elements and surfaces adjacent to joints from damage and disfigurement due to sealant work; be aware that sealant drips and smears may not be completely removable.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

E. Concrete Floor Joints That Will Be Exposed in Completed Work: Test joint filler in inconspicuous area to verify that it does not stain or discolor slab.

3.03 INSTALLATION

- Perform work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions.
- B. Perform installation in accordance with ASTM C1193.
- C. Perform acoustical sealant application work in accordance with ASTM C919.
- D. Measure joint dimensions and size joint backers to achieve width-to-depth ratio, neck dimension, and surface bond area as recommended by manufacturer, except where specific dimensions are indicated.
- E. Install bond breaker backing tape where backer rod cannot be used.
- F. Install sealant free of air pockets, foreign embedded matter, ridges, and sags, and without getting sealant on adjacent surfaces.
- G. Do not install sealant when ambient temperature is outside manufacturer's recommended temperature range, or will be outside that range during the entire curing period, unless manufacturer's approval is obtained and instructions are followed.
- H. Nonsag Sealants: Tool surface concave, unless otherwise indicated; remove masking tape immediately after tooling sealant surface.
- I. Concrete Floor Joint Filler: After full cure, shave joint filler flush with top of concrete slab.

3.04 FIELD QUALITY CONTROL

- Perform field quality control inspection/testing as specified in PART 1 under QUALITY ASSURANCE article.
- B. Destructive Adhesion Testing: If there are any failures in first 1000 linear feet, notify Architect immediately.
- C. Remove and replace failed portions of sealants using same materials and procedures as indicated for original installation.
- D. Repair destructive test location damage immediately after evaluation and recording of results.

END OF SECTION 079200

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 079513 EXPANSION JOINT COVER ASSEMBLIES

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ITS (DIR) Directory of Listed Products Current Edition.
- B. UL (DIR) Online Certifications Directory Current Edition.

1.02 ADMINISTRATIVE REQUIREMENTS

A. Installation Templates: For frames and anchors to be embedded in concrete or masonry, furnish templates to relevant installers; include installation instructions and tolerances.

1.03 SUBMITTALS

- A. Product Data: Provide joint assembly profiles, profile dimensions, anchorage devices and available colors and finish.
- B. Shop Drawings: Indicate joint and splice locations, miters, layout of the work, affected adjacent construction and anchorage locations.
- C. Manufacturer's Installation Instructions: Indicate rough-in sizes and required tolerances for item placement.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Metal/Resilient Expansion Joint Cover Assemblies:
 - 1. Architectural Art Mfg, Inc.
 - 2. Balco, Inc.
 - 3. Construction Specialties, Inc.
 - 4. Inpro.
 - 5. MM Systems Corp:.
 - 6. Substitutions: See Section 016000 Product Requirements.

2.02 EXPANSION JOINT COVER ASSEMBLY APPLICATIONS

- A. General: Provide 2-inch joint assemblies at all locations, unless otherwise indicated.
 - Color for all joints shall be selected from manufacturer's full range of available colors.
- B. Exterior Wall Joints (Preformed Foam): Pre-compressed and self-expanding, open-cell urethane foam. Pre-coated with water repellant coating on exterior surface, and with adhesive coating on sides to fit in opening.
 - 1. Products:
 - a. Construction Specialties; Model VF.
 - b. EMSEAL Joint Systems, Ltd.; Colorseal.
 - c. MM Systems; Series ESS.
 - d. Schul International Company, Inc.; Color Econoseal.
 - e. Watson Bowman Acme Corp; WeatherSeal II.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.03 EXPANSION JOINT COVER ASSEMBLIES

- A. Expansion Joint Cover Assemblies General: Factory-fabricated and assembled; designed to completely fill joint openings, sealed to prevent passage of air, dust, water, smoke; suitable for traffic expected.
 - 1. Joint Dimensions and Configurations: As indicated on drawings.
 - 2. Joint Cover Sizes: Selected to suit joint width and configuration, based on manufacturer's published recommendations and limitations.
 - 3. Lengths: Provide covers in full lengths required; avoid splicing wherever possible.
 - 4. Anchors, Fasteners, and Fittings: Provided by cover manufacturer.
- B. Covers In Gypsum Board Assemblies: Provide style with anchoring wings that can be completely covered by joint compound.
- C. Covers In Fire Rated Assemblies: Provide cover assembly having fire rating equivalent to that of assembly into which it is installed.
 - 1. Acceptable Evaluation Agencies: UL (DIR) and ITS (DIR).

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that joint preparation and dimensions are acceptable and in accordance with manufacturer's requirements.
- B. Verify that frames and anchors installed by others are in correct locations and suitable for installation of remainder of assembly.

3.02 INSTALLATION

- A. Install components and accessories in accordance with manufacturer's instructions.
- B. Align work plumb and level, flush with adjacent surfaces.
- C. Rigidly anchor to substrate to prevent misalignment.

3.03 PROTECTION

- A. Do not permit traffic over unprotected floor joint surfaces.
- B. Provide strippable coating to protect finish surface.

END OF SECTION 079513

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 081113 STEEL DOORS AND FRAMES

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ANSI/SDI A250.8 Specifications for Standard Steel Doors and Frames (SDI-100) 2017.
- B. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials 2022.
- C. BHMA A156.115 Hardware Preparation in Steel Doors and Steel Frames 2016.
- D. SDI 117 Manufacturing Tolerances for Standard Steel Doors and Frames 2019.

1.02 SUBMITTALS

- A. Product Data: Materials and details of design and construction, hardware locations, reinforcement type and locations, anchorage and fastening methods, and finishes.
- B. Shop Drawings: Details of each opening, showing elevations, glazing, frame profiles, and any indicated finish requirements.
- C. Manufacturer's Certificate: Certification that products meet or exceed specified requirements.

1.03 DELIVERY, STORAGE, AND HANDLING

- A. Comply with NAAMM HMMA 840 or ANSI/SDI A250.8 (SDI-100) in accordance with specified requirements.
- B. Protect with resilient packaging; avoid humidity build-up under coverings; prevent corrosion and adverse effects on factory applied painted finish.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Hollow Metal Doors and Frames:
 - 1. Ceco Door, an Assa Abloy Group company.
 - 2. Curries, an Assa Abloy Group company.
 - 3. Fleming Door Products, an Assa Abloy Group company.
 - 4. Krieger Specialty Products.
 - 5. Mesker, dormakaba Group.
 - 6. Pioneer Industries, Inc.; an Assa Abloy Group company.
 - 7. Republic Doors, an Allegion brand.
 - 8. Steelcraft, an Allegion brand.
 - 9. Technical Glass Products.

2.02 PERFORMANCE REQUIREMENTS

- A. Requirements for Hollow Metal Doors and Frames:
 - Steel Sheet: Comply with one or more of the following requirements; galvannealed steel complying with ASTM A653/A653M, cold-rolled steel complying with ASTM A1008/A1008M, or hot-rolled pickled and oiled (HRPO) steel complying with ASTM A1011/A1011M, commercial steel (CS) Type B, for each.
 - 2. Accessibility: Comply with ICC A117.1 and ADA Standards.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 3. Door Top and Bottom Closures: Flush end closure channel, with top and door faces aligned.
 - a. Inverted channel closure is acceptable for bottom edges and top edges of interior doors that are not exposed to view from above.
- 4. Door Edge Profile: Hinged edge square, and lock edge beveled Beveled edge.
- 5. Typical Door Face Sheets: Flush.
- 6. Glazed Lights: Non-removable stops on non-secure side; sizes and configurations as indicated on drawings. Style: Manufacturer's standard.
- 7. Hardware Preparations, Selections and Locations: Comply with NAAMM HMMA 830 and NAAMM HMMA 831 or BHMA A156.115 and ANSI/SDI A250.8 (SDI-100) in accordance with specified requirements.
- 8. Zinc Coating for Typical Interior and/or Exterior Locations: Provide metal components zinc-coated (galvanized) and/or zinc-iron alloy-coated (galvannealed) by the hot-dip process in accordance with ASTM A653/A653M, with manufacturer's standard coating thickness, unless noted otherwise for specific hollow metal doors and frames.
 - a. Based on SDI Standards: Provide at least A40/ZF120 (galvannealed) when necessary, coating not required for typical interior door applications, and at least A60/ZF180 (galvannealed) for corrosive locations.
- B. Combined Requirements: If a particular door and frame unit is indicated to comply with more than one type of requirement, comply with the specified requirements for each type; for instance, an exterior door that is also indicated as being sound-rated must comply with the requirements specified for exterior doors and for sound-rated doors; where two requirements conflict, comply with the most stringent.

2.03 HOLLOW METAL DOORS

- A. Door Finish: Factory primed and field finished.
- B. Exterior Doors: Thermally insulated. Fabricate from metallic-coated steel sheet.
 - 1. Based on SDI Standards: ANSI/SDI A250.8 (SDI-100).
 - a. Level 3 Extra Heavy-duty.
 - b. Physical Performance Level A, 1,000,000 cycles; in accordance with ANSI/SDI A250.4.
 - c. Model 2 Seamless.
 - d. Door Face Metal Thickness: 16 gauge, 0.053 inch, minimum.
 - e. Zinc Coating: A60/ZF180 galvannealed coating; ASTM A653/A653M.
 - 2. Door Core Material: Manufacturers standard core material/construction and in compliance with requirements.
 - a. Foam Plastic Insulation: Manufacturer's standard board insulation with maximum flame spread index (FSI) of 75, and maximum smoke developed index (SDI) of 450 in accordance with ASTM E84, and completely enclosed within interior of door.
 - 3. Door Thermal Resistance: R-Value of 6, minimum.
 - 4. Door Thickness: 1-3/4 inches, nominal.
 - 5. Weatherstripping: Refer to Division 08 "Door Hardware".
- Interior Doors, Non-Fire-Rated: Fabricate from either cold-rolled steel sheet or metallic-coated steel sheet.
 - 1. Based on SDI Standards: ANSI/SDI A250.8 (SDI-100).
 - a. Level 2 Heavy-duty.
 - b. Physical Performance Level B, 500,000 cycles; in accordance with ANSI/SDI A250.4.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- c. Model 1 Full Flush.
- d. Door Face Metal Thickness: 18 gauge, 0.042 inch, minimum.
- Door Core Material: Manufacturers standard core material/construction and in compliance with requirements, except kraft paper honeycomb core is not acceptable.
- 3. Door Thickness: 1-3/4 inches, nominal.
- D. Fire-Rated Doors: Comply with NFPA 80.
 - Based on SDI Standards: ANSI/SDI A250.8 (SDI-100).
 - Match construction and physical performance levels above for interior or exterior doors, as applicable.
 - 2. Fire Rating: As indicated, tested in accordance with UL 10C and NFPA 252 ("positive pressure fire tests").
 - Per NFPA 80, fire exit doors shall be labeled "Fire Door to Be Equipped with Fire Exit
 Hardware," and shall be reinforced and constructed to maintain the rating of the specific
 listed and labeled fire exit devices mounted on them.
 - Provide units listed and labeled by UL (DIR) or ITS (DIR).
 - a. Attach fire rating label to each fire rated unit.
 - 5. Door Core Material: Manufacturers standard core material/construction in compliance with requirements.
 - 6. Door Thickness: 1-3/4 inches, nominal.

2.04 HOLLOW METAL FRAMES

- A. Comply with standards and/or custom guidelines as indicated for corresponding door in accordance with applicable door frame requirements.
- B. Frame Finish: Factory primed and field finished.
- C. Exterior Door Frames: Face welded type.
 - Galvanizing: Components hot-dipped zinc-iron alloy-coated (galvannealed) in accordance with ASTM A653/A653M, with A40/ZF120 coating.
 - 2. Frame Metal Thickness: 16 gauge, 0.053 inch, minimum.
 - 3. Weatherstripping: Refer to Division 08 Section "Door Hardware".
- D. Interior Door Frames, Non-Fire Rated: Face welded type.
 - Frame Metal Thickness: 16 gauge, 0.053 inch, minimum.
- E. Door Frames, Fire-Rated: Face welded type.
 - Fire Rating: Same as door, labeled.
 - 2. Frame Metal Thickness: 16 gauge, 0.053 inch, minimum.
- F. Frames for Wood Doors: Comply with frame requirements in accordance with corresponding door.
- G. Mullions for Pairs of Doors: Fixed, except where removable is indicated, with profile similar to jambs.
 - 1. Where removable mullion is indicated, coordinate with removable mullion to be provided as an exit device accessory per Division 08 Section "Door Hardware."
- H. Borrowed Lites Glazing Frames: Construction and face dimensions to match door frames, and as indicated on drawings.
- Provide mortar guard boxes for hardware cut-outs in frames to be installed in masonry or to be grouted.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- J. Frames in Masonry Walls: Size to suit masonry coursing with head member 4 inches high to fill opening without cutting masonry units.
- K. Frames Wider than 48 inches: Reinforce with steel channel fitted tightly into frame head, flush with top.

2.05 FINISHES

A. Primer: Rust-inhibiting, complying with ANSI/SDI A250.10, door manufacturer's standard.

2.06 ACCESSORIES

- A. Louvers: Roll formed steel with overlapping frame; finish same as door components; factory-installed.
 - 1. In Fire-Rated Doors: UL (DIR) or ITS (DIR) listed fusible link louver, same rating as door.
 - 2. Style: Sightproof inverted V- or Y-blade.
 - 3. Fasteners: Exposed or concealed fasteners.
- B. Glazing: As specified in Section 088000.
- C. Removable and Fixed Stops: Formed sheet steel, mitered or butted corners; prepared for countersink style tamper proof screws.
 - 1. Provide fixed stops for exterior applications, and toward the secure side of interior glazed lites (for example, toward the corridor or more public accessible spaces).
 - 2. Heights of Stops: Unless otherwise indicated or recommended by glazing manufacturer, provide standard 5/8-inch height stops where allowed by standards, and provide 3/4-inch height for exterior 1-inch glazing units.
- D. Astragals and Edges for Double Doors: Pairs of door astragals, and door edge sealing and protection devices.
 - Provide UL listed products, complying with NFPA 80, and as required to maintain indicated fire rating.
 - 2. Provide surface mounted overlapping-type astragal to cover or fill space for full door height between pair of doors or door and adjacent jamb.
- E. Mechanical Fasteners for Concealed Metal-to-Metal Connections: Self-drilling, self-tapping, steel with electroplated zinc finish.
- F. Grout for Frames: Mortar grout complying with ASTM C476 with maximum slump of 4 inches as measured in accordance with ASTM C143/C143M for hand troweling in place; plaster grout and thinner pumpable grout are prohibited.
- G. Silencers: Resilient rubber, fitted into drilled hole; provide three on strike side of single door, three on center mullion of pairs, and two on head of pairs without center mullions.
- H. Temporary Frame Spreaders: Provide for factory- or shop-assembled frames.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that opening sizes and tolerances are acceptable.
- C. Verify that finished walls are in plane to ensure proper door alignment.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.02 INSTALLATION

- A. Install doors and frames in accordance with manufacturer's instructions and related requirements of specified door and frame standards or custom guidelines indicated.
 - 1. Install in accordance with ANSI/SDI A250.11.
 - Do not remove temporary frame spreaders until after frames have been properly set and secured.
- B. Install fire rated units in accordance with NFPA 80.
- C. Coordinate frame anchor placement with wall construction.
- D. Grout frames in masonry construction, using hand trowel methods; brace frames so that pressure of grout before setting will not deform frames.
- E. Install door hardware as specified in Section 087100.
- F. Comply with glazing installation requirements of Section 088000.
- G. Coordinate installation of electrical connections to electrical hardware items.
- H. Touch up damaged factory finishes.

3.03 TOLERANCES

- A. Clearances Between Door and Frame: Comply with related requirements of specified frame standards or custom guidelines indicated in accordance with SDI 117 or NAAMM HMMA 861.
 - 1. Comply with clearances indicated in NFPA 80 for fire-rated doors.
- B. Maximum Diagonal Distortion: 1/16 inch measured with straight edge, corner to corner.

3.04 ADJUSTING

A. Adjust for smooth and balanced door movement.

END OF SECTION 081113

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 081416 FLUSH WOOD DOORS

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. AWI/AWMAC/WI (AWS) Architectural Woodwork Standards, 2nd Edition 2014, with Errata (2016).
- B. NFPA 80 Standard for Fire Doors and Other Opening Protectives 2022.
- C. UL 10C Standard for Positive Pressure Fire Tests of Door Assemblies Current Edition, Including All Revisions.

1.02 SUBMITTALS

- Product Data: Indicate door core materials and construction; veneer species, type and characteristics.
- B. Shop Drawings: Show doors and frames, elevations, sizes, types, swings, undercuts, beveling, blocking for hardware, factory machining, factory finishing, cutouts for glazing and other details.
- C. Samples: Submit two samples of door veneer, approximately 8 by 8 inches in size illustrating wood grain, stain color, and sheen.
- D. Warranty, executed in Owner's name.

1.03 QUALITY ASSURANCE

A. Source Limitations: Provide all flush wood doors from a single manufacturer.

1.04 DELIVERY, STORAGE, AND HANDLING

- A. Package, deliver and store doors in accordance with specified quality standard.
- B. Accept doors on site in manufacturer's packaging, and inspect for damage.
- C. Protect doors with resilient packaging sealed with heat shrunk plastic; do not store in damp or wet areas or areas where sunlight might bleach veneer; seal top and bottom edges with tinted sealer if stored more than one week, and break seal on site to permit ventilation.

1.05 WARRANTY

- See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Interior Doors: Provide manufacturer's warranty for the life of the installation.
- C. Include coverage for delamination of veneer, warping beyond specified installation tolerances, defective materials, and telegraphing core construction.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Wood Veneer Faced Doors:
 - 1. Eggers Industries.
 - 2. Lambton Doors.
 - Masonite Architectural; Aspiro Select Wood Veneer Doors.
 - 4. Oshkosh Door.

Flush Wood Doors 081416 - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

5. VT Industries. Inc.

2.02 DOORS

- A. Doors: See drawings for locations and additional requirements.
 - Doors shall be manufactured by the hot-press method, bonding faces, crossbands, and core together in a single operation with Type I glue. Doors manufactured by cold-pressing 2- or 3-ply pre-manufactured door skins to multiple cores in the same press will not be accepted.
- B. Interior Doors: 1-3/4 inches thick unless otherwise indicated; flush construction.
 - Provide solid core doors at each location.
 - 2. Fire Rated Doors: Tested to ratings indicated on drawings in accordance with UL 10C Positive Pressure; Underwriters Laboratories Inc (UL) or Intertek/Warnock Hersey (WHI) labeled.
 - Provide stile construction with concealed intumescent seals at pairs of doors, meeting required fire-ratings without the need of astragal or metal edge construction.

2.03 DOOR AND PANEL CORES

- A. Non-Rated Solid Core and 20 Minute Rated Doors: Type particleboard core (PC), particleboard Grade LD-2 per ANSI A 208.1; plies and faces as indicated.
 - Provide structural-composite-lumber (SCLC) core for doors with glazing area cut out for 9inch stile width doors.
 - 2. Provide structural-composite-lumber (SCLC) core for doors with exit devices.
- B. Fire-Rated Doors: Mineral core type, with fire resistant composite core (FD), plies and faces as indicated above; with core blocking as required to provide adequate anchorage of hardware without through-bolting.

2.04 DOOR FACINGS

- A. Veneer Facing for Transparent Finish: [_____], veneer grade in accordance with quality standard indicated, plain sliced (flat cut), with book match between leaves of veneer, running match of spliced veneer leaves assembled on door or panel face.
 - 1. Vertical Edges: Any option allowed by quality standard for grade.
 - 2. "Pair Match" each pair of doors; "Set Match" pairs of doors within 10 feet of each other when doors are closed.

2.05 DOOR CONSTRUCTION

- A. Fabricate doors in accordance with door quality standard specified.
- B. Cores Constructed with stiles and rails:
 - 1. Provide solid blocks at lock edge for hardware reinforcement.
- C. Glazed Openings: Non-removable stops on non-secure side; sizes and configurations as indicated on drawings.
- D. Factory machine doors for hardware other than surface-mounted hardware, in accordance with hardware requirements and dimensions.
- E. Factory fit doors for frame opening dimensions identified on shop drawings, with edge clearances in accordance with specified quality standard.
- F. Provide edge clearances in accordance with the quality standard specified.

Flush Wood Doors 081416 - 2

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.06 FINISHES - WOOD VENEER DOORS

- A. Finish work in accordance with AWI/AWMAC/WI (AWS), Section 5 Finishing for grade specified and as follows:
 - 1. Transparent:
 - a. System 5, Varnish, Conversion or System 11, catalyzed polyurethane.
 - b. Sheen: Satin.
- B. Factory finish doors in accordance with approved sample.
- C. Seal door top edge with color sealer to match door facing where doors will be exposed to view from above.

2.07 ACCESSORIES

- A. Wood Louvers:
 - 1. Material and Finish: Match species of door panels.
- B. Glazing Stops: Wood, of same species as door facing, butted corners; prepared for countersink style tamper proof screws. At fire-rated doors, provide noncombustible wood stops with concealed metal clips for indicated fire rating.
- C. Door Hardware: Refer to Section 087100.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that opening sizes and tolerances are acceptable.
- C. Do not install doors in frame openings that are not plumb or are out-of-tolerance for size or alignment.

3.02 INSTALLATION

- A. Install doors in accordance with manufacturer's instructions and specified quality standard.
 - 1. Install fire-rated doors in accordance with NFPA 80 requirements.
- B. Factory-Finished Doors: Do not field cut or trim; if fit or clearance is not correct, replace door.
- C. Use machine tools to cut or drill for hardware.
- D. Coordinate installation of doors with installation of frames and hardware.
- Coordinate installation of glazing.

3.03 TOLERANCES

- A. Comply with specified quality standard for fit and clearance tolerances.
- B. Comply with specified quality standard for telegraphing, warp, and squareness.

3.04 ADJUSTING

- A. Adjust doors for smooth and balanced door movement.
- B. Adjust closers for full closure.

END OF SECTION 081416

Flush Wood Doors 081416 - 3

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 083100 ACCESS DOORS AND PANELS

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ITS (DIR) Directory of Listed Products Current Edition.
- B. UL (FRD) Fire Resistance Directory Current Edition.

1.02 SUBMITTALS

- A. Product Data: Provide sizes, types, finishes, hardware, scheduled locations, and details of adjoining work.
- B. Shop Drawings: Indicate exact position of each access door and/or panel unit.
 - Include a schedule indicating wall/ceiling type, door types, sizes, and hardware for each access door required.

1.03 COORDINATION

- A. Verification: Determine specific locations and sizes for access doors needed to gain access to concealed plumbing, mechanical, or other concealed work, and indicate in the schedule specified in "Submittals" Article.
 - This (083100) material specification includes access doors required for Divisions 21 (Fire Suppression), Division 22, (Plumbing), 23 (HVAC) and Division 26 (Electrical) work and any other access doors indicated on Drawings.

PART 2 PRODUCTS

2.01 WALL AND CEILING MOUNTED ACCESS UNITS

- A. Manufacturers:
 - 1. Activar Construction Products Group, Inc. JL Industries.
 - 2. ACUDOR Products Inc.
 - 3. Babcock-Davis.
 - 4. Bauco Access Panel Solutions Inc.
 - 5. Best Access Doors.
 - 6. Cendrex, Inc.
 - 7. Karp Associates, Inc.
 - 8. Larsen's Manufacturing Company.
 - 9. Milcor, Inc.
 - 10. Nystrom, Inc.
 - 11. Williams Brothers Corporation of America.
 - 12. Substitutions: See Section 016000 Product Requirements.
- B. Wall and Ceiling Mounted Units: Factory fabricated door and frame, fully assembled units with corner joints welded, filled and ground flush; square and without rack or warp; coordinate requirements with type of installation assembly being used for each unit.
 - 1. Material: Steel.
 - 2. Style (Gypsum Board locations): Recessed door panel for infill with wall/ceiling finish.
 - a. Gypsum Board Mounting Criteria: Use drywall bead type frame.

Access Doors and Panels 083100 - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 3. Style (Masonry locations): Exposed frame, with door surface flush with frame surface.
- 4. Door Style: Double-skinned hollow panel.
- 5. Frames: 16 gauge, 0.0598 inch, minimum thickness.
- 6. Double-Skinned Hollow Steel Sheet Door Panels: 16 gauge, 0.059 inch, minimum thickness, on both sides and along each edge.
- 7. Units in Fire-Rated Assemblies: Fire rating as required by applicable code for fire-rated assembly that access doors are being installed.
 - a. Provide products listed by ITS (DIR) or UL (FRD) as suitable for purpose indicated.
 - b. Provide certificate of compliance from authorities having jurisdiction indicating approval of fire rated doors.
 - c. Fire-rated door assemblies shall conform with and be installed in accordance with (1) NFPA 80, (2) door and frame manufacturer's installation instructions, and (3) listing requirements of qualified testing agency.
- 8. Steel Finish: Primed.
- 9. Hardware:
 - Hardware for Fire-Rated Units: As required for listing.
 - b. Hinges for Non-Fire-Rated Units: Concealed, constant force closure spring type.
 - c. Latch/Lock: Cylinder lock-operated cam latch, two keys for each unit.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that rough openings are correctly sized and located.
- B. Begin installation only after substrates have been properly prepared, and if the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.02 PREPARATION

- A. Clean surfaces thoroughly prior to proceeding with this work.
- B. Prepare surfaces using methods recommended by manufacturer for applicable substrates in accordance with project conditions.

3.03 INSTALLATION

- A. Install units in accordance with manufacturer's instructions.
- B. Install frames plumb and level in openings, and secure units rigidly in place.
- C. Position units to provide convenient access to concealed equipment when necessary.

END OF SECTION 083100

Access Doors and Panels 083100 - 2

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 084313 ALUMINUM-FRAMED STOREFRONTS

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. AAMA CW-10 Care and Handling of Architectural Aluminum from Shop to Site 2015.
- B. AAMA 1503 Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections 2009.
- C. AAMA 2604 Voluntary Specification, Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels (with Coil Coating Appendix) 2022.
- D. ASCE 7 Minimum Design Loads and Associated Criteria for Buildings and Other Structures Most Recent Edition Cited by Referring Code or Reference Standard.
- E. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes 2021.
- F. ASTM B221M Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric) 2021.
- G. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials 2022.
- H. ASTM E283/E283M Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Skylights, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen 2019.
- ASTM E330/E330M Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference 2014 (Reapproved 2021).
- J. ASTM E331 Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference 2000 (Reapproved 2016).
- K. NFRC 200 Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence 2020.

1.02 ADMINISTRATIVE REQUIREMENTS

A. Preinstallation Meeting: Conduct a preinstallation meeting one week before starting work of this section: require attendance by all affected installers.

1.03 SUBMITTALS

- A. Product Data: Provide component dimensions, describe components within assembly, anchorage and fasteners, glass and infill, door hardware, and internal drainage details.
- B. Shop Drawings: Indicate system dimensions, framed opening requirements and tolerances, affected related work, expansion and contraction joint location and details, and field welding required.
 - 1. Include design engineer's stamp or seal on shop drawings for attachments and anchors.
- C. Design Data: Provide framing member structural and physical characteristics, engineering calculations, and dimensional limitations.
- D. Hardware Schedule: Complete itemization of each item of hardware to be provided for each door, cross-referenced to door identification numbers in Contract Documents.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

E. Designer's qualification statement.

1.04 QUALITY ASSURANCE

A. Designer Qualifications: Design structural support framing components under direct supervision of a Professional Structural Engineer experienced in design of this Work and licensed in the State in which the Project is located.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Handle products of this section in accordance with AAMA CW-10.
- B. Protect finished aluminum surfaces with wrapping. Do not use adhesive papers or sprayed coatings that bond to aluminum when exposed to sunlight or weather.

1.06 FIELD CONDITIONS

A. Do not install sealants when ambient temperature is less than 40 degrees F. Maintain this minimum temperature during and 48 hours after installation.

1.07 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Correct defective Work within a two year period after Date of Substantial Completion.
- C. Provide ten year manufacturer warranty against excessive degradation of exterior finish. Include provision for replacement of units with excessive fading, chalking, or flaking.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Aluminum-Framed Storefront Exterior High-Performance Double Thermal Break Center Set 2" x 4.5":
 - 1. EFCO Corp; 403X.
 - 2. Kawneer North America; 451UT.
 - 3. Oldcastle Building Envelope; 3000 XT.
 - 4. Tubelite, Inc; TU 24000 Therml=block.
 - 5. YKK AP America, Inc; YES 45 XT.
- B. Aluminum-Framed Storefront Interior Non-Thermal Center Set 2" x 4.5":
 - 1. EFCO Corp; 402.
 - 2. Kawneer North America; Trifab VG 451.
 - 3. Oldcastle Building Envelope; FG 3000.
 - 4. Tubelite, Inc; E14000 Non-Thermal.
 - 5. YKK AP America, Inc; YES 45 FI.
- C. Aluminum-Framed Entrances Standard 1.75-inch thickness, insulated:
 - 1. EFCO Corp; D500.
 - 2. Kawneer North America; 500.
 - Oldcastle Building Envelope; 500.
 - 4. Tubelite, Inc; Standard Wide Stile Doors.
 - 5. YKK AP America, Inc; 50D.
- D. Aluminum-Framed Entrances Heavy-Duty 2-inch Thick Insulated Wide-Stile:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 1. EFCO Corp; D518 Durastile.
- 2. Kawneer North America; 500 Heavy Wall Entrance.
- 3. Oldcastle Building Envelope; Rugged Entrance.
- 4. Tubelite, Inc; Monumental Wide Stile Doors.
- 5. YKK AP America, Inc; 50M.

2.02 ALUMINUM-FRAMED STOREFRONT

- A. Aluminum-Framed Storefront: Factory fabricated, factory finished aluminum framing members with infill, and related flashings, anchorage and attachment devices.
 - 1. Glazing Position: Centered (front to back).
 - 2. Finish: High performance organic coatings.
 - a. Factory finish all surfaces that will be exposed in completed assemblies.
 - b. Touch-up surfaces cut during fabrication so that no natural aluminum is visible in completed assemblies, including joint edges.
 - 3. Fabrication: Joints and corners flush, hairline, and weatherproof, accurately fitted and secured; prepared to receive anchors and hardware; fasteners and attachments concealed from view; reinforced as required for imposed loads.
 - 4. Construction: Eliminate noises caused by wind and thermal movement, prevent vibration harmonics, and prevent "stack effect" in internal spaces.
 - 5. System Internal Drainage: Drain to the exterior by means of a weep drainage network any water entering joints, condensation occurring in glazing channel, and migrating moisture occurring within system.
 - 6. Expansion/Contraction: Provide for expansion and contraction within system components caused by cycling temperature range of 170 degrees F over a 12 hour period without causing detrimental effect to system components, anchorages, and other building elements.
 - 7. Movement: Allow for movement between storefront and adjacent construction, without damage to components or deterioration of seals.
 - 8. Perimeter Clearance: Minimize space between framing members and adjacent construction while allowing expected movement.

B. Performance Requirements:

- Wind Loads: Design and size components to withstand the specified load requirements without damage or permanent set, when tested in accordance with ASTM E330/E330M, using loads 1.5 times the design wind loads and 10 second duration of maximum load.
 - Design Wind Loads: Comply with requirements of ASCE 7 and as indicated on Structural drawings.
 - b. Member Deflection: Limit member deflection to flexure limit of glass in any direction, with full recovery of glazing materials.
- Water Penetration Resistance on Manufactured Assembly: No uncontrolled water on interior face, when tested in accordance with ASTM E331 at pressure differential of [____] psf.
- 3. Air Leakage: 0.06 cfm/sq ft maximum leakage of storefront wall area when tested in accordance with ASTM E283/E283M at 1.57 psf pressure difference.
- Condensation Resistance Factor of Framing: 56, minimum, measured in accordance with AAMA 1503.
- 5. Overall U-value Including Glazing: [____] Btu/(hr sq ft deg F), maximum.
- 6. Solar Heat Gain Coefficient Including Glazing: [_____], maximum, measured in accordance with NFRC 200.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.03 COMPONENTS

- A. Aluminum Framing Members: Tubular aluminum sections, thermally broken with interior section insulated from exterior, drainage holes and internal weep drainage system.
 - 1. Glazing Stops: Flush.
- B. Glazing: Refer to Section 088000.
- Infill Panels (Glazing Type G3): Insulated, aluminum, with edges formed to fit glazing channel and sealed.
 - 1. Total Nominal Thickness: 1 inch.
 - 2. Surface Burning Characteristics: Provide assemblies with Class A rating, with flame spread index of 25 or less and smoke developed index of 450 or less, when tested in accordance with ASTM E84.
 - 3. Face Sheets (Front and Back): Equal 0.024-inch smooth aluminum faces bonded to nominal 1/8-inch exterior grade hardboard or high-density corrugated polypropylene.
 - 4. Core: Rigid polyisocyanurate insulation core; minimum total panel R-value of 6.
 - 5. Finish: Same as storefront.
 - Products:
 - a. Citadel Architectural Products; GlazeGuard 1000 WR+.
 - b. Laminators, Inc; Thermolite/Omega Foam-Ply.
 - c. Mapes Architectural Products; Mapes-R Infill.
 - d. Substitutions: See Section 016000 Product Requirements.
- D. Swing Doors: Glazed aluminum.
 - 1. Thickness: 1-3/4 inches.
 - 2. Top Rail: 7 inches wide.
 - 3. Vertical Stiles: 5 inches wide (wide stile).
 - 4. Bottom Rail: 12 inches wide.
 - 5. Glazing Stops: Beveled.
 - 6. Finish: Same as storefront.

2.04 MATERIALS

- A. Extruded Aluminum: ASTM B221 (ASTM B221M).
- B. Fasteners: Stainless steel.
- C. Concealed Flashings: Stainless steel, 26 gauge, 0.0187 inch minimum thickness or sheet aluminum, 22 gauge, 0.026 inch minimum thickness.
- D. Sill Flashing Sealant: Elastomeric, silicone or polyurethane, compatible with flashing material.
- E. Sealant for Setting Thresholds: Non-curing butyl type.
- F. Glazing Gaskets: Type to suit application to achieve weather, moisture, and air infiltration requirements.

2.05 FINISHES

- A. High Performance Organic Coating: AAMA 2604; multiple coats, thermally cured fluoropolymer system.
- B. Color: As selected by Architect from manufacturer's standard range.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.06 HARDWARE

- A. For each door, include weatherstripping, sill sweep strip, and threshold.
- B. Other Door Hardware: Refer to Section 087100.
- C. Weatherstripping: Wool pile, continuous and replaceable; provide on all doors.
- D. Sill Sweep Strips: Resilient seal type, retracting, of neoprene; provide on all doors.
- E. Threshold: Extruded aluminum, one piece per door opening, ribbed surface; provide on all exterior doors.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify dimensions, tolerances, and method of attachment with other work.
- B. Verify that storefront wall openings and adjoining water-resistive and/or air barrier seal materials are ready to receive work of this section.

3.02 INSTALLATION

- A. Install wall system in accordance with manufacturer's instructions.
- B. Attach to structure to permit sufficient adjustment to accommodate construction tolerances and other irregularities.
- C. Provide alignment attachments and shims to permanently fasten system to building structure.
- D. Align assembly plumb and level, free of warp or twist. Maintain assembly dimensional tolerances, aligning with adjacent work.
- E. Provide thermal isolation where components penetrate or disrupt building insulation.
- F. Install sill flashings. Turn up ends and edges; seal to adjacent work to form water tight dam.
- G. Where fasteners penetrate sill flashings, make watertight by seating and sealing fastener heads to sill flashing.
- H. Pack fibrous insulation in shim spaces at perimeter of assembly to maintain continuity of thermal barrier.
- I. Set thresholds in bed of sealant and secure.
- J. Install glass and infill panels using glazing method required to achieve performance criteria; see Section 088000.
- K. Touch-up minor damage to factory applied finish; replace components that cannot be satisfactorily repaired.

3.03 TOLERANCES

- A. Maximum Variation from Plumb: 0.06 inch per 3 feet non-cumulative or 0.06 inch per 10 feet, whichever is less.
- B. Maximum Misalignment of Two Adjoining Members Abutting in Plane: 1/32 inch.

3.04 FIELD QUALITY CONTROL

A. Provide services of storefront manufacturer's field representative to observe for proper installation of system and submit report.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.05 ADJUSTING

A. Adjust operating hardware and sash for smooth operation.

3.06 CLEANING

- A. Remove protective material from pre-finished aluminum surfaces.
- B. Wash down surfaces with a solution of mild detergent in warm water, applied with soft, clean wiping cloths, and take care to remove dirt from corners and to wipe surfaces clean.

3.07 PROTECTION

A. Protect installed products from damage until Date of Substantial Completion.

END OF SECTION 084313

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 087100 - DOOR HARDWARE

PART 1 - GENERAL

1.01 **SUMMARY**

A. Section includes:

- 1. Mechanical and electrified door hardware
- 2. Electronic access control system components

B. Section excludes:

- Windows
- 2. Cabinets (casework), including locks in cabinets
- 3. Signage4. Toilet accessories
- 5. Overhead doors

C. Related Sections:

- 1. Division 01 Section "Alternates" for alternates affecting this section.
- 2. Division 06 Section "Rough Carpentry"
- 3. Division 06 Section "Finish Carpentry"
- 4. Division 07 Section "Joint Sealants" for sealant requirements applicable to threshold installation specified in this section.
- 5. Division 08 Sections:
 - a. "Metal Doors and Frames"
 - b. "Flush Wood Doors"
 - c. "Stile and Rail Wood Doors"
 - d. "Interior Aluminum Doors and Frames"
 - e. "Aluminum-Framed Entrances and Storefronts"
 - "Stainless Steel Doors and Frames" f.
 - g. "Special Function Doors"
 - h. "Entrances"
- 6. Division 26 "Electrical" sections for connections to electrical power system and for lowvoltage wiring.
- 7. Division 28 "Electronic Safety and Security" sections for coordination with other components of electronic access control system and fire alarm system.

REFERENCES 1.02

A. UL LLC

- 1. UL 10B Fire Test of Door Assemblies
- 2. UL 10C Positive Pressure Test of Fire Door Assemblies
- 3. UL 1784 Air Leakage Tests of Door Assemblies
- 4. UL 305 Panic Hardware

B. DHI - Door and Hardware Institute

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Sequence and Format for the Hardware Schedule
- 2. Recommended Locations for Builders Hardware
- 3. Keying Systems and Nomenclature
- 4. Installation Guide for Doors and Hardware

C. NFPA - National Fire Protection Association

- 1. NFPA 70 National Electric Code
- 2. NFPA 80 2016 Edition Standard for Fire Doors and Other Opening Protectives
- 3. NFPA 101 Life Safety Code
- 4. NFPA 105 Smoke and Draft Control Door Assemblies
- 5. NFPA 252 Fire Tests of Door Assemblies

D. ANSI - American National Standards Institute

- 1. ANSI A117.1 2017 Edition Accessible and Usable Buildings and Facilities
- 2. ANSI/BHMA A156.1 A156.29, and ANSI/BHMA A156.31 Standards for Hardware and Specialties
- 3. ANSI/BHMA A156.28 Recommended Practices for Keying Systems
- 4. ANSI/WDMA I.S. 1A Interior Architectural Wood Flush Doors
- 5. ANSI/SDI A250.8 Standard Steel Doors and Frames

1.03 SUBMITTALS

A. General:

- 1. Submit in accordance with Conditions of Contract and Division 01 Submittal Procedures.
- 2. Prior to forwarding submittal:
 - a. Review drawings and Sections from related trades to verify compatibility with specified hardware.
 - Highlight, encircle, or otherwise specifically identify on submittals: deviations from Contract Documents, issues of incompatibility or other issues which may detrimentally affect the Work.

B. Action Submittals:

- 1. Product Data: Submit technical product data for each item of door hardware, installation instructions, maintenance of operating parts and finish, and other information necessary to show compliance with requirements.
- 2. Riser and Wiring Diagrams: After final approval of hardware schedule, submit details of electrified door hardware, indicating:
 - a. Wiring Diagrams: For power, signal, and control wiring and including:
 - 1) Details of interface of electrified door hardware and building safety and security systems.
 - 2) Schematic diagram of systems that interface with electrified door hardware.
 - 3) Point-to-point wiring.
 - 4) Risers.
- Samples for Verification: If requested by Architect, submit production sample of requested door hardware unit in finish indicated and tagged with full description for coordination with schedule.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

a. Samples will be returned to supplier. Units that are acceptable to Architect may, after final check of operations, be incorporated into Work, within limitations of key coordination requirements.

4. Door Hardware Schedule:

- Submit concurrent with submissions of Product Data, Samples, and Shop Drawings.
 Coordinate submission of door hardware schedule with scheduling requirements of other work to facilitate fabrication of other work critical in Project construction schedule.
- b. Submit under direct supervision of a Door Hardware Institute (DHI) certified Architectural Hardware Consultant (AHC) or Door Hardware Consultant (DHC) with hardware sets in vertical format as illustrated by Sequence of Format for the Hardware Schedule published by DHI.
- c. Indicate complete designations of each item required for each opening, include:
 - 1) Door Index: door number, heading number, and Architect's hardware set number.
 - 2) Quantity, type, style, function, size, and finish of each hardware item.
 - 3) Name and manufacturer of each item.
 - 4) Fastenings and other pertinent information.
 - 5) Location of each hardware set cross-referenced to indications on Drawings.
 - 6) Explanation of all abbreviations, symbols, and codes contained in schedule.
 - 7) Mounting locations for hardware.
 - 8) Door and frame sizes and materials.
 - 9) Degree of door swing and handing.
 - 10) Operational Description of openings with electrified hardware covering egress, ingress (access), and fire/smoke alarm connections.

5. Key Schedule:

- a. After Keying Conference, provide keying schedule that includes levels of keying, explanations of key system's function, key symbols used, and door numbers controlled.
- Use ANSI/BHMA A156.28 "Recommended Practices for Keying Systems" as guideline for nomenclature, definitions, and approach for selecting optimal keying system.
- c. Provide 3 copies of keying schedule for review prepared and detailed in accordance with referenced DHI publication. Include schematic keying diagram and index each key to unique door designations.
- d. Index keying schedule by door number, keyset, hardware heading number, cross keying instructions, and special key stamping instructions.
- e. Provide one complete bitting list of key cuts and one key system schematic illustrating system usage and expansion. Forward bitting list, key cuts and key system schematic directly to Owner, by means as directed by Owner.
- f. Prepare key schedule by or under supervision of supplier, detailing Owner's final keying instructions for locks.

C. Informational Submittals:

- 1. Provide Qualification Data for Supplier, Installer and Architectural Hardware Consultant.
- 2. Provide Product Data:
 - a. Certify that door hardware approved for use on types and sizes of labeled fire-rated doors complies with listed fire-rated door assemblies.
 - b. Include warranties for specified door hardware.

D. Closeout Submittals:

1. Operations and Maintenance Data: Provide in accordance with Division 01 and include:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Complete information on care, maintenance, and adjustment; data on repair and replacement parts, and information on preservation of finishes.
- b. Catalog pages for each product.
- c. Final approved hardware schedule edited to reflect conditions as installed.
- d. Final keying schedule
- e. Copy of warranties including appropriate reference numbers for manufacturers to identify project.
- f. As-installed wiring diagrams for each opening connected to power, both low voltage and 110 volts.

E. Inspection and Testing:

- Submit written reports to the Owner and Authority Having Jurisdiction (AHJ) of the results of functional testing and inspection for:
 - a. Fire door assemblies, in compliance with NFPA 80.
 - b. Required egress door assemblies, in compliance with NFPA 101.

1.04 QUALITY ASSURANCE

A. Qualifications and Responsibilities:

- Supplier: Recognized architectural hardware supplier with a minimum of 5 years
 documented experience supplying both mechanical and electromechanical door
 hardware similar in quantity, type, and quality to that indicated for this Project. Supplier
 to be recognized as a factory direct distributor by the manufacturer of the primary
 materials with a warehousing facility in the Project's vicinity. Supplier to have on staff, a
 certified Architectural Hardware Consultant (AHC) or Door Hardware Consultant (DHC)
 available to Owner, Architect, and Contractor, at reasonable times during the Work for
 consultation.
- 2. Installer: Qualified tradesperson skilled in the application of commercial grade hardware with experience installing door hardware similar in quantity, type, and quality as indicated for this Project.
- 3. Architectural Hardware Consultant: Person who is experienced in providing consulting services for door hardware installations that are comparable in material, design, and extent to that indicated for this Project and meets these requirements:
 - a. For door hardware: DHI certified AHC or DHC.
 - Can provide installation and technical data to Architect and other related subcontractors.
 - c. Can inspect and verify components are in working order upon completion of installation.
 - d. Capable of producing wiring diagram and coordinating installation of electrified hardware with Architect and electrical engineers.
- 4. Single Source Responsibility: Obtain each type of door hardware from single manufacturer.

B. Certifications:

- 1. Fire-Rated Door Openings:
 - a. Provide door hardware for fire-rated openings that complies with NFPA 80 and requirements of authorities having jurisdiction.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

b. Provide only items of door hardware that are listed products tested by UL LLC, Intertek Testing Services, or other testing and inspecting organizations acceptable to authorities having jurisdiction for use on types and sizes of doors indicated, based on testing at positive pressure and according to NFPA 252 or UL 10C and in compliance with requirements of fire-rated door and door frame labels.

2. Smoke and Draft Control Door Assemblies:

- a. Provide door hardware that meets requirements of assemblies tested according to UL 1784 and installed in compliance with NFPA 105
- b. Comply with the maximum air leakage of 0.3 cfm/sq. ft. (3 cu. m per minute/sq. m) at tested pressure differential of 0.3-inch wg (75 Pa) of water.

3. Electrified Door Hardware

a. Listed and labeled as defined in NFPA 70, Article 100, by testing agency acceptable to authorities having jurisdiction.

4. Accessibility Requirements:

a. Comply with governing accessibility regulations cited in "REFERENCES" article 087100, 1.02.D3 herein for door hardware on doors in an accessible route. This project must comply with all Federal Americans with Disability Act regulations and all Local Accessibility Regulations.

C. Pre-Installation Meetings

1. Keying Conference

- a. Incorporate keying conference decisions into final keying schedule after reviewing door hardware keying system including:
 - 1) Function of building, flow of traffic, purpose of each area, degree of security required, and plans for future expansion.
 - 2) Preliminary key system schematic diagram.
 - 3) Requirements for key control system.
 - 4) Requirements for access control.
 - 5) Address for delivery of keys.

2. Pre-installation Conference

- Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
- b. Inspect and discuss preparatory work performed by other trades.
- c. Inspect and discuss electrical roughing-in for electrified door hardware.
- d. Review sequence of operation for each type of electrified door hardware.
- e. Review required testing, inspecting, and certifying procedures.
- Review questions or concerns related to proper installation and adjustment of door hardware.

3. Electrified Hardware Coordination Conference:

a. Prior to ordering electrified hardware, schedule and hold meeting to coordinate door hardware with security, electrical, doors and frames, and other related suppliers.

1.05 DELIVERY, STORAGE, AND HANDLING

A. Inventory door hardware on receipt and provide secure lock-up for hardware delivered to Project site. Promptly replace products damaged during shipping.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Tag each item or package separately with identification coordinated with final door hardware schedule, and include installation instructions, templates, and necessary fasteners with each item or package. Deliver each article of hardware in manufacturer's original packaging.
- C. Maintain manufacturer-recommended environmental conditions throughout storage and installation periods.
- D. Provide secure lock-up for door hardware delivered to Project. Control handling and installation of hardware items so that completion of Work will not be delayed by hardware losses both before and after installation.
- E. Handle hardware in manner to avoid damage, marring, or scratching. Correct, replace or repair products damaged during Work. Protect products against malfunction due to paint, solvent, cleanser, or any chemical agent.
- F. Deliver keys to manufacturer of key control system for subsequent delivery to Owner.

1.06 COORDINATION

- A. Coordinate layout and installation of floor-recessed door hardware with floor construction. Cast anchoring inserts into concrete.
- B. Installation Templates: Distribute for doors, frames, and other work specified to be factory or shop prepared. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing door hardware to comply with indicated requirements.
- C. Security: Coordinate installation of door hardware, keying, and access control with Owner's security consultant.
- D. Electrical System Roughing-In: Coordinate layout and installation of electrified door hardware with connections to power supplies and building safety and security systems.

1.07 WARRANTY

- A. Manufacturer's standard form in which manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within published warranty period.
 - Warranty does not cover damage or faulty operation due to improper installation, improper use or abuse.
 - 2. Warranty Period: Beginning from date of Substantial Completion, for durations indicated in manufacturer's published listings.

1.08 MAINTENANCE

- A. Furnish complete set of special tools required for maintenance and adjustment of hardware, including changing of cylinders.
- B. Turn over unused materials to Owner for maintenance purposes.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 2 - PRODUCTS

2.01 MANUFACTURERS

- A. The Owner requires use of certain products for their unique characteristics and project suitability to ensure continuity of existing and future performance and maintenance standards. After investigating available product offerings, the Awarding Authority has elected to prepare proprietary specifications. These products are specified with the notation: "No Substitute."
 - Where "No Substitute" is noted, submittals and substitution requests for other products will not be considered.
- B. Approval of manufacturers and/or products other than those listed as "Scheduled Manufacturer" or "Acceptable Manufacturers" in the individual article for the product category shall be in accordance with QUALITY ASSURANCE article, herein.
- C. Approval of products from manufacturers indicated in "Acceptable Manufacturers" is contingent upon those products providing all functions and features and meeting all requirements of scheduled manufacturer's product.
- D. Where specified hardware is not adaptable to finished shape or size of members requiring hardware, furnish suitable types having same operation and quality as type specified, subject to Architect's approval.

2.02 MATERIALS

A. Fabrication

- 1. Provide door hardware manufactured to comply with published templates generally prepared for machine, wood, and sheet metal screws. provide screws according to manufacturer's recognized installation standards for application intended.
- 2. Finish exposed screws to match hardware finish, or, if exposed in surfaces of other work, to match finish of this other work including prepared for paint surfaces to receive painted finish.
- 3. Provide concealed fasteners wherever possible for hardware units exposed when door is closed. Coordinate with "Metal Doors and Frames", "Flush Wood Doors", "Stile and Rail Wood Doors" to ensure proper reinforcements. Advise the Architect where visible fasteners, such as thru bolts, are required.
- B. Provide screws, bolts, expansion shields, drop plates and other devices necessary for hardware installation.
 - 1. Where fasteners are exposed to view: Finish to match adjacent door hardware material.

C. Cable and Connectors:

- 1. Where scheduled in the hardware sets, provide each item of electrified hardware and wire harnesses with number and gage of wires enough to accommodate electric function of specified hardware.
- 2. Provide Molex connectors that plug directly into connectors from harnesses, electric locking and power transfer devices.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3. Provide through-door wire harness for each electrified locking device installed in a door and wire harness for each electrified hinge, electrified continuous hinge, electrified pivot, and electric power transfer for connection to power supplies.

2.03 HINGES

A. Manufacturers and Products:

- 1. Scheduled Manufacturer and Product:
 - a. Ives 5BB series
- 2. Acceptable Manufacturers and Products:
 - a. Hager BB1191/1279 series
 - b. Stanley FBB series

B. Requirements:

- 1. Provide hinges conforming to ANSI/BHMA A156.1.
- 2. Provide five knuckle, ball bearing hinges.
- 3. 1-3/4 inch (44 mm) thick doors, up to and including 36 inches (914 mm) wide:
 - a. Exterior: Standard weight, bronze or stainless steel, 4-1/2 inches (114 mm) high
 - b. Interior: Standard weight, steel, 4-1/2 inches (114 mm) high
- 4. 1-3/4 inch (44 mm) thick doors over 36 inches (914 mm) wide:
 - a. Exterior: Heavy weight, bronze/stainless steel, 5 inches (127 mm) high
 - b. Interior: Heavy weight, steel, 5 inches (127 mm) high
- 5. 2 inches or thicker doors:
 - a. Exterior: Heavy weight, bronze or stainless steel, 5 inches (127 mm) high
 - b. Interior: Heavy weight, steel, 5 inches (127 mm) high
- 6. Adjust hinge width for door, frame, and wall conditions to allow proper degree of opening.
- 7. Provide three hinges per door leaf for doors 90 inches (2286 mm) or less in height, and one additional hinge for each 30 inches (762 mm) of additional door height.
- 8. Hinge Pins: Except as otherwise indicated, provide hinge pins as follows:
 - a. Steel Hinges: Steel pins
 - b. Non-Ferrous Hinges: Stainless steel pins
 - c. Out-Swinging Exterior Doors: Non-removable pins
 - d. Out-Swinging Interior Lockable Doors: Non-removable pins
 - e. Interior Non-lockable Doors: Non-rising pins
- 9. Provide hinges with electrified options as scheduled in the hardware sets. Provide with number and gage of wires enough to accommodate electric function of specified hardware. Locate electric hinge at second hinge from bottom or nearest to electrified locking component. Provide mortar guard for each electrified hinge specified.

2.04 CONTINUOUS HINGES

A. Manufacturers:

- 1. Scheduled Manufacturer:
 - a. Ives

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2. Acceptable Manufacturers:

- a. Select
- b. ABH

B. Requirements:

- Provide aluminum geared continuous hinges conforming to ANSI/BHMA A156.26, Grade 1.
- 2. Provide aluminum geared continuous hinges, where specified in the hardware sets, fabricated from 6063-T6 aluminum.
- 3. Provide split nylon bearings at each hinge knuckle for quiet, smooth, self-lubricating operation.
- 4. Provide hinges capable of supporting door weights up to 450 pounds, and successfully tested for 1,500,000 cycles.
- 5. On fire-rated doors, provide aluminum geared continuous hinges classified for use on rated doors by testing agency acceptable to authority having jurisdiction.
- 6. Provide aluminum geared continuous hinges with electrified option scheduled in the hardware sets. Provide with number and gage of wires enough to accommodate electric function of specified hardware.
- 7. Provide hinges 1 inch (25 mm) shorter in length than nominal height of door, unless otherwise noted or door details require shorter length and with symmetrical hole pattern.

2.05 EXIT DEVICES

A. Manufacturers and Products:

- 1. Scheduled Manufacturer and Product:
 - a. Von Duprin 98/35A series
- 2. Acceptable Manufacturers and Products:
 - a. No Substitute

B. Requirements:

- Provide exit devices tested to ANSI/BHMA A156.3 Grade 1 and UL listed for Panic Exit or Fire Exit Hardware.
- 2. Cylinders: Refer to "KEYING" article, herein.
- 3. Provide smooth touchpad type exit devices, fabricated of brass, bronze, stainless steel, or aluminum, plated to standard architectural finishes to match balance of door hardware.
- Touchpad must extend a minimum of one half of door width. No plastic inserts are allowed in touchpads.
- 5. Provide exit devices with deadlatching feature for security and for future addition of alarm kits and/or other electrified requirements.
- 6. Provide exit devices with weather resistant components that can withstand harsh conditions of various climates and corrosive cleaners used in outdoor pool environments.
- 7. Provide flush end caps for exit devices.
- 8. Provide exit devices with manufacturer's approved strikes.
- 9. Provide exit devices cut to door width and height. Install exit devices at height recommended by exit device manufacturer, allowable by governing building codes, and approved by Architect.
- 10. Mount mechanism case flush on face of doors or provide spacers to fill gaps behind devices. Where glass trim or molding projects off face of door, provide glass bead kits.

11. Provide cylinder or hex-key dogging as specified at non fire-rated openings.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 12. Removable Mullions: 2 inches (51 mm) x 3 inches (76 mm) steel tube. Where scheduled as keyed removable mullion, provide type that can be removed by use of a keyed cylinder, which is self-locking when re-installed.
- 13. Provide factory drilled weep holes for exit devices used in full exterior application, highly corrosive areas, and where noted in hardware sets.
- 14. Provide electrified options as scheduled.
- 15. Top latch mounting: double- or single-tab mount for steel doors, face mount for aluminum doors eliminating requirement of tabs, and double tab mount for wood doors.
- 16. Provide exit devices with optional trim designs to match other lever and pull designs used on the project.
- 17. Special Options:
 - a. CVC
 - Provide cable-actuated concealed vertical latch system in two-point for non-rated or fire rated wood doors up to a 90 minute rating and less bottom latch (LBL) configuration for non-rated or fire rated wood doors up to 20 minute rating. Vertical rods not permitted.
 - Cable: Stainless steel with abrasive resistant coating. Conduit and core wire ends snap into latch and center slides without use of tools.
 - b) Wood Door Prep: Maximum 1 inch x 1.1875 inch x 3.875 inches top latch pocket and 1 inch x 1.1875 inch x 5 inches bottom latch pocket which does not require the use of a metal wrap or edge for non-rated or fire rated wood doors up to a 45 minute rating.
 - c) Latchbolts and Blocking Cams: Manufactured from sintered metal low carbon copper- infiltrated steel, with molybdenum disulfide low friction coating.
 - d) Top Latchbolt: Minimum 0.38 inch (10 mm) and greater than 90-degree engagement with strike to prevent door and frame separation under high static load.
 - e) Bottom Latchbolt: Minimum of 0.44-inch (11 mm) engagement with strike.
 - f) Product Cycle Life: 1,000,000 cycles.
 - g) Latch Operation: Top and bottom latch operate independently of each other. Top latch fully engages top strike even when bottom latch is compromised. Separate trigger mechanisms not permitted.
 - h) Latch release does not require separate trigger mechanism.
 - i) Cable and latching system characteristics:
 - i. Installed independently of exit device installation, and capable of functioning on door prior to device and trim installation.
 - ii. Connected to exit device at single point in steel and aluminum doors, and two points for top and bottom latches in wood doors.
 - iii. Bottom latch height adjusted, from single point for steel and aluminum doors and two points for wood doors, after system is installed and connected to exit device, while door is hanging
 - iv. Bottom latch position altered up and down minimum of 2 inches (51 mm) in steel and aluminum doors without additional adjustment. Bottom latch deadlocks in every adjustment position in wood doors.
 - v. Top and bottom latches in steel and aluminum doors and top latch in wood doors may be removed while door is hanging.

2.06 CYLINDERS

- A. Manufacturers and Products:
 - 1. Scheduled Manufacturer and Product:
 - a. Schlage Everest 29 T

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Acceptable Manufacturers and Products:
 - a. No Substitute

B. Requirements:

- Provide cylinders/cores compliant with ANSI/BHMA A156.5; latest revision; cylinder face finished to match lockset; manufacturer's series as indicated. Refer to "KEYING" article, herein.
- 2. Provide cylinders in the below-listed configuration(s), distributed throughout the Project as indicated.
 - a. Conventional Patented Restricted: cylinder with interchangeable core with patented, restricted keyway.
- 3. Patent Protection: Cylinders/cores requiring use of restricted, patented keys, patent protected.
- 4. Nickel silver bottom pins.

2.07 KEYING

A. Scheduled System:

- 1. Existing factory registered system:
 - a. Provide cylinders/cores keyed into Owner's existing factory registered keying system.
 Comply with guidelines in ANSI/BHMA A156.28, incorporating decisions made at keying conference.

B. Requirements:

- 1. Construction Keying:
 - a. Replaceable Construction Cores.
 - 1) Provide temporary construction cores replaceable by permanent cores, furnished in accordance with the following requirements.
 - a) 3 construction control keys
 - b) 12 construction change (day) keys.
 - 2) Owner or Owner's Representative will replace temporary construction cores with permanent cores.

2. Permanent Keying:

- a. Provide permanent cylinders/cores keyed by the manufacturer according to the following key system.
 - 1) Master Keying system as directed by the Owner.
- b. Forward bitting list and keys separately from cylinders, by means as directed by Owner. Failure to comply with forwarding requirements will be cause for replacement of cylinders/cores involved at no additional cost to Owner.
- c. Provide keys with the following features:
 - 1) Material: Nickel silver; minimum thickness of .107-inch (2.3mm)
 - 2) Patent Protection: Keys and blanks protected by one or more utility patent(s).
 - Geographically Exclusive: Where High Security or Security cylinders/cores are indicated, provide nationwide, geographically exclusive key system complying with the following restrictions.
- d. Identification:
 - 1) Mark permanent cylinders/cores and keys with applicable blind code for identification. Do not provide blind code marks with actual key cuts.
 - 2) Identification stamping provisions must be approved by the Architect and Owner.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3) Stamp cylinders/cores and keys with Owner's unique key system facility code as established by the manufacturer; key symbol and embossed or stamped with "DO NOT DUPLICATE" along with the "PATENTED" or patent number to enforce the patent protection.
- 4) Failure to comply with stamping requirements will be cause for replacement of keys involved at no additional cost to Owner.
- 5) Forward permanent cylinders/cores to Owner, separately from keys, by means as directed by Owner.
- e. Quantity: Furnish in the following quantities.
 - 1) Change (Day) Keys: 3 per cylinder/core.
 - 2) Permanent Control Keys: 3.
 - 3) Master Keys: 6.

2.08 KEY CONTROL SYSTEM

A. Manufacturers:

- 1. Scheduled Manufacturer:
 - a. Telkee
- 2. Acceptable Manufacturers:
 - a. HPC
 - b. Lund

B. Requirements:

- Provide key control system, including envelopes, labels, tags with self-locking key clips, receipt forms, 3-way visible card index, temporary markers, permanent markers, and standard metal cabinet, all as recommended by system manufacturer, with capacity for 150% of number of locks required for Project.
 - a. Provide complete cross index system set up by hardware supplier, and place keys on markers and hooks in cabinet as determined by final key schedule.
 - b. Provide hinged-panel type cabinet for wall mounting.

2.09 DOOR CLOSERS

A. Manufacturers and Products:

- 1. Scheduled Manufacturer and Product:
 - a. LCN 4040XP series
- 2. Acceptable Manufacturers and Products:
 - a. No Substitute

B. Requirements:

- Provide door closers conforming to ANSI/BHMA A156.4 Grade 1 requirements by BHMA certified independent testing laboratory. ISO 9000 certify closers. Stamp units with date of manufacture code.
- 2. Provide door closers with fully hydraulic, full rack and pinion action with high strength cast iron cylinder, and full complement bearings at shaft.
- 3. Cylinder Body: 1-1/2-inch (38 mm) diameter piston with 5/8-inch (16 mm) diameter double heat-treated pinion journal. QR code with a direct link to maintenance instructions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Hydraulic Fluid: Fireproof, passing requirements of UL10C, and requiring no seasonal closer adjustment for temperatures ranging from 120 degrees F to -30 degrees F.
- 5. Spring Power: Continuously adjustable over full range of closer sizes, and providing reduced opening force as required by accessibility codes and standards. Provide snap-on cover clip, with plastic covers, that secures cover to spring tube.
- 6. Hydraulic Regulation: By tamper-proof, non-critical valves, with separate adjustment for latch speed, general speed, and backcheck. Provide graphically labelled instructions on the closer body adjacent to each adjustment valve. Provide positive stop on reg valve that prevents reg screw from being backed out.
- 7. Provide closers with solid forged steel main arms and factory assembled heavy-duty forged forearms for parallel arm closers.
- 8. Pressure Relief Valve (PRV) Technology: Not permitted.
- 9. Finish for Closer Cylinders, Arms, Adapter Plates, and Metal Covers: Powder coating finish which has been certified to exceed 100 hours salt spray testing as described in ANSI Standard A156.4 and ASTM B117, or has special rust inhibitor (SRI).
- Provide special templates, drop plates, mounting brackets, or adapters for arms as required for details, overhead stops, and other door hardware items interfering with closer mounting.

2.10 DOOR TRIM

A. Manufacturers:

- 1. Scheduled Manufacturer:
 - a. Ives
- 2. Acceptable Manufacturers:
 - a. Elmes
 - b. Trimco

B. Requirements:

1. Provide push plates, push bars, pull plates, pulls, and hands-free reversible door pulls with diameter and length as scheduled.

2.11 PROTECTION PLATES

A. Manufacturers:

- 1. Scheduled Manufacturer:
 - a. Ives
- 2. Acceptable Manufacturers:
 - a. Burns
 - b. Trimco

B. Requirements:

- 1. Provide protection plates with a minimum of 0.050 inch (1 mm) thick, beveled four edges as scheduled. Furnish with sheet metal or wood screws, finished to match plates.
- 2. Sizes plates 2 inches (51 mm) less width of door on single doors, pairs of doors with a mullion, and doors with edge guards. Size plates 1 inch (25 mm) less width of door on pairs without a mullion or edge guards.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3. At fire rated doors, provide protection plates over 16 inches high with UL label.

2.12 DOOR STOPS AND HOLDERS

A. Manufacturers:

- 1. Scheduled Manufacturer:
 - a. Ives
- 2. Acceptable Manufacturers:
 - a. Trimco
 - b. Burns

B. Provide door stops at each door leaf:

- Provide wall stops wherever possible. Provide concave type where lockset has a push button of thumbturn.
- 2. Where a wall stop cannot be used, provide universal floor stops.
- 3. Where wall or floor stop cannot be used, provide overhead stop.
- Provide roller bumper where doors open into each other and overhead stop cannot be used.

2.13 THRESHOLDS, SEALS, DOOR SWEEPS, AUTOMATIC DOOR BOTTOMS, AND GASKETING

A. Manufacturers:

- 1. Scheduled Manufacturer:
 - a. Zero International
- 2. Acceptable Manufacturers:
 - a. Reese
 - b. Legacy

B. Requirements:

- 1. Provide thresholds, weather-stripping, and gasketing systems as specified and per architectural details. Match finish of other items.
- 2. Smoke- and Draft-Control Door Assemblies: Where smoke- and draft-control door assemblies are required, provide door hardware that meets requirements of assemblies tested according to UL 1784 and installed in compliance with NFPA 105.
- 3. Provide door sweeps, seals, astragals, and auto door bottoms only of type where resilient or flexible seal strip is easily replaceable and readily available.
- 4. Size thresholds 1/2 inch (13 mm) high by 5 inches (127 mm) wide by door width unless otherwise specified in the hardware sets or detailed in the drawings.

2.14 SILENCERS

A. Manufacturers:

- 1. Scheduled Manufacturer:
 - a. Ives

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Acceptable Manufacturers:
 - a. Burns
 - b. Trimco

B. Requirements:

- 1. Provide "push-in" type silencers for hollow metal or wood frames.
- Provide one silencer per 30 inches (762 mm) of height on each single frame, and two for each pair frame.
- 3. Omit where gasketing is specified.

2.15 FINISHES

- A. FINISH: BHMA 626/652 (US26D); EXCEPT:
 - 1. Hinges at Exterior Doors: BHMA 630 (US32D)
 - 2. Aluminum Geared Continuous Hinges: BHMA 628 (US28)
 - 3. Push Plates, Pulls, and Push Bars: BHMA 630 (US32D)
 - 4. Protection Plates: BHMA 630 (US32D)
 - 5. Overhead Stops and Holders: BHMA 630 (US32D)
 - 6. Door Closers: Powder Coat to Match
 - 7. Wall Stops: BHMA 630 (US32D)
 - 8. Latch Protectors: BHMA 630 (US32D)
 - 9. Weatherstripping: Clear Anodized Aluminum
 - 10. Thresholds: Mill Finish Aluminum

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Prior to installation of hardware, examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire-rated door assembly construction, wall and floor construction, and other conditions affecting performance. Verify doors, frames, and walls have been properly reinforced for hardware installation.
- B. Examine roughing-in for electrical power systems to verify actual locations of wiring connections before electrified door hardware installation.
- C. Submit a list of deficiencies in writing and proceed with installation only after unsatisfactory conditions have been corrected.

3.02 INSTALLATION

- A. Mount door hardware units at heights to comply with the following, unless otherwise indicated or required to comply with governing regulations.
 - 1. Standard Steel Doors and Frames: ANSI/SDI A250.8.
 - 2. Custom Steel Doors and Frames: HMMA 831.
 - 3. Interior Architectural Wood Flush Doors: ANSI/WDMA I.S. 1A
 - 4. Installation Guide for Doors and Hardware: DHI TDH-007-20

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Install door hardware in accordance with NFPA 80, NFPA 101 and provide post-install inspection, testing as specified in section 1.03.E unless otherwise required to comply with governing regulations.
- C. Install each hardware item in compliance with manufacturer's instructions and recommendations, using only fasteners provided by manufacturer.
- D. Do not install surface mounted items until finishes have been completed on substrate. Protect all installed hardware during painting.
- E. Set units level, plumb and true to line and location. Adjust and reinforce attachment substrate as necessary for proper installation and operation.
- F. Drill and countersink units that are not factory prepared for anchorage fasteners. Space fasteners and anchors according to industry standards.
- G. Install operating parts so they move freely and smoothly without binding, sticking, or excessive clearance.
- H. Hinges: Install types and in quantities indicated in door hardware schedule but not fewer than quantity recommended by manufacturer for application indicated.
- Lock Cylinders:
 - 1. Install construction cores to secure building and areas during construction period.
 - 2. Replace construction cores with permanent cores as indicated in keying section.
 - 3. Furnish permanent cores to Owner for installation.
- J. Wiring: Coordinate with Division 26, ELECTRICAL and Division 28 ELECTRONIC SAFETY AND SECURITY sections for:
 - 1. Conduit, junction boxes and wire pulls.
 - 2. Connections to and from power supplies to electrified hardware.
 - 3. Connections to fire/smoke alarm system and smoke evacuation system.
 - Connection of wire to door position switches and wire runs to central room or area, as directed by Architect.
 - 5. Connections to panel interface modules, controllers, and gateways.
 - 6. Testing and labeling wires with Architect's opening number.
- K. Key Control System: Tag keys and place them on markers and hooks in key control system cabinet, as determined by final keying schedule.
- L. Door Closers: Mount closers on room side of corridor doors, inside of exterior doors, and stair side of stairway doors from corridors. Mount closers so they are not visible in corridors, lobbies and other public spaces unless approved by Architect.
- M. Closer/Holders: Mount closer/holders on room side of corridor doors, inside of exterior doors, and stair side of stairway doors.
- N. Power Supplies: Locate power supplies as indicated or, if not indicated, above accessible ceilings or in equipment room, or alternate location as directed by Architect.
- O. Thresholds: Set thresholds in full bed of sealant complying with requirements specified in Division 07 Section "Joint Sealants."

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- P. Stops: Provide floor stops for doors unless wall or other type stops are indicated in door hardware schedule. Do not mount floor stops where they may impede traffic or present tripping hazard.
- Q. Perimeter Gasketing: Apply to head and jamb, forming seal between door and frame.
- R. Meeting Stile Gasketing: Fasten to meeting stiles, forming seal when doors are closed.
- Door Bottoms and Sweeps: Apply to bottom of door, forming seal with threshold when door is closed.

3.03 ADJUSTING

- A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.
 - 1. Door Closers: Adjust sweep period to comply with accessibility requirements and requirements of authorities having jurisdiction.
- B. Occupancy Adjustment: Approximately three to six months after date of Substantial Completion, examine and readjust each item of door hardware, including adjusting operating forces, as necessary to ensure function of doors and door hardware.

3.04 CLEANING AND PROTECTION

- A. Clean adjacent surfaces soiled by door hardware installation.
- B. Clean operating items per manufacturer's instructions to restore proper function and finish.
- C. Provide final protection and maintain conditions that ensure door hardware is without damage or deterioration at time of Substantial Completion.

3.05 DOOR HARDWARE SCHEDULE

- A. The intent of the hardware specification is to specify the hardware for interior and exterior doors, and to establish a type, continuity, and standard of quality. However, it is the door hardware supplier's responsibility to thoroughly review existing conditions, schedules, specifications, drawings, and other Contract Documents to verify the suitability of the hardware specified.
- B. Discrepancies, conflicting hardware, and missing items are to be brought to the attention of the architect with corrections made prior to the bidding process. Omitted items not included in a hardware set should be scheduled with the appropriate additional hardware required for proper application.
- C. Hardware items are referenced in the following hardware schedule. Refer to the above specifications for special features, options, cylinders/keying, and other requirements.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

D. Hardware Sets:

83551 OPT0303034 Version 2

Legend:

Link to catalog cut sheet

★ Electrified Opening

Hardware Group No. 01 - PAIR, OUTSWING, ALUM STOREFRONT, RIM PANIC X MULLION

For use on Door #(s):

1B 2A

Provide each PR door(s) with the following:

(QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
2	2	EA	CONT. HINGE	112HD	628	IVE
•	1	EA	REMOVABLE MULLION	HW-KR4954 STAB	689	VON
•	1	EA	PANIC HARDWARE	CD-98-EO	630AM	VON
•	1	EA	PANIC HARDWARE	CD-98-NL-OP-110MD	630	VON
•	1	EA	MULLION STORAGE KIT	MT54	689	VON
•	1	EA	RIM HOUSING	20-079	626	SCH
(3	EA	MORTISE CYLINDER	30-032 X K510-680	626	SCH
4	4	EA	FSIC CORE	23-030 EV29 T	626	SCH
4	4	EA	FSIC CORE	23-030 ICX	622	SCH
2	2	EA	90 DEG OFFSET PULL	8190EZHD 10" STD	630- 316	IVE
2	2	EA	SURFACE CLOSER	4040XP EDA	689	LCN
2	2	EA	FLOOR STOP	FS18L	BLK	IVE
•	1	EA	MULLION SEAL	8780NBK PSA	BK	ZER
2	2	EA	DOOR SWEEP	39A	Α	ZER
	1	EA	THRESHOLD	655A-V3-223	Α	ZER

- 1. BALANCE OF SEALS/GASKETING BY ALUMINUM STOREFRONT DOOR/FRAME MFG.
- 2. MOUNT FLOOR STOP TO ALLOW FOR MAXIMUM DEGREE OF SWING.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

Hardware Group No. 01A - PAIR, OUTSWING, RIM PANIC X MULLION

For use on Door #(s):

5A

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
6	EA	HINGE	5BB1HW 4.5 X 4.5 NRP	630	IVE
1	EA	REMOVABLE MULLION	HW-KR4954 STAB	689	VON
1	EA	PANIC HARDWARE	CD-98-EO	630AM	VON
1	EA	PANIC HARDWARE	CD-98-NL-OP-110MD	630	VON
1	EA	MULLION STORAGE KIT	MT54	689	VON
1	EA	RIM HOUSING	20-079	626	SCH
3	EA	MORTISE CYLINDER	30-032 X K510-680	626	SCH
4	EA	FSIC CORE	23-030 EV29 T	626	SCH
4	EA	FSIC CORE	23-030 ICX	622	SCH
2	EA	90 DEG OFFSET PULL	8190EZHD 10" STD	630- 316	IVE
2	EA	SURFACE CLOSER	4040XP EDA	689	LCN
2	EA	FLOOR STOP	FS18L	BLK	IVE
1	SET	GASKETING	139A-S	Α	ZER
1	EA	MULLION SEAL	8780NBK PSA	BK	ZER
2	EA	DOOR SWEEP	39A	Α	ZER
1	EA	THRESHOLD	655A-V3-223	Α	ZER

^{1.} MOUNT FLOOR STOP TO ALLOW FOR MAXIMUM DEGREE OF SWING.

Hardware Group No. 01B - PAIR, OUTSWING, ALUM STOREFRONT, PUSH/PULL

For use on Door #(s):

1A

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
2	EA	CONT. HINGE	112HD	628	IVE
2	EA	DUMMY PUSH BAR	350	626	VON
2	EA	90 DEG OFFSET PULL	8190EZHD 10" STD	630- 316	IVE
2	EA	SURFACE CLOSER	4040XP CUSH	689	LCN

^{1.} BALANCE OF SEALS/GASKETING BY ALUMINUM STOREFRONT DOOR/FRAME MFG.

Hardware Group No. 01C - Not Used

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

Hardware Group No. 02 - SINGLE, OUTSWING, ALUM STOREFRONT

For use on Door #(s):

2B

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	CONT. HINGE	112HD	628	IVE
1	EA	PANIC HARDWARE	CD-98-NL-OP-110MD	630	VON
1	EA	RIM HOUSING	20-079	626	SCH
1	EA	MORTISE CYLINDER	30-032 X K510-680	626	SCH
1	EA	FSIC CORE	23-030 EV29 T	626	SCH
1	EA	FSIC CORE	23-030 ICX	622	SCH
1	EA	90 DEG OFFSET PULL	8190EZHD 10" STD	630- 316	IVE
1	EA	SURFACE CLOSER	4040XP EDA	689	LCN
1	EA	FLOOR STOP	FS18L	BLK	IVE
1	EA	DOOR SWEEP	39A	Α	ZER
1	EA	THRESHOLD	655A-V3-223	Α	ZER

- 1. BALANCE OF SEALS/GASKETING BY ALUMINUM STOREFRONT DOOR/FRAME MFG.
- 2. MOUNT FLOOR STOP TO ALLOW FOR MAXIMUM DEGREE OF SWING.

Hardware Group No. 03 - SINGLE, INSWING, GANG RESTROOM, FIRE RATED

For use on Door #(s):

3A 4A

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1HW 4.5 X 4.5	652	IVE
1	EA	PASSAGE SET	ND10S RHO	626	SCH
1	EA	SURFACE CLOSER	4040XP RW/PA TBWMS	689	LCN
1	EA	MOP PLATE	8400 3 1/2" X 1" LDW B-CS	630	IVE
1	EA	KICK PLATE	8400 8" X 2" LDW B-CS	630	IVE
1	EA	WALL STOP	WS406/407 CCV	626	IVE
1	EA	GASKETING	488SBK PSA	BK	ZER

Hardware Group No. 04 - CASED OPENING

For use on Door #(s):

2C

Provide each CO door(s) with the following:

QTY DESCRIPTION CATALOG NUMBER FINISH MFR

CASED OPENING - NO HARDWARE REQUIRED

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

DOOR HARDWARE INDEX:

Door#	HwSet#
1A	01B
1B	01
2A	01
2B	02
2C	04
3A	03
4A	03
5A	01A

END OF SECTION 087100

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 088000 GLAZING

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. 16 CFR 1201 Safety Standard for Architectural Glazing Materials Current Edition.
- B. ANSI Z97.1 American National Standard for Safety Glazing Materials Used in Buildings Safety Performance Specifications and Methods of Test 2015 (Reaffirmed 2020).
- C. ASCE 7 Minimum Design Loads and Associated Criteria for Buildings and Other Structures Most Recent Edition Cited by Referring Code or Reference Standard.
- D. ASTM C864 Standard Specification for Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers 2005 (Reapproved 2019).
- E. ASTM C1048 Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass 2018.
- F. ASTM C1376 Standard Specification for Pyrolytic and Vacuum Deposition Coatings on Flat Glass 2021a.
- G. ASTM E1300 Standard Practice for Determining Load Resistance of Glass in Buildings 2016.
- H. ASTM E2190 Standard Specification for Insulating Glass Unit Performance and Evaluation 2019.
- I. GANA (GM) GANA Glazing Manual 2008.
- J. IGMA TM-3000 North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial & Residential Use 1990 (2016).
- K. NFRC 100 Procedure for Determining Fenestration Product U-factors 2020.
- L. NFRC 200 Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence 2020.
- M. NFRC 300 Test Method for Determining the Solar Optical Properties of Glazing Materials and Systems 2023.

1.02 ADMINISTRATIVE REQUIREMENTS

A. Preinstallation Meeting: Convene a preinstallation meeting one week before starting work of this section; require attendance by each of the affected installers.

1.03 SUBMITTALS

- A. Product Data on Insulating Glass Unit and Glazing Unit Glazing Types: Provide structural, physical and environmental characteristics, size limitations, special handling and installation requirements.
- B. Product Data on Glazing Compounds and Accessories: Provide chemical, functional, and environmental characteristics, limitations, special application requirements, and identify available colors.
- C. Certificate: Certify that products of this section meet or exceed specified requirements.

1.04 QUALITY ASSURANCE

A. Perform Work in accordance with GANA (GM) and IGMA TM-3000 for glazing installation methods.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.05 FIELD CONDITIONS

- A. Do not install glazing when ambient temperature is less than 40 degrees F.
- B. Maintain minimum ambient temperature before, during and 24 hours after installation of glazing compounds.

1.06 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Insulating Glass Units: Provide a ten (10) year manufacturer warranty to include coverage for seal failure, interpane dusting or misting, including providing products to replace failed units.
- C. Laminated Glass: Provide a five (5) year manufacturer warranty to include coverage for delamination, including providing products to replace failed units.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Float Glass Manufacturers:
 - Cardinal Glass Industries.
 - Guardian Glass, LLC.
 - 3. Pilkington North America Inc.
 - 4. Vitro Architectural Glass (formerly PPG Glass).

2.02 PERFORMANCE REQUIREMENTS - EXTERIOR GLAZING ASSEMBLIES

- A. Provide type and thickness of exterior glazing assemblies to support assembly dead loads, and to withstand live loads caused by positive and negative wind pressure acting normal to plane of glass.
 - Design Pressure: Calculated in accordance with ASCE 7 and values indicated on Structural Drawings.
 - 2. Comply with ASTM E1300 for design load resistance of glass type, thickness, dimensions, and maximum lateral deflection of supported glass.
 - 3. Provide glass edge support system sufficiently stiff to limit the lateral deflection of supported glass edges to less than 1/175 of their lengths under specified design load.
 - 4. Glass thicknesses listed are minimum.
- B. Weather-Resistive Barrier Seals: Provide completed assemblies that maintain continuity of building enclosure water-resistive barrier, vapor retarder, and air barrier.
- C. Thermal and Optical Performance: Provide exterior glazing products with performance properties as indicated. Performance properties are in accordance with manufacturer's published data as determined with the following procedures and/or test methods:
 - 1. Center of Glass U-Value: Comply with NFRC 100 using Lawrence Berkeley National Laboratory (LBNL) WINDOW 6.3 computer program.
 - 2. Center of Glass Solar Heat Gain Coefficient (SHGC): Comply with NFRC 200 using Lawrence Berkeley National Laboratory (LBNL) WINDOW 6.3 computer program.
 - 3. Solar Optical Properties: Comply with NFRC 300 test method.

2.03 GLASS MATERIALS

- A. Float Glass: Provide float glass based glazing unless otherwise indicated.
 - 1. Kind HS Heat-Strengthened Type: Complies with ASTM C1048.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 2. Kind FT Fully Tempered Type: Complies with ASTM C1048.
- 3. Provide Type I, Quality-Q3, Class 1 (clear) glazing unless otherwise indicated.
 - Tinted Glazing: Where tinted glazing is indicated, provide Class 2 (tinted).
- 4. Fully Tempered Safety Glass: Complies with ANSI Z97.1 or 16 CFR 1201 criteria for safety glazing used in hazardous locations.

2.04 INSULATING GLASS UNITS

- A. Fabricator: Certified by glass manufacturer for type of glass, coating, and treatment involved and capable of providing specified warranty.
- B. Insulating Glass Units: Types as indicated.
 - 1. Durability: Certified by an independent testing agency to comply with ASTM E2190.
 - Coated Glass: Comply with requirements of ASTM C1376 for pyrolytic (hard-coat) or magnetic sputter vapor deposition (soft-coat) type coatings on flat glass; coated vision glass, Kind CV; coated overhead glass, Kind CO; or coated spandrel glass, Kind CS.
 - 3. Warm-Edge Spacers: Manufacturer's warm-edge technology design.
 - a. Spacer Width: As required for specified insulating glass unit.
 - b. Spacer Height: Manufacturer's standard.
 - c. Products:
 - 1) Quanex IG Systems, Inc; Super Spacer TriSeal.
 - 2) Technoform Glass Insulation; TGI-Spacer.
 - 3) Substitutions: See Section 016000 Product Requirements.
 - 4. Spacer Color: Black.
 - 5. Edge Seal:
 - a. Dual-Sealed System: Provide polyisobutylene sealant as primary seal applied between spacer and glass panes, and silicone, polysulfide, or polyurethane sealant as secondary seal applied around perimeter.
 - b. Color: Black.
 - 6. Purge interpane space with dry air, hermetically sealed.

2.05 GLAZING UNITS

- A. Type G1 Monolithic Interior Vision Glazing:
 - 1. Applications: Interior glazing unless otherwise indicated.
 - 2. Glass Type: Heat-strengthened / fully-tempered float glass. Provide with safety glazing labeling.
 - 3. Tint: Clear.
 - 4. Thickness: 1/4 inch, nominal.
- B. Type G2 Insulating Glass Units: Vision glass, double glazed.
 - 1. Applications: Exterior glazing unless otherwise indicated.
 - 2. Space between lites filled with air.
 - 3. Outboard Lite: Heat-strengthened / fully-tempered float glass, 1/4 inch thick, minimum.
 - a. Tint: Gray
 - b. Coating: Low-E (passive type), on #2 surface.
 - c. Coating Products (Low-E; Gray Tinted):
 - 1) Cardinal; ES 25 Pure Grey #2.
 - 2) Guardian; SN 68 Gray.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 3) Viracon; #VE3-2M.
- 4) Vitro; Solarban 60 (2) Solargray.
- 4. Warm-edge spacer.
- 5. Inboard Lite: Heat-strengthened / fully-tempered float glass, 1/4 inch thick, minimum.
 - a. Tint: Clear.
- 6. Total Thickness: 1 inch.
- 7. Thermal Transmittance (U-Value), Winter Center of Glass: 0.30, maximum.
- 8. Solar Heat Gain Coefficient (SHGC): 0.25, maximum.
- 9. Glazing Method: Dry glazing method, gasket glazing.
- 10. Provide with safety glazing labeling.

2.06 ACCESSORIES

- A. Setting Blocks: Silicone, with 80 to 90 Shore A durometer hardness; ASTM C864 Option II. Length of 0.1 inch for each square foot of glazing or minimum 4 inch by width of glazing rabbet space minus 1/16 inch by height to suit glazing method and pane weight and area.
- B. Spacer Shims: Neoprene, 50 to 60 Shore A durometer hardness; ASTM C864 Option
 II. Continuous by one half the height of the glazing stop by thickness to suit application, self adhesive on one face.
- C. Glazing Tape, Back Bedding Mastic Type: Preformed, butyl-based, 100 percent solids compound with integral resilient spacer rod applicable to application indicated; 5 to 30 cured Shore A durometer hardness; coiled on release paper; black color.
- D. Glazing Splines: Resilient silicone extruded shape to suit glazing channel retaining slot; ASTM C864 Option II; color black.

PART 3 EXECUTION

3.01 VERIFICATION OF CONDITIONS

- A. Verify that openings for glazing are correctly sized and within tolerances, including those for size, squareness, and offsets at corners.
- B. Verify that surfaces of glazing channels or recesses are clean, free of obstructions that may impede moisture movement, weeps are clear, and support framing is ready to receive glazing system.

3.02 PREPARATION

- A. Clean contact surfaces with appropriate solvent and wipe dry within maximum of 24 hours before glazing. Remove coatings that are not tightly bonded to substrates.
- B. Seal porous glazing channels or recesses with substrate compatible primer or sealer.
- C. Prime surfaces scheduled to receive sealant where required for proper sealant adhesion.

3.03 INSTALLATION, GENERAL

- A. Install glazing in compliance with written instructions of glass, gaskets, and other glazing material manufacturers, unless more stringent requirements are indicated, including those in glazing referenced standards.
- B. Do not exceed edge pressures around perimeter of glass lites as stipulated by glass manufacturer.
- C. Set glass lites of system with uniform pattern, draw, bow, and similar characteristics.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- D. Set glass lites in proper orientation so that coatings face exterior or interior as indicated.
- E. Prevent glass from contact with any contaminating substances that may be the result of construction operations such as, and not limited to the following; weld splatter, fire-safing, plastering, mortar droppings, etc.

3.04 INSTALLATION - DRY GLAZING METHOD (GASKET GLAZING)

- A. Application Exterior and/or Interior Glazed: Set glazing infills from either the exterior or the interior of the building.
- B. Place setting blocks at 1/4 points with edge block no more than 6 inch from corners.
- Rest glazing on setting blocks and push against fixed stop with sufficient pressure on gasket to attain full contact.
- Install removable stops without displacing glazing gasket; exert pressure for full continuous contact.

3.05 FIELD QUALITY CONTROL

- A. Glass and Glazing product manufacturers to provide field surveillance of the installation of their products.
- B. Monitor and report installation procedures and unacceptable conditions.

3.06 CLEANING

- A. Remove excess glazing materials from finish surfaces immediately after application using solvents or cleaners recommended by manufacturers.
- B. Remove nonpermanent labels immediately after glazing installation is complete.
- C. Clean glass and adjacent surfaces after sealants are fully cured.
- D. Clean glass on both exposed surfaces not more than 4 days prior to Date of Substantial Completion in accordance with glass manufacturer's written recommendations.

3.07 PROTECTION

- A. After installation, mark pane with an 'X' by using removable plastic tape or paste; do not mark heat absorbing or reflective glass units.
- B. Remove and replace glass that is damaged during construction period prior to Date of Substantial Completion.

END OF SECTION 088000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 092900 GYPSUM BOARD

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ANSI A108.11 American National Standard Specifications for Interior Installation of Cementitious Backer Units 2018.
- B. ANSI A118.9 American National Standard Specifications for Test Methods and Specifications for Cementitious Backer Units 2019.
- C. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes 2021.
- D. ASTM C475/C475M Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board 2017 (Reapproved 2022).
- E. ASTM C665 Standard Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing 2017.
- F. ASTM C840 Standard Specification for Application and Finishing of Gypsum Board 2020.
- G. ASTM C1047 Standard Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base 2019.
- H. ASTM C1177/C1177M Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing 2017.
- ASTM C1280 Standard Specification for Application of Exterior Gypsum Panel Products for Use as Sheathing 2018.
- J. ASTM C1325 Standard Specification for Fiber-Mat Reinforced Cementitious Backer Units 2022.
- K. ASTM C1396/C1396M Standard Specification for Gypsum Board 2017.
- L. ASTM C1629/C1629M Standard Classification for Abuse-Resistant Nondecorated Interior Gypsum Panel Products and Fiber-Reinforced Cement Panels 2019.
- M. ASTM C1658/C1658M Standard Specification for Glass Mat Gypsum Panels 2019, with Editorial Revision (2020).
- N. ASTM D3273 Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber 2021.
- O. ASTM G21 Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi 2015, with Editorial Revision (2021).
- P. GA-216 Application and Finishing of Gypsum Panel Products 2021.
- Q. UL 752 Standard for Bullet-Resisting Equipment Current Edition, Including All Revisions.

1.02 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide data on gypsum board, glass mat faced gypsum board, accessories, and joint finishing system.
- C. Test Reports: Bullet resistant sheathing and wallboard.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.03 DELIVERY, STORAGE, HANDLING, AND FIELD CONDITIONS

- A. Do not deliver or install until building is weather-tight and conditioned.
- B. Store materials in dry and clean location until needed for installation. During installation, handle in a manner that will prevent damage and to prevent marring and soiling of finished surfaces.
- C. Do not install gypsum products that have gotten wet or moldy, or show signs of past moisture damage.
- D. Maintain uniform temperature and humidity at occupancy conditions during and after installation. Allow products to acclimatize prior to installation.

PART 2 PRODUCTS

2.01 BOARD MATERIALS

- A. Gypsum Wallboard: Paper-faced gypsum panels as defined in ASTM C1396/C1396M; sizes to minimize joints in place; with tapered edges.
 - 1. Application: Use for vertical surfaces and ceilings, unless otherwise indicated.
 - 2. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
 - a. Mold-resistant board is required whenever gypsum board is indicated in rooms subject to steam or water, including mechanical rooms, toilet rooms, custodial rooms, and kitchens.
 - 3. At Assemblies Indicated with Fire-Resistance Rating: Use type required by indicated tested assembly; if no tested assembly is indicated, use Type X board, UL or WH listed.
 - Thickness:
 - a. Vertical Surfaces: 5/8 inch.
 - b. Ceilings: 5/8 inch.
 - c. Curved Surfaces: Provide flexible 1/4 inch thickness gypsum board.

B. Impact Resistant Wallboard:

- 1. Application: High-traffic areas indicated.
- Surface Abrasion: Level 3, minimum, when tested in accordance with ASTM C1629/C1629M.
- 3. Indentation: Level 1, minimum, when tested in accordance with ASTM C1629/C1629M.
- Soft Body Impact: Level 3, minimum, when tested in accordance with ASTM C1629/C1629M.
- Hard Body Impact: Level 2, minimum, when tested in accordance with ASTM C1629/C1629M.
- Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
- 7. Paper-Faced Type: Gypsum wallboard, as defined in ASTM C1396/C1396M.
- 8. Glass Mat-Faced Type: Gypsum wallboard, as defined in ASTM C1658/C1658M.
- 9. Type: Fire-resistance-rated Type X, UL or WH listed.
- 10. Thickness: 5/8 inch.
- 11. Edges: Tapered.
- 12. Paper-Faced Products:
 - a. American Gypsum Company; M-Bloc IR Type X.
 - b. CertainTeed Corporation; Extreme Impact Resistant Drywall with M2Tech.
 - c. National Gypsum Company; Gold Bond Hi-Impact XP Gypsum Board.
 - d. Substitutions: See Section 016000 Product Requirements.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 13. Glass Mat Faced Products:
 - a. Georgia-Pacific Gypsum; DensArmor Plus Impact-Resistant.
 - b. USG Corporation; USG Sheetrock Brand Glass-Mat Panels Mold Tough VHI.
 - c. Substitutions: See Section 016000 Product Requirements.
- C. Tile Backing Board:
 - Application: Surfaces behind tile in wet areas including tub and shower surrounds.
 - 2. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
 - ANSI Cement-Based Board: Non-gypsum-based; cementitious panels with glass fiber mesh embedded in front and back surfaces complying with ANSI A118.9 and ASTM C 1288 or ASTM C1325.
 - a. Thickness: 5/8 inch.
 - b. Available Products:
 - 1) FinPan, Inc.; Util-A-Crete Backer Board.
 - 2) National Gypsum Company; PermaBase Cement Board.
 - 3) USG Corporation; Durock Cement Board.
 - 4) Substitutions: See Section 016000 Product Requirements.
- D. Bullet Resistant Sheathing and Wallboard: Woven roving, multi-ply, ballistic grade fiberglass cloth with thermoset polyester resin; comply with UL 752 Level 3. Size boards to minimize joints.
 - 1. Thickness: Nominal 7/16 inch or 1/2 inch as standard with manufacturer.
 - Available Products:
 - a. ArmorCore by Waco Composites; Bullet Resistant Fiberglass Panels.
 - b. Armortex, Div. of Safeguard Security System, Inc.; OF 300.
 - c. Chicago Bullet Proof Systems; Fibre-Tex.
 - d. C.R. Laurence of North America; BRF300.
 - e. Insulgard Corporation; FG-300.
- E. Exterior Sheathing Board for Ceilings and Soffits: Sizes to minimize joints in place; ends square cut.
 - 1. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
 - 2. Fungal Resistance: No fungal growth when tested in accordance with ASTM G21.
 - Glass Mat Faced Sheathing: Glass mat faced gypsum substrate as defined in ASTM C1177/C1177M.
 - 4. Edges: Square.
 - 5. Available Glass Mat Faced Products:
 - a. American Gypsum Company; M-Glass Exterior Sheathing.
 - b. CertainTeed Corporation; GlasRoc Exterior Sheathing.
 - c. Georgia-Pacific Gypsum; DensGlass Sheathing.
 - d. National Gypsum Company; Gold Bond eXP Sheathing.
 - e. USG Corporation; USG Securock Brand Ultralight Glass-Mat Sheathing.

2.02 GYPSUM BOARD ACCESSORIES

A. Sound Attenuation Batts: ASTM C665; preformed glass fiber, friction fit type, unfaced. Thickness sized to fit metal stud cavity.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. Acoustic Sealant: Acrylic emulsion latex or water-based elastomeric sealant; do not use solvent-based non-curing butyl sealant. Refer to sealant AS-1 in Division 07 Section "Joint Sealants."
- C. Putty Pads: Non-hardening endothermic material, in pad form, faced on both sides with poly liner, designed to seal around penetrations and wiring devices, enhancing acoustic performance.
 - 1. Nominal Size: 7-1/4 x 7-1/4 x 3/16 inches.
 - Available Products:
 - a. 3M; Fire Barrier Moldable Putty Pads MPP+.
 - b. Hilti; Firestop Putty Pad, CFS-P PA.
 - Specified Technologies, Inc.; SpecSeal Putty Pad.
- D. Beads, Joint Accessories, and Other Trim: ASTM C1047, rigid plastic, galvanized steel, or rolled zinc, unless noted otherwise.
 - 1. Corner Beads: Low profile, for 90 degree outside corners.
 - L-Trim with Tear-Away Strip: Sized to fit gypsum wallboard size(s) indicated.
- E. Decorative Metal Trim:
 - 1. Material: Extruded aluminum alloy 6063-T5 temper.
 - 2. Finish: Anodized, clear.
 - 3. Type: Profile as selected from manufacturer's standard range.
- F. Metal Edge Trim for "Cloud" Suspended Ceilings: Steel or extruded aluminum; provide attachment clips, splice plates, and preformed corner pieces for a complete trim system.
 - 1. Trim Height: 4 inches.
 - 2. Finish: Baked enamel; white.
 - 3. Available Products:
 - a. Armstrong World Industries, Inc.; Axiom Classic.
 - b. Certainteed; Terminus Perimeter Trim.
 - c. Chicago Metallic Corp.; Infinity System.
 - d. USG Corporation; Compasso Suspension Trim.
- G. Acoustic Partition Closure at Storefront or Curtain Wall: Multi-piece rectangular-section assembly of nested U-shape aluminum extrusions for finished closure between aluminum storefront or curtainwall system vertical mullion (and glass where indicated), and partition assembly. Closure shall allow for movements of framing and glass it attaches to, and shall not allow direct metal to glass contact. Fill cavity of partition closure with acoustic batt insulation.
 - 1. Thickness: Aluminum closure plates not less than 0.125-inch thick.
 - 2. Acoustic Rating: Provide product with a minimum tested STC rating of 55.
 - Acoustic Material: Fungi- and microbe-resistant foam, Class A rated when tester per ASTM E 84.
 - 3. Acoustical Sealant: Seal both ends of partition closure with acoustical sealant.
 - 4. Finish: Powder coat; color selected by Architect from manufacturer's full range.
 - 5. Available Products:
 - a. Gordon, Inc; Mullion Mate.
 - b. Mull-It-Over Products; Mull-It-Over.
- H. Joint Materials: ASTM C475/C475M and as recommended by gypsum board manufacturer for project conditions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- Exterior Soffit Vents: One piece, perforated, ASTM B221 6063 T5 alloy aluminum, with edge suitable for direct application to gypsum board and manufactured especially for soffit application. Provide continuous vent.
 - 1. Available Manufacturers:
 - a. Fry Reglet.
 - b. Gordon, Inc.
 - c. Pittcon Industries.
 - Stockton Products.
 - 2. Flat, horizontal-to-horizontal application: 2-inch wide with three rows of vent slots for a minimum of 3 square inches of opening per linear foot.
 - 3. Finish: High performance organic coating; color selected by Architect from manufacturer's full range.
- J. Security Barrier Mesh: ASTM F 1267, Type II, Class 1; expanded and flattened diamond mesh security barrier. Fabricate of uncoated, minimum 18 gage carbon steel, weight 0.66 lbs/sq. ft. Provide with lath mesh size approximately 1/2-inch by 1-1/4-inch.
 - Mesh Fasteners: Provide fasteners that are non-corrosive to both mesh and framing substrate; as recommended by manufacturer for mesh-to-mesh and mesh-to-framing fastening.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that project conditions are appropriate for work of this section to commence.

3.02 ACOUSTIC ACCESSORIES INSTALLATION

- A. Sound Attenuation Batts: Place tightly within spaces, around cut openings, behind and around electrical and mechanical items within partitions, and tight to items passing through partitions.
- B. Acoustic Sealant: Install in accordance with manufacturer's instructions.

3.03 BOARD INSTALLATION

- A. Comply with ASTM C840, GA-216, and manufacturer's instructions. Install to minimize butt end joints, especially in highly visible locations.
- B. Single-Layer Nonrated: Install gypsum board in most economical direction, with ends and edges occurring over firm bearing.
- C. Double-Layer, Nonrated: Use gypsum board for first layer, placed parallel to framing or furring members, with ends and edges occurring over firm bearing. Use glass mat faced gypsum board at exterior walls and at other locations as indicated. Place second layer perpendicular to framing or furring members. Offset joints of second layer from joints of first layer.
- D. Fire-Resistance-Rated Construction: Install gypsum board in strict compliance with requirements of assembly listing.
- E. Install gypsum board with an open horizontal joint (gap) not to exceed 5/8-inch above finished floor slab, and tape and finish vertical joints to bottom edge of board to afford a smooth substrate for applied wall base.
- F. Exterior Sheathing: Comply with ASTM C1280. Install sheathing vertically, with edges butted tight and ends occurring over firm bearing.
- G. Cementitious Backing Board: Install over steel framing members where indicated, in accordance with ANSI A108.11 and manufacturer's instructions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- H. Bullet Resistant Sheathing and Wallboard:
 - 1. Install bullet-resistant sheathing according to manufacturer's written recommendations and with manufacturer-approved fasteners.
 - 2. Cover all joints between boards with a 4 inch strip of the same thickness material as the boards, centered on the joint.

3.04 INSTALLATION OF TRIM AND ACCESSORIES

- A. Control Joints: Place control joints in compliance with ASTM C 840, consistent with lines of building spaces, and as indicated.
 - 1. Not more than 30 feet apart on walls and ceilings over 50 feet long.
 - 2. At exterior soffits, not more than 30 feet apart in both directions.
- B. Corner Beads: Install at external corners, using longest practical lengths.
- C. Decorative Trim: Install at locations shown on drawings and in accordance with manufacturer's instructions.
- D. Exterior Soffit Vents: Install according to manufacturer's written instructions and in locations indicated on drawings. Provide vent area specified.
- E. Putty Pads: Install putty pads on the backside of items penetrating gypsum board on STC-rated walls/partitions. Items include, but are not limited to, wiring devices, cable, conduit, and pipe. Completely cover and seal around each penetration.

3.05 JOINT TREATMENT

- A. Finish gypsum board in accordance with levels defined in ASTM C840, as follows:
 - Level 4: Walls and ceilings to receive paint finish or wall coverings, unless otherwise indicated.
 - 2. Level 2: In utility areas, behind cabinetry, and on backing board to receive tile finish.
 - 3. Level 1: Fire-resistance-rated wall areas above finished ceilings, whether or not accessible in the completed construction.
- B. Tape, fill, and sand exposed joints, edges, and corners to produce smooth surface ready to receive finishes.
 - 1. Feather coats of joint compound so that camber is maximum 1/32 inch.
- Fill and finish joints and corners of cementitious backing board as recommended by manufacturer.

3.06 TOLERANCES

A. Maximum Variation of Finished Gypsum Board Surface from True Flatness: 1/8 inch in 10 feet in any direction.

END OF SECTION 092900

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 093000 TILING

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ANSI A108.1a American National Standard Specifications for Installation of Ceramic Tile in the Wet-Set Method, with Portland Cement Mortar 2017.
- B. ANSI A108.1b American National Standard Specifications for Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set or Latex-Portland Cement Mortar 2017.
- C. ANSI A108.1c Contractor's Option: Installation of Ceramic Tile in the Wet-Set Method with Portland Cement Mortar or Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set or Latex-Portland Cement Mortar 1999 (Reaffirmed 2021).
- D. ANSI A108.2 American National Standard General Requirements: Materials, Environmental and Workmanship 2019.
- E. ANSI A108.4 American National Standard Specifications for Installation of Ceramic Tile with Organic Adhesive or Water Cleanable Tile-Setting Epoxy Adhesive 2019.
- F. ANSI A108.5 American National Standard Specifications for Installation of Ceramic Tile with Dry-Set Portland Cement Mortar or Latex-Portland Cement Mortar 2021.
- G. ANSI A108.6 American National Standard Specifications for Installation of Ceramic Tile with Chemical Resistant, Water Cleanable Tile-Setting and -Grout Epoxy 1999 (Reaffirmed 2019).
- H. ANSI A108.9 American National Standard Specifications for Installation of Ceramic Tile with Modified Epoxy Emulsion Mortar/Grout 1999 (Reaffirmed 2019).
- I. ANSI A108.10 American National Standard Specifications for Installation of Grout in Tilework 2017.
- J. ANSI A108.13 American National Standard for Installation of Load Bearing, Bonded, Waterproof Membranes for Thin-Set Ceramic Tile and Dimension Stone 2005 (Reaffirmed 2021).
- K. ANSI A108.19 American National Standard Specifications for Interior Installation of Gauged Porcelain Tiles and Gauged Porcelain Tile Panels/Slabs by the Thin-Bed Method Bonded with Modified Dry-Set Cement Mortar or Improved Modified Dry-Set Cement Mortar 2020.
- ANSI A108.20 American National Standard Specifications for Exterior Installation of Gauged Porcelain Tiles and Gauged Porcelain Tile Panels/Slabs 2020.
- M. ANSI A118.4 American National Standard Specifications for Modified Dry-Set Cement Mortar 2019.
- N. ANSI A118.7 American National Standard Specifications for High Performance Cement Grouts for Tile Installation 2019.
- ANSI A118.10 American National Standard Specifications for Load Bearing, Bonded, Waterproof Membranes for Thin-Set Ceramic Tile and Dimension Stone 2014 (Reaffirmed 2019).
- P. ANSI A118.12 American National Standard Specifications for Crack Isolation Membranes for Thin-Set Ceramic Tile and Dimension Stone Installation 2014 (Reaffirmed 2019).
- Q. ANSI A118.15 American National Standard Specifications for Improved Modified Dry-Set Cement Mortar 2019.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- R. ANSI A137.1 American National Standard Specifications for Ceramic Tile 2022.
- S. TCNA (HB) Handbook for Ceramic, Glass, and Stone Tile Installation 2022.

1.02 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Convene a preinstallation meeting at the Project Site one week before starting work of this section; require attendance by affected installers.
 - 1. Review substrate preparation requirements.
 - 2. Review each type of tile, mortar, grout, and TCNA installation methods.
 - 3. Review requirements for waterproofing and/or crack isolation membrane(s).

1.03 SUBMITTALS

- A. Product Data: Provide manufacturers' data sheets on tile, mortar, grout, and accessories. Include instructions for using grouts and adhesives.
- B. Shop Drawings: Indicate tile layout, patterns, color arrangement, perimeter conditions, junctions with dissimilar materials, control and expansion joints, thresholds, ceramic accessories, and setting details.
 - 1. Include waterproofing details at floor drains, shower pans, cove base, and thresholds.
- C. Installer's Qualification Statement.
 - Submit documentation of National Tile Contractors Association (NTCA) or Tile Contractors' Association of America (TCAA) accreditation.
 - 2. Submit documentation of completion of apprenticeship and certification programs.
- Maintenance Data: Include recommended cleaning methods, cleaning materials, and stain removal methods.

1.04 QUALITY ASSURANCE

- A. Installer Qualifications: Installer shall have documented experience of work similar in scope, materials, and design to that indicated for this Project, with a record of successful in-service performance, with references upon request. Installer shall hold company-wide accreditation or employ individuals with one of the listed certifications (comply with at least one):
 - 1. Company-wide accreditation from one of the following:
 - Accredited Five-Star member of the National Tile Contractors Association (NTCA) or Trowel of Excellence member of the Tile Contractors' Association of America (TCAA).
 - 2. Installer Certification:
 - a. Ceramic Tile Education Foundation (CTEF): Certified Tile Installer (CTI).
 - b. Apprenticeship Program: Installer has achieved Journeyworker status through an apprenticeship from the International Union of Bricklayers and Allied Craftworkers (IUBAC) or a U.S. Department of Labor (DOL)-recognized program.

1.05 MOCK-UPS

- A. See Section 014000 Quality Requirements for general requirements for mock-up.
- Construct tile mock-up where indicated on drawings, incorporating all components specified for the location.
 - 1. Provide mock-up of minimum 5 square feet for each type of floor tile, unless otherwise indicated.
 - Provide mock-up of minimum 5 square feet for each type of wall tile, unless otherwise indicated.
 - 3. Approved mock-up may remain as part of the Work.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Store tile, grout, and mortar off the ground, protected from weather and water infiltration.
- B. Store products in unopened containers or packages until ready for use.
- C. Protect materials from freezing or overheating in accordance with manufacturer's instructions.

1.07 FIELD CONDITIONS

- A. Do not install solvent-based products in an unventilated environment.
- B. Maintain ambient and substrate temperature and humidity at levels required by referenced ANSI and TCNA tile standards, and per manufacturer's instructions.

PART 2 PRODUCTS

2.01 TILE

- A. Glazed Wall Tile, Type GWT: ANSI A137.1 standard grade.
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Daltile, "Color Wheel Classic" or one of the following:
 - a. American Orlean; "Color Story Wall"
 - b. Crossville Inc; "Retro Active 2.0"
 - 2. Size: 4 by 4 inch, nominal; 5/16-inch thick.
 - 3. Edges: Square.
 - 4. Surface Finish: Matte glaze.
 - 5. Color(s): To be selected by Architect from manufacturer's full range.

2.02 TRIM AND ACCESSORIES

- A. Non-Ceramic Trim: Satin brass anodized extruded aluminum, style and dimensions to suit application, for setting using tile mortar or adhesive.
 - Applications:
 - a. Open edges of wall tile.
 - b. Open edges of floor tile.
 - c. Wall corners, outside and inside.
 - d. Transition between floor finishes of different heights.
 - e. Thresholds at door openings.
 - f. Expansion and control joints, floor and wall.
 - g. Floor to wall joints.
 - h. Borders and other trim as indicated on drawings.
 - 2. Manufacturers:
 - a. Schluter-Systems.
 - b. Genesis APS International.
 - c. Blanke.
 - d. Ceramic Tool Company (CTC).
 - e. Substitutions: See Section 016000 Product Requirements.
- B. Thresholds: 2 inches wide by full width of wall or frame opening; beveled edge on both long edges; without holes, cracks, or open seams.
 - 1. Material: Marble, honed finish.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2. Applications:

a. At doorways where tile terminates.

2.03 SETTING MATERIALS

- A. Provide setting and grout materials from same manufacturer.
- B. Modified Dry-Set Mortar (Thinset): ANSI A118.4
 - Applications: Use this type at all locations where thinset mortar is indicated, unless otherwise indicated.
 - 2. Products:
 - a. H.B. Fuller Construction Products, Inc.; TEC Full Flex TA 390/391.
 - LATICRETE International, Inc.; 252 Silver.
 - c. MAPEI Corporation; Ultraflex 2.
 - d. Summitville Tiles, Inc.; S-1000 MP Thin-Set Latex Mortar.
 - e. Substitutions: See Section 016000 Product Requirements.
- C. Latex-Portland Cement LHT Mortar (Medium-Bed): ANSI A118.4.
 - 1. Applications: Use this type of bond coat where Large and Heavy Tile (LHT) mortar is indicated, in a 5/8-inch thick medium-bed application.
 - Products:
 - Custom Building Products; ProLite Premium Rapid Setting Large Format Tile Mortar, with Multi-Surface Bonding Primer.
 - b. H.B. Fuller Construction Products, Inc; TEC Ultimate Large Tile Mortar.
 - c. LATICRETE International, Inc; 257 TITANIUM.
 - d. MAPEI Corporation; Ultraflex LFT.
 - e. Merkrete, by Parex USA, Inc; Merkrete 735 Premium Flex.
 - f. Summitville Tiles, Inc.; S-1200 MP Premium Medium Bed Mortar.
 - g. Substitutions: See Section 016000 Product Requirements.
- D. Improved Latex-Portland Cement Dry-Set Mortar (Thinset): ANSI A118.15 and ISO 13007 "C2" classification.
 - 1. Applications: Use this type of mortar where indicated.
 - 2. Products:
 - a. H.B. Fuller Construction Products, Inc; TEC 3N1 Performance Mortar.
 - b. LATICRETE International, Inc; LATICRETE 254 Platinum.
 - c. MAPEI Corporation; Ultraflex 3.
 - d. Substitutions: See Section 016000 Product Requirements.

2.04 GROUTS

- A. Provide setting and grout materials from same manufacturer.
- B. High Performance Polymer Modified Grout: ANSI A118.7 polymer modified cement grout.
 - 1. Applications: Use this type of grout where indicated and where no other type of grout is indicated.
 - 2. Use sanded grout for joints 1/8 inch wide and larger; use unsanded grout for joints less than 1/8 inch wide.
 - 3. Color(s): As selected by Architect from manufacturer's full line.
 - Products:
 - a. Custom Building Products; Prism Color Consistent Grout.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- b. H.B. Fuller Construction Products, Inc; TEC AccuColor Plus Grout.
- c. LATICRETE International, Inc; LATICRETE PERMACOLOR Grout.
- d. MAPEI Corporation; Ultracolor Plus.
- e. Merkrete, by Parex USA, Inc; Merkrete Pro Grout.
- f. Substitutions: See Section 016000 Product Requirements.

2.05 MAINTENANCE MATERIALS

- A. Tile Sealants: Moisture- and mildew-resistant type sealants; one-part silicone for wall applications and multi-part urethane for floor applications. Sealants and accessories shall comply with requirements below and with requirements of Division 7 Section "Joint Sealants."
 - 1. Color(s): As selected by Architect from manufacturer's full line. Sealant colors shall match grout colors in adjacent joints unless otherwise indicated.
 - 2. Silicone Sealant (Walls): ASTM C 920, Type S, Grade NS, Class 25; Uses NT (non-traffic), G (glass), A (aluminum), O (other substrates indicated).
 - a. Products:
 - 1) GE Silicones, a division of GE Specialty Materials; SCS1700 Sanitary.
 - 2) Pecora Corporation; Pecora 898 NST.
 - 3) Tremco Inc.; Tremsil 200.
 - 4) Substitutions: See Section 016000 Product Requirements.
 - Urethane Sealant (Floors): ASTM C 920, Type M, Grade P, Class 25; Uses T (traffic), M (mortar), A (aluminum), O (other substrates indicated).
 - a. Products:
 - 1) Master Builders Solutions; MasterSeal SL 2.
 - 2) Pecora Corporation; NR-200 Urexpan.
 - 3) Sika Corporation; Sikaflex-2c SL.
 - 4) Tremco Inc.; THC-901.
 - 5) Substitutions: See Section 016000 Product Requirements.
 - 4. Sealant Accessories: Provide backer rod, primer, and other sealant accessories as recommended by sealant manufacturer for applications required.
- B. Grout Sealer: Liquid-applied, penetrating, moisture and stain protection for existing or new Portland cement grout.
 - 1. Composition: Water-based colorless silicone.
 - 2. Products:
 - a. Custom Building Products; Aqua Mix Sealer's Choice Gold.
 - b. Merkrete, by Parex USA, Inc; Merkrete Grout Sealer.
 - c. SGM, Inc.; Grout Sealer.
 - d. Summitville Tiles, Inc.; SL-99 Summitseal II.
 - e. Substitutions: See Section 016000 Product Requirements.
- C. Tile Sealer: Stain protection for exposed surfaces of unglazed ceramic tile, other porous tile, and grout. Provide penetrating sealer with no sheen, preserving natural tile appearance.
 - 1. Products:
 - a. Custom Building Products; Agua Mix Sealer's Choice Gold.
 - b. Rust-Oleum Corporation; Miracle Sealants 511 Impregnator Natural Looking Penetrating Sealer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- c. STONETECH, a division of LATICRETE international, Inc; STONETECH Heavy Duty Sealer.
- d. Substitutions: See Section 016000 Product Requirements.
- D. Grout Release: Temporary, water-soluble pre-grout coating.
 - Products:
 - a. Custom Building Products; Agua Mix Grout Release.
 - MAPEI Corporation; UltraCare Grout Release.
 - c. Substitutions: See Section 016000 Product Requirements.

2.06 ACCESSORY MATERIALS

- A. Concrete Floor Slab Crack Isolation Membrane: Material complying with ANSI A118.12; not intended as waterproofing.
 - 1. Crack Resistance: No failure at 1/8 inch gap, minimum.
 - 2. Peel-and-Stick Sheet Type:
 - a. Material: Rubberized membrane laminated to reinforcing fabric.
 - b. Thickness: 40 mils, nominal.
 - c. Products:
 - 1) Boiardi Products Corp.; a QEP company; Elastiment 340 Sound Control Sheet Membrane Waterproofing and Anti-Fracture/Crack-Suppression System.
 - Custom Building Products; Crack Buster Pro-Crack Prevention Mat Underlayment.
 - 3) MAPEI Corporation; Mapeguard 2.
 - 4) National Applied Construction Products, Inc.; ECB Anti-Fracture Membrane.
 - 5) Substitutions: See Section 016000 Product Requirements.
- B. Waterproofing Membrane: Specifically designed for bonding to cementitious substrate under thick mortar bed or thin-set tile; complying with ANSI A118.10.
 - 1. Crack Resistance: No failure at 1/8 inch gap, minimum; comply with ANSI A118.12.
 - 2. Fluid or Trowel Applied Type with Embedded Reinforcing Fabric:
 - Material: Synthetic rubber or Acrylic.
 - b. Thickness: 30 mils, minimum, dry film thickness.
 - c. Products:
 - 1) Custom Building Products: 9240 Waterproofing and Anti-Fracture Membrane.
 - H.B. Fuller Construction Products, Inc; TEC HydraFlex Waterproofing Crack Isolation Membrane.
 - 3) LATICRETE International, Inc; 9235 Waterproofing Membrane.
 - 4) MAPEI Corporation; Mapelastic AquaDefense.
 - 5) Merkrete, by Parex USA, Inc; Merkrete Hydro Guard 2000.
 - 6) Summitville Tiles, Inc.; S-9000.
 - Substitutions: See Section 016000 Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that subfloor surfaces are smooth and flat within the tolerances specified for that type of work, per ANSI A108.01, and are ready to receive tile.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- B. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive tile.
- C. Verify that subfloor surfaces are dust free and free of substances that could impair bonding of setting materials to subfloor surfaces.
- D. Verify that required floor-mounted utilities are in correct location.

3.02 PREPARATION

- Protect surrounding work from damage.
- B. Vacuum clean surfaces and damp clean.
- Seal substrate surface cracks with filler. Level existing substrate surfaces to acceptable flatness tolerances.
- D. For ease of cleaning and to prevent staining, precoat tile with temporary grout release. For unglazed ceramic and other porous tile types, provide either combination tile sealer/grout release, or a temporary grout release with final tile sealer applied after tile installation.

3.03 INSTALLATION - GENERAL

- A. Install tile, thresholds, and stair treads and grout in accordance with applicable requirements of ANSI A108.1a through ANSI A108.20, manufacturer's instructions, and TCNA (HB) recommendations.
- B. Lay tile to pattern indicated. Do not interrupt tile pattern through openings.
- C. Cut and fit tile to penetrations through tile, leaving sealant joint space. Form corners and bases neatly. Align floor joints.
- D. Place tile joints uniform in width, subject to variance in tolerance allowed in tile size. Make grout joints without voids, cracks, excess mortar or excess grout, or too little grout.
- E. Form internal angles square and external angles bullnosed.
- F. Install non-ceramic trim in accordance with manufacturer's instructions.
- G. Install thresholds where indicated.
- H. Sound tile after setting. Replace hollow sounding units.
- I. Keep control and expansion joints free of mortar, grout, and adhesive.
- J. Prior to grouting, allow installation to completely cure; minimum of 48 hours.
- K. Grout tile joints unless otherwise indicated. Use standard grout unless otherwise indicated.
- L. At changes in plane and tile-to-tile control joints, use tile sealant instead of grout, with either bond breaker tape or backer rod as appropriate to prevent three-sided bonding.

3.04 INSTALLATION - FLOORS - THIN-SET METHODS

- A. Over interior concrete substrates, install in accordance with TCNA (HB) Method F122/F122A, over combination waterproofing/crack-isolation membrane, with latex-Portland cement grout.
 - 1. Provide modified dry-set mortar in a standard thinset bed, except provide LHT mortar in a 5/8-inch medium bed at all large format tile (tile 12 inches or greater in any dimension).

3.05 INSTALLATION - WALL TILE

A. Over interior concrete and masonry install in accordance with TCNA (HB) Method W202, thinset with dry-set or latex-Portland cement bond coat.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.06 CLEANING

A. Clean tile and grout surfaces.

3.07 PROTECTION

A. Do not permit traffic over finished floor surface for 4 days after installation.

END OF SECTION 093000

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 095100 ACOUSTICAL CEILINGS

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process 2022.
- B. ASTM C635/C635M Standard Specification for Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings 2022.
- C. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials 2022.
- D. ASTM E1264 Standard Classification for Acoustical Ceiling Products 2022.

1.02 SUBMITTALS

- A. Shop Drawings: Indicate grid layout and related dimensioning.
- B. Product Data: Provide data on suspension system components, acoustical units, and specialty ceiling products as indicated.
- C. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 Product Requirements, for additional provisions.
 - 2. Extra Acoustical Panels: Quantity equal to 2 percent of total installed, of each type.

1.03 QUALITY ASSURANCE

A. Source Limitations: Provide each acoustical ceiling assembly (ceiling panel and suspension system) from a single manufacturer to obtain manufacturer's system warranty.

1.04 DELIVERY, STORAGE, AND HANDLING

- A. Do not deliver until building is weather-tight and conditioned.
- B. Store materials in dry and clean location until needed for installation. During installation, handle in a manner that will prevent damage and to prevent marring and soiling of finished surfaces.

1.05 FIELD CONDITIONS

A. Maintain uniform temperature and humidity at occupancy conditions during and after acoustical unit installation. Allow products to acclimatize prior to installation.

1.06 WARRANTY

- A. System Warranty: Provide a single source system warranty covering both acoustical ceiling panels and suspension system.
 - 1. Warranty shall cover material failures including sag, warping, shrinkage, or delamination, biologic growth including mold or mildew, and rusting of suspension system.
 - 2. Warranty Period: Minimum 15 years, from date of Substantial Completion.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 2 PRODUCTS

2.01 PERFORMANCE REQUIREMENTS

A. Surface Burning Characteristics: Each acoustical ceiling shall be Class A rated, with flame spread index of 25 or less, smoke developed index of 50 or less, when tested in accordance with ASTM E84.

2.02 ACOUSTICAL PANELS

- A. Acoustical Panels General: ASTM E1264, Class A.
 - Antibacterial/Antimicrobial Treatment: Provide acoustical panels that have been factorytreated by manufacturer for resistance to bacteria, mold, mildew, and fungus.
 - 2. Humidity/Sag Treatment: Provide acoustical panels that have been factory-treated by manufacturer for humidity and sag-resistance.
- B. Acoustical Panels ACP-B: Painted mineral fiber, with the following characteristics:
 - 1. Classification: ASTM E1264 Type III.
 - a. Form: 2, water felted.
 - 2. Size: 24 by 48 inch.
 - 3. Thickness: 3/4 inch.
 - Light Reflectance: Not less than 0.82, determined in accordance with ASTM E1264.
 - 5. NRC Range: Not less than 0.70, determined in accordance with ASTM E1264.
 - 6. Panel Edge: Square.
 - 7. Color: White.
 - 8. Products:
 - a. Armstrong World Industries, Inc; School Zone Fine Fissured Item #1713.
 - b. CertainTeed Ceilings, Inc; Fine Fissured High NRC Item #HHF-457 HNRCX.
 - c. USG Corporation; Radar High-NRC Acoustical Panels Item #22421.
 - d. Substitutions: See Section 016000 Product Requirements.

2.03 SUSPENSION SYSTEM(S)

- A. Metal Suspension Systems General: Complying with ASTM C635/C635M; die cut and interlocking components, with perimeter moldings, hold down clips, stabilizer bars, clips, and splices as required.
 - 1. Materials:
 - a. Steel Grid: ASTM A653/A653M, G30 coating, unless otherwise indicated.
 - 2. Cross Tee/Main Runner Connection: Override (stepped).
 - Main Runner End Coupling: Bayonet ("stab") type; knuckle type is not acceptable.
- B. Exposed Suspension System, Type ACP-x: Hot-dipped galvanized steel grid with aluminum cap.
 - High Humidity Applications: Provide in kitchens, rooms with showers, custodial rooms, mechanical rooms, and other rooms where increased corrosion resistance due to humidity or steam is required.
 - Structural Classification: Intermediate-duty, when tested in accordance with ASTM C635/C635M.
 - 3. Coating: Provide minimum G60 hot-dip galvanized coating.
 - 4. Profile: Tee; 15/16 inch face width.
 - 5. Finish: Baked enamel.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 6. Color: White.
- Products:
 - a. Armstrong World Industries, Inc; Prelude Plus XL Fire Guard.
 - b. CertainTeed Ceilings, Inc; 15/16" EZ Stab Classic Environmental System.
 - c. USG Corporation; Donn Brand ZXLA 15/16 inch Acoustical Suspension System.
 - d. Substitutions: See Section 016000 Product Requirements.
- C. Exposed Suspension System, Type ACP: Hot-dipped galvanized steel grid and cap.
 - Structural Classification: Intermediate-duty, when tested in accordance with ASTM C635/C635M.
 - 2. Profile: Tee: 15/16 inch face width.
 - 3. Finish: Baked enamel.
 - Products:
 - a. Armstrong World Industries, Inc; Prelude XL 15/16".
 - b. CertainTeed Ceilings, Inc; 15/16" EZ Stab Classic System.
 - c. USG Corporation; Donn Brand DX/DXL 15/16 inch Acoustical Suspension System.
 - d. Substitutions: See Section 016000 Product Requirements.

2.04 ACCESSORIES

- A. Support Channels and Hangers: Galvanized steel; size and type to suit application, seismic requirements, and ceiling system flatness requirement specified.
- B. Hanger Wire: 12 gauge, 0.08 inch galvanized steel wire.
- C. Perimeter Moldings: Same metal and finish as grid.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that layout of hangers will not interfere with other work.

3.02 PREPARATION

- A. Install after major above-ceiling work is complete.
- B. Coordinate the location of hangers with other work.

3.03 INSTALLATION - SUSPENSION SYSTEM

- A. Rigidly secure system, including integral mechanical and electrical components, for maximum deflection of 1:360.
- B. Lay out system to a balanced grid design with edge units no less than 50 percent of acoustical unit size.
- C. Perimeter Molding: Install at intersection of ceiling and vertical surfaces and at junctions with other interruptions.
 - Use longest practical lengths.
- D. Suspension System, Non-Seismic: Hang suspension system independent of walls, columns, ducts, pipes and conduit. Where carrying members are spliced, avoid visible displacement of face plane of adjacent members.
 - 1. Do not hang suspension system directly from steel floor or roof deck.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- E. Seismic Suspension System, Seismic Design Category C: Hang suspension system independent of walls, columns, ducts, pipes and conduit. Maintain a 3/8 inch clearance between grid ends and wall.
- F. Where ducts or other equipment prevent the regular spacing of hangers, reinforce the nearest affected hangers and related carrying channels to span the extra distance.
- G. Do not support components on main runners or cross runners if weight causes total dead load to exceed deflection capability.
- H. Support fixture loads using supplementary hangers located within 6 inches of each corner, or support components independently.
- I. Do not eccentrically load system or induce rotation of runners.

3.04 INSTALLATION - ACOUSTICAL UNITS

- A. Install acoustical units in accordance with manufacturer's instructions.
- B. Fit acoustical units in place, free from damaged edges or other defects detrimental to appearance and function.
- C. Fit border trim neatly against abutting surfaces.
- D. Install acoustical units level, in uniform plane, and free from twist, warp, and dents.
- E. Cutting Acoustical Units:
 - 1. Make field cut edges of same profile as factory edges.
- F. Where round obstructions and bullnose concrete block corners occur, provide preformed closures to match perimeter molding.

3.05 TOLERANCES

- A. Maximum Variation from Flat and Level Surface: 1/8 inch in 10 feet.
- B. Maximum Variation from Plumb of Grid Members Caused by Eccentric Loads: 2 degrees.

END OF SECTION 095100

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 096500 RESILIENT FLOORING

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM E648 Standard Test Method for Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source 2019a, with Editorial Revision (2020).
- B. ASTM F710 Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring 2022.
- C. ASTM F1066 Standard Specification for Vinyl Composition Floor Tile 2004 (Reapproved 2018).
- D. ASTM F1869 Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride 2022.
- E. ASTM F2170 Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes 2019a.
- F. NFPA 253 Standard Method of Test for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source 2023.

1.02 SUBMITTALS

- A. Product Data: Provide data on specified products, describing physical and performance characteristics; including sizes, patterns and colors available; and installation instructions.
- B. Shop Drawings: Indicate seaming plans and floor patterns.
- Selection Samples: Submit manufacturer's complete set of color samples for Architect's initial selection.

1.03 DELIVERY, STORAGE, AND HANDLING

- A. Upon receipt, immediately remove any shrink-wrap and check materials for damage and the correct style, color, quantity and run numbers.
- B. Store all materials off of the floor in an acclimatized, weather-tight space.
- C. Maintain temperature in storage area between 55 degrees F and 90 degrees F.

1.04 FIELD CONDITIONS

A. Store materials for not less than 48 hours prior to installation in area of installation at a temperature of 70 degrees F to achieve temperature stability. Thereafter, maintain conditions above 55 degrees F.

1.05 WARRANTY

- A. See Section 017800 Closeout Submittals, for additional warranty requirements.
- B. Manufacturer's Warranty: Provide a ten (10) year manufacturer warranty, covering defective material and installation.
- C. Installer's Warranty: Installer shall warrant that the products have been installed in accordance with manufacturer's instructions.
 - 1. The installer shall provide a ten (10) year warranty against product failure due to excessive moisture vapor transmission through the slab.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 2 PRODUCTS

2.01 TILE FLOORING

- A. Vinyl Composition Tile: Homogenous, with pattern and color extending throughout thickness of the tile. "Through-color" is not acceptable.
 - 1. Manufacturers:
 - a. Armstrong Flooring; Standard Execelon Imperial Texture.
 - b. Johnsonite, a Tarkett Company; Azrock.
 - c. Vinylasa; Nova.
 - d. Substitutions: See Section 016000 Product Requirements.
 - 2. Minimum Requirements: Comply with ASTM F1066, Class 2 ("through-pattern").
 - 3. Critical Radiant Flux (CRF): Minimum 0.45 watt per square centimeter, when tested in accordance with ASTM E648 or NFPA 253.
 - 4. Size: 12 by 12 inch.
 - 5. Thickness: 0.125 inch.
 - 6. Color and Pattern: To be selected by Architect from manufacturer's full range.

2.02 ACCESSORIES

- A. Subfloor Filler: Type recommended by adhesive material manufacturer.
- B. Primers, Adhesives, and Seam Sealer: Waterproof; types recommended by flooring manufacturer.
- C. Moisture Vapor Treatment: Where resilient flooring and accessories are installed over concrete slabs, and where field testing indicates high moisture vapor testing through concrete slabs, provide alkaline-resistant product designed to control excessive moisture vapor transmission through concrete slab in accordance with Division 01 MVT allowance and unit price, and per the following:
 - 1. Products: Provide product approved by flooring manufacturer and complying with performance requirements below, equivalent to one of the following:
 - a. Duraamen Engineered Products, Inc.; Perdure MVT.
 - b. Maxxon Corporation; Maxxon MVP.
 - c. Tnemec Company Inc.; Epoxoprime MVT, Series 208.
 - 2. Performance Requirements:
 - a. Verify with flooring manufacturer that submitted product maintains compliance with all provisions of flooring manufacturer's warranty.
 - b. Low-VOC: Provide product with VOC content less than 15 g/L.
 - Bond Strength to Concrete: Minimum 400 psi per ASTM D 4541 (100% concrete failure).
 - d. Permeance: Maximum 0.1 perm per ASTM E 96, and 0.10 grains/hr/ft²/in-Hg, per ASTM F3010.
 - e. Applications: Provide MVT for all concrete slabs on-grade and lightweight concrete elevated slabs.
- D. Floor Polish: Fluid-applied polish recommended by resilient flooring manufacturer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces are flat to tolerances acceptable to flooring manufacturer, free of cracks that might telegraph through flooring, clean, dry, and free of curing compounds, surface hardeners, and other chemicals that might interfere with bonding of flooring to substrate.
- B. Cementitious Subfloor Surfaces: Verify that substrates are ready for resilient flooring installation by testing for moisture and alkalinity (pH).
 - 1. Test as Follows: Perform one of each test per 1,000 sf of installation area.
 - a. Alkalinity (pH): ASTM F710.
 - b. Internal Relative Humidity: ASTM F2170.
 - c. Moisture Vapor Emission: ASTM F1869.
 - 2. If test results are not within limits recommended by flooring manufacturer, apply moisture vapor treatment (MVT) in accordance with manufacturer's requirements. MVT shall be provided per unit price and quantity allowance requirements.

3.02 PREPARATION

- A. Prepare floor substrates as recommended by flooring and adhesive manufacturers.
- B. Remove subfloor ridges and bumps. Fill minor low spots, cracks, joints, holes, and other defects with subfloor filler to achieve smooth, flat, hard surface.
- C. Prohibit traffic until filler is fully cured.
- D. Clean substrate.

3.03 INSTALLATION - GENERAL

- A. Starting installation constitutes acceptance of subfloor conditions.
- B. Install in accordance with manufacturer's written instructions.
- C. Adhesive-Applied Installation:
 - 1. Fit joints and butt seams tightly.
 - 2. Set flooring in place, press with heavy roller to attain full adhesion.
- D. Where type of floor finish, pattern, or color are different on opposite sides of door, terminate flooring under centerline of door.
- E. Install edge strips at unprotected or exposed edges, where flooring terminates, and where indicated.
- F. Scribe flooring to walls, columns, cabinets, floor outlets, and other appurtenances to produce tight joints.

3.04 INSTALLATION - TILE FLOORING

- A. Mix tile from container to ensure shade variations are consistent when tile is placed, unless otherwise indicated in manufacturer's installation instructions.
- B. Lay flooring with joints and seams parallel to building lines to produce symmetrical pattern, unless otherwise indicated.

3.05 CLEANING

- A. Remove excess adhesive from floor, base, and wall surfaces without damage.
- B. Clean in accordance with manufacturer's written instructions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

C. Polish: Apply not less than three coats of floor polish. Provide additional coats as required to comply with manufacturer's recommendations.

3.06 PROTECTION

A. Prohibit traffic on resilient flooring for 48 hours after installation.

END OF SECTION 096500

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 096513 RESILIENT BASE AND ACCESSORIES

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM E648 Standard Test Method for Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source 2019a, with Editorial Revision (2020).
- B. ASTM F710 Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring 2022
- C. ASTM F1066 Standard Specification for Vinyl Composition Floor Tile 2004 (Reapproved 2018).
- D. ASTM F1861 Standard Specification for Resilient Wall Base 2021.
- E. ASTM F1869 Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride 2022.
- F. ASTM F2169 Standard Specification for Resilient Stair Treads 2015 (Reapproved 2020).
- G. ASTM F2170 Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes 2019a.
- H. NFPA 253 Standard Method of Test for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source 2023.

1.02 SUBMITTALS

- A. Product Data: Provide data on specified products, describing physical and performance characteristics; including sizes, patterns and colors available; and installation instructions.
- Selection Samples: Submit manufacturer's complete set of color samples for Architect's initial selection.
- C. Verification Samples: Submit in manufacturer's standard size, illustrating color and pattern for each resilient flooring product specified.

1.03 DELIVERY, STORAGE, AND HANDLING

- A. Upon receipt, immediately remove any shrink-wrap and check materials for damage and the correct style, color, quantity and run numbers.
- B. Maintain temperature in storage area between 55 degrees F and 90 degrees F.
- C. Protect roll materials from damage by storing on end.

1.04 FIELD CONDITIONS

- A. Store materials for not less than 48 hours prior to installation in area of installation at a temperature of 70 degrees F to achieve temperature stability. Thereafter, maintain conditions above 55 degrees F.
- B. Maintain conditions at occupancy conditions for installation and until Substantial Completion.

PART 2 PRODUCTS

2.01 RESILIENT BASE

A. Resilient Base: ASTM F1861, Type TP, rubber, thermoplastic; Style B, Cove.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 1. Products (Type TP):
 - a. Armstrong World Industries, Inc.; Rubber Coved Toe Wall Base.
 - b. Flexco (USA), Inc.; Flexco Base 2000 Cove.
 - c. Johnsonite, a Tarkett Company; Rubber Wall Base Cove.
 - d. Mannington Commercial; Burkebase Type TP Coved.
 - e. Nora Systems, Inc; nora wall base; Article 820.
 - f. Roppe Corporation; 700 Series TPR Wall Base Style B (Coved).
 - g. Substitutions: See Section 016000 Product Requirements.
- 2. Critical Radiant Flux (CRF): Minimum 0.45 watt per square centimeter, when tested in accordance with ASTM E648 or NFPA 253.
- 3. Height: 4 inch.
- 4. Thickness: 0.125 inch minimum.
- 5. Finish: Satin.
- 6. Length: Roll; manufacturer's standard length.
- 7. Color: To be selected by Architect from manufacturer's full range.

2.02 STAIR COVERING

- A. Stair Treads: Rubber; full width and depth of stair tread in one piece; tapered thickness.
 - 1. Manufacturers:
 - a. Flexco, Inc.
 - b. Johnsonite, a Tarkett Company.
 - c. Mannington Commercial.
 - d. Nora Rubber Flooring.
 - e. Roppe Corporation.
 - f. Substitutions: See Section 016000 Product Requirements.
 - 2. Minimum Requirements: Comply with ASTM F2169, Type TS, rubber, vulcanized thermoset.
 - 3. Critical Radiant Flux (CRF): Minimum 0.45 watt per square centimeter, when tested in accordance with ASTM E648 or NFPA 253.
 - 4. Nominal Thickness: 0.250 inch, tapered towards rear.
 - 5. Nosing: Square, adjustable; 1-1/2 inch height.
 - 6. Striping: 2 inch wide contrasting color abrasive strips.
 - 7. Texture: Raised, with pattern selected from manufacturer's full range.
 - 8. Color: To be selected by Architect from manufacturer's full range.
- B. Stair Risers: Full height and width of tread in one piece, matching treads in material and color.
 - 1. Manufacturer: Provide risers by same manufacturer as treads.
 - 2. Thickness: 0.125 inch.
- C. Stair Stringers: Full height in one piece and in maximum available lengths, matching treads in material and color.
 - 1. Manufacturer: Provide stringers by same manufacturer as treads.
 - 2. Nominal Thickness: 0.080 inch.

2.03 MOLDINGS, TRANSITIONS, AND EDGE STRIPS

- A. Moldings, Transition and Edge Strips:
 - 1. Manufacturers:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- a. Flexco, Inc.
- b. Johnsonite.
- c. Mannington Commercial.
- d. R.C.A. Rubber Company (The).
- e. Roppe Corporation.
- f. VPI, LLC; Floor Products Division.
- g. Substitutions: See Section 016000 Product Requirements.
- Molding/Transition Strip Profiles: Provide in sizes as required to suit flooring thicknesses and applications.
 - a. Coved edge/cap for carpet.
 - b. Joiner between carpet and resilient flooring or other materials with different heights.
 - c. Transition strip between different types of materials that are the same height or between different styles/patterns of the same material.
 - d. Slim transition strip with approximately 1/4-inch wide visible transition profile.
 - e. Reducer strip at edges of flooring to reduce height to 0".
 - Subfloor leveling accessory to transition between materials with height differences up to 1/2 inch.
- 3. Material: Manufacturer's standard rubber or vinyl.
- 4. Color: To be selected by Architect from manufacturer's full range.

2.04 ACCESSORIES

- A. Leveling Compound: Blended cement mix, latex-modified, for use as trowelable underlayment, approved by resilient accessory manufacturer.
- B. Primers, Adhesives, and Seam Sealer: Waterproof; types recommended by flooring manufacturer.
- C. Moisture Vapor Treatment: Where resilient flooring and accessories are installed over concrete slabs, provide alkaline-resistant product designed to control excessive moisture vapor transmission through concrete slab, per the following:
 - 1. Products: Provide product approved by flooring manufacturer and complying with performance requirements below, equivalent to one of the following:
 - a. Duraamen Engineered Products, Inc.; Perdure MVT.
 - b. Maxxon Corporation; Maxxon MVP.
 - c. Tnemec Company Inc.; Epoxoprime MVT, Series 208.
 - 2. Performance Requirements:
 - a. Verify with flooring manufacturer that submitted product maintains compliance with all provisions of flooring manufacturer's warranty.
 - b. Low-VOC: Provide product with VOC content less than 15 g/L.
 - Bond Strength to Concrete: Minimum 400 psi per ASTM D 4541 (100% concrete failure).
 - d. Permeance: Maximum 0.1 perm per ASTM E 96, and 0.10 grains/hr/ft²/in-Hg, per ASTM F3010.
 - Applications: Provide MVT for all concrete slabs on-grade and lightweight concrete elevated slabs.
- D. Floor Polish: Fluid-applied polish recommended by resilient flooring manufacturer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces are flat to tolerances acceptable to flooring manufacturer, free of cracks that might telegraph through flooring, clean, dry, and free of curing compounds, surface hardeners, and other chemicals that might interfere with bonding of flooring to substrate.
- B. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive resilient base.
 - Do not apply wall base until other finish items, including casework and painting, are complete.
- C. Cementitious Subfloor Surfaces (Stair Treads/Landings): Verify that substrates are ready for resilient flooring installation by testing for moisture and alkalinity (pH).
 - 1. Test as Follows:
 - a. Alkalinity (pH): ASTM F710, when required by stair accessory manufacturer.
 - b. Internal Relative Humidity: ASTM F2170. One test per stair area.
 - c. Moisture Vapor Emission: ASTM F1869. One test per stair area.
 - 2. If test results are not within limits recommended by stair accessory manufacturer, apply moisture vapor treatment (MVT) in accordance with manufacturer's requirements. MVT shall be provided per unit price and quantity allowance requirements.

3.02 PREPARATION

- A. Prepare floor substrates as recommended by flooring and adhesive manufacturers.
- B. Remove subfloor ridges and bumps. Fill minor low spots, cracks, joints, holes, and other defects with leveling compound to achieve smooth, flat, hard surface.
- C. Prohibit traffic until leveling compound is fully cured.
- D. Clean substrate.

3.03 INSTALLATION - GENERAL

- A. Starting installation constitutes acceptance of subfloor conditions.
- B. Install in accordance with manufacturer's written instructions.
- C. Adhesive-Applied Installation:
 - 1. Fit joints and butt seams tightly.
 - 2. Set flooring in place, press with heavy roller to attain full adhesion.
- D. Where type of floor finish, pattern, or color are different on opposite sides of door, install such that molding profiles or transition strips are centered under the door panel.
- E. Install edge/reducer strips at unprotected or exposed edges, where flooring terminates, and where indicated.
 - 1. Resilient Strips: Attach to substrate using adhesive.

3.04 INSTALLATION - RESILIENT BASE

- A. Fit joints tightly and make vertical. Maintain minimum dimension of 18 inches between joints.
- B. Install base on solid backing. Bond tightly to wall and floor surfaces.
- C. Job form internal and external corners in accordance with manufacturer's instructions. Form corners by "V" cutting or scribing; do not bend material in a manner that creates stress whitening.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- D. In addition to walls, install base on other permanent construction with exposed vertical faces at floor level, including, but not limited to, columns, pilasters, and casework/cabinet knee and toe spaces.
- E. Scribe and fit to door frames and other interruptions.
- F. At uneven substrate surfaces (such as masonry mortar joints), provide manufacturer's recommended filler sealant or adhesive to fill voids along top of base.

3.05 INSTALLATION - STAIR COVERINGS

- A. Install stair coverings in one piece for full width and depth of tread.
- B. Install stringers configured tightly to stair profile.
- C. Adhere over entire surface. Fit accurately and securely.
- Clean stair tread and landing accessories and apply floor polish according to manufacturer's written instructions.

3.06 CLEANING

- A. Remove excess adhesive from floor, base, and wall surfaces without damage.
- B. Clean in accordance with manufacturer's written instructions.

3.07 PROTECTION

- A. Prohibit traffic on resilient accessories for 48 hours after installation.
- B. Cover resilient accessories and protect from heavy construction traffic and equipment until Substantial Completion.

END OF SECTION 096513

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 096700 FLUID-APPLIED FLOORING

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM D695 Standard Test Method for Compressive Properties of Rigid Plastics 2015.
- B. ASTM D4060 Standard Test Method for Abrasion Resistance of Organic Coatings by the Taber Abraser 2019.
- C. ASTM F710 Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring 2022.
- D. ASTM F1869 Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride 2022.
- E. ASTM F2170 Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes 2019a.
- F. ICRI 310.2R Selecting and Specifying Concrete Surface Preparation for Sealers, Coatings, Polymer Overlays, and Concrete Repair 2013.

1.02 ADMINSTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Convene at project site seven calendar days prior to scheduled beginning of construction activities of this section to review section requirements.
 - 1. Require attendance by representatives of installer and other entities directly affecting, or affected by, construction activities of this section.
 - 2. Notify Architect four calendar days in advance of scheduled meeting date.

1.03 SUBMITTALS

- A. Product Data: Provide data on specified products, describing physical and performance characteristics; sizes, patterns and colors available.
- B. Selection Samples: Provide manufacturer's color charts illustrating full range of patterns and colors for each flooring material.
- C. Verification Samples: Manufacturer's standard size physical samples, on rigid backing, illustrating each selected pattern and color.
- D. Concrete Subfloor Test Report: Submit a copy of the moisture and alkalinity (pH) test reports.
- E. Manufacturer's Installation Instructions: Indicate special procedures, perimeter conditions requiring special attention, and application rate for each coat.
- F. Applicator's Qualification Statement.
- G. Field Quality Control Reports: Submit inspection reports of manufacturer's technical representative.
- H. Maintenance Data: Include maintenance procedures, recommended maintenance materials, procedures for stain removal, repairing surface, and suggested schedule for cleaning.

1.04 QUALITY ASSURANCE

- A. Applicator Qualifications: Company specializing in performing the work of this section; certified and approved by manufacturer in writing.
 - Approved by manufacturer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.05 MOCK-UPS

- A. Construct mock-up(s) of fluid applied flooring to serve as basis for evaluation of texture and workmanship.
 - 1. Number of Mock-Ups to be Prepared: One.
 - 2. Use same materials and methods for use in the work.
 - 3. Use approved design samples as basis for mock-ups.
 - 4. Locate where directed by Architect.
 - 5. Minimum Size: 48 inches by 48 inches.
- B. See Section 014000 Quality Requirements for additional requirements.
- C. Obtain approval of mock-up by Architect before proceeding with work.
- D. Approved mock-up may remain as part of the work.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Store resin materials in a dry, secure area.
- B. Store materials for three days prior to installation in area of installation to achieve temperature stability.

1.07 FIELD CONDITIONS

- A. Maintain minimum temperature in storage area of 55 degrees F.
- B. Store materials in area of installation for minimum period of 24 hours prior to installation.
- C. Maintain ambient temperature required by manufacturer 72 hours prior to, during, and 24 hours after installation of materials.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Fluid-Applied Flooring:
 - 1. Crossfield Products Corp.
 - 2. Dur-A-Flex, Inc.
 - 3. Elite Crete Systems.
 - 4. Key Resin Company.
 - Master Builders Solutions.
 - 6. Sherwin-Williams Company.
 - 7. Sika Corporation.
 - 8. Stonhard, Inc.
 - 9. Substitutions: See Section 016000 Product Requirements.

2.02 PERFORMANCE REQUIREMENTS

A. Performance Requirements: Where a specific Basis-of-Design value is indicated, minor variations in test numbers shall be permitted for comparable/substitute products at Architect's discretion.
1. Compressive Strength: [____] psi, when tested in accordance with ASTM C579 (Basis-of-

Design).

2. Abrasion Resistance: Maximum weight loss of [_____] mg, when tested in accordance

 Abrasion Resistance: Maximum weight loss of [____] mg, when tested in accordance with ASTM D4060 (Basis-of-Design).

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 3. Impact Resistance: No cracking, chipping or delamination, when tested with Gardner Impact Tester at 16 ft lbs.
- 4. Adhesion: Minimum 300 psi at concrete substrate failure, per ASTM D 4541.
- B. Critical Radiant Flux: Minimum of 0.45 watts/sq cm, when tested in accordance with ASTM F648
- C. Slip Resistance: Minimum dynamic coefficient of friction (DCOF) of 0.6, when tested in accordance with NFSI / ANSI B101 Standard.

2.03 FLUID-APPLIED FLOORING SYSTEMS

- A. Fluid-Applied Flooring Type [_____]: Epoxy, with aggregate.
 - 1. Aggregate: Silica sand.
 - 2. System Thickness: 15 mils, nominal, dry film thickness (DFT).
 - 3. Texture: Slip resistant.
 - 4. Sheen: Gloss.
 - 5. Color: As selected by Architect.
 - 6. Products:
 - a. Crossfield Products Corp.; Dex-O-Tex
 - b. Key Resin Company
 - c. Sherwin-Williams Company; Armorseal 100% Solids Epoxy: www.protective.sherwin-williams.com/#sle.
 - d. Stonhard; Stonclad: www.stonhard.com/#sle.

2.04 ACCESSORIES

- A. Subfloor Filler: Type recommended by fluid-applied flooring manufacturer.
- B. Primer: Type recommended by fluid-applied flooring manufacturer.
- C. Moisture Vapor Treatment: Where fluid-applied flooring and accessories are installed over concrete slabs, provide alkaline-resistant product designed to control excessive moisture vapor transmission through concrete slab, per the following:
 - 1. Products: Provide product approved by flooring manufacturer and complying with performance requirements below, equivalent to one of the following:
 - a. Duraamen Engineered Products, Inc.; Perdure MVT.
 - b. Maxxon Corporation; Maxxon MVP.
 - c. Tnemec Company Inc.; Epoxoprime MVT, Series 208.
 - 2. Performance Requirements:
 - a. Verify with flooring manufacturer that submitted product maintains compliance with all provisions of flooring manufacturer's warranty.
 - b. Low-VOC: Provide product with VOC content less than 15 g/L.
 - c. Bond Strength to Concrete: Minimum 400 psi per ASTM D 4541 (100% concrete failure).
 - d. Permeance: Maximum 0.1 perm per ASTM E 96, and 0.10 grains/hr/ft²/in-Hg, per ASTM F3010.
 - e. Applications: Provide MVT for all concrete slabs on-grade and lightweight concrete elevated slabs.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that subfloor surfaces are smooth and flat within the tolerances specified for that type of work and are ready to receive flooring.
- B. Verify that subfloor surfaces are dust-free and free of substances that could impair bonding of materials to subfloor surfaces.
- C. Cementitious Subfloor Surfaces: Verify that substrates are ready for fluid-applied flooring installation by testing for moisture and alkalinity (pH).
 - 1. Test as Follows: Perform one test in each installation area.
 - a. Alkalinity (pH): ASTM F710.
 - b. Internal Relative Humidity: ASTM F2170.
 - Moisture Vapor Emission: ASTM F1869.
 - 2. If test results are not within limits recommended by fluid-applied flooring manufacturer, apply moisture vapor treatment (MVT) in accordance with manufacturer's requirements. MVT.shall be provided per unit price and quantity allowance requirements.
- D. Verify that required floor-mounted utilities are in correct location.

3.02 PREPARATION

- Remove subfloor ridges and bumps. Fill low spots, cracks, joints, holes, and other defects with subfloor filler.
- B. Prepare concrete surfaces according to ICRI 310.2R, CSP 4, minimum, unless otherwise required by manufacturer's installation requirements..
- C. Apply, trowel, and float filler to achieve smooth, flat, hard surface. Grind irregularities above the surface level. Prohibit traffic until filler is cured.
- D. Vacuum clean substrate.
- E. Apply primer to surfaces required by flooring manufacturer.

3.03 INSTALLATION - FLOORING

- A. Apply in accordance with manufacturer's instructions.
- B. Apply each coat to minimum thickness required by manufacturer.
- C. Finish to smooth level surface.
- D. Install flooring to the center of cased openings, and into door openings such that the transition to other floor material will occur under the center of the door leaf. Where transitions occur to another flooring material, extend resinous flooring to suit transition.
- E. Cove at vertical surfaces.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements, for additional requirements.
- B. Provide services of manufacturer's technical representative to inspect for proper installation of fluid-applied flooring system and submit inspection report.

3.05 PROTECTION

A. Prohibit traffic on floor finish for minimum 48 hours after installation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

B. Barricade area to protect flooring until fully cured.

END OF SECTION 096700

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 099100 PAINTING

PART 1 GENERAL

1.01 SECTION INCLUDES

- Surface preparation.
- B. Field application of paints.
- C. Scope: Finish interior surfaces exposed to view, unless fully factory-finished and unless otherwise indicated. Specific items include (but are not limited to) the following:
 - Fire- and Smoke-Rated Wall Identification: Permanently label fire- and smoke-rated walls, partitions, and barriers per requirements of applicable building code, with the words "FIRE / SMOKE BARRIER PROTECT ALL OPENINGS", using stenciled lettering not less than 3 inches high and with minimum 0.375-inch strokes.
 - a. Locate lettering in concealed accessible floor, floor-ceiling plenums, and attic spaces, located no more than 15 feet from end of wall and at intervals not exceeding 30 feet. Locate directly inside of access doors or panels that provide access to rated walls. Do not paint walls where exposed to view except in support spaces (mechanical / electrical rooms and similar spaces).
 - 2. Refer to the life safety plans and partition schedule on the drawings for rated wall and partition locations.
 - 3. Both sides and edges of plywood backboards for electrical and telecom equipment before installing equipment.
 - 4. Elevator pit ladders.
 - 5. Prime surfaces to receive wall coverings.
 - 6. Mechanical and Electrical:
 - a. In finished areas, paint insulated and exposed pipes, conduit, boxes, insulated and exposed ducts, hangers, brackets, collars and supports, mechanical equipment, and electrical equipment, unless otherwise indicated.
 - b. In finished areas, paint shop-primed items.
 - Paint interior surfaces of air ducts and convector and baseboard heating cabinets that are visible through grilles and louvers with one coat of flat black paint to visible surfaces.
 - d. Paint dampers exposed behind louvers, grilles, and convector and baseboard cabinets to match face panels.

D. Do Not Paint or Finish the Following Items:

- 1. Items factory-finished unless otherwise indicated; materials and products having factory-applied primers are not considered factory finished.
- 2. Items indicated to receive other finishes.
- Items indicated to remain unfinished.
- 4. Fire rating labels, equipment serial number and capacity labels, bar code labels, and operating parts of equipment.
- 5. Stainless steel, anodized aluminum, bronze, terne-coated stainless steel, and lead items.
- 6. Marble, granite, slate, and other natural stones.
- 7. Floors, unless specifically indicated.
- 8. Ceramic and other tiles.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 9. Brick, architectural concrete, architectural precast, cast stone, and integrally colored plaster, fiberglass, or stucco.
- 10. Glass.
- 11. Acoustical materials, unless specifically indicated.
- 12. Concealed pipes, ducts, and conduits.

1.02 REFERENCE STANDARDS

- MPI (APSM) Master Painters Institute Architectural Painting Specification Manual Current Edition.
- B. SSPC-SP 1 Solvent Cleaning 2015, with Editorial Revision (2016).
- C. SSPC-SP 6 Commercial Blast Cleaning 2007.

1.03 SUBMITTALS

- Product Data: Provide complete list of products to be used, with the following information for each:
 - 1. Manufacturer's name, product name and/or catalog number, and general product category (e.g., "alkyd enamel").
 - Cross-reference to specified paint system(s) product is to be used in; include description of each system.

1.04 DELIVERY, STORAGE, AND HANDLING

- A. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.
- B. Container Label: Include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation, and instructions for mixing and reducing.
- C. Paint Materials: Store at minimum ambient temperature of 45 degrees F and a maximum of 90 degrees F, in ventilated area, and as required by manufacturer's instructions.

1.05 FIELD CONDITIONS

- A. Do not apply materials when surface and ambient temperatures are outside the temperature ranges required by the paint product manufacturer.
- B. Follow manufacturer's recommended procedures for producing best results, including testing of substrates, moisture in substrates, and humidity and temperature limitations.
- C. Do not apply materials when relative humidity exceeds 85 percent, at temperatures less than 5 degrees F above the dew point, or to damp or wet surfaces.
- Minimum Application Temperatures for Paints: 50 degrees F for interiors unless required otherwise by manufacturer's instructions.
- E. Provide lighting level of 80 ft candles measured mid-height at substrate surface.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Paints:
 - 1. Benjamin Moore.
 - 2. PPG Paints.
 - 3. Sherwin-Williams Company.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.02 PAINTS AND FINISHES - GENERAL

- A. Paints and Finishes: Ready-mixed, unless intended to be a field-catalyzed paint.
 - 1. Provide paints and finishes of a soft paste consistency, capable of being readily and uniformly dispersed to a homogeneous coating, with good flow and brushing properties, and capable of drying or curing free of streaks or sags.
 - Supply each paint material in quantity required to complete entire project's work from a single production run.
 - 3. Do not reduce, thin, or dilute paint or finishes or add materials unless such procedure is specifically described in manufacturer's product instructions.

2.03 ACCESSORY MATERIALS

- A. Accessory Materials: Provide primers, sealers, cleaning agents, cleaning cloths, sanding materials, and clean-up materials as required for final completion of painted surfaces.
- B. Patching Material: Latex filler.
- C. Fastener Head Cover Material: Latex filler.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces are ready to receive work as instructed by the product manufacturer.
- B. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially affect proper application.
- C. Test shop-applied primer for compatibility with subsequent cover materials.
- D. Measure moisture content of surfaces using an electronic moisture meter. Do not apply finishes unless moisture content of surfaces is below the following maximums:
 - 1. Gypsum Wallboard: 12 percent.

3.02 PREPARATION

- A. Clean surfaces thoroughly and correct defects prior to application.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Remove or repair existing paints or finishes that exhibit surface defects.
- D. Remove or mask surface appurtenances, including electrical plates, hardware, light fixture trim, escutcheons, and fittings, prior to preparing surfaces or finishing.
- E. Seal surfaces that might cause bleed through or staining of topcoat.
- F. Concrete:
 - Remove release agents, curing compounds, efflorescence, and chalk. Do not coat surfaces if moisture content or alkalinity of surfaces to be coated exceeds that permitted in manufacturer's written instructions.

G. Masonry:

- Remove efflorescence and chalk. Do not coat surfaces if moisture content, alkalinity of surfaces, or if alkalinity of mortar joints exceed that permitted in manufacturer's written instructions. Allow to dry.
- H. Gypsum Board: Fill minor defects with filler compound. Spot prime defects after repair.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

I. Galvanized Surfaces:

1. Remove surface contamination and oils and wash with solvent according to SSPC-SP 1.

J. Ferrous Metal:

- 1. Solvent clean according to SSPC-SP 1.
- 2. Remove rust, loose mill scale, and other foreign substances using methods recommended in writing by paint manufacturer and blast cleaning according to SSPC-SP 6 "Commercial Blast Cleaning". Protect from corrosion until coated.

3.03 APPLICATION

- A. Remove unfinished louvers, grilles, covers, and access panels on mechanical and electrical components and paint separately.
- B. Apply products in accordance with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual".
- C. Where adjacent sealant is to be painted, do not apply finish coats until sealant is applied.
- D. Do not apply finishes to surfaces that are not dry. Allow applied coats to dry before next coat is applied.
- E. Apply each coat to uniform appearance in thicknesses specified by manufacturer.
- F. Sand wood and metal surfaces lightly between coats to achieve required finish.
- G. Vacuum clean surfaces of loose particles. Use tack cloth to remove dust and particles just prior to applying next coat.
- H. Reinstall electrical cover plates, hardware, light fixture trim, escutcheons, and fittings removed prior to finishing.

3.04 CLEANING

A. Collect waste material that could constitute a fire hazard, place in closed metal containers, and remove daily from site.

3.05 PROTECTION

- A. Protect finishes until completion of project.
- B. Touch-up damaged finishes after Substantial Completion.

3.06 EXTERIOR PAINT SCHEDULE

- A. General: Provide the following Paint systems for the various substrates, as indicated. Dry film thickness is noted as "DFT." Provide compatibility test areas on existing painted substrates.
- B. Zinc-Coated or Zinc-rich Primer-Coated Metal with Direct to Metal ("DTM") Gloss Acrylic Enamel Finish: 2 topcoats of DTM gloss enamel over primer, with min. total DFT of 2.5 mils.
 - 1. Prime Coat (Tie-Coat): Lead-free, acrylic base interior/exterior galvanized metal primer, premium grade. Apply over shop primer.
 - a. Moore: HP04 Ultra Spec HP Acrylic Metal Primer.
 - b. PPG: 90-712 Pitt-Tech Int/Ext Primer/Finish Industrial Enamel.
 - c. S-W: B66 Pro-Cryl Universal Primer.
 - First and Second Coats: DTM Acrylic Gloss Enamel.
 - a. Moore: HP28 Ultra Spec HP Acrylic Gloss Enamel.
 - b. PPG: 90-1310 Pitt-Tech Plus Int/Ext High Gloss DTM Industrial Enamel.
 - c. S-W: B66W1050 Series Pro Industrial DTM Acrylic Coating (Gloss).

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- C. Field-Applied Coatings for Ferrous Metal (AESS): Aliphatic urethane system of intermediate coat and topcoat. Provide scheduled products for exposed steel fabrications indicated as AESS.
 - 1. Field Touch-up: Match moisture curing urethane zinc-rich shop primer.
 - 2. Intermediate Coat: Moisture curing urethane and micaceous iron oxide or epoxy.
 - Moore: Corotech V160 Epoxy Mastic Coating.
 - b. PPG: 95-245 Pitt-Guard Rapid Coat D-T-R Epoxy Coating.
 - c. S-W: Macropoxy 646 Fast Cure Epoxy, B58-600/B58v600.
 - 3. Top Coat: Aliphatic urethane at 2.0 3.0 mils DFT.
 - a. Moore: Corotech V500 Aliphatic Acrylic Urethane.
 - b. PPG: 95-812 Pitthane Ultra Gloss Urethane Enamel.
 - c. S-W: Corothane I Aliphatic Finish Coat B65.
- D. Coatings to Repaint Exterior Ferrous Metal: Aliphatic urethane topcoat system over surfacetolerant epoxy mastic. Provide to repaint existing exposed steel fabrications with extended weather exposure deterioration and surface rust.
 - 1. Preparation: Clean steel to SSPC SP-3 Power Tool Cleaning to remove all rust scale, mill scale and loose rust, oil, grease and other contaminants.
 - 2. Primer: Surface-tolerant fast curing polyamide epoxy (mastic). 5.0 10.0 mils DFT.
 - a. Moore: P45 Mastic Epoxy Gloss Coating.
 - b. PPG: 95-245 Pitt-Guard Rapid Epoxy Mastic SG.
 - c. S-W: Macropoxy 646 Fast Cure Epoxy.
 - 3. First and Second Top Coats: Aliphatic urethane at 3.0 4.0 mils DFT per coat
 - a. Moore: P74 Aliphatic Acrylic Urethane.
 - b. PPG: Pitthane High Build Urethane Enamels 95 -8800 series.
 - c. S-W: B65-300 Series / B60V30 Hi-Solids Polyurethane.
- E. Concrete: Acrylic latex satin finish, two finish coats over alkali-resistant primer with minimum total DFT of not less than 3.5 mils.
 - 1. Prime Coat: Exterior Acrylic weathered masonry sealer/primer.
 - a. Moore: 608 Ultra Spec Masonry Int/Ext 100% Acrylic Sealer/Primer.
 - b. PPG: 4-603 Perma-Crete Int/Ext Alkali Resistant Primer.
 - c. S-W: A24w8300, Loxon Concrete & Masonry Primer.
 - First and Second Finish Coats: Exterior 100% Acrylic Satin sheen; premium grade.
 - a. Moore: N401 Regal Select Exterior Paint High Build Low Lustre Finish.
 - b. PPG: 76-45 Sun-Proof Ext House & Trim, Satin.
 - c. S-W: A82 Series A-100 Exterior Latex Satin.
- F. Concrete Masonry Units: Acrylic latex satin finish, two finish coats over primer with minimum total DFT of not less than 3.5 mils.
 - 1. Prime Coat: Exterior Acrylic weathered masonry sealer/primer.
 - a. Moore: 571 Ultra Spec Hi-Build Masonry Block Filler.
 - b. PPG: 6-15 Speedhide Int/Ext Acrylic Masonry Block Filler.
 - c. S-W: A24W200 Loxon Block Surfacer.
 - 2. First and Second Finish Coats: Exterior 100% Acrylic Satin sheen; premium grade.
 - a. Moore: N401 Regal Select Exterior Paint High Build Low Lustre Finish.
 - b. PPG: 76-45 Sun-Proof Ext House & Trim, Satin.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- c. S-W: A 82 Series A-100 Exterior Latex Satin.
- G. Exterior Gypsum Soffit Board with Smooth Finish 100% Acrylic Coating: Top coat(s) for total DFT of 10.0 mils minimum over primer-sealer.
 - 1. Prime Coat (Tie-Coat): Bonding primer-sealer.
 - a. Moore: N023 Fresh Start All Purpose 100% Acrylic Int/Ex Latex Primer.
 - b. PPG: 6-9 Speedhide Exterior Wood Primer Oil.
 - c. S-W: B51-450, Multi-Purpose Primer.
 - First and Second Finish Coats: Exterior 100% Acrylic Satin sheen; premium grade.
 - a. Moore: N401 Regal Select Exterior Paint High Build Low Lustre Finish.
 - b. PPG: 76-45 Sun-Proof Ext House & Trim. Satin Latex 100% Acrylic.
 - c. S-W: A82 Series A-100 Exterior Latex Satin.
 - First and Second Finish Coats: Exterior 100% Acrylic Flat finish; premium grade.
 - a. Moore: N400 Regal Select Exterior Paint High Build Flat Finish.
 - b. PPG: 72-45 Sun-Proof Ext House & Trim. Flat Latex 100% Acrylic
 - c. S-W: A6 Series A-100 Exterior Latex Flat
- H. General Painted Wood and Plywood with Acrylic Latex Satin Finish: 2 finish coats over primer with total DFT not less than 3.5 mils.
 - 1. Prime Coat: Alkyd-based wood sealer/primer.
 - a. Ben Moore: 024 Fresh Start Multi-Purpose Oil Based Primer.
 - b. PPG: 6-9 Speedhide Exterior Wood Primer
 - c. S-W: Y24W8020 Exterior Oil Wood Primer.
 - 2. First and Second Finish Coats: Exterior 100% Acrylic Satin sheen; premium grade.
 - Moore: N401 Regal Select Exterior Paint High Build Low Lustre Finish.
 - b. PPG: 76-45 Sun-Proof Ext House & Trim, Satin.
 - c. S-W: A82 Series A-100 Exterior Latex Satin.
- Exterior Wood Dumpster Enclosure Siding and Trim with Solid Color Latex-Emulsion Stain: 2
 Finish coats.
 - 1. Stain Coat: Acrylic latex solid color stain.
 - a. Moore: 610 ArborCoat Exterior Stain Solid Ultra Flat.
 - b. Cabot: Cabot O.V.T. Solid Color Acrylic Stain.
 - c. PPG: Olympic Solid Color Acrylic Latex Base Stain.
 - d. S-W: A16, Woodscapes Exterior Solid Acrylic Stain.

3.07 INTERIOR PAINT SCHEDULE

- A. General: Provide the following paint systems for the various substrates, as indicated. Dry film thickness is noted as "DFT." Provide compatibility test areas on existing painted substrates.
- B. Concrete Masonry Units: Low-VOC Acrylic Satin Finish. 2 Coats over filler, with total DFT not less than 2.5 mils. (Provide for CMU except where "epoxy finish" is indicated.)
 - Filler Coat, 100% Acrylic. Apply filler coat at a rate to ensure complete coverage. Brush, spray or roller apply and back roll or squeegee for smooth, pinhole-free treatment.
 - a. Moore: 571 Ultra Spec Hi-Build Masonry Block Filler.
 - b. PPG: 16-90 Pitt Glaze WB Acrylic Interior Exterior Block Filler.
 - c. S-W: B42W46 Heavy Duty Block Filler. (PrepRite not acceptable)

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- Waterproofing Filler Coat Showers & Wet Applications: Cementitious resin or epoxy block filler applied by brush, spray or roller and back rolled or squeegeed for smooth, pinhole-free treatment.
 - a. Moore: P31 Waterborne Epoxy Block filler.
 - b. PPG: 95-217 Epoxy Ester Cementitious Waterproofing Block Filler.
 - c. S-W: B42W400/B42V401 Kem Cati-Coat HS Epoxy Filler/Sealer.
- 3. Bonding Primer (previously painted): Acrylic bonding primer for exceptional adhesion to hard, glossy surfaces. Test for adhesion. Brush, spray or roller apply and back roll.
 - a. Moore: Stix Bonding Primer.
 - b. PPG: 17-921 PPG Seal Grip Acrylic Universal Primer/Sealer.
 - c. S-W: B51W150 Extreme Bond Interior/Exterior Primer.
- 4. First & Second Finish Coats: Commercial Interior Low-VOC Acrylic Satin Finish. Provide for wall finishes unless directed otherwise.
 - a. Moore: N538 Ultra Spec 500 Interior Eggshell Finish.
 - b. PPG: 6-4300 Speedhide Zero VOC Interior Eggshell Latex.
 - c. S-W: B20-2600 ProMar 200 Zero VOC Interior Latex Eg-Shel.
- C. Concrete Masonry Units Semi-Gloss Water-Borne Epoxy Finish: 2 Coats over filler:
 - 1. Block Filler Coat: Acrylic-latex or as required by manufacturer for topcoat. Brush, spray or roller apply and back roll for smooth pinhole-free treatment.
 - a. Moore: 571 Ultra Spec Hi-Build Masonry Block Filler.
 - b. PPG: 6-15 Speedhide Int/Ext Acrylic Masonry Block Filler.
 - c. PPG: 16-90 Pitt-Glaze WB Int/Ext Block Filler Latex.
 - d. S-W: B42W46 Heavy Duty Interior/Exterior Block Filler.
 - 2. First and Second Coats: Two-component, semi-gloss water born polyamide epoxy enamel applied at a DFT of 1.5 to 4.0 mils per coat.
 - a. Moore: Corotech V400 Polyamide Epoxy Coating.
 - b. PPG: 98-100 Aguapon WB Water Base Epoxy Semi-Gloss.
 - c. S-W: B73V300 Pro Industrial Water Based Catalyzed Epoxy Hardener.
- D. Gypsum Board Systems with Latex Finish: Semi-gloss finish at walls and flat finish on ceilings except as indicated otherwise. Provide best commercial Low-VOC formulation with 0 VOC per EPA test method 24.
 - 1. Filler Coat: 0 VOC (per EPS test method 24) Latex Primer.
 - a. Moore: N534 Ultra Spec 500 Interior Latex Primer.
 - b. PPG: 6-4900 Speedhide Zero VOC Interior Latex Primer.
 - c. S-W: B28-2600 ProMar 200 Zero VOC Interior Latex Primer.
 - 2. First & Second Finish Coats: Interior Low-VOC Acrylic Satin Finish. (Low lustre/Satin = 25-45% @60°) Provide for wall finishes unless indicated otherwise.
 - a. Moore: N538 Ultra Spec 500 Interior Eggshell.
 - b. PPG: 6-4300 Speedhide Zero VOC Interior Eggshell Latex.
 - c. S-W: B20-2600 ProMar 200 Zero VOC Interior Latex Eg-Shell.
 - d. S-W: B24-2600 ProMar 200 Zero VOC Interior Latex Low Sheen.
 - 3. First & Second Finish Coats: Interior Low-VOC Acrylic Flat Finish. Provide for ceiling applications unless indicated otherwise.
 - a. Moore: N536 Ultra Spec 500 Interior Flat.
 - b. PPG: 6-4100 Speedhide Zero VOC Interior Latex Flat.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- S-W: B30-2600 ProMar 200 Zero VOC Interior Latex Flat.
- E. Gypsum Board Systems with Water-Borne Polyamide Epoxy Finish ("EPX"):
 - Filler Coat: Manufacturer's recommended primer.
 - a. Moore: 217 Fresh Start Alkyd Enamel Underbody.
 - b. PPG: 6-2 Speedhide Interior Latex Sealer.
 - c. S-W: B28W2600 ProMar 200 Zero VOC Primer.
 - 2. First and Second Coats: Two-component, water born polyamide epoxy enamel applied at a DFT of 1.5 to 4.0 mils per coat. Provide semi-gloss finish unless directed otherwise.
 - a. Moore: Corotech V440 Waterborne Amine Epoxy.
 - b. PPG: 98-100 Aquapon WB Water Base Epoxy Semi-Gloss.
 - c. S-W: B70 Series B60V25 Water Based Catalyzed Epoxy.
- F. Ferrous Metal with Latex Dry Fog Finish: One finish coat over primed exposed construction. Provide nominal 50 square foot sample area to test for paint compatibility with substrates.
 - 1. Prime Coat: (Acrylic or recommended VOC-compliant metal primer for surfaces not preprimed.) 2.0 mils DFT.
 - a. Moore: N110 Superkote 5000 DryFall latex Flat.
 - b. PPG: 90-712 Pitt-Tech Int/Ext Primer/Finish Industrial Enamel.
 - c. S-W: B66-310 Pro-Cryl Universal Primer.
 - Top Coat: All exposed structure as scheduled. Acrylic Dry Fog 3.0 mils DFT. Provide color finish as selected by Architect from manufacturer's full range.
 - a. Moore: N110 Superkote 5000 DryFall Latex Flat.
 - b. PPG: 6-724XI Series Speedhide Super Tech WB Int. Dry-Fog Flat Latex Flat.
 - S-W: B42 BW3 Waterborne Acrylic Dry Fall, Flat.
- G. Ferrous Metal: Semi-Gloss Direct to Metal ("DTM") Acrylic Enamel Finish: 2 Coats over primer, with total DFT not less than 2.5 mils.
 - 1. Prime Coat: Lead-free, acrylic Base Primer. Not required on shop primed items.
 - a. Moore: HP29 Ultra Spec HP DTM Acrylic Semi-Gloss.
 - b. PPG: 90-712 Pitt-Tech Int/Ext Primer/Finish Industrial Enamel.
 - c. S-W: B66 W1 DTM Acrylic Primer/Finish (or B66 W200).
 - 2. Bonding Primer (previously painted): Acrylic bonding primer designed for previously painted ferrous metal to ensure secure bond. Brush, spray or roller apply and back roll.
 - a. Moore: SXA-110 Insl-X Waterborne Bonding Primer.
 - b. PPG: 90-912 Pitt-Tech Plus DTM Industrial Primer.
 - c. S-W: B66A50 DTM Bonding Primer.
 - First and Second Coat: DTM Acrylic Semi-Gloss Enamel. (30-40 units @ 60°)
 - a. Moore: HP29 Ultra Spec HP DTM Acrylic Semi-Gloss.
 - b. PPG: 90-1210 Pitt-Tech Int/Ext Semi-Gloss DTM Industrial Enamel.
 - S-W: B66W1150 Series Pro Industrial DTM Acrylic Semi-Gloss Coating.
- H. Zinc-Coated Metal: Semi-Gloss Direct to Metal ("DTM") Acrylic Enamel Finish: 2 Coats over primer, with min. total DFT of 2.5 mils.
 - 1. Prime Coat: Lead-free, acrylic base interior galvanized metal primer, premium grade.
 - a. Moore: HP04 Ultra Spec HP Acrylic Metal Primer.
 - b. PPG: 90-712 Pitt-Tech Int/Ext Primer/Finish Industrial Enamel.
 - S-W: B66W1150 Series Pro Industrial DTM Acrylic Semi-Gloss Coating.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 2. First and Second Coats: DTM Acrylic Semi-Gloss Enamel. Same as for ferrous metal.
- I. Intumescent Mastic-Coated Metal: Semi-Gloss Direct to Metal ("DTM") Acrylic Enamel Finish as approved by intumescent coating manufacturer: 2 Coats, with min. total DFT of 2.5 mils.

END OF SECTION 099100

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 102113.19 PLASTIC TOILET COMPARTMENTS

PART 1 GENERAL

1.01 REFERENCE STANDARDS

 A. NFPA 286 - Standard Methods of Fire Tests for Evaluating Contribution of Wall and Ceiling Interior Finish to Room Fire Growth 2019.

1.02 SUBMITTALS

- A. Product Data: Provide data on panel construction, hardware, and accessories.
 - 1. Provide data for wall anchors for attachment of wall brackets.
 - 2. Provide data substantiating that door latch product complies with accessibility standards.
 - 3. Provide data indicating NFPA 286 testing and compliance.
- B. Shop Drawings: Indicate partition plan, elevation views, dimensions, details of wall supports, door swings.
 - 1. Include locations of plumbing fixtures and floor drains.
 - 2. Include accessible and ambulatory stalls, including stall and door clearances.
- C. Selection Samples: Submit color charts indicating manufacturer's full range of colors. Color charts shall indicate which colors are NFPA 286 compliant.
- D. Verification Samples: Submit manufacturer's physical samples of each selected color.
- E. Maintenance Data: Include recommended cleaning methods, cleaning materials, and stain removal methods. Describe cleaning materials detrimental to finish surfaces and hardware finish.

1.03 WARRANTY

- A. See Section 017800 Closeout Submittals, for additional warranty requirements.
- B. Provide 15 year manufacturer warranty against defects in material and workmanship, excluding abuse.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Solid Plastic Toilet Compartments:
 - 1. Accurate Partitions Corp.; ASI Group.
 - 2. General Partitions Mfg. Corp.
 - 3. Global Partitions; ASI Group.
 - 4. Scranton Products.

2.02 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: Provide HDPE panels tested per NFPA 286 and shown to meet the following criteria:
 - 1. During the 40 kW exposure, flames shall not spread to the ceiling.
 - 2. During the 160 kW exposure:
 - Flame shall not spread to the outer extremity of the sample on any wall or ceiling.
 - b. Flashover, as defined in NFPA 286, shall not occur.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 3. The peak rate of heat release throughout the NFPA 286 test shall not exceed 800 kW.
- 4. The total smoke released throughout the NFPA 286 test shall not exceed 1,000 m².

2.03 PLASTIC TOILET COMPARTMENTS

- A. Solid Plastic Toilet Compartments: Factory fabricated doors, pilasters, and divider panels made of solid molded high density polyethylene (HDPE), tested in accordance with NFPA 286; floor-mounted headrail-braced.
 - 1. Doors:
 - a. Thickness: 1 inch.
 - b. Width: 24 inch.
 - c. Width for Handicapped Use: 36 inch, out-swinging.
 - d. Height: 55 inch.
 - 2. Panels:
 - a. Thickness: 1 inch.
 - b. Height: 55 inch.
 - 3. Pilasters:
 - a. Thickness: 1 inch.
 - b. Width: As required to fit space; minimum 3 inch.
 - 4. Urinal Screens: Wall mount (no post/pilaster). Match panel material and thickness; 42 inch height, and depth as indicated on Drawings.

2.04 ACCESSORIES

- A. Material for Hardware and Accessories: Provide stainless steel or anodized aluminum as indicated, with satin finish. Where not indicated, Contractor may provide either material at its option. Zamac is not acceptable.
- B. Pilaster Shoes: Stainless steel, satin finish, 3 inches high; concealing floor fastenings.
- C. Head Rails: Extruded aluminum, anti-grip profile.
 - Size: Manufacturer's standard size.
- D. Wall and Pilaster Brackets: Anodized aluminum, minimum 0.125 inch wall thickness; continuous type; approximately 1 inch shorter than panel height.
- E. Attachments, Screws, and Bolts: Stainless steel, tamper proof type.
 - 1. For attaching panels and pilasters to brackets: Through-bolts and nuts; tamper proof.
- F. Hinges: Coordinate hinges with latch and keeper to provide emergency access.
 - 1. Continuous-Type (Piano) Hinges (Heavy-Duty): Adjustable for door close positioning, with 1/8-inch pin of matching material. Provide spring-loaded self-closing type with five (5) adjustable internal springs at accessible, barrier-free, and outswinging doors, and provide gravity type with cam knuckles that can be adjusted to hold doors open at inswinging doors. Provide hinge length 1 inch shorter than door height.
- G. Door Hardware: Coordinate latch and keeper with hinges to provide emergency access.
 - 1. Door Latch (Heavy-Duty): Slide type, cast stainless steel with minimum 0.150-inch thickness slide bar, latch knob welded to slide bar.
 - 2. Door Strike and Keeper with Rubber Bumper (Heavy-Duty): Cast stainless steel, minimum 2.5-inch high with minimum 0.125-inch wall thickness, with integral rubber bumper. Mount on pilaster in alignment with door latch.
 - 3. Provide a door pull on both sides of door for accessible and ambulatory compartments, in compliance with the ADA Standards for Accessible Design.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- H. Coat Hook with Rubber Bumper: One per compartment, mounted centered on inside face of door.
- Rubber Door Bumper: Mount in upper corner of latch side of outswinging doors.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify correct spacing of and between plumbing fixtures.
- C. Verify correct location of built-in framing, anchorage, and bracing.

3.02 INSTALLATION

- A. Install partitions secure, rigid, plumb, and level in accordance with manufacturer's instructions.
- B. Maintain 3/8 inch to 1/2 inch space between wall and panels and between wall and end pilasters.
- C. Attach panel brackets securely to walls using anchor devices.
- D. Attach panels and pilasters to brackets. Locate head rail joints at pilaster center lines.

3.03 TOLERANCES

- A. Maximum Variation From True Position: 1/4 inch.
- B. Maximum Variation From Plumb: 1/8 inch.

3.04 ADJUSTING

- A. Adjust and align hardware to uniform clearance at vertical edge of doors, not exceeding 3/16 inch.
- B. Adjust hinges to position doors in partial opening position when unlatched. Return out-swinging doors to closed position.
- C. Adjust adjacent components for consistency of line or plane.

END OF SECTION 102113.19

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 102600 WALL AND DOOR PROTECTION

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM D256 Standard Test Methods for Determining the Izod Pendulum Impact Resistance of Plastics 2010 (Reapproved 2018).
- B. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials 2022.
- C. ASTM F476 Standard Test Methods for Security of Swinging Door Assemblies 2014.

1.02 SUBMITTALS

- A. Product Data: Indicate physical dimensions, features, wall mounting brackets with mounted measurements, anchorage details, and rough-in measurements.
- B. Shop Drawings: Include plans, elevation, sections, and attachment details. Show design and spacing of supports for protective corridor handrails, required to withstand structural loads.
- Selection Samples: Provide manufacturer's color charts for each product and material requiring color selection.
- Verification Samples: Submit physical samples, manufacturer's standard size, for each selected color.
- E. Warranty Documentation: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.

1.03 DELIVERY, STORAGE, AND HANDLING

- Deliver wall and door protection items in original, undamaged protective packaging. Label items to designate installation locations.
- B. Protect work from moisture damage.
- C. Protect work from UV light damage.
- D. Do not deliver products to project site until areas for storage and installation are fully enclosed, and interior temperature and humidity are in compliance with manufacturer's recommendations for each type of item.
- E. Store products in either horizontal or vertical position, in compliance with manufacturer's instructions.

1.04 WARRANTY

- A. See Section 017800 Closeout Submittals, for additional warranty requirements.
- B. Provide five year manufacturer and installer warranty for wall and door protection items.
 - 1. Failures include, but are not limited to, the following:
 - Structural failures, internal connection failures, and/or detachment of rail system from substrates.
 - Deterioration of materials beyond that expected of normal use, as intended by manufacturer.

Wall and Door Protection 102600 - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Corner Guards:
 - 1. Babcock-Davis.
 - 2. Construction Specialties, Inc.
 - 3. Inpro.
 - 4. Koroseal Interior Products.
 - 5. Nystrom, Inc.
 - 6. Trim-Tex, Inc.

2.02 PERFORMANCE CRITERIA

A. Impact Strength: Unless otherwise noted, provide protection products and assemblies that have been successfully tested for compliance with applicable provisions of ASTM D256 and/or ASTM F476.

2.03 PRODUCT TYPES

- A. Corner Guards Surface Mounted:
 - 1. Basis-of-Design Product: Construction Specialties; Acrovyn VA Series.
 - Material: Polyethylene terephthalate (PET or PETG); PVC-free with full height extruded aluminum retainer.
 - Surface Burning Characteristics: Provide assemblies with flame spread index of 25 or less and smoke developed index of 450 or less, when tested in accordance with ASTM E84.
 - 4. Width of Wings: 1-1/2 inches.
 - 5. Corner: Square.
 - 6. Color: As selected from manufacturer's standard colors.
 - 7. Length: One piece, 6 feet (72 inches) in length.
- B. Adhesives and Primers: As recommended by manufacturer.

2.04 FABRICATION

A. Fabricate components with tight joints, corners and seams.

2.05 SOURCE QUALITY CONTROL

- A. See Section 014000 Quality Requirements, for additional requirements.
- B. Provide wall and door protection systems of each type from a single source and manufacturer.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that rough openings, concealed blocking, and anchors are correctly sized and located.
- B. Verify that field measurements are as indicated on drawings.
- C. Verify that substrate surfaces for adhered items are clean and smooth.
 - Test painted or wall covering surfaces for adhesion in inconspicuous area, as recommended by manufacturer. Follow adhesive manufacturer's recommendations for

Wall and Door Protection 102600 - 2

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

remedial measures at locations and/or application conditions where adhesion test's results are unsatisfactory.

D. Start of installation constitutes acceptance of project conditions.

3.02 INSTALLATION

- A. Install components in accordance with manufacturer's instructions, level and plumb, secured rigidly in position to supporting construction.
- B. Position corner guard with bottom of corner guard immediately above top of wall base.
- C. Position protective wall covering no less than 1 inch above finished floor to allow for floor level variation.
 - 1. Wainscot Installation: Establish a level line at the specified height for entire length of run. Install by aligning top of edge of covering with this line.
 - 2. Apply adhesive with 1/8 inch V-notch trowel to an area of wall surface that can be completed within cure time of the adhesive.
 - 3. Install trim pieces as required for a complete installation. Allow tolerance for thermal movement.
 - 4. Use a roller to ensure maximum contact with adhesive.
 - 5. At inside and outside corners cut covering sheets to facilitate installation of trim pieces or corner guards.

3.03 TOLERANCES

- A. Maximum Variation From Required Height: 1/4 inch.
- B. Maximum Variation From Level or Plane For Visible Length: 1/4 inch.

3.04 CLEANING

- A. See Section 017419 Construction Waste Management and Disposal, for additional requirements.
- B. Clean wall and door protection items of excess adhesive, dust, dirt, and other contaminants.

END OF SECTION 102600

Wall and Door Protection 102600 - 3

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 102800 TOILET AND BATH ACCESSORIES

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ADA Standards Americans with Disabilities Act (ADA) Standards for Accessible Design 2010.
- B. ASTM A269/A269M Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service 2015a (Reapproved 2019).
- C. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process 2020.
- D. ASTM A666 Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar 2015.
- E. ASTM C1036 Standard Specification for Flat Glass 2021.
- F. ASTM C1048 Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass 2018.
- G. ASTM C1503 Standard Specification for Silvered Flat Glass Mirror 2018.
- H. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials 2021a.
- I. ASTM G21 Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi 2015, with Editorial Revision (2021).

1.02 ADMINISTRATIVE REQUIREMENTS

A. Coordinate the work with the placement of internal wall reinforcement and reinforcement of toilet partitions to receive anchor attachments.

1.03 SUBMITTALS

- A. Product Data: Submit data on accessories describing size, finish, details of function, and attachment methods.
- B. Setting Drawings: For cutouts required in other work; include templates, substrate preparation instructions, and directions for preparing cutouts and installing anchoring devices.
- C. Maintenance Data: For each type of accessory, to include in maintenance manual per Section 017800 Closeout Submittals. Include list of replacement parts and service recommendations.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Commercial Toilet, Shower, and Bath Accessories:
 - 1. A&J Washroom Accessories, Inc.
 - 2. American Specialties, Inc.
 - 3. Bobrick Washroom Equipment.
 - 4. Bradley Corporation.
- B. Under-Lavatory Pipe Supply Covers:
 - 1. Plumberex Specialty Products, Inc.
 - 2. Truebro; IPS Corporation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- C. Electric Hand/Hair Dryers:
 - 1. Dyson.
 - 2. Excel Dryer.
 - 3. World Dryer Corporation.

2.02 MATERIALS

- A. Accessories General: Shop assembled, free of dents and scratches and packaged complete with anchors and fittings, steel anchor plates, adapters, and anchor components for installation.
- B. Keys: Provide 6 master/universal keys, minimum, to Owner.
- C. Stainless Steel Sheet: ASTM A666, Type 304.
- D. Stainless Steel Tubing: ASTM A269/A269M, Grade TP304 or TP316.
- E. Galvanized Sheet Steel: Hot-dipped galvanized steel sheet, ASTM A653/A653M, with G90/Z275 coating.
- F. Mirror Glass: Annealed float glass, ASTM C1036 Type I, Class 1, Quality Q2, with silvering, protective and physical characteristics complying with ASTM C1503.
- G. Fasteners, Screws, and Bolts: Hot dip galvanized; tamper-proof; security type.
 - 1. Provide mechanical attachment of all accessories. Use of adhesive or double-side tape is not acceptable.

2.03 FINISHES

A. Stainless Steel: Satin finish, unless otherwise noted.

2.04 TOILET ACCESSORIES SCHEDULE, GENERAL

A. General: The following products make reference to the designations indicated on the Toilet Accessories Schedule, Toilet Assemblies, and toilet room plans on the drawings; herein designated as "TA-x".

2.05 COMMERCIAL TOILET ACCESSORIES

- A. Basis-of-Design: Bradley Corporation for all toilet accessories which model numbers are listed.
 - 1. Grab Bars (TA-A, B, & C): Stainless steel, smooth surface.
 - a. Standard Duty Grab Bars:
 - 1) Push/Pull Point Load: 250 pound-force, minimum.
 - Dimensions: 1-1/4 inch outside diameter, minimum 0.05 inch wall thickness, concealed flange mounting, 1-1/2 inch clearance between wall and inside of grab bar.
 - 3) Finish: Satin.
 - Length and Configuration: As indicated on drawings.
 - 5) Products:
 - (a) American Specialties, Inc.
 - (b) Bobrick Washroom Equipment, Inc.
 - (c) Bradley Corporation; 832 Series
 - 2. Toilet Paper Dispenser (TA-D): Single roll, surface-mounted, stainless steel, satin finish unit with tumbler lock.
 - a. Products:
 - 1) American Specialties, Inc.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 2) Bobrick Washroom Equipment, Inc.
- 3) Bradley Corporation; Model 5241.
- 3. Sanitary Napkin Disposal Unit (TA-E): Stainless steel, surface-mounted, self-closing door, with full-length stainless steel piano-type hinge, removable receptacle.
 - a. Products:
 - 1) American Specialties, Inc.
 - 2) Bobrick Washroom Equipment, Inc.
 - 3) Bradley Corporation; Model 4722-15
- 4. Soap Dispenser (TA-F): Liquid soap dispenser, wall-mounted, surface, with stainless steel cover and vertical stainless steel tank and working parts; battery box with light indicator, and window gauge refill indicator, tumbler lock.
 - a. Minimum Capacity: 25 ounces.
 - b. Products:
 - 1) American Specialties, Inc.
 - Bobrick Washroom Equipment, Inc.
 - Bradley Corporation; Model 6A00-11.
- 5. Mirrors (TA-G): Stainless steel framed, 1/4 inch thick annealed float glass; ASTM C1036.
 - Annealed Float Glass: Silvering, protective and physical characteristics in compliance with ASTM C1503.
 - b. Frame: 0.05 inch angle shapes, with mitered and welded and ground corners, and tamperproof hanging system; satin finish.
 - c. Products:
 - 1) American Specialties, Inc.
 - 2) Bobrick Washroom Equipment, Inc.
 - Bradley Corporation: Model 780-1836.
- 6. Paper Towel Dispenser (TA-R): Folded paper type, stainless steel, surface-mounted, with viewing slots on sides as refill indicator and tumbler lock.
 - a. Capacity: 300 C-fold minimum.
 - b. Products:
 - 1) American Specialties, Inc.
 - 2) Bobrick Washroom Equipment, Inc.
 - 3) Bradley Corporation; Model 250-15.
- 7. Robe Hook (TA-T): Heavy-duty stainless steel, double-prong, rectangular-shaped bracket and backplate for concealed attachment, bright polished finish. Provide one centered on interior face of door of all single-user toilet rooms; verify final mounting locations with Architect in field.
 - a. Products (Double-Prong):
 - 1) American Specialties, Inc.
 - 2) Bobrick Washroom Equipment, Inc.
 - 3) Bradley Corporation; Model 912.

2.06 UNDER-LAVATORY PIPE AND SUPPLY COVERS

- A. Under-Lavatory Pipe and Supply Covers:
 - 1. Insulate exposed drainage piping, including hot, cold, and tempered water supplies under lavatories or sinks to comply with ADA Standards.
 - 2. Exterior Surfaces: Smooth non-absorbent, non-abrasive surfaces.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- 3. Construction: 1/8 inch flexible PVC.
 - a. Surface Burning Characteristics: Flame spread index of 25 or less and smoke developed index of 450 or less, when tested in accordance with ASTM E84.
 - b. Microbial and Fungal Resistance: Comply with ASTM G21.
- 4. Color: White.
- 5. Fasteners: Reusable, snap-locking fasteners with no sharp or abrasive external surfaces.
- 6. Products:
 - a. Plumberex Specialty Products, Inc; Plumberex Trap Gear.
 - b. Truebro; IPS Corporation; Lav Guard 2.

2.07 ELECTRIC HAND/HAIR DRYERS

- A. Electric Hand Dryers: Traditional fan-in-case type, with downward fixed nozzle.
 - Operation: Automatic, sensor-operated on and off.
 - 2. Mounting: Surface mounted.
 - 3. Cover: Plastic.
 - a. Tamper-resistant screw attachment of cover to mounting plate.

2.08 UTILITY ROOM ACCESSORIES

- A. Combination Utility Shelf/Mop and Broom Holder: 0.05 inch thick stainless steel, Type 304, with 1/2 inch returned edges, 0.06 inch steel wall brackets.
 - 1. Drying rod: Stainless steel, 1/4 inch diameter.
 - 2. Hooks: Three, 0.06 inch stainless steel rag hooks at shelf front.
 - 3. Mop/broom holders: Four spring-loaded rubber cam holders at shelf front.
 - 4. Length: 36 inches.
 - 5. Products:
 - a. American Specialties, Inc.; Model 1315-4.
 - b. Bobrick Washroom Equipment, Inc.; Model B-224 x 36.
 - c. Bradley Corporation; Model 9984.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify exact location of accessories for installation.
- C. For electrically-operated accessories, verify that electrical power connections are ready and in the correct locations.

3.02 INSTALLATION

- Install accessories in accordance with manufacturers' instructions in locations indicated on drawings.
- B. Install plumb and level, securely and rigidly anchored to substrate.
- C. Mounting Heights: As required by accessibility regulations, unless otherwise indicated.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.03 PROTECTION

A. Protect installed accessories from damage due to subsequent construction operations.

END OF SECTION 102800

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 104400 FIRE PROTECTION SPECIALTIES

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. FM (AG) FM Approval Guide current edition.
- B. NFPA 10 Standard for Portable Fire Extinguishers 2022.
- C. UL (DIR) Online Certifications Directory Current Edition.

1.02 SUBMITTALS

- A. Product Data: Provide extinguisher operational features, extinguisher ratings and classifications, color and finish, anchorage details, and trim and door panel styles.
- B. Shop Drawings: Indicate locations of cabinets and cabinet physical dimensions.
- C. Maintenance Data: Include test, refill or recharge schedules and re-certification requirements.

1.03 FIELD CONDITIONS

- A. Do not install extinguishers when ambient temperature may cause freezing of extinguisher ingredients.
- B. Coordinate rough opening sizes to ensure cabinet locations meet ADA mounting requirements.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Fire Extinguishers and Cabinets:
 - 1. Activar Construction Products Group, Inc. JL Industries.
 - 2. Amerex Corporation.
 - 3. Ansul, a Tyco Business.
 - 4. Babcock-Davis.
 - 5. Badger Fire Protection.
 - 6. Buckeye Fire Equipment Company.
 - 7. Fire-End & Croker Corporation.
 - 8. Kidde, a unit of United Technologies Corp.
 - 9. Modern Metal Products; Div of Technico.
 - 10. Larsen's Manufacturing Co.
 - 11. MOON American.
 - 12. Nystrom, Inc.
 - 13. Oval Brand Fire Products.
 - 14. Potter-Roemer.
 - 15. Pyro-Chem, a Tyco Business.
 - 16. Strike First Corporation of America.

2.02 FIRE EXTINGUISHERS

A. Fire Extinguishers - General: Comply with product requirements of NFPA 10 and applicable codes, whichever is more stringent.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

- Provide extinguishers labeled by UL (DIR) or FM (AG) for purpose specified and as indicated.
- B. Multipurpose Dry Chemical Type Fire Extinguishers: Carbon steel tank, with pressure gauge.
 - 1. Class: 4-A: 60-B:C.
 - 2. Size: 10 pound.
 - 3. Finish: Baked polyester powder coat, color as selected.
 - 4. Temperature range: Minus 40 degrees F to 120 degrees F.
- C. Wet Chemical Type Fire Extinguishers: Stainless steel tank, with pressure gauge.
 - Class: K type.
 - 2. Size: 1.6 gallons.
 - 3. Temperature range: Minus 20 degrees F to 120 degrees F.

2.03 FIRE EXTINGUISHER CABINETS

- A. Cabinet Construction: Non-fire rated.
 - Formed cold-rolled steel sheet; minimum 0.036 inch thick base metal.
 - Available Products: One of the following, or comparable product by manufacturer from list above:
 - a. J.L. Industries/Activar; Ambassador Series.
 - b. Larsen's Manufacturing Co.; Model 2409-R2.
 - c. Potter-Roemer; Model 1700 Series.
- B. Cabinet Configuration: Recessed type.
 - 1. Size to accommodate extinguisher(s) and accessories indicated.
 - 2. Provide cabinet enclosure with right angle inside corners and seams, and with formed perimeter trim and door stiles.
 - 3. Trim Type: One piece trim and door frame, returned to wall surface. Flat edge trim; as standard with manufacturer.
 - 4. Door Glazing Style: Vertical duo, configuration as standard with manufacturer.
- C. Door: Minimum 0.036 inch metal thickness, reinforced for flatness and rigidity with nylon catch. Hinge doors for 180 degree opening with continuous piano hinge.
- D. Door Glazing: Tempered glass, clear, 1/8 inch thick, and set in resilient channel glazing gasket.
- E. Cabinet Mounting Hardware: Appropriate to cabinet, with pre-drilled holes for placement of anchors.
- F. Operating Hardware: Manufacturer's standard for cabinet type; continuous door hinge allowing 180 degree opening, with ADA-compliant door latch either surface mounted or flush inset into door panel, with cam or friction latch operation.
- G. Fabrication: Weld, fill, and grind components smooth.
- H. Finish of Cabinet Exterior Trim and Door: Baked enamel, color as selected.
- I. Finish of Cabinet Interior: White colored enamel.

2.04 ACCESSORIES

- A. Extinguisher Brackets: Formed steel, chrome-plated or baked-enamel finish.
- B. Lettering: "FIRE EXTINGUISHER" decal, or vinyl self-adhering, pre-spaced lettering in accordance with authorities having jurisdiction (AHJ).

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1. Apply vertically to door of fire extinguisher cabinets, and apply to wall surface at bracket mounted extinguishers.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify rough openings for cabinet are correctly sized and located.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install cabinets plumb and level in wall openings, no greater than 48 inches from finished floor to top of handle.
- C. Install mounting brackets at 44 inches above finish floor.
- D. Secure rigidly in place.
- E. Place extinguishers and accessories in cabinets and on wall brackets.
- F. Adjust cabinet doors after installation to ensure smooth operation.

3.03 PROTECTION AND CLEANING

- A. Protect fire extinguishers, fire extinguisher cabinets, and accessories from damage until Substantial Completion.
- B. Provide touchup to damaged finishes; replace items that cannot be satisfactorily repaired or refinished.

END OF SECTION 104400

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 107300 PROTECTIVE COVERS

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. AAMA 2604 Voluntary Specification, Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels (with Coil Coating Appendix) 2022.
- B. ASCE 7 Minimum Design Loads and Associated Criteria for Buildings and Other Structures Most Recent Edition Cited by Referring Code or Reference Standard.
- C. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes 2021.
- D. ASTM B221M Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric) 2021.
- E. ASTM C1107/C1107M Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink) 2020.
- F. AWS D1.2/D1.2M Structural Welding Code Aluminum 2014, with Errata (2020).

1.02 SUBMITTALS

- A. Metal Product Data: Product data sheets, including material descriptions and finishes, and preparation instructions and recommendations.
- B. Shop Drawings: Indicate profiles, sizes, connection attachments, footings, anchorage, size and type of fasteners, accessories and locations.
 - 1. Shop drawings shall be project specific; manufacturer's standard details are not acceptable.
- C. Selection Samples: Manufacturer's color charts for metal components.
- D. Verification Samples: Manufacturer's standard size physical samples, representing actual material and finish of exposed metal, for each color selected by Architect.
- E. Design Data: Submit comprehensive structural analysis of design for the specified loads. Stamp and sign calculations by professional engineer.
- F. Designer's qualification statement.
- G. Manufacturer's qualification statement.
- H. Installer's qualification statement.

1.03 QUALITY ASSURANCE

A. Designer Qualifications: Perform design under direct supervision of Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.

1.04 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Manufacturer's Warranty: Provide standard 1-year warranty covering all material deterioration, structural failure, and installation defect.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

C. Finish Warranty: Provide 5-year manufacturer warranty against excessive degradation of factory-applied finishes. Include provision for replacement of units with excessive fading, chalking, or flaking.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Basis-of-Design (Column Supported): Mapes Architectural Products; Post Supported Walkway Canopy.
- B. Acceptable Comparable Manufacturers:
 - 1. Architectural Fabrication, Inc.
 - 2. Dittmer Architectural Aluminum.
 - 3. Mitchell Metals.
 - 4. Perfection Architectural Systems, Inc.
 - 5. Superior Mason Products, LLC.
 - 6. Tennessee Valley Metals.

2.02 PROTECTIVE COVERS - GENERAL

- A. Design Criteria: Design and fabricate to resist gravity, wind, snow, ponding water, weather exposure, seismic, and other structural loads without failure, damage, or permanent deflection in accordance with ASCE 7, applicable building code, and as indicated on Drawings.
 - 1. Structural Design:
 - Post-Supported: Coordinate foundations and footing design with Division 3 Section
 "Cast-in-Place Concrete" and with Structural Drawings.
 - 2. Thermal Movement: Design protective covers to accommodate thermal movement caused by ambient temperature range of 120 degrees F and surface temperature range of 180 degrees F without buckling, failure of joint seals, undue stress on fasteners or other detrimental effects on assembly components.
- B. Configuration: Column layout, dimensions, clearances, and design as indicated on drawings.
 - Drainage Concept (Post Supported): Water collected in decking conducted into perimeter drain beams and discharged through columns. Discharge water either at grade level with diverter plates and column cutouts, or coordinate with subdrainage installer for connection into underground subdrainage system, as indicated on Drawings.
- C. Provide a complete system ready for erection at project site.
- D. Shop fabricate to the greatest extent possible; disassemble if necessary for shipping.

2.03 PROTECTIVE COVERS - ASSEMBLY

- A. Description: Flat top metal framework with metal covering supported by metal columns or hanger-rod assembly, as indicated.
- B. Column Anchorage: Column embedded in concrete footing. Provide column sleeves or Styrofoam blockouts for presetting into concrete formwork.
- C. Framework: Aluminum.
- D. Covering Materials:
 - Manufacturer's standard interlocking extruded aluminum decking modules.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.04 COMPONENTS

- A. Components for Post-Supported Protective Covers:
 - Columns: Extruded aluminum.
 - a. Type: Box tube column.
 - Cross-Section: 4 inches by 4 inches unless otherwise indicated, or unless larger column size is required due to structural engineering analysis. Minimum wall thickness of 0.125 inch.
 - c. Grout Key: Provide two 1-1/2 inch diameter holes on opposite sides in column base.
 - 2. Beams: Extruded aluminum; minimum wall thickness 0.125-inch.
 - a. Style: U-shaped drain beams.
 - b. Beam Depth: 7 inches (per basis-of-design).
 - 3. Extruded Aluminum Decking: Self-flashing, interlocking sections; minimum 0.078-inch thick.
 - a. Deck Profile: Manufacturer's standard deck section for corrugated soffit profile; size deck depth for structural spacing indicated.
 - 4. Fascia: Extruded aluminum; height per manufacturer's standard profile; minimum 0.125-inch thickness.
 - 5. Wall Attachment for Cantilever Type Post-Supported Canopies: Provide threaded rod anchors, extending fully through exterior wall. Provide integral eyebolt, "U" bracket, or manufacturer's standard clevis assembly at rod attachment anchors for hanger rod attachment. At all through anchors, provide galvanized steel compression sleeves, sized to wall cavity and cladding depth, and additional construction as needed to prevent transferring structural loads onto veneer/cladding. All loads shall transfer to structural "backup" wall.
 - a. The structural system above is per the Basis-of-Design product indicated. Manufacturer may submit an alternate pre-engineered structural system, provided the system complies with other requirements of this section and is capable of supporting loads from the primary wall structure.
- B. Exposed Framing Fasteners: Flush countersunk stainless steel screws or bolts; consistent with design of system and acceptable to manufacturer.
 - 1. Decking Fasteners: Stainless steel with neoprene washers.
 - 2. Finish exposed fasteners to match metal framing.
- C. Flashings: Metal and finish matching system framing components, with thickness as recommended by manufacturer for conditions encountered.

2.05 MATERIALS

- A. Aluminum:
 - Aluminum Extrusions: Alloy and temper 6063-T5, 6063-T6, or 6061-T6 members complying with ASTM B221 (ASTM B221M), with minimum thickness 1/8 inch for structural members and 1/16 inch for nonstructural members.
- B. Concrete for Footings: Refer to Division 3 Section "Cast-in-Place Concrete."
- C. Non-Shrink Cementitious Grout: Premixed compound consisting of non-metallic aggregate, cement, water reducing and plasticizing agents.
 - 1. Grout: Comply with ASTM C1107/C1107M.
- D. Bituminous Coating: ASTM D 1187 asphaltic coating or comparable protective coating to prevent corrosion between materials. Building felt is not acceptable.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

2.06 FABRICATION - METAL COMPONENTS

- A. Fit and shop assemble components in largest practical sizes, for delivery to site.
- B. Fabricate components with joints tightly fitted and secured.
- C. Provide notches, cut outs, and internal deflectors in members as noted to act as internal water drainage system.
- D. Weld aluminum members in accordance with AWS D1.2/D1.2M.
- E. Exposed Fastenings: Unobtrusively located; consistent with design of component, except where specifically noted otherwise.
- F. Supply components required for anchorage of framing. Fabricate anchors and related components of same material and finish as framing, except where specifically noted otherwise.
- G. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.
- H. Accurately form components to suit each other and to building structure.

2.07 FINISHES

- A. High Performance Organic Coatings: AAMA 2604, multiple coats, thermally cured fluoropolymer system.
- B. Finish Color: As selected by Architect from manufacturer's standard range.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine substrates and site area for conditions that might prevent satisfactory installation.
- B. Verify that foundation, electrical utilities, and placed anchors are in correct position.
- C. Verify that bearing surfaces are ready to receive this work.
- D. Do not proceed with installation until conditions are satisfactory.

3.02 PREPARATION

- Supply items required to be cast into concrete with setting templates for installation of work in other sections.
- B. Concrete Foundations/Footings: Coordinate with and provide column sleeves or Styrofoam blockouts to the concrete installer to ensure foundations comply with manufacturer's requirements.

3.03 INSTALLATION - FRAMING

- A. Install in accordance with manufacturer's instructions.
- B. Install components plumb and level, accurately fitted, free from distortion or defects.
- C. Post Supported Canopies: Anchor columns in concrete foundations with column sleeves or preset Styrofoam blockout locations. Insert columns into foundation space and fill remaining annular space between concrete and columns with non-shrink cementitious grout. Wipe off surplus anchoring material, provide 1/8-inch build up at column and slope smoothly away from column. Seal anchoring material when required by grout manufacturer's installation instructions.
- D. Protective Coating: Provide a protective coating to separate aluminum surfaces from masonry, concrete or cementitious materials, and dissimilar metals.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

3.04 INSTALLATION - METAL COVERING

- A. Install in accordance with manufacturer's instructions.
- B. Fasten metal decking to metal support members, aligned level and plumb.
- C. Install fascia panels, trim, and flashing.
- D. Separate dissimilar metals using concealed bituminous paint.
- E. Touch-up damaged finish coating using material provided by manufacturer to match original coating.

3.05 TOLERANCES

- A. Maximum Variation from Plumb, Level, or Line: 1/8 inch per 10 feet, or 3/8 inch total in overall dimension.
- B. Alignment of Two Adjoining Members Abutting in Plane: Within 1/16 inches.

3.06 CLEANING

- A. See Section 017000 Execution and Closeout Requirements for additional requirements.
- B. Clean all exposed surfaces after installation.

3.07 PROTECTION

- A. Touch-up, repair, or replace damaged components before Date of Substantial Completion.
- B. Protect protective covers after installation to prevent damage due to other work until Date of Substantial Completion.

END OF SECTION 107300

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

SECTION 122400 WINDOW SHADES

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM G21 Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi 2015, with Editorial Revision (2021).
- B. NFPA 70 National Electrical Code Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- C. NFPA 701 Standard Methods of Fire Tests for Flame Propagation of Textiles and Films 2023.
- D. UL 325 Standard for Door, Drapery, Gate, Louver, and Window Operators and Systems Current Edition, Including All Revisions.

1.02 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Convene one week prior to commencing work related to products of this section; require attendance of affected installers.
- B. Sequencing:
 - Do not fabricate shades until field dimensions for each opening have been taken with field conditions in place.
 - 2. Do not install shades until final surface finishes and painting are complete.

1.03 SUBMITTALS

- A. Product Data: Provide manufacturer's standard catalog pages and data sheets, including materials, finishes, fabrication details, dimensions, profiles, mounting requirements, and accessories.
- B. Shop Drawings: Include shade schedule indicating size, location and keys to details, head, jamb and sill details, mounting dimension requirements for each product and condition, and operation direction.
- C. Source Quality Control Submittals: Provide test reports indicating compliance with specified fabric properties.
- D. Selection Samples: Include fabric samples in full range of available colors and patterns.
- E. Verification Samples: Minimum size 6 inches square, representing actual materials, color and pattern.
- F. Operation and Maintenance Data: List of all components with part numbers, sources of supply, and operation and maintenance instructions; include copy of shop drawings.

1.04 QUALITY ASSURANCE

A. Installer Qualifications: Authorized installation representative of fabricator/manufacturer.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Deliver shades in manufacturer's unopened packaging, labeled to identify each shade for each opening.
- B. Handle and store shades in accordance with manufacturer's recommendations.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

1.06 FIELD CONDITIONS

A. Do not install products under environmental conditions outside manufacturer's absolute limits.

1.07 WARRANTY

- A. See Section 017800 Closeout Submittals, for additional warranty requirements.
- B. Provide manufacturer's warranty from Date of Substantial Completion, covering the following minimum terms:
 - 1. Electric Motors and Components: 5 years, minimum.
 - 2. Manual Operating Mechanism / Clutch: 10 years, minimum (excludes bead chain).
 - 3. Fabric: 10 years, minimum.
 - 4. Balance of Shade Hardware and Non-Operating Materials and Components: 25 years, minimum.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Interior Manually Operated Roller Shades:
 - 1. Draper, Inc; Clutch Operated FlexShade.
 - 2. Hunter Douglas Architectural; RB500 Manual Roller Shades.
 - 3. Lutron Electronics Co., Inc; Contract Roller Manual Roller Shades.
 - 4. MechoShade Systems LLC; Mecho/5 System.
 - 5. WT Shade; HeliaRise.
 - 6. Substitutions: See Section 016000 Product Requirements.
- B. Interior Motorized Roller Shades, Motors and Motor Controls:
 - Draper, Inc; Motorized FlexShade.
 - 2. Hunter Douglas Architectural; RB500 Motorized Roller Shades.
 - 3. Lutron Electronics Co., Inc; Contract Roller Motorized Roller Shades.
 - 4. MechoShade Systems LLC; Electroshade.
 - 5. WT Shade; MotoRise.
 - 6. Substitutions: See Section 016000 Product Requirements.
- C. Source Limitations: Provide products produced by a single manufacturer and obtained from a single supplier.

2.02 ROLLER SHADES

- A. General:
 - Provide shade system components that are easy to remove or adjust without removal of mounted shade brackets.
 - 2. Provide shade system that operates smoothly when shades are raised or lowered.
 - 3. Motorized Shades: Motor system housed inside roller tube, controlling shade movement via motor controls indicated; listed or recognized to UL 325.
 - a. Comply with NFPA 70.
 - b. Electrical Components: Listed, classified, and labeled as suitable for the purpose intended. Where applicable, system components to be FCC compliant.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

c. Motors: Size and configuration as recommended by manufacturer for the type, size, and arrangement of shades to be operated; integrated into shade operating components and concealed from view; fully compatible with controls to be installed.

B. Roller Shades:

- Description Interior Roller Shades: Single roller, manually operated fabric window shade system complete with mounting brackets, roller tubes, hembars, hardware, and accessories.
 - a. Drop Position: Regular roll.
 - b. Roll Direction: Roll down, closed position is at window sill.
 - c. Mounting: Window jamb mounted inside, between jambs.
 - d. Size: As indicated on drawings for rough opening sizes; field verify rough openings prior to fabrication.
- 2. Brackets and Mounting Hardware: As recommended by manufacturer for mounting indicated and to accommodate shade fabric roll-up size and weight.
- 3. Roller Tubes: As required for type of shade operation.
 - a. Material: Extruded aluminum, clear anodized finish or electrogalvanized/epoxy primed steel, as standard with manufacturer.
 - b. Size: As recommended by manufacturer; selected for suitability for installation conditions, span, and weight of shades.
 - Fabric Attachment: Utilize extruded channel in tube to accept vinyl spline welded to fabric edge.
- 4. Hembars: Designed to maintain bottom of shade straight and flat.
 - a. Style: Full wrap fabric covered bottom bar, flat profile with heat sealed closed ends.
- Manual Operation for Interior Shades:
 - Clutch Operator: Manufacturer's standard material and design, permanently lubricated.
 - Drive Chain: Continuous loop beaded ball chain, 95 pounds minimum breaking strength. Provide upper and lower limit stops.
- 6. Accessories:
 - a. Fascia: Extruded aluminum, size as required to conceal shade mounting, attachable to brackets without exposed fasteners; clear anodized finish.
 - Fasteners: Noncorrosive, and as recommended by shade manufacturer.

2.03 SHADE FABRIC

- A. Fabric: Nonflammable, color-fast, impervious to heat and moisture, and able to retain its shape under normal operation.
 - 1. Manufacturers:
 - a. Lutron Electronics Co., Inc; Basketweave 27 1%.
 - b. Mermet Corporation; E-Screen 1%.
 - c. Phifer, Inc; Style 2500 1%.
 - d. Substitutions: See Section 016000 Product Requirements.
 - 2. Material: Vinyl coated fiberglass.
 - Performance Requirements:
 - a. Flammability: Pass NFPA 701 large and small tests.
 - b. Fungal Resistance: No growth when tested according to ASTM G21.
 - 4. Color: As selected by Architect from manufacturer's full range of colors.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No.: 624004

5. Fabrication:

- a. Fabric Orientation: Railroaded, fabric is turned 90 degrees off the roll.
- If height of opening requires multiple panels of railroaded fabric, use manufacturer's standard sewn seams.

2.04 ROLLER SHADE FABRICATION

- A. Field measure finished openings prior to ordering or fabrication.
- B. Dimensional Tolerances: Fabricate shades to fit openings within specified tolerances.
 - Vertical Dimensions: Fill openings from head to sill with 1/4 inch maximum space between bottom bar and window stool.
 - 2. Horizontal Dimensions Inside Mounting: Fill openings from jamb to jamb, with maximum 1/4 inch gap at each edge of jamb.
- C. At openings requiring continuous multiple shade units with separate rollers, locate roller joints at window mullion centers; butt rollers end-to-end.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine finished openings for deficiencies that may preclude satisfactory installation.
- B. Start of installation shall be considered acceptance of substrates.

3.02 PREPARATION

- A. Prepare surfaces using methods recommended by manufacturer for achieving best result for substrate under the project conditions.
- B. Coordinate with window installation and placement of concealed blocking to support shades.

3.03 INSTALLATION

- A. Install in accordance with manufacturer's instructions and approved shop drawings, using mounting devices as indicated.
- B. Adjust level, projection, and shade centering from mounting bracket. Verify there is no telescoping of shade fabric. Ensure smooth shade operation.

3.04 CLEANING

- A. Clean soiled shades and exposed components as recommended by manufacturer.
- B. Replace shades that cannot be cleaned to "like new" condition.

3.05 PROTECTION

- A. Protect installed products from subsequent construction operations.
- B. Touch-up, repair, or replace damaged products before Substantial Completion.

END OF SECTION 122400

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 220500 - COMMON WORK RESULTS FOR PLUMBING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe chases, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawlspaces, and tunnels.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- D. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in chases.
- E. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.
- F. The following are industry abbreviations for plastic materials:
 - 1. ABS: Acrylonitrile-butadiene-styrene plastic.
 - 2. CPVC: Chlorinated polyvinyl chloride plastic.
 - 3. PE: Polyethylene plastic.
 - 4. PVC: Polyvinyl chloride plastic.
- G. The following are industry abbreviations for rubber materials:
 - 1. EPDM: Ethylene-propylene-diene terpolymer rubber.
 - 2. NBR: Acrylonitrile-butadiene rubber.

1.3 SUBMITTALS

- A. Product Data: For the following:
 - 1. Transition fittings.
 - 2. Dielectric fittings.
 - Mechanical sleeve seals.
 - 4. Escutcheons.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.4 OUALITY ASSURANCE

- A. Steel Support Welding: Qualify processes and operators according to AWS D1.1, "Structural Welding Code--Steel."
- B. Steel Pipe Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."
 - 1. Comply with provisions in ASME B31 Series, "Code for Pressure Piping."
 - 2. Certify that each welder has passed AWS qualification tests for welding processes involved and that certification is current.
- C. Electrical Characteristics for Plumbing Equipment: Equipment of higher electrical characteristics may be furnished provided such proposed equipment is approved in writing and connecting electrical services, circuit breakers, and conduit sizes are appropriately modified. If minimum energy ratings or efficiencies are specified, equipment shall comply with requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.
- B. Store plastic pipes protected from direct sunlight. Support to prevent sagging and bending.

1.6 COORDINATION

- A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for plumbing installations.
- B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- C. Coordinate requirements for access panels and doors for plumbing items requiring access that are concealed behind finished surfaces. Access panels and doors are specified in Division 08 Section "Access Doors and Frames."

1.7 INTENT OF CONTRACT DOCUMENTS

- A. Plumbing drawings are diagrammatic, indicating general locations and arrangements of pipe, and equipment. Not necessarily indicating all offsets, conditions, and appurtenances required to provide clearances for maximum practical accessibility to perform maintenance.
- B. Coordinate work in order to achieve proper operation and to provide a maintainable installed condition.
- C. Notify the Architect's representative immediately of conditions which do not comply or will not produce this result.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

D. Indicated configurations were used to size pipes, pumps, expansion tanks and other devices. Install piping and equipment generally as indicated. Minor deviations are permitted in the course of necessary coordination. Major changes shall be submitted for approval by the Architect's representative. Additional fittings and offsets not shown on the drawings are expected, anticipated by the design, and shall be provided. If more than 5% of the indicated number of fittings are required or if one change in direction is within six inches of another change in direction and this "Z" shape is not indicated notify the Architect's representative immediately. Provide necessary additional fittings and offsets. Changes in pipe size shall be made only with written approval from the Architect's representative.

PART 2 - PRODUCTS

2.1 PIPE, TUBE, AND FITTINGS

- A. Refer to other Division 22 piping sections for pipe, tube, and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

2.2 JOINING MATERIALS

- A. Refer to individual Division 22 piping sections for joining materials not listed below.
- B. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions inside & outside pipe and:
 - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness unless thickness or specific material is otherwise indicated.
 - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
 - 2. AWWA C110, rubber, flat face, 1/8-inch-thick, unless otherwise indicated, and full-face or ring type, unless otherwise indicated.
- C. Solder Filler Metals: ASTM B 32, lead-free (95% Tin, 5% Antimony) alloy. Include water-flushable flux according to ASTM B 813.
- D. Brazing Filler Metals: AWS A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing, unless otherwise indicated; and AWS A5.8, BAg1, silver alloy for refrigerant piping, unless otherwise indicated.
- E. Welding Filler Metals: Comply with AWS D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- F. Solvent Cements for Joining Plastic Piping:
 - 1. ABS Piping: ASTM D 2235.
 - 2. CPVC Piping: ASTM F 493.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. PVC Piping: ASTM D 2564. Include primer according to ASTM F 656.
- 4. PVC to ABS Piping Transition: ASTM D 3138.

2.3 MECHANICAL GROOVED JOINT COUPLINGS

- A. Manufacturer: Victaulic
- B. Description: Pipe joint consisting of a grooved pipe, EPDM gasket, steel housing, 2 bolts and 2 nuts.
- C. Gasket Material: Grade "E" EPDM suitable for use up to 250 degrees F.
- D. Housing: Carbon steel

2.4 DIELECTRIC FITTINGS

- A. Description: Combination fitting of copper alloy and ferrous materials with threaded, solder-joint, plain, or weld-neck end connections that match piping system materials.
- B. Insulating Material: Suitable for system fluid, pressure, and temperature.
- C. Dielectric Flanges: Factory-fabricated, companion-flange assembly, for 150 or 300 psig working pressure, as required to suit system pressures.
 - 1. Available Manufacturers:
 - a. Capitol Manufacturing Co.
 - b. Central Plastics Company.
 - c. Epco Sales, Inc.
 - d. Watts Industries, Inc.; Water Products Div.
- D. Dielectric-Flange Kits: Companion-flange assembly for field assembly. Include flanges, full-face- or ring-type neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.
 - 1. Available Manufacturers:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Central Plastics Company.
 - d. Pipeline Seal and Insulator, Inc.
 - 2. Separate companion flanges and steel bolts and nuts shall have 150- or 300-psig minimum working pressure where required to suit system pressures.
- E. Dielectric Couplings: Galvanized-steel coupling with inert and noncorrosive, thermoplastic lining; threaded ends; and 300-psig minimum working pressure at 225 deg F.
 - 1. Available Manufacturers:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Calpico, Inc.
- b. Lochinvar Corp.

2.5 SLEEVES

- A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- B. Steel Pipe: ASTM A 53, Type E, Grade B, Schedule 40, galvanized, plain ends.
- C. Cast Iron: Cast or fabricated "wall pipe" equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- D. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with set screws.
- E. Molded PE: Reusable, PE, tapered-cup-shaped, and smooth-outer surface with nailing flange for attaching to wooden forms.

2.6 ESCUTCHEONS

- A. Description: Manufactured wall and ceiling escutcheons and floor plates, with an ID to closely fit around pipe, tube, and insulation of insulated piping and an OD that completely covers opening.
- B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with polished chrome-plated finish.
- C. One-Piece, Cast-Brass Type: With set screw.
 - 1. Finish: Polished chrome-plated.
- D. Split-Casting, Cast-Brass Type: With concealed hinge and set screw.
 - 1. Finish: Polished chrome-plated.
- E. One-Piece, Floor-Plate Type: Cast-iron floor plate.
- F. Split-Casting, Floor-Plate Type: Cast brass with concealed hinge and set screw.

2.7 GROUT

- A. Description: ASTM C 1107, Grade B, non-shrink and nonmetallic, dry hydraulic-cement grout.
 - 1. Characteristics: Post-hardening, volume-adjusting, non-staining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 PLUMBING DEMOLITION

- A. Refer to Division 2 Sections "Site and Selective Demolition" for general demolition requirements and procedures.
- B. Disconnect, demolish, and remove plumbing systems, equipment, and components indicated to be removed.
 - 1. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
 - 2. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material.
 - 3. Equipment to Be Removed: Remove equipment and associated piping back to main unless otherwise indicated. Cap services.
 - 4. Equipment to Be Removed and Reinstalled: Disconnect and cap services. Remove, clean, and store equipment. When appropriate, reinstall, reconnect, and make equipment operational.
 - 5. Equipment to Be Removed and Salvaged: Remove equipment and associated piping back to main unless otherwise indicated. Cap services. Remove equipment, clean, and store as directed (May be off-site). Make available to owner at time of the owner's choosing.
- C. If pipe, insulation, or equipment to remain is damaged in appearance or is unserviceable, remove damaged or unserviceable portions and replace with new products of equal capacity and quality.

3.2 PIPING SYSTEMS - COMMON REQUIREMENTS

- A. Install piping according to the following and Division 22 Sections specifying piping systems.
- B. Install piping in concealed locations, unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping to permit valve servicing.
- F. Install piping at the minimum slopes required by authorities having jurisdiction unless otherwise indicated.
- G. Install piping free of sags and bends.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Select system components with pressure rating equal to or greater than system operating pressure.
- K. Install escutcheons for penetrations of walls, ceilings, and floors according to the following:
 - 1. Exposed, Interior Installations/Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type.
 - 2. Exposed, Interior Installations/Chrome-Plated Piping: One-piece, cast-brass type with polished chrome-plated finish and set-screw.
 - 3. Exposed, Interior Installations/Insulated Piping: One-piece, cast-brass type with polished chrome-plated finish.
 - 4. Exposed, Interior Installations/Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece, cast-brass type with finish to match surrounding surfaces.
 - 5. Exposed, Interior Installations/Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece or split-casting, cast-brass type with finish to match surrounding surfaces.
 - 6. Exposed, Interior Installations/Piping in Unfinished Service Spaces: None, provide sealant.
 - 7. Exposed, Interior Installations/Piping in Equipment Rooms: None, provide sealant.
 - 8. Exposed, Interior Installations/Piping at Floor Penetrations in Equipment Rooms, Fan Rooms, or similar wet spaces: None provide sealant and sleeve extending 2" above floor to prevent liquid leaking to floor below
- L. Sleeves are not required for core-drilled holes.
 - 1. Exception: Exposed, Interior Installations at Floor Penetrations in Equipment Rooms, Fan Rooms, or similar wet spaces.
- M. Permanent sleeves are not required for holes formed by removable PE sleeves.
 - 1. Exception: Exposed, Interior Installations at Floor Penetrations in Equipment Rooms, Fan Rooms, or similar wet spaces.
- N. Install sleeves for pipes passing through walls, floors, or roofs.
 - 1. Cut sleeves to length for mounting flush with both surfaces.
 - a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring.
 - 2. Install sleeves as walls and slabs are constructed.
 - a. PVC Pipe Sleeves: Permitted for pipes smaller than NPS 6 except aboveground, exterior-walls.
 - b. Steel Sheet Sleeves: Permitted for pipes NPS 6 and larger, penetrating gypsumboard partitions except aboveground, exterior-walls.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Stack Sleeve Fittings: For pipes penetrating floors. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor. Seal space outside sleeve fittings with grout.
- 3. Except for penetrations where mechanical sleeve seals are used, seal annular space between sleeve and pipe or pipe insulation, using joint sealants appropriate for size, depth, and location of joint. Refer to Division 7 Section "Joint Sealants".
- O. Aboveground Exterior Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Select sleeve size to allow for annular clear space required by the mechanical sleeve seal manufacturer between pipe and sleeve for installing mechanical sleeve seals.
 - 1. Install steel pipe for sleeves smaller than 6 inches in diameter.
 - 2. Install cast-iron "wall pipes" for sleeves 6 inches and larger in diameter.
 - 3. Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
 - 4. Sleeves from an approved sleeve seal manufacturer shall be acceptable.
- P. Underground Exterior Penetrations: Install cast-iron "wall pipes" for sleeves. Seal pipe penetrations using mechanical sleeve seals. Select sleeve size to allow for annular clear space required by the mechanical sleeve seal manufacturer between pipe and sleeve for installing mechanical sleeve seals.
- Q. Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
- R. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Refer to Section "Penetration Firestopping" for materials.
- S. Verify final equipment locations for roughing-in.
- T. Refer to equipment specifications in other Sections of these Specifications for roughing-in requirements.

3.3 PIPING JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 22 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.
- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8.
- F. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- G. Welded Joints: Construct joints according to AWS D10.12, using qualified processes and welding operators according to Part 1 "Quality Assurance" Article.
- H. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.
- I. Plastic Piping Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:
 - 1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
 - 2. ABS Piping: Join according to ASTM D 2235 and ASTM D 2661 Appendixes.
 - 3. CPVC Piping: Join according to ASTM D 2846/D 2846M Appendix.
 - 4. PVC Pressure Piping: Join schedule number ASTM D 1785, PVC pipe and PVC socket fittings according to ASTM D 2672. Join other-than-schedule-number PVC pipe and socket fittings according to ASTM D 2855.
 - 5. PVC Non-pressure Piping: Join according to ASTM D 2855.
 - 6. PVC to ABS Non-pressure Transition Fittings: Join according to ASTM D 3138 Appendix.
- J. Plastic Pressure Piping Gasketed Joints: Join according to ASTM D 3139.
- K. Plastic Non-pressure Piping Gasketed Joints: Join according to ASTM D 3212.
- L. PE Piping Heat-Fusion Joints: Clean and dry joining surfaces by wiping with clean cloth or paper towels. Join according to ASTM D 2657.
 - 1. Plain-End Pipe and Fittings: Use butt fusion.
 - 2. Plain-End Pipe and Socket Fittings: Use socket fusion.
- M. Fiberglass Bonded Joints: Prepare pipe ends and fittings, apply adhesive, and join according to pipe manufacturer's written instructions.
- N. Mechanical Joints: Prepare pipe ends and fittings, apply coupling, and join according to joint manufacturer's written instructions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.4 PIPING CONNECTIONS

- A. Make connections according to the following, unless otherwise indicated:
 - 1. Install unions, in piping 2" and smaller, one adjacent to each valve and at final connections to each piece of equipment.
 - 2. Install flanges, in piping NPS 2-1/2" and larger, adjacent to final connections to each piece of equipment.
 - 3. Install dielectric unions or flanges for connections of dissimilar metals.

3.5 EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- A. Install equipment to allow maximum possible headroom unless specific mounting heights are indicated.
- B. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.
- C. Install plumbing equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
- D. Install equipment to allow right of way for piping installed at required slope.

3.6 PAINTING

A. Damage and Touchup: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.7 HOUSEKEEPING PADS AND EQUIPMENT PADS

- A. Housekeeping pads and equipment pads: Anchor equipment to concrete according to equipment manufacturer's written instructions and according to seismic codes at project location.
 - 1. Construct concrete pads in accordance with drawing details.
 - 2. Details may be found on structural drawings. If details are not provided comply with the following:
 - a. Housekeeping pads inside the building shall be 4" thick and 6" larger all around than supported equipment. Provide a 1" chamfer on all edges.
 - b. If details are not provided, equipment pads outside the building shall be 8" thick with a 24" deep 12" wide turndown (footing) all around the outside edge of the pad. Provide welded wire mesh reinforcement. Pad shall be 12" larger all around than supported equipment.
 - c. Install dowel rods to connect housekeeping pad to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of the pad. Provide a 1" chamfer on all edges.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- d. Install epoxy-coated anchor bolts. For equipment on housekeeping pads bolts shall extend through housekeeping pad, and anchor into structural concrete floor.
- e. Place and secure anchor bolts using supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions for placement.
- f. Install anchor bolts to elevations required for proper attachment to supported equipment.
- g. Install anchor bolts according to anchor bolt manufacturer's written instructions.
- h. Use 3000-psi, 28-day compressive-strength concrete and reinforcement as specified in Section "Cast-in-Place Concrete".

3.8 ERECTION OF METAL SUPPORTS AND ANCHORAGES

- A. Refer to Section "Metal Fabrications" for structural steel.
- B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor plumbing materials and equipment.
- C. Field Welding: Comply with AWS D1.1.

3.9 GROUTING

- A. Mix and install grout for plumbing equipment base bearing surfaces, pump and other equipment base plates, and anchors.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms as required for placement of grout.
- D. Avoid air entrapment during placement of grout.
- E. Place grout, completely filling equipment bases.
- F. Place grout on concrete bases and provide smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout.

3.10 EXCAVATION AND BACKFILL

- A. Excavation and backfill shall be as indicated in Division 1 specifications and on the drawings. If excavation and backfill is not otherwise indicated the following shall apply:
 - 1. Excavate trenches to indicated gradients, lines, depths, and elevations.
 - a. Beyond the building perimeter, excavate trenches to allow installation of top of pipe below frost line.
 - 2. Excavate trenches to uniform widths to provide twelve inches clear on each side of pipe. Excavate trench walls vertically from trench bottom.
 - 3. Trench Bottoms: Excavate trench bottoms to provide flat surface. Place and compact six inches of sand. Excavate and shape sand to provide uniform bearing and support of

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- pipes. Shape sand to provide continuous support for bells, joints, fittings, and barrels of pipes. Sand shall be free of projecting stones and sharp objects.
- 4. Backfill and hand tamp to 95% proctor to six inches above the top of the pipe.
- 5. Backfill and machine tamp the remainder of the trench to 95% proctor in twelve inch lifts.

END OF SECTION 220500

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 220513 – MOTORS FOR PLUMBING EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

A. Manufacturer's catalog and efficiency data.

1.3 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70.

1.4 COORDINATION

- A. Equip all motors with overload protection.
 - 1. Locate overload protection near the motor.
 - 2. Overload protection:
 - a. Locate between the circuit breaker/fuse provided under Division 26 and the motor windings.
 - b. Comply with one of the following:
 - 1) Locate in motor by motor manufacturer. (Design Standard)
 - 2) Locate separate overload device near motor.
 - 3) Locate in, or with, disconnect switch by equipment manufacturer. Provision of such switch shall not modify, change, or eliminate Division 26 requirements. Provide indicated disconnecting means.
- B. Coordinate features of motors, installed units, and accessory devices. Provide motors that are:
- C. Compatible with controller.
- D. Matched to torque and horsepower requirements of the load.
- E. Matched to ratings and characteristics of supply circuit and required control sequence.
- F. Coordinate motor support with requirements for driven load; access for maintenance and motor replacement; installation of accessories, belts, belt guards; and adjustment of sliding rails for belt tensioning.
- G. Belt tension must be wrench and socket adjustable.
- H. Belt tensioning device must accommodate adjustable sheaves.

PART 2 - PRODUCTS

2.1 MOTOR REQUIREMENTS

A. Motor requirements apply except as follows:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Ratings, performance, or characteristics for a motor are specified in another Section or are scheduled on the drawings.
- C. Motor manufacturer requires ratings, performance, or characteristics, other than those specified to meet indicated performance.

2.2 MOTOR CHARACTERISTICS

- A. Frequency Rating: 60 Hz.
- B. Voltage Rating: NEMA standard voltage selected to operate on nominal circuit voltage to which motor is connected.
- C. Duty: Continuous at 105 deg F and 3300 feet above sea level.
- D. Capacity and Torque sufficient to:
 - 1. Start, accelerate, and operate connected load.
 - 2. Maintain designated speeds.
 - 3. Operate at installed altitude and environment.
 - 4. Operate with indicated operating sequence.
 - 5. Operate without exceeding nameplate ratings.
 - 6. Operate without utilizing service factor.
- E. Enclosure: Open drip-proof unless otherwise indicated.
- F. Minimum Service Factor: 1.15 unless otherwise indicated.

2.3 POLYPHASE MOTORS

- A. Description: NEMA MG 1, Design B, medium induction motor.
- B. Premium efficiency motors shall meet the following full load efficiency:

HP	ODP			TEFC		
	6 Pole	4 Pole	2 Pole	6 Pole	4 Pole	2 Pole
1	82.5	85.5	77.0	82.5	85.5	77.0
1.5	86.5	86.5	84.0	87.5	86.5	84.0
2	87.5	86.5	85.5	88.5	86.5	85.5
3	88.5	89.5	85.5	89.5	89.5	86.5
5	89.5	89.5	86.5	89.5	89.5	88.5
7.5	90.2	91.0	88.5	91.0	91.7	89.5
10	91.7	91.7	89.5	91.0	91.7	90.2
15	91.7	93.0	90.2	91.7	92.4	91.0
20	92.4	93.0	91.0	91.7	93.0	91.0
25	93.0	93.6	91.7	93.0	93.6	91.7
30	93.6	94.1	91.7	93.0	93.6	91.7
40	94.1	94.1	92.4	94.1	94.1	92.4
50	94.1	94.5	93.0	94.1	94.5	93.0
60	94.5	95.0	93.6	94.5	95.0	93.6
75	94.5	95.0	93.6	94.5	95.4	93.6
100	95.0	95.4	93.6	95.0	95.4	94.1
125	95.0	95.4	94.1	95.0	95.4	95.0
150	95.4	95.8	94.1	95.8	95.8	95.0

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- C. Efficiency: Premium
- D. Stator: Copper windings, unless otherwise indicated.
- E. Rotor: Squirrel cage, unless otherwise indicated.
- F. Bearings: Double-shielded, prelubricated ball bearings suitable for radial and thrust loading.
- G. Temperature Rise: Match insulation rating, unless otherwise indicated.
- H. Insulation: Class F, unless otherwise indicated.
- I. Code Letter Designation: NEMA starting Code F or G.
- J. Enclosure: Cast iron.
- K. Finish: Gray enamel.
- L. Motors Used with Reduced-Inrush Controllers: Match wiring connection requirements for controller with required motor leads. Provide terminals in motor terminal box, suited to control method.
- M. Source Quality Control: Perform the following tests on each motor according to NEMA MG 1:
- N. Measure winding resistance.
- O. Read no-load current and speed at rated voltage and frequency.
- P. Measure locked rotor current at rated frequency.
- Q. Perform high-potential test.

PART 3 - EXECUTION

3.1 FIELD QUALITY CONTROL

- A. Perform the following:
 - 1. Run each motor with its controller at load.
 - 2. Demonstrate correct rotation, alignment, and speed.
 - 3. Test interlocks and control features for proper operation.
 - 4. Verify that current in each phase is within nameplate rating.
 - 5. Verify RPM is in accordance with nameplate.
 - 6. Where a generator is provided, run each motor on the generator with its controller and load. Demonstrate correct rotation, alignment, and speed.

3.2 ADJUSTING

A. Align motors, bases, and shafts.

3.3 CLEANING

A. After completing equipment installation, inspect unit components. Remove paint splatters and other spots, dirt, and debris. Repair damaged finish to match original finish.

END OF SECTION 220513

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 220517 - SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

A. Product Data: For each type of product indicated.

PART 2 - PRODUCTS

2.1 SLEEVES

- A. Cast-Iron Wall Pipes: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.
- B. Galvanized-Steel Wall Pipes: ASTM A 53/A 53M, Schedule 40, with plain ends and welded steel collar; zinc coated.
- C. Galvanized-Steel-Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, with plain ends.
- D. Galvanized-Steel-Sheet Sleeves: 0.0239-inch (0.6-mm) minimum thickness; round tube closed with welded longitudinal joint.

2.2 MECHANICAL SLEEVE SEALS

- A. Description: Modular sealing element unit, designed for field assembly, to fill annular space between pipe and sleeve.
 - 1. Available Manufacturers:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Link Seal
 - d. Metraflex Co.
 - e. Pipeline Seal and Insulator, Inc.
 - 2. Sealing Elements: EPDM interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 3. Pressure Plates: Plastic. Include two for each sealing element.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

4. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements.

PART 3 - EXECUTION

3.1 SLEEVE INSTALLATION

- A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.
- B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.
 - 1. Sleeves are not required for core-drilled holes.
- C. Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed.
 - 1. Permanent sleeves are not required for holes in slabs formed by molded-PE or -PP sleeves.
 - 2. Cut sleeves to length for mounting flush with both surfaces.
 - a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.
 - 3. Using grout, seal the space outside of sleeves in slabs and walls without sleeve-seal system.
- D. Install sleeves for pipes passing through interior partitions.
 - 1. Cut sleeves to length for mounting flush with both surfaces.
 - 2. Install sleeves that are large enough to provide 1/4" clear space between sleeve and pipe or pipe insulation.
 - 3. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint. Comply with requirements for sealants.
- E. Fire Ratings: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials.

3.2 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building unless otherwise indicated. They are not required at sanitary and storm piping exits unless otherwise indicated.
- B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.3 SLEEVE AND SLEEVE-SEAL SCHEDULE

- A. Use sleeves and sleeve seals for the following piping-penetration applications:
 - 1. Exterior Concrete Walls above Grade, below Grade, Concrete Slabs-on-Grade, and Concrete Slabs above Grade:
 - a. Piping Smaller Than 6": Cast-iron wall sleeves with sleeve-seal system.
 - 1) Select sleeve size to allow for one inch (1") annular clear space between piping and sleeve for installing sleeve-seal system.
 - b. Piping 6" and Larger: Galvanized-steel-pipe sleeves with sleeve-seal system.

END OF SECTION 220517

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 220519 - METERS AND GAGES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Wiring Diagrams: For power, signal, and control wiring.
- C. Operation and Maintenance Data: For meters and gages to include in operation and maintenance manuals.

1.3 ABBREVIATIONS:

- A. AFF Above finished floor
- B. F Fahrenheit
- C. SS Stainless Steel

PART 2 - PRODUCTS

2.1 LIQUID-IN-GLASS THERMOMETERS

- A. Metal-Case, Industrial-Style, Liquid-in-Glass Thermometers:
 - 1. Available Manufacturers:
 - a. Flo Fab Inc.
 - b. Miljoco Corporation.
 - c. Palmer Wahl Instrumentation Group.
 - d. Tel-Tru Manufacturing Company.
 - e. Trerice, H. O. Co.
 - f. Weiss Instruments, Inc.
 - g. Winters Instruments U.S.
 - 2. Standard: ASME B40.200.
 - 3. Case: Cast aluminum; 9-inch nominal size unless otherwise indicated.
 - 4. Case Form: Adjustable angle unless otherwise indicated.
 - 5. Tube: Glass with magnifying lens and blue or red organic liquid.
 - 6. Tube Background: Nonreflective aluminum with permanently etched scale markings graduated in degrees F.
 - 7. Window: Glass

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 8. Stem: Aluminum length = 1/2 pipe diameter, 1/2 duct width or 12" whichever is less.
 - a. Air-Duct Installation: Provide ventilated shroud.
 - b. Thermowell Installation: Provide Bare stem.
- 9. Connector: 1-1/4 inches, with ASME B1.1 screw threads.
- 10. Accuracy: Plus or minus 1 percent of scale range or one scale division, to a maximum of 1.5 percent of scale range.

2.2 THERMOWELLS

A. Thermowells:

- 1. Standard: ASME B40.200.
- 2. Description: Pressure-tight, socket-type fitting made for insertion into threaded fitting.
- 3. Material: Brass.
- 4. Type: Stepped shank unless straight or tapered shank is indicated.
- 5. External Threads: NPS 1/2, NPS 3/4, or NPS 1, ASME B1.20.1 pipe threads.
- 6. Internal Threads: 1/2, 3/4, and 1 inch, with ASME B1.1 screw threads.
- 7. Bore: Diameter required to match thermometer bulb or stem.
- 8. Insertion Length: Length required to match thermometer bulb or stem.
- 9. Lagging Extension: Include on thermowells for insulated piping and tubing.
- 10. Bushings: For converting size of thermowell's internal screw thread to size of thermometer connection.

2.3 PRESSURE GAGES

A. Direct-Mounted, Metal-Case, Dial-Type Pressure Gages:

- 1. Available Manufacturers:
 - a. AMETEK, Inc.; U.S. Gauge.
 - b. Ashcroft Inc.
 - c. Ernst Flow Industries.
 - d. Flo Fab Inc.
 - e. Marsh Bellofram.
 - f. Miljoco Corporation.
 - g. Noshok.
 - h. Palmer Wahl Instrumentation Group.
 - i. REOTEMP Instrument Corporation.
 - j. Tel-Tru Manufacturing Company.
 - k. Trerice, H. O. Co.
 - 1. Watts Regulator Co.; a div. of Watts Water Technologies, Inc.
 - m. Weiss Instruments, Inc.
 - n. WIKA Instrument Corporation USA.
 - o. Winters Instruments U.S.
- 2. Standard: ASME B40.100.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Case: Solid-front, pressure relief type; cast aluminum or drawn steel; 4-1/2-inch nominal diameter.
- 4. Pressure-Element Assembly: Bourdon tube unless otherwise indicated.
- 5. Pressure Connection: Brass, with NPS 1/4, ASME B1.20.1 pipe threads and bottom-outlet type unless back-outlet type is indicated.
- 6. Movement: Phosphor bronze.
- 7. Dial: Nonreflective aluminum with permanently etched scale markings graduated in psi.
- 8. Pointer: Dark-colored metal.
- 9. Window: Glass.
- 10. Ring: Brass.
- 11. Accuracy: + or -1.0 percent of full scale.

2.4 GAGE ATTACHMENTS

- A. Snubbers: ASME B40.100, brass; with NPS 1/4, ASME B1.20.1 pipe threads and porousmetal-type surge-dampening device. Include extension for use on insulated piping.
- B. Siphons: Loop-shaped section of brass pipe with NPS 1/4 pipe threads.
- C. Valves: Brass or stainless-steel needle, with NPS 1/4, ASME B1.20.1 pipe threads.

2.5 TEST PLUGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Flow Design, Inc.
 - 2. Miljoco Corporation.
 - 3. National Meter, Inc.
 - 4. Peterson Equipment Co., Inc.
 - 5. Sisco Manufacturing Company, Inc.
 - 6. Trerice, H. O. Co.
 - 7. Watts Regulator Co.; a div. of Watts Water Technologies, Inc.
 - 8. Weiss Instruments, Inc.
- B. Description: Test-station fitting made for insertion into piping tee fitting.
- C. Body: Brass or stainless steel with core inserts and gasketed and threaded cap. Include extended stem on units to be installed in insulated piping.
- D. Thread Size: NPS 1/2, ASME B1.20.1 pipe thread.
- E. Minimum Pressure and Temperature Rating: 500 psig at 200 deg F.
- F. Core Inserts: Chlorosulfonated polyethylene synthetic and EPDM self-sealing rubber.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install thermowells with socket extending to center of pipe in piping tees.
- B. Install thermowells of sizes required to match thermometer connectors. Include bushings to match sizes.
- C. Install thermowells with extensions on insulated piping.
- D. Install direct-mounted thermometers in thermowells and adjust positions.
- E. Install pressure gages in piping tees located between 36" and 60" above finished floor unless otherwise indicated.
- F. Install valve and snubber for each pressure gage.
- G. Install test plugs in piping tees at locations indicated.
- H. Install permanent indicators on walls or brackets at 50" above finished floor unless otherwise indicated..
- I. Install connection fittings in accessible locations for attachment to portable indicators.
- J. Install thermometers in the following locations:
 - 1. Inlet and outlet of each water heater.
- K. Install pressure gages in the following locations:
 - 1. Inlet and outlet of each water heater.
 - 2. Suction and discharge of each pump.
- L. Install a test plug at each thermometer and pressure gauge.

3.2 THERMOMETER SCALE-RANGE SCHEDULE

- A. Scale Range for Domestic Cold-water Piping: 0 to 100 F with 2 degree scale divisions.
- B. Scale Range for Domestic Hot-water Piping 30 to 240 F with 2 degree scale divisions.

3.3 PRESSURE-GAGE SCALE-RANGE SCHEDULE

A. Scale Range for Domestic Water Piping: 0 psi to 100 psi.

END OF SECTION 220519

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 220523 - GENERAL DUTY VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. The following are standard abbreviations for valves:
 - 1. CWP: Cold working pressure.
 - 2. EPDM: Ethylene-propylene-diene terpolymer rubber.
 - 3. MPTFE: Modified polytetrafluoroethylene plastic.
 - 4. NBR: Acrylonitrile-butadiene rubber.
 - 5. PTFE: Polytetrafluoroethylene plastic.
 - 6. RPTFE: Reinforced polytetrafluoroethylene plastic.
 - 7. SWP: Steam working pressure.
 - 8. TFE: Tetrafluoroethylene plastic.
 - 9. WOG: Water Oil Gas.

1.3 SUBMITTALS

A. Product Data: For each type of valve proposed. Include body, seating, and trim materials; valve design; pressure and temperature classifications; end connections; arrangement; dimensions; and required clearances. Include proposed specialties and accessories.

1.4 QUALITY ASSURANCE

- A. ASME Compliance: ASME B31.1 for power piping valves and ASME B31.9 for building services piping valves.
 - 1. Exceptions: Domestic hot- and cold-water valves unless referenced.
- B. ASME Compliance for Ferrous Valves: ASME B16.10 and ASME B16.34 for dimension and design criteria.
- C. NSF Compliance: NSF 61 for valve materials for potable-water service.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 - 1. Protect internal parts against rust and corrosion.
 - 2. Protect threads, flange faces, grooves, and weld ends.
 - 3. Set ball valves open to minimize exposure of functional surfaces.
 - 4. Set butterfly valves closed or slightly open.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 5. Block check valves in either closed or open position.
- B. Use the following precautions during storage:
 - 1. Maintain valve end protection.
 - 2. Store valves indoors and maintain at higher than ambient dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 VALVES, GENERAL

- A. Refer to Part 3 "Valve Applications" Article for applications of valves.
- B. Bronze & Brass: Shall be dezincification resistant. (Zinc content shall be less than 15%)
- C. Bronze Valves: 2" and smaller with threaded ends, unless otherwise indicated.
- D. Ferrous Valves: 2-1/2" and larger with flanged ends, unless otherwise indicated.
- E. Valve Pressure and Temperature Ratings: Not less than indicated for system pressure and temperature.
- F. Valve Sizes: Same as the larger of the upstream or downstream pipe, unless otherwise indicated.
- G. Valve Actuators:
 - 1. As indicated in other Part 2 articles.
 - 2. Where indicated, provide a chain actuator.
 - 3. Chain Actuator: For attachment to valves of size and mounting height indicated.
 - 4. Wrench: For plug valves with square heads. Furnish Owner with 1 wrench for every 10 plug valves, for each size square plug head.
- H. Extended Valve Stems: Provide on insulated valves.
- I. Valve Flanges: Provide ASME B16.1 for cast-iron valves, ASME B16.5 for steel, and ASME B16.24 for bronze.
- J. Valve Grooved Ends: AWWA C606.
- K. Threaded: With threads according to ASME B1.20.1.
- L. Valve Bypass and Drain Connections: MSS SP-45.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.2 COPPER-ALLOY BALL VALVES

- A. Two-Piece, Copper-Alloy Ball Valves (Full Port):
 - 1. Conbraco Industries-Apollo 77C series with stainless steel ball & stem (Un-insulated piping)
 - 2. Conbraco Industries-Apollo 77C series with stainless steel ball & stem. Provide 2 ¼" stem extension (Insulated piping)
 - 3. Other Manufacturers:
 - a. Milwaukee
 - b. Watts
 - c. Nibco
 - 4. Handle Nut: Zinc plated steel or 300 series stainless steel.
 - 5. Handle: Zinc plated steel, clear chromate plastic, or vinyl coated.
 - 6. Threaded Pack Gland: Brass ASTM B-16
 - 7. Packing: MPTFE or TFE
 - 8. Stem (Blowout Proof): ASTM A-276 type 316 stainless steel. Provide 2 ½" stem extension for Insulated piping.
 - 9. Thrust Washer: MPTFE or RPTFE
 - 10. Ball: Full-port, ASTM A-276 Type 316 stainless steel.
 - 11. Seats: MPTFE or Reinforced TFE (RPTFE)
 - 12. Body: Bronze ASTM B-584 for solder or threaded connection.
 - 13. Body End Piece: Bronze ASTM B-584 for solder or threaded connection.
 - 14. Rating: 150 psig saturated steam, 600 psig non-shock cold water, oil, and gas.
 - 15. Conform To: MSS SP-110
- B. Two-Piece, Bronze Ball Valves UL listed for shut-off gas service (Up to 2 ½"):
 - 1. Conbraco Industries-Apollo 80-100 series (Un-insulated piping).
 - 2. Conbraco Industries-Apollo 80-100 series with stainless steel ball & stem. Provide 2 ¼" stem extension (Insulated piping)
 - 3. Other Manufacturers:
 - a. Milwaukee
 - b. Watts
 - c. Nibco
 - 4. Handle Nut: Zinc plated steel or 300 series stainless steel.
 - 5. Handle: Zinc plated steel, clear chromate plastic, or vinyl coated.
 - 6. Threaded Pack Gland: Brass ASTM B-16
 - 7. Packing: MPTFE or TFE
 - 8. Stem (Blowout Proof): ASTM A-276 type 316 stainless steel. Provide 2 ½" stem extension for Insulated piping.
 - 9. Thrust Washer: MPTFE or RPTFE
 - 10. Ball: Brass ASTM B-16, chrome plated.
 - 11. Seats: MPTFE or Reinforced TFE (RPTFE)
 - 12. Body: Bronze ASTM B-584 for threaded connection.
 - 13. Body End Piece: Bronze ASTM B-584 for threaded connection.
 - 14. Rating: 150 psig saturated steam, 250 psi gas, vacuum service to 29".
 - 15. Conform To: MSS SP-110
- C. Two-Piece, Copper-Alloy Ball Valves (Full Port):Conbraco Industries Apollo 77C-140 series with stainless steel ball & stem (Un-insulated piping)

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Conbraco Industries Apollo 77 C-140 series with stainless steel ball & stem. Provide 2 1/4" stem extension (Insulated piping)
- 3. Other Manufacturers:
 - a. Milwaukee
 - b. Watts
 - c. Nibco.
- 4. Handle Nut: Zinc plated steel or 300 series stainless steel.
- 5. Handle: Zinc plated steel, clear chromate plastic, or vinyl coated.
- 6. Threaded Pack Gland: Brass ASTM B-16 Alloy 360
- 7. Packing: RPTFE or TFE
- 8. Stem (Blowout Proof): ASTM A-276 type 316 stainless steel. Provide 2 ¹/₄" stem extension for Insulated piping.
- 9. Thrust Washer: MPTFE or Reinforced TFE
- 10. Ball: Full-port, ASTM A-276 Type 316 stainless steel.
- 11. Seats: MPTFE or Reinforced TFE
- 12. Body: Bronze ASTM B-584 for solder or threaded connection.
- 13. Body End Piece: Bronze ASTM B-584 for solder or threaded connection.
- 14. Rating: 150 psig saturated steam, 600 psig non-shock cold water, oil, and gas.
- 15. Conform To: MSS SP-110

2.3 MOTORIZED BALL VALVES

- A. Electrically Operated Valves: Comply with UL 429.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ASCO Power Technologies, LP; Division of Emerson. Model 8210
 - b. Magnatrol Valve Corporation.
 - c. Parker Hannifin Corporation; Climate & Industrial Controls Group; Skinner Valve Div.
 - d. Watts Regulator Co.; Division of Watts Water Technologies, Inc.
 - 2. Pilot operated.
 - 3. Body: Brass or aluminum.
 - 4. Seats and Disc: Nitrile rubber.
 - 5. Springs and Valve Trim: Stainless steel.
 - 6. 120-V ac, 60 Hz, Class B, continuous-duty molded coil, and replaceable.
 - 7. NEMA ICS 6, Type 4, coil enclosure.
 - 8. Normally closed.
 - 9. Visual position indicator.

2.4 LARGE GAS BALL VALVES (ABOVE 2 ½" to 10"):

- A. Carbon Steel ANSI class 150, flanged, standard port ball valve with stainless steel ball and stem.
 - 1. Conbraco Industries-Apollo 88A-140 series
 - 2. Other Manufacturers:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Milwaukee
- b. Watts
- c. Nibco
- 3. Provide gear operator with oversized hand wheel.
- 4. Packing Gland: ASTM A108 Type 1215
- 5. Packing: RPTFE or TFE
- 6. Stem (Blowout Proof): ASTM A108 Type 1215
- 7. Ball: Standard-port, ASTM A-276 Type 316 stainless steel solid ball.
- 8. Seats: RPTFE
- 9. Thrust Washer: RPTFE.
- 10. Body: Carbon steel ASTM A216 WCB.
- 11. Body Nut: ASTM A194, grade 2H.
- 12. UL (YRPV): Listed for gas shut-off service.
- 13. Rating: 150 psig saturated steam

2.5 FERROUS-ALLOY BUTTERFLY VALVES

- A. General: Butterfly valves shall provide bi-directional bubble tight dead end service without a downstream flange.
- B. Wafer-lug type butterfly valves:
 - 1. Conbraco Industries-Apollo 141(wafer)/143(lug)
 - 2. Other Manufacturers:
 - a. Stockham
 - b. Demco
 - c. Nibco
 - 3. Shaft: ASTM A-582 Type 416 Stainless steel single piece through shaft.
 - 4. Collar Bushing: ASTM B-124 Brass or PTFE.
 - 5. Stem Seal: EPDM OR Buna-N Rubber
 - 6. Body Seal: EPDM Rubber
 - 7. Upper Bushing: CDA 122 Copper or PTFE
 - 8. Liner: EPDM Rubber
 - 9. Disc: ASTM B-148 alloy 954/955 aluminum bronze.
 - 10. Lower Bushing: CDA 122 copper or PTFE.
 - 11. Body Wafer: ASTM A-536 Ductile Iron or ASTM A-126 CL. B cast iron.
 - 12. Body Lug: ASTM A-536 Ductile Iron or ASTM A-126 CL. B cast iron.
 - 13. Ratings:
 - a. 2" through 12" 200 psig CWP.
 - o. 14" through 24" 150 psig CWP.
 - 14. Conform To: MSS SP-67, MSS SP-25, API-609
 - 15. Operator:
 - a. Valves up to and including 6": Lever-lock operator.
 - b. Valves 8" and larger: Self locking worm gear operator equipped with adjustable stops at open and shut positions.
- C. Grooved-End 300 psig butterfly valves:
 - 1. NIBCO Model GD 4765
 - 2. Other Manufacturers:
 - a. Victaulic

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Upper Stem: ASTM A-582 Type 416 Stainless steel.
- 4. Upper Bearing: Split metal.
- 5. O-Ring: EPDM
- 6. Body: ASTM A-395 ductile iron with polyimide coating.
- 7. Disc: ASTM A-395 ductile iron with EPDM encapsulation.
- 8. Lower Bearing: Split metal.
- 9. Dust Plug: PVC
- 10. Rating: 300 psig CWP.
- 11. Conform To: MSS SP-67
- 12. Operator:
 - a. Valves up to and including 6": Lever-lock operator.
 - b. Valves 8" and larger: Self locking worm gear operator equipped with adjustable stops at open and shut positions.

D. Flanged 200 psig butterfly valves:

- 1. NIBCO Model FC-2765-0
- 2. Upper Stem: ASTM A-582 Type 416 Stainless steel.
- 3. Upper Bushing: TFE over porous bronze, steel backed.
- 4. O-Ring: EPDM
- 5. Body: ASTM A-126 Class B cast iron with polyimide coating.
- 6. Disc: ASTM A-395 ductile iron with EPDM encapsulation.
- 7. Lower Bushing: TFE over porous bronze, steel backed.
- 8. Lower Stem: ASTM A-582 Type 416 Stainless steel.
- 9. Dust Plug: PVC
- 10. Rating: 200 psig CWP.
- 11. Conform To: MSS SP-67 and MSS SP-25
- 12. Operator:
 - a. Valves up to and including 6": Lever-lock operator.
 - b. Valves 8" and larger: Self locking worm gear operator equipped with adjustable stops at open and shut positions.

E. Flanged 200 psig butterfly valves for Gas Service:

- 1. NIBCO Model FC-2765-0
- 2. Upper Stem: ASTM A-582 Type 416 Stainless steel.
- 3. Upper Bushing: TFE over porous bronze, steel backed.
- 4. O-Ring: EPDM
- 5. Body: ASTM A-126 Class B cast iron with polyimide coating.
- 6. Disc: ASTM A-395 ductile iron with EPDM encapsulation.
- 7. Lower Bushing: TFE over porous bronze, steel backed.
- 8. Lower Stem: ASTM A-582 Type 416 Stainless steel.
- 9. Dust Plug: PVC
- 10. Rating: 200 psig CWP.
- 11. Conform To: MSS SP-67 and MSS SP-25
- 12. Operator:
 - a. Valves up to and including 6": Lever-lock operator.
 - b. Valves 8" and larger: Self locking worm gear operator equipped with adjustable stops at open and shut positions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.6 BRONZE CHECK VALVES

- A. Bronze, Horizontal Swing Check Valves:
 - 1. NIBCO Model 413
 - 2. Other Manufacturers:
 - a. Milwaukee
 - b. Stockham
 - 3. Bonnet: ASTM B-62 bronze.
 - 4. Body: ASTM B-62 bronze.
 - 5. Hinge Pin: ASTM B-140 alloy C31400 bronze, or B-134 alloy C23000 bronze.
 - 6. Disc Hanger:
 - a. Sizes 1/4" thru 3/4": Type 304 stainless steel.
 - b. Sizes 1" and larger: ASTM B-62 bronze.
 - 7. Hanger Nut: ASTM B-16 bronze.
 - 8. Disc Holder: ASTM B-62 bronze.
 - 9. Seat Disc:
 - a. Water and Other Heat Transfer Fluids: ASTM B-62 bronze.
 - b. Steam: TFE
 - 10. Seat Disc Nut: ASTM B-16 or B-62 bronze.
 - 11. Hinge Pin Plug: ASTM B-140 alloy C31600 bronze.
 - 12. Seat Disc Washer (When Provided): ASTM B-98 alloy C65500 or B-103 bronze.
 - 13. Rating: 125 psig SWP and 200 psig CWP.
 - 14. Conform To: MSS SP-80
- B. Bronze, Inline Spring Loaded Check Valves:
 - 1. Conbraco Industries-Apollo 61-100 series
 - 2. Other Manufacturers:
 - a. Milwaukee
 - b. Stockham
 - c. Nibco
 - 3. Body: ASTM B-584 alloy C84400 bronze.
 - 4. Retainer/Stem: ASTM B16 brass or ASTM A-582 alloy C30300 stainless steel.
 - 5. Ball Check: RPTFE or
 - 6. Disc Holder 316 Stainless steel
 - a. Disc:
 - 1) Water, Oil, Gas: Buna-N
 - 2) Steam: TFE
 - b. Seat Screw: ASTM A-276 alloy S43000 stainless steel.
 - c. Body End: ASTM B-584 alloy C84400 bronze.
 - d. Rating: 125 psig SWP and 250 psig CWP.
 - 7. Guide: ASTM B16 Brass
 - 8. Spring: Type 316 stainless steel.
 - 9. Rating: 125 psig SWP and 400 psig WOG.

2.7 IRON BODY CHECK VALVES

- A. Iron Body, Horizontal Swing Check Valves:
 - 1. NIBCO Model 918-B
 - 2. Other Manufacturers:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Milwaukee
- b. Stockham
- 3. Body Bolt: ASTM A-307 steel.
- 4. Bonnet: ASTM A-126 class B cast iron.
- 5. Body Gasket: Synthetic Fibers.
- 6. Body Nut: ASTM A-307 steel
- 7. Side Plug: ASTM B-16 alloy C36000 Brass.
- 8. Hanger Pin: ASTM B-16 alloy C36000 Brass.
- 9. Hanger: ASTM B-584 alloy C84400 cast bronze.
- Disc: ASTM B-584 alloy C84400 cast bronze or ASTM A-536 ductile iron w/bronze face ring.
- 11. Seat Ring: ASTM B-584 alloy C84400 cast bronze.
- 12. Disc Nut: ASTM B-16 alloy C36000.
- 13. Body: ASTM A-126 class B cast iron.
- 14. Disc Bolt: ASTM B-16 alloy C36000 Brass.
- 15. Disc Plate: ASTM A-126 class B cast iron.
- 16. Disc Cage: ASTM A-126 class B cast iron.
- 17. Rating: 125 psig SWP and 200 psig CWP.
- 18. Conform To: MSS SP-71 Type 1.
- B. Grooved-End, Ductile-Iron Spring Assisted Check Valves: Victaulic Series 716 with EPDM disc seal.
- C. Spring Actuated Silent Check Valves:
 - 1. NIBCO Model F-910
 - 2. Other Manufacturers:
 - a. Milwaukee
 - b. Stockham
 - 3. Body: ASTM A48 class 35 cast iron.
 - 4. Seat: ASTM B-584 alloy C83600 (B) bronze.
 - 5. Disc: ASTM B-584 alloy C83600 bronze.
 - 6. Spring: Type 302 ASTM A313 stainless steel.
 - 7. Bushing:
 - a. 6" and Smaller: ASTM B-16 brass
 - b. 8" and Larger: ASTM B-584 alloy C83600 bronze.
 - 8. Set Screws: Type 304 ASTM A-276 stainless steel.
 - 9. Rating: 200 psig CWP.
 - 10. Conform To: MIL-V-18436F

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Operate valves in positions from fully- pen to fully-closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- E. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access.
- C. Install valves in horizontal piping with stem at or above center of pipe.
- D. Install valves in position to allow full stem movement.
- E. Install chainwheels on operators for ball and butterfly valves 4" and larger and more than 96 inches above finished floor. Extend chains to 60 inches above finished floor.
- F. Install check valves for proper direction of flow and as follows:
 - 1. Swing Check Valves: In horizontal position with hinge pin level.
 - 2. Center-Guided and Plate-Type Check Valves: In horizontal or vertical position, between flanges.
 - 3. Lift Check Valves: With stem upright and plumb.

3.3 ADJUSTING

A. Adjust valve packing after piping systems have been tested and put into service but before final testing and balancing. Replace valves if persistent leaking occurs.

3.4 VALVE APPLICATIONS

- A. Refer to piping Sections for specific valve applications. If valve applications are not indicated, use the following:
 - 1. Shutoff Service: Ball or butterfly valves.
 - 2. Throttling Service: Ball or butterfly valves.
 - 3. Pump Discharge: Spring-loaded, lift-disc check valves and ball or butterfly valves.
- B. If valves with specified SWP classes or CWP ratings are not available, the same types of valves with higher SWP class or CWP ratings may be substituted.
- C. Domestic Water Piping: Use the following types of valves:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Valves, NPS 2" and Smaller: Two-Piece, Copper-Alloy Ball Valves (Full Port).
- 2. Valves, NPS 2-1/2" and 3":
 - a. Two-piece or three-piece, Copper-Alloy Ball Valves (Full Port).
 - b. Wafer-Lug, grooved-end, or flanged butterfly valves.
- 3. Valves, NPS 4" and Larger: Wafer-Lug, grooved-end, or flanged butterfly valves.
- 4. Pump Discharge Check Valves (Horizontal or Vertical), NPS 2" and Smaller: Bronze, Inline Lift Check Valves.
- 5. Horizontal Check Valves, NPS 2" and Smaller: Bronze, Horizontal Swing Check Valves.
- 6. Vertical Check Valves, NPS 2" and Smaller: Bronze, Inline Lift Check Valves.
- 7. Pump Discharge Check Valves (Horizontal or Vertical), NPS 2-1/2" and Larger: Grooved-End, Ductile-Iron Spring Assisted Check Valves or Spring Actuated Silent Check Valves.
- 8. Horizontal Check Valves, NPS 2-1/2" and Larger: Bronze, Horizontal Swing Check Valves.
- 9. Vertical Check Valves, NPS 2-1/2" and Larger: Grooved-End, Ductile-Iron Spring Assisted Check Valves or Spring Actuated Silent Check Valves.
- D. Gas Piping: Use the following types of valves:
 - 1. Valves, NPS 2" and Smaller: Two-Piece, Copper-Alloy Ball Valves (Full Port).
 - 2. Valves, NPS 2-1/2" and 3":
 - a. Two-piece or three-piece, Copper-Alloy Ball Valves (Full Port).
 - b. Wafer-Lug, grooved-end, or flanged butterfly valves.
 - 3. Valves, NPS 4" and Larger: Wafer-Lug, grooved-end, or flanged butterfly valves.
 - 4. Pump Discharge Check Valves (Horizontal or Vertical), NPS 2" and Smaller: Bronze, Inline Lift Check Valves.
 - 5. Horizontal Check Valves, NPS 2" and Smaller: Bronze, Horizontal Swing Check Valves.
 - 6. Vertical Check Valves, NPS 2" and Smaller: Bronze, Inline Lift Check Valves.
 - 7. Pump Discharge Check Valves (Horizontal or Vertical), NPS 2-1/2" and Larger: Grooved-End, Ductile-Iron Spring Assisted Check Valves or Spring Actuated Silent Check Valves.
 - 8. Horizontal Check Valves, NPS 2-1/2" and Larger: Bronze, Horizontal Swing Check Valves.
 - 9. Vertical Check Valves, NPS 2-1/2" and Larger: Grooved-End, Ductile-Iron Spring Assisted Check Valves or Spring Actuated Silent Check Valves.

END OF SECTION 220523

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 220529 - HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. MSS: Manufacturers Standardization Society of the Valve and Fittings Industry Inc.
- B. Terminology: As defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

1.3 PERFORMANCE REQUIREMENTS

- A. Design Requirement: Design trapeze pipe hangers and equipment supports, including comprehensive engineering analysis by a qualified professional engineer where using methods other than indicated.
- B. Structural Performance: Hangers and supports for HVAC piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
 - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test medium.
 - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
 - 3. Design seismic-restraint hangers and supports for piping and equipment.

1.4 OUALITY ASSURANCE

- A. Structural Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."
- B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.

PART 2 - PRODUCTS

2.1 METAL PIPE HANGERS AND SUPPORTS

A. Carbon-Steel Pipe Hangers and Supports:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
- 2. Galvanized Metallic Coatings: Pregalvanized or hot dipped.
- 3. Nonmetallic Coatings: Plastic coating, jacket, or liner.
- 4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
- 5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

B. Copper Pipe Hangers:

- 1. Description: MSS SP-58, Types 1 through 58, copper-coated-steel, factory-fabricated components.
- 2. Hanger Rods: Continuous-thread rod, nuts, and washer made of copper-coated steel.

2.2 TRAPEZE PIPE HANGERS

- A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.
- B. Trapeze Pipe Hanger Installation: Arrange for grouping of parallel runs of piping and support together on field-assembled channel systems.
 - 1. Assemble and provide according to manufacturer's written instructions. Center piping on channel to evenly distribute load.
 - 2. Pipe sizes and numbers shall be in accordance with the following:

TRAPEZE PIPE HANGER TABLE								
PIPE SIZE	4"	3"	2 ½"	2"	1 1/2"	1 1/4"	1"	TOTAL # of PIPES
NUMBER OF PIPES PERMITTED IN ONE CHANNEL SUPPORT	2	0	0	0	0	0	0	2
	0	2	2	0	0	0	0	4
	0	2	0	4	0	0	0	6
	0	2	0	0	6	0	0	8
	0	0	4	2	0	0	0	6
	0	0	4	0	2	2	0	8
	0	0	4	0	0	8	0	12
	0	0	0	6	2	2	2	12
	0	0	0	8	0	2	0	10
	0	0	0	0	14	0	0	14
	0	0	0	0	0	16	0	16

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

Notes:

- 1. Piping larger than 4" in diameter is not permitted in a channel support system.
- 2. Channel support systems shall be limited to eight (8) pipes per channel and two (2) channels (levels) per support system.
- 3. Smaller pipes can be substituted for larger pipes. For example two 3/4" pipes may be installed in lieu of two 1" pipes, or 2" in lieu of 3", etc.
- 4. Spacing shall be in accordance with requirements for the smallest supported pipe. Refer to other specification sections for spacing requirements. If spacing requirements are not indicated comply with MSS SP-69.

C. Metal Framing Systems:

- 1. Available Manufacturers:
 - a. Anvil International; a subsidiary of Mueller Water Products Inc.
 - b. Empire Industries, Inc.
 - c. ERICO International Corporation.
 - d. Haydon Corporation; H-Strut Division.
 - e. NIBCO INC.
 - f. PHD Manufacturing, Inc.
 - g. PHS Industries, Inc.
- 2. Description: Shop- or field-fabricated pipe-support assembly made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
- 3. Standard: Comply with MFMA-4.
- 4. Channels: Continuous slotted steel channel with inturned lips.
- 5. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
- 6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
- 7. Coating: Zinc.

2.3 THERMAL-HANGER SHIELD INSERTS

A. Available Manufacturers:

- 1. Carpenter & Paterson, Inc.
- 2. Clement Support Services.
- 3. ERICO International Corporation.
- 4. National Pipe Hanger Corporation.
- 5. PHS Industries, Inc.
- 6. Pipe Shields, Inc.; a subsidiary of Piping Technology & Products, Inc.
- 7. Piping Technology & Products, Inc.
- 8. Rilco Manufacturing Co., Inc.
- 9. Value Engineered Products, Inc.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Insulation-Insert Material for Cold Piping: ASTM C 552, Type II cellular glass with 100-psig or ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength and vapor barrier.
- C. Insulation-Insert Material for Hot Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate with 100-psig, ASTM C 552, Type II cellular glass with 100-psig, or ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength.
- D. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- E. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- F. Insert Length: Extend 2" beyond sheet metal shield for piping operating below ambient air temperature.

2.4 PIPE STANDS

- A. General Requirements for Pipe Stands: Shop- or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.
 - 1. Available Manufacturers:
 - a. Cooper B-Line Dura-Blok
 - b. MAPA Products
 - c. Mifab, Inc. C-Port
 - d. Miro Industries, Inc.
 - e. OMG, Inc.
 - f. PHP Systems/Design
 - g. Pipe Prop
 - h. Roof Top Blox
 - 2. Provide pipe supports for supporting gas, condensate, refrigeration lines, or hyrdronic piping on flat roof surfaces. Support shall rest on roof surface without penetrating the roof surface. Supports for condensate piping shall be adjustable vertically to ensure pipe slopes as required.
- B. Compact Pipe Stand: One-piece plastic unit with integral-rod roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.
- C. Curb Mounted Pipe Stands: Shop- or field-fabricated pipe supports made from structural-steel shapes, continuous-thread rods, and rollers, for mounting on permanent stationary roof curb.

2.5 EQUIPMENT SUPPORTS

A. Description: Welded, shop or field fabricated equipment support made from structural carbon-steel shapes unless indicated otherwise.

2.6 MISCELLANEOUS MATERIALS

A. Structural Steel: ASTM A 36/A 36M, carbon-steel plates, shapes, and bars; black and galvanized.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
 - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Provide hangers, supports, clamps, and attachments as required to properly support piping from the building structure.
- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69, MSS SP-89, and Table above. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.
- D. Thermal-Hanger Shield Installation: Provide in pipe hanger or shield for insulated piping.
- E. Pipe Stand Installation: Assemble components and mount on smooth roof surface. Do not penetrate roof membrane.
- F. Provide hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- H. Provide hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- I. Provide lateral bracing with pipe hangers and supports to prevent swaying.
- J. Provide building attachments within concrete slabs or attach to structural steel. Building attachments may not used on steel joists unless otherwise indicated. Provide additional attachments at concentrated loads, including valves, flanges, and strainers, 2-1/2" and larger and at changes in direction of piping. Provide concrete inserts before concrete is placed; fasten inserts to forms and provide reinforcing bars through openings at top of inserts.
- K. Load Distribution: Provide hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- L. Pipe Slopes: Provide hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- M. Insulated Piping:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Attach clamps and spacers to piping.
 - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating below Ambient Air Temperature: Provide thermal-hanger shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
- 2. Provide MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
- 3. Provide MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
- 4. Shield Dimensions for Pipe: Not less than the following:
 - a. Pipe $\frac{1}{4}$ " to $3-\frac{1}{2}$ ": 12 inches long and 0.048 inch thick.
 - b. Pipe 4": 12 inches long and 0.06 inch thick.
 - c. Pipe 5" and 6": 18 inches long and 0.06 inch thick.
 - d. Pipe 8" to 14": 24 inches long and 0.075 inch thick.
- 5. Pipes 8" and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
- 6. Thermal-Hanger Shields: Provide with insulation same thickness as piping insulation.

3.2 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make bearing surface smooth.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.3 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
 - 1. Provide materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.4 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.5 PAINTING

- A. Touchup: Unless otherwise indicated clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Provide same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and immediately apply galvanizing-repair paint. Paint shall comply with ASTM A 780.

3.6 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Provide hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.
- D. Provide nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Provide copper-plated pipe hangers and copper attachments for copper piping and tubing.
- F. Provide padded hangers for piping that is subject to scratching.
- G. Provide thermal-hanger shield inserts for insulated piping and tubing.
- H. Horizontal-Piping Hangers and Supports: Unless otherwise indicated provide the following:
 - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of stationary pipes $\frac{1}{2}$ " to 30".
 - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F pipes 4" to 14", requiring up to 4" of insulation.
 - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes ³/₄" to 14", requiring clamp flexibility and up to 4 inches of insulation.
 - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes ½" to 14" if little or no insulation is required.
 - 5. Pipe Hangers (MSS Type 5): For suspension of pipes ½" to 4", to allow off-center closure for hanger installation before pipe erection.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes ³/₄" to 8".
- 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes ½" to 8".
- 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes ½" to 8".
- 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes ½" to 8".
- 10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes ½" to 8".
- 11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS ½" to 3".
- 12. U-Bolts (MSS Type 24): For support of heavy pipes ½" to 14".
- 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
- 14. Pipe Saddle Supports (MSS Type 36): For support of pipes 4" to 14", with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
- 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes 4" to 14", with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
- 16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes 2-½" to 14" if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
- 17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes 1" to 14", from two rods if longitudinal movement caused by expansion and contraction might occur.
- 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes 2-½" to 14", from single rod if horizontal movement caused by expansion and contraction might occur.
- 19. Complete Pipe Rolls (MSS Type 44): For support of pipes 2" to 14" if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
- 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes 2" to 14" if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
- 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes 2" to 14"if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- I. Vertical-Piping Clamps: Unless otherwise indicated provide the following:
 - 1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers 3/4" to 14".
 - 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers ³/₄" to 14" if longer ends are required for riser clamps.
- J. Hanger-Rod Attachments: Unless otherwise indicated provide the following:
 - 1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 - 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 - 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 - 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 - 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 6. Flat Plate, Double Nut, and Washer as Detailed on Structural Drawings: For attaching to bar joists. Method of attachment to bar joists must be approved by the structural engineer and joist manufacturer.
- K. Building Attachments: Unless otherwise indicated provide the following:
 - 1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 - 2. Flat Plate, Double Nuts, and Washer as Detailed on Structural Drawings: For use under roof installations with bar-joist construction to attach to bottom chord of joist.
 - 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 - 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 - 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 - 6. C-Clamps (MSS Type 23): For structural shapes.
 - 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 - 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 - 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 - 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel Ibeams for heavy loads, with link extensions.
 - 11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 - 12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Provide one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
 - 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 - 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 - 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- L. Saddles and Shields: Unless otherwise indicated provide the followings:
 - 1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 - 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 - 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- M. Spring Hangers and Supports: Unless otherwise indicated provide the following:
 - 1. Restraint-Control Devices (MSS Type 47): To control pipe movement.
 - 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41, roll hanger with springs.
- 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
- 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
- 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
- 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
- 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- N. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- O. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- P. Provide powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where indicated in concrete construction.

END OF SECTION 220529

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 220553 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- C. Valve Schedules: For each piping system to include in maintenance manuals.

1.3 QUALITY ASSURANCE

A. ASME Compliance: Comply with ASME A13.1, "Scheme for the Identification of Piping Systems," for letter size, length of color field, colors, and viewing angles of identification devices for piping.

1.4 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

A. Metal Labels for Equipment:

- 1. Material and Thickness: Brass, Aluminum, or anodized aluminum, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
- 2. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- 3. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- 4. Fasteners: Stainless-steel rivets or self-tapping screws.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

5. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

B. Plastic Labels for Equipment:

- 1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.
- 2. Letter Color: White.
- 3. Background Color: Black.
- 4. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- 5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- 6. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- 7. Fasteners: Stainless-steel rivets or self-tapping screws.
- 8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- C. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified.
- D. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number and identify Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

2.2 WARNING SIGNS AND LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.
- B. Letter Color: White.
- C. Background Color: Red.
- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- G. Fasteners: Stainless-steel rivets or self-tapping screws.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

I. Label Content: Include caution and warning information, plus emergency notification instructions.

2.3 PIPE LABELS

- A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.
- B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.
- C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.
- D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings, pipe size, and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with piping system service lettering to accommodate both directions, or as separate unit on each pipe label to indicate flow direction.
 - 2. Lettering Size: At least 1-1/2 inches high.

2.4 STENCILS

- A. Stencils: Prepared with letter sizes according to ASME A13.1 for piping; minimum letter height of 1-1/4 inches for ducts; and minimum letter height of 3/4 inch for access panel and door markers, equipment markers, equipment signs, and similar operational instructions.
 - 1. Stencil Material: Metal or fiberboard.
 - 2. Stencil Paint: Exterior, gloss, black, unless otherwise indicated. Paint shall be low VOC and shall meet the requirements of section 09910. Paint may be in pressurized spray-can form.
 - 3. Identification Paint: Exterior, in colors according to ASME A13.1, unless otherwise indicated. Paint shall be low VOC and shall meet the requirements of section 09910.

2.5 VALVE TAGS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers, numbering scheme approved by Architect. Provide 5/32-inch hole for fastener.
 - 1. Material: 0.032-inch- thick brass or
 - 2. Material: 0.0375-inch- thick stainless steel or
 - 3. Material: 3/32-inch- thick laminated plastic with 2 black surfaces and white inner layer.
- B. Valve-Tag Fasteners: Brass wire-link or beaded chain; or S-hook.

2.6 VALVE SCHEDULES

A. Valve Schedules: For each piping system, on standard-size bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Valve-Schedule Frames: Glazed display frame for removable mounting on masonry walls for each page of valve schedule. Include mounting screws and hangers.
- 2. Frame: Finished hardwood or extruded aluminum.
- 3. Glazing: ASTM C 1036, Type I, Class 1, Glazing Quality B, 2.5-mm, single-thickness glass.

2.7 VALVE PLAN

- A. Valve Plan: Prepare a scale drawing. Provide the location and identity of each valve.
 - 1. Valve Plan Frames: Glazed display frame for removable mounting on masonry walls for each page of valve plan. Include mounting screws and hangers.
 - 2. Frame: Finished hardwood or extruded aluminum.
 - 3. Glazing: ASTM C 1036, Type I, Class 1, Glazing Quality B, 2.5-mm, single-thickness glass.

2.8 WARNING TAGS

- A. Warning Tags: Preprinted or partially preprinted, accident-prevention tags, of plasticized card stock with matte finish suitable for writing.
 - 1. Size: 3 by 5-1/4 inches minimum.
 - 2. Fasteners: Brass grommet and wire.
 - 3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
 - 4. Color: Yellow background with black lettering.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 EQUIPMENT LABEL INSTALLATION

- A. Install and permanently fasten equipment nameplates on each major item of plumbing equipment that does not have nameplate, or has a nameplate that is damaged or located where not easily visible. Locate nameplates where easily visible. Include nameplates for the following general categories of equipment:
 - 1. Fuel-burning units.
 - 2. Pumps, compressors, and other motor-driven equipment.
 - 3. Heat exchangers and similar equipment.
 - 4. Water heaters and storage tanks.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Install equipment markers with permanent adhesive on or near each major item of mechanical equipment. Data required for markers may be included on signs, and markers may be omitted if both are indicated.
 - 1. Letter Size: Minimum 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
 - 2. Data: Distinguish among multiple units, indicate operational requirements, indicate safety and emergency precautions, warn of hazards and improper operations, and identify units.
 - 3. Locate markers where accessible and visible. Include markers for the following general categories of equipment:
 - a. Main control and operating valves, including safety devices and hazardous units such as gas outlets.
 - b. Meters, gages, and thermometers.
 - c. Fuel-burning units.
 - d. Pumps, compressors, and other motor-driven equipment.
 - e. Heat exchangers and similar equipment.
 - f. Water heaters and storage tanks.
- C. Stenciled Equipment Marker Option: Stenciled markers may be provided instead of laminated-plastic equipment markers, at Installer's option, if lettering larger than 1 inch high is needed for proper identification because of distance from normal location of required identification.
- D. Install equipment signs with screws or permanent adhesive on or near each major item of mechanical equipment. Locate signs where easily visible.
 - 1. Identify mechanical equipment with equipment markers in the following color codes:
 - a. Green: For cooling equipment and components.
 - b. Yellow: For heating equipment and components.
 - c. Orange: For combination cooling and heating equipment and components.
 - d. Brown: For energy-reclamation equipment and components.
 - e. Blue: For equipment not listed in a through d
 - 2. Letter Size: Minimum 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
 - 3. Data: Distinguish among multiple units, indicate operational requirements, indicate safety and emergency precautions, warn of hazards and improper operations, and identify units.
- E. Install access panel markers with screws on equipment access panels.

3.3 PIPE LABEL INSTALLATION

A. Piping Color-Coding: Painting of piping is specified in other sections.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Stenciled Pipe Label Option: Stenciled labels may be provided instead of manufactured pipe labels, at Installer's option. Install stenciled pipe labels with painted, color-coded bands or rectangles on each piping system.
 - 1. Identification Paint: Use for contrasting background.
 - 2. Stencil Paint: Use for pipe marking.]
- C. Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
 - 1. Near each valve and control device.
 - 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 - 3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
 - 4. At access doors, manholes, and similar access points that permit view of concealed piping.
 - 5. Near major equipment items and other points of origination and termination.
 - 6. Spaced at maximum intervals of 25 feet.
 - 7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.
- D. Pipe Label Color Schedule:
 - 1. Domestic Cold Water Piping:
 - a. Background Color: Green.
 - b. Letter Color: White.
 - 2. Domestic Hot Water Piping:
 - a. Background Color: Green.
 - b. Letter Color: White.
 - 3. Sanitary Waste and Storm Drainage Piping:
 - a. Background Color: Green.
 - b. Letter Color: White.
 - 4. Propane Gas Piping:
 - a. Background Color: Yellow.
 - b. Letter Color: Black.

3.4 VALVE-TAG INSTALLATION

A. Install tags on valves and control devices in piping systems, except check valves; valves within factory-fabricated equipment units; plumbing fixture supply stops; shutoff valves; faucets; convenience and lawn-watering hose connections; and HVAC terminal devices and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following:
 - 1. Valve-Tag Size and Shape:
 - a. Domestic Cold Water: 1 ½", round.
 - b. Domestic Hot Water: 1 ½", round.
 - c. Domestic Hot Water Recirculation: 1 ½", round.
 - d. Propane: 2", round.
 - 2. Valve-Tag Color:
 - a. Domestic Cold Water: Blue.
 - b. Domestic Hot Water: Red.
 - c. Domestic Hot Water Recirculation: Red.
 - d. Propane: 2", Yellow.
 - 3. Letter Color:
 - Domestic Cold Water: Black.
 - b. Domestic Hot Water: White.
 - c. Domestic Hot Water Recirculation: White.
 - d. Propane: 2", Black.

3.5 VALVE SCHEDULE INSTALLATION

A. Mount valve schedules on wall in accessible location in each major equipment room and where directed by owner.

3.6 WARNING-TAG INSTALLATION

A. Write required message on, and attach warning tags to, equipment and other items where required.

3.7 ADJUSTING

A. Relocate mechanical identification materials and devices that have become visually blocked by other work.

3.8 CLEANING

A. Clean faces of mechanical identification devices and glass fronts of valve schedules and plans.

END OF SECTION 220553

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 220700 - PLUMBING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. Outdoor pipe: Pipe located outside the building insulation envelope.
- B. Plenum: An unoccupied space or void, on the conditioned side of the building insulation and vapor barrier, being used to return conditioned air to the inlet side of a return or exhaust fan either directly or via a duct connection. An example would be a space with air handling light fixtures or openings in the ceiling used to transport air through the ceiling and then to an open duct located above the ceiling in another location.
- C. Indirectly Conditioned Space: A space having no direct conditioning but, due to air movement induced by an exhaust, or return opening, is conditioned by makeup air from an adjacent space. An example would be a small toilet. Boiler rooms, fan rooms, and mechanical rooms do not qualify as indirectly conditioned spaces.
- D. Inside the Building Insulation Envelope: For the purposes of this section, boiler rooms, fan rooms, and mechanical rooms are considered to be OUTSIDE the building insulation envelope.
- E. Exposed: Visible from any angle without removal of building element or equipment.
- F. Concealed: Enclosed in building element or above ceiling such that it is not visible from any angle without removal of building element or equipment.

1.3 SUBMITTALS

- A. Product Data: Identify thermal conductivity, thickness, and jackets (both factory and field applied, if any), for each type of product indicated.
- B. Shop Drawings: Show fabrication and installation details for the following:
 - 1. Detail application of removable insulation covers.
 - 2. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
 - 3. Detail attachment and covering of heat tracing inside insulation.
 - 4. Detail insulation application at pipe expansion joints for each type of insulation.
 - 5. Detail insulation application at elbows, fittings, flanges, valves, and specialties for each type of insulation.
 - 6. Detail removable insulation at piping specialties, equipment connections, and access panels.
 - 7. Detail application of field-applied jackets.
 - 8. Detail application at linkages of control devices.
 - 9. Detail field application for each equipment type.

1.4 QUALITY ASSURANCE

A. Fire-Test-Response Characteristics: Insulation and related materials shall have fire-test-response characteristics indicated, as determined by testing identical products per ASTM E 84,

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing and inspecting agency.

- 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
- 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Ship insulation materials in containers marked by manufacturer with type, grade, and maximum use temperature.
- B. Ship Insulated Piping System Components on pallets and wood supports. Securely fasten and protect from damage. Store off the ground and cover with opaque waterproof tarp to protect materials from sunlight and rain.

1.6 COORDINATION

- A. Coordinate size and location of supports, hangers, and insulation shields specified in Section "Hangers and Supports for HVAC Piping and Equipment."
- B. Coordinate clearance requirements with piping Installer for piping insulation, duct Installer for duct insulation, and equipment Installer for equipment insulation.
- C. Maintain clearances required for maintenance.
- D. Coordinate installation and testing of heat tracing.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers:
 - 1. Mineral-Fiber Insulation:
 - a. CertainTeed Manson.
 - b. Johns Manville
 - c. Knauf FiberGlass GmbH.
 - d. Owens-Corning Fiberglas Corp.
 - e. Schuller International, Inc.
 - 2. Flexible Elastomeric Thermal Insulation:
 - a. Armstrong World Industries, Inc.
 - b. Rubatex Corp.
 - 3. Polyolefin Insulation:
 - a. Armstrong World Industries, Inc.
 - b. IMCOA.
 - 4. Closed-Cell Phenolic-Foam Insulation:
 - a. Kooltherm Insulation Products, Ltd.
 - 5. Removable Insulation Covers:
 - a. Advance Thermal Corp.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.2 INSULATION MATERIALS

- A. Comply with requirements in Part 3 schedule articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- F. Mineral-Fiber Board: Glass fibers bonded with a thermosetting resin. Comply with ASTM C 612, Type IB, with factory applied FSK Jacket. Meet the requirements of ASTM C 1290, Type III, inorganic glass fibers bonded by a thermosetting resin to maximum service temperature of 250°F.. Faced insulation shall not exceed 25 Flame Spread, 50 Smoke Developed when tested in accordance with ASTM E84.
- G. Semi-Rigid Mineral-Fiber Board: Glass fibers bonded with a thermosetting resin. Comply with ASTM C 1136, Type I, II, III, & IV with factory applied all-service jacket (ASJ) or Type II, IV with factory applied Foil Scrim Kraft (FSK) jacket.
- H. Mineral-Fiber Pipe Insulation: Glass fibers bonded with a thermosetting resin complying with the following:
 - 1. Preformed Pipe Insulation: Comply with ASTM C 547, Type 1, with factory-applied, all-purpose, vapor-retarder jacket.
 - 2. Semi-Rigid Mineral-Fiber Board: Glass fibers bonded with a thermosetting resin. Comply with ASTM C 1136, Type I, II, III, IV with factory applied all-service jacket (ASJ) or Type II, IV with factory applied Foil Scrim Kraft (FSK) jacket.
 - 3. Mineral-Fiber Insulating Cements: Comply with ASTM C 195.
 - 4. Expanded or Exfoliated Vermiculite Insulating Cements: Comply with ASTM C 196.
 - 5. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449/C 449M.
- I. Flexible Elastomeric: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials and Type II for sheet materials.
 - 1. Adhesive: As recommended by insulation material manufacturer.
 - 2. Ultraviolet-Protective Coating: As recommended by insulation manufacturer.
- J. Closed-Cell Phenolic-Foam: Block insulation of rigid, expanded, closed-cell structure. Comply with ASTM C 1126, Type II, Grade 1.
- K. Prefabricated Thermal Insulating Fitting Covers: Comply with ASTM C 450 for dimensions used in preforming insulation to cover valves, elbows, tees, and flanges.

2.3 FIELD-APPLIED JACKETS

- A. General: ASTM C 921, Type 1, unless otherwise indicated.
- B. Glass Cloth: Woven glass-fiber fabric, plain weave, minimum 8 ounces per square yard.
- C. Foil and Paper Jacket: Laminated, glass-fiber-reinforced, flame-retardant kraft paper and aluminum foil.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. PVC Jacket: High-impact, ultraviolet-resistant PVC; 20 mils thick; roll stock ready for shop or field cutting and forming.
 - 1. Adhesive: As recommended by insulation material manufacturer.
 - 2. PVC Duct Jacket Color: White or gray.
 - 3. PVC Pipe Jacket Color: Color-code piping jackets based on materials contained within the piping system.
- E. Aluminum Jacket: Deep corrugated sheets manufactured from aluminum alloy complying with ASTM B 209, and having an integrally bonded moisture barrier over entire surface in contact with insulation. Factory cut and rolled to indicated sizes. Comply with ASTM B 209, 3003 alloy, H-14 temper.
 - 1. Finish and Thickness: Stucco-embossed finish, 0.016 inch thick.
 - 2. Moisture Barrier: 1-mil- thick, heat-bonded polyethylene and kraft paper.
 - 3. Elbows: Preformed, 45- and 90-degree, short- and long-radius elbows; same material, finish, and thickness as jacket.
- F. Stainless-Steel Jacket: Deep corrugated sheets of stainless steel complying with ASTM A 666, Type 304 or 316; 0.10 inch thick; and roll stock ready for shop or field cutting and forming to indicated sizes.
 - 1. Moisture Barrier: 1-mil-thick, heat-bonded polyethylene and kraft paper.
 - 2. Elbows: Gore type, for 45- and 90-degree elbows in same material, finish, and thickness as jacket.
 - 3. Jacket Bands: Stainless steel, Type 304, 3/4 inch wide.
- G. Heavy PVC Pipe Fitting Covers: Factory-fabricated fitting covers manufactured from 30-milthick, high-impact, ultraviolet-resistant PVC.
 - 1. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories for the disabled.
 - 2. Adhesive: As recommended by insulation material manufacturer.
- H. Standard PVC Pipe Fitting Covers: Factory-fabricated fitting covers manufactured from 20-mil-thick, high-impact, ultraviolet-resistant PVC.
 - 1. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories for the disabled.
 - 2. Adhesive: As recommended by insulation material manufacturer.

2.4 REMOVABLE INSULATION COVERS

A. Pre-manufactured easily removable insulation cover/blanket intended for insulation of equipment and devices requiring periodic maintenance.

2.5 ACCESSORIES AND ATTACHMENTS

- A. Glass Cloth and Tape: Comply with MIL-C-20079H, Type I for cloth and Type II for tape. Woven glass-fiber fabrics, plain weave, presized a minimum of 8 oz./sq. yd..
 - 1. Tape Width: 4 inches.
- B. Bands: 3/4 inch wide, in one of the following materials compatible with jacket:
 - 1. Stainless Steel: ASTM A 666, Type 304; 0.020 inch thick.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Galvanized Steel: 0.005 inch thick.
- 3. Aluminum: 0.007 inch thick.
- 4. Brass: 0.010 inch thick.
- 5. Nickel-Copper Alloy: 0.005 inch thick.
- C. Wire: 0.080-inch, nickel-copper alloy; 0.062-inch, soft-annealed, stainless steel; or 0.062-inch, soft-annealed, galvanized steel.
- D. Weld-Attached Anchor Pins and Washers: Copper-coated steel pin for capacitor-discharge welding and galvanized speed washer. Pin length sufficient for insulation thickness indicated.
 - 1. Welded Pin Holding Capacity: 100 lb for direct pull perpendicular to the attached surface.
- E. Adhesive-Attached Anchor Pins and Speed Washers: Galvanized steel plate, pin, and washer manufactured for attachment to duct, pipe, plenum and breeching with adhesive. Pin length sufficient for insulation thickness indicated.
 - 1. Adhesive: Recommended by the anchor pin manufacturer as appropriate for surface temperatures of ducts, pipes, plenums, and breechings; and to achieve a holding capacity of 100 lb. for direct pull perpendicular to the adhered surface.
- F. Self-Adhesive Anchor Pins and Speed Washers: Galvanized steel plate, pin, and washer manufactured for attachment to duct, pipe, and plenum with adhesive. Pin length sufficient for insulation thickness indicated.

2.6 VAPOR RETARDERS

A. Mastics: Materials recommended by insulation material manufacturer that are compatible with insulation materials, jackets, and substrates.

2.7 REMOVABLE INSULATION COVERS

A. Pre-manufactured easily removable insulation cover/blanket intended for insulation of equipment and devices requiring periodic maintenance.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation and other conditions affecting performance of insulation application.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

3.3 GENERAL APPLICATION REQUIREMENTS

A. Apply insulation materials, accessories, and finishes according to the manufacturer's written instructions; with smooth, straight, and even surfaces; and free of voids throughout the length of piping, and fittings.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Refer to schedules at the end of this Section for materials, forms, jackets, and thickness required for each system.
- C. Use accessories compatible with insulation materials and suitable for the service. Use accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Apply multiple layers of insulation with seams staggered.
- E. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- F. Seal joints and seams with vapor-retarder mastic on insulation indicated to receive a vapor retarder.
- G. Keep insulation materials dry at all times. Insulation that becomes wet or is otherwise damaged beyond repair, shall be removed immediately and replaced. Replacement material and installation shall be in accordance with these specifications.
- H. Apply insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by the insulation material manufacturer.
- I. Apply insulation with the minimum number of joints practical.
- J. Apply insulation over fittings, valves, and specialties, with continuous thermal and vapor-retarder integrity, unless otherwise indicated.
- K. Refer to special instructions for applying insulation over fittings, valves, and specialties.
- L. Hangers and Anchors: Where vapor retarder is indicated, seal penetrations in insulation at hangers, supports, anchors, and other projections with vapor-retarder mastic.
 - 1. Apply insulation continuously through hangers and around anchor attachments.
 - 2. For insulation application where vapor retarders are indicated, extend insulation on anchor legs at least 12 inches from point of attachment to pipe and taper insulation ends. Seal tapered ends with a compound recommended by the insulation material manufacturer to maintain vapor retarder.
 - 3. Install insert materials and apply insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by the insulation material manufacturer.
 - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect the jacket from tear or puncture by the hanger, support, and shield.
- M. Insulation Terminations: For insulation application where vapor retarders are indicated, seal ends with a compound recommended by the insulation material manufacturer to maintain vapor retarder.
- N. Apply insulation with integral jackets as follows:
 - 1. Pull jacket tight and smooth.
 - 2. Joints and Seams: Cover with tape and vapor retarder as recommended by insulation material manufacturer to maintain vapor seal.
 - 3. Vapor-Retarder Mastics: Where vapor retarders are indicated, apply mastic on seams and joints and at ends adjacent to duct flanges, pipe joints, and fittings.
- O. Cut insulation according to manufacturer's written instructions to prevent compressing insulation to less than 75 percent of its nominal thickness.
- P. Install vapor-retarder mastic on ducts, pipes, plenums, and equipment.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Ducts, pipes, plenums, and equipment with Vapor Retarders: Overlap insulation facing at seams and seal with vapor-retarder mastic and pressure-sensitive tape having same facing as insulation. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-retarder seal.
- 2. Ducts, pipes, plenums, and equipment without Vapor Retarders: Overlap insulation facing at seams and secure with outward clinching staples and pressure-sensitive tape having same facing as insulation.
- Q. Roof Penetrations: Apply insulation for interior applications to a point even with top of roof flashing.
 - 1. Seal penetrations with vapor-retarder mastic.
 - 2. Apply insulation for exterior applications tightly joined to interior insulation ends.
 - 3. Seal insulation to roof flashing with vapor-retarder mastic.
- R. Interior Wall and Partition Penetrations: Apply insulation continuously through walls and partitions, except fire-rated walls and partitions.
- S. Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire/smoke damper sleeves for fire-rated wall and partition penetrations.
- T. Floor Penetrations: Terminate insulation at underside of floor assembly and at floor support at top of floor.
 - 1. For insulation indicated to have vapor retarders, taper termination and seal insulation ends with vapor-retarder mastic.

3.4 MINERAL-FIBER INSULATION APPLICATION

- A. Board Applications for Ducts, Plenums, & Equipment: Secure board insulation with adhesive and anchor pins and speed washers.
 - 1. Apply adhesives according to manufacturer's recommended coverage rates per square foot, for 100 percent coverage of duct, plenum, & equipment surfaces.
 - 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings, transitions, and equipment. Adhesive may be omitted from top surface of horizontal rectangular ducts.
 - 3. Space anchor pins as follows:
 - a. On duct & equipment sides with dimensions 18 inches and smaller, along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - b. On duct & equipment sides with dimensions larger than 18 inches. Space 16 inches o.c. each way, and 3 inches maximum from insulation joints. Apply additional pins and clips to hold insulation tightly against surface at bracing.
 - c. Anchor pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
 - d. Do not compress insulation to less than 75% of its original thickness during installation.
 - 4. Cut excess portion of pins extending beyond speed washers. Cover exposed pins and washers with tape matching insulation facing.
 - 5. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation segment with 1/2-inch staples, 1-inch o.c., and cover with pressure-sensitive tape having same facing as insulation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 6. Apply insulation on rectangular duct elbows and transitions with a full insulation segment for each surface. Groove and score insulation to fit as closely as possible to outside and inside radius of elbows. Apply insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
- 7. Insulate duct and equipment stiffeners, hangers, and flanges that protrude beyond the insulation surface with 6" wide strips of the insulating materia. Secure on alternating sides of stiffener, hanger, and flange with anchor pins spaced 6 inches o.c.
- 8. Apply vapor-retarder mastic to open joints, breaks, and punctures for insulation indicated to receive vapor retarder.

3.5 FLEXIBLE ELASTOMERIC THERMAL INSULATION APPLICATION

- A. Apply insulation to ducts, plenums, and equipment as follows:
 - 1. Follow the manufacturer's written instructions for applying insulation.
 - 2. Seal longitudinal seams and end joints with manufacturer's recommended adhesive. Cement to avoid openings in insulation that will allow passage of air to the duct, plenum, and equipment surface.

3.6 CLOSED-CELL PHENOLIC-FOAM INSULATION APPLICATION

- A. Apply insulation as follows:
 - 1. Secure each layer of insulation with stainless-steel bands at 12-inch intervals and tighten without deforming the insulation materials.
 - 2. Apply two-layer insulation with joints tightly butted and staggered at least 3 inches. Secure inner layer with 0.062-inch, soft-annealed, stainless steel wire spaced at 12-inch intervals. Secure outer layer with stainless-steel bands at 12-inch intervals.
 - 3. On exposed applications, finish insulation with a skim coat of mineral-fiber, hydraulic-setting cement to surface of installed insulation. When dry, apply flood coat of lagging adhesive and press on one layer of glass cloth or tape. Overlap edges at least 1 inch. Apply finish coat of lagging adhesive over glass cloth or tape. Thin the finish coat to achieve smooth finish.

3.7 FIELD-APPLIED JACKET APPLICATION

- A. Apply glass-cloth jacket, where indicated, directly over bare insulation or insulation with factory-applied jackets.
 - 1. Apply jacket smooth and tight to surface with 2-inch overlap at seams and joints.
 - 2. Embed glass cloth between two 0.062-inch- thick coats of jacket manufacturer's recommended adhesive.
 - 3. Completely encapsulate insulation with jacket, leaving no exposed raw insulation.

3.8 FINISHES

- A. Glass-Cloth Jacketed Insulation: Paint insulation finished with glass-cloth jacket as indicated.
- B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.
- C. Color: Final color shall be as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.9 APPLICATIONS

- A. Insulation materials and thickness are specified at the end of this Section.
- B. Insulate all pipe and equipment:
 - 1. Insulate pipe in accordance with the application schedule(s) below.
 - 2. Exceptions: Unless otherwise indicated, do not apply insulation to the following systems, materials, and equipment:
 - a. Vibration-control devices.
 - b. Testing agency labels and stamps.
 - c. Nameplates and data plates.
 - d. Manholes.
 - e. Handholes.
 - f. Cleanouts.
 - g. Plastic Condensate Drain piping.
 - h. Factory-insulated equipment.
 - i. Flexible connectors.

3.10 INDOOR APPLICATION SCHEDULE (ABOVE GRADE):

- A. Service: Domestic hot water and domestic circulated hot water.
 - 1. Insulation Material: Mineral fiber preformed or flexible elastomeric pipe insulation.
 - 2. Insulation Thickness: Apply the following insulation thicknesses:
 - a. Copper Pipe, ½" through 1½" in diameter: 1"
 - b. Copper Pipe, 1½" through 3" in diameter: 1½"
 - c. Copper Pipe, larger than 3" in diameter: 2"
 - 3. Vapor Retarder Required: No.
 - 4. Finish: Exposed = Painted, concealed = none.
- B. Service: Domestic cold water.
 - 1. Insulation Material: Mineral fiber preformed or flexible elastomeric pipe insulation.
 - 2. Insulation Thickness: ½"
 - 3. Vapor Retarder Required: Yes.
 - 4. Finish: Exposed = Painted, concealed = none.
- C. Service: Rainwater conductors (Including secondary roof drain conductors). Insulate first thirty linear feet of piping including vertical piping from drain body and first horizontal piping run. If a second vertical run occurs before thirty linear feet is reached, terminate insulation at end of first horizontal run.
 - 1. Insulation Material: Mineral fiber preformed pipe insulation with Factory Applied FSK Jacket.
 - 2. Insulation Thickness: 1"
 - 3. Vapor Retarder Required: Yes.
 - 4. Finish: Exposed = Painted, concealed = none.
- D. Service: Roof drain and overflow drain bodies.
 - 1. Insulation Material: Semi-Rigid Mineral-Fiber Board Thermal Insulation
 - 2. Insulation Thickness: 1½"
 - 3. Vapor Retarder Required: Yes.
 - 4. Finish: Exposed = Painted, concealed = none.
- E. Service: Exposed piping:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Mineral fiber preformed pipe insulation with Factory Applied FSK Jacket.
- 2. Insulation Thickness: 1"
- 3. Vapor Retarder Required: Yes.
- 4. Finish: Exposed = Painted, concealed = none.
- F. Service: Floor Drains, Traps, and Sanitary Drain Piping within 10 Feet of Drain Receiving Drainage from any Equipment. Measurement shall be pipe length.
 - 1. Insulation Material: Mineral fiber preformed pipe insulation with Factory Applied FSK Jacket.
 - 2. Insulation Thickness: 1"
 - 3. Vapor Retarder Required: Yes.
 - 4. Finish: Exposed = Painted, concealed = none.
- G. Service: Condensate Drains, & Traps.
 - 1. Insulation Material: Mineral fiber preformed pipe insulation with Factory Applied FSK Jacket.
 - 2. Insulation Thickness: 1"
 - 3. Vapor Retarder Required: Yes.
 - 4. Finish: Exposed = Painted, concealed = none.
- H. Service: Equipment Non-condensate Drains, & Traps.
 - 1. Insulation Material: Mineral fiber preformed pipe insulation with Factory Applied FSK Jacket.
 - 2. Insulation Thickness: 1"
 - 3. Vapor Retarder Required: Yes.
 - 4. Finish: Exposed = Painted, concealed = none.

3.11 INDOOR APPLICATION SCHEDULE (BELOW GRADE):

1. None required.

END OF SECTION 220700

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 221116 - DOMESTIC WATER PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 PERFORMANCE REQUIREMENTS

- A. Provide components and installation capable of producing domestic water piping systems with the following minimum working-pressure ratings, unless otherwise indicated:
 - 1. Domestic Water Service Piping: 160 psig.
 - 2. Domestic Water Distribution Piping: 125 psig.

1.3 SUBMITTALS

A. Product Data: For pipe, tube, fittings, and couplings.

1.4 QUALITY ASSURANCE

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 61, "Drinking Water System Components-Health Effects; Sections 1 through 9," for potable domestic water piping and components.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

- A. Refer to Part 3 "Piping Applications" Article for applications of pipe, tube, fitting, and joining materials.
- B. Transition Couplings for Underground Pressure Piping: AWWA C219, metal, sleeve-type coupling or other manufactured fitting the same size as, with pressure rating at least equal to and ends compatible with, piping to be joined.
- C. Mechanically formed outlets: Branch connections utilizing the T-Drill method of forming outlets and making branch connections.
- D. Press fittings:
 - 1. Propress by Vieaga
 - 2. Xpress by Elkhart Products

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

a. and nuts.

2.2 COPPER TUBING

- A. Soft Copper Tube: ASTM B 88, Type K, water tube, annealed temper.
 - 1. Copper Pressure Fittings: ASME B16.18, cast-copper-alloy or ASME B16.22, wrought-copper, solder-joint fittings. Furnish wrought-copper fittings if indicated.
 - 2. Bronze Flanges: ASME B16.24, Class 150, with solder-joint end. Furnish Class 300 flanges if required to match piping.
 - 3. Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body, with ball-and-socket, metal-to-metal seating surfaces and solder-joint or threaded ends.
- B. Hard Copper Tube: ASTM B 88, Type L, water tube, drawn temper.
 - 1. Copper Pressure Fittings: ASME B16.18, cast-copper-alloy or ASME B16.22, wrought-copper, solder-joint fittings. Furnish wrought-copper fittings if indicated.
 - 2. Bronze Flanges: ASME B16.24, Class 150, with solder-joint end. Furnish Class 300 flanges if required to match piping.
 - 3. Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body, with ball-and-socket, metal-to-metal seating surfaces and solder-joint or threaded ends.
 - 4. Copper, Grooved-End Fittings: ASTM B 75 copper tube or ASTM B 584 bronze castings.
 - a. Copper-Tubing, Keyed Couplings: Copper-tube dimensions and design similar to AWWA C606. Include ferrous housing sections, gasket suitable for hot water, and bolts and nuts.

PART 3 - EXECUTION

3.1 EXCAVATION

A. Refer to other sections for excavating, trenching, and backfilling.

3.2 PIPING APPLICATIONS

- A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below, unless otherwise indicated.
- B. Flanges may be used on aboveground piping, unless otherwise indicated.
- C. Grooved joints may be used on aboveground grooved-end piping.
- D. Fitting Options:
 - 1. Press Fittings: Mechanically crimped fittings with neoprene gasket.
- E. Underground Domestic Water Service Piping: Match civil materials to first flange.
- F. Aboveground Domestic Water Piping: Use the following piping materials for each size range:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. 1-1/2" and Smaller: Hard copper tube, Type L copper pressure fittings; and soldered joints.
- 2. 2": Hard copper tube, Type L copper pressure fittings; and soldered joints or hard copper tube, Type L with grooved ends; copper grooved-end fittings; copper-tubing, keyed couplings; and grooved joints.
- 3. 2-1/2" and above": Hard copper tube, Type L copper pressure fittings; and soldered joints or hard copper tube, Type L with grooved ends; copper grooved-end fittings; copper-tubing, keyed couplings; and grooved joints.
- G. Underground Domestic Water Piping: Use the following piping materials for each size range:
 - 1. 2" and Smaller: Soft copper tube, Type K copper pressure fittings; and soldered joints with no joints permitted below concrete slabs.
 - 2. 2-1/2" and above: Soft copper tube, Type K copper pressure fittings; and soldered joints.

3.3 VALVE APPLICATIONS

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
 - 1. Shutoff Duty: Use bronze ball valves for piping NPS 2 and smaller. Use cast-iron butterfly valves with flanged ends for piping NPS 2-1/2 and larger.
 - 2. Throttling Duty: Use bronze ball valves for piping NPS 2 and smaller. Use cast-iron butterfly valves with flanged ends for piping NPS 2-1/2 and larger.
 - 3. Hot-Water-Piping, Balancing Duty: Use automatic flow control valves.
 - 4. Drain Duty: Hose-end drain valves.
- B. Grooved-end valves may be used with grooved-end piping.

3.4 PIPING INSTALLATION

- A. Extend domestic water service piping to exterior water distribution piping in sizes and locations indicated.
- B. Install underground copper according to CDA's "Copper Tube Handbook."
- C. Install cast-iron sleeve with water stop and mechanical sleeve seal at each service pipe penetration through foundation wall. Select number of interlocking rubber links required to make installation watertight.
- D. Install aboveground domestic water piping level and plumb.
- E. Fill water piping. Check components to determine that they are not air bound and that piping is full of water.
- F. Perform the following steps before operation:
 - 1. Close drain valves, hydrants, and hose bibbs.
 - 2. Open shutoff valves to fully open position.
 - 3. Open throttling valves to proper setting.
 - 4. Remove plugs used during testing of piping and plugs used for temporary sealing of piping during installation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 5. Remove and clean strainer screens. Close drain valves and replace drain plugs.
- 6. Remove filter cartridges from housings, and verify that cartridges are as specified for application where used and that cartridges are clean and ready for use.
- G. Check plumbing equipment and verify proper settings, adjustments, and operation. Do not operate water heaters before filling with water.
- H. Check plumbing specialties and verify proper settings, adjustments, and operation.
 - 1. Water-Pressure Regulators: Set outlet pressure at 80 psig maximum, unless otherwise indicated.
- I. Energize pumps and verify proper operation.

3.5 JOINT CONSTRUCTION

- A. Soldered Joints: Use ASTM B 813, water-flushable, lead-free flux; ASTM B 32, lead-free-alloy solder; and ASTM B 828 procedure, unless otherwise indicated.
- B. Grooved Joints: Assemble joints with keyed-coupling housing, gasket, lubricant, and bolts according to coupling and fitting manufacturer's written instructions.
- C. Mechanically crimped fittings shall be installed in accordance with manufacturer's installation instructions.

3.6 VALVE INSTALLATION

- A. Install sectional valve close to water main on each branch and riser serving plumbing fixtures or equipment. Use ball valves for piping NPS 2 and smaller. Use butterfly valves for piping NPS 2-1/2 and larger.
- B. Install shutoff valve on each water supply to equipment and on each water supply to plumbing fixtures without supply stops. Use ball valves for piping NPS 2 and smaller. Use butterfly valves for piping NPS 2-1/2 and larger.
- C. Install balancing valve in each hot-water circulation return branch and discharge side of each pump and circulator. Use ball valves for piping NPS 2 and smaller and butterfly valves for piping NPS 2-1/2 and larger.

3.7 HANGER AND SUPPORT INSTALLATION

- A. Refer to Section 220529 "Hangers and Supports for Plumbing Piping" for pipe hanger and support devices.
- B. Install the following:
 - 1. Vertical Piping: MSS Type 8 or Type 42, clamps.
 - 2. Individual, Straight, Horizontal Piping Runs: According to the following:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
 - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Longer Than 100 Feet, if indicated: MSS Type 49, spring cushion rolls.
- 3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
- 4. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Support vertical piping and tubing at base and at each floor.
- D. Rod diameter may be reduced 1 size for double-rod hangers, to a minimum of 3/8 inch.
- E. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
 - 1. NPS 3/4 and Smaller: 60 inches with 3/8-inch rod.
 - 2. NPS 1 and NPS 1-1/4: 72 inches with 3/8-inch rod.
 - 3. NPS 1-1/2 and NPS 2: 96 inches with 3/8-inch rod.
 - 4. NPS 2-1/2: 108 inches with 1/2-inch rod.
 - 5. NPS 3 to NPS 5: 10 feet with 1/2-inch rod.
 - 6. NPS 6: 10 feet with 5/8-inch rod.
 - 7. NPS 8: 10 feet with 3/4-inch rod.
- F. Install supports for vertical copper tubing every 10 feet.
- G. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.
- H. Where bends in the pipe occur, place hangers 1/3 of the maximum allowed spacing distance of the bend (i.e. is the maximum span is 12 feet, the hanger shall be 4 feet from the bend. Pipe shall be supported from both sides of the bend.

3.8 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment and machines to allow service and maintenance.
- C. Connect domestic water piping to exterior water service piping. Use transition fitting to join dissimilar piping materials.

3.9 FIELD QUALITY CONTROL

- A. Inspect domestic water piping as follows:
 - 1. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.
 - 2. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:
 - a. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- b. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- 3. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- 4. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

B. Test domestic water piping as follows:

- 1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
- 2. Leave uncovered and unconcealed new, altered, extended, or replaced domestic water piping until it has been tested and approved. Expose work that was covered or concealed before it was tested.
- 3. Cap and subject piping to static water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials. Isolate test source and allow to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.
- 4. Repair leaks and defects with new materials and retest piping or portion thereof until satisfactory results are obtained.
- 5. Prepare reports for tests and required corrective action.

3.10 ADJUSTING

- A. Adjust balancing valves in hot-water-circulation return piping to provide adequate flow.
 - 1. Manually adjust ball-type balancing valves in hot-water-circulation return piping to provide flow of hot water in each branch.

3.11 CLEANING

- A. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.
- B. Clean and disinfect potable domestic water piping as follows:
 - 1. Purge new piping and parts of existing domestic water piping that have been altered, extended, or repaired before using.
 - 2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction or, if methods are not prescribed, procedures described in AWWA C651, AWWA C652 or as described below:
 - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
 - b. Fill and isolate system according to either of the following:
 - 1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.
 - 2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for three hours.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
- d. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedures if biological examination shows contamination.
- C. Prepare and submit reports of purging and disinfecting activities to authorities having jurisdiction.

END OF SECTION 221116

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 221119 - DOMESTIC WATER PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 PERFORMANCE REQUIREMENTS

A. Minimum Working Pressure for Domestic Water Piping Specialties: 125 psig, unless otherwise indicated.

1.3 SUBMITTALS

- A. Product Data: For each type of product proposed.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Operation and Maintenance Data: For domestic water piping specialties to include in emergency, operation, and maintenance manuals.

1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. NSF Compliance: Comply with NSF 61, "Drinking Water System Components Health Effects; Sections 1 through 9."

PART 2 - PRODUCTS

2.1 VACUUM BREAKERS

- A. Pipe-Applied, Atmospheric-Type (Anti-siphon) Vacuum Breakers:
 - 1. Available Manufacturers:
 - a. Ames Co.
 - b. Apollo Valves Apollo Valves Conbraco Industries, Inc.
 - c. Watts Industries, Inc.; Water Products Div.
 - d. Zurn Plumbing Products Group; Wilkins Div.
 - 2. Standard: ASSE 1001.
 - 3. Sizes: ³/₄" thru 3" as required to match connected piping.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Body: Brass or Bronze.
- 5. Inlet and Outlet Connections: Threaded.
- 6. Finish: Rough bronze or chrome plated.

B. Pressure Vacuum Breakers:

- 1. Available Manufacturers:
 - a. Ames Co.
 - b. Apollo Valves Apollo Valves Conbraco Industries, Inc.
 - c. Watts Industries, Inc.; Water Products Div.
 - d. Zurn Plumbing Products Group; Wilkins Div.
- 2. Standard: ASSE 1020.
- 3. Operation: Continuous-pressure applications.
- 4. Accessories:
 - a. Valves: Ball type, on inlet and outlet.

C. Spill-Resistant Vacuum Breakers:

- 1. Available Manufacturers:
 - a. Apollo Valves Apollo Valves Conbraco Industries, Inc.
 - b. Watts Industries, Inc.; Water Products Div.
- 2. Standard: ASSE 1056.
- 3. Operation: Continuous-pressure applications.
- 4. Sizes: ³/₄" thru 1" as required to match connected piping.
- 5. Accessories:
 - a. Valves: Ball type, on inlet and outlet.

2.2 BACKFLOW PREVENTERS

- A. Reduced-Pressure-Zone (RPZ) Backflow Preventers:
 - 1. Available Manufacturers:
 - a. Ames Co.
 - b. Apollo Valves Apollo Valves Conbraco Industries, Inc.
 - c. Watts Industries, Inc.; Water Products Div.
 - d. Zurn Plumbing Products Group; Wilkins Div.
 - 2. Standard: ASSE 1013.
 - 3. Operation: Continuous-pressure applications.
 - 4. Pressure Loss: 10 psig maximum, through middle 1/3 of flow range.
 - 5. Sizes: 3/4" thru 10"
 - 6. Body: Brass or bronze for 2" and smaller; cast iron or steel with interior lining complying with AWWA C550 or that is FDA approved for 2 ½" and larger.
 - 7. Configuration: Comply with drawing requirements.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

8. Accessories:

- a. Valves: Ball type with threaded ends on inlet and outlet of 2" and smaller; outside screw and yoke gate-type with flanged ends on inlet and outlet of 2 ½" and larger.
- b. Air-Gap Fitting: ASME A112.1.2, matching backflow-preventer connection.

2.3 AUTOMATIC FLOW CONTROL VALVES

A. Manufacturers:

- 1. Bell & Gossett
- 2. Flow Design, Inc.
- 3. Griswold Controls
- 4. Hays Fluid Controls
- 5. Pro Hydronic Specialties
- B. Valves shall be factory set to maintain constant flow with plus or minus 10 percent. Each valve shall have an identification tag attached by chain, and be factory marked with the zone or equipment identification, valve number, and flow rate. Valve shall be line size and as follows:
 - 1. Body: Gray-iron or brass, designed for 175 psig at 200 deg For; brass or ferrous-metal, designed for 300 psig at 250 deg F.
 - 2. Cartridge: Stainless steel or nickel chrome plated brass, tamperproof, self-cleaning, piston-spring assembly, or polyphenylsulfone orifice seat with polymer diaphragm (Hays) removable for inspection or replacement.
 - 3. Adjustment: Flow and pressure differential shall be adjustable by cartridge replacement.
 - 4. Configuration: "Y" or other permitting cartridge replacement without valve removal for sizes 2" and smaller.
 - 5. Sizes: Match connecting pipe.
 - 6. Accessories:
 - a. Provide unions and isolation valves or other configuration permitting cartridge replacement with valve removal for sizes larger than 2."
 - b. Minimum pressure differential shall not exceed 2 psi (unless otherwise indicated)
 - c. Maximum pressure differential shall not be less than 32 psi (unless otherwise indicated).
 - d. Flow rates shall be as indicated on equipment schedules on the drawings.
 - e. Valves shall be installed in return piping.
 - f. Ball valves and unions included as part of the valve package may be used in place of ball valves and unions specified and indicated on the drawings only when in positions indicated. Ball valves shall be provided with a solid stainless steel or chrome plated brass ball.
 - g. Provide a #20 mesh Y-strainer with blow-down valve and garden hose connection between the supply side valve and equipment.
 - h. Valves may be provided as part of a "hose kit."

2.4 TEMPERATURE-ACTUATED WATER MIXING VALVES

- A. Thermostatic Water Mixing Valves:
 - 1. Refer to drawing schedule for manufacturer and operating requirements.
 - 2. Available Manufacturers:
 - a. Lawler Manufacturing Company, Inc.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- b. Leonard Valve Company.
- c. Powers; a Watts Industries Co.
- d. Symmons Industries, Inc.
- 3. Standard: ASSE 1017.
- 4. Pressure Rating: 125 psig.
- 5. Material: Bronze body with corrosion-resistant interior components.
- 6. Connections: union inlets and outlet.
- 7. Accessories:
 - a. Check stops on hot- and cold-water supplies.
 - b. Handle.
 - c. Dial thermometer on inlets and outlet.
 - d. Pressure gauges on inlets and outlet.
- 8. Pressure Rating: 125 psig, unless otherwise indicated.
- B. Individual-Fixture, Water Tempering Valves:
 - 1. Refer to drawing schedule for manufacturer and operating requirements.
 - 2. Available Manufacturers:
 - a. Apollo Valves Conbraco Industries, Inc.
 - b. Lawler Manufacturing Company, Inc.
 - c. Leonard Valve Company.
 - d. Powers; a Watts Industries Co.
 - e. Watts Industries, Inc.; Water Products Div.
 - f. Zurn Plumbing Products Group; Wilkins Div.
 - 3. Standard: ASSE 1016, thermostatically controlled water tempering valve.
 - 4. Pressure Rating: 125 psig minimum, unless otherwise indicated.
 - 5. Body: Bronze body with corrosion-resistant interior components.
 - 6. Temperature Control: Adjustable.
 - 7. Inlets and Outlet: Threaded. Provide unions and valves.
 - 8. Finish: Chrome-plated bronze.

2.5 STRAINERS

- A. Pattern: "Y"
 - 1. Pressure Rating: 125 psig minimum, unless otherwise indicated.
 - 2. Body: Bronze for NPS 2 and smaller; cast iron or steel with interior lining complying with AWWA C550 or FDA-approved, epoxy coating and for NPS 2-1/2 and larger.
 - 3. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
 - 4. Screen: Stainless steel with round perforations, unless otherwise indicated.
 - 5. Perforation Size:
 - a. StrainersNPS 2 and Smaller: 0.033 inch.
 - b. Strainers NPS 2-1/2 to NPS 4: 0.062 inch.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Strainers NPS 5 and Larger: 0.10 inch.
- 6. Drain: Factory-installed, hose-end drain valve.

2.6 HOSE BIBBS

A. Hose Bibbs:

- 1. Standard: ASME A112.18.1 for sediment faucets.
- 2. Body Material: Bronze.
- 3. Seat: Bronze, replaceable.
- 4. Supply Connections: NPS 1/2 or NPS 3/4 threaded or solder-joint inlet.
- 5. Outlet Connection: Garden-hose thread complying with ASME B1.20.7.
- 6. Pressure Rating: 125 psig.
- 7. Vacuum Breaker: Field-installed, nonremovable, drainable, hose-connection vacuum breaker complying with ASSE 1011.
- 8. Finish: Chrome or nickel plated.
- 9. Operation: Operating key.
- 10. Include operating key with each hose bibb.
- 11. Include integral wall flange with each chrome- or nickel-plated hose bibb.

2.7 WALL HYDRANTS

A. Refer to plumbing fixture rough-in schedule on drawings.

2.8 WATER HAMMER ARRESTERS

- A. Available Manufacturers:
 - 1. AMTROL, Inc.
 - 2. Josam Company.
 - 3. MIFAB, Inc.
 - 4. PPP Inc.
 - 5. Sioux Chief Manufacturing Company, Inc.
 - 6. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
 - 7. Tyler Pipe; Wade Div.
 - 8. Watts Drainage Products Inc.
 - 9. Zurn Plumbing Products Group; Specification Drainage Operation.
- B. Standard: ASSE 1010 or PDI-WH 201.
- C. Type: Metal bellows or copper tube with piston.
- D. Size: ASSE 1010, Sizes AA and A through F or PDI-WH 201, Sizes A through F.

2.9 TRAP GUARD

- A. Available Manufacturers:
 - 1. ProSet Systems, Model TG

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SureSeal Manufacturing, Inline Floor Drain Trap Sealer

B. General:

2.

- 1. Comply with ASSE 1072-2007.
- 2. ProSet Systems: Smooth, soft, flexible, elastomeric PVC material molded into shape, open on top with curl closure at bottom. SureSeal: ABS plastic body with neoprene rubber diaphragm and sealing gasket with 80 durometer compression fit sealing gasket on gravity drain outlet connection.
- 3. Allows wastewater to open and adequately discharge floor drain through its interior.
- 4. Closes and returns to original molded shape after wastewater discharge is complete.
- 5. Size shall be as required to match drain in which it is installed.

2.10 TRAP-SEAL PRIMER VALVES

- A. Supply-Type, Trap-Seal Primer Valves:
 - 1. Available Manufacturers:
 - a. MIFAB, Inc.
 - b. PPP Inc.
 - c. Sioux Chief Manufacturing Company, Inc.
 - d. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
 - e. Watts Industries, Inc.; Water Products Div.
 - 2. Standard: ASSE 1018.
 - 3. Pressure Rating: 125 psig minimum.
 - 4. Body: Bronze.
 - 5. Inlet and Outlet Connections: NPS 1/2 threaded, union, or solder joint.
 - 6. Gravity Drain Outlet Connection: NPS 1/2 threaded or solder joint.
 - 7. Finish: Chrome plated, or rough bronze for units used with pipe or tube that is not chrome finished.
- B. Drainage-Type, Trap-Seal Primer Valves:
 - 1. Available Manufacturers:
 - a. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
 - 2. Standard: ASSE 1044, lavatory P-trap with NPS 3/8 minimum, trap makeup connection.
 - 3. Size: NPS 1-1/4 minimum.
 - 4. Material: Chrome-plated, cast brass.

2.11 TRAP-SEAL PRIMER SYSTEMS

- A. Trap-Seal Primer Systems:
 - 1. Available Manufacturers:
 - 2. Basis-of-Design Product: Subject to compliance with requirements, provide the product indicated on Drawings or a comparable product by one of the following:
 - a. PPP Inc.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Standard: ASSE 1044
- 4. Piping: ASTM B 88, Type L; copper, water tubing.
- 5. Cabinet: Unless otherwise indicated, recessed or surface-mounting steel box with stainless-steel cover.
- 6. Electric Controls: 24-hour timer, solenoid valve, and manual switch for 120-V ac power.
- 7. Vacuum Breaker: ASSE 1001.
- 8. Number of Outlets: Refer to drawings.
- 9. Size of Outlets: ½"

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Refer to Section "Common Work Results for Plumbing" for piping joining materials, joint construction, and basic installation requirements.
- B. Install backflow preventers where indicated: If not indicated on each water supply to mechanical equipment and systems and to other equipment and water systems that may be sources of contamination. Comply with authorities having jurisdiction.
 - 1. Locate backflow preventers in same room as connected equipment or system.
 - 2. Install drain for backflow preventers with atmospheric-vent drain connection with air-gap fitting, fixed air-gap fitting, or equivalent positive pipe separation of at least two pipe diameters in drain piping and pipe to floor drain. Locate air-gap device attached to or under backflow preventer. Simple air breaks are not acceptable for this application.
 - 3. Do not install bypass piping around backflow preventers.
- C. Install balancing valves with-in 12" of ceiling at access door or tile where they can be reached with-out obstruction.
- D. Install thermostatic mixing valves with check stops or shutoff valves on inlets and with shutoff valve on outlet.
 - 1. Install thermometers and pressure gauges.
 - 2. Install cabinet-type units recessed in or surface mounted on wall as indicated.
- E. Install strainers where indicated.
- F. Install outlet boxes recessed in wall. Install 2-by-4-inch fire-retardant-treated-wood blocking wall reinforcement between studs. Fire-retardant-treated-wood blocking is specified in Section "Rough Carpentry."
- G. Install water hammer arresters in water piping according to PDI-WH 201.
- H. Install supply-type, trap-seal primer valves with outlet piping pitched down toward drain trap a minimum of 1/8" per foot, and connect to floor-drain body, trap, or inlet fitting. Adjust valve for proper flow.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- I. Install drainage-type, trap-seal primer valves as lavatory trap with outlet piping pitched down toward drain trap a minimum of 1/8" per foot, and connect to floor-drain body, trap, or inlet fitting.
- J. Install trap-seal primer systems with outlet piping pitched down toward drain trap a minimum of 1/8" per foot, and connect to floor-drain body, trap, or inlet fitting. Adjust system for proper flow.
- K. Install trap guards in accordance with manufacturers instructions.
- L. Fasten wall-hanging plumbing specialties securely to supports attached to building substrate if supports are specified and to building wall construction if no support is indicated.
- M. Fasten recessed-type plumbing specialties to reinforcement built into walls.
- N. Install wood-blocking reinforcement for wall-mounting and recessed-type plumbing specialties.
- O. Install individual shutoff valve in each water supply to plumbing specialties. Use ball valve if specific valve is not indicated. Install shutoff valves in accessible locations. Refer to Section "Valves" for general-duty ball valves.
- P. Install air vents at water piping high points. Include ball valve in inlet.
- Q. Install traps on plumbing specialty drain outlets. Omit traps on indirect wastes unless trap is indicated.
- R. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding pipe fittings.

3.2 LABELING AND IDENTIFYING

A. Indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit. Nameplates and signs are specified in Section "Plumbing Identification"

3.3 FIELD QUALITY CONTROL

- A. Perform the following tests and prepare test reports:
 - 1. Test each reduced-pressure-principle backflow preventer, double-check backflow-preventer and double-check, detector-assembly according to authorities having jurisdiction and the device manufacturer's recommendations.
- B. Remove and replace malfunctioning domestic water piping specialties and retest as specified above.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.4 ADJUSTING

- A. Set field-adjustable pressure set points.
- B. Set field-adjustable flow set points.
- C. Set field-adjustable temperature set points.

END OF SECTION 221119

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 221316 - SANITARY WASTE AND VENT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. The following are industry abbreviations for plastic and rubber piping materials:
 - 1. EPDM: Ethylene-propylene-diene terpolymer.
 - 2. LEED: Leadership in Energy and Environmental Design
 - 3. NBR: Acrylonitrile-butadiene rubber.
 - 4. PE: Polyethylene plastic.
 - 5. PVC: Polyvinyl chloride plastic.
 - 6. TPE: Thermoplastic elastomer.
 - 7. USGBC: United States Green Building Council

1.3 PERFORMANCE REQUIREMENTS

- A. Provide components and installation capable of producing piping systems with the following minimum working-pressure ratings, unless otherwise indicated:
 - 1. Soil, Waste, and Vent Piping: 10-foot head of water.

1.4 SUBMITTALS

- A. Product Data: For pipe, tube, fittings, and couplings.
- B. Submittal:
 - 1. Product Data for USGBC LEED Credit EQ 4.1: For solvent cements and adhesive primers, include printed statement of VOC content.

1.5 QUALITY ASSURANCE

A. Piping materials shall bear label, stamp, or other markings of testing agency.

PART 2 - PRODUCTS

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.1 PIPING MATERIALS

- A. Refer to Part 3 "Piping Applications" Article for applications of pipe, tube, fitting, and joining materials.
- B. Flexible Transition Couplings for Underground Nonpressure Piping: ASTM C 1173 with elastomeric sleeve. Include ends of same sizes as piping to be joined and include corrosion-resistant metal band on each end.

2.2 CAST-IRON SOIL PIPING

- A. All cast iron soil pipe and fittings shall be marked with the Collective Trademark of the Cast Iron Soil Pipe Institute or NewAge Casting.
- B. Pipe and Fittings: ASTM A 888 or CISPI 301.
- C. Hub-and-Spigot Gaskets: ASTM C 564, rubber.
- D. Hub-less Couplings:
 - 1. All hub-less couplings shall bear the NSF trademark.
 - 2. General: CISPI 310 and ASTM C 1277 assembly of stainless steel corrugated shield, stainless steel bands and fasteners, and ASTM C 564 rubber sleeve with integral, center pipe stop.
 - 1) Heavy-Duty, Type 304, Stainless-Steel Couplings: ASTM C 1540, Type 304, stainless-steel shield; stainless-steel bands; and ASTM C 564, rubber sleeve.
 - a) NPS 1-1/2 to NPS 4: 3-inch- wide shield with 4 bands.
 - b) NPS 5 to NPS 10: 4-inch- wide shield with 6 bands.
 - b. Heavy-Duty, Cast-Iron Couplings: ASTM A 48/A 48M, 2-piece, cast-iron housing; stainless-steel bolts and nuts; and ASTM C 564, rubber sleeve.

2.3 PVC PIPE AND FITTINGS

- A. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.
 - 1. PVC Socket Fittings: ASTM D 2665, socket type, made to ASTM D 3311, drain, waste, and vent patterns.
- B. Solvent Cement and Adhesive Primer:
 - 1. Use PVC solvent cement that has a VOC content of 510 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 2. Use adhesive primer that has a VOC content of 550 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS

- A. Transition fittings with pressure ratings at least equal to piping pressure ratings may be used in applications below, unless otherwise indicated.
- B. Aboveground, Soil, Waste, and Vent Piping located inside plenum: Hub-less cast-iron soil piping with heavy duty couplings.
- C. Underground, Soil, Waste, and Vent Piping:
 - 2. Service Weight Hub and Spigot cast iron soil pipe and fittings.
 - 3. Epoxy coated Service Weight Hub and Spigot cast iron soil pipe and fittings.
 - 4. Other than kitchen waste: PVC pipe and fittings.

3.2 PIPING INSTALLATION

- A. Refer to Section "Facility Sanitary Sewers" for Project-site sanitary sewer piping.
- B. Refer to Section "Common Work Results for Plumbing" for basic installation.
- C. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers.
- D. Install cleanout fitting with closure plug inside the building in sanitary force-main piping.
- E. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers.
- F. Install cast-iron sleeve with water stop and mechanical sleeve seal at each service pipe penetration through foundation wall. Select number of interlocking rubber links required to make installation watertight.
- G. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
- H. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical. Use long-turn, double Y-branch and 1/8-bend fittings if 2 fixtures are installed back to back or side by side with common drain pipe. Straight tees, elbows, and crosses may be used on vent lines. Do not change direction of flow more than 90 degrees. Use proper size of standard increasers and reducers if pipes of different sizes are connected. Reducing size of drainage piping in direction of flow is prohibited.
- I. Lay buried building drainage piping beginning at low point of each system. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

upstream. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements. Maintain swab in piping and pull past each joint as completed.

- J. Install soil and waste drainage and vent piping at the minimum slopes required by authorities having jurisdiction.
- K. Install underground PVC soil and waste drainage piping according to ASTM D 2321.
- L. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.

3.3 JOINT CONSTRUCTION

- A. Refer to section "Common Work Results for Plumbing" for basic piping joint construction.
- B. Join hub-and-spigot, cast-iron soil piping with gasket joints according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for compression joints.
- C. Join hub-less cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hub-less-coupling joints.
- D. PVC Non-pressure Piping Joints: Join piping according to ASTM D 2665.

3.4 HANGER AND SUPPORT INSTALLATION

- A. Refer to Section "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices in zones other than A & B.
- B. Join hubless cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-coupling joints.
- C. Install the following:
 - 1. Vertical Piping: MSS Type 8 or Type 42, clamps.
 - 2. Individual, Straight, Horizontal Piping Runs: According to the following:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
 - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
 - c. Longer Than 100 Feet, if indicated: MSS Type 49, spring cushion rolls.
 - 3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
 - 4. Base of Vertical Piping: MSS Type 52, spring hangers.
- D. Support vertical piping and tubing at base and at each floor.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- E. Rod diameter may be reduced 1 size for double-rod hangers, with 3/8-inch minimum rods.
- F. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:
 - 1. 1 ½" and 2": 60" with 3/8"rod.
 - 2. 3": 60" with ½"rod.
 - 3. 4" and NPS 5: 60" with 5/8" rod.
 - 4. 6": 60" with ³/₄" rod.
 - 5. 8" to 12": 60" with 7/8" rod.
 - 6. 15": 60" with 1" rod.
- G. Install supports for vertical cast-iron soil piping every 15 feet.
- H. Install hangers for PVC piping with the following maximum horizontal spacing and minimum rod diameters:
 - 1. 1 ½" and 2": 48" with 3/8" rod.
 - 2. 3": 48" with ½" rod.
 - 3. 4" and 5": 48" with 5/8" rod.
 - 4. 6": 48" with 3/4" rod.
 - 5. 8" to 12": 48" with 7/8" rod.
- I. Install supports for vertical PVC piping every 48".
- J. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.

3.5 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.
- C. Connect drainage and vent piping.

3.6 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
 - 1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Re-inspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for re-inspection.
- C. Reports: Where required or indicated prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test sanitary drainage and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:
 - 1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
 - 2. Leave uncovered and unconcealed new, altered, extended, or replaced drainage and vent piping until it has been tested and approved. Expose work that was covered or concealed before it was tested.
 - 3. Roughing-in Plumbing Test Procedure: Test drainage and vent piping, except outside leaders, on completion of roughing-in. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water. From 15 minutes before inspection starts to completion of inspection, water level must not drop. Inspect joints for leaks.
 - 4. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
 - 5. Prepare reports for tests and required corrective action.

3.7 CLEANING

- A. Clean interior of piping. Remove dirt and debris as work progresses.
- B. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.

3.8 PROTECTION

A. Exposed PVC Piping: Protect plumbing vents exposed to sunlight with two coats of water-based latex paint.

END OF SECTION 221316

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 221319 - SANITARY WASTE PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 ABBREVIATIONS

- A. RPZ Reduced Pressure Zone
- B. FOG Fats, oils, and greases.

1.3 DEFINITIONS

A. Withstand: Units shall remain in place without separation of any parts when subjected to seismic forces indicated. "Essential facility" units shall be fully operational after the seismic event.

1.4 SUBMITTALS

- A. Product Data: Include rated capacities, operating characteristics, and accessories:
- B. Shop Drawings:
- C. Operation and Maintenance Data: To include in emergency, operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Drainage piping specialties shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 14, "Plastics Piping Components and Related Materials," for plastic sanitary piping specialty components.

1.6 COORDINATION

A. Coordinate size and location of roof penetrations.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 2 - PRODUCTS

2.1 CLEANOUTS

A. General:

- 1. Available Manufacturers:
 - a. Josam Company; Josam Div.
 - b. MIFAB, Inc.
 - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
 - d. Tyler Pipe; Wade Div.
 - e. Watts Drainage Products Inc.
 - f. Zurn Plumbing Products Group; Specification
- 2. Standard: ASME A112.36.2M.
- 3. Size: Same as connected drainage piping
- 4. Closure Material: Match pipe, brass, PVC, or ABS

B. Floor Cleanouts:

- 1. Housing: threaded, adjustable.
- 2. Type: Threaded, adjustable housing.
- 3. Body: Cast iron.
- 4. Outlet Connection: Inside calk, Spigot, or Threaded.
- 5. Adjustable Housing Material: Cast iron with threads.
- 6. Frame and Cover Material and Finish: Satin finish nikaloy.
- 7. Frame and Cover Shape: Round or Square (Contractors Option).
- 8. Top Loading Classification: Extra Heavy Duty.
- 9. Riser: ASTM A 74, Service weight, cast-iron drainage pipe fitting and riser to cleanout.
- 10. Carpet Ring: Yes for carpeted floors.
- 11. Tile Recess: Yes for tiled floors.
- 12. Terrazzo: Yes for terrazzo floors

C. Wall Cleanouts:

- 1. Wall access: Yes
- 2. Body: Match connected piping.
- 3. Closure: Countersunk or raised-head, drilled-and-threaded plug.
- 4. Closure Plug Size: Same as cleanout size but not larger than four inches in diameter.
- 5. Wall Access: Round, flat, chrome-plated brass, nickel-bronze, copper-alloy, or stainless-steel cover plate with screw.

2.2 FLOOR DRAINS

- 1. Basis-of-Design Product: Subject to compliance with requirements, provide the product indicated on Drawings or a comparable product by one of the following:
 - a. Josam Company; Josam Div.
 - b. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
 - c. Zurn Plumbing Products Group; Light Commercial Operation.
 - d. Zurn Plumbing Products Group; Specification Drainage Operation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Standard: ASME A112.6.3
- 3. Pattern: As indicated.
- 4. Clamping Flange: Required.

2.3 THROUGH-PENETRATION FIRESTOP ASSEMBLIES

A. Through-Penetration Firestop Assemblies:

- 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. ProSet Systems Inc.
- 2. Standard: UL 1479 assembly of sleeve and stack fitting with firestopping plug.
- 3. Size: Same as connected soil, waste, or vent stack.
- 4. Sleeve: Molded PVC plastic, of length to match slab thickness and with integral nailing flange on one end for installation in cast-in-place concrete slabs.
- 5. Plastic Stack Fitting (For Use Where Plastic Stacks Are Indicated): ASTM A 48/A 48M, gray-iron, hubless-pattern, wye branch with neoprene O-ring at base and gray-iron plug in thermal-release harness. Include PVC protective cap for plug.
- 6. Special Coating (For Use Where Plastic Laboratory Stacks are Indicated: Corrosion resistant on interior of fittings.

2.4 MISCELLANEOUS SANITARY DRAINAGE PIPING SPECIALTIES

- A. Floor-Drain, Trap-Seal Primer Fittings:
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide the product indicated on Drawings or a comparable product by one of the following:
 - a. PPP
 - b. Josam
 - c. Smith
 - d. Zurn
 - 2. Description: Cast iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
 - 3. Size: Same as floor drain inlet.

B. Air-Gap Fittings:

- 1. Standard: ASME A112.1.2, for fitting designed to ensure fixed, positive air gap between installed inlet and outlet piping.
- 2. Body: Bronze or cast iron.
- 3. Inlet: Opening in top of body.
- 4. Outlet: Larger than inlet.
- 5. Size: Same as connected waste piping and with inlet large enough for associated indirect waste piping.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.5 MOTORS

- A. General requirements for motors are specified in Division 22 Section "Common Motor Requirements for Plumbing Equipment."
 - 1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.
 - 2. Controllers, Electrical Devices, and Wiring: Electrical devices and connections are specified in Division 26 Sections.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Refer to Division 22 Section "Common Work Results for Plumbing" for piping joining materials, joint construction, and basic installation requirements.
- B. Install backwater valves in building drain piping. For interior installation, provide cleanout deck plate flush with floor and centered over backwater valve cover, and of adequate size to remove valve cover for servicing.
- C. Install cleanouts.
- D. Install cleanout deck plates with top flush with finished floor.
- E. For wall cleanouts located in concealed piping, install cleanout access covers, with cover tight to finished wall
- F. Install floor drains at low points of surface areas to be drained. Set grates of drains flush with finished floor, unless otherwise indicated.
 - 1. Position floor drains as indicated. If indication is not clear, position for easy access and maintenance.
 - 2. Set floor drains at elevations indicated.
 - 3. Install floor-drain flashing flange so no leakage occurs between drain and adjoining flooring. Maintain integrity of waterproof membranes where penetrated.
 - 4. Install individual traps for floor drains connected to sanitary building drain.
- G. Install trench drains at low points of surface areas to be drained. Set grates of drains flush with finished surface, unless otherwise indicated.
- H. Install through-penetration firestop assemblies in plastic conductors and stacks at rated penetrations.
- I. Install floor-drain, trap-seal primer fittings on inlet to floor drains indicated to receive trap-seal primer.
- J. Install air-gap fittings on RPZ backflow preventers and where indicated.
- K. Install sleeve flashing device with each riser and stack passing through floors with waterproof membrane.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment to allow service and maintenance.
- C. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- D. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

3.3 LABELING AND IDENTIFYING

A. Distinguish among multiple units, inform operator of operational requirements, and refer to Division 22 Section "Identification for Plumbing Piping and Equipment."

3.4 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Checks and Inspections:
 - 1. Leak Check: After installation, charge system and check for leaks. Repair leaks and recheck until no leaks exist.

3.5 PROTECTION

- A. Protect drains during construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.
- B. Place plugs in ends of open pipes at end of each day or when work stops.

END OF SECTION 221319

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 224200 - PLUMBING FIXTURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following conventional plumbing fixtures and related components:
 - 1. Water closets.
 - 2. Urinals.
 - 3. Lavatories.
 - 4. Water cooler/Bottle filling stations
- B. Related Sections include the following:
 - 1. Division 10 Section "Toilet, Bath, and Laundry Accessories."
 - 2. Division 22 Section "Domestic Water Piping Specialties" for backflow preventers, floor drains, and specialty fixtures not included in this Section.
 - 3. Division 22 Section "Security Plumbing Fixtures."
 - 4. Division 22 Section "Emergency Plumbing Fixtures."

1.3 DEFINITIONS

- A. ABS: Acrylonitrile-butadiene-styrene plastic.
- B. Accessible Fixture: Plumbing fixture that can be approached, entered, and used by people with disabilities.
- C. Fitting: Device that controls the flow of water into or out of the plumbing fixture. Fittings specified in this Section include supplies and stops, faucets and spouts, shower heads and tub spouts, drains and tailpieces, and traps and waste pipes. Piping and general-duty valves are included where indicated.
- D. FRP: Fiberglass-reinforced plastic.
- E. PMMA: Polymethyl methacrylate (acrylic) plastic.
- F. PVC: Polyvinyl chloride plastic.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.4 SUBMITTALS

- A. Product Data: For each type of plumbing fixture indicated. Include selected fixture and trim, fittings, accessories, appliances, appurtenances, equipment, and supports. Indicate materials and finishes, dimensions, construction details, and flow-control rates.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Operation and Maintenance Data: For plumbing fixtures to include in emergency, operation, and maintenance manuals.
- D. Warranty: Special warranty specified in this Section.

1.5 QUALITY ASSURANCE

- A. Source Limitations: Obtain plumbing fixtures, faucets, and other components of each category through one source from a single manufacturer.
 - 1. Exception: If fixtures, faucets, or other components are not available from a single manufacturer, obtain similar products from other manufacturers specified for that category.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Regulatory Requirements: Comply with requirements in ICC A117.1, "Accessible and Usable Buildings and Facilities"; Public Law 90-480, "Architectural Barriers Act"; and Public Law 101-336, "Americans with Disabilities Act"; for plumbing fixtures for people with disabilities.
- D. Regulatory Requirements: Comply with requirements in Public Law 102-486, "Energy Policy Act," about water flow and consumption rates for plumbing fixtures.
- E. NSF Standard: Comply with NSF 61, "Drinking Water System Components--Health Effects," for fixture materials that will be in contact with potable water.
- F. Select combinations of fixtures and trim, faucets, fittings, and other components that are compatible.
- G. Comply with the following applicable standards and other requirements specified for plumbing fixtures:
 - 1. Enameled, Cast-Iron Fixtures: ASME A112.19.1M.
 - 2. Porcelain-Enameled, Formed-Steel Fixtures: ASME A112.19.4M.
 - 3. Stainless-Steel Commercial, Handwash Sinks: NSF 2 construction.
 - 4. Vitreous-China Fixtures: ASME A112.19.2M.
 - 5. Water-Closet, Flush Valve, Tank Trim: ASME A112.19.5.
 - 6. Water-Closet, Flushometer Tank Trim: ASSE 1037.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- H. Comply with the following applicable standards and other requirements specified for lavatory and sink faucets:
 - 1. Backflow Protection Devices for Faucets with Side Spray: ASME A112.18.3M.
 - 2. Backflow Protection Devices for Faucets with Hose-Thread Outlet: ASME A112.18.3M.
 - 3. Diverter Valves for Faucets with Hose Spray: ASSE 1025.
 - 4. Faucets: ASME A112.18.1.
 - 5. Hose-Connection Vacuum Breakers: ASSE 1011.
 - 6. Hose-Coupling Threads: ASME B1.20.7.
 - 7. Integral, Atmospheric Vacuum Breakers: ASSE 1001.
 - 8. NSF Potable-Water Materials: NSF 61.
 - 9. Pipe Threads: ASME B1.20.1.
 - 10. Sensor-Actuated Faucets and Electrical Devices: UL 1951.
 - 11. Supply Fittings: ASME A112.18.1.
 - 12. Brass Waste Fittings: ASME A112.18.2.
- I. Comply with the following applicable standards and other requirements specified for miscellaneous fittings:
 - 1. Atmospheric Vacuum Breakers: ASSE 1001.
 - 2. Brass and Copper Supplies: ASME A112.18.1.
 - 3. Manual-Operation Flushometers: ASSE 1037.
 - 4. Brass Waste Fittings: ASME A112.18.2.
 - 5. Sensor-Operation Flushometers: ASSE 1037 and UL 1951.
- J. Comply with the following applicable standards and other requirements specified for miscellaneous components:
 - 1. Floor Drains: ASME A112.6.3.
 - 2. Grab Bars: ASTM F 446.
 - 3. Hose-Coupling Threads: ASME B1.20.7.
 - 4. Off-Floor Fixture Supports: ASME A112.6.1M.
 - 5. Pipe Threads: ASME B1.20.1.
 - 6. Plastic Toilet Seats: ANSI Z124.5.
 - 7. Supply and Drain Protective Shielding Guards: ICC A117.1.

1.6 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Faucet Washers and O-Rings: Equal to 10 percent of amount of each type and size installed.
 - 2. Faucet Cartridges and O-Rings: Equal to 5 percent of amount of each type and size installed.
 - 3. Flushometer Valve, Repair Kits: Equal to 10 percent of amount of each type installed, but no fewer than 2 of each type.
 - 4. Provide hinged-top wood or metal box, or individual metal boxes, with separate compartments for each type and size of extra materials listed above.
 - 5. Water-Closet Tank, Repair Kits: Equal to 5 percent of amount of each type installed.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

6. Toilet Seats: Equal to 5 percent of amount of each type installed.

PART 2 - PRODUCTS

2.1 WATER CLOSETS

- A. WATER CLOSET FLOOR MOUNTED ACCESSIBLE (WC-1) WITH MANUAL DIAPHRAM TYPE FLUSH VALVE
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Kohler No. K-4405 (1.28 Gallon Flush)
 - a. Material: Vitreous china
 - b. Color: White
 - c. Valve: Sloan Model Royal 111-1.28 (1.28 Gal. Flush)
 - 1) Supply Rough-in Elevation: 11-1/2" above spud connection
 - 2) Provide:
 - a. Accessible handle located on wide side of approach.
 - b. Sweat Solder Adapter and Cast Wall Flange with set screw.
 - d. Seat: Church 9500SSCT (White)
 - 1) Elongated extra heavy weight seat with stainless steel self-sustaining check hinge.
 - 2) Open front, no cover
 - e. Manufacturers:
 - 1) Water Closet
 - a) American Standard
 - b) Eljer
 - c) Crane
 - d) Gerber
 - e) Sloan
 - f) Zurn
 - 2) Flush Valve:
 - a) Delany
 - b) Zurn
 - c) Moen
 - d) Sloan
 - 3) Seat
 - a) Olsonite
 - b) Centoco
- B. WATER CLOSET FLOOR MOUNTED (WC-2) WITH MANUAL DIAPHRAM TYPE FLUSH VALVE
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Kohler No. K- 4406 (1.28 Gallon Flush)
 - a. Material: Vitreous china

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- b. Color: White
- c. Valve: Sloan Model Royal 111-1.28 (1.28 Gal. Flush)
 - 1) Supply Rough-in Elevation: 11-1/2" above spud connection
 - 2) Provide:
 - a. Accessible handle located on wide side of approach.
 - b. Sweat Solder Adapter and Cast Wall Flange with set screw
- d. Seat: Church 9500SSCT (White)
 - 1) Elongated extra heavy weight seat with stainless steel self-sustaining check hinge.
 - 2) Open front, no cover
- e. Manufacturers:
 - 1) Water Closet
 - a) American Standard
 - b) Eljer
 - c) Crane
 - d) Gerber
 - e) Sloan
 - f) Zurn
 - 2) Flush Valve:
 - a) Delany
 - b) Zurn
 - c) Moen
 - d) Sloan
 - 3) Seat
 - a) Olsonite
 - b) Centoco

2.2 URINALS

A. URINAL – ACCESSIBLE (UR-1) WITH MANUAL PISTON TYPE FLUSH VALVE

- 1. Manufacturer & Model Number: Kohler No. K-4991-ET (0.125 Gallon Flush)
- 2. Material: Vitreous china
- 3. Color: White
- 4. Flush Valve: Sloan Model 186 0.125 (0.125 Gallon Flush)
 - a. Supply Rough-in Elevation: 11-1/2" above spud connection
 - b. Accessible handle located on wide side of approach.
 - c. Sweat Solder Adapter and Cast Wall Flange with set screw.
 - d. Vandal resistant stop cap with set screw.
- 5. Carrier: Josam Series 17560-UR.
 - a. Options
 - 1) Provide components for thicker walls when required.
 - 2) Provide valve plate for attaching to upright.
- 6. Other Manufacturers: Provide products, features, and accessories equal to those specified above.
 - a. Urinal
 - 1) American Standard

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2) Eljer
- 3) Crane
- 4) Gerber
- b. Flush Valve
 - 1) Delany
 - 2) Zurn
 - 3) Sloan

B. URINAL (UR-2) WITH MANUAL TYPE FLUSH VALVE

- 1. Manufacturer & Model Number: Kohler No. K-4991-ET (0.125 Gallon Flush)
- 2. Material: Vitreous china
- 3. Color: White
- 4. Flush Valve: <u>Sloan Model 186 0.125</u> (0.125 Gallon Flush)
 - a. Supply Rough-in Elevation: 11-1/2" above spud connection
 - b. Accessible handle located on wide side of approach.
 - c. Sweat Solder Adapter and Cast Wall Flange with set screw.
 - d. Vandal resistant stop cap with set screw.
- 5. Carrier: Josam Series 17560-UR.
 - a. Options
 - 1) Provide components for thicker walls when required.
 - 2) Provide valve plate for attaching to upright.
- 6. Other Manufacturers: Provide products, features, and accessories equal to those specified above.
 - a. Urinal
 - 1) American Standard
 - 2) Eljer
 - 3) Crane
 - 4) Gerber
 - b. Flush Valve
 - 1) Delany
 - 2) Zurn
 - 3) Moen
 - 4) Sloan

2.3 LAVATORIES

A. WALL HUNG LAV – ACCESSIBLE (LA-1) WITH SENSOR FAUCET

- 1. Basis-of-Design Product: Subject to compliance with requirements, provide <u>Kohler No. K-1722</u> or a comparable product by one of the following:
 - a. Material: Vitreous china
 - b. Color: White
- 2. Faucet: Sloan Model Number EFX-600
 - a. Hardwired Infrared Sensor
 - b. Filtered Solenoid valve w/ serviceable "Y" Strainer
 - c. Splash Proof Circuit control Module
 - d. Vandal resistant Spray head

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- e. Below deck thermostatic Mixing valve
- f. 0.5 GPM
- g. Sensor Range adjustment Screw
- h. Variable time out settings
- i. BakCheck tee for hot and cold water supply
- j. Metal jacketed wire protection for sensor and solenoid leads
- 3. Drain: McGuire Part Number 155A
- 4. Trap: McGuire Part Number 8902C-F
 - 1) 1-1/4"x 1-1/2" cast brass polished chrome trap with cleanout plug and brass slip nuts.
 - 2) 17-gauge seamless tubular chrome plated brass wall bend.
 - 3) Forged brass chrome plated wall flange with setscrew.
- 5. Supplies: McGuire Part Number 2165-N3-F
 - 1) ½" IPS x 3/8" OD
 - 2) ½" x 3" chrome plated brass nipple.
 - 3) Heavy brass chrome plated wall flange with set-screw
 - 4) Contractor shall coordinate supply connection to faucet.
- 6. Insulation: <u>Tru-Bro Lav Guard #102</u>
 - 1) Color: White
 - 2) Insulate P-trap, hot and cold angle valves, hot and cold risers.
- 7. Other Manufacturers: Provide products, features, and accessories equal to those specified above.
 - 1) Lavatory
 - a) American Standard
 - b) Eljer
 - c) Gerber
 - 2) Faucet:
 - a) Speakman
 - b) Cambridge Brass
 - c) T&S Brass
 - 3) Drain:
 - a) Kohler
 - b) Cambridge Brass
 - c) Chicago
 - 4) Trap:
 - a) Kohler
 - b) Cambridge Brass
 - 5) Supplies:
 - a) Cambridge Brass
 - b) Kohler
 - 6) Insulation:
 - a) McGuire

2.4 WATER COOLERS

- A. BI-LEVEL WATER COOLER ACCESSIBLE (EWC-1):
 - 1. Manufacturer & Model Number: Elkay model EZSTL8WS

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Self-contained BI-LEVEL wall hung electric refrigerated water cooler and bottle filler.
- b. Non-filter 8 GPH at 50 degrees F
- c. Vandal resistant bubbler
- d. Push bar activation on front, left, & right of unit.
- e. Built-in flow regulator
- f. Connect to water supply using dielectric coupling.
- g. Polyester elastomer flexible bubbler.
- h. Provide quick connect fittings.
- i. Provide cane apron on upper fountain.
- i. Material: Stainless steel.
- k. Color: Manufacturer's standard.
- 1. Electrical: 115V, 1 PH, 60 HZ, 4.0 Full load amps, 370 Watts.
- 2. Supply: McGuire Part Number 2165-N3-F
 - a. ½" IPS x 3/8" OD
 - b. ½" x 3" chrome plated brass nipple.
 - c. Heavy brass chrome plated wall flange with set-screw
 - d. Provide dielectric connection.
 - e. Wheel Handle.
- 3. Provide 1½"diameter plastic tailpiece extension. Electrically isolate cooler from drainage and vent system.
- 4. Trap: McGuire Part Number 8912-C-F
 - a. Size:1-1/2"x 1-1/2"
 - b. Material: Polished chrome plated cast brass.
 - c. Cleanout plug: Yes
 - d. Nuts: Polished chrome plated brass.
 - e. Wall bend: 17-gauge seamless tubular chrome plated brass.
 - f. Wall flange: Chrome plated brass with setscrew. Where drain pipe connection protrudes from wall contractor may provide deep flange.
- 5. Other Manufacturers: Provide products, features, and accessories equal to those specified above.
 - a. Drinking Fountain:
 - 1) Acorn Aqua
 - 2) Haws Corp
 - 3) Oasis
 - 4) Murdock
 - b. Trap:
 - 1) Kohler
 - 2) Cambridge Brass

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine roughing-in of water supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before plumbing fixture installation.
- B. Examine cabinets, counters, floors, and walls for suitable conditions where fixtures will be installed.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Assemble plumbing fixtures, trim, fittings, and other components according to manufacturers' written instructions.
- B. Install off-floor supports, affixed to building substrate, for wall-mounting fixtures.
 - 1. Use carrier supports with waste fitting and seal for back-outlet fixtures.
 - 2. Use carrier supports without waste fitting for fixtures with tubular waste piping.
 - 3. Use chair-type carrier supports with rectangular steel uprights for accessible fixtures.
- C. Install back-outlet, wall-mounting fixtures onto waste fitting seals and attach to supports.
- D. Install floor-mounting fixtures on closet flanges or other attachments to piping or building substrate.
- E. Install wall-mounting fixtures with tubular waste piping attached to supports.
- F. Install counter-mounting fixtures in and attached to casework.
- G. Install fixtures level and plumb according to roughing-in drawings.
- H. Install water-supply piping with stop on each supply to each fixture to be connected to water distribution piping. Attach supplies to supports or substrate within pipe spaces behind fixtures. Install stops in locations where they can be easily reached for operation.
 - 1. Exception: Use ball valves if supply stops are not specified with fixture. Valves are specified in Division 22 Section "General-Duty Valves for Plumbing Piping."
- I. Install trap and tubular waste piping on drain outlet of each fixture to be directly connected to sanitary drainage system.
- J. Install tubular waste piping on drain outlet of each fixture to be indirectly connected to drainage system.
- K. Install flushometer valves for accessible water closets and urinals with handle mounted on wide side of compartment. Install other actuators in locations that are easy for people with disabilities to reach.
- L. Install tanks for accessible, tank-type water closets with lever handle mounted on wide side of compartment.
- M. Install toilet seats on water closets.
- N. Install faucet-spout fittings with specified flow rates and patterns in faucet spouts if faucets are not available with required rates and patterns. Include adapters if required.
- O. Install water-supply flow-control fittings with specified flow rates in fixture supplies at stop valves.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- P. Install faucet flow-control fittings with specified flow rates and patterns in faucet spouts if faucets are not available with required rates and patterns. Include adapters if required.
- Q. Install shower flow-control fittings with specified maximum flow rates in shower arms.
- R. Install traps on fixture outlets.
 - 1. Exception: Omit trap on fixtures with integral traps.
 - 2. Exception: Omit trap on indirect wastes, unless otherwise indicated.
- S. Install escutcheons at piping wall ceiling penetrations in exposed, finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding fittings. Escutcheons are specified in Division 22 Section "Common Work Results for Plumbing."
- T. Set service basins in leveling bed of cement grout. Grout is specified in Division 22 Section "Common Work Results for Plumbing."
- U. Seal joints between fixtures and walls, floors, and countertops using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Sealants are specified in Division 07 Section "Joint Sealants."

3.3 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect fixtures with water supplies, stops, and risers, and with traps, soil, waste, and vent piping. Use size fittings required to match fixtures.
- C. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- D. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

3.4 FIELD QUALITY CONTROL

- A. Verify that installed plumbing fixtures are categories and types specified for locations where installed.
- B. Check that plumbing fixtures are complete with trim, faucets, fittings, and other specified components.
- C. Inspect installed plumbing fixtures for damage. Replace damaged fixtures and components.
- D. Test installed fixtures after water systems are pressurized for proper operation. Replace malfunctioning fixtures and components, then retest. Repeat procedure until units operate properly.
- E. Install fresh batteries in sensor-operated mechanisms.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.5 ADJUSTING

- A. Operate and adjust faucets and controls. Replace damaged and malfunctioning fixtures, fittings, and controls.
- B. Operate and adjust controls. Replace damaged and malfunctioning units and controls.
- C. Adjust water pressure at faucets and flushometer valves to produce proper flow and stream.
- D. Replace washers and seals of leaking and dripping faucets and stops.
- E. Install fresh batteries in sensor-operated mechanisms.

3.6 CLEANING

- A. Clean fixtures, faucets, and other fittings with manufacturers' recommended cleaning methods and materials. Do the following:
 - 1. Remove faucet spouts and strainers, remove sediment and debris, and reinstall strainers and spouts.
 - 2. Remove sediment and debris from drains.
- B. After completing installation of exposed, factory-finished fixtures, faucets, and fittings, inspect exposed finishes and repair damaged finishes.

3.7 PROTECTION

- A. Provide protective covering for installed fixtures and fittings.
- B. Do not allow use of plumbing fixtures for temporary facilities unless approved in writing by Owner.

END OF SECTION 224200

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 230500 - COMMON WORK RESULTS FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe chases, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawlspaces, and tunnels.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- D. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in chases.
- E. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.
- F. The following are industry abbreviations for rubber materials:
 - 1. EPDM: Ethylene-propylene-diene terpolymer rubber.
 - 2. NBR: Acrylonitrile-butadiene rubber.

1.3 SUBMITTALS

- A. Product Data: For the following:
 - 1. Transition fittings.
 - 2. Dielectric fittings.
 - 3. Mechanical sleeve seals.
 - 4. Escutcheons.
- B. Welding certificates.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.4 QUALITY ASSURANCE

- A. Equipment and appliances comprising portions of the mechanical systems regulated by the applicable building codes shall be listed and labeled in accordance with the current edition of those codes.
- B. Equipment and appliances comprising portions of the mechanical systems shall be installed in accordance with the listing, manufacturer's installation instructions, and the applicable building codes. Manufacturer's installation instructions shall be available on the job site for use and inspection.
- C. Steel Support Welding: Qualify processes and operators according to AWS D1.1, "Structural Welding Code--Steel."
- D. Steel Pipe Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."
 - 1. Comply with provisions in ASME B31 Series, "Code for Pressure Piping."
 - 2. Certify that each welder has passed AWS qualification tests for welding processes involved and that certification is current.
- E. Electrical Characteristics for HVAC Equipment: Equipment of higher electrical characteristics may be furnished provided such proposed equipment is approved in writing and connecting electrical services, circuit breakers, and conduit sizes are appropriately modified. If minimum energy ratings or efficiencies are specified, equipment shall comply with requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.

1.6 COORDINATION

- A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for HVAC installations.
- B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- C. Coordinate requirements for access panels and doors for HVAC items requiring access that are concealed behind finished surfaces. Access panels and doors are specified in Division 08 Section "Access Doors and Frames."

1.7 INTENT OF CONTRACT DOCUMENTS

A. Mechanical and HVAC drawings are diagrammatic, indicating general locations and arrangements of pipe, duct, and equipment. Not necessarily indicating all offsets, conditions,

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- and appurtenances required to provide clearances for maximum practical accessibility to perform maintenance.
- B. Coordinate work in order to achieve proper operation and to provide a maintainable installed condition.
- C. Notify the Architect's representative immediately of conditions which do not comply or will not produce this result.
- D. Indicated configurations were used to size pipes, pumps, expansion tanks and other devices. Install piping, duct, and equipment generally as indicated. Minor deviations are permitted in the course of necessary coordination. Major changes shall be submitted for approval by the Architect's representative. Additional fittings and offsets not indicated are expected, anticipated by the design, and shall be provided. If more than 5% of the indicated number of fittings are required or if one change in direction is within six inches of another change in direction and this "Z" shape is not indicated notify the Architect's representative immediately. Provide necessary additional fittings and offsets. Changes in pipe size shall be made only with written approval from the Architect's representative.

1.8 BUILDING AUTOMATION SYSTEM

A. All HVAC equipment shall he controlled directly by the Building Automation System. Equipment specific pneumatic or electronic controls manufactured and installed by the equipment manufacturer will not be permitted. Refer to section "Building Automation System"

PART 2 - PRODUCTS

2.1 PIPE, TUBE, AND FITTINGS

- A. Refer to Section "Hydronic Piping" for additional pipe, tube, and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

2.2 JOINING MATERIALS

- A. Refer to individual Division 23 piping sections for joining materials not listed below.
- B. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions inside & outside pipe and:
 - 1. ASME B16.21, non-metallic, flat, asbestos-free, 1/8-inch maximum thickness unless thickness or specific material is otherwise indicated.
 - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. AWWA C110, rubber, flat face, 1/8 inch thick, unless otherwise indicated, and full-face or ring type, unless otherwise indicated.
- C. Solder Filler Metals: ASTM B 32, lead-free (95% Tin, 5% Antimony) alloy. Include water-flushable flux according to ASTM B 813.
- D. Brazing Filler Metals: AWS A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing, unless otherwise indicated; and AWS A5.8, BAg-5, silver alloy for refrigerant piping, unless otherwise indicated.
- E. Welding Filler Metals: Comply with AWS D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

2.3 DIELECTRIC FITTINGS

- A. Description: Combination fitting of copper alloy and ferrous materials with threaded, solder-joint, plain, or weld-neck end connections that match piping system materials.
- B. Insulating Material: Suitable for system fluid, pressure, and temperature.
- C. Dielectric Flanges: Factory-fabricated, companion-flange assembly, for 150- or 300-psig minimum working pressure as required to suit system pressures.
 - 1. Available Manufacturers:
 - a. Capitol Manufacturing Co.
 - b. Central Plastics Company.
 - c. Epco Sales, Inc.
 - d. Watts Industries, Inc.; Water Products Div.
- D. Dielectric-Flange Kits: Companion-flange assembly for field assembly. Include flanges, full-face- or ring-type neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.
 - 1. Available Manufacturers:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Central Plastics Company.
 - d. Pipeline Seal and Insulator, Inc.
 - 2. Separate companion flanges and steel bolts and nuts shall have 150- or 300-psig minimum working pressure where required to suit system pressures.
- E. Dielectric Couplings: Galvanized steel coupling with inert and non-corrosive, thermoplastic lining; threaded ends; and 300-psig minimum working pressure at 225°F.
 - 1. Available Manufacturers:
 - a. Calpico, Inc.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

b. Lochinvar Corp.

2.4 MECHANICAL SLEEVE SEALS

- A. Description: Modular sealing element unit, designed for field assembly, to fill annular space between pipe and sleeve.
 - 1. Available Manufacturers:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Metraflex Co.
 - d. Pipeline Seal and Insulator, Inc.
 - 2. Sealing Elements: EPDM interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 3. Pressure Plates: Plastic. Include two for each sealing element.
 - 4. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements.

2.5 SLEEVES

- A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- B. Steel Pipe: ASTM A 53, Type E, Grade B, Schedule 40, galvanized, plain ends.
- C. Cast Iron: Cast or fabricated "wall pipe" equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- D. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with set screws.
- E. Molded PE: Reusable, PE, tapered cup-shaped and smooth-outer surface with nailing flange for attaching to wooden forms.

2.6 ESCUTCHEONS

- A. Description: Manufactured wall and ceiling escutcheons and floor plates, with an ID to closely fit around pipe, tube, and insulation of insulated piping and an OD that completely covers opening.
- B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with polished chrome-plated finish.
- C. One-Piece, Cast-Brass Type: With set screw.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Finish: Polished chrome-plated.
- D. Split-Casting, Cast-Brass Type: With concealed hinge and set screw.
 - 1. Finish: Polished chrome-plated.
- E. One-Piece, Floor-Plate Type: Cast-iron floor plate.
- F. Split-Casting, Floor-Plate Type: Cast brass with concealed hinge and set screw.

2.7 GROUT

- A. Description: ASTM C 1107, Grade B, non-shrink and non-metallic, dry hydraulic cement grout.
 - 1. Characteristics: Post-hardening, volume-adjusting, non-staining, non-corrosive, non-gaseous, and recommended for interior and exterior applications.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.
 - 3. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 HVAC DEMOLITION

- A. Refer to Sections "Cutting and Patching" and "Selective Structure Demolition" for general demolition requirements and procedures.
- B. Disconnect, demolish, and remove HVAC systems, equipment, and components indicated to be removed.
 - 1. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
 - 2. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material.
 - 3. Equipment to Be Removed: Remove equipment and associated piping back to main unless otherwise indicated. Cap services.
 - 4. Equipment to Be Removed and Reinstalled: Disconnect and cap services. Remove, clean, and store equipment. When appropriate, reinstall, reconnect, and make equipment operational.
 - 5. Equipment to Be Removed and Salvaged: Remove equipment and associated piping back to main unless otherwise indicated. Cap services. Remove equipment, clean, and store as directed (May be off-site). Make available to owner at time of the owner's choosing.
- C. If pipe, insulation, or equipment to remain is damaged in appearance or is unserviceable, remove damaged or unserviceable portions and replace with new products of equal capacity and quality.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.2 PIPING SYSTEMS - COMMON REQUIREMENTS

- A. Install piping according to the following and Division 23 Sections specifying piping systems.
- B. Install piping in concealed locations, unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated.
- D. Install piping above accessible ceilings allowing sufficient space for ceiling panel removal.
- E. Install piping to permit valve operation & servicing.
- F. Install condensate drain piping at 1% slope.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections unless otherwise indicated.
- I. Install piping leaving room for installation of insulation.
- J. Install system components with pressure rating equal to or greater than system operating pressure.
- K. Install escutcheons for penetrations of walls, ceilings, and floors according to the following:
 - 1. Exposed, Interior Installations/Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type.
 - 2. Exposed, Interior Installations/Chrome-Plated Piping: One-piece, cast-brass type with polished chrome-plated finish and set-screw.
 - 3. Exposed, Interior Installations/Insulated Piping: One-piece, cast-brass type with polished chrome-plated finish.
 - 4. Exposed, Interior Installations/Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece, cast-brass type with finish to match surrounding surfaces.
 - 5. Exposed, Interior Installations/Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece or split-casting, cast-brass type with finish to match surrounding surfaces.
 - 6. Exposed, Interior Installations/Piping in Unfinished Service Spaces: None, provide sealant.
 - 7. Exposed, Interior Installations/Piping in Equipment Rooms: None, provide sealant.
 - 8. Exposed, Interior Installations/Piping at Floor Penetrations in Equipment Rooms, Fan Rooms, or similar wet spaces: None provide sealant and sleeve extending 2" above floor to prevent liquid leaking to floor below.
- L. Provide seal around piping penetrations of full height interior walls, both rated and non-rated, that occur above ceilings. Refer to Section 079200 Joint Sealants.
- M. Sleeves are not required for core-drilled holes.
 - 1. Exception: Exposed, Interior Installations at Floor Penetrations in Equipment Rooms, Fan Rooms, or similar wet spaces.

- N. Permanent sleeves are not required for holes formed by removable PE sleeves.
 - 1. Exception: Exposed, Interior Installations at Floor Penetrations in Equipment Rooms, Fan Rooms, or similar wet spaces.
- O. Install sleeves for pipes passing through walls, floors, or roofs.
 - 1. Cut sleeves to length for mounting flush with both surfaces.
 - a. Exception: Extend sleeves installed in floors of mechanical equipment rooms, fan rooms or other similar wet areas 2 inches above finished floor level. Extend castiron sleeve fittings below floor slab as required to secure clamping ring.
 - 2. Install sleeves as walls and slabs are constructed.
 - a. PVC Pipe Sleeves: Permitted for pipes smaller than 6" except aboveground, exterior-walls.
 - b. Steel Sheet Sleeves: Permitted for pipes 6" and larger, penetrating gypsum-board partitions except aboveground, exterior-walls.
 - c. Seal space outside sleeve fittings with grout and sealant.
 - 3. Except for penetrations where mechanical sleeve seals are used, seal annular space between sleeve and pipe or pipe insulation, using joint sealants appropriate for size, depth, and location of joint. Refer to Section "Joint Sealants".
- P. Aboveground Exterior Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Select sleeve size to allow for annular clear space required by the mechanical sleeve seal manufacturer between pipe and sleeve for installing mechanical sleeve seals.
 - 1. Install steel pipe for sleeves smaller than 6 inches in diameter.
 - 2. Install cast-iron "wall pipes" for sleeves 6 inches and larger in diameter.
 - 3. Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
 - 4. Sleeves from an approved sleeve seal manufacturer shall be acceptable.
- Q. Underground Exterior Penetrations: Install cast-iron "wall pipes" for sleeves. Seal pipe penetrations using mechanical sleeve seals. Select sleeve size to allow for annular clear space required by the mechanical sleeve seal manufacturer between pipe and sleeve for installing mechanical sleeve seals.
- R. Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
- S. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Refer to Section "Penetration Firestopping" for materials.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- T. Verify final equipment locations for roughing-in.
- U. Refer to equipment specifications in other Sections of these Specifications for roughing-in requirements.

3.3 PIPING JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 22 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Soldered Joints: Apply water-flushable flux, unless otherwise indicated, to tube end. Construct joints using lead-free solder alloy.
- E. Brazed Joints: Construct joints using copper-phosphorus brazing filler metal.
- F. Threaded Joints: Thread pipe with tapered pipe threads. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads unless otherwise indicated.
- G. Welded Joints: Construct joints using qualified processes and welding operators.
- H. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.
- I. Mechanical Joints: Prepare pipe ends and fittings, apply coupling, and join according to joint manufacturer's written instructions.

3.4 PIPING CONNECTIONS

- A. Make connections according to the following, unless otherwise indicated:
 - 1. Install unions, in piping 2" and smaller, one adjacent to each valve and at final connections to each piece of equipment.
 - 2. Install flanges, in piping NPS 2-1/2" and larger, adjacent to final connections to each piece of equipment.
 - 3. Install dielectric unions or flanges for connections of dissimilar metals.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.5 EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- A. Install equipment to allow maximum possible headroom unless specific mounting heights are indicated.
- B. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.
- C. Install HVAC equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to service side of equipment.
- D. Install equipment to allow space for other systems.

3.6 PAINTING

A. Damage and Touchup: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.7 HOUSEKEEPING PADS AND EQUIPMENT PADS

- A. Housekeeping pads and equipment pads: Anchor equipment to concrete according to equipment manufacturer's written instructions and according to seismic codes at project location.
 - 1. Construct concrete pads in accordance with drawing details.
 - 2. Details may be found on structural drawings. If details are not provided comply with the following:
 - a. Housekeeping pads inside the building shall be 6" thick and 6" larger all around than supported equipment. Provide #4 rebar at 12" on center each way at middepth of slab. Provide a 3/4" chamfer on all edges.
 - b. Equipment pads outside the building shall be 8" thick with a 12" deep and 20" wide turndown (footing) all around the outside edge of the pad. Provide #5 rebar at 16" on center each way at mid-depth of slab. Pad shall be 6" larger all around than supported equipment.
 - c. Install epoxy-coated anchor bolts. For equipment on housekeeping pads bolts shall extend through housekeeping pad, and anchor into structural concrete floor.
 - d. Place and secure anchor bolts using supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions for placement.
 - e. Install anchor bolts to elevations required for proper attachment to supported equipment.
 - f. Install anchor bolts according to anchor bolt manufacturer's written instructions.
 - g. Use 3000-psi, 28-day compressive-strength concrete and reinforcement as specified in Section "Cast-in-Place Concrete".

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.8 ERECTION OF METAL SUPPORTS AND ANCHORAGES

- A. Refer to Section "Metal Fabrications" for structural steel.
- B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor HVAC materials and equipment.
- C. Field Welding: Comply with AWS D1.1.

3.9 GROUTING

- A. Mix and install grout for HVAC equipment base bearing surfaces, pump and other equipment base plates, and anchors.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms as required for placement of grout.
- D. Avoid air entrapment during placement of grout.
- E. Place grout, completely filling equipment bases.
- F. Place grout on concrete bases and provide smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout.

END OF SECTION 230500

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 230513 – MOTORS FOR HVAC EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

A. Manufacturer's catalog and efficiency data.

1.3 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70.

1.4 COORDINATION

- A. All motors are required to be equipped with overload protection located near the motor.
 - 1. Overload protection shall:
 - a. Be located between the circuit breaker or fuse provided under Division 26 and the motor windings.
 - b. Meet one of the options specified in the following paragraph.
 - 2. Overload protection may be:
 - a. Located in the motor installed by the motor manufacturer. (preferred)
 - b. A separate device located near the motor.
 - c. Located in, or with, a disconnect switch provided by the equipment manufacturer. Provision of this switch shall not modify, change, or eliminate any Division 26 requirement. This means some equipment shall be provided or specified with two disconnecting means.
- B. Coordinate features of motors, installed units, and accessory devices. Provide motors that are:
 - 1. Compatible with controller
 - 2. Matched to torque and horsepower requirements of the load.
 - 3. Matched to ratings and characteristics of supply circuit and required control sequence.
- C. Coordinate motor support with requirements for driven load; access for maintenance and motor replacement; installation of accessories, belts, belt guards; and adjustment of sliding rails for belt tensioning.
- D. Belt tension must be wrench and socket adjustable.
- E. Belt tensioning device must accommodate adjustable sheaves.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 2 - PRODUCTS

2.1 MOTOR REQUIREMENTS

- A. Motor requirements apply except as follows:
 - 1. Ratings, performance, or characteristics for a motor are specified in another Section or are scheduled on the drawings.
 - 2. Motor manufacturer requires ratings, performance, or characteristics, other than those specified to meet indicated performance.

2.2 MOTOR CHARACTERISTICS

- A. Frequency Rating: 60 Hz.
- B. Voltage Rating: NEMA standard voltage selected to operate on nominal circuit voltage to which motor is connected.
- C. Duty: Continuous at 105 deg F and 3300 feet above sea level.
- D. Capacity and Torque sufficient to:
 - 1. Start, accelerate, and operate connected load.
 - 2. Maintain designated speeds.
 - 3. Operate at installed altitude and environment.
 - 4. Operate with indicated operating sequence.
 - 5. Operate without exceeding nameplate ratings.
 - 6. Operate without utilizing service factor.
- E. Enclosure: Open drip-proof unless otherwise indicated.
- F. Minimum Service Factor: 1.15 unless otherwise indicated.

2.3 POLYPHASE MOTORS

- A. Description: NEMA MG 1, Design B, medium induction motor.
- B. NEMA Premium efficiency motors shall meet the following full load efficiency:

HP	ODP			TEFC		
	6 Pole	4 Pole	2 Pole	6 Pole	4 Pole	2 Pole
1	82.5	85.5	77.0	82.5	85.5	77.0
1.5	86.5	86.5	84.0	87.5	86.5	84.0
2	87.5	86.5	85.5	88.5	86.5	85.5
3	88.5	89.5	85.5	89.5	89.5	86.5
5	89.5	89.5	86.5	89.5	89.5	88.5
7.5	90.2	91.0	88.5	91.0	91.7	89.5
10	91.7	91.7	89.5	91.0	91.7	90.2
15	91.7	93.0	90.2	91.7	92.4	91.0
20	92.4	93.0	91.0	91.7	93.0	91.0
25	93.0	93.6	91.7	93.0	93.6	91.7
30	93.6	94.1	91.7	93.0	93.6	91.7
40	94.1	94.1	92.4	94.1	94.1	92.4

50	94.1	94.5	93.0	94.1	94.5	93.0
60	94.5	95.0	93.6	94.5	95.0	93.6
75	94.5	95.0	93.6	94.5	95.4	93.6
100	95.0	95.4	93.6	95.0	95.4	94.1
125	95.0	95.4	94.1	95.0	95.4	95.0
150	95.4	95.8	94.1	95.8	95.8	95.0

- C. Efficiency: NEMA Premium
- D. Stator: Copper windings, unless otherwise indicated.
- E. Rotor: Squirrel cage, unless otherwise indicated.
- F. Bearings: Double-shielded, pre-lubricated ball bearings suitable for radial and thrust loading.
 - a. For motors 100 HP or greater, bearings shall be ceramic.
- G. Temperature Rise: Match insulation rating, unless otherwise indicated.
- H. Insulation: Class F, unless otherwise indicated.
- I. Code Letter Designation: NEMA starting Code F or G.
- J. Enclosure: Cast iron.
- K. Finish: Gray enamel.
- L. Motors Used with Reduced-Inrush Controllers: Match wiring connection requirements for controller with required motor leads. Provide terminals in motor terminal box, suited to control method.
- M. Motors Used with Variable Speed Drives: Ratings, characteristics, and features coordinated with and approved by controller manufacturer.
 - 1. Windings: Copper magnet wire with moisture-resistant insulation varnish, designed and tested to resist transient spikes, high frequencies, and short time rise pulses produced by pulse-width modulated inverters.
 - 2. Premium Efficiency Motors: Class B temperature rise, Class F insulation.
 - 3. Inverter-Duty Motors: Class F temperature rise, Class H insulation.
 - 4. Thermal Protection: Comply with NEMA MG 1 requirements for thermally-protected motors.
 - 5. Shaft Grounding: Provide AEGIS bearing protection ring or approved equal.
 - a. All motors operated on variable frequency drives shall be equipped with a maintenance free, conductive micro fiber, shaft grounding ring with a minimum of two rows of circumferential micro fibers to discharge electrical shaft currents within the motor and/or its bearings.
 - b. Motors up to 100 HP shall be provided with a minimum of one shaft grounding ring installed either on the drive end or non-drive end. Motors over 100 HP shall be provided with an insulated bearing on the non-drive end and a shaft grounding ring on the drive end of the motor.
 - c. Grounding rings shall be provided and installed by the motor manufacturer in accordance with the shaft grounding ring manufacturer's recommendations.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- N. Source Quality Control: Perform the following tests on each motor according to NEMA MG 1:
 - 1. Measure winding resistance.
 - 2. Read no-load current and speed at rated voltage and frequency.
 - 3. Measure locked rotor current at rated frequency.
 - 4. Perform high-potential test.

PART 3 - EXECUTION

3.1 FIELD QUALITY CONTROL

- A. Perform the following:
 - 1. Run each motor with its controller at load.
 - 2. Demonstrate correct rotation, alignment, and speed.
 - 3. Test interlocks and control features for proper operation.
 - 4. Verify that current in each phase is within nameplate rating.
 - 5. Verify RPM is in accordance with nameplate.
 - 6. Where a generator is provided, run each motor on the generator with its controller and load. Demonstrate correct rotation, alignment, and speed.

3.2 ADJUSTING

A. Align motors, bases, and shafts.

3.3 CLEANING

A. After completing equipment installation, inspect unit components. Remove paint splatters and other spots, dirt, and debris. Repair damaged finish to match original finish.

END OF SECTION 230513

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 230529 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. MSS: Manufacturers Standardization Society of the Valve and Fittings Industry Inc.
- B. Terminology as defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

1.3 PERFORMANCE REQUIREMENTS

- A. Design Requirement: Design trapeze pipe hangers and equipment supports, including comprehensive engineering analysis by a qualified professional engineer where using methods other than indicated.
- B. Structural Performance: Hangers and supports for HVAC piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
 - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test medium.
 - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Show fabrication and installation details and include calculations for the following and include Product Data for components:
 - 1. Trapeze pipe hangers.
 - 2. Metal framing systems.
 - 3. Pipe stands.
 - 4. Equipment supports.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.5 QUALITY ASSURANCE

- A. Structural Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."
- B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.

PART 2 - PRODUCTS

2.1 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
 - 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
 - 2. Galvanized Metallic Coatings: Pre-galvanized or hot dipped.
 - 3. Nonmetallic Coatings: Plastic coating, jacket, or liner.
 - 4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
 - 5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

B. Copper Pipe Hangers:

- 1. Description: MSS SP-58, Types 1 through 58, copper-coated-steel, factory-fabricated components.
- 2. Hanger Rods: Continuous-thread rod, nuts, and washer made of copper-coated steel.

2.2 THERMAL-HANGER SHIELD INSERTS

- A. Available Manufacturers:
 - 1. Carpenter & Paterson, Inc.
 - 2. Clement Support Services.
 - 3. ERICO International Corporation.
 - 4. National Pipe Hanger Corporation.
 - 5. PHS Industries, Inc.
 - 6. Pipe Shields, Inc.; a subsidiary of Piping Technology & Products, Inc.
 - 7. Piping Technology & Products, Inc.
 - 8. Rilco Manufacturing Co., Inc.
 - 9. Value Engineered Products, Inc.
- B. Insulation-Insert Material for Cold Piping: ASTM C 552, Type II cellular glass with 100-psig or ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength and vapor barrier.
- C. Insulation-Insert Material for Hot Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate with 100-psig, ASTM C 552, Type II cellular glass with 100-psig, or

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

ASTM C 591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength.

- D. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- E. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- F. Insert Length: Extend 2" beyond sheet metal shield for piping operating below ambient air temperature.

2.3 PIPE STANDS

- A. General Requirements for Pipe Stands: Shop- or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.
 - 1. Available Manufacturers:
 - a. Cooper B-Line Dura-Blok
 - b. MAPA Products
 - c. Mifab, Inc. C-Port
 - d. Miro Industries, Inc.
 - e. OMG, Inc.
 - f. PHP Systems/Design
 - g. Pipe Prop
 - h. Roof Top Blox
 - i. Rooftop Support Systems Eberl Iron Works, Inc.
 - 2. Provide pipe supports for supporting gas, condensate, refrigeration lines, or hydronic piping on flat roof surfaces. Support shall rest on roof surface without penetrating the roof surface. Supports for condensate piping shall be adjustable vertically to ensure pipe slopes as required.
- B. Compact Pipe Stand: One-piece plastic unit with integral-rod roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.
- C. Curb Mounted Pipe Stands: Shop- or field-fabricated pipe supports made from structural-steel shapes, continuous-thread rods, and rollers, for mounting on permanent stationary roof curb.

2.4 EQUIPMENT SUPPORTS/RAILS

- A. Description: Welded, shop or field fabricated equipment support made from structural carbon-steel shapes unless indicated otherwise.
 - 1. Available Manufacturers:
 - a. Curbs Plus, Inc. CPES-X
 - b. Kees Equipment Support Model SF
 - c. Pate Company Equipment Support ES-2
 - d. Portals Plus ER-2A
 - e. Roof Products and Systems Equipment Rails ER-2B
 - f. Thybar Corporation TEMS 3

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2. Construction:

- a. Minimum 18 gauge, G90 galvanized steel. Fully mitered and welded corners. Integral base plate. 3" Cant style support. All welds prime painted after fabrication. Full-depth internal C-channel reinforcing on 12" centers and 6" spreader channels on alternating 12" centers. 18 Gauge counterflashing factory-installed with tekscrews and neoprene washers. Factory-installed 2'x4" pressure-treated wood nailer.
- b. Minimum height of 12" above finished roof or as noted.

2.5 MISCELLANEOUS MATERIALS

- A. Structural Steel: ASTM A 36/A 36M, carbon-steel plates, shapes, and bars; black and galvanized.
- B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, non-shrink and nonmetallic grout; suitable for interior and exterior applications.
 - 1. Properties: Non-staining, noncorrosive, and nongaseous.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Provide hangers, supports, clamps, and attachments as required to properly support piping from the building structure.
- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69, MSS SP-89, and Table above. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.
- D. Thermal-Hanger Shield Installation: Provide in pipe hanger or shield for insulated piping.
- E. Pipe Stand Installation:
 - 1. Pipe Stand Types except Curb-Mounted Type: Assemble components and mount on smooth roof surface. Do not penetrate roof membrane.
 - 2. Curb-Mounted-Type Pipe Stands: Assemble components or fabricate pipe stand and mount on permanent, stationary roof curb. See Division 07 Section "Roof Accessories" for curbs
- F. Provide hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- H. Provide lateral bracing with pipe hangers and supports to prevent swaying.
- I. Provide building attachments within concrete slabs or attach to structural steel. Building attachments may not used on steel joists unless otherwise indicated. Provide additional attachments at concentrated loads, including valves, flanges, and strainers, 2-1/2" and larger and at changes in direction of piping. Provide concrete inserts before concrete is placed; fasten inserts to forms and provide reinforcing bars through openings at top of inserts.
- J. Load Distribution: Provide hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- K. Pipe Slopes: Provide hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.

L. Insulated Piping:

- 1. Attach clamps and spacers to piping.
 - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating below Ambient Air Temperature: Provide thermal-hanger shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
- 2. Provide MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
- 3. Provide MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
- 4. Shield Dimensions for Pipe: Not less than the following:
 - a. Pipe $\frac{1}{4}$ " to $3-\frac{1}{2}$ ": 12 inches long and 0.048 inch thick.
 - b. Pipe 4": 12 inches long and 0.06 inch thick.
 - c. Pipe 5" and 6": 18 inches long and 0.06 inch thick.
 - d. Pipe 8" to 14": 24 inches long and 0.075 inch thick.
- 5. Pipes 8" and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
- 6. Thermal-Hanger Shields: Provide with insulation same thickness as piping insulation.

3.2 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make bearing surface smooth.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.3 ROOF EQUIPMENT SUPPORTS

- A. Equipment supports must span a minimum of two structural roof members.
- B. No load shall be applied to a cantilever exceeding 12" in length.
- C. Fasten base flange to roof steel or deck with stitch weld or mechanical fastener not exceeding 18" on center in accordance with NRCA specifications.

3.4 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
 - 1. Provide materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

3.5 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.6 PAINTING

- A. Touchup: Unless otherwise indicated clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Provide same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and immediately apply galvanizing-repair paint. Paint shall comply with ASTM A 780.

3.7 HANGER AND SUPPORT SCHEDULE

A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.

- B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Provide hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.
- D. Provide nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Provide copper-plated pipe hangers and copper attachments for copper piping and tubing.
- F. Provide padded hangers for piping that is subject to scratching.
- G. Provide thermal-hanger shield inserts for insulated piping and tubing.
- H. Horizontal-Piping Hangers and Supports: Unless otherwise indicated provide the following:
 - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of stationary pipes ½" to 30".
 - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F pipes 4" to 14", requiring up to 4" of insulation.
 - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes ³/₄" to 14", requiring clamp flexibility and up to 4 inches of insulation.
 - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes ½" to 14" if little or no insulation is required.
 - 5. Pipe Hangers (MSS Type 5): For suspension of pipes ½" to 4", to allow off-center closure for hanger installation before pipe erection.
 - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes ³/₄" to 8".
 - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes ½" to 8".
 - 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes ½" to 8".
 - 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes ½" to 8".
 - 10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes ½" to 8".
 - 11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS ½" to 3".
 - 12. U-Bolts (MSS Type 24): For support of heavy pipes ½" to 14".
 - 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
 - 14. Pipe Saddle Supports (MSS Type 36): For support of pipes 4" to 14", with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
 - 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes 4" to 14", with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
 - 16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes 2-½" to 14" if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.

- 17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes 1" to 14", from two rods if longitudinal movement caused by expansion and contraction might occur.
- 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes 2-½" to 14", from single rod if horizontal movement caused by expansion and contraction might occur.
- 19. Complete Pipe Rolls (MSS Type 44): For support of pipes 2" to 14" if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
- 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes 2" to 14" if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
- 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes 2" to 14"if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- I. Vertical-Piping Clamps: Unless otherwise indicated provide the following:
 - 1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers 3/4" to 14".
 - 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers ³/₄" to 14" if longer ends are required for riser clamps.
- J. Hanger-Rod Attachments: Unless otherwise indicated provide the following:
 - 1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 - 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 - 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 - 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 - 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
 - 6. Flat Plate, Double Nut, and Washer as Detailed on Structural Drawings: For attaching to bar joists. Method of attachment to bar joists must be approved by the structural engineer and joist manufacturer.
- K. Building Attachments: Unless otherwise indicated provide the following:
 - 1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 - 2. Flat Plate, Double Nuts, and Washer as Detailed on Structural Drawings: For use under roof installations with bar-joist construction to attach to bottom chord of joist.
 - 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 - 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 - 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 - 6. C-Clamps (MSS Type 23): For steel I-beams. Only allowed for open web joists if load does not exceed 50 lbs.
 - 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 - 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 - 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel Ibeams for heavy loads.

- 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel Ibeams for heavy loads, with link extensions.
- 11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
- 12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Provide one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
- 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
- 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
- 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- 16. For sloping structure, provide clamp with swivel such that required threaded rod is vertical. Bending of threaded rod is not acceptable.
- L. Saddles and Shields: Unless otherwise indicated provide the followings:
 - 1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 - 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 - 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- M. Spring Hangers and Supports: Unless otherwise indicated provide the following:
 - 1. Restraint-Control Devices (MSS Type 47): To control pipe movement.
 - 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 - 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41, roll hanger with springs.
 - 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 - 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
 - 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
 - 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
 - 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- N. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- O. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- P. Provide powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where indicated in concrete construction.

END OF SECTION 230529

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 230548 - VIBRATION AND SEISMIC CONTROL FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. IBC: International Building Code.
- B. ICC-ES: ICC-Evaluation Service.
- C. OSHPD: Office of Statewide Health Planning & Development for the State of California.
- D. ASCE: American Society of Civil Engineers

1.3 PERFORMANCE REQUIREMENTS

- A. Seismic design category: C
 - 1. Provide Seismic installation of smoke control systems.
- B. Wind-Restraint Loading:
 - 1. Basic Wind Speed: 123 MPH
 - 2. Building Classification Category: III.
 - 3. Minimum 10 lb/sq. ft. multiplied by the maximum area of the HVAC component projected on a vertical plane that is perpendicular to the wind direction, and 45 degrees either side of perpendicular.
- C. Component coefficients shall be in accordance with the ASCE 7.

1.4 RESPONSIBILITIES:

- A. The manufacturer of vibration isolation and seismic restraint systems and devices shall:
 - 1. Determine the sizes and locations of isolators and seismic restraints.
 - 2. Provide equipment isolation and seismic restraint indicated.
 - 3. Guarantee indicated isolation system deflections.
 - 4. Provide installation instructions and drawings.
 - 5. Certify correctness of installation upon completion.
- B. The Contractor shall cause all vibration isolation systems, including the isolators, seismic restraints/snubbers and flexible connectors between the isolated equipment and associated piping, ducting, and electrical work to be designed by a manufacturer experienced in this type of work.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.5 SUBMITTALS

A. Product Data:

- 1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
- 2. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of seismic-restraint component used.
- 3. Interlocking Snubbers: Include ratings for horizontal, vertical, and combined loads.
- 4. Seismic and Wind-Restraint Details:
 - a. Design Analysis: To support selection and arrangement of seismic and wind restraints. Include calculations of combined tensile and shear loads.
 - b. Details: Indicate fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events. Indicate association with vibration isolation devices.
 - c. Coordinate seismic-restraint and vibration isolation details with wind-restraint details required for equipment mounted outdoors.
- B. Coordination Drawings: For areas indicated at ½" = 1'0" and where sections are cut on contract drawings, indicate coordination of seismic bracing for HVAC piping and equipment with other systems and equipment in the vicinity, include other supports and seismic restraints.
- C. Qualification Data: For testing agency.

D. Shop Drawings:

- 1. Vibration Isolation Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include auxiliary motor slides and rails, base weights, equipment static loads, power transmission, component misalignment, and cantilever loads.
- 2. Dimensioned Outline Drawings for Each Scheduled Piece of Equipment: Identify center of gravity.
- 3. Dimensioned Outline Drawings for Each Scheduled Piece of Equipment: Locate and describe mounting and anchorage provisions.
- E. Manufacturer Seismic Qualification Certification: Submit certification that all specified equipment will withstand seismic forces identified in "Performance Requirements" Article above. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event." Include the following:
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculations.
 - 2. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

1.6 QUALITY ASSURANCE

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- A. Seismic-restraint devices shall have horizontal and vertical load testing and analysis and shall bear anchorage preapproval OPA number from OSHPD, preapproval by ICC-ES, or preapproval by another agency acceptable to authorities having jurisdiction, showing maximum seismic-restraint ratings. Ratings based on independent testing are preferred to ratings based on calculations. If preapproved ratings are not available, submittals based on independent testing are preferred. Calculations (including combining shear and tensile loads) to support seismic-restraint designs must be signed and sealed by a qualified professional engineer.
- B. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."
- C. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
- D. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.

PART 2 - PRODUCTS

2.1 VIBRATION ISOLATORS

- A. Available Manufacturers:
 - 1. Amber/Booth Company, Inc.
 - 2. B-Line Systems, Inc.
 - 3. Kinetics Noise Control.
 - 4. Mason Industries.
 - 5. Vibration Mountings & Controls, Inc.
 - 6. Vibro-Acoustics, Inc.
- B. Pads: Oil- and water-resistant elastomer or natural rubber, arranged in single or multiple layers, molded with a nonslip pattern and galvanized steel baseplates of sufficient stiffness for uniform loading over pad area, and factory cut to sizes that match requirements of supported equipment.
 - 1. Resilient Material: Oil- and water-resistant neoprene.
 - 2. Durometer Rating: Minimum 30.
 - 3. Number of Layers: 1 2 3 or 4.
- C. Mounts: Double-deflection type, with molded, oil-resistant rubber, or neoprene isolator elements with factory-drilled, encapsulated top plate for bolting to equipment and with baseplate for bolting to structure. Color-code or otherwise identify to indicate capacity range.
 - 1. Durometer Rating: Minimum 30.
 - 2. Materials: Cast-ductile-iron or welded steel housing containing two separate and opposing, oil-resistant rubber or neoprene elements that prevent central threaded element and attachment hardware from contacting the housing during normal operation.
 - 3. Neoprene: Shock-absorbing materials compounded according to the standard for bridge-bearing neoprene as defined by AASHTO.

- D. Restrained Mounts: All-directional mountings with seismic restraint.
 - 1. Materials: Cast-ductile-iron or welded steel housing containing two separate and opposing, oil-resistant rubber or neoprene elements that prevent central threaded element and attachment hardware from contacting the housing during normal operation.
 - 2. Neoprene: Shock-absorbing materials compounded according to the standard for bridge-bearing neoprene as defined by AASHTO.
- E. Spring Isolators: Freestanding, laterally stable, open-spring isolators.
 - 1. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 - 2. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 - 3. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 - 4. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 - 5. Baseplates: Factory drilled for bolting to structure and bonded to ½" thick, rubber isolator pad attached to baseplate underside. Baseplates shall limit floor load to 500 psig.
 - 6. Top Plate and Adjustment Bolt: Threaded top plate with adjustment bolt and cap screw to fasten and level equipment.
- F. Restrained Spring Isolators: Freestanding, steel, open-spring isolators with seismic or limit-stop restraint.
 - 1. Housing: Steel with resilient vertical-limit stops to prevent spring extension due to weight being removed; factory-drilled baseplate bonded to ½" thick, neoprene or rubber isolator pad attached to baseplate underside; and adjustable equipment mounting and leveling bolt that acts as blocking during installation.
 - 2. Restraint: Seismic or limit stop as required for equipment and authorities having jurisdiction.
 - 3. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 - 4. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 - 5. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 - 6. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
- G. Housed Spring Mounts: Housed spring isolator with integral seismic snubbers.
 - 1. Housing: Ductile-iron or steel housing to provide all-directional seismic restraint.
 - 2. Base: Factory drilled for bolting to structure.
 - 3. Snubbers: Vertically adjustable to allow a maximum of ½" travel up or down before contacting a resilient collar.
- H. Elastomeric Hangers: Double-deflection type, with molded, oil-resistant rubber or neoprene isolator elements bonded to steel housings with threaded connections for hanger rods. Colorcode or otherwise identify to indicate capacity range.
- I. Spring Hangers: Combination coil-spring and elastomeric-insert hanger with spring and insert in compression.

- 1. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
- 2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
- 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
- 4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
- 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
- 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene. Steel-washer-reinforced cup to support spring and bushing projecting through bottom of frame.
- 7. Self-centering hanger rod cap to ensure concentricity between hanger rod and support spring coil.
- J. Spring Hangers with Vertical-Limit Stop: Combination coil-spring and elastomeric-insert hanger with spring and insert in compression and with a vertical-limit stop.
 - 1. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
 - 2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 - 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 - 4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 - 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 - 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
 - 7. Adjustable Vertical Stop: Steel washer with neoprene washer "up-stop" on lower threaded rod
 - 8. Self-centering hanger rod cap to ensure concentricity between hanger rod and support spring coil.
- K. Thrust Limits: Combination coil spring and elastomeric insert with spring and insert in compression and with a load stop. Include rod and angle-iron brackets for attaching to equipment.
 - 1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
 - 2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 - 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 - 4. Lateral Stiffness: More than 80 percent of the rated vertical stiffness.
 - 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 - 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
 - 7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.
- L. Pipe Riser Resilient Support: All-directional, acoustical pipe anchor consisting of 2 steel tubes separated by a minimum of 1/2-inch- thick, 60-durometer neoprene. Include steel and neoprene

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

vertical-limit stops arranged to prevent vertical travel in both directions. Design support for a maximum load on the isolation material of 500 psig and for equal resistance in all directions.

M. Resilient Pipe Guides: Telescopic arrangement of 2 steel tubes separated by a minimum of 1/2-inch-thick, 60-durometer neoprene. Factory set guide height with a shear pin to allow vertical motion due to pipe expansion and contraction. Shear pin shall be removable and reinsertable to allow for selection of pipe movement. Guides shall be capable of motion to meet location requirements.

2.2 RESTRAINED VIBRATION ISOLATION ROOF-CURB RAILS

- A. Available Manufacturers:
 - 1. Amber/Booth Company, Inc.
 - 2. Kinetics Noise Control.
 - 3. Mason Industries.
 - 4. Vibration Mountings & Controls, Inc.
 - 5. Vibro-Acoustics, Inc.
- B. General Requirements for Restrained Vibration Isolation Roof-Curb Rails: Factory-assembled, fully enclosed, insulated, air- and watertight curb rail designed to resiliently support equipment and to withstand seismic and wind forces.
- C. Lower Support Assembly: Formed sheet-metal section containing adjustable and removable steel springs that support upper frame. Upper frame shall provide continuous support for equipment and shall be captive to resiliently resist seismic and wind forces. Lower support assembly shall have a means for attaching to building structure and a wood nailer for attaching roof materials, and shall be insulated with a minimum of 2" of rigid, glass-fiber insulation on inside of assembly.
- D. Spring Isolators: Adjustable, restrained spring isolators shall be mounted on 1/4-inch- (6-mm-) thick, elastomeric vibration isolation pads and shall have access ports, for level adjustment, with removable waterproof covers at all isolator locations. Isolators shall be located so they are accessible for adjustment at any time during the life of the installation without interfering with the integrity of the roof.
 - 1. Restrained Spring Isolators: Freestanding, steel, open-spring isolators with seismic or wind restraint.
 - a. Housing: Steel with resilient vertical-limit stops and adjustable equipment mounting and leveling bolt.
 - b. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 - c. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 - d. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 - e. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
- E. Snubber Bushings: All-directional, elastomeric snubber bushings at least 1/4 inch (6 mm) thick.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

F. Water Seal: Galvanized sheet metal with EPDM seals at corners, attached to upper support frame, extending down past wood nailer of lower support assembly, and counterflashed over roof materials.

2.3 VIBRATION ISOLATION EQUIPMENT BASES

- A. Available Manufacturers:
- B. Manufacturers:
 - 1. Amber/Booth Company, Inc.
 - 2. Kinetics Noise Control.
 - Mason Industries.
 - 4. Vibration Mountings & Controls, Inc.
 - 5. Vibro-Acoustics, Inc.
- C. Steel Base: Factory-fabricated, welded, structural-steel bases and rails.
 - 1. Design Requirements: Lowest possible mounting height with not less than 1" clearance above the floor. Include equipment anchor bolts and auxiliary motor slide bases or rails.
 - a. Include supports for suction and discharge elbows for pumps.
 - 2. Structural Steel: Steel shapes, plates, and bars complying with ASTM A 36/A 36M. Bases shall have shape to accommodate supported equipment.
 - 3. Support Brackets: Factory-welded steel brackets on frame for outrigger isolation mountings and to provide for anchor bolts and equipment support.
- D. Inertia Base: Factory-fabricated, welded, structural-steel bases and rails ready for placement of cast-in-place concrete.
 - 1. Design Requirements: Lowest possible mounting height with not less than 1-inch (25-mm) clearance above the floor. Include equipment anchor bolts and auxiliary motor slide bases or rails.
 - a. Include supports for suction and discharge elbows for pumps.
 - 2. Structural Steel: Steel shapes, plates, and bars complying with ASTM A 36/A 36M. Bases shall have shape to accommodate supported equipment.
 - 3. Support Brackets: Factory-welded steel brackets on frame for outrigger isolation mountings and to provide for anchor bolts and equipment support.
 - 4. Fabrication: Fabricate steel templates to hold equipment anchor-bolt sleeves and anchors in place during placement of concrete. Obtain anchor-bolt templates from supported equipment manufacturer.

2.4 SEISMIC-RESTRAINT DEVICES

- A. Available Manufacturers:
 - 1. Amber/Booth Company, Inc.
 - 2. Cooper B-Line, Inc.; a division of Cooper Industries.
 - 3. Hilti, Inc.
 - 4. Kinetics Noise Control.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 5. Mason Industries.
- 6. Unistrut; Tyco International, Ltd.
- 7. Vibro-Acoustics, Inc.
- B. Structural Safety Factor: Allowable strength in tension, shear, and pullout force of components shall be at least four times the maximum seismic forces to which they will be subjected.
- C. Snubbers: Factory fabricated using welded structural-steel shapes and plates, anchor bolts, and replaceable resilient isolation washers and bushings.
 - 1. Anchor bolts for attaching to concrete shall be seismic-rated, drill-in, and stud-wedge or female-wedge type.
 - 2. Resilient Isolation Washers and Bushings: Oil- and water-resistant neoprene.
 - 3. Maximum ¼" air gap, and minimum ¼" thick resilient cushion.
- D. Channel Support System: MFMA-3, shop- or field-fabricated support assembly made of slotted steel channels with accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; and rated in tension, compression, and torsion forces.
- E. Restraint Cables: ASTM A 603 galvanized steel cables with end connections made of steel assemblies with thimbles, brackets, swivels, and bolts designed for restraining cable service; and with a minimum of two clamping bolts for cable engagement.
- F. Hanger Rod Stiffener: Provide for affected systems steel tube, steel slotted-support-system sleeve with internally bolted connections, or reinforcing steel angle clamped to hanger rod.
- G. Bushings for Floor-Mounted Equipment Anchor Bolts: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchor bolts and studs.
- H. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices used.
- I. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.
- J. Mechanical Anchor Bolts for nonisolated equipment in up to 10 hp: Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488. Minimum length of eight times diameter.
- K. Adhesive Anchor Bolts: Drilled-in and capsule anchor system containing polyvinyl or urethane methacrylate-based resin and accelerator, or injected polymer or hybrid mortar adhesive. Provide anchor bolts and hardware with zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488.

2.5 FACTORY FINISHES

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- A. Finish: Manufacturer's standard paint applied to factory-assembled and -tested equipment before shipping.
 - 1. Powder coating on springs and housings.
 - 2. All hardware shall be galvanized. Hot-dip galvanize metal components for exterior use.
 - 3. Baked enamel or powder coat for metal components on isolators for interior use.
 - 4. Color-code or otherwise mark vibration isolation and seismic and wind control devices to indicate capacity range.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and equipment to receive vibration isolation and seismic- and wind-control devices for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLICATIONS

- A. Multiple Pipe Supports: Secure pipes to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.
- B. Hanger Rod Stiffeners: Install hanger rod stiffeners where required to prevent buckling of hanger rods due to seismic forces.
- C. Strength of Support and Seismic-Restraint Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry seismic loads within loading limits.

3.3 VIBRATION-CONTROL AND SEISMIC-RESTRAINT DEVICE INSTALLATION

A. Comply with requirements indicated in the Contract Documents, in codes and ordinances, by Authority Having Jurisdiction, and by Manufacturer, for installation of all devices.

3.4 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

A. Install flexible connections in piping where they cross seismic joints, where adjacent sections or branches are supported by different structural elements, and where the connections terminate with connection to equipment that is anchored to a different structural element from the one supporting the connections as they approach equipment.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.5 FIELD QUALITY CONTROL

A. Perform tests.

B. Tests:

- 1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
- 2. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
- 3. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
- 4. Test at least four of each type and size of installed anchors and fasteners selected by Architect.
- 5. Test to 90 percent of rated proof load of device.
- 6. Measure isolator restraint clearance.
- 7. Measure isolator deflection.
- 8. Verify snubber minimum clearances.
- 9. If a device fails test, modify all installations of same type and retest until satisfactory results are achieved.
- C. Prepare test reports.

3.6 ADJUSTING

- A. Adjust isolators after piping system is at operating weight.
- B. Adjust limit stops on restrained spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.
- C. Adjust active height of spring isolators.
- D. Adjust restraints to permit free movement of equipment within normal mode of operation.

3.7 VIBRATION ISOLATION SCHEDULE

A. Piping and Conduit

- 1. All piping and conduit connected to pumps, air handling units, or other pieces of moving equipment which are isolated from the structure by spring type vibration isolators shall be isolated from these units by flexible pipe connectors and shall be suspended on isolation hangers to a point 20 feet away. Refer to Section "Hydronic Piping" for flexible pipe connectors.
- 2. Provide spring hangers with 1/2" deflection for suspended piping.
- 3. Provide spring isolators with 1/2" deflection for floor-mounted piping.
- B. Ductwork

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1. Flexible connectors shall be used for ductwork connections to air handling units. Refer to Section "Metal Duct Accessories." Ductwork shall be suspended with elastomeric hangers for a distance of 20 feet from air handling units.

C. Indoor Air Handling Units

1. Provide elastomeric neoprene isolator pad with 1/4" deflection located on concrete equipment pad.

D. Power Ventilators

1. Provide elastomeric hangers for units suspended from structure above ceiling.

E. Condensing Units

1. Provide elastomeric neoprene isolator pad with 1/4" deflection located on equipment curb.

END OF SECTION 230548

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 230553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Equipment labels.
 - 2. Warning signs and labels.
 - 3. Pipe labels.
 - 4. Duct labels.
 - 5. Warning tags.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- C. Valve numbering scheme.
- D. Valve Schedules: For each piping system to include in maintenance manuals.

1.4 QUALITY ASSURANCE

A. ASME Compliance: Comply with ASME A13.1, "Scheme for the Identification of Piping Systems," for letter size, length of color field, colors, and viewing angles of identification devices for piping.

1.5 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with location of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

- A. Equipment Nameplates: Metal, with data engraved or stamped, for permanent attachment on equipment.
 - 1. Data:
 - a. Manufacturer, product name, model number, and serial number.
 - b. Capacity, operating and power characteristics, and essential data.
 - c. Labels of tested compliances.
 - 2. Location: Accessible and visible.
 - 3. Fasteners: As required to mount on equipment.
- B. Equipment Markers: Engraved, color-coded laminated plastic. Include contact-type, permanent adhesive.
 - 1. Terminology: Match schedules as closely as possible.
 - 2. Data:
 - a. Name and plan number.
 - b. Equipment service.
 - c. Design capacity.
 - d. Other design parameters such as pressure drop, entering and leaving conditions, and speed.
 - 3. Size: 2-1/2 by 4 inches for control devices, dampers, and valves; 4-1/2 by 6 inches for equipment.

C. Metal Labels for Equipment:

- 1. Material and Thickness: Brass, 0.032-inch stainless steel, 0.025-inch aluminum, 0.032-inch or anodized aluminum, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
- 2. Letter Color: White or black.
- 3. Background Color: Black or white.
- 4. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- 5. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- 6. Fasteners: Stainless-steel rivets or self-tapping screws.
- 7. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

D. Plastic Labels for Equipment:

- 1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8-inch-thick, and having predrilled holes for attachment hardware.
- 2. Letter Color: White or black.
- 3. Background Color: Black or white.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- 5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- 6. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- 7. Fasteners: Stainless-steel rivets or self-tapping screws.
- 8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- E. Access Panel and Door Markers: 1/16-inch-thick, engraved laminated plastic, with abbreviated terms and numbers corresponding to identification.
 - 1. Fasteners: Self-tapping, stainless-steel screws or contact-type, permanent adhesive.
- F. Label Content: Include equipment's drawing designation (tag) with unique equipment number as scheduled.

2.2 WARNING SIGNS AND LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8-inch thick, and having predrilled holes for attachment hardware.
- B. Letter Color: White or black.
- C. Background Color: Black or white.
- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- G. Fasteners: Stainless-steel rivets or self-tapping screws.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Label Content: Include equipment's drawing designation (tag) with unique equipment number as scheduled. Include caution and warning information plus emergency notification instructions.

2.3 PIPE LABELS

A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction according to ASME A13.1.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Pretensioned Pipe Labels: Pre-coiled, semi-rigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.
- C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.
- D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings; also include pipe size and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with piping system service lettering to accommodate both directions or as separate unit on each pipe label to indicate flow direction.
 - 2. Lettering Size: Size letters according to ASME A13.1 for piping.

2.4 DUCT LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8-inch-thick, and having predrilled holes for attachment hardware.
- B. Letter Color: White or black.
- C. Background Color: Black or white.
- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- G. Fasteners: Stainless-steel rivets or self-tapping screws.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- Duct Label Contents: Include identification of duct service using same designations or abbreviations as used on Drawings; also include duct size and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with duct system service lettering to accommodate both directions or as separate unit on each duct label to indicate flow direction.

2.5 WARNING TAGS

- A. Description: Preprinted or partially preprinted accident-prevention tags of plasticized card stock with matte finish suitable for writing.
 - 1. Size: 3 by 5-1/4 inches minimum.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Fasteners: Reinforced grommet and wire or string.
- 3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
- 4. Color: Safety-yellow background with black lettering.

2.6 ACOUSTICAL CEILING GRID MARKER

- A. General: Plastic tape a minimum of three one-thousandths of an inch thick (3.0 mils) with pressure-sensitive, permanent-type, self-adhesive back.
- B. Width: three quarters of an inch (3/4) or 22 millimeters.
- C. Letter Size: 1/4" minimum or 8 millimeters.
- D. Letter Color: Black
- E. Tape Color: White.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

3.3 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

3.4 PIPE LABEL INSTALLATION

A. Piping Color Coding: Painting of piping is specified in Section 099123 "Interior Painting."

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Pipe Label Locations: Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
 - 1. Near each valve and control device.
 - 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 - 3. Near penetrations and on both sides of through walls, floors, ceilings, and inaccessible enclosures.
 - 4. At access doors, manholes, and similar access points that permit view of concealed piping.
 - 5. Near major equipment items and other points of origination and termination.
 - 6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
 - 7. On piping above removable acoustical ceilings, omit intermediately spaced labels.
- C. Directional Flow Arrows: Arrows shall be used to indicate direction of flow in pipes, including pipes where flow is allowed in both directions.
- D. Pipe Label Color Schedule:
 - 1. Refrigerant Piping: Black letters on a safety-orange background.

3.5 DUCT LABEL INSTALLATION

- A. Install duct markers with permanent adhesive on air ducts in colors complying with ASME A13.1.
- B. Install plastic-laminated or self-adhesive duct labels with permanent adhesive on air ducts in the following color codes:
 - 1. Blue: For cold-air supply ducts.
 - 2. Yellow: For hot-air supply ducts.
 - 3. Green: For exhaust-, outside-, relief-, return-, and mixed-air ducts.
- C. Locate labels near points where ducts enter into and exit from concealed spaces and at maximum intervals of 50 feet in each space where ducts are exposed or concealed by removable ceiling system.

3.6 FIRE AND SMOKE DAMPERS

A. Access points for fire, smoke and fire-smoke dampers shall be permanently identified on the exterior of the duct by a label or sign with letters not less than 1" in height reading: "FIRE/SMOKE DAMPER, SMOKE DAMPER, or FIRE DAMPER."

3.7 ACOUSTICAL CEILING GRID MARKER INSTALLATION

A. Attach tape with indicated text to t-bar below item of equipment.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Attach tape to grid.
- C. Prepare surface and attach tape in accordance with manufacturer' recommendations.
- D. Surfaces to receive tape shall be clean and free of scale, dirt, and grease.
- E. Center tape on support grid. Tape shall be visible from within space.
- F. Provide with lettering at equipment located above lay-in tile ceilings including but not limited to:
 - 1. Air Handling Units: Text = AHU
 - 2. Fan Coil Units: Text = FCU
 - 3. Blower Coils: Text = BC
 - 4. Coils: Text = C
 - 5. Heat Pumps: Text = HP
 - 6. Fans: Text = F
 - 7. Damper operators: Text = D

3.8 WARNING-TAG INSTALLATION

A. Write required message on, and attach warning tags to, equipment and other items where required.

3.9 ADJUSTING

A. Relocate mechanical identification materials and devices that have become visually blocked by other work.

3.10 CLEANING

A. Clean faces of mechanical identification devices.

END OF SECTION 230553

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 230700 - HVAC INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

- A. Outdoor duct and pipe: Duct conveying untreated outside air at ambient temperature and humidity.
- B. Outdoor pipe: Pipe located outside the building insulation envelope.
- C. Supply air duct: Duct conveying air on the discharge side of an air handling unit or fan which will be delivered to a space in a building through a diffuser or connection to the return duct of another unit. Ductwork on the discharge side of a 100% outside air unit is considered to be Supply air duct.
- D. Return air duct: Duct conveying air from a space or plenum that will return to an air handling unit or energy transfer device. The air may be returned to the supply air duct after being conditioned, or it may be exhausted after passing through an energy transfer device. Typical examples of an energy transfer devices are plate heat exchangers, runaround coils, heat pipes, and energy wheels.
- E. Exhaust air duct: Duct conveying air from a space or plenum that will be exhausted from the building without being passed through an energy transfer device.
- F. Plenum: An unoccupied space or void, on the conditioned side of the building insulation and vapor barrier, being used to return conditioned air to the inlet side of a return or exhaust fan either directly or via a duct connection. An example would be a space with air handling light fixtures or openings in the ceiling used to transport air through the ceiling and then to an open duct located above the ceiling in another location.
- G. Indirectly Conditioned Space: A space having no direct conditioning but, due to air movement induced by an exhaust, or return opening, is conditioned by makeup air from an adjacent space. An example would be a small toilet. Boiler rooms, fan rooms, and mechanical rooms do not qualify as indirectly conditioned spaces.
- H. Inside the Building Insulation Envelope: For the purposes of this section, boiler rooms, fan rooms, and mechanical rooms are considered to be OUTSIDE the building insulation envelope.

1.3 SUBMITTALS

- A. Product Data: Identify thermal conductivity, thickness, and jackets (both factory and field applied, if any), for each type of product indicated.
- B. Shop Drawings: Show fabrication and installation details for the following:
 - 1. Detail application of removable insulation covers.
 - 2. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
 - 3. Detail attachment and covering of heat tracing inside insulation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Detail insulation application at pipe expansion joints for each type of insulation.
- 5. Detail insulation application at elbows, fittings, flanges, valves, and specialties for each type of insulation.
- 6. Detail removable insulation at piping specialties, equipment connections, and access panels.
- 7. Detail application of field-applied jackets.
- 8. Detail application at linkages of control devices.
- 9. Detail field application for each equipment type.

1.4 QUALITY ASSURANCE

- A. Fire-Test-Response Characteristics: Insulation and related materials shall have fire-test-response characteristics indicated, as determined by testing identical products per ASTM E 84, by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing and inspecting agency.
 - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
 - 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Ship insulation materials in containers marked by manufacturer with type, grade, and maximum use temperature.
- B. Ship Insulated Piping System Components on pallets and wood supports. Securely fasten and protect from damage. Store off the ground and cover with opaque waterproof tarp to protect materials from sunlight and rain.

1.6 COORDINATION

- A. Coordinate size and location of supports, hangers, and insulation shields specified in Section "Hangers and Supports for HVAC Piping and Equipment."
- B. Coordinate clearance requirements with piping Installer for piping insulation, duct Installer for duct insulation, and equipment Installer for equipment insulation.
- C. Maintain clearances required for maintenance.
- D. Coordinate installation and testing of heat tracing.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers:
 - 1. Mineral-Fiber Insulation:
 - a. CertainTeed Corporation.
 - b. Johns Manville.
 - c. Knauf Insulation.
 - d. Owens Corning.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Flexible Elastomeric Thermal Insulation:
 - a. Aeroflex USA, Inc.
 - b. Armacell, LLC.
 - c. K-Flex USA.
- 3. Polyolefin Insulation:
 - a. Armstrong World Industries, Inc.
 - b. IMCOA.
- 4. Closed-Cell Phenolic-Foam Insulation:
 - a. Kooltherm Insulation Products, Ltd.
- 5. Calcium Silicate Insulation:
 - a. Johns Manville.
 - b. Owens Corning.
- 6. Removable Insulation Covers:
 - a. Advance Thermal Corp.
- 7. Grease (Kitchen Hood) Exhaust Duct
 - a. 3M
 - b. Morgan Thermal Ceramics
 - c. Unifrax
- B. Comply with requirements in Part 3 schedule articles for where insulating materials shall be applied.
- C. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- D. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- E. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- F. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- G. Duct Liner: Refer to specification section "Metal Ducts"
- H. Mineral-Fiber Board: Glass fibers bonded with a thermosetting resin. Comply with ASTM C 612, Type IB, with factory applied FSK Jacket. Meet the requirements of ASTM C 1290, Type III, inorganic glass fibers bonded by a thermosetting resin to maximum service temperature of 250°F. Faced insulation shall not exceed 25 Flame Spread, 50 Smoke Developed when tested in accordance with ASTM E84.
- I. Semi-Rigid Mineral-Fiber Board: Glass fibers bonded with a thermosetting resin. Comply with ASTM C 1136, Type I, II, III, & IV with factory applied all-service jacket (ASJ) or Type II, IV with factory applied Foil Scrim Kraft (FSK) jacket.
- J. Mineral-Fiber Blanket with Factory Applied FSK Jacket: Meet the requirements of ASTM C 1290, Type III, inorganic glass fibers bonded by a thermosetting resin with a multi-purpose foil-scrim kraft (FSK) jacket to maximum service temperature of 250°F. FSK shall meet the requirements of ASTM C 1136, Type II, when surface burning characteristics are determined in accordance with ASTM E 84 with the foil surface of the material exposed to the flame as it is in

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

the final composite. Composite (insulation, facing and adhesive) shall not exceed 25 Flame Spread, 50 Smoke Developed when tested in accordance with ASTM E 84. Insulation properties shall be as follows:

- 1. Thickness: 1-1/2"
 - a. Density: 0.75 pcf
 - b. Minimum uncompressed R value: 5.1
 - c. Minimum installed R value assuming 25% compression: 4.2
- 2. Thickness: 2"
 - a. Density: 1.0 pcf
 - b. Minimum uncompressed R value: 7.4
 - c. Minimum installed R value assuming 25% compression: 6.0
- 3. Alternate to 2" 1.0 pcf: Thickness: 2.2"
 - a. Density: 0.75 pcf
 - b. Minimum uncompressed R value: 7.4
 - c. Minimum installed R value assuming 25% compression: 6.0
- 4. Thickness: 3"
 - a. Density: 0.75 pcf
 - b. Minimum uncompressed R value: 10.2
 - c. Minimum installed R value assuming 25% compression: 8.3
- K. Mineral-Fiber Pipe Insulation: Glass fibers bonded with a thermosetting resin complying with the following:
 - 1. Preformed Pipe Insulation: Comply with ASTM C 547, Type 1, with factory-applied, all-purpose, vapor-retarder jacket.
 - 2. Semi-Rigid Mineral-Fiber Board: Glass fibers bonded with a thermosetting resin. Comply with ASTM C 1136, Type I, II, III, IV with factory applied all-service jacket (ASJ) or Type II, IV with factory applied Foil Scrim Kraft (FSK) jacket.
 - 3. Mineral-Fiber Insulating Cements: Comply with ASTM C 195.
 - 4. Expanded or Exfoliated Vermiculite Insulating Cements: Comply with ASTM C 196.
 - 5. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449/C 449M.
- L. Flexible Elastomeric: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials and Type II for sheet materials.
 - 1. Adhesive: As recommended by insulation material manufacturer.
 - 2. Ultraviolet-Protective Coating: As recommended by insulation manufacturer.
- M. Prefabricated Thermal Insulating Fitting Covers: Comply with ASTM C 450 for dimensions used in preforming insulation to cover valves, elbows, tees, and flanges.
- 2.2 FIELD-APPLIED JACKETS
 - A. General: ASTM C 921, Type 1, unless otherwise indicated.
 - B. Glass Cloth: Woven glass-fiber fabric, plain weave, minimum 8 ounces per square yard.
 - C. Foil and Paper Jacket: Laminated, glass-fiber-reinforced, flame-retardant kraft paper and aluminum foil.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. Aluminum Jacket: Smooth or stucco embossed sheets manufactured from aluminum alloy complying with ASTM B 209 and having an integrally bonded moisture barrier over entire surface in contact with insulation. Factory cut and rolled to indicated sizes. Comply with ASTM B 209, 3003 alloy, H-14 temper.
 - 1. Finish and Thickness: Stucco-embossed finish, 0.016 inch thick.
 - 2. Moisture Barrier: 1-mil- thick, heat-bonded polyethylene and kraft paper.
 - 3. Elbows: Preformed, 45- and 90-degree, short- and long-radius elbows; same material, finish, and thickness as jacket.
- E. Standard PVC Pipe Fitting Covers: Factory-fabricated fitting covers manufactured from 20-mil-thick, high-impact, ultraviolet-resistant PVC.
 - 1. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories for the disabled.
 - 2. Adhesive: As recommended by insulation material manufacturer.

2.3 ACCESSORIES AND ATTACHMENTS

- A. Glass Cloth and Tape: Comply with MIL-C-20079H, Type I for cloth and Type II for tape. Woven glass-fiber fabrics, plain weave, presized a minimum of 8 oz./sq. yd..
 - 1. Tape Width: 4 inches.
- B. Bands: 3/4 inch wide, in one of the following materials compatible with jacket:
 - 1. Stainless Steel: ASTM A 666, Type 304; 0.020 inch thick.
 - 2. Galvanized Steel: 0.005 inch thick.
 - 3. Aluminum: 0.007 inch thick.
 - 4. Brass: 0.010 inch thick.
 - 5. Nickel-Copper Alloy: 0.005 inch thick.
- C. Wire: 0.080-inch, nickel-copper alloy; 0.062-inch, soft-annealed, stainless steel; or 0.062-inch, soft-annealed, galvanized steel.
- D. Weld-Attached Anchor Pins and Washers: Copper-coated steel pin for capacitor-discharge welding and galvanized speed washer. Pin length sufficient for insulation thickness indicated.
 - 1. Welded Pin Holding Capacity: 100 lb for direct pull perpendicular to the attached surface.
- E. Adhesive-Attached Anchor Pins and Speed Washers: Galvanized steel plate, pin, and washer manufactured for attachment to duct, pipe, plenum and breeching with adhesive. Pin length sufficient for insulation thickness indicated.
 - 1. Adhesive: Recommended by the anchor pin manufacturer as appropriate for surface temperatures of ducts, pipes, plenums, and breechings; and to achieve a holding capacity of 100 lb. for direct pull perpendicular to the adhered surface.
- F. Self-Adhesive Anchor Pins and Speed Washers: Galvanized steel plate, pin, and washer manufactured for attachment to duct, pipe, and plenum with adhesive. Pin length sufficient for insulation thickness indicated.
- G. Pipe Attachments for Flexible Elastomeric Insulation: Provide pipe support with high compressive strength material insert imbedded in closed-cell elastomeric foam to prevent

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

condensation and insulation damage at support points. Provide friction insulation tape for connection of pipe insulation to pipe support system.

1. Manufacturers:

- a. Aeroflex Aerofix
- b. Armacell Armafix Ecolight
- c. Cooper B-Line, Inc. / Eaton Armafix
- d. K-Flex USA K-Flex 360 Pipe Support
- e. ZSi-Foster Cush-A-Therm

2.4 VAPOR RETARDERS

A. Mastics: Materials that are compatible with insulation materials, jackets, and substrates.

2.5 REMOVABLE INSULATION COVERS

A. Pre-manufactured easily removable insulation cover/blanket intended for insulation of equipment and devices requiring periodic maintenance.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation and other conditions affecting performance of insulation application.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

3.3 GENERAL APPLICATION REQUIREMENTS

- A. Apply insulation materials, accessories, and finishes according to the manufacturer's written instructions; with smooth, straight, and even surfaces; and free of voids throughout the length of ducts, piping, and fittings.
- B. Refer to schedules at the end of this Section for materials, forms, jackets, and thickness required for each system.
- C. Use accessories compatible with insulation materials and suitable for the service. Use accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Apply multiple layers of insulation with longitudinal and end seams staggered.
- E. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- F. Seal joints and seams with vapor-retarder mastic on insulation indicated to receive a vapor retarder.
- G. Keep insulation materials dry at all times. Insulation that becomes wet or is otherwise damaged beyond repair, shall be removed immediately and replaced. Replacement material and installation shall be in accordance with these specifications.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- H. Apply insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by the insulation material manufacturer.
- I. Apply insulation with the minimum number of joints practical.
- J. Apply insulation over fittings, valves, and specialties, with continuous thermal and vaporretarder integrity, unless otherwise indicated.
- K. Refer to special instructions for applying insulation over fittings, valves, and specialties.
- L. Hangers and Anchors: Where vapor retarder is indicated, seal penetrations in insulation at hangers, supports, anchors, and other projections with vapor-retarder mastic.
 - 1. Apply insulation continuously through hangers and around anchor attachments.
 - 2. For insulation application where vapor retarders are indicated, extend insulation on anchor legs at least 12 inches from point of attachment to pipe and taper insulation ends. Seal tapered ends with a compound recommended by the insulation material manufacturer to maintain vapor retarder.
 - 3. Install insert materials and apply insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by the insulation material manufacturer.
 - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect the jacket from tear or puncture by the hanger, support, and shield.
- M. Insulation Terminations: For insulation application where vapor retarders are indicated, seal ends with a compound recommended by the insulation material manufacturer to maintain vapor retarder
- N. Apply insulation with integral jackets as follows:
 - 1. Pull jacket tight and smooth.
 - 2. Joints and Seams: Cover with tape and vapor retarder to maintain vapor seal.
 - 3. Vapor-Retarder Mastics: Where vapor retarders are indicated, apply mastic on seams and joints and at ends adjacent to duct flanges, pipe joints, and fittings.
- O. Cut insulation according to manufacturer's written instructions to prevent compressing insulation to less than 75 percent of its nominal thickness.
- P. Install vapor-retarder mastic on ducts, pipes, plenums, and equipment.
 - 1. Ducts, pipes, plenums, and equipment with Vapor Retarders: Overlap insulation facing at seams and seal with vapor-retarder mastic and pressure-sensitive tape having same facing as insulation. Repair punctures, tears, and penetrations with tape and mastic to maintain vapor-retarder seal.
 - 2. Ducts, pipes, plenums, and equipment without Vapor Retarders: Overlap insulation facing at seams and secure with outward clinching staples and pressure-sensitive tape having same facing as insulation.
- Q. Interior Wall and Partition Penetrations: Apply insulation continuously through walls and partitions, except fire-rated walls and partitions.
- R. Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire/smoke damper sleeves for fire-rated wall and partition penetrations.
- S. Floor Penetrations: Terminate insulation at underside of floor assembly and at floor support at top of floor.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1. For insulation indicated to have vapor retarders, taper termination and seal insulation ends with vapor-retarder mastic.

3.4 MINERAL-FIBER INSULATION APPLICATION

- A. Blanket Applications for Ducts, Pipes, and Plenums: Secure blanket insulation with adhesive, and anchor pins with speed washers.
 - 1. Apply adhesives according to manufacturer's recommended coverage rates per square foot, for 100 percent coverage of duct, pipe, and plenum surfaces.
 - 2. Apply adhesive to entire circumference of ducts & pipes and to all surfaces of fittings and transitions. Adhesive may be omitted from the top of horizontal rectangular ducts.
 - 3. Install anchor pins and speed washers on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
 - a. On duct sides with dimensions 18 inches and smaller, along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - b. On duct sides with dimensions larger than 18 inches. Space 16 inches o.c. each way, and 3 inches maximum from insulation joints. Apply additional pins and clips to hold insulation tightly against surface at cross bracing.
 - c. Anchor pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
 - d. Do not compress insulation to less than 75% of its original thickness during installation.
 - 4. Install anchor pins and speed washers on sides, top, and bottom of horizontal pipes.
 - 5. Impale insulation over anchors and attach speed washers.
 - 6. Cut excess portion of pins extending beyond speed washers. Cover exposed pins and washers with tape matching insulation facing.
 - 7. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation segment with 1/2-inch staples, 1-inch o.c., and cover with pressure-sensitive tape having same facing as insulation.
 - 8. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. Secure with steel band at end joints and spaced a maximum of 18 inches o.c.
 - 9. Apply insulation on rectangular duct elbows, pipe fittings, and transitions with a full insulation segment for each surface. Apply insulation on round and flat-oval duct elbows, and pipe elbows, with individually mitered gores cut to fit the elbow.
 - 10. Insulate duct and pipe stiffeners, hangers, and flanges that protrude beyond the insulation surface with 6-inch- wide strips of the same material as insulation. Secure on alternating sides of stiffener, hanger, and flange with anchor pins spaced 6 inches o.c.
 - 11. Apply vapor-retarder mastic to open joints, breaks, and punctures for insulation indicated to receive vapor retarder.
- B. Board Applications for Ducts, Plenums, & Equipment: Secure board insulation with adhesive and anchor pins and speed washers.
 - 1. Apply adhesives according to manufacturer's recommended coverage rates per square foot, for 100 percent coverage of duct, plenum, & equipment surfaces.
 - 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings, transitions, and equipment. Adhesive may be omitted from top surface of horizontal rectangular ducts.

3. Space anchor pins as follows:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. On duct & equipment sides with dimensions 18 inches and smaller, along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
- b. On duct & equipment sides with dimensions larger than 18 inches. Space 16 inches o.c. each way, and 3 inches maximum from insulation joints. Apply additional pins and clips to hold insulation tightly against surface at bracing.
- c. Anchor pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
- d. Do not compress insulation to less than 75% of its original thickness during installation.
- 4. Cut excess portion of pins extending beyond speed washers. Cover exposed pins and washers with tape matching insulation facing.
- 5. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation segment with 1/2-inch staples, 1-inch o.c., and cover with pressure-sensitive tape having same facing as insulation.
- 6. Apply insulation on rectangular duct elbows and transitions with a full insulation segment for each surface. Groove and score insulation to fit as closely as possible to outside and inside radius of elbows. Apply insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
- 7. Insulate duct and equipment stiffeners, hangers, and flanges that protrude beyond the insulation surface with 6" wide strips of the insulating materia. Secure on alternating sides of stiffener, hanger, and flange with anchor pins spaced 6 inches o.c.
- 8. Apply vapor-retarder mastic to open joints, breaks, and punctures for insulation indicated to receive vapor retarder.

3.5 FLEXIBLE ELASTOMERIC THERMAL INSULATION APPLICATION

- A. Apply insulation to ducts, plenums, and equipment as follows:
 - 1. Follow the manufacturer's written instructions for applying insulation.
 - 2. Seal longitudinal seams and end joints with manufacturer's recommended adhesive. Cement to avoid openings in insulation that will allow passage of air to the duct, plenum, and equipment surface.

3.6 FIELD-APPLIED JACKET APPLICATION

- A. Apply glass-cloth jacket, where indicated, directly over bare insulation or insulation with factory-applied jackets.
 - 1. Apply jacket smooth and tight to surface with 2-inch overlap at seams and joints.
 - 2. Embed glass cloth between two 0.062-inch- thick coats of jacket manufacturer's recommended adhesive.
 - 3. Completely encapsulate insulation with jacket, leaving no exposed raw insulation.

3.7 FINISHES

- A. Glass-Cloth Jacketed Insulation: Paint insulation finished with glass-cloth jacket as specified in Division 9 Section "Paints."
- B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

C. Color: Final color shall be as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.

3.8 DIFFUSER APPLICATIONS

- A. Insulate exposed metal surfaces on top of all supply diffusers. Where diffusers are mounted in a metal pan, insulate the top of the pan.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 1 inch.
 - 3. Vapor Retarder Required: Yes.
- B. Insulate slot diffuser plenums where uninsulated plenums are provided.

3.9 APPLICATIONS

- A. Insulation materials and thickness are specified at the end of this Section.
- B. Insulate all ductwork, pipe and equipment:
 - 1. Insulate ductwork in accordance with the application schedule(s) below.
 - 2. Exceptions: Unless otherwise indicated, do not apply insulation to the following systems, materials, and equipment:
 - a. Vibration-control devices.
 - b. Testing agency labels and stamps.
 - c. Nameplates and data plates.
 - d. Manholes.
 - e. Handholes.
 - f. Cleanouts.
 - g. Plastic condensate drain piping.
 - h. Pipe-mounted condensate sensors.
 - i. Return ductwork inside the building insulation envelope.
 - j. Indoor exposed return air ductwork.
 - k. Exhaust ductwork.
 - 1) Exception: Duct beginning 18" upstream of backdraft damper and continuing to building envelope insulation.
 - 1. Metal ducts with duct liner.
 - m. Factory-insulated flexible ducts.
 - n. Factory-insulated plenums, casings, terminal boxes, and filter boxes and sections.
 - o. Flexible connectors.
 - p. Access panels and doors in air-distribution systems.
 - q. Ductwork used for smoke control supply and exhaust.

3.10 INDOOR APPLICATION SCHEDULE

- A. Service: Condensate drain piping except plastic.
 - 1. Insulation Material: Mineral fiber preformed pipe insulation.
 - 2. Insulation Thickness: 1"
 - 3. Vapor Retarder Required: Yes.
 - 4. Finish: Finished Spaces = Painted, concealed = none.
- B. Refrigerant Suction and Hot-Gas Piping/Tubing:
 - 1. Insulation Material and Thickness:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Cellular Glass: 1-1/2 inches thick.
- b. Flexible Elastomeric: 1 inch thick.
- c. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
- C. Service: Unless otherwise indicated provide the following:
 - 1. Concealed Ducts and Plenums:
 - a. Material: Mineral-Fiber Blanket.
 - b. Thickness: 2 inches.
 - c. Vapor Retarder Required: Yes.
 - 2. Ducts and Plenums in Finished Spaces:
 - a. Material: Mineral-Fiber Board.
 - b. Thickness: 1-1/2 inches.
 - c. Field-Applied Jacket: Glass cloth.
 - d. Vapor Retarder Required: Yes.
 - e. Paint: Color as selected by architect. Refer to section "Painting".
- D. Service: Round and flat oval, supply-air ducts, concealed and within the building insulation envelope.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 1-1/2 inches.
 - 3. Vapor Retarder Required: Yes.
- E. Service: Round and flat oval, outside-air ducts, concealed and within the building insulation envelope.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 1-1/2 inches.
 - 3. Vapor Retarder Required: Yes.
- F. Service: Rectangular, supply-air ducts, concealed and within the building insulation envelope.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 1-1/2 inches.
 - 3. Vapor Retarder Required: Yes.
- G. Service: Rectangular, outside-air ducts, concealed and within the building insulation envelope.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 1-1/2 inches.
 - 3. Vapor Retarder Required: Yes.
- H. Service: Round and flat oval, supply-air ducts, concealed in vented attics and in unvented attics with insulated ceilings.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 2 inches.
 - 3. Vapor Retarder Required: Yes.
- I. Service: Round and flat oval, return-air ducts, concealed in vented attics and unvented attics with insulated ceilings.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 1-1/2 inches.
 - 3. Vapor Retarder Required: Yes.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- J. Service: Rectangular, supply-air ducts, concealed in vented attics and unvented attics with insulated ceilings.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 2 inches.
 - 3. Vapor Retarder Required: Yes.
- K. Service: Rectangular, return-air ducts, concealed in vented attics and unvented attics with insulated ceilings.
 - 1. Material: Mineral-Fiber Blanket Thermal Insulation with Factory Applied FSK Jacket.
 - 2. Thickness: 1-1/2 inches.
 - 3. Vapor Retarder Required: Yes.
- L. Service: Round and flat oval, supply-air ducts, exposed.
 - 1. Refer to section "Metal Ducts"
- M. Service: Round and flat oval, outside-air ducts, exposed.
 - 1. Refer to section "Metal Ducts"
- N. Service: Rectangular, supply-air ducts, in Finished Spaces.
 - 1. Material: Mineral-Fiber Board Thermal Insulation, Unfaced
 - 2. Thickness: 1-1/2 inches.
 - 3. Field-Applied Jacket: Glass cloth.
 - 4. Vapor Retarder Required: Yes.
 - 5. Paint: Color as selected by architect. Refer to section "Painting".
- O. Service: Rectangular, outside-air ducts, in Finished Spaces.
 - 1. Material: Mineral-Fiber Board Thermal Insulation, Unfaced
 - 2. Thickness: 2 inches
 - 3. Field-Applied Jacket: Glass cloth.
 - 4. Vapor Retarder Required: Yes.
 - 5. Paint: Color as selected by architect. Refer to section "Painting".
- P. Service: Range-hood exhaust ducts, concealed and in Finished Spaces.
 - 1. Range hood exhaust ducts shall be listed, labeled, factory-built, and insulated commercial kitchen grease ducts as specified in section "Metal Ducts".

3.11 OUTDOOR APPLICATION SCHEDULE

- A. Insulation shall be applied after heat tracing and temperature sensors are in place and have been tested.
- B. Refrigerant Suction and Hot-Gas Piping:
 - 1. Insulation Material and Thickness:
 - a. Flexible Elastomeric: 2 inches thick.
 - b. Mineral-Fiber, Preformed Pipe Insulation, Type I: 2 inches thick.
 - 2. Finish: Two coats of UV coating or mastic protectant recommended by the insulation manufacturer or outdoor aluminum jacket.

END OF SECTION 230700

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 230900 - BUILDING AUTOMATION SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUMMARY

A. Scope of Work:

- 1. Furnish a totally native BACnet-based system. The building controllers, application controllers, and input/output devices shall communicate using the protocols and network standards as defined by ANSI/ASHRAE Standard 135-2008, BACnet. No gateways shall be used for communication to controllers installed under this section. Gateways may be used for communication to existing systems or to systems installed under other sections.
- 2. Provide necessary BACnet-compliant hardware and software to meet the system's functional specifications. Provide Protocol Implementation Conformance Statement (PICS) for Windows-based control software and every controller in system, including unitary controllers.
- 3. Prepare individual hardware layouts, interconnection drawings, and software configuration from project design data.
- 4. Implement the detailed design for analog and binary objects, system databases, graphic displays, logs, and management reports based on control descriptions, logic drawings, configuration data, and bid documents.
- 5. Design, provide, and install equipment cabinets, panels, data communication network cables needed, and associated hardware.
- 6. Provide and install interconnecting cables between supplied cabinets, application controllers, and input/output devices.
- 7. Provide and install interconnecting cables between operator's terminals and peripheral devices supplied under this section.
- 8. Provide complete manufacturer's specifications for items that are supplied. Include vendor name of every item supplied.
- 9. Provide supervisory specialists and technicians at the job site to assist in phases of system installation, startup, and commissioning.
- 10. Provide comprehensive operator and technician training program as described herein.
- 11. Provide as-built documentation, operator's terminal software, diagrams, and other associated project operational documentation (such as technical manuals) on approved media, the sum total of which accurately represents the final system.
- 12. Provide new sensors, dampers, valves, and install only new electronic actuators.

B. Related Sections include the following:

1. Division 23 Section "Meters and Gauges for HVAC Piping" for measuring equipment that relates to this Section.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2. Division 23 Section "Sequence of Operations for HVAC Controls" for requirements that relate to this Section.

C. Work Under Other Sections:

- 1. All wells, valves, taps, dampers, flow stations, etc. furnished by the BAS manufacturer shall be installed under Section "Hydronic Piping".
- 2. The following shall be provided under Division 23 specifications sections:
 - a. 120V power to BAS panels and devices with circuits indicated on the drawings. See paragraph "Coordination" below.
 - b. Wiring of power feeds to disconnect switches and starters.
 - c. Wiring from disconnect switches and starters to electric motors.
 - d. Wiring of any remote start/stop switches and manual or automatic motor speed control devices not furnished under this section of the specifications.

1.3 SYSTEM DESCRIPTION

- A. A distributed logic control system complete with software and hardware functions shall be provided and installed. System shall be completely based on ANSI/ASHRAE Standard 135-2008, BACnet and achieved listing under the BACnet Testing Laboratories BACnet Advanced Workstation Software (B-AWS). This system is to control mechanical equipment, including but not limited to unitary equipment such as VAV boxes, heat pumps, fan-coils, AC units, air handlers and any other listed equipment using native BACnet-compliant components. Non-BACnet-compliant or proprietary equipment or systems (including gateways) shall not be acceptable and are specifically prohibited.
- B. Building controllers shall include complete energy management software, including scheduling building control strategies with optimum start and logging routines. Energy management software and firmware shall be resident in field hardware and shall not be dependent on the operator's terminal. Operator's terminal software is to be used for access to field-based energy management functions only. Provide zone-by-zone direct digital logic control of space temperature, scheduling, runtime accumulation, equipment alarm reporting, and override timers for after-hours usage.
- C. Room sensors shall be architecturally pleasing, sense temperature, allow tenant to override system and adjust temperature setpoint, and include a jack that allows the service technician to adjust any zone parameter. Include wiring for sensor and field service tool.
- D. Application controllers for every terminal unit (including but not limited to VAV) air handler, central plant equipment, and any other piece of controlled equipment shall be fully programmable. Application controllers shall be mounted next to controlled equipment and communicate with building controller through BACnet LAN.

1.4 SYSTEM PERFORMANCE

A. Comply with the following performance requirements:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Graphic Display: Display graphic with minimum 20 dynamic points with current data within 10 seconds.
- 2. Graphic Refresh: Update graphic with minimum 20 dynamic points with current data within 8 seconds.
- 3. Object Command: Reaction time of less than two seconds between operator command of a binary object and device reaction.
- 4. Object Scan: Transmit change of state and change of analog values to control units or workstation within six seconds.
- 5. Alarm Response Time: Annunciate alarm within 45 seconds.
- 6. Program Execution Frequency: Run capability of applications as often as five seconds, but selected consistent with mechanical process under control.
- 7. Performance: Programmable controllers shall execute DDC PID control loops, and scan and update process values and outputs at least once per second.
- 8. Reporting Accuracy and Stability of Control: Report values and maintain measured variables within tolerances as follows:
 - a. Space Temperature: Plus or minus 1 deg F.
 - b. Ducted Air Temperature: Plus or minus 1 deg F.
 - c. Outside Air Temperature: Plus or minus 2 deg F.
 - d. Dew Point Temperature: Plus or minus 3 deg F.
 - e. Temperature Differential: Plus or minus 0.25 deg F.
 - f. Relative Humidity: Plus or minus 5 percent.
 - g. Air Pressure (Ducts): Plus or minus 0.1-inch wg.
 - h. Electrical: Plus or minus 5 percent of reading.

1.5 WARRANTY

- A. Provide all services, materials and equipment necessary for the successful operation of the entire BAS system for a period of one year beginning on the date of Substantial Completion.
- B. Services, materials, and equipment shall include but not be limited to:
 - 1. The adjustment, required testing, and repair of the system including all computer equipment, transmission lines, transmission equipment, sensors and control devices.
 - 2. On-line support services shall be provided as follows:
 - a. The local BAS representative shall have the capability to monitor and control the facility's building automation system via a dialup or internet connection. This connection to the facility shall be made within 2 hours of the time a problem is reported.
 - b. If the problem is not resolved by local support, the national office of the building automation system manufacturer, having the same dialup capability, shall also attempt to solve the problem online. If the problem cannot be resolved with online support, the BAS representative shall dispatch the appropriate personnel to the job site to resolve the problem within 4 hours of the time that the problem is reported.
 - c. This coverage shall include normal business hours, after business hours, weekends and holidays.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.6 SUBMITTALS

- A. Pre-submittal meeting: The Contractor performing work under this Section of the specifications shall attend a meeting for coordinating the control system with major pieces of equipment including Rooftop Units. The meeting shall be held on the project site in the contractor's trailer or other location acceptable to the Contractor. The Contractor shall be responsible for arranging the meeting. Submittals shall be essentially complete at the time of the meeting so detailed coordination items can be discussed.
- B. Submit ten (10) complete sets of documentation in the following phased delivery schedule:
 - 1. Schedule of dampers including size, leakage, and flow characteristics.
 - 2. Schedule of valves including leakage and flow characteristics.
 - 3. Product Data: Include manufacturer's technical literature for each control device. Indicate dimensions, capacities, performance characteristics, electrical characteristics, finishes for materials, and installation and startup instructions for each type of product indicated. Include each control device labeled with setting or adjustable range of control.
 - a. DDC System Hardware: Bill of materials of equipment indicating quantity, manufacturer, and model number. Include technical data for interface equipment, control units, transducers/transmitters, sensors, actuators, valves, relays/switches, control panels, and operator interface equipment.
 - b. Control System Software: Include technical data for operating system software, operator interface, color graphics, and other third-party applications.
 - c. Controlled Systems: Instrumentation list with element name, type of device, manufacturer, model number, and product data. Include written description of sequence of operation including schematic diagram.
 - 4. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection. Include the following:
 - a. System schematics, including:
 - 1) Written sequences of operation
 - 2) Listing of connected data points, including connected control unit and input device.
 - a) Point names
 - b) Point addresses
 - 3) Power, signal, and control wiring. Differentiate between manufacturer-installed and field-installed wiring.
 - 4) Details of control panel faces, including controls, instruments, and labeling.
 - 5) Schematic flow diagrams showing fans, pumps, coils, dampers, valves, and control devices.
 - 6) Trunk cable schematic showing programmable control unit locations and trunk data conductors.
 - 7) System graphics indicating monitored systems, data (connected and calculated) point addresses, and operator notations.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 8) System configuration showing peripheral devices, batteries, power supplies, diagrams, modems, and interconnections.
- C. Maintenance Data: For systems to include in maintenance manuals specified in Division 1. Include the following:
 - 1. Maintenance instructions and lists of spare parts for each type of control device.
 - 2. Interconnection wiring diagrams with identified and numbered system components and devices.
 - 3. Keyboard illustrations and step-by-step procedures indexed for each operator function.
 - 4. Inspection period, cleaning methods, cleaning materials recommended, and calibration tolerances.
 - 5. Calibration records and list of set points.
- D. Project Record Documents: Record actual locations of control components, including control units, thermostats, and sensors. Revise Shop Drawings to reflect actual installation and operating sequences.
- E. Upon project completion, submit operation and maintenance manuals, consisting of the following:
 - 1. Index sheet listing contents in alphabetical order.
 - 2. Manufacturer's equipment parts list of all functional components of the system.
 - 3. DVD of system schematics including wiring diagrams.
 - 4. Sequences of operations
 - 5. As-built interconnection wiring diagrams.
 - 6. Operator's manual.
 - 7. Trunk cable schematic showing remote electronic panel locations and all trunk data.
 - 8. List of connected data points, including panels to which they are connected and input device (sensors, thermostat, etc.)
 - 9. Software and firmware operational documentation. Include the following:
 - a. Software operating and upgrade manuals.
 - b. Program software backup: On a magnetic media or compact disc, complete with data files.
 - c. Device address list.
 - d. Printout of software application and graphic screens.
 - e. Software license required by control systems.
 - 10. Software Upgrade Kit: For Owner to use in modifying software to suit future power system revisions or monitoring and control revisions.
 - 11. Field Test Reports: Indicate and interpret test results for compliance with performance requirements.
- F. Submit product data sheets for airflow measuring devices indicating minimum placement requirements, sensor density, sensor distribution, and installed accuracy to the host control system. Submit a schedule of airflow measuring devices indicating compliance with specified accuracy at minimum and maximum airflow rates. Submit installation, operation and maintenance documentation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.7 QUALITY ASSURANCE

- A. The BAS system shall be designed and installed, commissioned, and serviced by a manufacturer's authorized installer.
- B. Manufacturer Qualifications: A firm experienced in manufacturing automatic temperature-control systems similar to those indicated for this Project and with a record of successful inservice performance.
- C. All materials and equipment used shall be standard components, regularly manufactured for this and/or other systems and not custom designed especially for this project.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- E. Electronic equipment shall conform to the requirements of FCC Regulation, Part 15, Section 15, governing radio frequency electromagnetic interference and shall be so labeled.
- F. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilation Systems."
- G. Comply with ASHRAE 135 for DDC system components.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Factory-Mounted Components: Where control devices specified in this Section are indicated to be factory-mounted on equipment, arrange for shipping of control devices to equipment manufacturer.
- B. System Software: Update to latest version of software at Project completion.

1.9 COORDINATION

- A. Control Wiring: The BAS manufacturer shall be responsible for all BAS and temperature control wiring for a complete and operable system. All wire and cable shall be plenum-rated and shall be in accordance with Division 26 specification sections and all local, state and national codes and ordinances.
- B. Where plenum-rated BAS cable is routed in concealed, accessible spaces, the cable may be run in the cable trays or in J-Hooks provided under this section of the specifications. Where plenum-rated BAS cable is routed in exposed or inaccessible areas, it shall be run conduit provided under this section of the specifications.

C. Power Wiring:

- 1. Power wiring indicated (device and circuit designation indicated) on the drawings shall be provided under Division 26.
- 2. The BAS manufacturer shall be responsible for power wiring not indicated (device or circuit designation not indicated) on the Drawings. It shall be the BAS manufacturer's

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- responsibility to review the Contract Documents to determine the extent of power wiring included in Division 26 and to provide additional power wiring as required. Work shall be in accordance with Division 26 specifications and all local, state and national codes and ordinances.
- 3. Where the contractor performing work under this section requires an additional circuit for power wiring to a device or panel under paragraph 2 above, an RFI shall be issued requesting approval to use an available circuit in the nearest panel. Once approval is granted, all wiring and conduit from the breaker to the device or panel shall be provided under this section of the specifications.
- D. Coordinate location of thermostats, humidistats, and other exposed control sensors with plans and room details before installation. All conduits shall be concealed within walls and above ceilings unless indicated otherwise.
- E. Coordinate installation of conduit to avoid cutting of finished surfaces.
- F. Coordinate equipment with Division 26 Section "Lighting Control Devices" to achieve compatibility with equipment that interfaces with that system.
- G. Coordinate equipment with Division 28 Section "Digital Addressable Fire Alarm" to achieve compatibility with equipment that interfaces with that system.
- H. Coordinate supply of conditioned electrical branch circuits for control units and operator workstation.

1.10 PROJECT CONDITIONS

A. Maintain environmental conditions (temperature, humidity and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

PART 2 - PRODUCTS

2.1 MANUFACTURER

- 1. Alerton
- 2. Automated Logic
- 3. Honeywell
- 4. Johnson Controls Inc.
- 5. Trane
- 6. Schneider Electric
- 7. Siemens
- 8. Delta Controls

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.2 DDC EQUIPMENT

- A. Existing Operator Workstations: All BAS interface software should be installed on the existing head end computers as applicable, coordinate desired computers with owner. Provide at least two hard copies on CD or DVD of all software required for interface. Provide 2 copies of software tools required to modify programming and sequences of operation.
 - 1. Application Software:
 - a. I/O capability from operator station.
 - b. System security for each operator via software password and access levels.
 - c. Automatic system diagnostics; monitor system and report failures.
 - d. Database creation and support.
 - e. Automatic and manual database save and restore.
 - f. Dynamic color graphic displays with up to 10 screen displays at once.
 - g. Custom graphics generation and graphics library of HVAC equipment and symbols.
 - h. Alarm processing, messages, and reactions.
 - i. Trend logs retrievable in spreadsheets and database programs.
 - j. Alarm and event processing.
 - k. Object and property status and control.
 - 1. Automatic restart of field equipment on restoration of power.
 - m. Data collection, reports, and logs. Include standard reports for the following:
 - 1) Current values of all objects.
 - 2) Current alarm summary.
 - 3) Disabled objects.
 - 4) Alarm lockout objects.
 - 5) Logs.
 - n. Custom report development.
 - o. Workstation application editors for controllers and schedules.
 - p. Maintenance management.
- B. I/O Interface: Hardwired inputs and outputs may tie into system through controllers. Protect points so that shorting will cause no damage to controllers.
 - 1. Binary Inputs: Allow monitoring of on-off signals without external power.
 - 2. Pulse Accumulation Inputs: Accept up to 10 pulses per second.
 - 3. Analog Inputs: Allow monitoring of low-voltage (0- to 10-V dc), current (4 to 20 mA), or resistance signals.
 - 4. Binary Outputs: Provide on-off or pulsed low-voltage signal, selectable for normally open or normally closed operation with three-position (on-off-auto) override switches and status lights.
 - 5. Analog Outputs: Provide either modulating signal, low voltage (0- to 10-V dc) or current (4 to 20 mA) with status lights, two-position (auto-manual) switch, and manually adjustable potentiometer.
 - 6. Tri-State Outputs: Provide two coordinated binary outputs for control of three-point, floating-type electronic actuators.
 - 7. Universal I/Os: Provide software selectable binary or analog outputs.
- C. Power Supplies: Transformers with Class 2 current-limiting type or overcurrent protection; limit connected loads to 80 percent of rated capacity. DC power supply shall match output current and voltage requirements and be full-wave rectifier type with the following:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Output ripple of 5.0 mV maximum peak to peak.
- 2. Combined 1 percent line and load regulation with 100-mic.sec. response time for 50 percent load changes.
- 3. Built-in overvoltage and overcurrent protection and be able to withstand 150 percent overload for at least 3 seconds without failure.

2.3 DDC CONTROLLERS

- A. No controller shall be loaded to more than 80%. IE: A controller with 20 available points shall be loaded with 16 points or less.
- B. DDC controllers shall be stand-alone, multi-tasking, multi-user, real-time digital control processors consisting of modular hardware with plug-in enclosed processors, communication controllers, power supplies and input/output point modules. Controller size shall be sufficient to fully meet the requirements of the contract documents. Each controller shall support a minimum of two (2) LAN Device Networks.
- C. Each DDC controller shall have sufficient memory to support its own operating system and databases, including:
 - 1. Control processes
 - 2. Energy management applications
 - 3. Alarm management applications including custom alarm messages for each level alarm for each point in the system.
 - 4. Historical/trend data for points specified.
 - 5. Maintenance support applications.
 - 6. Custom processes.
 - 7. Operator I/O.
 - 8. Dial-up communications.
 - 9. Manual override monitoring.
- D. Each DDC controller shall support any combination of industry standard inputs and outputs.
- E. Provide all processors, power supplies and communication controllers so that the implementation of a point only requires the addition of the appropriate point input/output termination module and wiring.
- F. DDC controllers shall provide a minimum two RS-232C serial data communication ports for operation of operator I/O devices such as industry standard printers, operator terminals, modems and portable laptop operator's terminals. DDC controllers shall allow temporary use of portable devices without interrupting the normal operation of permanently connected modems, Ethernet connections, printers, or terminals.
- G. Each DDC controller shall continuously perform self-diagnostics, communication diagnosis and diagnosis of all panel components. The DDC controller shall provide both local and remote annunciation of any detected component failures, low battery conditions or repeated failure to establish communication.
- H. Isolation shall be provided at all peer-to-peer network terminations, as well as all field point terminations to suppress induced voltage transients consistent with IEEE Standards 587-1980.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- I. In the event of the loss of normal power, there shall be an orderly shutdown of all DDC controllers to prevent the loss of database or operating system software. Non-volatile memory shall be incorporated for all critical controller configuration data and battery backup shall be provided to support the real-time clock and all volatile memory for a minimum of 100 days.
 - 1. Upon restoration of normal power, the DDC controller shall automatically resume full operation without manual intervention.
 - 2. Should DDC controller memory be lost for any reason, the system shall automatically reload the DDC controller via the local RS-232C port, via telephone line dial-in or Ethernet from the existing network workstation PC.
- J. Provide a separate DDC controller for each RTU or other HVAC system. It is intended that each unique system be provided with its own point resident DDC controller.

2.4 DDC CONTROLLER RESIDENT SOFTWARE FEATURES

A. General:

- 1. The software programs specified in this Section shall be provided as an integral part of DDC Controllers and shall not be dependent upon any higher-level computer for execution.
- B. Control Software Description:
 - 1. The DDC Controllers shall have the ability to perform the following pre-tested control algorithms:
 - a. Two-position control
 - b. Proportional control
 - c. Proportional plus integral control
 - d. Proportional, integral, plus derivative control
 - e. Automatic tuning of control loops
- C. DDC Controllers shall have the ability to perform any or all the following energy management routines:
 - 1. Time-of-day scheduling
 - 2. Calendar-based scheduling
 - 3. Holiday scheduling
 - 4. Temporary schedule overrides
 - 5. Start-Stop Time Optimization
 - 6. Automatic Daylight Savings Time Switchover
 - 7. Night setback control
 - 8. Enthalpy switchover (economizer)
 - 9. Peak demand limiting
 - 10. Temperature-compensated duty cycling
 - 11. Trending
- D. DDC Controllers shall be able to execute custom, job-specific processes defined by the user, to automatically perform calculations and special control routines.
- E. Alarm management shall be provided to monitor and direct alarm information to operator devices. Each DDC Controller shall perform distributed, independent alarm analysis and filtering to minimize operator interruptions due to non-critical alarms, minimize network traffic

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

and prevent alarms from being lost. At no time shall the DDC Controllers ability to report alarms be affected by either operator or activity at a PC workstation, local I/O device or communications with other panels on the network.

F. A variety of historical data collection utilities shall be provided to manually or automatically sample, store and display system data for points as specified.

2.5 APPLICATION SPECIFIC CONTROLLERS (ASC)

- A. Each DDC Controller shall be able to extend its performance and capacity using remote application specific controllers (ASCs) through LAN Device Networks.
- B. Each ASC shall operate as a stand-alone controller capable of performing its specified control responsibilities independently of other controllers in the network. Each ASC shall be a microprocessor-based, multi-tasking, real-time digital control processor.
- C. Each ASC shall be capable of control of the terminal device independent of the manufacturer of the terminal device.
- D. Terminal Equipment Controllers:
 - 1. Provide for control of each piece of equipment, including, but not limited to, the following:
 - a. Exhaust fans

2.6 ELECTRONIC SENSORS

- A. Description: Vibration and corrosion resistant; for wall, immersion, or duct mounting as required.
- B. Thermistor Temperature Sensors and Transmitters and Resistance Temperature Detectors and Transmitters:
 - 1. Accuracy: Plus or minus 0.5 deg F at calibration point.
 - 2. Wire: Twisted, shielded-pair cable.
 - 3. Insertion Elements in Ducts: Single point, 8 inches long; use where not affected by temperature stratification or where ducts are smaller than 9 sq. ft.
 - 4. Averaging Elements in Ducts: 36 inches long, flexible; use where prone to temperature stratification or where ducts are larger than 10 sq. ft.
 - 5. Insertion Elements for Liquids: Brass or stainless-steel socket with minimum insertion length of 2-1/2 inches.
 - 6. Room Sensor Cover Construction: Manufacturer's standard locking covers.
 - a. Set-Point Adjustment (classrooms, offices, work rooms and conference rooms): Exposed warmer/cooler slider. Range of adjustment capable at zone sensor shall be programmable through the BAS.
 - b. Set-Point Adjustment (other spaces): Concealed.
 - c. Set-Point Indication: Concealed.
 - d. Thermometer: Concealed.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- e. Color: Manufacturer's standard.
- f. Orientation: Vertical.
- g. Option: No manufacturer logo.
- 7. Outside-Air Sensors: Watertight inlet fitting, shielded from direct sunlight.
- 8. Space Sensor Guards: Provide heavy-duty, cast aluminum guards for sensors located in the gymnasium, auxiliary gymnasium, auditorium and commons.
- 9. Public Corridors: In public corridors and entrances, provide blank stainless-steel cover plate sensors with insulated back and security screws.
- C. Humidity Sensors: Capacitance or bulk polymer resistance type.
 - 1. Accuracy: 5 percent full range with linear output.
 - 2. Room Sensor Range: 20 to 80 percent relative humidity.
 - 3. Room Sensor Cover Construction: Manufacturer's standard locking covers.
 - a. Color: Manufacturer's standard.
 - b. Orientation: Vertical.
 - c. Set-Point Adjustment: Concealed.
 - d. Set-Point Indication: Concealed.
 - 4. Outside-Air Sensor: 20 to 80 percent relative humidity range with mounting enclosure, suitable for operation at outdoor temperatures of 0 to 185 deg F.
 - 5. Duct-Mounted: Electric insertion, 2-position type with adjustable, 2 percent throttling range, 20 to 80 percent operating range, and single- or double-pole contacts.

D. Pressure Transmitters/Transducers:

- 1. Static-Pressure Transmitter: Non-directional sensor with suitable range for expected input and temperature-compensated.
 - a. Accuracy: 2 percent of full scale with repeatability of 0.5 percent.
 - b. Output: 4 to 20 mA.
 - c. Building Static-Pressure Range: 0- to 0.25-inch wg.
 - d. Duct Static-Pressure Range: 0- to 5-inch wg.
- 2. Water Pressure Transducers: Stainless-steel diaphragm construction, suitable for service; minimum 150-psig operating pressure; linear output 4 to 20 mA.
- 3. Water Differential-Pressure Transducers: Stainless-steel diaphragm construction, suitable for service; minimum 150-psig operating pressure and tested to 300-psig; linear output 4 to 20 mA.
- 4. Differential-Pressure Switch (Air or Water): Snap acting, with pilot-duty rating and with suitable scale range and differential. Accuracy shall be +/- 5% of range.
- 5. Pressure Transmitters: Direct acting for gas, liquid, or steam service; range suitable for system; linear output 4 to 20 mA.

E. Current Sensing Switch:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1. Sensor supply voltage and supply current shall be induced from monitored conductor. Contact rating shall be 0.2 amperes at 30 volts DC/AC. Trip set point shall be adjustable to +/-1% of range. Current sensing switch wiring shall not be polarity sensitive.

F. Liquid Level Sensors:

1. Liquid level sensors shall have ½" accuracy calibrated to detect water in temperature range from 60°F to 80°F. Output signal shall be 4 to 20 mA. Sensor material shall be stainless steel or other non-corrosive material.

2.7 STATUS SENSORS

- A. Status Inputs for Fans: Differential-pressure switch with pilot-duty rating and with adjustable range of 0- to 5-inch wg.
- B. Status Inputs for Pumps: Differential-pressure switch with pilot-duty rating and with adjustable pressure-differential range of 8 to 60 psig, piped across pump.
- C. Status Inputs for Electric Motors: Comply with ISA 50.00.01, current-sensing fixed- or split-core transformers with self-powered transmitter, adjustable and suitable for 175 percent of rated motor current.
- D. Voltage Transmitter (100- to 600-V ac): Comply with ISA 50.00.01, single-loop, self-powered transmitter, adjustable, with suitable range and 1 percent full-scale accuracy.
- E. Current Switches: Self-powered, solid-state with adjustable trip current, selected to match current and system output requirements.
- F. Electronic Valve/Damper Position Indicator: Visual scale indicating percent of travel and 2- to 10-V dc, feedback signal.
- G. Water-Flow Switches: Bellows-actuated mercury or snap-acting type with pilot-duty rating, stainless-steel or bronze paddle, with appropriate range and differential adjustment, in NEMA 250, Type 1 enclosure.

2.8 THERMOSTATS

A. Available Manufacturers:

- 1. Danfoss Inc.; Air-Conditioning and Refrigeration Div.
- 2. Heat-Timer Corporation.
- 3. tekmar Control Systems, Inc.
- B. Combination Thermostat and Fan Switches: Line-voltage thermostat with push-button or lever-operated fan switch.
 - 1. Label switches "FAN ON-OFF" or "FAN HIGH-LOW-OFF" or "FAN HIGH-MED-LOW-OFF."
 - 2. Mount on single electric switch box.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- C. Electric, solid-state, microcomputer-based room thermostat with remote sensor.
 - 1. Automatic switching from heating to cooling.
 - 2. Preferential rate control to minimize overshoot and deviation from set point.
 - 3. Set up for four separate temperatures per day.
 - 4. Instant override of set point for continuous or timed period from 1 hour to 31 days.
 - 5. Short-cycle protection.
 - 6. Programming based on every day of week.
 - 7. Selection features include degree F or degree C display, 12- or 24-hour clock, keyboard disable, remote sensor, and fan on-auto.
 - 8. Battery replacement without program loss.
 - 9. Thermostat display features include the following:
 - a. Time of day.
 - b. Actual room temperature.
 - c. Programmed temperature.
 - d. Programmed time.
 - e. Duration of timed override.
 - f. Day of week.
 - g. System mode indications include "heating," "off," "fan auto," and "fan on."
- D. Low-Voltage, On-Off Thermostats: NEMA DC 3, 24-V, bimetal-operated, mercury-switch type, with adjustable or fixed anticipation heater, concealed set-point adjustment, 55 to 85 deg F set-point range, and 2 deg F maximum differential.
- E. Line-Voltage, On-Off Thermostats: Bimetal-actuated, open contact or bellows-actuated, enclosed, snap-switch or equivalent solid-state type, with heat anticipator; listed for electrical rating; with concealed set-point adjustment, 55 to 85 deg F set-point range, and 2 deg F maximum differential.
 - 1. Electric Heating Thermostats: Equip with off position on dial wired to break ungrounded conductors.
 - 2. Selector Switch: Integral, manual on-off-auto.
- F. Remote-Bulb Thermostats: On-off or modulating type, liquid filled to compensate for changes in ambient temperature; with copper capillary and bulb, unless otherwise indicated.
 - 1. Bulbs in water lines with separate wells of same material as bulb.
 - 2. Bulbs in air ducts with flanges and shields.
 - 3. Averaging Elements: Copper tubing with either single- or multiple-unit elements, extended to cover full width of duct or unit; adequately supported.
 - 4. Scale settings and differential settings are clearly visible and adjustable from front of instrument.
 - 5. On-Off Thermostat: With precision snap switches and with electrical ratings required by application.
 - 6. Modulating Thermostats: Construct so complete potentiometer coil and wiper assembly is removable for inspection or replacement without disturbing calibration of instrument.
- G. Immersion Thermostat: Remote-bulb or bimetal rod-and-tube type, proportioning action with adjustable throttling range and adjustable set point.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- H. Airstream Thermostats: Two-pipe, fully proportional, single-temperature type; with adjustable set point in middle of range, adjustable throttling range, plug-in test fitting or permanent pressure gage, remote bulb, bimetal rod and tube, or averaging element.
- I. Electric, Low-Limit Duct Thermostat: Snap-acting, single-pole, single-throw, manual- or automatic- reset switch that trips if temperature sensed across any 12 inches of bulb length is equal to or below set point.
 - 1. Bulb Length: Minimum 20 feet.
 - 2. Quantity: One thermostat for every 20 sq. ft. of coil surface.
- J. Electric, High-Limit Duct Thermostat: Snap-acting, single-pole, single-throw, manual- or automatic- reset switch that trips if temperature sensed across any 12 inches of bulb length is equal to or above set point.
 - 1. Bulb Length: Minimum 20 feet.
 - 2. Quantity: One thermostat for every 20 sq. ft. of coil surface.
- K. Heating/Cooling Valve-Top Thermostats: Proportional acting for proportional flow, with molded-rubber diaphragm, remote-bulb liquid-filled element, direct and reverse acting at minimum shutoff pressure of 25 psig, and cast housing with position indicator and adjusting knob.

2.9 ACTUATORS

- A. Electric Motors: Size to operate with sufficient reserve power to provide smooth modulating action or two-position action.
 - 1. Comply with requirements in Division 23 Section "Common Motor Requirements for HVAC Equipment."
 - 2. Permanent Split-Capacitor or Shaded-Pole Type: Gear trains completely oil immersed and sealed. Equip spring-return motors with integral spiral-spring mechanism in housings designed for easy removal for service or adjustment of limit switches, auxiliary switches, or feedback potentiometer.
 - 3. Non-spring-Return Motors for Valves Larger than NPS 2-1/2: Size for running torque of 150 in. x lbf and breakaway torque of 300 in. x lbf.
 - 4. Spring-Return Motors for Valves Larger than NPS 2-1/2: Size for running and breakaway torque of 150 in. x lbf.
 - 5. Non-spring-Return Motors for Dampers Larger than 25 Sq. Ft.: Size for running torque of 150 in. x lbf and breakaway torque of 300 in. x lbf.
 - 6. Spring-Return Motors for Dampers Larger than 25 Sq. Ft.: Size for running and breakaway torque of 150 in. x lbf.
- B. Electronic Actuators: Direct-coupled type designed for minimum 60,000 full-stroke cycles at rated torque.
 - 1. Valves: Size for torque required for valve close off at maximum pump differential pressure.
 - 2. Dampers: Size for running torque calculated as follows:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Parallel-Blade Damper with Edge Seals: 7 inch-lb/sq. ft. of damper.
- b. Opposed-Blade Damper with Edge Seals: 5 inch-lb/sq. ft. of damper.
- c. Parallel-Blade Damper without Edge Seals: 4 inch-lb/sq. ft of damper.
- d. Opposed-Blade Damper without Edge Seals: 3 inch-lb/sq. ft. of damper.
- e. Dampers with 2- to 3-Inch wg of Pressure Drop or Face Velocities of 1000 to 2500 fpm: Increase running torque by 1.5.
- f. Dampers with 3- to 4-Inch wg of Pressure Drop or Face Velocities of 2500 to 3000 fpm: Increase running torque by 2.0.
- 3. Coupling: V-bolt and V-shaped, toothed cradle.
- 4. Overload Protection: Electronic overload or digital rotation-sensing circuitry.
- 5. Fail-Safe Operation: Mechanical, spring-return mechanism. Provide external, manual gear release on non-spring-return actuators.
- 6. Power Requirements (Modulating): Maximum 10 VA at 24-V ac or 8 W at 24-V dc.
- 7. Proportional Signal: 2- to 10-V dc or 4 to 20 mA, and 2- to 10-V dc position feedback signal.
- 8. Temperature Rating: Minus 22 to plus 122 deg F.
- 9. Temperature Rating (Smoke Dampers): Minus 22 to plus 250 deg F.

2.10 DAMPERS

- A. Dampers: AMCA-rated, parallel or opposed-blade design; 0.108-inch- minimum thick, galvanized-steel or 0.125-inch- minimum thick, extruded-aluminum frames with holes for duct mounting; damper blades shall not be less than 0.064-inch- thick galvanized steel with maximum blade width of 8 inches and length of 48 inches.
 - 1. Secure blades to 1/2-inch- diameter, zinc-plated axles using zinc-plated hardware, with oil-impregnated sintered bronze blade bearings, blade-linkage hardware of zinc-plated steel and brass, ends sealed against spring-stainless-steel blade bearings, and thrust bearings at each end of every blade.
 - 2. Operating Temperature Range: From minus 40 to plus 200 deg F.
 - 3. Edge Seals, Standard Pressure Applications: Closed-cell neoprene.
 - 4. Edge Seals, Low-Leakage Applications: Use inflatable blade edging or replaceable rubber blade seals and spring-loaded stainless-steel side seals, rated for leakage at less than 10 cfm per sq. ft. of damper area, at differential pressure of 4-inch wg when damper is held by torque of 50 in. x lbf; when tested according to AMCA 500D.
- 2.11 CURRENT SENSING RELAYS: By controls contractor for all equipment.
- 2.12 miscellaneous relays and switches:
 - A. General: Where required by the sequence of operation switches, relays, and miscellaneous devices necessary to accomplish the sequence shall be provided under this Section.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 3 - EXECUTION

3.1 PROJECT MANAGEMENT

- A. Provide a designated project manager who will be responsible for the following:
 - 1. Construct and maintain project schedule
 - 2. On-site coordination with all applicable trades and subcontractors
 - 3. Authorized to accept and execute orders or instructions from owner/architect
 - 4. Attend project meetings as necessary to avoid conflicts and delays
 - 5. Make necessary field decisions relating to this scope of work
 - 6. Coordination/Single point of contact.

3.2 EXAMINATION

- A. Verify that power supply is available to control units and operator workstation.
- B. Verify that duct-, pipe-, and equipment-mounted devices are installed before proceeding with installation.

3.3 INSTALLATION

- A. Install software in control units and operator workstation(s). Implement all features of programs to specified requirements and as appropriate to sequence of operation.
- B. Connect and configure equipment and software to achieve sequence of operation specified in Section 23 section "Sequence of Control."
- C. Verify location of thermostats, humidistats, and other exposed control sensors with Drawings and room details before installation. Install devices next to light switch(es) when space is available with top of device at 48 inches above finished floor. Where space next to light switch(es) is not available, align device vertically with light switch and locate device with top at 40 inches above the finished floor.
 - 1. Install averaging elements in ducts and plenums in crossing or zigzag pattern.
- D. Install guards on thermostats where indicated on Drawings.
- E. Install automatic dampers according to Division 23 Section "Air Duct Accessories."
- F. Install damper motors on outside of duct in warm areas, not in locations exposed to outdoor temperatures.
- G. Install labels and nameplates to identify control components according to Division 23 Section "Identification for HVAC Piping and Equipment."
- H. Install hydronic instrument wells, valves, and other accessories according to Division 23 Section "Hydronic Piping."

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

I. Install duct volume-control dampers according to Division 23 Sections specifying air ducts.

3.4 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connections, and to assist in field testing. Report results in writing.
- B. Perform the following field tests and inspections and prepare test reports:
 - 1. Operational Test: After electrical circuitry has been energized, start units to confirm proper unit operation. Remove and replace malfunctioning units and retest.
 - 2. Test and adjust controls and safeties.
 - 3. Test calibration of electronic controllers by disconnecting input sensors and stimulating operation with compatible signal generator.
 - 4. Test each point through its full operating range to verify that safety and operating control set points are as required.
 - 5. Test each control loop to verify stable mode of operation and compliance with sequence of operation. Adjust PID actions.
 - 6. Test each system for compliance with sequence of operation.
 - 7. Test software and hardware interlocks.

C. DDC Verification:

- 1. Verify that instruments are installed before calibration, testing, and loop or leak checks.
- 2. Check instruments for proper location and accessibility.
- 3. Check instrument installation for direction of flow, elevation, orientation, insertion depth, and other applicable considerations.
- 4. Check instrument tubing for proper fittings, slope, material, and support.
- 5. Check flow instruments. Inspect tag number and line and bore size, and verify that inlet side is identified and that meters are installed correctly.
- 6. Check pressure instruments, piping slope, installation of valve manifold, and self-contained pressure regulators.
- 7. Check temperature instruments and material and length of sensing elements.
- 8. Check control valves. Verify that they are in correct direction.
- 9. Check DDC system as follows:
 - a. Verify that DDC controller power supply is from emergency power supply.
 - b. Verify that wires at control panels are tagged with their service designation and approved tagging system.
 - c. Verify that spare I/O capacity has been provided.
 - d. Verify that DDC controllers are protected from power supply surges.
- D. Replace damaged or malfunctioning controls and equipment and repeat testing procedures.

3.5 ADJUSTING

A. Calibrating and Adjusting:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Calibrate instruments.
- 2. Make three-point calibration test for both linearity and accuracy for each analog instrument.
- 3. Calibrate equipment and procedures using manufacturer's written recommendations and instruction manuals. Use test equipment with accuracy at least double that of instrument being calibrated.
- 4. Control System Inputs and Outputs:
 - a. Check analog inputs at 0, 50, and 100 percent of span.
 - b. Check analog outputs using milliampere meter at 0, 50, and 100 percent output.
 - c. Check digital inputs using jumper wire.
 - d. Check digital outputs using ohmmeter to test for contact making or breaking.
 - e. Check resistance temperature inputs at 0, 50, and 100 percent of span using a precision-resistant source.

5. Flow:

- a. Set differential pressure flow transmitters for 0 and 100 percent values with 3-point calibration accomplished at 50, 90, and 100 percent of span.
- b. Manually operate flow switches to verify that they make or break contact.

6. Pressure:

- a. Calibrate pressure transmitters at 0, 50, and 100 percent of span.
- b. Calibrate pressure switches to make or break contacts, with adjustable differential set at minimum.

7. Temperature:

- a. Calibrate resistance temperature transmitters at 0, 50, and 100 percent of span using a precision-resistance source.
- b. Calibrate temperature switches to make or break contacts.
- 8. Stroke and adjust control valves and dampers without positioners, following the manufacturer's recommended procedure, so that valve or damper is 100 percent open and closed.
- 9. Stroke and adjust control valves and dampers with positioners, following manufacturer's recommended procedure, so that valve and damper is 0, 50, and 100 percent closed.
- 10. Provide diagnostic and test instruments for calibration and adjustment of system.
- 11. Provide written description of procedures and equipment for calibrating each type of instrument. Submit procedures review and approval before initiating startup procedures.
- B. Adjust initial temperature and humidity set points.
- C. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to three visits to Project during other than normal occupancy hours for this purpose.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.6 TRAINING

- A. Provide 8 hours of training for Owner's designated operating personnel. Training shall include:
 - 1. Explanation of drawings and operation & maintenance manuals
 - 2. Walk-through of the job to locate control components
 - 3. Operator workstation and peripherals
 - 4. Operation of Portable computer
 - 5. DDC controller and ASC operation/function
 - 6. Operator control functions including graphic generation and field panel programming
 - 7. Explanation of adjustment, calibration and replacement procedures
- B. Since the Owner may require personnel to have more comprehensive understanding of the hardware and software, additional training must be available from the Manufacturer. If necessary additional training will be contracted by the Owner at a later date.
- C. Coordinate with Owner is videotape documentation of training is required.

END OF SECTION 230900

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 230993 - SEQUENCE OF OPERATIONS FOR HVAC CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUMMARY

- A. This Section includes control sequences for HVAC systems, subsystems, and equipment.
- B. Related Sections include the following:
 - 1. Division 23 Section "Building Automation System" for control equipment and devices and for submittal requirements.

1.3 DEFINITIONS

- A. BAS: Building automation system.
- B. CO₂: Carbon dioxide.
- C. CO: Carbon monoxide
- D. DDC: Direct digital control.
- E. PPM: Parts per million.
- F. RPM: Revolutions per minute.
- G. SCR: Silicon-Controlled Rectifier.
- H. TAB: Testing, Adjusting and Balancing.
- I. VAV: Variable air volume.
- J. VFD: Variable-frequency drive

1.4 GENERAL REQUIREMENTS OF THIS SECTION

A. Control sequences shall be accomplished in accordance with control drawings and the sequences specified in this section. It is the intent of this section to utilize sequences included in pre-programmed controllers when such sequences provide the intended operation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Points may not be deleted without prior approval from the Architect.
- C. Every attempt has been made to indicate all required points on the control drawings.

 Occasionally an additional point, or points, may be required to accomplish a specified sequence.

 The contractor performing work under this section shall understand the work to be implied and required by the contract documents. Additional hardware and software required shall be provided under section "Building Automation System" at no additional cost to the Owner.
 - 1. Such points include:
 - a. Sensors of all types whether or not specified under section "Building Automation System"
 - b. Air flow measuring stations.
 - c. Wiring, conduit, and related devices such as relays.
 - 2. Exceptions
 - a. Equipment and devices covered under sections other than "Building Automation System".

1.5 DISPLAY GRAPHICS:

- A. Include system schematic for each system. Indicate all points in system on at least one graphic.
- B. Indicate all commanded values and temperatures.
- C. Indicate all sensed temperatures.
- D. Indicate all alarms.
- E. Indicate all status points.
- F. Indicate all monitored conditions.

1.6 WARRANTY

A. Provide all services, materials and equipment necessary for the successful operation of the entire BAS system for a period of one year beginning on the date of substantial completion.

1.7 SUBMITTALS

A. Refer to Section "Building Automation System."

PART 2 - SEQUENCES

- 2.1 SET POINTS: Unless indicated otherwise all set points shall be adjustable from the head end.
- 2.2 OCCUPIED / UNOCCUPIED

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- A. The BAS shall institute occupied and unoccupied control sequences based on a time-of-day schedule furnished by the Owner.
- B. The Owner shall have the capability to program holidays and special functions.
- C. The owner shall have the ability to override occupied / unoccupied maintenance / and unoccupied operation of each piece of equipment from the head end.

2.3 OPTIMUM START:

A. The BAS shall institute optimum start strategies for morning warm up and cool down functions. Equipment shall start early enough to restore occupied temperature set points 30 minutes prior to occupancy.

2.4 OUTSIDE AIR SENSORS:

- A. Temperature: The BAS shall monitor outside air temperature as sensed by the outside air temperature sensor.
- B. Humidity: The BAS shall monitor outside air relative humidity as sensed by the outside air humidity sensor.

2.5 PACKAGED HEAT PUMP (WITH ECONOMIZER, 5 tons and above)

A. General: This air handling unit includes a constant speed supply and exhaust fan, modulating outside air damper, modulating return air damper, modulating & staged packaged direct expansion cooling and heating coil. It provides temperature and humidity control for a single zone. Unit controls are factory installed and provided by unit manufacturer to meet the general intent as indicated below. Unit mounted controls shall interface to the BAS as described in 230900, Building Automation System.

B. Initial Set Points:

- 1. Occupied:
 - a. Cooling: 75°F
 - b. Heating: 70°F
 - c. Space relative humidity: 55%
- 2. Unoccupied:
 - a. Cooling: 85°F
 - b. Heating: 55°F
 - c. Space relative humidity: 60%

C. Enable/Disable:

1. Occupied Operation: During occupied hours, the unit shall be enabled, the supply and exhaust fan shall be started, and dampers shall modulate in accordance with applicable sequences below.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Unoccupied Operation: During unoccupied hours, the supply fan shall be cycled on and off to maintain unoccupied set points with outdoor air damper (D-1) closed and return air damper (D-2) open.
 - a. Unoccupied Heating: Should the space temperature fall below the unoccupied heating space temperature set point, the unit shall be started in the warm-up mode until the space temperature rises 5°F above the unoccupied heating space temperature set point.
 - b. Unoccupied Cooling: Should the space temperature rise above the unoccupied cooling space temperature set point, the unit shall be started in the cool-down mode until the space temperature falls 5°F below the unoccupied cooling space temperature set point.
 - c. Unoccupied Humidity Control: If the space relative humidity rises above the unoccupied space relative humidity set point, the unit shall operate in the dehumidification mode until the relative humidity drops 5% RH below the unoccupied space relative humidity set point.
- 3. Warm-up Operation: The BAS shall optimize the early start of the unit in warm-up mode to reach the occupied space heating set point by the occupied time. During warm-up operation the outside air damper (D-1) shall be closed and return air damper (D-2) open.
- 4. Cool-down Operation: The BAS shall optimize the early start of the unit in cool-down mode to reach the occupied space cooling set point by the occupied time. During cooldown operation the outside air damper (D-1) shall be closed and return air damper (D-2) open.
- 5. Startup: Start time shall be based on the BAS optimum start programming in accordance with a predetermined schedule to be furnished by the Owner and programmed into the BAS. The outside air damper shall remain closed while the unit operates in warm-up/cool-down mode to restore occupied set points. At occupancy time, the unit shall begin to modulate the outside air damper in accordance with its sequence of control.

D. Supply Fan Control:

- 1. During unoccupied hours, the fan shall be cycled as necessary to maintain set points. When fan is cycled on, control shall be similar to occupied operation.
- 2. During occupied hours, the supply fan shall deliver design airflow.
- 3. Fan Failure Alarm: Should the supply fan fail (sensed by its current sensing relay), the unit shall be disabled, and an alarm shall be sent to the head end identifying the unit and stating that the supply fan has failed.

E. Exhaust Fan Control (where specified):

- 1. During unoccupied hours, the fan shall be disabled.
- 2. During occupied hours, the exhaust fan shall deliver design airflow.
- 3. Fan Failure Alarm: Should the exhaust fan fail (sensed by its current sensing relay), the unit shall be disabled, and an alarm shall be sent to the head end identifying the unit and stating that the supply fan has failed.
- F. Cooling Control: The unit shall confirm the supply fan is running before enabling cooling. If cooling is required, the direct expansion packaged cooling shall modulate the lead circuit as the first state of cooling, where if additional capacity is needed, it should stage on the other compressors to maintain the space set point. Condenser fans shall be staged per each circuit or as recommended by equipment manufacturer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- G. Heating Control: If heating is required, the direct expansion heat pump shall stage on to maintain the space set point and control reversing valves to heating mode. Condenser fans shall be staged per each circuit or as recommended by equipment manufacturer. For units with electric heat, it shall be staged on as the second stage of heat to maintain space set point.
- H. Dehumidification Mode: During occupied or unoccupied operation when the relative humidity (as sensed by the relative humidity sensor) rises above set point, the unit shall be placed in dehumidification mode. The unit's internal controls shall utilize DX cooling to dehumidify and hot gas reheat as necessary to prevent overcooling of the space. The unit shall remain in dehumidification mode until the relative humidity drops to 5% RH below set point.
- I. Outdoor Air Damper (D-1):
 - 1. Unoccupied: Damper shall be modulated fully closed. The damper end switch shall confirm the damper is closed. If the damper fails to close, an alarm shall be sent to the head end identifying the unit and stating that the outdoor damper failed to close.
 - 2. Occupied: The damper shall modulate fully open.
 - Economizer: The damper shall modulate to open inversely with the return air damper (D-2) to maintain above scheduled outdoor air (as sensed by the outdoor air flow measuring station) to maintain leaving air temperature as the first stage of cooling.
- J. Return Air Damper (D-2):
 - 1. Unoccupied: Damper shall be fully open. The damper end switch shall confirm the damper is open. If the damper fails to open, an alarm shall be sent to the head end identifying the unit and stating that the return damper failed to open.
 - 2. Occupied: The damper shall modulate fully closed.
 - 3. Economizer: The damper shall modulate to close inversely with the outside air damper (D-1) to maintain leaving air temperature as the first stage of cooling.
- K. Economizer Mode: Whenever outside air enthalpy is less than return air enthalpy and cooling is required, economizer operation shall be enabled.
 - 1. Economizer operation shall be available twenty-four hours per day and shall override unoccupied damper controls.
- L. Space Temperature: Space temperature shall be sensed using the wall mounted temperature sensor.
- M. Dead band: A five-degree (5°F) dead band shall be maintained between heating and cooling set points at all times. This shall not be an adjustable value on the head end graphics.
- N. Life Safety: Duct smoke detectors located in the return/exhaust air duct, upon detection of products of combustion from any detector, signal the building fire alarm system and shut down the unit & supply fan. This function shall be manually reset from the unit and shall be so identified on the head-end graphics. An alarm shall also be provided to the BAS head-end.
- O. System Safety: Whenever the supply fan is stopped or airflow ceases for any reason (as sensed by the motor status sensing circuit), the supply fan shall be deactivated and alarm issued to BAS. The outdoor air damper (D-1) shall be closed and return damper (D-2) open. In all modes of operation, commanded position values for all control devices such as dampers shall be readable from the head-end.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- P. Condensate Pan Overflow Prevention: The unit shall monitor float switches in the condensate pan under the evaporator. If the float switch detects the pan is about to overflow and has reached its high limit, the unit shall disable the cooling and issue an alarm to the BAS.
- Q. Filter Change Alarm: The differential pressure across the filters shall be monitored, where if the differential pressure exceeds 1" wg (adjustable), an alarm is issued to BAS.

2.6 FAN (Control Method Occupancy Sensor)

A. General: These are general duty fans which operate based on the space occupancy sensor. Refer to the Fan Schedule for fan information.

B. Occupied/Unoccupied:

- 1. Unoccupied Operation: During unoccupied hours the fan shall be off and the damper shall be closed.
- 2. Occupied Operation: During occupancy as sensed by the occupancy sensor, the fan shall be on and the damper shall be open.

C. Start:

1. At the start of occupied operation, the motorized damper associated with the fan shall open. Once the damper is confirmed open, the fan shall start.

D. Stop:

1. At the beginning of unoccupied operation, the fan shall stop and the associated damper shall close.

E. Fan failure alarm:

1. If the fan fails to start (as sensed by its current sensing relay) an alarm shall be sent to the head end identifying the fan and stating that is has failed to start.

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 230993

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 232113 - HYDRONIC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

- A. Pre-submittal meeting: The contractor performing work under this section of the specifications shall attend a meeting for the purpose of coordinating with the control system. The meeting shall be held on the project site in the contractor's trailer or other location acceptable to the contractor. The contractor shall be responsible for arranging the meeting. Submittals shall be essentially complete at the time of the meeting so detailed coordination items can be discussed.
- B. Product Data: For each type of the following:
 - 1. Pressure-seal fittings.
 - 2. Valves-Include flow and pressure drop curves/information based on manufacturer's testing for calibrated-orifice balancing valves and automatic flow control valves.
 - 3. Air control devices.
 - 4. Chemical treatment.
 - 5. Hydronic specialties.
 - 6.
- C. Maintenance Data: For hydronic specialties, balancing valves, automatic flow control valves, and special-duty valves to include in maintenance manuals.

1.3 QUALITY ASSURANCE

A. ASME Compliance: Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation. Safety valves and pressure vessels shall bear the appropriate ASME label. Fabricate and stamp air separators and expansion tanks to comply with the ASME Boiler and Pressure Vessel Code, Section VIII, Division 1.

1.4 COORDINATION

- A. Coordinate layout and installation of hydronic piping and suspension system components with other construction, including light fixtures, HVAC equipment, fire-suppression-system components, and partition assemblies.
- B. Coordinate pipe sleeve installations for foundation wall penetrations.
- C. Coordinate piping installation with roof curbs, equipment supports, and roof penetrations. Roof specialties are specified in Division 7 Sections.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. Coordinate pipe fitting pressure classes with products specified in related Sections.
- E. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into base. Concrete, reinforcement, and formwork requirements are specified in Division 3 Sections.
- F. Coordinate installation of pipe sleeves for penetrations through exterior walls and floor assemblies. Coordinate with requirements for firestopping specified in Division 7 Section "Penetration Firestopping Systems" for fire and smoke wall and floor assemblies.

1.5 BUILDING AUTOMATION SYSTEM COORDINATION:

A. If indicated, all wells, valves, taps, dampers, flow stations, etc. furnished under Section "Building Automation System" shall be installed under this Section.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Hydronic piping, components, and installation shall withstand the following minimum working pressure and temperature unless otherwise indicated: 150 psig at 200 degrees F.

2.2 PIPING MATERIALS

A. General: Refer to Part 3 "Piping Applications" Article for applications of pipe and fitting materials.

2.3 COPPER TUBE AND FITTINGS

- A. Drawn-Temper Copper Tubing: ASTM B 88, Type L.
- B. Annealed-Temper Copper Tubing: ASTM B 88, Type K. (underground installations)
- C. DWV Copper Tubing: ASTM B 306, Type DWV.
- D. Wrought-Copper Fittings: ASME B16.22.
- E. Copper or Bronze Pressure-Seal Fittings:
 - 1. Manufacturers:
 - a. Elkhart Products Corporation.
 - b. Mueller Industries, Inc.
 - c. NIBCO, Inc.
 - d. Viega, LLC.
 - 2. Housing: Copper
 - 3. O-Rings and Pipe Stops: EPDM.
 - 4. Tools: Manufacturer's special tools.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 5. Minimum 200 psig working pressure rating at 250°F.
- F. Wrought-Copper Unions: ASME B16.22.

2.4 PLASTIC PIPE AND FITTINGS

- A. CPVC Plastic Pipe: ASTM F 441/F 441M, with wall thickness as indicated in "Piping Applications" Article.
 - 1. CPVC Plastic Pipe Fittings: Socket-type pipe fittings, ASTM F 438 for Schedule 40 pipe; ASTM F 439 for Schedule 80 pipe.
- B. PVC Plastic Pipe: ASTM D 1785, with wall thickness as indicated in "Piping Applications" Article.
 - 1. PVC Plastic Pipe Fittings: Socket-type pipe fittings, ASTM D 2466 for Schedule 40 pipe; ASTM D 2467 for Schedule 80 pipe.

2.5 JOINING MATERIALS

- A. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos free, 1/8-inch maximum thickness unless otherwise indicated.
 - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
- B. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.
- C. Plastic, Pipe-Flange Gasket, Bolts, and Nuts: Type and material recommended by piping system manufacturer unless otherwise indicated.
- D. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- E. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for joining copper with copper; or BAg-1, silver alloy for joining copper with bronze or steel.
- F. Welding Filler Metals: Comply with AWS D10.12M/D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- G. Solvent Cements for CPVC Piping: ASTM F 493.
- H. Solvent Cements for PVC Piping: ASTM D 2564. Include primer according to ASTM F 656.

2.6 TRANSITION FITTINGS

A. Plastic-to-Metal Transition Fittings:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1. One-piece fitting with one threaded brass or copper insert and one solvent-cement-joint end of material and wall thickness to match plastic pipe material.

B. Plastic-to-Metal Transition Unions:

1. Brass or copper end, solvent-cement-joint end of material and wall thickness to match plastic pipe material, rubber gasket, and threaded union.

2.7 DIELECTRIC FITTINGS

- B. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.
- C. Dielectric Unions:
 - 1. Available Manufacturers:
 - a. Capitol Manufacturing Company.
 - b. Matco-Norca.
 - c. Watts Water Technologies, Inc.
 - d. Zurn Industries, LLC.
 - 2. Description:
 - a. Standard: ASSE 1079.
 - b. Pressure Rating: 150 psig.
 - c. End Connections: Solder-joint copper alloy and threaded ferrous.
- D. Dielectric Flanges:
 - 1. Available Manufacturers:
 - a. Capitol Manufacturing Company.
 - b. Matco-Norca.
 - c. Watts Water Technologies, Inc.
 - d. Zurn Industries, LLC.
 - 2. Description:
 - a. Standard: ASSE 1079.
 - b. Factory-fabricated, bolted, companion-flange assembly.
 - c. Pressure Rating: 150 psig.
 - d. End Connections: Solder-joint copper alloy and threaded ferrous; threaded solder-joint copper alloy and threaded ferrous.
- E. Dielectric-Flange Insulating Kits:
 - 1. Available Manufacturers:
 - a. Advance Products and Systems, Inc.
 - b. Calpico, Inc.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Central Plastics Company.
- d. Pipeline Seal and Insulator, Inc.

2. Description:

- a. Nonconducting materials for field assembly of companion flanges.
- b. Pressure Rating: 150 psig.
- c. Gasket: Neoprene or phenolic.
- d. Bolt Sleeves: Phenolic or polyethylene.
- e. Washers: Phenolic with steel backing washers.

F. Dielectric Nipples:

- 1. Available Manufacturers:
 - a. Elster Perfection Corporation.
 - b. Grinnell Mechanical Products.
 - c. Matco-Norca.
 - d. Precision Plumbing Products, Inc.

2. Description:

- a. Standard: IAPMO PS 66.
- b. Electroplated steel nipple, complying with ASTM F 1545.
- c. Pressure Rating: 300 psig at 225 deg F.
- d. End Connections: Male threaded.
- e. Lining: Inert and noncorrosive, propylene.

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS

- A. Type K annealed-temper copper tubing, wrought-copper fittings, and soldered joints. Use the fewest possible joints.
- B. Condensate-Drain Piping: Type DWV, drawn-temper copper tubing, wrought-copper fittings, and soldered joints or Schedule 40 PVC or CPVC plastic pipe and fittings with solvent-welded joints.
 - 1. Exceptions where PVC, CPVC, and other forms of plastic are not permitted:
 - a. Jails.
 - b. Prisons.
 - c. Plenums.
 - d. Locations prohibited by codes or standards.
- C. Miscellaneous: Same materials and joining methods as connecting service.

3.2 PIPING INSTALLATIONS

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Install piping as indicated unless deviations to layout are approved in writing on Coordination Drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping to permit valve servicing.
- F. Install piping at indicated slopes.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Select system components with pressure rating equal to or greater than system operating pressure.
- K. Install groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.
- L. Install drains, consisting of a tee fitting, NPS 3/4 ball valve, and 8" NPS 3/4 threaded nipple with cap, at low points in piping system mains and elsewhere as required for system drainage.
- M. Install piping at a uniform grade of 0.2 percent upward in direction of flow.
- N. Install branch connections to mains using tee fittings in main pipe, with the branch connected to the bottom of the main pipe. For up-feed risers, connect the branch to the top of the main pipe.
- O. Install unions in piping, NPS 2 and smaller, adjacent to valves, at final connections of equipment, and elsewhere as indicated.
- P. Install flanges in piping, NPS 2-1/2 and larger, at final connections of equipment and elsewhere as indicated.
- Q. Install all wells, valves, taps, flow stations, etc. furnished under Section "Building Automation System."
- R. Install exterior piping at a uniform grade of 0.2 percent upward in direction of flow. Interior piping may be installed level.
- S. Install condensate drain piping at a minimum uniform slope of 1" in 10'-0"in the direction of flow.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- T. Reduce pipe sizes using concentric reducers, or eccentric reducers installed with level side up.
- U. Provide branch connections with the takeoff coming off the top of the main.
- V. Install strainers on supply side of each control valve, pressure-reducing valve, solenoid valve, in-line pump, and as indicated. Install 3/4" diameter by 8" long nipple and ball valve in blowdown connection of strainers 3/4" and larger. Match size of strainer blow-down connection for strainers smaller than 3/4".
- W. Provide seal around piping penetrations of full height interior walls, both rated and non-rated, that occur above ceilings. Refer to Section 079200 Joint Sealants.
- X. Where piping penetrates a non-fire-resistance-rated floor or floor/ceiling assembly or ceiling membrane of a non-fire-resistance-rated roof/ceiling assembly, provide the following:
 - 1. For noncombustible piping that connects not more than five stories, protect the annular space around the piping with an approved, noncombustible material to resist the free passage of flame and the products of combustion or with a tested and classified throughpenetration firestop system.
 - 2. For piping that connects not more than two stories, protect the annular space around the piping with an approved, noncombustible material to resist the free passage of flame and the products of combustion.
 - 3. For piping that penetrates a non-rated wall, protect the annular space around the penetrating piping with an approved, non-combustible materials that resists the free passage of flame and the products of combustion.

3.3 PIPE JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 23 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Soldered Joints: Apply ASTM B 813, water-flushable flux to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.
- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8.
- F. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are damaged.
 - 3. Damaged Welds: Do not use pipe sections that have cracked or open welds.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

G. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned.

3.4 HANGERS AND SUPPORTS

- A. Hanger, support, and anchor devices are specified in Division 23 Section "Hangers and Supports." Comply with requirements below for maximum spacing of supports.
- B. Install hangers for steel piping with the following maximum spacing and minimum rod sizes:
 - 1. ³/₄": Maximum span, 7'-0"; minimum rod size, ¹/₄".
 - 2. 1": Maximum span, 7'-0"; minimum rod size, ½".
 - 3. 1½": Maximum span, 9'-0"; minimum rod size, 3/8".
 - 4. 2": Maximum span, 10'-0"; minimum rod size, 3/8".
 - 5. 2½": Maximum span, 11'-0"; minimum rod size, 3/8".
 - 6. 3": Maximum span, 12'-0"; minimum rod size, 3/8".
 - 7. 4": Maximum span, 14'-0"; minimum rod size, ½".
 - 8. 6": Maximum span, 17'-0"; minimum rod size, ½".
 - 9. 8": Maximum span, 19'-0"; minimum rod size, 5/8".
 - 10. 10": Maximum span, 20'-0"; minimum rod size, ³/₄".
 - 11. 12": Maximum span, 23'-0"; minimum rod size, 7/8".
 - 12. 14": Maximum span, 25'-0"; minimum rod size, 1".
 - 13. 16": Maximum span, 27'-0"; minimum rod size, 1".
 - 14. 18": Maximum span, 28'-0"; minimum rod size, 11/4".
 - 15. 20": Maximum span, 30'-0"; minimum rod size, 11/4".
- C. Where hangers for steel piping are to be suspended from open-web steel joists, install hangers at maximum spacing that will result in hanger loads that comply with the requirements on the structural drawings.
- D. Install hangers for copper piping with the following maximum spacing and minimum rod sizes:
 - 1. ³/₄": Maximum span, 5'-0"; minimum rod size, ¹/₄".
 - 2. 1": Maximum span, 6'-0"; minimum rod size, ½".
 - 3. 1½": Maximum span, 8'-0"; minimum rod size, 3/8".
 - 4. 2": Maximum span, 8'-0"; minimum rod size, 3/8".
 - 5. 2½": Maximum span, 9'-0"; minimum rod size, 3/8".
 - 6. 3": Maximum span, 10'-0"; minimum rod size, 3/8".
- E. Plastic Piping Hanger Spacing: Space hangers according to pipe manufacturer's written instructions for service conditions. Avoid point loading. Space and install hangers with the fewest practical rigid anchor points.
- F. Support vertical runs at roof, at each floor, and at 10-foot intervals between floors.
- 3.5 Where changes in direction or tees occur, place hangers 1/3 of the maximum allowed spacing distance from the change in direction or tee (i.e. if the maximum span is 12 feet, the hanger shall be 4feet from the change in direction or tee). Pipe shall be supported from both sides of a change in direction.

3.6 END OF SECTION 232113

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 232300 - REFRIGERANT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

- A. Product Data: For each type of valve and refrigerant piping specialty indicated for the following:
 - 1. Thermostatic expansion valves.
 - 2. Filter dryers.
 - 3. Strainers.
- B. Operation and Maintenance Data: For refrigerant valves and piping specialties to include in maintenance manuals.

1.3 PRODUCT STORAGE AND HANDLING

A. Store piping in a clean and protected area with end caps in place to ensure that piping interior and exterior are clean when installed.

1.4 QUALITY ASSURANCE

- A. Welding/Brazing: Qualify procedures and personnel according to ASME Boiler and Pressure Vessel Code: Section IX; "Welding and Brazing Qualifications."
- B. ASHRAE Standard: Comply with ASHRAE 15, "Safety Code for Mechanical Refrigeration."
- C. ASME Standard: Comply with ASME B31.5, "Refrigeration Piping."
- D. UL Standard: Provide products complying with UL 207, "Refrigerant-Containing Components and Accessories, Nonelectrical"; or UL 429, "Electrically Operated Valves."

1.5 COORDINATION

- A. Coordinate layout and installation of refrigerant piping and suspension system components with other construction, including light fixtures, HVAC equipment, fire-suppression-system components, and partition assemblies.
- B. Coordinate pipe sleeve installations for wall penetrations.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- C. Coordinate installation of roof curbs, equipment supports, and roof penetrations.
- D. Coordinate pipe sleeve installations for penetrations in exterior walls and floor assemblies. Coordinate with requirements for firestopping.
- E. Coordinate pipe fitting pressure classes with products specified in related Sections.
- F. Some components listed in this section may be factory installed, such as thermostatic mixing valves or service valves.

PART 2 - PRODUCTS

2.1 COPPER TUBE AND FITTINGS

- A. Copper Tube: ASTM B 280, Type ACR.
- B. Wrought-Copper Fittings: ASME B16.22.
- C. Wrought-Copper Unions: ASME B16.22.
- D. Solder Filler Metals: ASTM B 32. Use 95-5 tin antimony solder to join copper socket fittings on copper pipe.
- E. Brazing Filler Metals: AWS A5.8.

2.2 VALVES AND SPECIALTIES

- A. Service Valves:
 - 1. Body: Forged brass with brass cap including key end to remove core.
 - 2. Core: Removable ball-type check valve with stainless-steel spring.
 - 3. Seat: Polytetrafluoroethylene.
 - 4. End Connections: Copper spring.
 - 5. Working Pressure Rating: 500 psig.
- B. Thermostatic Expansion Valves: Comply with ARI 750.
 - 1. Body, Bonnet, and Seal Cap: Forged brass or steel.
 - 2. Diaphragm, Piston, Closing Spring, and Seat Insert: Stainless steel.
 - 3. Packing and Gaskets: Non-asbestos.
 - 4. Capillary and Bulb: Copper tubing filled with refrigerant charge.
 - 5. Suction Temperature: 40 deg F.
 - 6. Superheat: Adjustable.
 - 7. Reverse-flow option for heat-pump applications.
 - 8. End Connections: Socket, flare, or threaded union.
 - 9. Working Pressure Rating: 450 psig.

C. Moisture/Liquid Indicators:

1. Body: Forged brass.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Window: Replaceable, clear, fused glass window with indicating element protected by filter screen.
- 3. Indicator: Color coded to show moisture content in ppm.
- 4. Minimum Moisture Indicator Sensitivity: Indicate moisture above 60 ppm.
- 5. End Connections: Socket or flare.
- 6. Working Pressure Rating: 500 psig.
- 7. Maximum Operating Temperature: 240 deg F.
- D. Permanent Filter Dryers: Comply with ARI 730.
 - 1. Body and Cover: Painted-steel shell.
 - 2. Filter Media: 10 micron, pleated with integral end rings; stainless-steel support.
 - 3. Desiccant Media: Activated alumina or charcoal.
 - 4. Designed for reverse flow where heat-pump applications are indicated.
 - 5. End Connections: Socket.
 - 6. Access Ports: NPS 1/4 connections at entering and leaving sides for pressure differential measurement.
 - 7. Maximum Pressure Loss: 2 psig Insert value.
 - 8. Rated Flow: Match equipment.
 - 9. Working Pressure Rating: 500 psig.
 - 10. Maximum Operating Temperature: 240 deg F.

2.3 REFRIGERANTS

- A. Available Manufacturers:
 - 1. Atofina Chemicals, Inc.
 - 2. DuPont Company; Fluorochemicals Div.
 - 3. Honeywell, Inc.; Genetron Refrigerants.
 - 4. INEOS Fluor Americas LLC.
- B. ASHRAE 34, R-410A: Pentafluoroethane/Difluoromethane.

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS FOR REFRIGERANT

- A. Liquid Lines: Copper, Type ACR, annealed-temper tubing and wrought-copper fittings with brazed or soldered joints.
- B. Suction Lines for Heat-Pump Applications: Copper, Type ACR, annealed-temper tubing and wrought-copper fittings with brazed or soldered joints.

3.2 VALVE AND SPECIALTY APPLICATIONS

A. Install moisture/liquid indicator and filter dryer in each refrigerant circuit.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.3 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems; indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Shop Drawings.
- B. Install refrigerant piping according to ASHRAE 15.
- C. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- F. Install piping adjacent to machines to allow service and maintenance.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Select system components with pressure rating equal to or greater than system operating pressure.
- J. Install piping as short and direct as possible, with a minimum number of joints, elbows, and fittings.
- K. Arrange piping to allow inspection and service of refrigeration equipment. Install valves and specialties in accessible locations to allow for service and inspection. Install access doors or panels as specified in Division 08 Section "Access Doors and Frames" if valves or equipment requiring maintenance is concealed behind finished surfaces.
- L. Install refrigerant piping in protective conduit where installed belowground.
- M. Install refrigerant piping in rigid or flexible conduit in locations where exposed to mechanical injury.
- N. Slope refrigerant piping as follows:
 - 1. Install horizontal suction lines with a uniform slope downward to compressor.
 - 2. Install traps and double risers to entrain oil in vertical runs.
 - 3. Liquid lines may be installed level.
- O. When brazing or soldering, remove solenoid-valve coils and sight glasses; also remove valve stems, seats, & packing, and accessible internal parts of refrigerant specialties. Do not apply heat near expansion-valve bulb.
- P. Install piping with adequate clearance between pipe and adjacent walls and hangers or between pipes for insulation installation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- Q. Identify refrigerant piping and valves according to Section "Identification for HVAC Piping and Equipment."
- R. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section "Sleeves and Sleeve Seals for HVAC Piping."
- S. Install sleeve seals for piping penetrations of exterior walls and floor slabs. Comply with requirements for sleeve seals specified in Section "Sleeves and Sleeve Seals for HVAC Piping."
- T. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section "Escutcheons for HVAC Piping."

3.4 PIPE JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- C. Fill pipe and fittings with an inert gas (nitrogen or carbon dioxide), during brazing.
- D. Soldered Joints: Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook."
- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," Chapter "Pipe and Tube."
 - 1. Use Type BcuP, copper-phosphorus alloy for joining copper socket fittings with copper pine
 - 2. Use Type BAg, cadmium-free silver alloy for joining copper with bronze.

3.5 HANGERS AND SUPPORTS

- A. Hanger, support, and anchor products are specified in Section "Hangers and Supports for HVAC Piping and Equipment."
- B. Install the following pipe attachments:
 - 1. Adjustable steel clevis hangers for individual horizontal runs less than 20'-0" long.
 - 2. Roller hangers and spring hangers for individual horizontal runs 20'-0" or longer.
 - 3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal piping 20'-0" or longer, supported on a trapeze.
 - 4. Spring hangers to support vertical runs.
 - 5. Copper-clad hangers and supports for hangers and supports in direct contact with copper pipe.
- C. Install hangers for copper tubing with the following maximum spacing and minimum rod sizes:

1. ½": Maximum span, 60"; minimum rod size, ¼".

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. 5/8": Maximum span, 60"; minimum rod size, ½".
- 3. 1": Maximum span, 72"; minimum rod size, ½".
- 4. 1 1/4": Maximum span, 96"; minimum rod size, 3/8".
- 5. 1 ½": Maximum span, 96"; minimum rod size, 3/8".
- D. Support multifloor vertical runs at least at each floor.

3.6 FIELD QUALITY CONTROL

- A. Perform tests and inspections and prepare test reports.
- B. Tests and Inspections:
 - 1. Comply with ASME B31.5, Chapter VI.
 - 2. Test refrigerant piping, specialties, and receivers. Isolate compressor, condenser, evaporator, and safety devices from test pressure if they are not rated above the test pressure.
 - 3. Test high- and low-pressure side piping of each system separately at not less than the pressures indicated in Part 1 "Performance Requirements" Article.
 - a. Fill system with nitrogen to the required test pressure.
 - b. System shall maintain test pressure at the manifold gage throughout duration of test.
 - c. Test joints and fittings with electronic leak detector or by brushing a small amount of soap and glycerin solution over joints.
 - d. Remake leaking joints using new materials, and retest until satisfactory results are achieved.

3.7 SYSTEM CHARGING

- A. Charge system using the following procedures:
 - 1. Evacuate entire refrigerant system with a vacuum pump to 500 micrometers. If vacuum holds for 12 hours, system is ready for charging.
 - 2. Break vacuum with refrigerant gas, allowing pressure to build up to manufacturer's recommendation.

3.8 ADJUSTING

- A. Adjust thermostatic expansion valve to obtain proper performance.
- B. Adjust high- and low-pressure switch settings to avoid short cycling in response to fluctuating suction pressure.
- C. Adjust set-point temperature of air-conditioning controllers to the system design temperature.

END OF SECTION 232300

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 233113 - METAL DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 PERFORMANCE REQUIREMENTS

- A. Seal all ducts to seal class A as defined in SMACNA's HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005:
 - 1. Seal all longitudinal joints.
 - 2. Seal all transverse joints.
 - 3. Seal all penetrations.
- B. Seal Class: A
- C. Test pressure:
 - 1. 3.0" WC for round and flat oval duct.
 - 2. 6.0" WC for rectangular duct.
 - 3. Un-tested: NA
- D. Testing: Leak test all ductwork operating at 3.0" WC or greater.
- E. Duct Construction: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005" and performance requirements and design criteria indicated in "Duct Schedule" Article.
- F. Liner Airstream Surfaces: Liner surfaces in contact with the airstream shall comply with ASHRAE 62.1-2007, paragraph 5.5.
- G. Cleanliness: All factory fabricated duct shall be cleaned with a non-toxic, biodegradable cleaner/degreaser and shall be shrink wrapped prior to shipment.
- H. Structural Performance: Smoke removal duct hangers, supports and seismic restraints shall withstand the effects of gravity and seismic loads and stresses within limits and under conditions described in SMACNA's HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005 and ASCE/SEI 7.

1.3 ABBREVIATIONS

- A. BAS Building Automation System
- B. NRTL Nationally Recognized Testing Laboratory
- C. SMACNA Sheet Metal and Air Conditioning Contractors' National Association

D. WC Water Column

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.4 DEFINITIONS:

- A. Duct System: For the purposes of this section "duct system" shall mean all metal supply, return, and exhaust duct and fittings between the air moving device and the space.
- B. Low Pressure: Plus two (2.0) inches WC to minus one (1.0) inches WC
- C. Medium Pressure: More than two (2.0) inches WC to plus ten (10.0) inches WC or more than minus one (1.0) inch to minus ten (10.0) inches WC
- D. High Pressure: More than plus or minus ten (10.0) inches WC.

1.5 SUBMITTALS

- A. Product Data / Documentation: For each of the following:
 - 1. Sheet metal thicknesses.
 - 2. Liners and adhesives.
 - 3. Pre-manufactured ductwork.
 - 4. Sealants and gaskets.
 - 5. VOC content for adhesives and sealants.
 - 6. Seismic-restraint devices.
- B. CAD-generated Shop Drawings:
 - 1. Provide coordination shop drawings with all trades for entire building including kitchen, laundry and water/mechanical rooms. Include
 - 2. Show fabrication and installation details for metal ducts.
 - 3. 1/4" = 1'-0" scale minimum including duct layout indicating sizes and pressure classes for the following areas:
 - a. Areas indicated on the drawings at 1/4" = 1'-0" scale.
 - b. Areas where sections are cut.
 - c. Auditoriums.
 - d. Gymnasiums.
 - e. Commercial kitchens.
 - f. Commercial laundries.
 - g. Finished spaces with exposed ductwork.
 - 1) Exceptions:
 - a) Janitors closets
 - b) Storage Rooms
 - c) Receiving Areas
 - 2) Include:
 - a) Plans, elevations and sections.
 - b) Elevations of top and bottom of ducts.
 - c) Dimensions of main duct runs from building grid lines.
 - 4. 3/4" = 1'-0" scale minimum for the following:
 - a. Hangers and supports, including methods for duct and building attachment, vibration isolation.
 - b. Duct accessories, including access doors and panels.
 - c. Equipment installation based on approved equipment submittals.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- d. Penetrations through fire-rated and other partitions.
- e. Fittings.
- f. Components.

C. Submittals during construction:

- 1. Leakage Test Report: Documentation of work performed for compliance with ASHRAE/IESNA 90.1-2007, Section 6.4.4.2.2 "Duct Leakage Tests."
- 2. Duct-Cleaning Test Report: Documentation of work performed for compliance with ASHRAE 62.1-2007, Section 7.2.4 "Ventilation System Start-Up."

1.6 QUALITY ASSURANCE

- A. Provide work in compliance with applicable Building Code requirements.
- B. Welding Qualifications: Qualify procedures and personnel according to the following:
- C. AWS D1.1/D1.1M, "Structural Welding Code Steel," for hangers and supports.
- D. AWS D1.2/D1.2M, "Structural Welding Code Aluminum," for aluminum supports.
- E. AWS D9.1M/D9.1, "Sheet Metal Welding Code," for duct joint and seam welding.
- F. ASHRAE Compliance: Comply with applicable requirements in ASHRAE 62.1-2007, Section 5 "Systems and Equipment" and Section 7 "Construction and System Start-Up."
- G. ASHRAE/IESNA Compliance: Comply with applicable requirements in ASHRAE/IESNA 90.1-2007, Section 6.4.4 "HVAC System Construction and Insulation."
- H. Mockups (Contractor's option in lieu of 3"=1'-0" details):
 - 1. Before installing duct systems, build mockups. Build mockups to comply with the following requirements, using materials indicated for the completed Work:
 - 2. Three transverse joints.
 - 3. One Reinforced section with 3 reinforcements.
 - 4. One of each type; attachments to other work.
 - 5. Two typical flexible duct or flexible-connector connections.
 - 6. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

PART 2 - PRODUCTS

2.1 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005" based on indicated static-pressure class unless otherwise indicated.
- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 2-1, "Transverse (Girth) Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005."

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 2-2, "Rectangular Duct/Longitudinal Seams" for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005."
- D. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Chapter 4, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005."

2.2 LOW PRESSURE SINGLE-WALL ROUND DUCTS AND FITTINGS –CONCEALED

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Chapter 3, "Round, Oval, and Flexible Duct," based on specified static-pressure class unless otherwise indicated.
- B. Snap-Lock Round Pipe
 - 1. Meet SMACNA Class 3 Leakage standards and SMACNA Seal Class A with external, mastic duct sealant. Provide ASTM A653 galvanized steel, 26 gauge, G-60 coating. Product shall meet pressure rating of -1" wg to +2" wg.
 - 2. Available Manufacturers:
 - a. GreenSeam Industries (GreenSeam Plus)

C. Manufacturers:

- 1. Eastern Sheet Metal.
- 2. Hamlin Sheet Metal.
- 3. Linx Industries Lindab.
- 4. McGill AirFlow LLC.
- 5. MKT Metal Manufacturing
- 6. Semco, Inc.
- 7. Sheet Metal Connectors, Inc.
- 8. Spiral Manufacturing Co., Inc.
- D. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 3-1, "Round Duct Transverse Joints"
 - 1. Transverse Joints in Ducts Equal to or Larger Than 48" in Diameter: Flanged.
 - 2. Gasketed, EPDM, self-sealing Joints such as Eastern Tight or Spiro Safe may be used for ducts smaller than 48" in diameter.
 - 3. Flanges may be substituted in ducts smaller than 48" in diameter.
- E. Duct support intervals, and other provisions: In accordance with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005."
- F. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 3-2, "Seams Round Duct and Fittings," for static-pressure class, applicable sealing requirements, materials involved,

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005."
- G. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 3-5, "90° Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005." Adjustable elbows are not permitted.
- H. All round duct shall not be less than 26-gauge.

2.3 LOW PRESSURE SINGLE-WALL ROUND DUCTS AND FITTINGS -EXPOSED

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Chapter 3, "Round, Oval, and Flexible Duct," "FIGURE 3-2 ROUND DUCT LONGITUDINAL SEAMS" "SPIRAL SEAM RL-1" to plus-or-minus 10" WC unless otherwise indicated.
- B. Manufacturers:
 - 1. Eastern Sheet Metal.
 - 2. Hamlin Sheet Metal.
 - Linx Industries Lindab.
 - 4. McGill AirFlow LLC.
 - 5. MKT Metal Manufacturing
 - 6. Semco, Inc.
 - 7. Sheet Metal Connectors, Inc.
 - 8. Spiral Manufacturing Co., Inc.
- C. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 3-1, "Round Duct Transverse Joints"
- D. Static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005." And the following:
 - 1. Transverse Joints in Ducts Equal to or Larger Than 48" in Diameter or Flat Oval with a Major Dimension Equal to or Larger Than 48": Flanged.
 - 2. Gasketed, EPDM, self-sealing Joints such as Eastern Tight or Spiro Safe may be used for ducts smaller than 48" in diameter.
 - 3. Flanges may be substituted in ducts smaller than 48" in diameter.
- E. Longitudinal Seams: Duct shall be spiral according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 3-2, "Round Duct Longitudinal Seams"
- F. Tees and Laterals: Tees and laterals shall be created with fittings. Fabricate fittings according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005." Adjustable elbows are not permitted.
- G. Static-pressure class: Applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards Metal and Flexible. Third Edition 2005."

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- H. Longitudinal seams shall be spiral type.
- I. All round duct shall not be less than 26-gauge.

2.4 SHEET METAL MATERIALS

- A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
 - 1. Galvanized Coating Designation: G90.
 - 2. Finishes for Surfaces Exposed to View: Mill phosphatized.
- C. Carbon-Steel Sheets: Comply with ASTM A 1008/A 1008M.
- D. Stainless-Steel Sheets: Comply with ASTM A 480/A 480M, Type 316, cold rolled, annealed, sheet. Exposed surface finish shall be No. 4.
- E. Aluminum Sheets: Comply with ASTM B 209 Alloy 3003, H14 temper; with mill finish for concealed ducts, and standard, one-side bright finish for duct surfaces exposed to view.
- F. Reinforcement Shapes and Plates: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- G. Where black- and galvanized-steel shapes and plates are used to reinforce aluminum ducts, isolate the different metals with butyl rubber, neoprene, or EPDM gasket materials.
- H. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.5 DUCT LINER

- A. For double wall duct: Not required. All other duct: Provide where indicated.
- B. Fibrous-Glass Duct Liner: Comply with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."
 - 1. Manufacturers:
 - a. CertainTeed Corporation.
 - b. Johns Manville.
 - c. Knauf Insulation.
 - d. Owens Corning.
 - 2. Maximum Thermal Conductivity:
 - 1) Type I, Flexible: 0.26 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
 - 2) Type II, Rigid: 0.23 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. For supply ductwork, provide antimicrobial, erosion-resistant coating: Apply to the surface of the liner that will form the interior surface of the duct to act as a moisture repellent and erosion-resistant coating. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.
- 4. Water-Based Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 916.
- C. Flexible Elastomeric Duct Liner: Preformed, cellular, closed-cell, sheet materials complying with ASTM C 534, Type II, Grade 1; and with NFPA 90A or NFPA 90B. Foam shall contain or be coated with EPA-approved or EPA-registered antimicrobial additive or paint.
 - 1. Manufacturers:
 - a. Aeroflex USA, Inc.
 - b. Armacell LLC.
 - c. K-Flex USA.
 - 2. Maximum Thermal Conductivity: 0.25 Btu x in./h x sq. ft. x deg F at75 deg F mean temperature when tested according to ASTM C 518.
 - 3. Surface-Burning Characteristics: Maximum flame-spread index of 25 and maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
 - 4. Liner Adhesive: As recommended by insulation manufacturer and complying with NFPA 90A or NFPA 90B.
- D. Natural-Fiber Duct Liner: 85 percent cotton, 10 percent borate, and 5 percent polybinding fibers, treated with a microbial growth inhibitor and complying with NFPA 90A or NFPA 90B.
 - 1. Manufacturers:
 - a. Ductmate Industries, Inc.
 - 2. Maximum Thermal Conductivity: 0.24 Btu x in./h x sq. ft. x deg F at75 deg F mean temperature when tested according to ASTM C 518.
 - 3. Surface-Burning Characteristics: Maximum flame-spread index of 25 and maximum smoke-developed index of 50 when tested according to ASTM E 84; certified by an NRTL.
 - 4. Liner Adhesive: As recommended by insulation manufacturer and complying with NFPA 90A or NFPA 90B.
- E. Insulation Pins and Washers:
 - 1. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch- diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
 - 2. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick galvanized steel; with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
- F. Shop Application of Duct Liner: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 7-11, "Flexible Duct Liner Installation."

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
- 2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
- 3. Butt transverse joints without gaps, and coat joint with adhesive.
- 4. Fold and compress liner in corners of rectangular ducts or cut and fit to ensure buttededge overlapping.
- 5. Do not apply liner in rectangular ducts with longitudinal joints, except at corners of ducts, unless duct size and dimensions of standard liner make longitudinal joints necessary.
- 6. Apply adhesive coating on longitudinal seams in ducts with air velocity of 2500 fpm.
- 7. Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.
- 8. Secure transversely oriented liner edges facing the airstream with metal nosings that have either channel or "Z" profiles or are integrally formed from duct wall. Fabricate edge facings at the following locations:
 - a. Fan discharges.
 - b. Intervals of lined duct preceding unlined duct.
 - c. Upstream edges of transverse joints in ducts where air velocities are higher than 2500 fpm or where indicated.
- G. Terminate inner ducts with buildouts attached to fire-damper sleeves, dampers, turning vane assemblies, or other devices. Fabricated buildouts (metal hat sections) or other buildout means are optional; when used, secure buildouts to duct walls with bolts, screws, rivets, or welds.

2.6 SEALANT AND GASKETS

- A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723.
 - 1. Materials: Certified by a NRTL.
- B. Tape sealing systems are not permitted.
- C. Water-Based Joint and Seam Sealant:
 - 1. Application Method: Brush on.
 - 2. Solids Content: Minimum 65 percent.
 - 3. Shore A Hardness: Minimum 20.
 - 4. Water resistant.
 - 5. Mold and mildew resistant.
 - 6. VOC: Maximum 75 g/L (less water).
 - 7. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
 - 8. Service: Indoor or outdoor.
 - 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.
 - 10. Indoor applications: Sealant with VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 11. Maximum Static-Pressure Class: 10-inch wg, positive or negative.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 12. Service: Indoor or outdoor.
- 13. Substrate: Compatible with galvanized sheet steel, stainless steel, or aluminum sheets.
- D. Flanged Joint Sealant: Comply with ASTM C 920.
 - 1. General: Single-component, acid-curing, silicone, elastomeric.
 - 2. Type: S.
 - 3. Grade: NS.
 - 4. Class: 25.
 - 5. Use: O.
 - 6. Indoor applications: Sealant with VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- E. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.

2.7 HANGERS AND SUPPORTS

- A. Hanger Rods: Galvanized, all-thread.
- B. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."
- C. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A 603.
- D. Steel Cables for Stainless-Steel Ducts: Stainless steel complying with ASTM A 492.
- E. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.
- F. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.
- G. Trapeze and Riser Supports:
 - 1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
 - 2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.
 - 3. Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate.

PART 3 - EXECUTION

3.1 DUCT INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved by Architect in writing.
- B. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005" unless otherwise indicated.
- C. Install ducts with fewest possible joints.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. Install factory-fabricated fittings for changes in direction, size, and shape and for branch connections.
- E. Unless otherwise indicated, install ducts vertically or horizontally, and parallel or perpendicular to building lines.
- F. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building. Maintain clearances for equipment maintenance.
- G. Install ducts with a clearance of 1 inch, plus allowance for installation of insulation at specified thickness.
- H. Do not route ducts through transformer vaults, electrical equipment rooms, elevator equipment rooms or electrical enclosures.
- I. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.
- J. Provide fire dampers where ducts pass through fire-rated interior partitions, fire-rated exterior walls, fire-rated floor assemblies, or fire-rated shaft enclosures.
- K. Protect duct interiors from moisture, construction debris, dust, and other foreign materials. Comply with SMACNA's "Duct Cleanliness for New Construction Guidelines."

3.2 PROTECTION OF WALL AND FLOOR PENETRATIONS OF NON-RATED ASSEMBLIES

- A. Where ducts penetrate non-fire-resistance-rated wall or floor assemblies, protect the penetration with one of the following:
 - 1. For a duct that connects not more than two stories vertically, protect the annular space around the penetrating duct with an approved, noncombustible material that resists the free passage of flame and the products of combustion.
 - 2. For a duct that connects not more than three stories, protect the annular space around the penetrating duct with an approved, noncombustible material that resists the free passage of flame and the products of combustion and a fire damper at each floor line.
 - 3. For ducts that penetrate a smoke partition without a smoke damper, protect the annular space around the penetrating duct with an approved, non-combustible materials that resists the free passage of flame and the products of combustion.
 - 4. For ducts that penetrate a non-rated wall, protect the annular space around the penetrating duct with an approved, non-combustible materials that resists the free passage of flame and the products of combustion.

3.3 INSTALLATION OF EXPOSED DUCTWORK

- A. Protect ducts exposed in finished spaces from being dented, scratched, or damaged.
- B. Trim duct sealants flush with metal. Create a smooth and uniform exposed bead. Do not use two-part tape sealing system.
- C. Grind welds to provide smooth surface free of burrs, sharp edges, and weld splatter. When welding stainless steel with a No. 3 or 4 finish, grind the welds flush, polish the exposed welds,

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- and treat the welds to remove discoloration caused by welding. Do not weld or grind lined ductwork.
- D. Maintain consistency, symmetry, and uniformity in the arrangement and fabrication of duct, fittings, hangers, supports, accessories, and air outlets.
- E. Repair or replace damaged sections and finished work that does not comply with these requirements.

3.4 DUCT SEALING

- A. Seal all ducts to seal class A as defined in SMACNA's HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005:
 - 1. Seal all longitudinal joints.
 - 2. Seal all transverse joints.
 - 3. Seal all penetrations.

3.5 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Chapter 5, "Hangers and Supports."
- B. Building Attachments: Unless indicated otherwise, provide concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
 - 1. Where practical, install concrete inserts before placing concrete.
 - 2. Do not use powder-actuated concrete fasteners for lightweight-aggregate concrete or for slabs less than 4 inches thick.
- C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.
- D. Hangers Exposed to View: Threaded rod and channel supports.
- E. Support vertical ducts with channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor or at a maximum interval of 18 feet.
- F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

3.6 SEISMIC-RESTRAINT-DEVICE INSTALLATION

- A. Design hangers and braces to support the duct and to restrain against seismic forces required by applicable building codes. Comply with ASCE/SEI 7 and brace changes of direction longer than 12 feet.
- B. Select seismic-restraint devices with capacities adequate to carry present and future static and seismic loads.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- C. Install cables so they do not bend across edges of adjacent equipment or building structure.
- D. Install cable restraints on ducts that are suspended with vibration isolators.
- E. Attachment to Structure: If specific attachment is not indicated, anchor bracing and restraints to structure, to flanges of beams, to upper truss chords of bar joists, or to concrete members.
- F. Drilling for and Setting Anchors:
 - Identify position of reinforcing steel and other embedded items prior to drilling holes
 for anchors. Do not damage existing reinforcement or embedded items during drilling.
 Notify the Architect if reinforcing steel or other embedded items are encountered during
 drilling. Locate and avoid prestressed tendons, electrical and telecommunications
 conduit, and gas lines.
 - 2. Do not drill holes in concrete or masonry until concrete, mortar, and grout has achieved full design strength.
 - 3. Wedge Anchors: Protect threads from damage during anchor installation. Install heavy-duty sleeve anchors with sleeve fully engaged in the structural element to which anchor is to be fastened.
 - 4. Set anchors to manufacturer's recommended torque, using a torque wrench.
 - 5. Install zinc-coated steel anchors for interior applications and stainless-steel anchors for applications exposed to weather.

3.7 CONNECTIONS

- A. Make connections to equipment with flexible connectors.
- B. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005" for branch, outlet, inlet, and terminal unit connections unless otherwise indicated.

3.8 PAINTING

A. Paint interior of metal ducts that are visible through registers and grilles and that do not have duct liner. Apply two coats of flat black, latex paint over a compatible galvanized-steel primer.

3.9 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Visually inspect, for proper seal application, all ductwork not tested prior to insulation application. Prepare inspection report.
- C. Leakage Test. Test ducts with operational pressures greater than 3" WC.
 - 1. Comply with SMACNA's "HVAC Air Duct Leakage Test Manual." Prepare a report for each test.
 - 2. Test ducts, disassemble, reassemble, reseal, and retest until leakage class 3 (as defined in SMACNA's HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005) is achieved.
 - 3. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
 - 4. Test for leaks before applying external insulation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 5. Conduct tests at static pressures equal to maximum design pressure of system or section being tested.
- 6. Give seven days' advance notice to Architect and Owner for testing.

D. Duct System Cleanliness Tests:

- 1. Visually inspect duct system to ensure that no visible contaminants are present. If visible contaminants are present, proceed to sub-paragraph 2 below. If not, no further cleaning shall be required.
- 2. Test sections of metal duct systems, up to one location per ten thousand (10,000) square feet of building area, or a minimum of two (2) per system, whichever is greater, chosen by the Owner's Representative, for cleanliness according to "Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems." Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm. Cut hole in duct and install access door at each location selected. Size shall be as indicated in Division 23 Section "Air Duct Accessories."
- 3. Duct system shall be considered dirty and in need of cleaning if any test location does not pass the cleanliness test. Cleaning shall be performed in accordance with this specification.
- E. Prepare and submit test and inspection reports.

3.10 DUCT CLEANING

- A. Clean new duct systems before testing, adjusting, and balancing.
- B. Comply with SMACNA "Duct Cleanliness for New Construction Guidelines" dated 2000, for protection, cleaning, and installation methods for all ductwork. Adhere to the requirements for a duct cleanliness level of "C" (advanced level) as detailed in Section 3.11.

3.11 START UP

A. Air Balance: Comply with requirements in Division 23 Section "Testing, Adjusting, and Balancing for HVAC."

3.12 DUCT SCHEDULE

- A. Fabricate ducts with galvanized sheet steel except as otherwise indicated and as follows:
- B. Elbow Configuration:
 - 1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 4-2, "Rectangular Elbows."
 - a. Velocity less than 1500 fpm or lower:
 - 1) Radius Type RE 1. Centerline radius = 3W/2.
 - 2) Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 4-3, "Vanes and Vane Runners," and Figure 4-4, "Vane Support in Elbows."
 - 3) Transfer ducts indicated with mitered elbows do not require turning vanes.

b. Velocity 1500 fpm or Higher:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1) Radius Type RE 3. Centerline radius = 3w/2 and three vanes.
- 2) Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 2-3, "Vanes and Vane Runners," and Figure 2-4, "Vane Support in Elbows."
- 2. Round Duct: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 3-4, "Round Duct Elbows."
 - a. Minimum centerline radius-to-diameter ratio shall be 1.5 with a maximum of 5 Elbow Segments. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Table 3-1, "Mitered Elbows." Elbows with less than a 90 degree change of direction shall have segments per Table 3-1 in SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005".
 - b. Round Elbows, 12 Inches and Smaller in Diameter: Stamped, segmented, spiral or pleated. Adjustable elbows not acceptable.
 - c. Round Elbows, 14 Inches and Larger in Diameter: Standing seam, segmented, or spiral.
- 3. Flat Oval Duct: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 3-7, "Flat Oval Ducts" for elbows.

C. Branch Configuration:

- 1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 4-6, "Branch Connections."
 - a. Rectangular Main to Rectangular Branch: 45-degree entry.
 - b. Rectangular Main to Round Branch: Conical or bell mouth. No flanged or spin-in fittings permitted.
- 2. Round and Flat Oval: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005," Figure 3-6, "Conical Tees."
 - a. Conical fitting.
 - b. Conical saddle taps.
 - c. No 90 degree taps or 90 degree saddle taps permitted.

D. Divided Flow Branches:

1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards – Metal and Flexible, Third Edition 2005, "Figure 4-5 Divided Flow Branches."

3.13 Duct Pressure Classes:

- A. Supply ducts from units to air terminals: 1 inch WC.
- B. Return ducts: 1 inch WC.
- C. Exhaust ducts: 2 inch WC.

END OF SECTION 233113

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 233300 - AIR DUCT ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

- A. Product Data: For the following:
 - 1. Motorized control dampers.
 - 2. Turning vanes.
 - Flexible connectors.
- B. Wiring Diagrams: For power, signal, and control wiring.
- C. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

1.3 QUALITY ASSURANCE

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with AMCA 500-D testing for damper rating.
- C. Comply with SMACNA standards for manual airflow regulators (dampers).

1.4 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Fusible Links: Furnish quantity equal to 10 percent of amount installed. Minimum 1 of each type used.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible" for acceptable duct installation methods unless otherwise indicated.
- C. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Galvanized Coating Designation: G90.
- 2. Exposed-Surface Finish: Mill phosphatized.
- D. Stainless-Steel Sheets: Comply with ASTM A 480/A 480M, Type 304, and having a NO 2 finish for concealed ducts and NO 4 finish for exposed ducts.
- E. Aluminum Sheets: Comply with ASTM B 209, Alloy 3003, temper H14; with mill finish for concealed ducts and standard, 1-side bright finish for exposed ducts.
- F. Extruded Aluminum: Comply with ASTM B 221, Alloy 6063, Temper T6.
- G. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.
- H. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches; compatible materials for aluminum and stainless-steel ducts.

2.2 RADIUS FORMING BRACES

- A. Available manufacturers:
 - 1. Titus, FlexRight (Basis of Design)
 - 2. Flexible Technologies, Inc., Thermaflex Division, FlexFlow
 - 3. Hart & Cooley, Smart Flow Elbow
- B. General: UL-2043 listed or NRTL approved product constructed of metal or plastic manufactured for use with flexible duct to form a kink free elbow using the flexible duct. Any flexible duct used in forming the elbow shall be included in the maximum permitted length. Resulting flexible duct shall comply with SMACNA HVAC Duct Construction Standards.
- C. Duct Size: 6" through 16" in diameter.
- D. Inside (Bend) Radius: Minimum of one duct diameter along centerline.
- E. Attachments: Plastic zip ties or stainless steel worm gear clamps.
- F. Support to Overhead: Shall meet SMACNA requirements. Use of specified attachments for support shall not be permitted.

2.3 MANUFACTURED TURNING VANES

- A. Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
- B. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible"; Figures 2-3, "Vanes and Vane Runners," and 2-4, "Vane Support in Elbows."
- C. Vane Construction: Single wall for ducts up to 48 inches wide and double wall for larger dimensions.

2.4 DUCT-MOUNTED ACCESS DOORS

- A. Available Manufacturers:
 - 1. Ductmate Industries, Inc.
 - 2. Flexmaster U.S.A., Inc.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Greenheck Fan Corporation.
- 4. Kees
- 5. McGill AirFlow LLC.
- B. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible"; Figures 2-10, "Duct Access Doors and Panels," and 2-11, "Access Panels Round Duct."
 - 1. Door:
 - a. Double wall, rectangular.
 - b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
 - c. Hinges and Latches: 1-by-1-inch butt or piano hinge and cam latches.
 - d. Fabricate doors airtight and suitable for duct pressure class.
 - 2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
 - 3. Number of Hinges and Locks:
 - a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
 - b. Access Doors up to 18 Inches Square: Two hinges and two sash locks.
 - c. Access Doors up to 24 by 48 Inches: Three hinges and two compression latches with outside and inside handles.
 - d. Access Doors Larger Than 24 by 48 Inches: Four hinges and two compression latches with outside and inside handles.

2.5 FLEXIBLE CONNECTORS

- A. Do not use on smoke control/management fans. Install on all other fans and fan equipped units even when provided with internal isolation.
- B. Available Manufacturers:
 - 1. Ductmate Industries, Inc.
 - 2. Duro Dyne Corporation.
 - 3. Ventfabrics, Inc.
 - 4. Hart & Cooley, Inc.
- C. Materials: Flame-retardant or noncombustible fabrics.
- D. Coatings and Adhesives: Comply with UL 181, Class 1.
- E. Connector: Factory fabricated with a fabric strip 3½ to 4½ inches wide attached to 2 strips of 2½ to 4½ inches wide, 23 to 25 gauge "0.0269 to .0209 inch thick" galvanized sheet steel, stainless sheet steel, or aluminum sheets. Provide metal compatible with connected ducts.
- F. Indoor System, Flexible Connector Fabric: Glass fabric double-coated with neoprene.
 - 1. Minimum Weight: 26 oz/sq. yd.
 - 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
 - 3. Service Temperature: Minus 40 to plus 200 deg F.
- G. Outdoor System, Flexible Connector Fabric: Glass fabric double-coated with weatherproof, synthetic rubber resistant to UV rays and ozone.
 - 1. Minimum Weight: 24 oz/sq. yd.
 - 2. Tensile Strength: 530 lbf/inch in the warp and 440 lbf/inch in the filling.
 - 3. Service Temperature: Minus 50 to plus 250 deg F.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

H. Thrust Limiters:

- 1. Field fabricated cable restraints on equipment producing greater than 4.0" WC of positive pressure.
- 2. Field fabricated cable restraints as detailed. If not detailed; Provide restraint consisting of a 1/16 inch diameter vinyl coated steel cable at 24" maximum on center, attached to flange bolts on each side of flexible connector. Cable length shall be such that, when in tension, ½" of movement in the flexible connection is preserved. If flanges are not used, contractor may provide steel, stainless steel, or aluminum angles for attaching cables. Match duct material. Cables shall attach to screw or fastener holding angle to duct and shall be routed through a 3/16" diameter hole in the bracket offset approximately 1" from duct.
- 3. Direction of connector movement: Parallel with airflow, perpendicular to connector.

2.6 ACCESSORY HARDWARE

- A. Temporary Test Holes: Drilled in duct as required.
- B. Permanent Test Holes: Cast iron, or cast aluminum, to suit adjacent material, including cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit wall + insulation thickness.
- C. Adhesives: High strength, quick setting, waterproof, and resistant to grease.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards Metal and Flexible."
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.
- C. Install backdraft dampers at inlet of exhaust fans, exhaust ducts as close as possible to louver inlets, and where indicated.
- D. Install fire dampers where indicated according to UL listing and manufacturer's written instructions.
- E. Connect ducts to duct silencers with flexible duct connectors.
- F. Turning Vanes:
 - 1. Install turning vanes in all duct elbows larger than 12" in height or width.
 - 2. Exceptions:
 - a. Where prohibited by the applicable code, laws, ordinances or local requirements.
 - b. Where specifically eliminated by Contract.

G. Flexible Connectors

1. Install flexible connectors to connect ducts to equipment- except smoke control/management equipment.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2. Where required, install thrust limiters at all flexible connectors consisting of a 1/16-inch diameter vinyl coated steel cable at 24" maximum on center, attached to flange bolts on each side of flexible connector. Cable length shall be such that, when in tension, 1/2" of movement in the flexible connection is preserved. If flanges are not used, provide steel, stainless steel, or aluminum angles for attaching cables. Match angle material to duct material. Cables shall attach to screw or fastener holding angle and shall be routed through a 3/16" diameter hole in the angle offset approximately 1" from duct.

3.2 TESTING AND BALANCING

- A. Install permanent test holes at fan inlets and outlets within 6 inches of fan, where indicated, and where necessary for testing and balancing. Test holes not required at outlet of roof-mounted fans.
- B. Install temporary test hole plugs in temporary test holes. Repair insulation at temporary test holes.

3.3 FIELD QUALITY CONTROL

- A. Tests and Inspections:
 - 1. Operate dampers to verify full range of movement without interference.
 - 2. Inspect access doors. Verify that door can be opened and closed. Verify fire damper, and combination fire and smoke damper fusible links can be reset and changed. Verify fire damper, and combination fire and smoke damper doors open in the direction of air pressure (out on supply ducts and in on return and exhaust ducts).
 - 3. Operate fire, smoke, and combination fire and smoke dampers to verify full range of movement, verify non-interference, and verify that the proper heat-response device is installed.
 - 4. Inspect elbows for turning vanes. Verify they are installed where required.
 - 5. Inspect turning vanes using access doors for proper and secure installation.
 - 6. Operate remote damper operators prior to ceiling installation to verify full range of movement of operator and damper. Verify no interference with damper movement.

END OF SECTION 233300

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 233423 - HVAC POWER VENTILATORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

- A. Product Data: Provide manufacturer's technical data for each ventilator including rated capacities, dimensions, required clearances, operating characteristics, mounting requirements, and furnished specialties and accessories. Provide power and control wiring diagrams. Also include the following:
 - 1. Certified fan performance curves with system operating conditions indicated.
 - 2. Certified fan sound-power ratings.
 - 3. Motor ratings and electrical characteristics, plus motor and electrical accessories.
 - 4. Material thickness and finishes, including color charts.
 - 5. Dampers, including housings, linkages, and operators.
 - 6. Roof curbs with required slope and dimensions. Indicate shimming if required.
 - 7. Fan speed controllers.
- B. Operation and Maintenance Data: For ventilators to include in emergency, operation, and maintenance manuals.

1.3 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. AMCA Compliance: Fans shall have AMCA-Certified performance ratings and shall bear the AMCA-Certified Ratings Seal.
- C. UL Standards: Power ventilators shall comply with UL 705. Power ventilators for use for grease (kitchen) hood exhaust shall also comply with UL 762.

1.4 COORDINATION

- A. Coordinate size and location of structural-steel support members.
- B. Coordinate sizes and locations of roof curbs, equipment supports, and roof penetrations with actual equipment provided.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.5 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Belts: One set for each belt-driven fan. Mark belt set with fan ID and turn over to owner's representative.

PART 2 - PRODUCTS

2.1 CENTRIFUGAL ROOF VENTILATOR(S) (DOWNBLAST)

A. Manufacturers:

- 1. Acme Engineering & Manufacturing Corporation.
- 2. Twin City Fan & Blower.
- 3. Greenheck Fan Corporation.
- 4. Loren Cook Company.
- B. Housing: Removable, spun-aluminum dome top and outlet baffle, or extruded-aluminum, rectangular top to direct discharge air downward.
- C. Base (Curb Cap): Square, one-piece, aluminum with venturi inlet cone.
- D. Hinged Sub-Base: Galvanized steel hinged arrangement permitting service and maintenance.
- E. Fan Wheels: Statically and dynamically balanced aluminum hub and wheel with backward-inclined blades matched to inlet cone.
- F. Belt Drives (where indicated in Fan Schedule): Comply with the following:
 - 1. Provide drives sized for a minimum of 150% of driven horsepower.
 - 2. Provide resilient mounting to housing.
 - 3. Fan Shaft: Turned, ground, and polished steel; keyed to wheel hub.
 - 4. Shaft Bearings: Permanently lubricated, permanently sealed, self-aligning ball bearings.
 - 5. Pulleys: Cast-iron, adjustable-pitch motor pulley.
 - 6. Fan and motor isolated from exhaust airstream
 - 7. Belt(s): Provide grip notch belt(s). Provide belt tensioner.
 - 8. Motors and drives:
 - a. Mount on vibration isolators.
 - b. Draw air for motor cooling into the motor compartment from an area free of discharge contaminants.
 - c. Make readily accessible for maintenance.
- G. Electrically-Commutated Motor (where direct drive indicated in Fan Schedule):
 - 1. Motor enclosure: Open type.
 - 2. Motor shall be DC electronic commutation type motor (ECM).

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Motor shall be permanently lubricated, heavy duty ball bearing type to match with the fan load and prewired to the specific voltage and phase.
- 4. Internal motor circuitry to convert AC power supplied to fan to DC power to operate motor.
- 5. Motor shall be speed controllable down to 20% of full speed. Speed shall be controlled by either a potentiometer dial mounted at the motor or by a 0-10 VDC signal.

H. Overload (Running) Protection:

- 1. Provide motor overload protection as a requirement of this section.
- 2. Provide motor overload protection as recommended by the manufacturer
- 3. Comply with the Section 230513 "Motors for HVAC Equipment"
- I. Wind-band: Join to curb-cap with leak-proof continuously welded seam.

J. Accessories:

- 1. Provide disconnect switch.
- 2. Provide removable, 1/2-inch mesh, aluminum or brass wire bird screen.
- 3. Provide parallel-blade dampers mounted in fan base or duct with normally closed electric actuator wired to close when fan stops. Actuator shall not be required to fail closed.
- 4. Motorized Backdraft Damper(s): Provide damper(s) with electric actuator(s) wired to close when fan stops and open with fan is on. Actuator voltage shall match fan motor voltage. Where matching actuator and fan voltage is not possible, fan manufacturer shall provide transformer to produce compatible voltage to actuator. Wiring of fan and backdraft damper actuator(s) shall be by Division 26.
- 5. Provide roof curb. Refer to Roof Curb Paragraph below.

2.2 MOTORS

- A. Refer to section "Common Motor Requirements for HVAC Equipment."
- B. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors.
 - 1. Motor Sizes: Size shall be as indicated. If not indicated, provide motor large enough to drive load and avoid operation in service factor range above 1.0.
 - 2. Controls: Provide controllers, electrical devices, and wiring to comply with requirements specified in Division 26 Sections.
- C. Enclosure Type: Totally enclosed, fan cooled.

2.3 SOURCE QUALITY CONTROL

A. Certify fan performance ratings, including flow rate, pressure, power, air density, speed of rotation, and efficiency by factory tests according to AMCA 210, "Laboratory Methods of Testing Fans for Aerodynamic Performance Rating." Label fans with the AMCA-Certified Ratings Seal.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install HVAC Power Ventilators level and plumb.
- B. Support suspended units from structure using threaded steel rods and elastomeric hangers having a static deflection of 0.5 inches.
- C. Install units with clearances for service and maintenance.
- D. Label units.

3.2 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

B. Tests and Inspections:

- 1. Verify that Shipping blocking and bracing are removed.
- 2. Verify that unit is secure and connections to ducts and electrical components are complete. Verify that proper thermal-overload protection is installed in motors, starters, and disconnect switches.
- 3. Verify that cleaning and adjusting are complete.
- 4. For belt drive units disconnect fan drive from motor, verify proper motor rotation direction, and verify fan wheel free rotation and smooth bearing operation. Reconnect fan drive system, align belts, adjust belt tension, and install belt guards.
- 5. Adjust damper linkages & operators for proper damper operation.
- 6. Verify lubrication for bearings and other moving parts.
- 7. Verify that manual and automatic volume control, fire, smoke, and fire/smoke dampers in connected ductwork systems are in a fully open position.
- 8. Disable automatic temperature-control operators, energize motor and adjust fan to indicated rpm.
- 9. Measure and record motor voltage and amperage.
- 10. Shut unit down and reconnect automatic temperature-control operators.
- 11. Remove and replace malfunctioning units and retest as specified above.
- C. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Prepare test and inspection reports.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.3 TESTING, ADJUSTING, BALANCING, AND LUBRICATION

- A. Adjust damper linkages for proper damper operation.
- B. Comply with requirements in Section "Testing, Adjusting, and Balancing for HVAC".
- C. Replace fan and motor pulleys to achieve design airflow.
 - 1. Disable automatic temperature-control operators, energize motor and adjust fan to required rpm.
 - 2. Measure and record RPM.
 - 3. Measure and record motor voltage and amperage.
- D. Re-lubricate bearings.

END OF SECTION 233423

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 233713 - DIFFUSERS, REGISTERS, AND GRILLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated, include the following:
 - 1. Data Sheet: Indicate materials of construction, finish, mounting details, and performance data including throw, drop, static pressure drop, and noise ratings.
 - 2. Diffuser, Register, and Grille Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.

PART 2 - PRODUCTS

2.1 DIFFUSERS, GRILLES, AND REGISTERS

A. Manufacturers:

- 1. Anemostat.
- 2. Carnes.
- 3. Krueger.
- 4. MetalAire, Inc.
- 5. Nailor Industries.
- 6. Price Industries.
- 7. Titus.
- 8. Tuttle & Bailey.

B. General:

- 1. All trim pieces shall be mechanically fastened. Friction fit trim rings/frames shall not be provided or shall be mechanically fastened in the field. Fasteners shall not be visible.
- 2. Finish:
 - a. Powder-coated or baked enamel, white, unless noted otherwise.
- 3. Filter Grille Mounting Frame: Shall accept a 2" deep MERV 8 (30%) pleated media filter. Refer to Section "Particulate Air Filtration" for filter requirements. Provide two sets of filters for each filter grille.
- 4. Mounting: As indicated in schedule or match condition indicated.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

C. Linear Slot Diffuser Plenums

- 1. Linear slot diffuser plenums shall be fully insulated. Provide one of the following:
 - a. Factory-installed, internal fiberglass insulation on sides and end caps.
 - b. Factory-installed, external aluminum foil-backed insulation.
 - c. Field-installed external insulation on plenums not factory-insulated. Refer to Section 230700 HVAC Insulation.

D. Ceiling Diffusers

- 1. Ceiling diffuser backpans shall be externally insulated. Provide one of the following:
 - a. Factory-installed with foil/scrim vapor barrier insulation with a minimum R-value of 6.
 - b. Field-installed external insulation on backpans not factory-insulated. Refer to Section 230700 HVAC Insulation.
- 2. For diffusers connected to flexible duct, provide one of the following:
 - a. Diffuser manufacturer's optional extended depth, beaded inlet neck.
 - b. Field-provided 4" long galvanized steel duct collar with diameter matching diffuser inlet. Attach to diffuser inlet with a minimum of four sheet metal screws evenly distributed around collar.

2.2 SOURCE QUALITY CONTROL

A. Verification of Performance: Rate diffusers, registers, and grilles according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas where diffusers, registers, and grilles are to be installed for installation tolerances and other conditions affecting performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install diffusers, registers, and grilles level and plumb.
- B. Install diffusers, registers, and grilles flush with ceiling unless otherwise indicated.
- C. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Install in

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

locations indicated as much as practical. For units installed in lay-in ceiling panels, center units in both directions in panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.

- D. Linear Slot Diffuser Installation: Adjust each slot diffuser so half the slots throw horizontally along the ceiling in each direction unless indicated otherwise. For linear slot diffusers above windows at building perimeter, one half of the total slots at each diffuser shall be adjusted to throw air vertically downward to wash window, and the other half of the slots shall be adjusted to throw air horizontally across ceiling unless indicated otherwise.
- E. Diffusers, registers and grilles shall be supported independently of the ceiling system and shall not be supported from conduit, piping or unrelated ductwork.
- F. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance.

3.3 ADJUSTING

A. After installation, adjust diffusers, registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION 233713

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 234100 - PARTICULATE AIR FILTRATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 DEFINITIONS

A. Construction Filter: A filter maintained during construction to protect ductwork from construction dust, dirt, and debris. Construction filters shall be removed temporarily during balancing and permanently after the building is occupied.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated include dimensions, required operating clearances, required access clearances, and weights.
- B. Operating Characteristics: For each type of product indicated provide rated flow capacity, initial and final pressure drop at rated flow capacity.
- C. Efficiency: For each type of product indicated efficiency/MERV rating and test method.
- D. Fire Classification: For each type of product indicated provide the fire classification.
- E. Specialties and Accessories: For each type of product indicated provide furnished specialties and accessories.

F. LEED Submittals:

1. Product Data: Documentation indicating MERV rating, location, and airstream served by each filter type.

1.4 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For each type of filter and rack to include in emergency, operation, and maintenance manuals.
- B. Replace all permanent filters with new filters of types specified.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. ASHRAE Compliance:
 - 1. Comply with applicable requirements in ASHRAE 62.1, Section 4 "Outdoor Air Quality"; Section 5 "Systems and Equipment"; and Section 7 "Construction and Startup."
 - 2. Comply with ASHRAE 52.1 for arrestance and ASHRAE 52.2 for MERV for methods of testing and rating air-filter units.
- C. Comply with NFPA 90A and NFPA 90B.

1.6 COORDINATION

- A. Coordinate sizes and locations:
 - 1. Within air handling units.
 - 2. On open return ducts during construction.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers:
 - 1. Air Filters, and Filter-Holding Systems:
 - a. 3M.
 - b. Airguard.
 - c. American Air Filter Company, Inc. Flanders.
 - d. Camfil USA.
 - e. Columbus Industries, Inc.
 - f. Koch Filter Corp.
 - 2. Filter Gages:
 - a. Airguard Industries, Inc.
 - b. Dwyer Instruments Inc.

2.2 GENERAL FILTERS

- A. For return filter grilles, general filtration, and construction filters provide the following:
 - 1. Media: Cotton and synthetic pleated with an average efficiency of 25-30% and an average arrestance of 90-92% in accordance with ASHRAE test standard 52.1-1992.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Thickness: Unless otherwise indicated thickness shall be 2".
- 3. Media Support Grid: Welded wire on 1" centers with 96% free area bonded to the media.
- 4. Filter Frame: High wet strength cardboard with diagonal support members bonded to the media on the entering side and exiting side of each pleat.
- 5. Holding Frame: Galvanized steel with metal grid on outlet side, polyurethane gaskets, and spring fasteners.
- 6. Farr 30/30 or equal.

2.3 PRE-FILTERS

- A. Where pre-filters are indicated and for construction filters provide the following:
 - 1. Media: Cotton and synthetic pleated with an average efficiency of 25-30% and an average arrestance of 90-92% in accordance with ASHRAE test standard 52.1-1992.
 - 2. Thickness: Unless otherwise indicated thickness shall be 4".
 - 3. Media Support Grid: Welded wire on 1" centers with 96% free area bonded to the media.
 - 4. Filter Frame: High wet strength cardboard with diagonal support members bonded to the media on the entering side and exiting side of each pleat.
 - 5. Holding Frame: Galvanized steel with metal grid on outlet side, polyurethane gaskets, and spring fasteners.
 - 6. Farr 30/30 or equal.

2.4 INSTALLATION

- A. Position each filter with clearance for normal service and maintenance.
- B. Install filters to prevent passage of unfiltered air.
- C. Do not operate fan system until filters are in place. During construction, all ductwork must be protected from dirt and debris. Remove filters used during construction and testing. Replace all filters in units with new filters of types specified.
- D. Unit operation during construction:
 - 1. Install minimum MERV 8 construction filters to protect all return ductwork from dirt and debris. Supply fan shall operate at all times.
- E. Unit not operating during construction:
 - 1. Install plastic sheet material over all supply and return openings to protect all ductwork from dirt and debris.
 - 2. Fans shall be off.
- F. Construction filter installation: Adhere all edges of filter with metal foil peel-n-stick tape having an acrylic adhesive.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.5 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
 - 1. Check for leakage of unfiltered air while system is operating.
- B. Air filter and installation will be considered defective if they do not pass.
- C. Prepare a report for each filter.

2.6 TESTING AND BALANCING

A. Immediately prior to testing and balancing, install new filters of the same type that shall be permanently installed.

END OF SECTION 234100

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 238113 - WALL MOUNTED HEAT PUMPS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Provisions of the Contract and of the Contract Documents apply to this Section.

1.2 SUMMARY

- A. Section includes wall mounted heat pumps and their accessories and controls, in the following configurations:
 - 1. Wall mounted heat pump units.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include rated capacities, operating characteristics, furnished specialties, electrical characteristics, and accessories.
- B. Shop Drawings: For wall mounted heat pumps, include plans, elevations, sections, details for wall penetrations, and attachments to other work.
 - 1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 2. Wiring Diagrams: For power, signal, and control wiring.
- C. Color Samples: For unit cabinet, discharge grille, and exterior louver, and for each color and texture specified.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: Based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified testing agency for wall mounted heat pumps.
- B. Field quality-control reports.
- C. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For wall mounted heat pumps to include in emergency, operation, and maintenance manuals.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.6 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 4 "Outdoor Air Quality," Section 5 "Systems and Equipment," Section 6 "Ventilation Rate Procedures," and Section 7 "Construction and Startup."
- C. ASHRAE/IESNA Compliance: Applicable requirements in ASHRAE/IESNA 90.1.
- D. Certified to AHRI Standard 390-2003 for SPVU (Single Package Vertical Units).

1.7 COORDINATION

A. Coordinate layout and installation of wall mounted heat pumps and wall construction with other construction that penetrates walls or is supported by them.

1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of wall mounted heat pumps that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period for Sealed Refrigeration System: Manufacturer's standard, but not less than five years from date of Substantial Completion, including components and labor.
 - 2. Warranty Period for Nonsealed System Parts: Manufacturer's standard, but not less than five years from date of Substantial Completion, including only components and excluding labor.
 - 3. Warranty Period for Heat Exchangers: Manufacturer's standard, but not less than five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturer:
 - 1. Bard.
 - 2. Marvair.

2.2 MANUFACTURED UNITS

A. Description: Factory-assembled and -tested, self-contained, wall mounted heat pump with weatherproof casing, direct expansion heat pump with 2 stage scroll compressor.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.3 CHASSIS

- A. Cabinet: 20 gauge thick steel weatherproof panels. Unit base of 16-gauge galvanized steel. Cooling section shall be insulated with 1" thick fiberglass insulation.
 - 1. Mounting: Wall with full length side mounting brackets integral to the cabinet.
 - 2. Opening shall be provided for power connections.
 - 3. Access openings appropriate for fans, compressors, and for removing other internal components.
 - 4. Separate access door for changing filters.
- B. Refrigeration System: Direct-expansion indoor coil with capillary restrictor; and hermetically sealed scroll compressor with vibration isolation and overload protection.
 - 1. Refrigeration circuit equipped with factory installed high and low pressure controls and liquid line filter dryer.
 - 2. 2 Stage scroll compressor with 2 stages of cooling and heating.
 - 3. Compressor shall be double isolated floating mounting system with sound blanket and discharge muffler.
 - 4. Evaporator Fan: Direct drive with a ECM (electrically commutated motor) motor.
 - 5. Charge: R-410A.

C. Hot Gas Reheat:

- 1. Refrigeration circuit equipped with factory installed hot gas reheat circuit for dehumidification.
- D. Filters: MERV 8 fiberglass pleated filters.
- E. Condensate Drain: Manufacturer's standard drain pan to direct condensate to drain connection.
- F. Heating
 - 1. Electric-Resistance Heating Coil: Nickel-chromium-wire, electric-resistance heating elements with contactor and high-temperature-limit switch.
- G. Energy Recovery Ventilator (ERV):
 - 1. Shall consist of rotary wheel and insulated cassette frame with seals, drive motor and belt.
 - 2. ERV assembly complete with intake and exhaust blowers.
 - 3. Total energy wheel coated with silica gel desiccant permanently bonded without the use of binders or adhesives.
 - 4. Washable with detergent or alkaline coil cleaner and water.
 - 5. All diameter and perimeter seals shall be provided as part of the cassette assembly and shall be factory set.
 - 6. Certified in accordance with AHSRAE Standard 84 and ARI Standard 1060.
 - 7. Unit shall comply with ANSI/ASHRAE 62.1.
- H. Disconnect Switch: Power disconnect switch in sub-base.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.4 CONTROLS

- A. Control Module: Unit-mounted control for heating, cooling, and fan operation with wall mounted thermostat. Include the following features:
 - 1. Low Ambient Lockout Control: Prevents cooling-cycle operation below 40 deg F outdoor air temperature.
 - 2. Heat-Pump Ambient Control: Field-adjustable switch changes to heat-pump heating operation above 40 deg F and to supplemental heating below plus 25 deg F.
 - 3. Temperature-Limit Control: Prevents occupant from exceeding preset setback or setup temperature.
 - 4. Reverse-Cycle Defrost: Solid-state sensor monitors frost buildup on outdoor coil and reverses unit to melt frost.
- B. Wired Thermostat: Low-voltage adjustable thermostat with two stages of heat, two stages of cooling, humidity control, remote outdoor thermostat, with auto-changeover.

2.5 SOURCE QUALITY CONTROL

A. Unit Performance Ratings: Factory test to comply with AHRI Standard 390-2003 Single Package Vertical Units.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install units level and plumb, maintaining manufacturer's recommended clearances and tolerances.
- B. Install wall sleeves in finished wall assembly; seal and weatherproof. Joint-sealant materials and applications are specified in Section 079200 "Joint Sealants."

3.2 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

B. Tests and Inspections:

- 1. Inspect for and remove shipping bolts, blocks, and tie-down straps.
- 2. After installing wall mounted heat pumps and after electrical circuitry has been energized, test for compliance with requirements.
- 3. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- C. Wall mounted heat pumps will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

3.3 STARTUP SERVICE

- A. Perform startup service.
- B. After installation, verify the following:
 - 1. Unit is level on base and is flashed in exterior wall.
 - 2. Unit casing has no visible damage.
 - 3. Compressor, air-cooled condenser coil, and fans have no visible damage.
 - 4. Labels are clearly visible.
 - 5. Controls are connected and operable.
 - 6. Shipping bolts, blocks, and tie-down straps are removed.
 - 7. Filters are installed and clean.
 - 8. Drain pan and drain line are installed correctly.
 - 9. Electrical wiring installation complies with manufacturer's submittal and installation requirements in electrical Sections.
 - 10. Installation. Perform startup checks according to manufacturer's written instructions, including the following:
 - a. Lubricate bearings on fan.
 - b. Check fan-wheel rotation for correct direction without vibration and binding.
- C. After startup service and performance test, change filters.

3.4 ADJUSTING

- A. Adjust initial temperature set points.
- B. Set field-adjustable switches and circuit-breaker trip ranges as indicated.

3.5 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain wall mounted heat pumps.

END OF SECTION 238113

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 238239 - UNIT HEATERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. The drawings and general provisions of the Contract Documents apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Propeller unit heaters with hot water heating coils.
 - 2. Wall heaters with propeller fans and electric-resistance heating coils.

1.3 DEFINITIONS

- A. CWP: Cold working pressure.
- B. PTFE: Polytetrafluoroethylene plastic.
- C. TFE: Tetrafluoroethylene plastic.

1.4 SUBMITTALS

- A. Product Data: Include rated capacities, operating characteristics, furnished specialties, and accessories for each product indicated.
- B. Samples for Initial Selection: Finish colors for units with factory-applied color finishes.
- C. Samples for Verification: Finish colors for each type of cabinet unit heater and wall and ceiling heaters indicated with factory-applied color finishes.
- D. Operation and Maintenance Data: For cabinet unit heaters to include in emergency, operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1-2007, Section 5 "Systems and Equipment" and Section 7 "Construction and Startup."

UNIT HEATERS 238239 - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

C. ASHRAE/IESNA 90.1-2007 Compliance: Applicable requirements in ASHRAE/IESNA 90.1-2007, Section 6 - "Heating, Ventilating, and Air-Conditioning."

PART 2 - PRODUCTS

2.1 PROPELLER UNIT HEATERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Airtherm; a Mestek Company.
 - 2. Carrier Corp.
 - 3. Daikin Applied (McQuay International)
 - 4. Dunham-Bush, Inc.
 - 5. Engineered Air.
 - 6. International Environmental Corp.
 - 7. Ruffneck Heaters, Starozik Industries Ltd.
 - 8. Trane
 - 9. USA Coil & Air Inc.
- B. Description: An assembly including casing, coil, fan, and motor in horizontal discharge configuration with adjustable discharge louvers.
- C. Comply with UL 2021.
- D. Cabinet: Removable panels for maintenance access to controls.
- E. Cabinet Finish: Manufacturer's standard baked enamel applied to factory-assembled and -tested propeller unit heater before shipping.
- F. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1-2007.
- G. Discharge Louver: Adjustable fin diffuser for horizontal units and conical diffuser for vertical units.
- H. Electric-Resistance Heating Coil: Nickel-chromium heating wire, free from expansion noise and hum, embedded in magnesium oxide refractory and sealed in corrosion-resistant metallic sheath. Terminate elements in stainless-steel, machine-staked terminals secured with stainless-steel hardware, and limit controls for high temperature protection. Provide integral circuit breaker for overcurrent protection.
- I. Fan: Propeller type with aluminum wheel directly mounted on motor shaft in the fan venturi.
- J. Fan Motors: Comply with requirements in Division 23 Section "Common Motor Requirements for HVAC Equipment."
 - 1. Motor Type: Permanently lubricated, multispeed.

UNIT HEATERS 238239 - 2

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

K. Control Devices:

- 1. Unit-mounted, fan-speed switch.
- 2. Unit-mounted thermostat.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas to receive unit heaters for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Examine roughing-in for electrical connections to verify actual locations before unit heater installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install propeller unit heaters level and plumb.
- B. Suspend propeller unit heaters from structure with all-thread hanger rods and elastomeric hangers. Hanger rods and attachments to structure are specified in Division 23 Section "Hangers and Supports for HVAC Piping and Equipment." Vibration hangers are specified in Division 23 Section "Vibration and Seismic Controls for HVAC Piping and Equipment."

3.3 CONNECTIONS

- A. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- B. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

3.4 FIELD QUALITY CONTROL

- A. Perform the following field tests and inspections and prepare test reports:
 - 1. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
 - 2. Operate electric heating elements through each stage to verify proper operation and electrical connections.
 - 3. Test and adjust controls and safety devices. Replace damaged and malfunctioning controls and equipment.
- B. Remove and replace malfunctioning units and retest as specified above.

UNIT HEATERS 238239 - 3

MAYO HIGH SCHOOL – TOILET RENOVATION DARLINGTON, SOUTH CAROLINA DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

ADJUSTING 3.5

Adjust initial temperature set points. A.

END OF SECTION 238239

UNIT HEATERS 238239 - 4

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 260500 - COMMON WORK RESULTS FOR ELECTRICAL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Electrical equipment coordination and installation.
- 2. Sleeves for raceways and cables.
- 3. Sleeve seals.
- 4. Grout.
- 5. Common electrical installation requirements.

1.3 SUBMITTALS

A. Provide drawings depicting the layout of each electrical room, electrical closet, security electronics room or any other similar space in which electrical equipment will be installed using a minimum scale of 1/2"=1'-0'. The drawings shall use the dimensions of the actual equipment being supplied for the project and shall include all NEC working clearances around the equipment. Drawings shall also include any the work of any other trade that will performing work in the space. Rough in may not begin until the submittal is approved by the engineer.

1.4 COORDINATION

- A. Coordinate arrangement, mounting, and support of electrical equipment:
 - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
 - 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
 - 3. To allow right of way for piping and conduit installed at required slope.
 - 4. So connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
- B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- C. Coordinate location of access panels and doors for electrical items that are behind finished surfaces or otherwise concealed.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.5 QUALITY ASSURANCE

A. Third party agencies shall be amongst those accredited by the NCBCC (North Carolina Building Code Council) to Label Electrical & Mechanical Equipment".

PART 2 - PRODUCTS

2.1 SLEEVES FOR RACEWAYS AND CABLES

- A. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Sleeves for Rectangular Openings: Galvanized sheet steel.
 - 1. Minimum Metal Thickness:
 - a. For sleeve cross-section rectangle perimeter less than 50 inches (1270 mm) and no side more than 16 inches (400 mm), thickness shall be 0.052 inch (1.3 mm).
 - b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches (1270 mm) and 1 or more sides equal to, or more than, 16 inches (400 mm), thickness shall be 0.138 inch (3.5 mm).

2.2 SLEEVE SEALS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Metraflex Co.
 - d. Pipeline Seal and Insulator, Inc.
 - 2. Sealing Elements: NBR interlocking links shaped to fit surface of cable or conduit. Include type and number required for material and size of raceway or cable.
 - 3. Pressure Plates: Plastic. Include two for each sealing element.
 - 4. Connecting Bolts and Nuts: Carbon steel with corrosion-resistant coating of length required to secure pressure plates to sealing elements. Include one for each sealing element.

2.3 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.4 SECURITY FASTENERS:

- A. Description: Accessories, anchorage inserts, and security fasteners providing a complete tamperproof installation.
- B. Exposed Security Fasteners:
 - 1. Fastener: Provide <u>torx-head</u> (star with center reject pin) security fasteners for anchoring work in exposed security areas.
 - 2. Finish: Finish shall match that specified of the item anchored.
 - 3. Tools: Provide tools for fastening devices.

PART 3 - EXECUTION

3.1 COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION

- A. Comply with NECA 1-2006. Mounting heights indicated in contract documents supersede NECA 1.
- B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- D. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electrical equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- E. Right of Way: Give to piping systems installed at a required slope.

3.2 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Electrical penetrations occur when raceways, cables, wireways, cable trays, or busways penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- E. Cut sleeves to length for mounting flush with both surfaces of walls.
- F. Extend sleeves installed in floors 2 inches (50 mm) above finished floor level.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- G. Size pipe sleeves to provide 1/4-inch (6.4-mm) annular clear space between sleeve and raceway or cable, unless indicated otherwise.
- H. Seal space outside of sleeves with grout for penetrations of concrete and masonry
 - 1. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
- I. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint.
- J. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials.
- K. Aboveground, Exterior-Wall Penetrations: Seal penetrations using steel pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch (25-mm) annular clear space between pipe and sleeve for installing mechanical sleeve seals.

3.3 SLEEVE-SEAL INSTALLATION

- A. Install to seal exterior wall penetrations.
- B. Use type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

3.4 FIRESTOPPING

A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for electrical installations to restore original fire-resistance rating of assembly.

3.5 SECURITY FASTENERS

A. All fasteners exposed in security areas shall be security fasteners. Where standard fasteners on manufactured devices and equipment are accessible, they shall be replaced with security fasteners.

END OF SECTION 260500

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Building wires and cables rated 600 V and less.
 - 2. Connectors, splices, and terminations rated 600 V and less.

1.3 DEFINITIONS

- A. RACEWAY: An enclosed channel of metal or nonmetallic materials designed expressly for holding wires or cables. Raceways include, but are not limited to, rigid metal conduit, rigid nonmetallic conduit, intermediate metal conduit, liquidtight flexible conduit, flexible metallic tubing, flexible metal conduit, electrical nonmetallic tubing, and electrical metallic tubing.
 - 1. Cables such as MC, AC, or Greenfield are NOT raceways.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 CONDUCTORS AND CABLES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Cerro Wire LLC.
 - 2. General Cable; General Cable Corporation.
 - 3. Southwire Company.
 - 4. Encore Wiring Corporation.
- B. Copper Conductors: Comply with NEMA WC 70/ICEA S-95-658.
- C. Conductor Insulation: Comply with NEMA WC 70/ICEA S-95-658 for Type THHN-2-THWN-2.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

D. Multiconductor Cable:

- 1. Shall only be allowed where specially indicated on the drawings.
- 2. Comply with NEMA WC 70/ICEA S-95-658 for metal-clad cable, Type MC with ground wire

2.2 CONNECTORS AND SPLICES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. 3M.
 - 2. Hubbell Power Systems, Inc.
 - 3. ILSCO.
 - 4. Tyco Electronics Corp.
- B. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

2.3 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.

PART 3 - EXECUTION

3.1 CONDUCTOR MATERIAL APPLICATIONS

- A. Feeders: Cooper unless Aluminum specifically indicated on the drawings
 - 1. When aluminum feeders are allowed, provide Copper for feeders smaller than No. 4 AWG; copper or aluminum for feeders No. 4 AWG and larger. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- B. Branch Circuits: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.

3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

- A. Service Entrance: Type THHN-2-THWN-2, conductors in raceway or Type XHHW-2, single conductors in raceway. Type SE or Type USE multiconductor cable are not allowed.
- B. Exposed Feeders: Type THHN-2-THWN-2, conductors in raceway.
- C. Feeders Concealed in Ceilings, Walls, Partitions, and Crawlspaces: Type THHN-2-THWN-2, conductors in raceway.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. Feeders Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN-2-THWN-2 conductors in raceway.
- E. Exposed Branch Circuits, Including in Crawlspaces: Type THHN-2-THWN-2, conductors in raceway
- F. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN-2-THWN-2, conductors in raceway.
- G. Branch Circuits Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN-2-THWN-2, conductors in raceway, Type XHHW-2, conductors in raceway.
- H. Feeders and Branch Circuits are not permitted to be installed in Cable Tray

3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Conceal cables in finished walls, ceilings, and floors unless otherwise indicated.
- B. Complete raceway installation between conductor and cable termination points according to Section 260533 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.
- C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- F. Branch Circuits Concealed in Casework: MC cable may be used to feed to outlet boxes fish concealed in built-in casework. Route cable supported tight in upper inside corners of casework, not in conflict with drawers or cabinet doors.
- G. Branch Circuits Concealed Existing to Remain Drywall Partitions: MC cable may be used to feed to outlet boxes fish concealed in the drywall partition. Convert to conduit and conductor with 3' of exiting the partition.
- H. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."
- I. Whips from Junction Box Concealed in Ceilings to Lighting Fixtures:
 - 1. Type MC Cable or FMC, with minimum #12AWG copper THHN/THWN and full size equipment grounding conductor. Maximum whip length 72".
 - 2. MC Cable and FMC shall be supported within 24" of fixture connection so that whip is not in contact with ceiling or grid. Securing to <u>fixture support wires</u> with batwings is acceptable but not to ceiling support wires.
 - 3. Do not connect fixture whips from fixture to fixture (daisy chain). No more than 4 whips shall be connected to any one junction box.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- J. AC cable is not acceptable in any application.
- K. All single-phase circuits shall include a dedicated neutral (grounded) and grounding conductor, unless specifically noted otherwise.
 - 1. The intent of this is to eliminate multiwire branch circuits and allow disconnection of one circuit without requiring disconnection of other(s) as would be required to comply with NEC 210.4(B). Per NEC 310.15(B)(b) each of these neutral (grounded) conductor is not considered to be load-bearing so derating is not required.
- L. Contract drawings are based upon a maximum of 3 current-carrying conductors in a conduit. Contractor may rework indicated circuitry to install a maximum of (6) L-N circuits (120 or 277V) in a single conduit. There shall be no more than 2 each A, B, C phase conductors per homerun. Each shall have dedicated neutral (grounded) conductor.
 - 1. Do not group L-L circuits in a homerun, unless specifically indicated on the drawings.
 - 2. Where there are more than 3 current-carrying conductors in a conduit, derate conductor ampacities in accordance with NEC Table 310.15(B)(2)(a).
 - 3. When running more than 3 ungrounded conductors in a raceway, increase size of conduits beyond those indicated in contract documents, as required to not exceed NEC Chapter 9, Table 1 conduit-fill requirements. As-built drawings shall clearly indicate which circuits are grouped in homeruns.
- M. Unless otherwise indicated, minimum conductor size shall be 12 AWG.

3.4 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torquetightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.
- B. Make splices, terminations, and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
 - 1. Use oxide inhibitor in each splice, termination, and tap for aluminum conductors where permitted.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 12 inches of slack.

3.5 IDENTIFICATION

- A. Identify and color-code conductors and cables according to Section 260553 "Identification for Electrical Systems."
- B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

3.6 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.7 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Section 078413 "Penetration Firestopping."

3.8 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors for compliance with requirements.
 - 2. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
 - 3. Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each splice in conductors No. 3 AWG and larger. Remove box and equipment covers so splices are accessible to portable scanner. Correct deficiencies determined during the scan.
 - a. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each splice 11 months after date of Substantial Completion.
 - Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - c. Record of Infrared Scanning: Prepare a certified report that identifies splices checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
- B. Test and Inspection Reports: Prepare a written report to record the following:
 - 1. Procedures used.
 - 2. Results that comply with requirements.
 - 3. Results that do not comply with requirements and corrective action taken to achieve compliance with requirements.
- C. Cables will be considered defective if they do not pass tests and inspections. Remove and replace malfunctioning cables and retest as specified above.

END OF SECTION 260519

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 260526 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes grounding and bonding systems and equipment.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

1.4 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For grounding to include in emergency, operation, and maintenance manuals.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Burndy; Part of Hubbell Electrical Systems.
 - 2. ERICO International Corporation.
 - 3. Galvan Industries, Inc.; Electrical Products Division, LLC.
 - 4. ILSCO.
 - 5. O-Z/Gedney; an EGS Electrical Group brand; an Emerson Industrial Automation business.

2.2 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70 and marked for intended location and application.
- B. Comply with UL 467 for grounding and bonding materials and equipment.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.3 CONDUCTORS

- A. Insulated Conductors: Copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.
- B. Grounding Electrode Conductors: For the main service and transformers within the building shall be bare stranded copper and shall be sized no smaller than that indicated on the drawings or in the NEC table 250-66.

C. Bare Copper Conductors:

- 1. Solid Conductors: ASTM B 3.
- 2. Stranded Conductors: ASTM B 8.
- 3. Tinned Conductors: ASTM B 33.
- 4. Bonding Cable: 28 kcmil, 14 strands of No. 17 AWG conductor, 1/4 inch in diameter.
- 5. Bonding Conductor: No. 4 or No. 6 AWG, stranded conductor.
- 6. Bonding Jumper: Copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.
- 7. Tinned Bonding Jumper: Tinned-copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.

2.4 CONNECTORS

- A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction for applications in which used and for specific types, sizes, and combinations of conductors and other items connected.
- B. Bolted Connectors for Conductors and Pipes: Copper or copper alloy.
- C. Welded Connectors: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.
- D. Bus-Bar Connectors: Mechanical type, cast silicon bronze, solderless compression-type wire terminals, and long-barrel, two-bolt connection to ground bus bar.

2.5 GROUNDING ELECTRODES

- A. Ground Rods: Copper-clad steel; 3/4 inch by 10 feet.
 - 1. Termination: Factory-attached No. 4/0 AWG bare conductor at least 48 inches long.
 - 2. Backfill Material: Electrode manufacturer's recommended material.

PART 3 - EXECUTION

3.1 APPLICATIONS

A. Conductors: Install solid conductor for No. 8 AWG and smaller, and stranded conductors for No. 6 AWG and larger unless otherwise indicated.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Underground Grounding Conductors: Install bare copper conductor, No. 2/0 AWG minimum. Bury at least 24 inches below grade.
- C. Grounding Bus: Install in electrical equipment rooms, in rooms housing service equipment, teledata rooms and elsewhere as indicated.
- D. Conductor Terminations and Connections:
 - 1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
 - 2. Underground Connections: Welded connectors except at test wells and as otherwise indicated.
 - 3. Connections to Ground Rods at Test Wells: Bolted connectors.
 - 4. Connections to Structural Steel: Welded connectors.

3.2 GROUNDING AT THE SERVICE

A. Equipment grounding conductors and grounding electrode conductors shall be connected to the ground bus. Install a main bonding jumper between the neutral and ground buses.

3.3 GROUNDING SEPARATELY DERIVED SYSTEMS

A. Generator: Install grounding electrode(s) at the generator location. The electrode shall be connected to the equipment grounding conductor and to the frame of the generator.

3.4 EQUIPMENT GROUNDING

- A. Install insulated equipment grounding conductors with all feeders and branch circuits.
- B. Water Heater, Heat-Tracing, and Antifrost Heating Cables: Install a separate insulated equipment grounding conductor to each electric water heater and heat-tracing cable. Bond conductor to heater units, piping, connected equipment, and components.
- C. Metallic Fences:
 - 1. Grounding Conductor: Bare copper, not less than No. 8 AWG.
 - 2. Gates: Shall be bonded to the grounding conductor with a flexible bonding jumper.
 - 3. Barbed Wire: Strands shall be bonded to the grounding conductor.

3.5 INSTALLATION

- A. Grounding Conductors: Route along shortest and straightest paths possible unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.
- B. When provided, Ground Bonding Common with Lightning Protection System: Comply with NFPA 780 and UL 96 when interconnecting with lightning protection system. Bond electrical power system ground directly to lightning protection system grounding conductor at closest

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

point to electrical service grounding electrode. Use bonding conductor sized same as system grounding electrode conductor, and install in conduit.

- C. Ground Rods: Drive rods until tops are 2 inches below finished floor or final grade unless otherwise indicated.
 - 1. Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating if any.
 - 2. For grounding electrode system, install at least three rods spaced at least one-rod length from each other and located at least the same distance from other grounding electrodes, and connect to the service grounding electrode conductor.
- D. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance except where routed through short lengths of conduit.
 - 1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
 - 2. Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install bonding so vibration is not transmitted to rigidly mounted equipment.
 - 3. Use exothermic-welded connectors for outdoor locations; if a disconnect-type connection is required, use a bolted clamp.
- E. Grounding and Bonding for Piping:
 - 1. Metal Water Service Pipe: Install insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes; use a bolted clamp connector or bolt a lug-type connector to a pipe flange by using one of the lug bolts of the flange. Where a dielectric main water fitting is installed, connect grounding conductor on street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
 - 2. Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with a bolted connector.
 - 3. Bond each aboveground portion of gas piping system downstream from equipment shutoff valve.
- F. Grounding for Steel Building Structure: Install a driven ground rod at base of each corner column and at intermediate exterior columns at distances not more than 60 feet apart.

3.6 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Tests and Inspections:
 - 1. After installing grounding system but before permanent electrical circuits have been energized, test for compliance with requirements.
- C. Grounding system will be considered defective if it does not pass tests and inspections.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- D. Prepare test and inspection reports.
- E. Report measured ground resistances that exceed 10 ohms.
- F. Excessive Ground Resistance: If resistance to ground exceeds specified values, notify Architect promptly and include recommendations to reduce ground resistance.

END OF SECTION 260526

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Hangers and supports for electrical equipment and systems.
 - 2. Construction requirements for concrete bases.

1.3 DEFINITIONS

- A. EMT: Electrical metallic tubing.
- B. IMC: Intermediate metal conduit.
- C. RMC: Rigid metal conduit.

1.4 PERFORMANCE REQUIREMENTS

- A. Design supports for multiple raceways capable of supporting combined weight of supported systems and its contents.
- B. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
- C. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed for this Project, with a minimum structural safety factor of five times the applied force.

1.5 QUALITY ASSURANCE

A. Comply with 2005 NFPA 70.

1.6 COORDINATION

A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 2 - PRODUCTS

2.1 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Two Hole Steel Slotted Support Systems: Comply with MFMA-4, factory-fabricated components for field assembly.
 - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Cooper B-Line, Inc.; a division of Cooper Industries.
 - b. ERICO International Corporation.
 - c. Thomas & Betts Corporation.
 - d. Unistrut; an Atkore International company.
 - 2. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
 - 3. Channel Dimensions: Selected for applicable load criteria.
- B. Raceway and Cable Supports: As described in NECA 1 and NECA 101 and as required by NEC except in secure areas, the distance between supports shall be one half that specified by NEC. (twice as many supports as required by NEC).
- C. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- D. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for non-armored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be malleable iron.
- E. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- F. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces shall be tamperproof include the following:
 - 1. Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 - a. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1) Hilti Inc.
 - 2) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
 - 3) MKT Fastening, LLC.
 - 4) Simpson Strong-Tie Co., Inc.; Masterset Fastening Systems Unit.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.
 - a. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1) Cooper B-Line, Inc.; a division of Cooper Industries.
 - 2) Empire Tool and Manufacturing Co., Inc.
 - 3) Hilti Inc.
 - 4) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
 - 5) MKT Fastening, LLC.
- 3. Concrete Inserts: Steel or malleable-iron, slotted support system units similar to MSS Type 18; complying with MFMA-4 or MSS SP-58.
- 4. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.
- 5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
- 6. Toggle Bolts: All-steel springhead type.
- 7. Hanger Rods: Threaded steel.

2.2 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.
- B. Materials: Comply with requirements in Division 05 Section "Metal Fabrications" for steel shapes and plates.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems except if requirements in this Section are stricter.
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMT, IMC, and RMC as required by NFPA 70. Minimum rod size shall be 1/4 inch (6 mm) in diameter.
- C. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
 - 1. Secure raceways and cables to these supports with two-bolt conduit clamps.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.2 SUPPORT INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this Article.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb (90 kg).
- C. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
 - 1. To Wood: Fasten with lag screws or through bolts.
 - 2. To New Concrete: Bolt to concrete inserts.
 - 3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 - 4. To Existing Concrete: Expansion anchor fasteners.
 - 5. To Steel: Beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69.
 - 6. To Light Steel: Sheet metal screws.
 - 7. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate.
- D. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Comply with installation requirements in Division 05 Section "Metal Fabrications" for site-fabricated metal supports.
- B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- C. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 CONCRETE BASES

- A. Construct concrete bases of dimensions indicated but not less than 4 inches larger in both directions than supported unit, and so anchors will be a minimum of 10 bolt diameters from edge of the base.
- B. Use 3000-psi, 28-day compressive-strength concrete. Concrete materials, reinforcement, and placement requirements are specified in Section 033000 "Cast-in-Place Concrete."
- C. Anchor equipment to concrete base.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
- 2. Install anchor bolts to elevations required for proper attachment to supported equipment.
- 3. Install anchor bolts according to anchor-bolt manufacturer's written instructions.

3.5 PAINTING

- A. Touchup: Comply with requirements in Division 09 painting Sections for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 260529

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 260533 - RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 DEFINITIONS

- A. EMT: Electrical metallic tubing.
- B. RGS: Rigid Galvanized Steel conduit.
- C. FMC: Flexible metal conduit.
- D. IMC: Intermediate metal conduit.
- E. LFMC: Liquidtight flexible metal conduit.
- F. LFNC: Liquidtight flexible nonmetallic conduit.
- G. NBR: Acrylonitrile-butadiene rubber.
- H. RNC: Rigid nonmetallic conduit.
- I. ACCESSIBLE: Conduit less than 12' above the finished floor that is capable of being exposed without damaging the building structure or finish or not permanently closed in by the structure or finish of the building. Example: Conduit below 12' AFF that is above a removable ceiling tile is considered "Accessible"
- J. SECURE: Area in which inmates have supervised or non-supervised access on a routine or constant basis. Refer to Architectural drawings for the areas designated as secure. If not clearly defined, the space shall be deemed as secure.
- K. RACEWAY: An enclosed channel of metal or nonmetallic materials designed expressly for holding wires or cables. Raceways include, but are not limited to, rigid metal conduit, rigid nonmetallic conduit, intermediate metal conduit, liquidtight flexible conduit, flexible metallic tubing, flexible metal conduit, electrical nonmetallic tubing, and electrical metallic tubing.
 - 1. Cables such as MC, AC, or Greenfield are NOT raceways.

1.3 ACTION SUBMITTALS

A. Product Data: For surface raceways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 2 - PRODUCTS

2.1 METAL CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Allied Tube & Conduit.
 - 2. O-Z/Gedney; an EGS Electrical Group brand; an Emerson Industrial Automation business.
 - 3. Robroy Industries.
 - 4. Thomas & Betts Corporation.
- B. Listing and Labeling: Metal conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. GRC: Comply with ANSI C80.1 and UL 6.
- D. IMC: Comply with ANSI C80.6 and UL 1242.
- E. PVC-Coated Steel Conduit: PVC-coated rigid steel conduit.
 - 1. Comply with NEMA RN 1.
 - 2. Coating Thickness: 0.040 inch, minimum.
- F. EMT: Comply with ANSI C80.3 and UL 797.
- G. FMC: Comply with UL 1; zinc-coated steel.
- H. LFMC: Flexible steel conduit with PVC jacket and complying with UL 360.
- I. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
 - 1. Fittings for EMT: Steel compression type.
 - 2. Expansion Fittings: PVC or steel to match conduit type, complying with UL 651, rated for environmental conditions where installed, and including flexible external bonding jumper.
 - 3. Coating for Fittings for PVC-Coated Conduit: Minimum thickness of 0.040 inch, with overlapping sleeves protecting threaded joints.
- J. Joint Compound for IMC, GRC, or ARC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

2.2 NONMETALLIC CONDUITS, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. AFC Cable Systems, Inc.
 - 2. Electri-Flex Company.
 - 3. RACO; Hubbell.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Thomas & Betts Corporation.
- B. Listing and Labeling: Nonmetallic conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. RNC: Type EPC-40-PVC, complying with NEMA TC 2 and UL 651 unless otherwise indicated.

2.3 METAL WIREWAYS AND AUXILIARY GUTTERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Cooper B-Line, Inc.; a division of Cooper Industries.
 - 2. Hoffman; a brand of Pentair Equipment Protection.
 - 3. Square D.
- B. Description: Sheet metal, complying with UL 870 and NEMA 250, unless otherwise indicated, and sized according to NFPA 70.
 - 1. Metal wireways installed outdoors shall be listed and labeled NEMA 3R, Flanged-and-gasketed type, and marked for intended location and application.
- C. Fittings and Accessories: Include covers, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- D. Wireway Covers: Screw-cover type unless otherwise indicated.
- E. Finish: Manufacturer's standard enamel finish.

2.4 SURFACE RACEWAYS

- A. Listing and Labeling: Surface raceways shall be listed and labeled as defined in NFPA 70, and marked for intended location and application.
- B. Surface Metal Raceways: Galvanized steel with snap-on covers complying with UL 5. Manufacturer's standard enamel finish in color selected by Architect].
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. MonoSystems, Inc.
 - b. Panduit Corp.
 - c. Wiremold / Legrand.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.5 BOXES, ENCLOSURES, AND CABINETS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. EGS/Appleton Electric.
 - 2. Erickson Electrical Equipment Company.
 - 3. Hoffman; a brand of Pentair Equipment Protection.
 - 4. Hubbell Incorporated.
 - 5. O-Z/Gedney; an EGS Electrical Group brand; an Emerson Industrial Automation business.
 - 6. RACO; Hubbell.
- B. General Requirements for Boxes, Enclosures, and Cabinets: Boxes, enclosures, and cabinets installed in wet locations shall be listed for use in wet locations.
- C. Sheet Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- D. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, ferrous alloy or aluminum, Type FD, with gasketed cover.
- E. Metal Floor Boxes:
 - 1. Material: Cast metal.
 - 2. Shape: Rectangular.
 - 3. Listing and Labeling: Metal floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- F. Luminaire Outlet Boxes: Nonadjustable, designed for attachment of luminaire weighing 50 lb. Outlet boxes designed for attachment of luminaires weighing more than 50 lb shall be listed and marked for the maximum allowable weight.
- G. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- H. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, cast aluminum or galvanized, cast iron with gasketed cover.
- I. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- J. Gangable boxes are not prohibited.

2.6 FLOOR BOXES AND SERVICE FITTINGS

- 1. Floor boxes mounted in grade slabs shall be manufactured from cast-iron and be approved for use on grade and above grade floors.
- 2. Floor boxes not in grade slab shall be manufactured from stamped-steel and be approved for use on above-grade floors.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. All floor boxes shall have four independent wiring compartments that allow capacity for up to four duplex receptacles and/or communication services. The box shall provide two 1" and two 1 1/4" conduit hubs. The box shall be fully adjustable...
- 4. Activation covers shall be available in flanged and flangeless versions of cast aluminum. Covers shall be available with options for tile or carpet inserts, flush covers, or furniture feed. Unless indicated otherwise, provide the following cover configurations:
 - 1) Power/Telecom Outlets: Brushed aluminum flanged with blank lid flush with floor and carpet/tile cutouts.
 - 2) Furniture Floor Feed: Brushed aluminum flanged with 1" trade size screw plug opening and one combination 1 1/4" and 2" trade size screw plug openings.
 - 3) Color and materiel shall be selected by the Architect
 - 4) The activation cover shall be listed by UL to meet the applicable U.S. and Canadian safety standards for scrub water exclusion when used on tile, terrazzo, wood, and carpet covered floors.

2.7 POKE-THRU ASSEMBLIES

- 1. 8" Poke-thru devices provide an interface between power, communication and audio/visual (A/V) cabling in an above grade concrete floor and the workstation or activation location where power, communication and/or A/V device outlets are required. These devices provide recessed device outlets that will not obstruct the floor area.
- 2. Insert: Insert body shall recess the devices a minimum of 2-3/4 inches (69mm) and have a polyester based backing enamel finished interior; ivory color. Furnish with necessary channels to provide complete separation of power and communication services. Provide compartments that allow for up to four duplex receptacles and/or communication ports
- 3. Body consists of an intumescent firestop material to maintain fire rating of the floor slab. Provide insert with a retaining feature to hold the poke-thru device in the floor slab without additional fasteners. Poke-thru insert shall also consist of a 3/4-inch trade size conduit stub that is connected to the insert body and a stamped steel junction box for wire splicing and connections. Stamped steel junction box shall also contain the means necessary to electrically ground the poke-thru device to the system ground
- 4. Activation Cover: Manufactured of die-cast aluminum alloy; finished in powder-coated color selected by the Architect. Provide with gaskets to maintain scrub water tightness. Provide cover with spring-loaded slides to allow cables to egress out of the unit and maintain as small an egress opening as possible.

PART 3 - EXECUTION

3.1 RACEWAY APPLICATION

- A. Outdoors: Apply raceway products as specified below unless otherwise indicated:
 - 1. Exposed Conduit: GRC.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Concealed Conduit, Aboveground: GRC.
- 3. Concealed in Masonry: GRC or NMC grouted solid after installation. Convert to metallic conduit per this specification prior to exiting the wall above ground
- 4. Concealed in Poured Concrete Walls: GRC or NMC. Convert to metallic conduit per this specification prior to exiting the wall above ground
- 5. Underground Conduit: RNC, Type EPC-40-PVC, direct buried.
- 6. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
- 7. Boxes and Enclosures, Aboveground: NEMA 250, Type 3R
- B. Indoors: Apply raceway products as specified below unless otherwise indicated:
 - 1. Exposed, Not Subject to Physical Damage: EMT.
 - 2. Exposed and Subject to Physical Damage: GRC. Raceway locations include the following:
 - a. Loading dock.
 - b. Corridors used for traffic of mechanized carts, forklifts, and pallet-handling units.
 - c. Mechanical rooms.
 - 3. Concealed in Ceilings and Interior Walls and Partitions: EMT.
 - 4. Concealed in Masonry: GRC or NMC grouted solid after installation. Convert to metallic conduit per this specification prior to exiting the wall above ground
 - 5. Concealed in Poured Concrete Walls: GRC or NMC. Convert to metallic conduit per this specification prior to exiting the wall above ground
 - 6. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations.
 - 7. Damp or Wet Locations: GRC.
 - 8. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4 stainless steel in institutional and commercial kitchens and damp or wet locations.
- C. Minimum Raceway Size: 3/4-inch trade size.
- D. Raceway Fittings: Compatible with raceways and suitable for use and location.
 - 1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
 - 2. PVC Externally Coated, Rigid Steel Conduits: Use only fittings listed for use with this type of conduit. Patch and seal all joints, nicks, and scrapes in PVC coating after installing conduits and fittings. Use sealant recommended by fitting manufacturer and apply in thickness and number of coats recommended by manufacturer.
 - 3. EMT: Use compression, steel fittings. Comply with NEMA FB 2.10.
 - 4. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.
 - Concealed conduit to the greatest extent possible. For all exposed and accessible conduit within the secure perimeter, provide RGS, IMC unless otherwise noted on the drawings. Refer to Architectural drawings for secure perimeter.
- E. Whips from Junction Box Concealed in Ceilings to Lighting Fixtures:
 - 1. Above non-removeable or security type ceilings, junction boxes are not acceptable. Provide conduit between the fixtures.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Within the secure perimeter, above accessible ceilings, provide Interlocked Electrical Flexible Conduit connection whips in maximum length of 4'-0". Standard FMC or MC is not acceptable in this application.
- 3. Above accessible ceilings outside the secure perimeter provide FMC or MC connection whips in maximum length of 6'-0".
- F. AC is not acceptable in any application
- G. Do not install aluminum conduits, boxes, or fittings.
- H. Install surface raceways only where indicated on Drawings.
- I. Do not install nonmetallic conduit where ambient temperature exceeds 120 deg F.

3.2 INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum conduits. Comply with NFPA 70 limitations for types of raceways allowed in specific occupancies and number of floors.
- B. All conduit shall be tight to the structure and securely with two-hole steel conduit straps. Unless indicated otherwise on the drawings, for all exposed or accessible conduit inside the secure perimeter, the distance between supports shall be one half that specified by NEC. (twice as many supports as required by NEC).
- C. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.
- D. Complete raceway installation before starting conductor installation.
- E. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for hangers and supports.
- F. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- G. Install no more than the equivalent of three 90-degree bends in any conduit run except for control wiring conduits, for which fewer bends are allowed. Support within 12 inches of changes in direction.
- H. Conceal conduit within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- I. All conduit to be installed on exterior masonry shall not run continuously within the wall cavity.
- J. Support conduit within 6 inches of enclosures to which attached.
- K. Raceways Embedded in Slabs are not permitted, except as required for entry into recessed floor boxes. Conduits shall be routed below the slab within the porous fill and stub-up at the required location. Transition from RNC to RGS with RGS elbow before rising above the floor. After

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

RGS elbow, stub-up conduit shall be type indicated in Part 3.1 above. RNC shall not be permitted exposed above the floor

- L. Where raceways are terminated with threaded hubs, screw raceways or fittings tightly into hub so end bears against wire protection shoulder. Where chase nipples are used, align raceways so coupling is square to box; tighten chase nipple so no threads are exposed.
- M. Do not embed threadless fittings in concrete unless specifically approved by Architect for each specific location.
- N. Stub-ups to Above Recessed Ceilings:
 - 1. Use EMT, IMC, or RMC for raceways.
 - 2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.
- O. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.
- P. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors including conductors smaller than No. 4 AWG.
- Q. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to 1-1/4-inch trade size and insulated throat metal bushings on 1-1/2-inch trade size and larger conduits terminated with locknuts. Install insulated throat metal grounding bushings on service conduits.
- R. Install raceways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.
- S. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to assure a continuous ground path.
- T. Cut conduit perpendicular to the length. For conduits 2-inch trade size and larger, use roll cutter or a guide to make cut straight and perpendicular to the length.
- U. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire. Cap underground raceways designated as spare above grade alongside raceways in use.
- V. Special Fittings and Installations:
 - 1. Install in each run of aboveground RMC and EMT conduit that is located where environmental temperature change may exceed 100 deg F and that has straight-run length that exceeds 100 feet.
 - 2. Install type and quantity of fittings that accommodate temperature change listed for each of the following locations:
 - a. Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F temperature change.
 - b. Outdoor Locations Exposed to Direct Sunlight: 155 deg F temperature change.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- c. Indoor Spaces Connected with Outdoors without Physical Separation: 125 deg F temperature change.
- d. Attics: 135 deg F temperature change.
- 3. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per deg F of temperature change for PVC conduits. Install fitting(s) that provide expansion and contraction for at least 0.000078 inch per foot of length of straight run per deg F of temperature change for metal conduits.
- 4. Install expansion fittings at all locations where conduits cross building or structure expansion joints. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.
- W. Flexible Conduit Connections: Comply with NEMA RV 3. Use a maximum of 72 inches of flexible conduit for recessed and semi-recessed luminaires, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.
 - 1. Use LFMC or LFNC in damp or wet locations not subject to severe physical damage.
- X. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements and also refer to Architectural elevations. Install boxes with height measured to center of box unless otherwise indicated.
- Y. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surfaces to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box. Retain the fire rating of any fire rated wall or assembly
- Z. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
- AA. Locate boxes so that cover or plate will not span different building finishes.
- BB. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.
- CC. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.
- DD. Set metal floor boxes level and flush with finished floor surface.

3.3 INSTALLATION OF UNDERGROUND CONDUIT

A. Direct-Buried Conduit:

- 1. Excavate trench bottom to provide firm and uniform support for conduit. Prepare trench bottom for pipe less than 6 inches in nominal diameter.
- 2. After installing conduit, backfill and compact. Start at tie-in point, and work toward end of conduit run, leaving conduit at end of run free to move with expansion and contraction as temperature changes during this process. Firmly hand tamp backfill around conduit to

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

provide maximum supporting strength. After placing controlled backfill to within 12 inches of finished grade, make final conduit connection at end of run and complete backfilling with normal compaction as specified in Section 312000 "Earth Moving."

- 3. Install manufactured rigid steel conduit elbows for stub-ups at poles and equipment and at building entrances through floor.
 - a. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with 3 inches of concrete for a minimum of 12 inches on each side of the coupling.
 - b. For stub-ups at equipment mounted on outdoor concrete bases and where conduits penetrate building foundations, extend steel conduit horizontally a minimum of 60 inches from edge of foundation or equipment base. Install insulated grounding bushings on terminations at equipment.
- 4. Underground Warning Tape: Comply with requirements in Section 260553 "Identification for Electrical Systems."

3.4 INSTALLATION OF UNDERGROUND HANDHOLES AND BOXES

- A. Install handholes and boxes level and plumb and with orientation and depth coordinated with connecting conduits to minimize bends and deflections required for proper entrances.
- B. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1/2-inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.
- C. Elevation: In paved areas, set so cover surface will be flush with finished grade. Set covers of other enclosures 1 inch above finished grade.
- D. Install handholes with bottom below frost line, below grade.

3.5 CONDUIT COLOR CODING

- A. All outlet boxes, junction boxes and pull boxes shall have their covers and exterior visible surfaces painted with colors to match the surface color scheme outlined below. This includes covers on boxes above lift-out and other type accessible ceilings, where identification shall also include branch circuit designation. Mark conduit a minimum of each 10'-0"
 - 1. Blue for 120/208-volts normal circuits
 - 2. Black for 277/480-volts normal circuits
 - 3. Bright red for all conduit related to fire alarm system.
 - 4. Dark red (burgundy) for all conduit related to security.
 - 5. Green for all conduit related to NEC 701 and 702 emergency systems
 - 6. Orange for all conduit related NEC 700 emergency systems
 - 7. Brown for all conduit related to data systems.
 - 8. White for all conduit related to paging systems.
 - 9. Purple for all conduit related to TV systems or other LV systems.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.6 FIRESTOPPING

A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Maintain the fire rating of all fire rated walls and assemblies in which electrical raceway or boxes are installed.

END OF SECTION 260533

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 260553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Identification for raceways.
- 2. Identification of power and control cables.
- 3. Identification for conductors.
- 4. Underground-line warning tape.
- 5. Warning labels and signs.
- 6. Instruction signs.
- 7. Equipment identification labels.
- 8. Miscellaneous identification products.

1.3 ACTION SUBMITTALS

A. Product Data: For each electrical identification product indicated.

1.4 QUALITY ASSURANCE

- A. Comply with ANSI A13.1 and IEEE C2.
- B. Comply with NFPA 70.
- C. Comply with 29 CFR 1910.144 and 29 CFR 1910.145.
- D. Comply with ANSI Z535.4 for safety signs and labels.
- E. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, shall comply with UL 969.

1.5 COORDINATION

A. Coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual; and with those required by codes, standards, and 29 CFR 1910.145. Use consistent designations throughout Project.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- C. Coordinate installation of identifying devices with location of access panels and doors.
- D. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 POWER AND CONTROL RACEWAY IDENTIFICATION MATERIALS

- A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each raceway size.
- B. Colors for Raceways Carrying Circuits at 600 V or Less:
 - 1. Black letters on an orange field.
 - 2. Legend: Indicate voltage and system or service type.
- C. Colors for Raceways Carrying Circuits at More Than 600 V:
 - 1. Black letters on an orange field.
 - 2. Legend: "DANGER CONCEALED HIGH VOLTAGE WIRING."
- D. Vinyl Labels for Raceways Carrying Circuits at 600 V or Less: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound clear adhesive tape for securing ends of legend label.
- E. Snap-Around Labels for Raceways Carrying Circuits at 600 V or Less: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeve, with diameter sized to suit diameter of raceway or cable it identifies and to stay in place by gripping action.
- F. Snap-Around, Color-Coding Bands for Raceways Carrying Circuits at 600 V or Less: Slit, pretensioned, flexible, solid-colored acrylic sleeve, 2 inches long, with diameter sized to suit diameter of raceway or cable it identifies and to stay in place by gripping action.
- G. Tape and Stencil for Raceways Carrying Circuits More Than 600 V: 4-inch- wide black stripes on 10-inch centers diagonally over orange background that extends full length of raceway or duct and is 12 inches wide. Stop stripes at legends.
- H. Metal Tags: Brass or aluminum, 2 by 2 by 0.05 inch, with stamped legend, punched for use with self-locking cable tie fastener.
- I. Write-On Tags: Polyester tag, 0.015 inch thick, with corrosion-resistant grommet and cable tie for attachment to conductor or cable.
 - 1. Marker for Tags: Permanent, waterproof, black ink marker recommended by tag manufacturer.
 - 2. Marker for Tags: Machine-printed, permanent, waterproof, black ink marker recommended by printer manufacturer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.2 METAL-CLAD CABLE IDENTIFICATION MATERIALS

- A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each cable size.
- B. Colors for Cables Carrying Circuits at 600 V and Less:
 - 1. Black letters on an orange field.
 - 2. Legend: Indicate voltage and system or service type.
- C. Colors for Cables Carrying Circuits at More Than 600 V:
 - 1. Black letters on an orange field.
 - 2. Legend: "DANGER HIGH VOLTAGE WIRING."
- D. Vinyl Labels: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound clear adhesive tape for securing ends of legend label.
- E. Self-Adhesive Vinyl Tape: Colored, heavy duty, waterproof, fade resistant; 2 inches wide; compounded for outdoor use.
- F. Heat-Shrink Preprinted Tubes: Flame-retardant polyolefin tube with machine-printed identification label. Sized to suit diameter of and shrinks to fit firmly around cable it identifies. Full shrink recovery at a maximum of 200 deg F. Comply with UL 224.

2.3 POWER AND CONTROL CABLE IDENTIFICATION MATERIALS

- A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each cable size.
- B. Vinyl Labels: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound clear adhesive tape for securing ends of legend label.
- C. Self-Adhesive, Self-Laminating Polyester Labels: Preprinted, 3-mil- thick flexible label with acrylic pressure-sensitive adhesive that provides a clear, weather- and chemical-resistant, self-laminating, protective shield over the legend. Labels sized to fit the cable diameter such that the clear shield overlaps the entire printed legend.
- D. Heat-Shrink Preprinted Tubes: Flame-retardant polyolefin tube with machine-printed identification label. Sized to suit diameter of and shrinks to fit firmly around cable it identifies. Full shrink recovery at a maximum of 200 deg F. Comply with UL 224.
- E. Metal Tags: Brass or aluminum, 2 by 2 by 0.05 inch, with stamped legend, punched for use with self-locking cable tie fastener.
- F. Write-On Tags: Polyester tag, 0.015 inch thick, with corrosion-resistant grommet and cable tie for attachment to conductor or cable.
 - 1. Marker for Tags: Permanent, waterproof, black ink marker recommended by tag manufacturer.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Marker for Tags: Machine-printed, permanent, waterproof, black ink marker recommended by printer manufacturer.
- G. Snap-Around Labels: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeve, with diameter sized to suit diameter of cable it identifies and to stay in place by gripping action.
- H. Snap-Around, Color-Coding Bands: Slit, pretensioned, flexible, solid-colored acrylic sleeve, 2 inches long, with diameter sized to suit diameter of cable it identifies and to stay in place by gripping action.

2.4 CONDUCTOR IDENTIFICATION MATERIALS

- A. Color-Coding Conductor Tape: Colored, self-adhesive vinyl tape not less than 3 mils thick by 1 to 2 inches wide.
- B. Self-Adhesive, Self-Laminating Polyester Labels: Preprinted, 3-mil- thick flexible label with acrylic pressure-sensitive adhesive that provides a clear, weather- and chemical-resistant, self-laminating, protective shield over the legend. Labels sized to fit the conductor diameter such that the clear shield overlaps the entire printed legend.
- C. Snap-Around Labels: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeve, with diameter sized to suit diameter of conductor it identifies and to stay in place by gripping action.
- D. Snap-Around, Color-Coding Bands: Slit, pretensioned, flexible, solid-colored acrylic sleeve with diameter sized to suit diameter of conductor it identifies and to stay in place by gripping action.
- E. Heat-Shrink Preprinted Tubes: Flame-retardant polyolefin tube with machine-printed identification label. Sized to suit diameter of and shrinks to fit firmly around conductor it identifies. Full shrink recovery at a maximum of 200 deg F. Comply with UL 224.
- F. Marker Tapes: Vinyl or vinyl-cloth, self-adhesive wraparound type, with circuit identification legend machine printed by thermal transfer or equivalent process.
- G. Write-On Tags: Polyester tag, 0.015 inch thick, with corrosion-resistant grommet and cable tie for attachment to conductor or cable.
 - 1. Marker for Tags: Permanent, waterproof, black ink marker recommended by tag manufacturer.
 - 2. Labels for Tags: Self-adhesive label, machine-printed with permanent, waterproof, black ink recommended by printer manufacturer, sized for attachment to tag.

2.5 FLOOR MARKING TAPE

A. 2-inch- wide, 5-mil pressure-sensitive vinyl tape, with yellow and black stripes and clear vinyl overlay.

2.6 UNDERGROUND-LINE WARNING TAPE

A. Tape:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Recommended by manufacturer for the method of installation and suitable to identify and locate underground electrical and communications utility lines.
- 2. Printing on tape shall be permanent and shall not be damaged by burial operations.
- 3. Tape material and ink shall be chemically inert, and not subject to degrading when exposed to acids, alkalis, and other destructive substances commonly found in soils.

B. Color and Printing:

- 1. Comply with ANSI Z535.1 through ANSI Z535.5.
- 2. Inscriptions for Red-Colored Tapes: ELECTRIC LINE, HIGH VOLTAGE,.
- 3. Inscriptions for Orange-Colored Tapes: TELEPHONE CABLE, CATV CABLE, COMMUNICATIONS CABLE, OPTICAL FIBER CABLE,.

C. Warning Tape:

- 1. Detectable three-layer laminate, consisting of a printed pigmented polyolefin film, a solid aluminum-foil core, and a clear protective film that allows inspection of the continuity of the conductive core, bright-colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
- 2. Overall Thickness: 5 mils.
- 3. Foil Core Thickness: 0.35 mil.
- 4. Weight: 28 lb/1000 sq. ft..
- 5. 3-Inch Tensile According to ASTM D 882: 70 lbf, and 4600 psi.

2.7 WARNING LABELS AND SIGNS

- A. Comply with NFPA 70 and 29 CFR 1910.145.
- B. Self-Adhesive Warning Labels: Factory-printed, multicolor, pressure-sensitive adhesive labels, configured for display on front cover, door, or other access to equipment unless otherwise indicated.
- C. Baked-Enamel Warning Signs: Preprinted aluminum signs, punched or drilled for fasteners, with colors, legend, and size required for application. 1/4-inch grommets in corners for mounting. Nominal size, 7 by 10 inches.
- D. Metal-Backed, Butyrate Warning Signs: Weather-resistant, nonfading, preprinted, cellulose-acetate butyrate signs with 0.0396-inch galvanized-steel backing; and with colors, legend, and size required for application. 1/4-inch grommets in corners for mounting. Nominal size, 10 by 14 inches.
 - 1. Warning labels and signs shall include, but are not limited to, the following:
 - a. Multiple Power Source Warning: "DANGER ELECTRICAL SHOCK HAZARD EQUIPMENT HAS MULTIPLE POWER SOURCES."
 - b. Workspace Clearance Warning: "WARNING OSHA REGULATION AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR 36 INCHES"
 - c. Arc Flash Hazard Warning: Refer to Section 260574 for requirements.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.8 INSTRUCTION SIGNS

- A. Engraved, laminated acrylic or melamine plastic, minimum 1/16 inch thick for signs up to 20 sq. inches and 1/8 inch thick for larger sizes.
 - 1. Engraved legend with black letters on white face.
 - 2. Punched or drilled for mechanical fasteners.
 - 3. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.
- B. Adhesive Film Label: Machine printed, in black, by thermal transfer or equivalent process. Minimum letter height shall be 3/8 inch.

2.9 EQUIPMENT IDENTIFICATION LABELS

A. Engraved, Laminated Acrylic or Melamine Label: Punched or drilled for screw mounting. White letters on a dark-gray background. Minimum letter height shall be 3/8 inch.

2.10 CABLE TIES

- A. General-Purpose Cable Ties: Fungus inert, self extinguishing, one piece, self locking, Type 6/6 nylon.
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 12,000 psi.
 - 3. Temperature Range: Minus 40 to plus 185 deg F.
 - 4. Color: Black except where used for color-coding.
- B. UV-Stabilized Cable Ties: Fungus inert, designed for continuous exposure to exterior sunlight, self extinguishing, one piece, self locking, Type 6/6 nylon.
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 12,000 psi.
 - 3. Temperature Range: Minus 40 to plus 185 deg F.
 - 4. Color: Black.
- C. Plenum-Rated Cable Ties: Self extinguishing, UV stabilized, one piece, self locking.
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 7000 psi.
 - 3. UL 94 Flame Rating: 94V-0.
 - 4. Temperature Range: Minus 50 to plus 284 deg F.
 - 5. Color: Black.

2.11 MISCELLANEOUS IDENTIFICATION PRODUCTS

A. Paint: Comply with requirements in painting Sections for paint materials and application requirements. Select paint system applicable for surface material and location (exterior or interior).

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

B. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Verify identity of each item before installing identification products.
- B. Location: Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.
- C. Apply identification devices to surfaces that require finish after completing finish work.
- D. Self-Adhesive Identification Products: Clean surfaces before application, using materials and methods recommended by manufacturer of identification device.
- E. Attach signs and plastic labels that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.
- F. System Identification Color-Coding Bands for Raceways and Cables: Each color-coding band shall completely encircle cable or conduit. Place adjacent bands of two-color markings in contact, side by side. Locate bands at changes in direction, at penetrations of walls and floors, at 50-foot maximum intervals in straight runs, and at 25-foot maximum intervals in congested areas.
- G. Aluminum Wraparound Marker Labels and Metal Tags: Secure tight to surface of conductor or cable at a location with high visibility and accessibility.
- H. Cable Ties: For attaching tags. Use general-purpose type, except as listed below:
 - 1. Outdoors: UV-stabilized nylon.
 - 2. In Spaces Handling Environmental Air: Plenum rated.
- I. Underground-Line Warning Tape: During backfilling of trenches install continuous underground-line warning tape directly above line at 6 to 8 inches below finished grade. Use multiple tapes where width of multiple lines installed in a common trench or concrete envelope exceeds 16 inches overall.
- J. Painted Identification: Comply with requirements in painting Sections for surface preparation and paint application.

3.2 IDENTIFICATION SCHEDULE

A. Accessible Raceways and Metal-Clad Cables, 600 V or Less, for Service, Feeder, and Branch Circuits More Than 30 A, and 120 V to ground: Identify with self-adhesive vinyl label. Install labels at 10-foot maximum intervals.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. Accessible Raceways and Cables within Buildings: Identify the covers of each junction and pull box of the following systems with self-adhesive vinyl labels with the wiring system legend and system voltage. System legends shall be as follows:
 - 1. Emergency Power.
 - 2. Power.
 - 3. UPS.
- C. Power-Circuit Conductor Identification, 600 V or Less: For conductors in vaults, pull and junction boxes, manholes, and handholes, use color-coding conductor tape to identify the phase.
 - 1. Color-Coding for Phase and Voltage Level Identification, 600 V or Less: Use colors listed below for ungrounded service feeder and branch-circuit conductors.
 - a. Color shall be factory applied or field applied for sizes larger than No. 8 AWG, if authorities having jurisdiction permit.
 - b. Colors for 208/120-V Circuits:
 - 1) Phase A: Black.
 - 2) Phase B: Red.
 - 3) Phase C: Blue.
 - 4) Grounded (Neutral): White.
 - 5) Ground: Green.
 - c. Colors for 480/277-V Circuits:
 - 1) Phase A: Brown.
 - 2) Phase B: Orange.
 - 3) Phase C: Yellow.
 - 4) Grounded (Neutral): Gray.
 - 5) Ground: Green.
 - d. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum distance of 6 inches from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.
- D. Power-Circuit Conductor Identification, More than 600 V: For conductors in vaults, pull and junction boxes, manholes, and handholes, use nonmetallic plastic tag holder with adhesive-backed phase tags, and a separate tag with the circuit designation.
- E. Install instructional sign including the color-code for grounded and ungrounded conductors using adhesive-film-type labels.
- F. Control-Circuit Conductor Identification: For conductors and cables in pull and junction boxes, manholes, and handholes, use self-adhesive, self-laminating polyester labels with the conductor or cable designation, origin, and destination.
- G. Control-Circuit Conductor Termination Identification: For identification at terminations provide heat-shrink preprinted tubes or self-adhesive, self-laminating polyester labels with the conductor designation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- H. Conductors to Be Extended in the Future: Attach marker tape to conductors and list source.
- I. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, and signal connections.
 - 1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.
 - 2. Use system of marker tape designations that is uniform and consistent with system used by manufacturer for factory-installed connections.
 - 3. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual.
- J. Locations of Underground Lines: Identify with underground-line warning tape for power, lighting, communication, and control wiring and optical fiber cable.
 - 1. Limit use of underground-line warning tape to direct-buried cables.
 - 2. Install underground-line warning tape for both direct-buried cables and cables in raceway.
- K. Workspace Indication: Install floor marking tape to show working clearances in the direction of access to live parts. Workspace shall be as required by NFPA 70 and 29 CFR 1926.403 unless otherwise indicated. Do not install at flush-mounted panelboards and similar equipment in finished spaces.
- L. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting: Self-adhesive warning labels.
 - 1. Comply with 29 CFR 1910.145.
 - 2. Identify system voltage with black letters on an orange background.
 - 3. Apply to exterior of door, cover, or other access.
 - 4. For equipment with multiple power or control sources, apply to door or cover of equipment including, but not limited to, the following:
 - a. Power transfer switches.
 - b. Controls with external control power connections.
- M. Operating Instruction Signs: Install instruction signs to facilitate proper operation and maintenance of electrical systems and items to which they connect. Install instruction signs with approved legend where instructions are needed for system or equipment operation.
- N. Emergency Operating Instruction Signs: Install instruction signs with white legend on a red background with minimum 3/8-inch- high letters for emergency instructions at equipment used for power transfer and load shedding.
- O. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and the Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification.
 - 1. Labeling Instructions:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- a. Indoor Equipment: Adhesive film label with clear protective overlay. Unless otherwise indicated, provide a single line of text with 1/2-inch- high letters on 1-1/2-inch- high label; where two lines of text are required, use labels 2 inches high.
- b. Outdoor Equipment: Engraved, laminated acrylic or melamine label.
- c. Elevated Components: Increase sizes of labels and letters to those appropriate for viewing from the floor.
- d. Unless provided with self-adhesive means of attachment, fasten labels with appropriate mechanical fasteners that do not change the NEMA or NRTL rating of the enclosure.

2. Equipment to Be Labeled:

- a. Panelboards: Typewritten directory of circuits in the location provided by panelboard manufacturer. Panelboard identification shall be, laminated acrylic or melamine label.
- b. Enclosures and electrical cabinets.
- c. Access doors and panels for concealed electrical items.
- d. Switchboards.
- e. Transformers: Label that includes tag designation shown on Drawings for the transformer, feeder, and panelboards or equipment supplied by the secondary.
- f. Emergency system boxes and enclosures.
- g. Enclosed switches.
- h. Enclosed circuit breakers.
- i. Enclosed controllers.
- j. Variable-speed controllers.
- k. Push-button stations.
- 1. Power transfer equipment.
- m. Contactors.
- n. Remote-controlled switches, dimmer modules, and control devices.
- o. Battery-inverter units.
- p. Power-generating units.
- q. Monitoring and control equipment.
- r. UPS equipment.

END OF SECTION 260553

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 260923 - LIGHTING CONTROL DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Show installation details for occupancy and light-level sensors.
 - 1. Interconnection diagrams showing field-installed wiring.
 - 2. Include diagrams for power, signal, and control wiring.

1.3 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For each type of lighting control device to include in emergency, operation, and maintenance manuals.

1.4 COORDINATION

A. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression system, and partition assemblies.

1.5 WARRANTY

- A. Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of lighting controls that fail in materials or workmanship or from transient voltage surges, and the Contractor agrees to provide associated electrical work to make good within the specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Failure equipment to operate, or to operate reliably.
 - b. Damage of electronic components due to transient voltage surges.
 - 2. Warranty Period: One year from date of Final Acceptance for material and labor.
 - 3. Extended Material Warranty Period Failure Due to Transient Voltage Surges: 10 years from date of Final Acceptance.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

PART 2 - PRODUCTS

2.1 TIME SWITCHES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Cooper Industries, Inc.
 - 2. Intermatic, Inc.
 - 3. Leviton Manufacturing Co., Inc.
 - 4. NSi Industries LLC.
- B. Electronic Time Switches: Solid state, programmable, with alphanumeric display; complying with UL 917.
 - 1. Listed and labeled as defined in NFPA 70, and marked for intended location and application.
 - 2. Contact Configuration: DPDT
 - 3. Contact Rating: 30-A inductive or resistive, 240-V ac.
 - 4. Programs: Each channel is individually programmable with two on-off set points on a 24-hour schedule, allowing different set points for each day of the week.
 - 5. Astronomic Time: All channels.
 - 6. Automatic daylight savings time changeover.
 - 7. Battery Backup: Not less than seven days reserve, to maintain schedules and time clock.

2.2 OUTDOOR PHOTOELECTRIC SWITCHES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Cooper Industries, Inc.
 - 2. Intermatic, Inc.
 - 3. NSi Industries LLC.
 - 4. Tyco Electronics.
- B. Description: Solid state, with SPST dry contacts rated for 1800-VA tungsten or 1000-VA inductive, to operate connected relay, contactor coils, or microprocessor input; complying with UL 773A.
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Light-Level Monitoring Range: 1.5 to 10 fc, with an adjustment for turn-on and turn-off levels within that range, and a directional lens in front of the photocell to prevent fixed light sources from causing turn-off.
 - 3. Time Delay: Fifteen second minimum, to prevent false operation.
 - 4. Surge Protection: Metal-oxide varistor.
 - 5. Mounting: Twist lock complies with NEMA C136.10, with base-and-stem mounting or stem-and-swivel mounting accessories as required to direct sensor to the north sky exposure.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.3 DAYLIGHT-HARVESTING DIMMING CONTROLS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Cooper Industries, Inc.
 - 2. Hubbell Building Automation, Inc.
 - 3. Leviton Manufacturing Co., Inc.
 - 4. Lithonia Lighting; Acuity Brands Lighting, Inc.
 - 5. Watt Stopper.
- B. System Description: Sensing daylight and electrical lighting levels, the system adjusts the indoor electrical lighting levels. As daylight increases, the lights are dimmed.
 - 1. Lighting control set point is based on two lighting conditions:
 - a. When no daylight is present (target level).
 - b. When significant daylight is present.
 - 2. System programming is done with two hand-held, remote-control tools.
 - a. Initial setup tool.
 - b. Tool for occupants to adjust the target levels by increasing the set point up to 25 percent, or by minimizing the electric lighting level.
- C. Ceiling-Mounted Dimming Controls: Solid-state, light-level sensor unit, with separate controller unit, to detect changes in lighting levels that are perceived by the eye.
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Sensor Output: 0- to 10-V dc to operate electronic dimming ballasts. Sensor is powered by controller unit.
 - 3. Power Pack: Sensor has 24-V dc, Class 2 power source, as defined by NFPA 70.
 - 4. Light-Level Sensor Set-Point Adjustment Range: 20 to 60 fc.
- 2.4 May be provided integral to the indoor occupancy sensors

2.5 INDOOR OCCUPANCY SENSORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Hubbell Building Automation, Inc.
 - 2. Leviton Manufacturing Co., Inc.
 - 3. Lithonia Lighting; Acuity Brands Lighting, Inc.
 - 4. Lutron Electronics Co., Inc.
 - 5. Sensor Switch, Inc.
 - 6. Watt Stopper.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. General Requirements for Sensors: Wall- or ceiling-mounted, solid-state indoor occupancy sensors with a separate power pack.
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Operation: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
 - 3. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A. Sensor is powered from the power pack.
 - 4. Power Pack: Dry contacts rated for 20-A ballast load at 120- and 277-V ac, for 13-A tungsten at 120-V ac, and for 1 hp at 120-V ac. Sensor has 24-V dc, 150-mA, Class 2 power source, as defined by NFPA 70.
 - 5. Mounting:
 - a. Sensor: Suitable for mounting in any position on a standard outlet box.
 - b. Relay: Externally mounted through a 1/2-inch knockout in a standard electrical enclosure.
 - c. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.
 - 6. Indicator: Digital display, to show when motion is detected during testing and normal operation of sensor.
 - 7. When daylighting is indicated on the drawings, provide Automatic Light-Level Sensor: Adjustable from 2 to 200 fc; turn lights off when selected lighting level is present.
- C. Dual-Technology Type: Ceiling mounted; detect occupants in coverage area using PIR and ultrasonic detection methods. The particular technology or combination of technologies that control on-off functions is selectable in the field by operating controls on unit.
 - 1. Sensitivity Adjustment: Separate for each sensing technology.
 - 2. Detector Sensitivity: Detect occurrences of 6-inch- minimum movement of any portion of a human body that presents a target of not less than 36 sq. in., and detect a person of average size and weight moving not less than 12 inches in either a horizontal or a vertical manner at an approximate speed of 12 inches/s.
 - 3. Detection Coverage:
 - a. Standard Height Units: In areas that have ceiling heights of 12 feet or lower, provide Watt Stopper unit DT-300 (or approved equal): Detect occupancy anywhere within a circular area up to 2000 square feet. Detectors shall be networkable to allow coverage of larger or irregularly shaped areas.
 - b. High Ceiling Units: In areas that have ceiling/mounting height over 12 feet up to 40 foot mounting including but not limited to Gymnasium, Auditorium, Cafeteria (commons) and forum spaces, provide Watt Stopper unit HB3x0 with L4 lens, or approved equal. Detect occupancy anywhere within a circular area up to 3500 square feet. Detectors shall be networkable to allow coverage of larger or irregularly shaped areas.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

2.6 SWITCHBOX-MOUNTED OCCUPANCY SENSORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Hubbell Building Automation, Inc.
 - 2. Leviton Manufacturing Co., Inc.
 - 3. Lutron Electronics Co., Inc.
 - 4. Sensor Switch, Inc.
 - 5. Watt Stopper.
- B. General Requirements for Sensors: Automatic-wall-switch occupancy sensor, suitable for mounting in a single gang switchbox.
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Operating Ambient Conditions: Dry interior conditions, 32 to 120 deg F.
 - 3. Switch Rating: Not less than 800-VA fluorescent at 120 V, 1200-VA fluorescent at 277 V, and 800-W incandescent.

C. Wall-Switch Sensor:

- 1. Standard Range: 210-degree field of view, field adjustable from 210 to 40 degrees; with a minimum coverage area of 2100 sq. ft.
- 2. Sensing Technology: Dual technology
- 3. Voltage: Dual voltage, 120 and 277 V.
- 4. Ambient-Light Override: Concealed, field-adjustable, light-level sensor from 10 to 150 fc. The switch prevents the lights from turning on when the light level is higher than the set point of the sensor.
- 5. Concealed, field-adjustable, "off" time-delay selector at up to 30 minutes.
- 6. Concealed "off" time-delay selector at 30 seconds, and 5, 10, and 20 minutes.
- 7. Adaptive Technology: Self-adjusting circuitry detects and memorizes usage patterns of the space and helps eliminate false "off" switching.

2.7 LIGHTING CONTACTORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Allen-Bradley/Rockwell Automation.
 - 2. ASCO Power Technologies, LP.
 - 3. General Electric Company.
 - 4. Square D.
- B. Description: Electrically operated, combination-type lighting contactors with nonfused disconnect, complying with NEMA ICS 2 and UL 508.
 - 1. Current Rating for Switching: Listing or rating consistent with type of load served, including tungsten filament, inductive, and high-inrush ballast (ballast with 15 percent or less total harmonic distortion of normal load current).

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Fault Current Withstand Rating: Equal to or exceeding the available fault current at the point of installation.
- 3. Enclosure: Comply with NEMA 250.
- 4. Provide with control and pilot devices as indicated on Drawings, matching the NEMA type specified for the enclosure.

2.8 CONDUCTORS AND CABLES

- A. Power Wiring to Supply Side of Remote-Control Power Sources: Not smaller than No. 12 AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."
- B. Classes 2 and 3 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 18 AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."
- C. Class 1 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 14AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

PART 3 - EXECUTION

3.1 SENSOR INSTALLATION

- A. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression systems, and partition assemblies.
- B. Install and aim sensors in locations to achieve not less than 90 percent coverage of areas indicated. Do not exceed coverage limits specified in manufacturer's written instructions.

3.2 CONTACTOR INSTALLATION

A. Mount electrically held lighting contactors with elastomeric isolator pads to eliminate structureborne vibration, unless contactors are installed in an enclosure with factory-installed vibration isolators.

3.3 WIRING INSTALLATION

- A. Wiring Method: Comply with Section 260519 "Low-Voltage Electrical Power Conductors and Cables." Minimum conduit size is 1/2 inch.
- B. Wiring within Enclosures: Comply with NECA 1. Separate power-limited and non-power-limited conductors according to conductor manufacturer's written instructions.
- C. Size conductors according to lighting control device manufacturer's written instructions unless otherwise indicated.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

D. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.

3.4 IDENTIFICATION

- A. Identify components and power and control wiring according to Section 260553 "Identification for Electrical Systems."
 - 1. Identify controlled circuits in lighting contactors.
 - 2. Identify circuits or luminaires controlled by photoelectric and occupancy sensors at each sensor.
- B. Label time switches and contactors with a unique designation.

3.5 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Operational Test: After installing time switches and sensors, and after electrical circuitry has been energized, start units to confirm proper unit operation.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- B. Lighting control devices will be considered defective if they do not pass tests and inspections.
- C. Prepare test and inspection reports.

3.6 ADJUSTING

A. Occupancy Adjustments: When requested within months from date of Final Completion, provide on-site assistance in adjusting sensors to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.7 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain lighting control devices.

END OF SECTION 260923

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 262726 - WIRING DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Receptacles, receptacles with integral GFCI, and associated device plates.
 - 2. Communications outlets.
 - 3. Snap switches and wall-box dimmers.

1.3 DEFINITIONS

- A. EMI: Electromagnetic interference.
- B. GFCI: Ground-fault circuit interrupter.
- C. Pigtail: Short lead used to connect a device to a branch-circuit conductor.
- D. RFI: Radio-frequency interference.
- E. TVSS: Transient voltage surge suppressor.
- F. UTP: Unshielded twisted pair.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: List of legends and description of materials and process used for pre-marking wall plates.
- C. Field quality-control test reports.
- D. Operation and Maintenance Data: For wiring devices to include in all manufacturers' packing label warnings and instruction manuals that include labeling conditions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.5 QUALITY ASSURANCE

- A. Source Limitations: Obtain each type of wiring device and associated wall plate through one source from a single manufacturer. Insofar as they are available, obtain all wiring devices and associated wall plates from a single manufacturer and one source.
- B. Comply with NFPA 70.

1.6 COORDINATION

A. Receptacles for Owner-Furnished Equipment: Match plug configurations.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers' Names: Shortened versions (shown in parentheses) of the following manufacturers' names are used in other Part 2 articles:
 - 1. Cooper Wiring Devices; a division of Cooper Industries, Inc. (Cooper).
 - 2. Hubbell Incorporated; Wiring Device-Kellems (Hubbell).
 - 3. Leviton Mfg. Company Inc. (Leviton).
 - 4. Pass & Seymour/Legrand; Wiring Devices & Accessories (Pass & Seymour).

2.2 STRAIGHT BLADE RECEPTACLES

- A. In buildings used for instruction of students in grade K-6, all outlets install in the building shall be tamper resistant.
- B. Convenience Receptacles, 125 V, 20 A: Comply with NEMA WD 1, NEMA WD 6 configuration 5-20R, and UL 498.
 - 1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Cooper Wiring Devices, Inc.
 - b. Hubbell.
 - c. Leviton Manufacturing Co., Inc.
 - d. Pass & Seymour/Legrand (Pass & Seymour).

2.3 GFCI RECEPTACLES

- A. General Description: Straight blade, non-feed-through type. Comply with NEMA WD 1, NEMA WD 6, UL 498, and UL 943, Class A, and include indicator light that is lighted when device is tripped.
- B. Duplex GFCI Convenience Receptacles, 125 V, 20 A:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Cooper Wiring Devices, Inc.
 - b. Hubbell.
 - c. Leviton Manufacturing Co., Inc.
 - d. Pass & Seymour/Legrand (Pass & Seymour).

2.4 TOGGLE SWITCHES

- A. Comply with NEMA WD 1 and UL 20.
- B. Manufacturers:
 - 1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Cooper Wiring Devices, Inc.
 - b. Hubbell.
 - c. Leviton Manufacturing Co., Inc.
 - d. Pass & Seymour/Legrand (Pass & Seymour).
- C. Switches, 120/277 V, 20 A:
 - 1. Description: Refer to drawings for pole configuration
- D. Pilot Light Switches, 20 A:
 - 1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Cooper; 2221PL for 120 V and 277 V.
 - b. Hubbell: HPL1221PL for 120 V and 277 V.
 - c. Leviton; 1221-PLR for 120 V, 1221-7PLR for 277 V.
 - d. Pass & Seymour; PS20AC1-PLR for 120 V.
 - 2. Description: Single pole, with lighted handle, illuminated when switch is "ON."

2.5 WALL PLATES

- A. Single and combination types to match corresponding wiring devices.
 - 1. Plate-Securing Screws: Metal with head color to match plate finish.
 - 2. Material for Finished Spaces: Steel with white baked enamel, suitable for field painting.
 - 3. Material for Unfinished Spaces: Galvanized steel.
 - 4. Material for Damp Locations: Cast aluminum with spring-loaded lift cover, and listed and labeled for use in "wet locations."

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

B. Wet-Location, Weatherproof Cover Plates: NEMA 250, complying with type 3R weather-resistant, extra-duty rated, while-in-use, die-cast aluminum with lockable cover.

2.6 FINISHES

- A. Color: Wiring device catalog numbers in Section Text do not designate device color.
 - 1. Wiring Devices Connected to Normal Power System: White, unless otherwise indicated or required by NFPA 70 or device listing.
 - 2. Wiring Devices Connected to Emergency Power System: Red.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Comply with NECA 1, including the mounting heights listed in that standard, unless otherwise noted.

B. Coordination with Other Trades:

- 1. Take steps to ensure that devices and their boxes are protected. Do not place wall finish materials over device boxes and do not cut holes for boxes with routers that are guided by riding against outside of the boxes.
- 2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.
- 3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
- 4. Install wiring devices after all wall preparation, including painting, is complete.

C. Conductors:

- 1. Do not strip insulation from conductors until just before they are spliced or terminated on devices.
- 2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
- 3. The length of free conductors at outlets for devices shall meet provisions of NFPA 70, Article 300, without pigtails.
- 4. Existing Conductors:
 - a. Cut back and pigtail or replace all damaged conductors.
 - b. Straighten conductors that remain and remove corrosion and foreign matter.
 - c. Pigtailing existing conductors is permitted provided the outlet box is large enough.

D. Device Installation:

- 1. Replace all devices that have been in temporary use during construction or that show signs that they were installed before building finishing operations were complete.
- 2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
- 4. Connect devices to branch circuits using pigtails that are not less than 6 inches (152 mm) in length.
- 5. When there is a choice, use side wiring with binding-head screw terminals. Wrap solid conductor tightly clockwise, 2/3 to 3/4 of the way around terminal screw.
- 6. Use a torque screwdriver when a torque is recommended or required by the manufacturer.
- 7. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.
- 8. Tighten unused terminal screws on the device.
- 9. When mounting into metal boxes, remove the fiber or plastic washers used to hold device mounting screws in yokes, allowing metal-to-metal contact.

E. Receptacle Orientation:

- 1. Install ground pin of vertically mounted receptacles up, and on horizontally mounted receptacles to the right.
- F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.
- G. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.

3.2 IDENTIFICATION

- A. Comply with Division 26 Section "Identification for Electrical Systems."
 - 1. Receptacles: Identify panelboard and circuit number from which served. Use durable wire markers or tags inside outlet boxes.

3.3 WARRANTY

A. Warranty: Replace devices that fail in materials or workmanship within One year from date of Final Completion.

3.4 FIELD QUALITY CONTROL

- A. Perform tests and inspections and prepare test reports.
 - 1. Test Instruments: Use instruments that comply with UL 1436.
 - 2. Test Instrument for Convenience Receptacles: Digital wiring analyzer with digital readout or illuminated LED indicators of measurement.

B. Tests for Convenience Receptacles:

- 1. Line Voltage: Acceptable range is 105 to 132 V.
- 2. Percent Voltage Drop under 15-A Load: A value of 6 percent or higher is not acceptable.
- 3. Ground Impedance: Values of up to 2 ohms are acceptable.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. GFCI Trip: Test for tripping values specified in UL 1436 and UL 943.
- 5. Using the test plug, verify that the device and its outlet box are securely mounted.
- 6. The tests shall be diagnostic, indicating damaged conductors, high resistance at the circuit breaker, poor connections, inadequate fault current path, defective devices, or similar problems. Correct circuit conditions, remove malfunctioning units and replace with new ones, and retest as specified above.

END OF SECTION 262726

WIRING DEVICES 262726 - 6

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 262813 - FUSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for spare-fuse cabinets. Include the following for each fuse type indicated:
 - 1. Ambient Temperature Adjustment Information: If ratings of fuses have been adjusted to accommodate ambient temperatures, provide list of fuses with adjusted ratings.
 - a. For each fuse having adjusted ratings, include location of fuse, original fuse rating, local ambient temperature, and adjusted fuse rating.
 - b. Provide manufacturer's technical data on which ambient temperature adjustment calculations are based.
 - 2. Dimensions and manufacturer's technical data on features, performance, electrical characteristics, and ratings.
 - 3. Current-limitation curves for fuses with current-limiting characteristics.
 - 4. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse. Submit in electronic format suitable for use in coordination software and in PDF format.
 - 5. Coordination charts and tables and related data.

1.3 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For fuses to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
 - 1. Ambient temperature adjustment information.
 - 2. Current-limitation curves for fuses with current-limiting characteristics.
 - 3. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse used on the Project. Submit in electronic format suitable for use in coordination software and in PDF format.
 - 4. Coordination charts and tables and related data.

FUSES 262813 - 1

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.4 FIELD CONDITIONS

A. exposed is less than 40 deg F or more than 100 deg F, apply manufacturer's ambient temperature adjustment factors to fuse ratings.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Cooper Bussmann; a division of Cooper Industries.
 - 2. Edison; a brand of Cooper Bussmann; a division of Cooper Industries.
 - 3. Littelfuse, Inc.
- B. Source Limitations: Obtain fuses, for use within a specific product or circuit, from single source from single manufacturer.

2.2 CARTRIDGE FUSES

- A. Characteristics: NEMA FU 1, current-limiting, nonrenewable cartridge fuses with voltage ratings consistent with circuit voltages.
 - 1. Type RK-1: 600-V, zero- to 600-A rating, 200 kAIC, time delay.
 - 2. Type CC: 600-V, zero- to 30-A rating, 200 kAIC, time delay.
 - 3. Type J: 600-V, zero- to 600-A rating, 200 kAIC.
 - 4. Type L: 600-V, 601- to 6000-A rating, 200 kAIC, time delay.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. Comply with NEMA FU 1 for cartridge fuses.
- D. Comply with NFPA 70.
- E. Coordinate fuse ratings with utilization equipment nameplate limitations of maximum fuse size and with system short-circuit current levels.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine fuses before installation. Reject fuses that are moisture damaged or physically damaged.
- B. Examine holders to receive fuses for compliance with installation tolerances and other conditions affecting performance, such as rejection features.

FUSES 262813 - 2

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- C. Examine utilization equipment nameplates and installation instructions. Install fuses of sizes and with characteristics appropriate for each piece of equipment.
- D. Evaluate ambient temperatures to determine if fuse rating adjustment factors must be applied to fuse ratings.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 FUSE APPLICATIONS

A. Cartridge Fuses:

- 1. Service Entrance: Class L, time delay.
- 2. Feeders: Class RK1, time delay.
- 3. Motor Branch Circuits: Class RK5, time delay.
- 4. Large Motor Branch (601-4000 A): Class L, time delay.
- 5. Power Electronics Circuits: Class J, high speed.
- 6. Other Branch Circuits: Class RK1, time delay.
- 7. Control Transformer Circuits: Class CC, time delay, control transformer duty.

3.3 INSTALLATION

A. Install fuses in fusible devices. Arrange fuses so rating information is readable without removing fuse.

3.4 IDENTIFICATION

A. Install labels complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems" and indicating fuse replacement information inside of door of each fused switch and adjacent to each fuse block, socket, and holder.

END OF SECTION 262813

FUSES 262813 - 3

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 262816 - ENCLOSED SWITCHES AND CIRCUIT BREAKERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 DEFINITIONS

- A. NC: Normally closed.
- B. NO: Normally open.
- C. SPDT: Single pole, double throw.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of enclosed switch, circuit breaker, accessory, and component indicated. Include dimensioned elevations, sections, weights, and manufacturers' technical data on features, performance, electrical characteristics, ratings, accessories, and finishes.
 - 1. Enclosure types and details for types other than NEMA 250, Type 1.
 - 2. Current and voltage ratings.
 - 3. Short-circuit current ratings (interrupting and withstand, as appropriate).
 - 4. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices, accessories, and auxiliary components.
 - 5. Include time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device.
- B. Shop Drawings: For enclosed switches and circuit breakers. Include plans, elevations, sections, details, and attachments to other work.
 - 1. Wiring Diagrams: For power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.
 - 1. Test procedures used.
 - 2. Test results that comply with requirements.
 - 3. Results of failed tests and corrective action taken to achieve test results that comply with requirements.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For enclosed switches and circuit breakers to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
 - 1. Manufacturer's written instructions for testing and adjusting enclosed switches and circuit breakers.
 - 2. Time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device.

1.6 QUALITY ASSURANCE

- A. Source Limitations: Obtain enclosed switches and circuit breakers, overcurrent protective devices, components, and accessories, within same product category, from single source from single manufacturer.
- B. Product Selection for Restricted Space: Drawings indicate maximum dimensions for enclosed switches and circuit breakers, including clearances between enclosures, and adjacent surfaces and other items. Comply with indicated maximum dimensions.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- D. Comply with NFPA 70.

1.7 PROJECT CONDITIONS

- A. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:
 - 1. Ambient Temperature: Not less than minus 22 deg F and not exceeding 104 deg F.
 - 2. Altitude: Not exceeding 6600 feet.
- B. Interruption of Existing Electric Service: If indicated on the drawings, Do not interrupt electric service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electric service according to requirements indicated:
 - 1. Notify **Owner** no fewer than **seven** days in advance of proposed interruption of electric service.
 - 2. Indicate method of providing temporary electric service.
 - 3. Do not proceed with interruption of electric service without **Owner's** written permission.
 - 4. Comply with NFPA 70E.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.8 COORDINATION

A. Coordinate layout and installation of switches, circuit breakers, and components with equipment served and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

PART 2 - PRODUCTS

2.1 All panelboards, switchboards, circuit breakers, dry type transformers and disconnect switches shall be of the same manufacturer.

2.2 NONFUSIBLE & FUSIBLE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Eaton Electrical Sector; Eaton Corporation.
 - 2. General Electric Company.
 - 3. Siemens Industry, Inc.
 - 4. Square D.
- B. Type HD, Heavy Duty, Single Throw, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, with clips or bolt pads to accommodate specified fuses, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.

C. Accessories:

- 1. Equipment Ground Kit: Internally mounted and labeled for copper and aluminum ground conductors.
- 2. Neutral Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.
- 3. Class R Fuse Kit: Provides rejection of other fuse types when Class R fuses are specified.
- 4. Auxiliary Contact Kit: **One** NO/NC (Form "C") auxiliary contact(s), arranged to activate before switch blades open.
- 5. Lugs: Mechanical type, suitable for number, size, and conductor material.
- 6. Service-Rated Switches: When indicated on the drawings, Labeled for use as service equipment.

2.3 MOLDED-CASE CIRCUIT BREAKERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Eaton Electrical Sector; Eaton Corporation.
 - 2. General Electric Company.
 - 3. Siemens Industry, Inc.
 - 4. Square D.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- B. General Requirements: Comply with UL 489, NEMA AB 1, and NEMA AB 3, with interrupting capacity to comply with available fault currents.
- C. Thermal-Magnetic Circuit Breakers: Inverse time-current element for low-level overloads and instantaneous magnetic trip element for short circuits. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
- D. Adjustable, Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
- E. Electronic Trip Circuit Breakers: Field-replaceable rating plug, rms sensing, with the following field-adjustable settings:
 - 1. Instantaneous trip.
 - 2. Long- and short-time pickup levels.
 - 3. Long- and short-time time adjustments.
 - 4. Ground-fault pickup level, time delay, and I²t response.
- F. Current-Limiting Circuit Breakers: Frame sizes 400 A and smaller, and let-through ratings less than NEMA FU 1, RK-5.
- G. Integrally Fused Circuit Breakers: Thermal-magnetic trip element with integral limiter-style fuse listed for use with circuit breaker and trip activation on fuse opening or on opening of fuse compartment door.
- H. Ground-Fault, Circuit-Interrupter (GFCI) Circuit Breakers: Single- and two-pole configurations with Class A ground-fault protection (6-mA trip).
- I. Ground-Fault, Equipment-Protection (GFEP) Circuit Breakers: With Class B ground-fault protection (30-mA trip).
- J. Features and Accessories:
 - 1. Standard frame sizes, trip ratings, and number of poles.
 - 2. Lugs: Mechanical type, suitable for number, size, trip ratings, and conductor material.
 - 3. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and high-intensity discharge lighting circuits.
 - 4. Ground-Fault Protection: Comply with UL 1053; **integrally mounted, self-powered** type with mechanical ground-fault indicator; relay with adjustable pickup and time-delay settings, push-to-test feature, internal memory, and shunt trip unit; and three-phase, zero-sequence current transformer/sensor.
 - 5. Shunt Trip: Trip coil energized from separate circuit, with coil-clearing contact.

2.4 MOLDED-CASE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Eaton Electrical Sector; Eaton Corporation.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. General Electric Company.
- 3. Siemens Industry, Inc.
- 4. Square D.
- B. General Requirements: MCCB with fixed, high-set instantaneous trip only, and short-circuit withstand rating equal to equivalent breaker frame size interrupting rating.

C. Features and Accessories:

- 1. Standard frame sizes and number of poles.
- 2. Lugs: Mechanical type, suitable for number, size, trip ratings, and conductor material.
- 3. Ground-Fault Protection: Comply with UL 1053; remote-mounted and powered type with mechanical ground-fault indicator; relay with adjustable pickup and time-delay settings, push-to-test feature, internal memory, and shunt trip unit; and three-phase, zero-sequence current transformer/sensor.
- 4. Shunt Trip: Trip coil energized from separate circuit, with coil-clearing contact.

2.5 ENCLOSURES

- A. Enclosed Switches and Circuit Breakers: NEMA AB 1, NEMA KS 1, NEMA 250, and UL 50, to comply with environmental conditions at installed location.
 - 1. Indoor, Dry and Clean Locations: NEMA 250, Type 1.
 - 2. Outdoor Locations: NEMA 250, Type 3R.
 - 3. Kitchen and Wash-Down Areas: NEMA 250, Type 4X, stainless steel.
 - 4. Other Wet or Damp, Indoor Locations: NEMA 250, Type 4.
 - 5. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: NEMA 250, Type 12.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine elements and surfaces to receive enclosed switches and circuit breakers for compliance with installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install individual wall-mounted switches and circuit breakers with tops at uniform height unless otherwise indicated.
- B. Install fuses in fusible devices.
- C. Comply with NECA 1.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.3 IDENTIFICATION

- A. Comply with requirements in Section 260553 "Identification for Electrical Systems."
 - 1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
 - 2. Label each enclosure with engraved metal or laminated-plastic nameplate.

3.4 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Acceptance Testing Preparation:
 - 1. Test insulation resistance for each enclosed switch and circuit breaker, component, connecting supply, feeder, and control circuit.
 - 2. Test continuity of each circuit.

C. Tests and Inspections:

- 1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
- 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
- 3. Perform the following infrared scan tests and inspections and prepare reports:
 - a. Initial Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each enclosed switch and circuit breaker. Remove front panels so joints and connections are accessible to portable scanner.
 - b. Instruments and Equipment: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
- 4. Test and adjust controls, remote monitoring, and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Enclosed switches and circuit breakers will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports, including a certified report that identifies enclosed switches and circuit breakers and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.5 ADJUSTING

- A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.
- B. Set field-adjustable circuit-breaker trip ranges.

MAYO HIGH SCHOOL – TOILET RENOVATION DARLINGTON, SOUTH CAROLINA DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

END OF SECTION 262816

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 262913 - ENCLOSED CONTROLLERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes the following enclosed controllers rated 600 V and less:
 - 1. Full-voltage manual.
 - 2. Full-voltage magnetic.
 - 3. Combination magnetic starter/disconnect switch.

B. Related Section:

1. Division 23 Section "Variable-Frequency Motor Controllers" for general-purpose, ac, adjustable-frequency, pulse-width-modulated controllers for use on variable torque loads in ranges up to 200 hp.

1.3 DEFINITIONS

- A. CPT: Control power transformer.
- B. MCCB: Molded-case circuit breaker.
- C. MCP: Motor circuit protector.
- D. N.C.: Normally closed.
- E. N.O.: Normally open.
- F. OCPD: Overcurrent protective device.
- G. SCR: Silicon-controlled rectifier.

1.4 SUBMITTALS

- A. Product Data: For each type of enclosed controller. Include manufacturer's technical data on features, performance, electrical characteristics, ratings, and enclosure types and finishes.
- B. Shop Drawings: For each enclosed controller. Include dimensioned plans, elevations, sections, details, and required clearances and service spaces around controller enclosures.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Show tabulations of the following:
 - a. Each installed unit's type and details.
 - b. Factory-installed devices.
 - c. Nameplate legends.
 - d. Short-circuit current rating of integrated unit.
 - e. Listed and labeled for integrated short-circuit current (withstand) rating of OCPDs in combination controllers by an NRTL acceptable to authorities having jurisdiction.
 - f. Features, characteristics, ratings, and factory settings of individual OCPDs in combination controllers.
- 2. Wiring Diagrams: For power, signal, and control wiring.
- C. Field quality-control reports.
- D. Operation and Maintenance Data: For enclosed controllers to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
 - 1. Routine maintenance requirements for enclosed controllers and installed components.
 - 2. Manufacturer's written instructions for setting field-adjustable overload relays.
- E. Load-Current and List of Settings of Adjustable Overload Relays: Compile after motors have been installed, and arrange to demonstrate that switch settings for motor running overload protection suit actual motors to be protected.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Store enclosed controllers indoors in clean, dry space with uniform temperature to prevent condensation. Protect enclosed controllers from exposure to dirt, fumes, water, corrosive substances, and physical damage.

1.6 PROJECT CONDITIONS

- A. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:
 - 1. Ambient Temperature: Not less than minus 22 deg F (minus 30 deg C) and not exceeding 113 deg F (45 deg C).
 - 2. Altitude: Not exceeding 6600 feet (2010 m).

1.7 COORDINATION

- A. Coordinate layout and installation of enclosed controllers with other construction including conduit, piping, equipment, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.
- B. Coordinate installation of roof curbs, equipment supports, and roof penetrations.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.8 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Indicating Lights: Two of each type and color installed.
 - 2. Auxiliary Contacts: Furnish one spare for each size and type of magnetic controller installed.
 - 3. Power Contacts: Furnish three spares for each size and type of magnetic contactor installed.

PART 2 - PRODUCTS

2.1 FULL-VOLTAGE CONTROLLERS

- A. General Requirements for Full-Voltage Controllers: Comply with NEMA ICS 2, general purpose, Class A.
- B. Fractional Horsepower Manual Controllers: "Quick-make, quick-break" toggle action; marked to show whether unit is off, on, or tripped.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
 - b. General Electric Company; GE Consumer & Industrial Electrical Distribution.
 - c. Rockwell Automation, Inc.; Allen-Bradley brand.
 - d. Siemens Energy & Automation, Inc.
 - e. Square D; a brand of Schneider Electric.
 - 2. Configuration: Nonreversing.
 - 3. Overload Relays: Inverse-time-current characteristics; NEMA ICS 2, Class 10 tripping characteristics; heaters matched to nameplate full-load current of actual protected motor; external reset push button; bimetallic type.
 - 4. Surface mounting.
 - 5. Red pilot light.
- C. Magnetic Controllers: Full voltage, across the line, electrically held.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
 - b. General Electric Company; GE Consumer & Industrial Electrical Distribution.
 - c. Rockwell Automation, Inc.; Allen-Bradley brand.
 - d. Siemens Energy & Automation, Inc.
 - e. Square D; a brand of Schneider Electric.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Configuration: Nonreversing.
- 3. Contactor Coils: Pressure-encapsulated type with coil transient suppressors.
 - a. Operating Voltage: Depending on contactor NEMA size and line-voltage rating, manufacturer's standard matching control power or line voltage.
- 4. Power Contacts: Totally enclosed, double-break, silver-cadmium oxide; assembled to allow inspection and replacement without disturbing line or load wiring.
- 5. Control Circuits: 120V ac; obtained from integral CPT, with primary and secondary fuses, with CPT of sufficient capacity to operate integral devices, remotely located pilot, indicating, and control devices.
 - a. CPT Capacity: 500 VA.
- 6. Bimetallic Overload Relays (unless otherwise noted):
 - a. Inverse-time-current characteristic.
 - b. Class 10 tripping characteristic.
 - c. Heaters in each phase matched to nameplate full-load current of actual protected motor and with appropriate adjustment for duty cycle.
 - d. Ambient compensated.
- 7. Solid-State Overload Relay (smoke control SEF and OAF fans):
 - a. Switch or dial selectable for motor running overload protection.
 - b. Sensors in each phase.
 - c. Class 10/20 selectable tripping characteristic selected to protect motor against voltage and current unbalance and single phasing.
 - d. Class II ground-fault protection, with start and run delays to prevent nuisance trip on starting.
- D. Combination Magnetic Controller: Factory-assembled combination of magnetic controller, OCPD, and disconnecting means.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
 - b. General Electric Company; GE Consumer & Industrial Electrical Distribution.
 - c. Rockwell Automation, Inc.; Allen-Bradley brand.
 - d. Siemens Energy & Automation, Inc.
 - e. Square D; a brand of Schneider Electric.
 - 2. Fusible Disconnecting Means:
 - a. NEMA KS 1, heavy-duty, horsepower-rated, fusible switch with clips or bolt pads to accommodate Class R fuses.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- b. Lockable Handle: Accepts three padlocks and interlocks with cover in closed position.
- 3. Auxiliary Contacts: N.O./N.C., arranged to activate before switch blades open.

2.2 ENCLOSURES

- A. Enclosed Controllers: NEMA ICS 6, to comply with environmental conditions at installed location.
 - 1. Dry and Clean Indoor Locations: Type 1.
 - 2. Outdoor Locations: Type 3R.

2.3 ACCESSORIES

- A. General Requirements for Control Circuit and Pilot Devices: NEMA ICS 5; factory installed in controller enclosure cover unless otherwise indicated.
 - 1. Pilot Lights and Selector Switches: Heavy-duty type.
 - a. Pilot Lights: LED type; Red when "ON". Green when "OFF (safe).
 - b. Selector Switches: Rotary type "Hand-Off-Auto (HOA)."
- B. Reversible N.C./N.O. auxiliary contact(s).
- C. Control Relays: Auxiliary and adjustable solid-state time-delay relays.
- D. Phase-Failure, Phase-Reversal, and Undervoltage and Overvoltage Relays: Solid-state sensing circuit with isolated output contacts for hard-wired connections. Provide adjustable undervoltage, overvoltage, and time-delay settings.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and surfaces to receive enclosed controllers, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.
- B. Examine enclosed controllers before installation. Reject enclosed controllers that are wet, moisture damaged, or mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Wall-Mounted Controllers: Install enclosed controllers on walls with tops at uniform height unless otherwise indicated, and by bolting units to wall or mounting on lightweight structural-

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

steel channels bolted to wall. For controllers not at walls, provide freestanding racks complying with Division 26 Section "Hangers and Supports for Electrical Systems."

- B. Install fuses in each fusible-switch enclosed controller.
- C. Install fuses in control circuits if not factory installed. Comply with requirements in Division 26 Section "Fuses."
- D. Install heaters in thermal overload relays. Select heaters based on actual nameplate full-load amperes after motors have been installed.
- E. Install, connect, and fuse thermal-protector monitoring relays furnished with motor-driven equipment.
- F. Comply with NECA 1.

3.3 IDENTIFICATION

- A. Identify enclosed controllers, components, and control wiring. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
 - 1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
 - 2. Label each enclosure with engraved nameplate.
 - 3. Label each enclosure-mounted control and pilot device.

3.4 CONTROL WIRING INSTALLATION

- A. Install wiring between enclosed controllers and remote devices.
- B. Bundle, train, and support wiring in enclosures.
- C. Connect selector switches and other automatic-control selection devices where applicable.
 - 1. Connect selector switches to bypass only those manual- and automatic-control devices that have no safety functions when switch is in manual-control position.

3.5 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Acceptance Testing Preparation:
 - 1. Test insulation resistance for each enclosed controller, component, connecting supply, feeder, and control circuit.
 - 2. Test continuity of each circuit.
- C. Tests and Inspections:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Inspect and test controllers, wiring, components, connections, and equipment installation.
- 2. Test insulation resistance for each enclosed-controller element, component, connecting motor supply, feeder, and control circuits.
- 3. Test continuity of each circuit.
- 4. Verify that voltages at controller locations are within plus or minus 10 percent of motor nameplate rated voltages. If outside this range for any motor, notify Architect before starting the motor(s).
- 5. Test each motor for proper phase rotation.
- 6. Perform each electrical test and visual and mechanical inspection stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
- 7. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
- 8. Test and adjust controls, remote monitoring, and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Enclosed controllers will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports including a certified report that identifies enclosed controllers and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.6 ADJUSTING

A. Set field-adjustable switches, auxiliary relays, time-delay relays, timers, and overload-relay pickup and trip ranges.

3.7 WARRANTY

A. Warranty: Repair or replace equipment that fail in materials or workmanship within One year from date of Final Completion.

3.8 PROTECTION

A. Replace controllers whose interiors have been exposed to water or other liquids prior to Final Acceptance.

3.9 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain enclosed controllers.

END OF SECTION 262913

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 265119 - LED INTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Interior solid-state luminaires that use LED technology.
 - 2. Exit Signs
 - 3. Lighting fixture supports.

1.3 DEFINITIONS

- A. CCT: Correlated color temperature.
- B. CRI: Color Rendering Index.
- C. Fixture: See "Luminaire."
- D. IP: International Protection or Ingress Protection Rating.
- E. LED: Light-emitting diode.
- F. Lumen: Measured output of lamp and luminaire, or both.
- G. Luminaire: Complete lighting unit, including lamp, reflector, and housing.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Arrange in order of luminaire designation.
 - 2. Include data on features, accessories, and finishes.
 - 3. Include physical description and dimensions of luminaires.
 - 4. Include emergency lighting units, including batteries and chargers.
 - 5. Include life, output (lumens, CCT, and CRI), and energy efficiency data.
 - 6. Photometric data and adjustment factors based on laboratory tests.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 7. Confirmation of compliance with Design Lighting Consortium (DLC) or ENERGY STAR product requirements.
- B. Shop Drawings: For nonstandard or custom luminaires.
 - 1. Include plans, elevations, sections, and mounting and attachment details.
 - 2. Include details of luminaire assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 3. Include diagrams for power, signal, and control wiring.
- C. Product Schedule: For luminaires. Use same designations indicated on Drawings.
- D. For each fixture provide a color palette of the manufacturer's full color offering. Indicate which colors are standard (no additional cost) and which are custom (additional cost). Architect shall pick the color of all fixtures at the time of the submittal.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For luminaires and lighting systems to include in operation and maintenance manuals.
 - 1. Provide a list of all lamp types used on Project; use ANSI and manufacturers' codes.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Protect finishes of exposed surfaces by applying a strippable, temporary protective covering before shipping.

1.7 WARRANTY

A. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within Five years from date of Final Completion.

1.8 EXTRA MATERIALS

- A. Provide extra materials described below that match products installed including installation. Uninstalled devices shall be packaged with protective covering for storage, identified with labels describing contents and turned over to the owner at the completion of the project.
 - 1. Ballasts/Drivers: 1 for every 100 of each type and rating installed. Furnish at least one of each type.
 - 2. Globes and Guards: 1 for every 20 of each type and rating installed. Furnish at least one of each type.
 - 3. Exit signs: Provide 10% of total count but not less than 10 additional exit signs (single face or double face, as needed)
 - 4. Including 100' of conduit, boxes, wire, associated accessories and installation for each unit listed above. Units shall be installed as directed by the Architect, Owner, or Authority Having Jurisdiction (AHJ).

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

1.9 SUBSTITUTIONS

- A. In Lighting Fixture Schedule where titles below are column or row headings that introduce lists, the following requirements apply to product selection:
 - 1. Basis of Design Product: The design of each luminaire and its support is based on the first product named. Subject to compliance with requirements, provide either the named product or a comparable product by another manufacturer.
- 2. The lighting fixture layout indicated in the Contract Documents is based upon photometric data, quality, construction and appearance of fixtures listed in the lighting fixture schedule. Substitutions of listed fixtures are allowed provided the following is provided:
 - 2. Substitution package shall be submitted to Architect no later than fifteen (15) days prior to bid for review and approval.
 - 3. Provide all data for the substitution package in a table similar in format to the lighting fixture schedule on the drawings.
 - 4. Provide cut sheets of substitute fixtures with the various features highlighted.
 - 5. Architect has final functional and aesthetic approval on all substituted fixtures.
 - 6. Pre-bid approved will still be subject to the usual post bid submittal process and review.

PART 2 - PRODUCTS

2.1 LUMINAIRE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. All interior LED lighting fixtures shall be compliant with current product requirements of Design Lighting Consortium (DLC) or ENERGY STAR program.
- C. Recessed Fixtures: Comply with NEMA LE 4.
- D. Bulb shape complying with ANSI C79.1.
- E. CRI of minimum 80 CCT of 4100K.
- F. Rated lamp life of 50,000.
- G. Lamps dimmable from 100 percent to 10 percent of maximum light output.
- H. Internal driver:
 - 1. Minimum efficiency: 85% at full load.
 - 2. Minimum Operating Ambient Temperature: -20° C. (-4° F.).
 - 3. Input Voltage: $120 277V (\pm 10\%)$ at 60 Hz.
 - 4. Integral short circuit, open circuit, and overload protection.
 - 5. Power Factor: > 0.95.
 - 6. Total Harmonic Distortion: $\leq 20\%$.
 - 7. Comply with FCC 47 CFR Part 15.
- I. LED Modules:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Comply with IES LM-79 and LM-80 requirements.
- 2. Minimum CRI 80 and color temperature 4200° K unless otherwise specified in LIGHTING FIXTURE SCHEDULE.
- 3. Minimum Rated Life: 50,000 hours per IES L70.
- 4. Light output lumens as indicated in the LIGHTING FIXTURE SCHEDULE.
- J. Nominal Operating Voltage: Provide Universal voltage (MVOLT) ballast where possible. Otherwise provide per the drawings.
- K. Lens Thickness: At least 0.125 inch minimum unless otherwise indicated.

L. Housings:

- 1. Extruded-aluminum or steel housing and heat sink.
- 2. Powder-coat painted finish.

2.2 EXIT SIGNS

- A. General Requirements for Exit Signs: Comply with UL 924; for sign colors, visibility, luminance, and lettering size, comply with authorities having jurisdiction.
- B. Internally Lighted Signs:
 - 1. Lamps for AC Operation: LEDs, 50,000 hours minimum rated lamp life.
 - 2. Battery Powered Exit Signs: Integral automatic charger in a self-contained power pack.
 - a. Battery: Sealed, maintenance-free, nickel-cadmium type.
 - b. Charger: Fully automatic, solid-state type with sealed transfer relay.
 - c. Operation: Relay automatically energizes lamp from battery when circuit voltage drops to 80 percent of nominal voltage or below. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
 - d. Test Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
 - e. LED Indicator Light: Indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.
 - f. Remote Test: Switch in hand-held remote device aimed in direction of tested unit initiates coded infrared signal. Signal reception by factory-installed infrared receiver in tested unit triggers simulation of loss of its normal power supply, providing visual confirmation of either proper or failed emergency response.

2.3 MATERIALS

A. Metal Parts:

- 1. Free of burrs and sharp corners and edges.
- 2. Sheet metal components shall be steel unless otherwise indicated.
- 3. Form and support to prevent warping and sagging.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

B. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

C. Diffusers:

- 1. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
- 2. Lens Thickness: At least 0.125 inch minimum unless otherwise indicated.
- D. Factory-Applied Labels: Comply with UL 1598. Include recommended lamps. Locate labels where they will be readily visible to service personnel, but not seen from normal viewing angles when lamps are in place.
 - 1. Label shall include the following lamp characteristics:
 - a. "USE ONLY" and include specific lamp type.
 - b. Lamp diameter, shape, size, wattage, and coating.
 - c. CCT and CRI for all luminaires.

2.4 METAL FINISHES

A. Variations in finishes are unacceptable in the same piece. Variations in finishes of adjoining components are acceptable if they are within the range of approved Samples and if they can be and are assembled or installed to minimize contrast.

2.5 LUMINAIRE FIXTURE SUPPORT COMPONENTS

- A. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for channel and angle iron supports and nonmetallic channel and angle supports.
- B. Single-Stem Hangers: 1/2-inch steel tubing with swivel ball fittings and ceiling canopy. Finish same as luminaire.
- C. Wires: ASTM A 641/A 641 M, Class 3, soft temper, zinc-coated steel, 12 gage.
- D. Rod Hangers: 3/16-inch minimum diameter, cadmium-plated, threaded steel rod.
- E. Hook Hangers: Integrated assembly matched to luminaire, line voltage, and equipment with threaded attachment, cord, and locking-type plug.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

B. Examine roughing-in for luminaire to verify actual locations of luminaire and electrical connections before fixture installation. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 TEMPORARY LIGHTING

A. If approved by the Architect, use selected permanent luminaires for temporary lighting. When construction is sufficiently complete, clean luminaires used for temporary lighting and install new lamps.

3.3 INSTALLATION

- A. Comply with NECA 1.
- B. Install luminaires level, plumb, and square with ceilings and walls unless otherwise indicated.
- C. Install lamps in each luminaire.

D. Supports:

- 1. Sized and rated for luminaire weight.
- 2. Able to maintain luminaire position after cleaning and relamping.
- 3. Provide support for luminaire without causing deflection of ceiling or wall.
- 4. Luminaire mounting devices shall be capable of supporting a horizontal force of 100 percent of luminaire weight and vertical force of 400 percent of luminaire weight.

E. Flush-Mounted Luminaire Support:

- 1. Secured to outlet box.
- 2. Attached to ceiling structural members at four points equally spaced around circumference of luminaire.
- 3. Trim ring flush with finished surface.

F. Wall-Mounted Luminaire Support:

- 1. Attached to structural members in walls
- 2. Do not attach luminaires directly to gypsum board.

G. Ceiling-Mounted Luminaire Support:

1. Ceiling mount with two 5/32-inch diameter aircraft cable supports attached to structure. Do not attached to ceiling with no additional support.

H. Suspended Luminaire Support:

- 1. Pendants and Rods: Where longer than 48 inches, brace to limit swinging.
- 2. Stem-Mounted, Single-Unit Luminaires: Suspend with twin-stem hangers. Support with approved outlet box and accessories that hold stem and provide damping of luminaire oscillations. Support outlet box vertically to building structure using approved devices.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Continuous Rows of Luminaires: Use tubing or stem for wiring at one point and tubing or rod for suspension for each unit length of luminaire chassis, including one at each end.
- 4. Do not use ceiling grid as support for pendant luminaires. Connect support wires or rods to building structure.

I. Ceiling-Grid-Mounted Luminaires:

- 1. Lighting fixtures: Set level, plumb, and square with ceilings and walls.
- 2. Support for Lighting Fixtures in or on Grid-Type Suspended Ceilings.
 - a. Do not use grid alone to at support element.
 - b. Install a minimum of two support system rods or wires for each fixture located no more than 6 inches (150 mm) from lighting fixture corners diagonally across the fixture.
 - c. Wire or rod shall have a minimum strength factor of the weight of fixture at a safety factor of 3.
 - d. Secure luminaire to the luminaire opening using approved fasteners in a minimum of two locations, spaced near diagonal corners of luminaire.
- 3. Fixtures of Sizes Less Than Ceiling Grid:
 - a. Install as indicated on reflected ceiling plans or center in acoustical panel, and support fixtures independently with at least two 3/4-inch (20-mm) metal channels spanning and secured to ceiling tees.
 - b. Fixtures larger than 18"x18" shall also be supported by a minimum of two support system rods or wires for each fixture located no more than 6 inches (150 mm) from lighting fixture corners diagonally across the fixture.
- J. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for wiring connections.

3.4 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

3.5 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
 - 2. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery power and retransfer to normal.
- B. Luminaire will be considered defective if it does not pass operation tests and inspections.
- C. Prepare test and inspection reports.

END OF SECTION 265119

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 265619 – LED EXTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Exterior solid-state luminaires that are designed for and exclusively use LED lamp technology.
- 2. Luminaire supports.
- 3. Luminaire-mounted photoelectric relays.

1.3 DEFINITIONS

- A. CCT: Correlated color temperature.
- B. CRI: Color rendering index.
- C. Fixture: See "Luminaire."
- D. IP: International Protection or Ingress Protection Rating.
- E. Lumen: Measured output of lamp and luminaire, or both.
- F. Luminaire: Complete lighting unit, including lamp, reflector, and housing.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of luminaire.
 - 1. Arrange in order of luminaire designation.
 - 2. Include data on features, accessories, and finishes.
 - 3. Include physical description and dimensions of luminaire.
 - 4. Lamps, include life, output (lumens, CCT, and CRI), and energy-efficiency data.
 - 5. Photometric data and adjustment factors based on laboratory tests,
 - 6. Means of attaching luminaires to supports and indication that the attachment is suitable for components involved.

LED EXTERIOR LIGHTING

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 7. Confirmation of compliance with Design Lighting Consortium (DLC) or ENERGY STAR product requirements.
- B. Shop Drawings: For nonstandard or custom luminaires.
 - 1. Include plans, elevations, sections, and mounting and attachment details.
 - 2. Include details of luminaire assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 3. Include diagrams for power, signal, and control wiring.
- C. Product Schedule: For luminaires. Use same designations indicated on Drawings.
- D. For each fixture provide a color palette of the manufacturer's full color offering. Indicate which colors are standard (no additional cost) and which are custom (additional cost). Architect shall pick the color of all fixtures at the time of the submittal.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For luminaires [and photoelectric relays] to include in operation and maintenance manuals.
 - 1. Provide a list of all lamp types used on Project. Use ANSI and manufacturers' codes.
 - 2. Provide a list of all photoelectric relay types used on Project; use manufacturers' codes.

1.6 QUALITY ASSURANCE

A. Provide luminaires from a single manufacturer for each luminaire type.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Protect finishes of exposed surfaces by applying a strippable, temporary protective covering prior to shipping.

1.8 FIELD CONDITIONS

A. Verify existing and proposed utility structures prior to the start of work associated with luminaire installation.

1.9 EXTRA MATERIALS

- A. Provide extra materials described below that match products installed including installation. Uninstalled devices shall be packaged with protective covering for storage, identified with labels describing contents and turned over to the owner at the completion of the project.
 - 1. Ballasts/Drivers: 1 for every 100 of each type and rating installed. Furnish at least one of each type.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 2. Globes and Guards: 1 for every 20 of each type and rating installed. Furnish at least one of each type.
- 3. Including 100' of conduit, boxes, wire, associated accessories and installation for each unit listed above. Units shall be installed as directed by the Architect, Owner, or Authority Having Jurisdiction (AHJ).

1.10 WARRANTY

- A. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Structural failures, including luminaire support components.
 - b. Faulty operation of luminaires and accessories.
 - c. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
- B. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within Five years from date of Final Completion.

1.11 SUBSTITUTIONS

- A. In Lighting Fixture Schedule where titles below are column or row headings that introduce lists, the following requirements apply to product selection:
 - 1. Basis of Design Product: The design of each luminaire and its support is based on the first product named. Subject to compliance with requirements, provide either the named product or a comparable product by another manufacturer.
- 2. The lighting fixture layout indicated in the Contract Documents is based upon photometric data, quality, construction and appearance of fixtures listed in the lighting fixture schedule. Substitutions of listed fixtures are allowed provided the following is provided:
 - 2. Substitution package shall be submitted to Architect no later than fifteen (15) days prior to bid for review and approval.
 - 3. Provide all data for the substitution package in a table similar in format to the lighting fixture schedule on the drawings.
 - 4. Provide cut sheets of substitute fixtures with the various features highlighted.
 - 5. Architect has final functional and aesthetic approval on all substituted fixtures.
 - 6. Pre-bid approved will still be subject to the usual post bid submittal process and review.

PART 2 - PRODUCTS

2.1 LUMINAIRE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

B. NRTL Compliance: Luminaires shall be listed and labeled for indicated class and division of hazard by an NRTL.

Coordinate "FM Global Compliance" Paragraph below with Drawings.

- C. FM Global Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by FM Global.
- D. UL Compliance: Comply with UL 1598 and listed for wet location.
- E. CRI of minimum 70 CCT of 4100 K
- F. L70 lamp life of 50,000 hours.
- G. Lamps dimmable from 100 percent to 10 percent of maximum light output.
- H. Internal driver.
- I. Nominal Operating Voltage: Provide Universal voltage (MVOLT) ballast where possible. Otherwise provide per the drawings.
- J. Source Limitations: For luminaires, obtain each color, grade, finish, type, and variety of luminaire from single source with resources to provide products of consistent quality in appearance and physical properties.

2.2 FINISHES

- A. Variations in Finishes: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- B. Luminaire Finish: Manufacturer's standard paint applied to factory-assembled and -tested luminaire before shipping. Where indicated, match finish process and color of pole or support materials.
- C. Factory-Applied Finish for Aluminum Luminaires: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
 - 1. Finish designations prefixed by AA comply with the system established by the Aluminum Association for designating aluminum finishes.
 - 2. Natural Satin Finish: Provide fine, directional, medium satin polish (AA-M32); buff complying with AA-M20 requirements; and seal aluminum surfaces with clear, hard-coat wax.
 - 3. Class I, Clear-Anodic Finish: AA-M32C22A41 (Mechanical Finish: Medium satin; Chemical Finish: Etched, medium matte; Anodic Coating: Architectural Class I, clear coating 0.018 mm or thicker) complying with AAMA 611.
- D. Factory-Applied Finish for Steel Luminaires: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Surface Preparation: Clean surfaces to comply with SSPC-SP 1, to remove dirt, oil, grease, and other contaminants that could impair paint bond. Grind welds and polish surfaces to a smooth, even finish. Remove mill scale and rust, if present, from uncoated steel, complying with SSPC-SP 5/NACE No. 1 or SSPC-SP 8.
- 2. Exterior Surfaces: Manufacturer's standard finish consisting of one or more coats of primer and two finish coats of high-gloss, high-build polyurethane enamel.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for luminaire electrical conduit to verify actual locations of conduit connections before luminaire installation.
- C. Examine walls, roofs, canopy ceilings and overhang ceilings for suitable conditions where luminaires will be installed.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 TEMPORARY LIGHTING

A. If approved by the Architect, use selected permanent luminaires for temporary lighting. When construction is substantially complete, clean luminaires used for temporary lighting and install new lamps.

3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Comply with NECA 1.
- B. Use fastening methods and materials selected to resist seismic forces defined for the application and approved by manufacturer.
- C. Install lamps in each luminaire.
- D. Fasten luminaire to structural support.

E. Supports:

- 1. Sized and rated for luminaire weight.
- 2. Able to maintain luminaire position after cleaning and relamping.
- 3. Support luminaires without causing deflection of finished surface.
- 4. Luminaire-mounting devices shall be capable of supporting a horizontal force of 100 percent of luminaire weight and a vertical force of 400 percent of luminaire weight.

F. Wall-Mounted Luminaire Support:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Attached to structural members in walls
- G. Wiring Method: Install cables in raceways. Conceal raceways and cables.
- H. Install luminaires level, plumb, and square with finished grade unless otherwise indicated. Install luminaires at height and aiming angle as indicated on Drawings.
- I. Coordinate layout and installation of luminaires with other construction.
- J. Adjust luminaires that require field adjustment or aiming. Include adjustment of photoelectric device to prevent false operation of relay by artificial light sources, favoring a north orientation.
- K. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables" and 260533 "Raceways and Boxes for Electrical Systems" for wiring connections and wiring methods.

3.4 BOLLARD LUMINAIRE INSTALLATION:

- A. Align units for optimum directional alignment of light distribution.
- B. Install on concrete base with top 4 inches above finished grade or surface at luminaire location. Cast conduit into base, and shape base to match shape of bollard base. Finish by troweling and rubbing smooth.

3.5 INSTALLATION OF INDIVIDUAL GROUND-MOUNTED LUMINAIRES

- A. Aim as indicated on Drawings.
- B. Install on concrete base with top [4 inches] <Insert dimension> above finished grade or surface at luminaire location. Cast conduit into base, and finish by troweling and rubbing smooth. Concrete materials, installation, and finishing are specified in Section 033000 "Cast-in-Place Concrete."

3.6 CORROSION PREVENTION

- A. Aluminum: Do not use in contact with earth or concrete. When in direct contact with a dissimilar metal, protect aluminum by insulating fittings or treatment.
- B. Steel Conduits: Comply with Section 260533 "Raceways and Boxes for Electrical Systems." In concrete foundations, wrap conduit with 0.010-inch-thick, pipe-wrapping plastic tape applied with a 50 percent overlap.

3.7 FIELD QUALITY CONTROL

- A. Inspect each installed luminaire for damage. Replace damaged luminaires and components.
- B. Perform the following tests and inspections:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
- 2. Verify operation of photoelectric controls.
- 3. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
- C. Luminaire will be considered defective if it does not pass tests and inspections.
- D. Prepare a written report of tests, inspections, observations, and verifications indicating and interpreting results. If adjustments are made to lighting system, retest to demonstrate compliance with standards.

3.8 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain luminaires and photocell relays.

END OF SECTION 265619

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 280500 - COMMON WORK RESULTS FOR ELECTRONIC SAFETY AND SECURITY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Electronic safety and security equipment coordination and installation.
- 2. Sleeves for raceways and cables.
- 3. Sleeve seals.
- 4. Grout.
- 5. Common electronic safety and security installation requirements.

1.3 DEFINITIONS

- A. EPDM: Ethylene-propylene-diene terpolymer rubber.
- B. NBR: Acrylonitrile-butadiene rubber.

1.4 SUBMITTALS

A. Product Data: For sleeve seals.

1.5 COORDINATION

- A. Coordinate arrangement, mounting, and support of electronic safety and security equipment:
 - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
 - 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
 - 3. To allow right of way for piping and conduit installed at required slope.
 - 4. So connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
- B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- C. Coordinate location of access panels and doors for electronic safety and security items that are behind finished surfaces or otherwise concealed. Access doors and panels are specified in Division 08 Section "Access Doors and Frames."
- D. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."."

1.6 QUALITY ASSURANCE

A. Third party agencies shall be amongst those accredited by the NCBCC (North Carolina Building Code Council) to Label Electrical & Mechanical Equipment".

PART 2 - PRODUCTS

2.1 SLEEVES FOR RACEWAYS AND CABLES

- A. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- C. Sleeves for Rectangular Openings: Galvanized sheet steel.
 - 1. Minimum Metal Thickness:
 - a. For sleeve cross-section rectangle perimeter less than 50 inches (1270 mm) and no side more than 16 inches (400 mm), thickness shall be 0.052 inch (1.3 mm).
 - b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches (1270 mm) and 1 or more sides equal to, or more than, 16 inches (400 mm), thickness shall be 0.138 inch (3.5 mm).

2.2 SLEEVE SEALS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Metraflex Co.
 - d. Pipeline Seal and Insulator, Inc.
 - 2. Sealing Elements: interlocking links shaped to fit surface of cable or conduit. Include type and number required for material and size of raceway or cable.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. Pressure Plates: Include two for each sealing element.
- 4. Connecting Bolts and Nuts: Of length required to secure pressure plates to sealing elements. Include one for each sealing element.

2.3 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

PART 3 - EXECUTION

3.1 COMMON REQUIREMENTS FOR ELECTRONIC SAFETY AND SECURITY INSTALLATION

- A. Comply with NECA 1.
- B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- D. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electronic safety and security equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- E. Right of Way: Give to piping systems installed at a required slope.

3.2 SLEEVE INSTALLATION FOR ELECTRONIC SAFETY AND SECURITY PENETRATIONS

- A. Electronic safety and security penetrations occur when raceways, pathways, cables, wireways, or cable trays penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- E. Cut sleeves to length for mounting flush with both surfaces of walls.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- F. Extend sleeves installed in floors 2 inches (50 mm) above finished floor level.
- G. Size pipe sleeves to provide 1/4-inch (6.4-mm) annular clear space between sleeve and raceway or cable, unless indicated otherwise.
- H. Seal space outside of sleeves with grout for penetrations of concrete and masonry
 - 1. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
- I. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants."
- J. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping."
- K. Roof-Penetration Sleeves: Seal penetration of individual raceways and cables with flexible boottype flashing units applied in coordination with roofing work.
- L. Aboveground, Exterior-Wall Penetrations: Seal penetrations using pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch (25-mm) annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- M. Underground, Exterior-Wall Penetrations: Install cast-iron pipe sleeves. Size sleeves to allow for 1-inch (25-mm) annular clear space between raceway or cable and sleeve for installing mechanical sleeve seals.

3.3 SLEEVE-SEAL INSTALLATION

- A. Install to seal exterior wall penetrations.
- B. Use type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

3.4 FIRESTOPPING

A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for electronic safety and security installations to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 07 Section "Penetration Firestopping."

END OF SECTION 280500

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

SECTION 283111 - DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes but is not limited to:
 - 1. Manual fire-alarm boxes.
 - 2. Smoke detectors.
 - 3. Duct smoke detectors.
 - 4. Heat detectors.
 - 5. Notification appliances.
 - 6. Extra materials.

1.3 DEFINITIONS

- A. LED: Light-emitting diode.
- B. NICET: National Institute for Certification in Engineering Technologies.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product, including furnished options and accessories.
 - 1. Include construction details, material descriptions, dimensions, profiles, and finishes.
 - 2. Include rated capacities, operating characteristics, and electrical characteristics.
 - 3. Provide UL file numbers documenting UL listing for purpose for every component of the system.
- B. Shop Drawings: For fire-alarm system.
 - 1. Include plans, elevations, sections, details, and attachments to other work.
 - 2. Comply with recommendations in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter in NFPA 72.
 - 3. Include voltage drop calculations for notification appliance circuits (NAC). Load visual NAC's to a maximum of 60% capacity to allow for additional devices or resetting candela output of devices provided.
 - 4. Include battery-size calculations.. Load batteries to a maximum of 60% capacity to allow for additional devices or resetting candela output of devices provided.
 - 5. Include performance parameters and installation details for each detector, verifying that each detector is listed for complete range of air velocity, temperature, and humidity possible when air-handling system is operating.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 6. Include 1/8" = 1'-0" scale floor plans to indicate final outlet locations showing address of each addressable device. Show size and route of cable and conduits.
- 7. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and locations. Indicate conductor sizes, indicate termination locations and requirements, and distinguish between factory and field wiring.
- 8. Detail assembly and support requirements.
- 9. Include input/output matrix.
- 10. Include performance parameters and installation details for each detector.
- 11. Verify that each duct detector is listed for complete range of air velocity, temperature, and humidity possible when air-handling system is operating.
- C. System Operation Description: Detailed description for this Project, including method of operation and supervision of each type of circuit and sequence of operations for manually and automatically initiated system inputs and outputs. Manufacturer's standard descriptions for generic systems are not acceptable.
- D. Field quality-control reports.
- E. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
 - 1. Comply with the "Records" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
 - 2. Provide "Record of Completion Documents" according to NFPA 72 article "Permanent Records" in the "Records" Section of the "Inspection, Testing and Maintenance" Chapter.
 - 3. Provide "As-Built" prints and PDF format copies of layout floor plans indicating all field revisions since shop drawing submittals. Updated prints shall have been made in CAD, not hand markups. Provide disk with AutoCAD compatible plans of As-Built plans.
 - 4. Record copy of site-specific software.
 - 5. Provide "Maintenance, Inspection and Testing Records" according to NFPA 72 article of the same name and include the following:
 - a. Frequency of testing of installed components.
 - b. Frequency of inspection of installed components.
 - c. Requirements and recommendations related to results of maintenance.
 - d. Manufacturer's user training manuals.
 - 6. Manufacturer's required maintenance related to system warranty requirements.
 - 7. Abbreviated operating instructions for mounting at fire-alarm control unit.
 - 8. Copy of NFPA 25.
 - 9. Device address list including plain text descriptions/locations, room names and numbers coordinated with Owner's actual designations, not necessarily those on the Contract Documents.
 - 10. Warranty: Signed copy of warranty and software agreement.
- 1.5 A documentation cabinet shall be installed at the system control unit or at another approved location at the protected premises for storage of all record documentation. Where the documentation cabinet is not in the same location as the system control unit, its location shall be

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

identified at the system control unit. The documentation cabinet shall be prominently labeled SYSTEM RECORD DOCUMENTS. (2013 NFPA 72 National Fire Alarm and Signaling Code Section 7.7.2).

1.6 QUALITY ASSURANCE

- A. Installer Qualifications:
 - 1. Personnel shall be trained and certified by manufacturer for installation of units required for this Project.
 - 2. Installation shall be supervised by personnel certified by NICET as fire-alarm Level III technician.
- B. Source Limitations for Fire-Alarm System and Components: Obtain fire-alarm system from single source from single manufacturer.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 1. Fire Alarm Systems and components performing release service shall be listed and labeled for that purpose.

1.7 EXTRA MATERIALS

- A. Provide extra materials described below that match products installed including installation. Uninstalled devices shall be packaged with protective covering for storage, identified with labels describing contents and turned over to the owner at the completion of the project.

 - 4. Indoor Horns/Speakers with Strobes Lights......4% of installed quantity
 - 5. Indoor Strobe-only Notification Appliances.......4% of installed quantity

 - 7. Isolation Modules / Isolation Bases......4% of installed quantity
 - 8. Addressable, Electronic Heat Detectors......4% of installed quantity
 - 9. Spot-Type Smoke Detectors / Sounder Bases......6% of installed quantity
 - 10. No spares are required for projected beam, air sampling, or duct smoke detectors
- B. Contractor shall itemize Extra Materials material and labor on the project Schedule of Values.

1.8 PROJECT CONDITIONS

- A. Perform a full test of any existing system prior to starting work unless system will be fully removed. Document any equipment or components not functioning as designed.
- B. Interruption of Existing Fire-Alarm Service: Do not interrupt fire-alarm service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary guard service according to requirements indicated:

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Notify **Owner** no fewer than ten business days in advance of proposed interruption of firealarm service.
- 2. Do not proceed with interruption of fire-alarm service without **Owner's** written permission.
- C. Existing Fire-Alarm Equipment: Maintain existing equipment fully operational until new equipment has been tested and accepted. As new equipment is installed, label it "NOT IN SERVICE" until it is accepted. Remove labels from new equipment when put into service, and label existing fire-alarm equipment "NOT IN SERVICE" until removed from the building.
- D. Equipment Removal: After acceptance of new fire-alarm system, remove existing disconnected fire-alarm equipment and wiring.
- E. Use of Devices during Construction: Protect devices during construction unless devices are placed in service to protect the facility during construction.

1.9 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace fire-alarm system equipment and components that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period: **Five** years from date of Final Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Existing system is a Simplex 4100ES.

2.2 MANUAL PULL STATIONS

- A. Description: Fabricated of plastic, and finished in red with molded, raised-letter operating instructions of contrasting color.
 - 1. Double-action mechanism requires two actions, such as a push and a pull, to initiate an
 - 2. Station Reset: Key or wrench operated; double pole, double throw; switch rated for the voltage and current at which it operates.
 - 3. Integral Addressable Module: Arranged to communicate manual-station status (normal, alarm, or trouble) to the FACP.

2.3 SYSTEM SMOKE DETECTORS

- A. General Requirements for System Smoke Detectors:
 - 1. Comply with UL 268; operating at 24-V dc, nominal.
 - 2. Detectors shall be two-wire type.
 - 3. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to fire-alarm control unit.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 4. Base Mounting: Detector and associated electronic components shall be mounted in a twist-lock module that connects to a fixed base. Provide terminals in the fixed base for connection to building wiring.
- 5. Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
- 6. Integral Visual-Indicating Light: LED type indicating detector has operated and power-on status.
- 7. Remote Control: Unless otherwise indicated, detectors shall be analog-addressable type, individually monitored at fire-alarm control unit for calibration, sensitivity, and alarm condition and individually adjustable for sensitivity by fire-alarm control unit.
 - a. Rate-of-rise temperature characteristic shall be selectable at fire-alarm control unit for 15 or 20 deg F (8 or 11 deg C) per minute.
 - b. Fixed-temperature sensing shall be independent of rate-of-rise sensing and shall be settable at fire-alarm control unit to operate at 135 or 155 deg F (57 or 68 deg C).
 - c. Provide multiple levels of detection sensitivity for each sensor.

B. Photoelectric Smoke Detectors:

- 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
- 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).

C. Duct Smoke Detectors: Photoelectric type complying with UL 268A.

- 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
- 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).
- 3. Environmental compensation, programmable sensitivity settings, status testing, and monitoring of sensor dirt accumulation for the duct smoke sensor shall be provided by the FACP.
- 4. The Duct Housing shall provide a supervised relay driver circuit for driving up to 15 relays with a single "Form C" contact rated at 7A@ 28VDC or 10A@ 120VAC. This auxiliary relay output shall be fully programmable (controlled by the FACP, not by the detector itself). Relay shall be mounted within 3 feet of HVAC control circuit.
- 5. Duct Housing shall provide a relay control trouble indicator Yellow LED.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 6. Duct Housing shall have a transparent cover to monitor for the presence of smoke. Cover shall secure to housing by means of four (4) captive fastening screws.
- 7. Duct Housing shall provide two (2) Test Ports for measuring airflow and for testing. These ports will allow aerosol injection in order to test the activation of the duct smoke sensor.
- 8. For maintenance purposes, it shall be possible to clean the duct housing sampling tubes by accessing them through the duct housing front cover.
- 9. Each duct smoke sensor shall have a Remote Test Station with an alarm LED and test switch. If the station is not located directly below the detector, provide permanent signage at the station indicating detector location.
- 10. Where located outdoors, provide NEMA 4X weatherproof duct housing enclosure that shall provide for the circulation of conditioned air around the internally mounted addressable duct sensor housing to maintain the sensor housing at its rated temperature range. The housing shall be UL Listed to Standard 268A.

2.4 HEAT DETECTORS

- A. General Requirements for Heat Detectors: Comply with UL 521.
- B. Heat Detector, Combination Type: Actuated by either a fixed temperature of 135 deg F (57 deg C) or a rate of rise that exceeds 15 deg F (8 deg C)] per minute unless otherwise indicated.
 - 1. Mounting: Twist-lock base interchangeable with smoke-detector bases.
 - 2. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to fire-alarm control unit.

2.5 NOTIFICATION APPLIANCES

- A. General Requirements for Notification Appliances: Connected to notification appliance signal circuits, equipped for mounting as indicated and with screw terminals for system connections.
 - 1. Combination Devices: Factory-integrated audible and visible devices in a single-mounting assembly, equipped for mounting as indicated and with screw terminals for system connections.
- B. Chimes, High-Level Output: Vibrating type, 81-dBA minimum rated output.
- C. Horns: Electric-vibrating-polarized type, 24-V dc; with provision for housing the operating mechanism behind a grille. Comply with UL 464. Horns shall produce a sound-pressure level of 90 dBA, measured 10 feet (3 m) from the horn, using the coded signal prescribed in UL 464 test protocol.
- D. Visible Notification Appliances: Xenon strobe lights comply with UL 1971, with clear or nominal white polycarbonate lens mounted on an aluminum faceplate. The word "FIRE" is engraved in minimum 1-inch- (25-mm-) high letters on the lens.
 - 1. Rated Light Output:
 - a. 15/30/75/110 cd, selectable in the field.
 - 2. Mounting: Wall mounted unless otherwise indicated.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 3. For units with guards to prevent physical damage, light output ratings shall be determined with guards in place.
- 4. Flashing shall be in a temporal pattern, synchronized with other units.
- 5. Strobe Leads: Factory connected to screw terminals.
- 6. Mounting Faceplate: Factory finished, white.

2.6 FIRE ALARM WIRE AND CABLE

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Comtran Corp.
 - 2. Draka USA.
 - 3. Genesis Cable Products; Honeywell International, Inc.
 - 4. Rockbestos-Suprenant Cable Corporation.
 - 5. West Penn Wire/CDT; a division of Cable Design Technologies.
- B. General Wire and Cable Requirements: NRTL listed and labeled as complying with NFPA 70, Article 760.
- C. Signaling Line Circuits: Twisted, shielded pair, size as recommended by system manufacturer.
- D. Non-Power-Limited Circuits: Solid-copper conductors with 600-V rated, 75 deg C, color-coded insulation.
 - 1. Low-Voltage Circuits: No. 16 AWG, minimum.
 - 2. Line-Voltage Circuits: No. 12 AWG, minimum.
- E. All fire alarm circuitry shall be run in conduit in accordance with Section 260533 "Raceways and Boxes."

PART 3 - EXECUTION

3.1 EQUIPMENT INSTALLATION

- A. Comply with NFPA 72 for installation of fire-alarm equipment.
- B. Smoke- or Heat-Detector Spacing:
 - 1. Comply with NFPA 72, "Smoke-Sensing Fire Detectors" Section in the "Initiating Devices" Chapter, for smoke-detector spacing.
 - 2. Comply with NFPA 72, "Heat-Sensing Fire Detectors" Section in the "Initiating Devices" Chapter, for heat-detector spacing.
 - 3. Spacing of detectors for irregular areas, for irregular ceiling construction, and for high ceiling areas shall be determined according to Appendix A [or Appendix B]in NFPA 72.
 - 4. HVAC: Locate detectors not closer than [3 feet (1 m)] [5 feet (1.5 m)] from air-supply diffuser or return-air opening.
- C. Duct Smoke Detectors: Comply with manufacturer's written instructions.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

- 1. Furnish duct smoke detectors and instructions for installation to the contractor performing work under Division 23.
- 2. Verify that each unit is listed for the complete range of air velocity, temperature, and humidity possible when air-handling system is operating.
- 3. After installation by Div 23, verify devices are installed in accordance with the manufacturer's instructions.
- 4. Provide circuitry and connections.
- D. Audible Alarm-Indicating Devices: Install not less than 6 inches (150 mm) below the ceiling. Install bells and horns on flush-mounted back boxes with the device-operating mechanism concealed behind a grille.
- E. Visible Alarm-Indicating Devices: Install at least 6 inches (150 mm) below the ceiling.
- F. Device Location-Indicating Lights: Locate in public space near the device they monitor.

3.2 WIRING INSTALLATION

- A. Wiring Method: Install wiring in metal raceway according to Division 26 Section "Raceways and Boxes." Conceal raceway except in unfinished spaces and as indicated.
- B. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by the manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with the fire alarm system to terminal blocks. Mark each terminal according to the system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.
- C. Cable Taps: Taps are specifically prohibit other than at device terminal blocks, or on terminal blocks in cabinets Use numbered terminal strips in cabinets or equipment enclosures where circuit connections are made.
- D. Color-Coding: Color-code fire alarm conductors differently from the normal building power wiring. Use one color-code for alarm circuit wiring and a different color-code for supervisory circuits. Color-code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Paint fire alarm system junction boxes and covers red.

3.3 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
- B. Install framed instructions in a location visible from fire-alarm control unit.

DCSD Solicitation No.: FAC2223-03 / Architect's Project No: 624003

3.4 GROUNDING

A. Ground fire-alarm control unit and associated circuits; comply with IEEE 1100. Install a ground wire from main service ground to fire-alarm control unit.


3.5 FIELD QUALITY CONTROL

- A. For existing systems, test 100% of the existing devices reworked in the renovation and 10% of the devices not touched by the renovation.
- B. Field tests shall be witnessed by authorities having jurisdiction.
- C. Tests and Inspections:
 - 1. Visual Inspection: Conduct visual inspection prior to testing.
 - a. Inspection shall be based on completed Record Drawings and system documentation that is required by NFPA 72 in its "Completion Documents, Preparation" Table in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter.
 - b. Comply with "Visual Inspection Frequencies" Table in the "Inspection" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72; retain the "Initial/Reacceptance" column and list only the installed components.
 - 2. System Testing: Comply with "Test Methods" Table in the "Testing" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
 - 3. Test audible appliances for the public operating mode according to manufacturer's written instructions. Perform the test using a portable sound-level meter complying with Type 2 requirements in ANSI S1.4.
 - 4. Test visible appliances for the public operating mode according to manufacturer's written instructions.
 - 5. Factory-authorized service representative shall prepare the "Fire Alarm System Record of Completion" in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter in NFPA 72 and the "Inspection and Testing Form" in the "Records" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
- D. Fire-alarm system will be considered defective if it does not pass tests and inspections. Take corrective action and retest until accepted by the AHJ.
- E. Prepare test and inspection reports.

3.6 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain fire-alarm system. Schedule training in 2 sessions at the Owner's convenience.

END OF SECTION 283111



2018 AHERA Reinspection For Darlington County School District Mayo High School 405 Chestnut Street Darlington, South Carolina

A 3-Year AHERA Reinspection of known or assumed asbestos containing material was performed per the requirements of the Asbestos Hazard Emergency Response at Mayo High School on February 13, 2018. The following highlights the findings of the survey and provides proper management planner recommendations for applicable areas.

Homogeneous Areas with a Changed Condition:

There are no materials with a changed condition.

Inspector Comments:

Although a reinspection was completed at this school, it does not guarantee that the previous sample data is accurate under current regulations. Before renovations are scheduled, all areas that will be disturbed must have the homogenous sample data checked for accuracy and/or be re-sampled.

The inspector would like to stress that all materials must be treated as asbestos containing material regardless of the year of installation until the documentation is shown that proves the material does not contain asbestos. Under South Carolina law a material that has been inspected or sampled more than three years prior, must be re-sampled or certified by a licensed inspector.

Management Planner Recommendations:

There are no recommendations at this time, other than to continue to maintain the asbestos-containing and/or assumed asbestos-containing materials in accordance with the AHERA Management Plan.

Darlington County School District Mayo High School Reinspection/2018 Page 1



Copies of all AHERA Inspection Reports must be maintained in the office of the Main Office of each school, as well in the office of the LEA. Any abatement of asbestos-containing materials from the school must be documented indicating the date, type of material, and the name of the abatement contractor.

Name of Inspector: Stanley Berry
Signature of Inspector:
Signature of Inspector:
SC-DHEC: <u>ASB-20411</u>
Name of Management Planner: Kay H. Horton
Signature of Management Planner:
SC-DHEC: ASB-23394
Name of LEA Designee: Ervin McElveen
Signature of LEA Designee:
Date of Implementation within Management Plan:







AHERA REINSPECTION TABLE

CRE JOB #: 15782-RIN

Location:

Mayo High School, 405 Chestnut St., Darlington, SC

Client:

Darlington County School District

DATE: 2/13/18

For each Homogeneous Area that has a changed condition, additional information has been included discussing the change. AHERA Categories (1-8) Legend:

1-Damaged or Sig. Damaged TSI, 2-Damaged Friable Surfacing ACM, 3-Sig. Damaged Friable Surfacing ACM, 4-Damaged or Sig. Damaged Friable Misc. ACM, 5-ACBM with Potential for Damage, 6-ACBM with Potential for Sig. Damage, 7-Remaining friable ACBM, 8-Non-friable ACM in good condition

Homogeneous Area #	Material Type	Previous Reinspection Assessment	Current Reinspection Assessment	Location/ Comments
HA06	TSI Hard Pipe Joint Insulation	_X NonFriable Condition: X Good Dam Sig. Dam. Potential For Disturbance: X Low _ Medium High	NonX_ Friable Good Current Condition Low Pot. For Disturbance 8 AHERA Category (1-8) No Changed Condition	Found in the cafeteria-above the suspended ceiling and Building 3-Classroom 314, above the suspended ceiling.
HA08	12"X12" Tan Vinyl Floor Tile & Mastic	_X_NonFriable Condition: X_Good Dam Sig. Dam. Potential For Disturbance: X_Low Medium High	X Non Friable Good Current Condition Low Pot. For Disturbance 8 AHERA Category (1-8) No Changed Condition	Found in Building 3 in the electrical room and room 308 (storage closet).
HA10	New 12"X12" Gray Vinyl Floor tile	_X_ Non Friable Condition: _X_ Good Dam Sig. Dam. Potential For Disturbance: _X_ Low Medium High	X Non Friable Good Current Condition Low Pot. For Disturbance 8 AHERA Category (1-8) No Changed Condition	Found in the main building-C-10, kitchen pantry, C- 14 and C-15. The music room and storage room have carpet. There are 12"X12" light gray vinyl floor tiles in the classrooms on the 2nd Floor. *Note: The 2012 report listed that 9"X9" white vinyl floor tile and mastic was found in the above areas. This material has since been removed.

SC Inspector License #___ASB-20411 Inspector: ___Stanley Berry____





AHERA REINSPECTION TABLE CRE JOB #: 15782-RIN

Location: Mayo High School, 405 Chestnut St., Darlington, SC

Client: Darlington County School District DATE: 2/13/18

For each Homogeneous Area that has a changed condition, additional information has been included discussing the change. AHERA Categories (1-8) Legend:

1-Damaged or Sig. Damaged TSI, 2-Damaged Friable Surfacing ACM, 3-Sig. Damaged Friable Surfacing ACM, 4-Damaged or Sig. Damaged Friable Misc. ACM, 5-ACBM with Potential for Damage, 6-ACBM with Potential for Sig. Damage, 7-Remaining friable ACBM, 8-Non-friable ACM in good condition

Homogeneous Area #	Material Type	Previous Reinspection Assessment	Current Reinspection Assessment	Location/ Comments
HA11	New 12"X12" Gray Vinyl Floor tile	X Non- Friable Condition: X Good Dam. Sig. Dam. Potential For Disturbance: X Low Medium High	X Non Friable Good Current Condition Low _ Pot. For Disturbance AHERA Category (1-8)No Changed Condition	Found in the maintenance building. *Note: The 2012 report listed that 9"X9" gray vinyl floor tile and mastic were found in the above areas. This material has since been removed.
HA16	12"X12" Green Vinyl Floor Tile	_X_ Non Friable Condition: X_ Good Dam Sig. Dam. Potential For Disturbance: X_ Low Medium High	X Non Friable Good _ Current Condition Low _ Pot. For Disturbance _ 8 _ AHERA Category (1-8) _ No _ Changed Condition	Found in Building 1-1st and 2nd Floor Janitor's Closets.
HA24	Fire Doors	_X_ Non Friable Condition: X_ Good Dam Sig. Dam. Potential For Disturbance: _X_ Low Medium High	X Non Friable Good Current Condition Low Pot. For Disturbance B AHERA Category (1-8) No Changed Condition	Found in the hallways of Building 1 and Building 3.

SC Inspector License #___ASB-20411 Inspector: ___Stanley Berry_____





AHERA REINSPECTION TABLE				CRE JOB #: 15782-RIN			
Location:	Mayo High School, 405 Chestnut St., Darlington, SC						
Client:	Darlington County School District			DATE: 2/13/18			
For each Homogeneous Area that has a changed condition, additional information has been included discussing the change. AHERA Categories (1-8) Legend: 1-Damaged or Sig. Damaged TSI, 2-Damaged Friable Surfacing ACM, 3-Sig. Damaged Friable Surfacing ACM, 4-Damaged or Sig. Damaged Friable Misc. ACM, 5-ACBM with Potential for Damage, 6-ACBM with Potential for Sig. Damaged Friable ACBM, 8-Non-friable ACM in good condition							
Homogeneous Area#	Material Type	Previous Reinspection Assessment	Current Reinspection Assessment	Location/ Comments			

SC Inspector License #___ASB-20411 Inspector: __Stanley Berry