

Collins Architectural Group, p.s.  
950 12<sup>th</sup> Avenue, Suite 200  
Longview, WA 98632

Addendum No. 4

Page No. 1 of 2

Date: July 18<sup>th</sup>, 2023

Project: R.A. Long High School  
Classroom Kitchen Remodel  
Longview, WA

**Notice to Contractor:**

The following changes in the Contract Documents, including the Drawings and Specifications, constitute this Addendum. All changes included in Addenda shall become a part of the Contract Documents for this Project. Any changes herein offset only the specific Drawings or Notes on Drawings or words or paragraphs in Specifications referenced to and the balance of the Drawings shall remain in full force.

**ARCHITECTURAL SPECIFICATION**

| <u>ITEM</u> | <u>SHEET NO./</u><br><u>SECTION NO.</u> | <u>DESCRIPTION</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-------------|-----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 4.0         | A3.0                                    | Clarification: In reference to floor plan note 9; the icemaker drain hose shall be piped to the existing waste piping for the adjacent sink upstream from the trap. An in-line pump shall be used to pump the drain water from the icemaker up into the existing waste piping. Provide the code-required air gap fitting before the icemaker drain line connects to the existing sink waste piping.                                                                                                                   |
| 4.1         | A3.0                                    | Revision: The three-compartment sink will need a larger waste line than is existing. See page 2 for the attached sketch showing the approximate location of the existing waste lines that will need to be connected to. Size waste line appropriately for the capacity of a three-compartment sink. This sink is not intended to be used for food prep. There is an existing crawl space below the floor of the kitchen. Access is provided from an adjacent space. There is a concrete floor within the crawl space. |

**END OF ADDENDUM No. 4**

