



2024 SUMMER HVAC IMPROVEMENTS AT EDISON MIDDLE SCHOOL

07/18/2023

Addendum # 2

This addendum is hereby a part of those documents and contracts, the same as if bound therein and it shall supersede anything contained in the original bid manual with which it might conflict.

1. Provide four new data drops in each classroom to replace the existing drops. The new drops will be CAT 6E serving the IDB board, wireless access point and two for the teacher. Replace all other wireless access points, printer locations, and one drop in each office. Existing cabling to be removed.
2. Tie up / and take down all existing Low voltage systems and devices except fire alarm devices. Demo existing fire alarm devices as needed and install new voice evacuation systems, cabling, and devices throughout entire building. Provide and install new duct/ smoke detector as required at new RTU's. Provide cabling and terminations to low pressure sensors at all new RTU's.

The end