



ADDENDUM 1

| | |
|-------------------------|-------------------------------------------------|
| RFP NUMBER: | TE1135 – Outside Plant Fiber Optic Construction |
| ADDENDUM NUMBER: | 1 |
| ADDENDUM ISSUED: | 09/25/2023 |

I. CHANGES & ADDITIONS

The original Request for Proposal No. TE1135: Outside Plant Fiber Optic Construction remains in effect except as revised by the following changes, which shall take precedence over anything to the contrary in the specifications.

- A. Page 28, Section VII, Attachment 1 – Cost Sheet has been added.

II. QUESTIONS & ANSWERS

The following questions are as they were presented to Park Hill School District. The answers to said questions have been answered as completely and accurately as possible.

Q1: Can you clarify what will be owner provided vs what will be contractor provided?

A1: **The hand holes, splices cases with trays, fiber, and innerduct will be provided. All other materials to complete installation will be contractor provided, including but not limited to duct couplers, duct plugs, fiber splice protection sleeves, tracer wire, mule tape, etc.**

Q2: Is tracer wire provided?

A2: **No, tracer wire is to be contractor provided.**

Q3: Is there preferred specifications for tracer wire?

A3: **Provide 12awg, soft-drawn solid copper tracer wire with orange HMWPE or HDPE insulation. Wire shall be continuous between hand holes, no splices allowed. Copper clad steel (CCS), THHN, stranded, bare copper, etc. will not be accepted.**

Q4: Interception points, are there existing splice casings?

A4: **Both interception points will require proposed splice cases. Existing fiber to be expressed through proposed splice cases, uncut.**



Q5: Per Map #4, will there be any existing enclosures?

A5: Please see A4.

Q6: Is splicing the responsibility of the contractor?

A6: Yes.

Q7: Who is your MODOT Inspector?

A7: We do not know who the MODOT inspector will be for this project.

Q8: What are your restoration standards?

A8: We will follow MODOT standards on MODOT right of way. For county right of way, we will follow Platte County restoration standards.

Q9: Who will provide the permitting for MODOT?

A9: The project owner is responsible for permitting MODOT.

Q10: Will you have a construction manager available daily?

A10: Yes.

Q11: PHSD reserves the right to limit the total value of all subcontractors to 60% - how lenient is the 60%?

A11: 60% is contractually required.

Q12: What prevailing wage do you require?

A12: Contractor and certified payroll are required to meet the requirements of the current Platte County, Missouri Prevailing Wage Law. The current Annual Wage Order is No. 30., incremental adjustments.



V. ACKNOWLEDGEMENT

Each bidder shall acknowledge receipt of this Addendum No. 1 of Request for Proposal No. *TE1135: Outside Plant Fiber Optic Construction* by his/her signature affixed hereto and shall attach this Addendum to the original bid submitted. Failure to sign and submit this addendum may render your bid Non-Responsive.

Certification by Bidder:

Signature: _____ Date: _____

Title: _____ Company: _____