

ADDENDUM NUMBER FIVE

FOR

**DISTRICT FIVE OF
LEXINGTON & RICHLAND COUNTIES
CHAPIN ELEMENTARY SCHOOL**

PREPARED BY

**CALLOWAY JOHNSON MOORE WEST (CJMW)
201 WEST MAIN STREET
LEXINGTON, SOUTH CAROLINA 29072**

AND

**SOUTHERN MANAGEMENT GROUP
1213 LADY STREET, FOURTH FLOOR (29201)
POST OFFICE BOX 1785
COLUMBIA, SOUTH CAROLINA 29202**

DATE OF ISSUE: April 13, 2009

TO: ALL PRIME BIDDERS OF RECORD

This addendum modified the Contract Documents only in the manner and to the extent stated herein and shown on any accompanying drawings and will become a part of the Contract Documents. Except as specified or otherwise indicated by this addendum, all work shall be in accordance with the basic requirements of the Contract Documents.

BIDDER SHALL ACKNOWLEDGE RECEIPT OF ADDENDUM IN THE SPACE PROVIDED ON THE BID FORM. FAILURE TO DO SO MAY CONSTITUTE INFORMALITY IN THE BID.

Item 1: CJMW Addendum Number Five consisting of 2 pages.

End of Addendum No. 5

This Portion of Addendum No. 5 includes the following:

Clarifications and Changes to Specifications: 8 Items

Clarifications and Changes to Drawings: 1 Item

Conditional Approved Equals: (Not including Prior Approvals Listed on Electrical Drawings): None

Attachments: None

CLARIFICATIONS AND CHANGES TO SPECIFICATIONS:

1. **Section 02514 PORTLAND CEMENT CONCRETE PAVING:**

Modify paragraph 3.11 to read:

3.11 SCHEDULES

A. Concrete Sidewalks: 3,000 psi 28 day concrete, 4 inches thick, Portland Cement, light broom finish.

B. Curb and Gutter: 3,000 psi 28 day concrete, in accordance with details, Portland Cement, light broom finish.

2. **Section 02514 PORTLAND CEMENT CONCRETE PAVING:**

Modify "END OF SECTION SOUTH CAROLINA STATE UNIVERSITY DEFERRED MAINTENANCE PHASE I STORM DRAINAGE UPGRADE PAGE 02514" to read: "END OF SECTION"

3. **Section 04810 Unit Masonry Assemblies – 2.06. C – Cavity Mortar Control:**

Add to end of paragraph: "Cavity mortar control is not indicated on drawings, however is to be installed per this specification section."

4. **Section 04810 Unit Masonry Assemblies – 1.04.E.2 – Extra Glazed Units**

Delete: "Extra Glazed Units

Replace with: "150 units comprised of up to three different colors. Of these units, 50 shall be special shapes."

5. **Section 04810 Unit Masonry Assemblies– 2.01.5 – Pre-Faced Units:**

Add paragraph: "d. Up to three (3) colors to be selected from manufacturer's full range".

6. **Section 07510 Built-Up Bituminous Roofing – 2.05 Deck Sheathing:**

Delete this paragraph in its entirety. There is no gypsum deck sheathing at roof.

7. **Section 09260 Gypsum Board Assemblies – 2.04.C -**

Delete this paragraph in its entirety: "C. Water-Resistive Barrier: As specified in Section 07260."

8. **Section 11410: Food Service Equipment – 1.01.B:**

Delete: "B. The Food Service Contract shall be by Owner under separate contract; however, the General Contractor shall be responsible for coordination and installation of primary utility connections for-Kitchen Equipment based on drawings to be provided by the Food Service Contractor."

Replace With: "B. The Food Service Contract shall be included as part of this bid and the itemized equipment specified in Part 2 of this section shall be provided by the awarded bidder to the owner."

CLARIFICATIONS AND CHANGES TO DRAWINGS:

1. **Drawing Sheet C7:**
Change the pavement section of the "Pavement Section without Curb and Gutter on the CES to CMS Road" to be 18" Compacted Subgrade @ 98% Standard Proctor Maximum Dry Density, Minimum (ASTM D-698), 6" Macadam Base Course, and 2 ½" Asphaltic Concrete Surface Course.

2. **Drawing Sheets CS4 and A201:**
Delete note: "Replace 145' with new fence to match adjacent play yard fence after construction:

Replace with: "After construction, replace 145' with new 4' fence per specification section 02821 to match existing play yard fence removed for construction fence.

END OF ADDENDUM 5