ADDENDUM NUMBER SIX

FOR

DISTRICT FIVE OF LEXINGTON & RICHLAND COUNTIES CHAPIN ELEMENTARY SCHOOL

PREPARED BY

CALLOWAY JOHNSON MOORE WEST (CJMW)
201 WEST MAIN STREET
LEXINGTON, SOUTH CAROLINA 29072

AND

SOUTHERN MANAGEMENT GROUP
1213 LADY STREET, FOURTH FLOOR (29201)
POST OFFICE BOX 1785
COLUMBIA, SOUTH CAROLINA 29202

DATE OF ISSUE: April 14, 2009

TO: ALL PRIME BIDDERS OF RECORD

This addendum modified the Contract Documents only in the manner and to the extent stated herein and shown on any accompanying drawings and will become a part of the Contract Documents. Except as specified or otherwise indicated by this addendum, all work shall be in accordance with the basic requirements of the Contract Documents.

BIDDER SHALL ACKNOWLEDGE RECEIPT OF ADDENDUM IN THE SPACE PROVIDED ON THE BID FORM. FAILURE TO DO SO MAY CONSTITUTE INFORMALITY IN THE BID.

Item 1: CJMW Addendum Number Six consisting of 1 page.

End of Addendum No. 6

This Portion of Addendum No. 6 includes the following:

Clarifications and Changes to Specifications: **1 Item**
Clarifications and Changes to Drawings: **None**
Conditional Approved Equals: **None**
Attachments: **None**

CLARIFICATIONS AND CHANGES TO SPECIFICATIONS:

1. **Section 16120:** Paragraph 3.1 B. (Previously modified by Addendum 4)

   Delete the second sentence in its entirety. In its place add: "Remove all existing voice or data cables in areas A and B (classroom pod areas). These cables shall be demolished entirely. All ETV cables shall remain. Any communications cables that remain shall be bundled at intervals not exceeding 10' and shall be coiled above the ceiling out of the way of new work. They shall be supported at intervals not exceeding 3' from structure not by ceiling, not by ceiling supports, not by other work."

END OF ADDENDUM 6