

Monthly Building Permit Issuance Report

Building permits that were issued in the last month.

Permit Status = Issued

Permit Date Range >= 10/1/2023

Permit Date Range <= 10/31/2023

Permit Department = Building

Report Totals

Number of Permits	JOB VALUE	Total Paid
116	\$3,053,120.97	\$46,301.80

Commercial Electrical

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01401	10 NUTMEG DR, Ellington, CT 06029	Issued	10/17/2023	\$140,000.00	\$30.00	Wire new building. Install a 600 amp main, install 18 meters for tenants and one owners panel, wire interior and exterior lighting. wire 18 bathrooms
BLD23-01351	117 WEST RD, Ellington, CT 06029	Issued	10/18/2023	\$3,750.00	\$75.00	Wire new hood duct with ansul system, wire dough mixer, reattach sign light,disconnect plugs behind hood, replace existing 2x2 lights with led.
BLD23-01366	78 ABBOTT RD, Ellington, CT 06029	Issued	10/18/2023	\$15,000.00	\$30.96	New Storage Building. Next to Building #1 and #2 built in last two years. New 320 amp electrical service underground to power building. 230 ft from road. 4 inch conduit. Two 200 amp breakers outside by meter socket to feed two 40 circuit 200 amp panels inside. Inside will consist of heating, lighting and outlets. Two conduits (2in)in ground, in slab for wiring inside building. CRS #14186212
3				\$158,750.00	\$135.96	

Commercial Mechanical

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01408	117 WEST RD, Ellington, CT 06029	Issued	10/26/2023	\$30,000.00	\$479.88	Install Captive Aire hood system
BLD23-01238	135 WEST RD, Ellington, CT 06029	Issued	10/16/2023	\$0.00	\$30.00	Install new HVAC roof-top units and rooftop exhaust fan per plans and specs.
BLD23-01453	29 MAIN ST, Ellington, CT 06029	Issued	10/26/2023	\$86,759.00	\$0.00	Replace 2 oil fired hot water boilers with condensing gas fired boilers and tie in new gas line to boilers.
BLD23-01460	29 MAIN ST, Ellington, CT 06029	Issued	10/26/2023	\$37,583.00	\$0.00	Furnish & install vrf split system air conditioning for upstairs offices
4				\$154,342.00	\$509.88	

Commercial Plumbing

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01390	117 WEST RD, Ellington, CT 06029	Issued	10/26/2023	\$4,100.00	\$61.92	Installation of an UL-300 approved wet chemical fire suppression system for the kitchen hood located at Holiday Restaurant and Pizza.
1				\$4,100.00	\$61.92	

Commercial Renovation

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01107	80 MEADOW BROOK RD, Ellington, CT 06029	Issued	10/23/2023	\$600,000.00	\$9,520.20	We are converting an existing barn into the Modern Milkman milk bottling plant.
1				\$600,000.00	\$9,520.20	

Deck/Shed/Accessory Structure

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-00057	65 MIDDLE RD, Ellington, CT 06029	Issued	10/31/2023	\$5,500.00	\$190.92	24 x 24 pole barn with dirt floor
BLD23-01396	20 FARMSTEAD LN, Ellington, CT 06029	Issued	10/17/2023	\$2,500.00	\$144.48	We will remove the existing deck and replace it with a smaller version only on the driveway side of the home. We will install a 4' X 8' deck with 6 stairs to replace what is there now. We will pour a 4' X 4' Concrete pad for the landing. For our support, we will use (2) Techno Post Helical piers spaced 6' apart and 3' from the house with 6" X 6" posts for support. We will use 2" X 8" construction 16" on center. We will use a 3-ply 2" X 8" X 8' Support beam with a 6" to 8" cantilever. The ledger board will be secured with 5" ledger locks, 2 ledger locks per bay. We will use Simpson hurricane ties to secure the deck to the ledger along with joist hangers for each joist. We will build stairs with 7" rise X 11" tread per code. The railings will be 36" tall and the spindles will be less than 4" apart. We will put a secondary rail on 1 side of the stairs with returns on both ends.
BLD23-01370	4 DAISY LN, Ellington, CT 06029	Issued	10/23/2023	\$26,000.00	\$615.00	install of a roof above the existing deck to create a 3 season porch
BLD23-01373	6 MOSER DR, Ellington, CT 06029	Issued	10/16/2023	\$12,000.00	\$195.00	Replace rotted wood and railings of existing 12'+16' deck and stairs.
BLD23-01340	11 PIONEER DR, Ellington, CT 06029	Issued	10/18/2023	\$9,972.75	\$252.84	Remove existing 8x12 shed and install new 12x20 shed from The Barn Yard.
BLD23-01336	120 REEVES RD, Ellington, CT 06029	Issued	10/23/2023	\$16,000.00	\$335.00	20X24 covered Porch and 8X10 deck connected to the porch off the back of the house.
BLD23-01304	249 CRYSTAL LAKE RD, Ellington, CT 06029	Issued	10/25/2023	\$50,000.00	\$975.00	Construct a 18x22 accessory dwelling unit with a 10x20 Lean to Porch.
BLD23-01320	8 FROG HOLLOW RD, Ellington, CT 06029	Issued	10/26/2023	\$44,271.57	\$900.00	Installation of 14' x 24' shed with attached greenhouse.
BLD23-01291	16 ANGEL TRACE, Ellington, CT 06029	Issued	10/31/2023	\$36,500.00	\$804.96	Extending the existing deck off the back of the house. The current deck is really more of a landing area (approx 50 sq ft). Planning for an L-shaped deck, approx 995 sq. feet. Work will most likely be done in phases over the span of a year.

Deck/Shed/Accessory Structure

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01332	6 HILLSDALE DR, Ellington, CT 06029	Issued	10/16/2023	\$30,000.00	\$675.00	Demo and dispose of existing multi-level deck. Excavate and replace sewer outlet pipe. Fill in lower level with gravel and compact. Install 8 new piers in two rows and pressure treated framing. Install composite decking. The new deck will be 16'X24' with a pressure treated rim. The stairs will be composite and the risers will be pressure treated. We will install a powder coated aluminum railing to close the end of decking and on the stairs with a self-closing gate.
10				\$232,744.32	\$5,088.20	

Other

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01301	7 NUTMEG DR, Unit A5, Ellington, CT 06029	Issued	10/11/2023	\$0.00	\$80.00	The company name is "Off-Road Fabrication LLC". The LLC is registered with the State of Connecticut. This is part-time for the Owner, Jason Legault. The fabrication will consist of pipe bending and race car frames only. There will be no foot traffic.
BLD23-01325	24 WAPPING WOOD RD, Ellington, CT 06029	Issued	10/11/2023	\$2,000.00	\$129.00	installing a portico above front door. This portico is actually a smaller footprint of what is currently there now so I am not getting closer to the property lines - I am actually getting farther away. It will extend 10 feet above ground level though (at its peak)
BLD23-01334	5 BANCROFT RD, Ellington, CT 06029	Issued	10/11/2023	\$0.00	\$82.56	Home Occupation - Landscape Business
BLD23-01225	12 MAIN ST, Unit 7, Ellington, CT 06029	Issued	10/11/2023	\$0.00	\$82.56	Treatment facility for Naturopathic Doctors. No work or major renovations need to be completed.
4				\$2,000.00	\$374.12	

Residential Electrical

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01383	10 BARBARAS WAY, Ellington, CT 06029	Issued	10/11/2023	\$1,000.00	\$30.96	Wiring for outdoor condenser, GFI outlet.
BLD23-01393	105 MAIN ST, Ellington, CT 06029	Issued	10/12/2023	\$4,845.00	\$30.96	200 amp service upgrade and kitchen/ dining room remodel.
BLD23-01385	18 STEIN RD, Ellington, CT 06029	Issued	10/11/2023	\$1,500.00	\$46.44	Rewire basement. With existing laundry wire 8 new outlets 4 recessed lights and wire furnace.
BLD23-01388	18 CRANBERRY LN, Ellington, CT 06029	Issued	10/11/2023	\$0.00	\$30.96	200 amp Service Wire 2500 sq ft house, Auto switch for gen installed CRS # 14872952
BLD23-01410	237 SANDY BEACH RD, Ellington, CT 06029	Issued	10/16/2023	\$200.00	\$30.96	install production meter CRS # 14931387
BLD23-01414	14 PRIVATE GROUNDS1, Ellington, CT 06029	Issued	10/16/2023	\$950.00	\$30.96	Install temporary service.
BLD23-01415	16 MILLER LN, Ellington, CT 06029	Issued	10/16/2023	\$575.00	\$30.96	ADD SERVICE GFCI BY CONDENSER, SNAKE NEW T-STAT

Residential Electrical

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01335	7 HOTEL LAKE RD, Ellington, CT 06029	Issued	10/2/2023	\$1,270.00	\$46.44	Wire a 3 ton Dakin heat pump. This includes a disconnect and a flex whip. Wire a 120volt weather resistant GFCI outlet next to condenser.
BLD23-01422	35 CRYSTAL RIDGE DR, Ellington, CT 06029	Issued	10/18/2023	\$950.00	\$30.96	Add GFI service outlet outside and in attic Change A/C breaker Wire air handler
BLD23-01352	55 HAYES AVE, Ellington, CT 06029	Issued	10/3/2023	\$950.00	\$30.00	Remove and reinstall underground service
BLD23-01353	6 GARNET LN, Ellington, CT 06029	Issued	10/3/2023	\$0.00	\$30.00	200 amp service, branch circuit wiring
BLD23-01375	4 VALLEY FARMS RD, Ellington, CT 06029	Issued	10/11/2023	\$1,900.00	\$46.44	100 amp service, installing 60 amp breaker at the main panel. Then, running #6s to the emporia EVSE set to 48amp and mounted in the garage.
BLD23-01367	267 JOBS HILL RD, Ellington, CT 06029	Issued	10/11/2023	\$0.00	\$30.96	Wiring for HVAC system
BLD23-01368	28 OVERHILL RD, Ellington, CT 06029	Issued	10/11/2023	\$9,800.00	\$30.96	Wire outlets, switches and light fixtures to code for new home. Wire all appliances. Wire one new 200 amp underground service.
BLD23-01362	186 ABBOTT RD, Ellington, CT 06029	Issued	10/4/2023	\$7,000.00	\$123.84	Installing 10KW generator along with 100a 16 circuit critical loads panel with 2 load shedding modules for air handler and water heater. Installing: 10Kw generator, Generac 7171 10kw air cooled standby generator aluminum enclosure g force engine wifi enabled. Generac RXG16EZA1W 100a rated 16ckt automatic transfer switch 2 Generac 7000 Smart Management Modules
BLD23-01327	3 GERALDINE DR, Ellington, CT 06029	Issued	10/2/2023	\$200.00	\$30.96	install production meter CRS#14614827
BLD23-01331	24 WAPPING WOOD RD, Ellington, CT 06029	Issued	10/3/2023	\$2,000.00	\$30.96	Electrical wiring for the new addition. Outlets, switches, a fan, recessed lights and then connect to fuse box where there are open circuits to use. Edited to add: Upgrade to 200 amp Run 220 power to disconnect on to hot tub Run 220 power to disconnect going to mini split on wall Run wires to manually have a connection to a generator if needed Dig 24 inch depth ditch to provide power from house to outside shed
17				\$33,140.00	\$663.72	

Residential Mechanical

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01462	7 WHEELOCK RD, Ellington, CT 06029	Issued	10/26/2023	\$12,000.00	\$201.24	Installation of a ductless heat pump, 24K btu
BLD23-01479	29 ELIZABETH ST, Ellington, CT 06029	Issued	10/31/2023	\$2,000.00	\$46.44	run gas line and install vent free gas log set into existing masonry fireplace
BLD23-01486	75 HOPKINS RD, Ellington, CT 06029	Issued	10/31/2023	\$18,000.00	\$294.12	Heat pump installation
BLD23-01488	26 LADD RD, Ellington, CT 06029	Issued	10/31/2023	\$2,000.00	\$30.96	Install (1) 120 above ground propane tank and new gas line to gas log provided by others.
BLD23-01491	7 GARNET LN, Ellington, CT 06029	Issued	10/31/2023	\$0.00	\$30.96	Rough in 205' of 3/4" poly gas line from existing underground 1000 gallon propane tank to pool heater & 2-outdoor fire features.

Residential Mechanical

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01493	57 MIDDLE RD, Ellington, CT 06029	Issued	10/31/2023	\$8,746.00	\$154.80	furnish and install 1 new propane fired warm air furnace with 5 ton heatpump condenser, 5 ton coil and new Wifi thermostats.
BLD23-01435	6 GARNET LN, Ellington, CT 06029	Issued	10/23/2023	\$0.00	\$30.96	Install 1-500 gallon underground propane tank & rough in 15' of gas line.
BLD23-01437	8 BROOK CROSSING, Ellington, CT 06029	Issued	10/23/2023	\$4,990.00	\$92.88	install 2 275 gallon oil tanks in the basement
BLD23-01380	52 EGYPT RD, Ellington, CT 06029	Issued	10/11/2023	\$4,500.00	\$92.88	Install 500 gallon above ground propane tank & gas line to greenhouse heater.
BLD23-01442	28 OVERHILL RD, Ellington, CT 06029	Issued	10/23/2023	\$0.00	\$30.96	Install Lennox high efficiency gas furnace with air conditioning. All necessary ductwork. All gas piping.
BLD23-01468	20 RIDGEVIEW DR, Ellington, CT 06029	Issued	10/30/2023	\$7,632.00	\$139.32	Install Peerless w/bv e 03 cast iron boiler in direct replacement.
BLD23-01363	213 WEST RD, Ellington, CT 06029	Issued	10/4/2023	\$11,866.00	\$201.24	Installation of Thermopride oil furnace model # OL8FA119.
BLD23-01369	28 WINDSOR WALK, Ellington, CT 06029	Issued	10/11/2023	\$2,000.00	\$46.44	run gas line to direct vent space heater
BLD23-01376	267 JOBS HILL RD, Ellington, CT 06029	Issued	10/11/2023	\$0.00	\$30.96	Install gas piping for gas furnace
BLD23-01341	22 GREEN ST, Ellington, CT 06029	Issued	10/2/2023	\$3,875.00	\$77.40	replacing oil tank
BLD23-01423	1 WINDMILL RD, Ellington, CT 06029	Issued	10/18/2023	\$17,714.00	\$294.12	Installation of Energy Kinetics Resolute boiler model # EK1R+.
BLD23-01420	39 BRIDGE ST, Ellington, CT 06029	Issued	10/18/2023	\$28,599.00	\$464.40	Installation of Mitsubishi ductless heat pump model MXZ-SM48NAHZ with 5 wall mount air handlers
BLD23-01421	5 CANTOR KNOLL, Ellington, CT 06029	Issued	10/18/2023	\$12,800.00	\$216.72	Installation of American Standard AC model # 4A7A4060N1000A
BLD23-01411	107 MAIN ST, Ellington, CT 06029	Issued	10/16/2023	\$12,000.00	\$195.00	Will install new Viessmann Wall hung boiler. This boiler is Model #B1HE-199. This boiler is 199,00 BTUs. It will replace 3 old gas boilers all 45,00 BTU in put. Totaling 135,000 BTUs. Old boilers are a net of 37,000 BTU input making a total of 111,000 BTUs. In future we will be adding another apartment after oil boiler goes bad. Will use existing gas line to use for new boiler. We may in future add water heaters to this system.
BLD23-01412	3 KATHERINE WAY, Ellington, CT 06029	Issued	10/16/2023	\$7,888.00	\$139.32	Installation of American Standard gas furnace model # S9X1B080U4SBA
BLD23-01399	6 GARNET LN, Ellington, CT 06029	Issued	10/23/2023	\$22,000.00	\$30.96	Install Lennox high efficiency gas furnace with air conditioning. All necessary ductwork. All gas piping.
BLD23-01400	113 SHENIPSIT ST, Ellington, CT 06029	Issued	10/12/2023	\$11,700.00	\$201.24	Remove current oil fired boiler and replace with a new oil fired boiler.
BLD23-01404	16 BRONISZ DR, Ellington, CT 06029	Issued	10/23/2023	\$10,000.00	\$170.28	To replace ac coil and condenser with a bosch ac coil and condenser heat pump
BLD23-01387	267 JOBS HILL RD, Ellington, CT 06029	Issued	10/11/2023	\$1,100.00	\$30.96	place (4) 120g lp tanks to stub out

Residential Mechanical

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01397	28 OVERHILL RD, Ellington, CT 06029	Issued	10/25/2023	\$1,000.00	\$30.96	Install 1-500 gallon underground propane tank & gas line to house & connect to approved plumbers stub out.
BLD23-01382	10 BARBARAS WAY, Ellington, CT 06029	Issued	10/11/2023	\$23,438.00	\$387.00	Install 4 ton minisplit heatpump condenser w 3 ton air handler in attic and 1 minisplit
26				\$225,848.00	\$3,662.52	

Residential New

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01195	3 GARNET LN, Ellington, CT 06029	Issued	10/23/2023	\$282,020.00	\$4,470.00	Single family home with 4 bedrooms, 3 car garage, and 2614 sq.ft. of living space.
1				\$282,020.00	\$4,470.00	

Residential Plumbing

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01050	9 TREE TOP RD, Ellington, CT 06029	Issued	10/2/2023	\$0.00	\$30.00	Building rough plumbing DWV. All water lines, water heater, outside faucets. And complete plumbing and finish
BLD23-01365	17 LANZ LN, Ellington, CT 06029	Issued	10/11/2023	\$3,000.00	\$61.92	Remove and replace the existing water heater with new A.O. Smith ENS-50 110 water heater.
BLD23-01417	9 JUSTIN DR, Ellington, CT 06029	Issued	10/17/2023	\$0.00	\$30.96	New plumbing for kitchen and bathroom renovations
BLD23-01339	105 MAIN ST, Ellington, CT 06029	Issued	10/2/2023	\$0.00	\$30.00	Kitchen remodel job. Replace hot water baseboard heating. Install new kitchen sink & fixtures.
BLD23-01405	90 REEVES RD, Ellington, CT 06029	Issued	10/16/2023	\$983.74	\$30.96	Run 15ft of 1/2" copper line for generator
BLD23-01485	18 CRANBERRY LN, Ellington, CT 06029	Issued	10/31/2023	\$0.00	\$30.00	Complete rough to finish plumbing as per blueprint specifications. Plumbing materials to consist of ABS DWV pipe and fittings. Uponor aquapex water pipe and fittings. PVC pipe and fittings for radon.
6				\$3,983.74	\$213.84	

Residential Renovation

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01448	8 RANDY RD, Ellington, CT 06029	Issued	10/25/2023	\$11,040.00	\$201.24	Roof replacement 23sq, strip and re-shingle GAF timberline HDZ, Ice and water shield 6'. tape plywood seams if applicable.
BLD23-01449	10 KETCHBROOK LN, Ellington, CT 06029	Issued	10/25/2023	\$13,650.00	\$232.20	Roof replacement 26sq, strip and re-shingle GAF timberline HDZ, Ice and water shield 6'. tape plywood seams if applicable.

Residential Renovation

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01381	2 FLORENCE AVE, Ellington, CT 06029	Issued	10/16/2023	\$23,187.74	\$387.00	Remove existing sections of roofing. Full ice/water shield Synthetic moisture barrier to balance. Tape all plywood seams where applicable. Install GAF Timberline shingles. Total squares 28. Roof diagram to be uploaded. Areas in yellow and orange are is the area of work. Dormer repair: Remove the existing aluminum siding from dormers and store safely for reinstall. New house wrap to be installed on all dormer walls.All dormer flashing to be replaced with new aluminum step flashing and white apron flashing. Ice and water protection to run of 18" of all dormer walls. caulk dormer windows. Reinstall the existing siding on dormers once roofing is complete.
BLD23-01377	47 SCHOOL HOUSE RD, Ellington, CT 06029	Issued	10/11/2023	\$2,600.00	\$60.00	Replace 3 double hung windows with 3 - 35X52 casement style 400 series windows. Size remaining the same. No structural changes.
BLD23-01374	4 PIONEER DR, Ellington, CT 06029	Issued	10/11/2023	\$5,000.00	\$92.88	Add laundry and shower to existing bath
BLD23-01372	2 VINAY COURT, Ellington, CT 06029	Issued	10/24/2023	\$8,000.00	\$120.00	Adding a 240 sq.ft. room in the basement for office space/rec room. No bedrooms permitted.
6				\$63,477.74	\$1,093.32	

Roofing/Siding/Windows/Doors

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01342	23 DOGWOOD LN, Ellington, CT 06029	Issued	10/11/2023	\$15,600.00	\$255.00	Strip roof of all roofing materials down to plywood and place in on site dumpster. Replace any damaged plywood as necessary. Apply 2 rows of ice and water shield to all eaves. Cover remainder of roof with synthetic underlayment. Install metal drop and rake edge on all roof eaves and rakes. Replace vent boots and flash in and do any other necessary. Cap ridges with Timber tex hip and ridge caps. Install 2 new skylights, with all new flashing.
BLD23-01344	403 SOMERS RD, Ellington, CT 06029	Issued	10/11/2023	\$14,300.00	\$247.68	Remove all asphalt roofing from house. Install 100% of ice and water over wood deck. Install Timberline HDZ or Owens Corning TruDefinition lifetime architectural shingles to include metal drip, rake edge. 28 sqrs
BLD23-01384	50 GRAND BLVD, Ellington, CT 06029	Issued	10/11/2023	\$17,500.00	\$294.12	strip existing roof down to roof deck install ice & water (6') at all eaves install seam tape at all plywood joints synthetic underlayment over entire roof deck install new ridge vent if needed and 32.9 sq of shingles
BLD23-01398	45 HILLSIDE DR, Ellington, CT 06029	Issued	10/12/2023	\$12,000.00	\$195.00	Remove wood siding, install insulation and vinyl siding. No shutters, no gutters. Homeowner will take care of that.
BLD23-01395	7 ROSA CT, Ellington, CT 06029	Issued	10/16/2023	\$21,342.12	\$356.04	Removing existing Roof to wood Installing new GAF Architectural single
BLD23-01389	51 GRISWOLD RD, Ellington, CT 06029	Issued	10/16/2023	\$21,840.00	\$356.04	Remove all asphalt roofing from house. Install 100% of ice and water. Install Timberline HDZ or Owens Corning TruDefinition lifetime architectural shingles to include metal drip, rake edge, and ridge vent (if applicable). 45 sqrs
BLD23-01406	5 LEWIS CIR, Ellington, CT 06029	Issued	10/16/2023	\$6,930.00	\$123.84	Roof replacement 14sq, strip and re-shingle GAF timberline HDZ, Ice and water shield 6', tape plywood seams if applicable.
BLD23-01402	87 SHENIPSIT ST, Ellington, CT 06029	Issued	10/16/2023	\$7,300.00	\$139.32	Strip off all existing asphalt shingles.(13sq) Install 6ft ice and water from the bottom of the roof. Put the 4" tape on the seams of the plywood and cover with 15lb felt paper. Install new GAF architectural asphalt shingles.

Roofing/Siding/Windows/Doors

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01403	121 PINNEY ST, Ellington, CT 06029	Issued	10/18/2023	\$29,850.00	\$479.88	We are removing old windows and replacing with new construction Harvey windows We are removing existing vinyl siding and replacing with new double 4 vinyl siding
BLD23-01409	16 RIDGEVIEW DR, Ellington, CT 06029	Issued	10/16/2023	\$12,000.00	\$201.24	Strip roof, install 6' of ice and water at eave, 3' in valley; tape all plywood seams, if applicable; install synthetic underlayment, new drip and rake edge, starter strip and new architectural shingles; re-flash chimney with lead; 26 squares
BLD23-01455	200 WEST RD, Ellington, CT 06029	Issued	10/26/2023	\$481,000.00	\$7,230.00	Strip roof, install 6' of ice and water at eave, 3' in valley; tape all plywood seams, if applicable; install synthetic underlayment, new drip and rake edge, starter strip and new architectural shingles; re-flash chimney with lead; 12 buildings total
BLD23-01467	20 RANDY RD, Ellington, CT 06029	Issued	10/26/2023	\$7,000.00	\$123.84	•remove existing roofing shingles from entire home and garage •inspect all plywood for rot or deterioration •install ice and water shield protection on entire roof surface •install f8 style drip edge and OC starter course shingles along the entire roof perimeter •replace vent pipe flashings with new flashing boots and new bathroom fan vent •existing skylight to stay in place •remove skylight flashing and reinstall after weatherproofing barrier is installed •assess all wall flashings and replace as necessary •install new lead counter flashing on the chimney •install ridge cap shingles at the roof peaks ****Install GAF timberline HDZ 50 year architectural roof shingles- 14 squares
BLD23-01358	6 OVERLOOK PASS, Ellington, CT 06029	Issued	10/4/2023	\$19,800.00	\$325.08	Remove the existing roof of 31 squares, install 6 feet of ice/water on all eaves, install seam tape on remaining plywood, install F-8 drip metal, install synthetic underlayment, and install 30-year arches with 6 nails per shingle, will provide underlayment photos
BLD23-01478	31 MANHATTAN RD, Ellington, CT 06029	Issued	10/30/2023	\$16,825.00	\$278.64	Strip roof, install 6' of ice and water at eave, 3' in valley; tape all plywood seams, if applicable; install synthetic underlayment, new drip and rake edge, starter strip and new architectural shingles; re-flash chimney with lead; 30 squares
BLD23-01482	5 ROTHE LN, Ellington, CT 06029	Issued	10/31/2023	\$30,000.00	\$479.88	Complete roofing system with full ice and water.
BLD23-01494	48 MAPLE ST, Ellington, CT 06029	Issued	10/31/2023	\$17,600.00	\$294.12	Strip roof, install 6' of ice and water at eave, 3' in valley; tape all plywood seams, if applicable; install synthetic underlayment, new drip and rake edge, starter strip and new architectural shingles; re-flash chimney with lead; replace 4 skylights; 20 squares
BLD23-01489	469 SOMERS RD, Ellington, CT 06029	Issued	10/31/2023	\$19,975.00	\$325.08	Strip roof, install 6' of ice and water at eave, 3' in valley; tape all plywood seams, if applicable; install synthetic underlayment, new drip and rake edge, starter strip and new architectural shingles; re-flash chimney with lead; 40 squares
BLD23-01471	87 MUDDY BROOK RD, Ellington, CT 06029	Issued	10/30/2023	\$23,719.00	\$387.00	Replace 10 windows; no structural changes
BLD23-01472	22 CHERRYWOOD DR, Ellington, CT 06029	Issued	10/30/2023	\$13,981.00	\$232.20	Replace 5 windows; no structural changes
BLD23-01473	6 OAKWOOD CIR, Ellington, CT 06029	Issued	10/30/2023	\$17,350.00	\$294.12	Complete roof system replacement with ice and water over the whole roof.
BLD23-01474	22 MIDDLE RD, Ellington, CT 06029	Issued	10/30/2023	\$4,271.00	\$92.88	Replace 1 entry door; no structural changes
BLD23-01475	152 SADDs MILL RD, Ellington, CT 06029	Issued	10/30/2023	\$7,731.00	\$139.32	Replace 1 window and 1 entry door; no structural changes
BLD23-01476	46 WAPPING WOOD RD, Ellington, CT 06029	Issued	10/30/2023	\$9,800.00	\$170.28	Strip roof, install 6' of ice and water at eave, 3' in valley; tape all plywood seams, if applicable; install synthetic underlayment, new drip and rake edge, starter strip and new architectural shingles; re-flash chimney with lead; 15 squares

Roofing/Siding/Windows/Doors

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01445	94 TRIPP RD, Ellington, CT 06029	Issued	10/31/2023	\$9,000.00	\$150.00	Remove existing shingles, 2 layers of ice and water at eaves, tape all plywood joints, and cover with synthetic felt paper. Install new 30-year architectural shingle with ridge vent.
BLD23-01431	9 MIDDLE BUTCHER RD, Ellington, CT 06029	Issued	10/23/2023	\$13,000.00	\$216.72	rip and replace shingles 20 squares total house garage and barn
BLD23-01438	111 HOFFMAN RD, Ellington, CT 06029	Issued	10/23/2023	\$16,075.00	\$278.64	Strip roof, install 6' of ice and water at eave, 3' in valley; tape all plywood seams, if applicable; install synthetic underlayment, new drip and rake edge, starter strip and new architectural shingles; re-flash chimney with lead; 28 squares
BLD23-01439	21 BROCKWAY RD, Ellington, CT 06029	Issued	10/23/2023	\$27,218.31	\$448.92	Strip roof, install 6' of ice and water at eave, 3' in valley; tape all plywood seams, if applicable; install synthetic underlayment, new drip and rake edge, starter strip and new architectural shingles; re-flash chimney with lead; 35 squares
BLD23-01326	98 PINNACLE RD, Ellington, CT 06029	Issued	10/2/2023	\$24,660.54	\$402.48	Remove existing shingles and replace with 30 square new architectural asphalt shingles following code and manufacturer's recommendations. Install Ice and water shield as required by code and 4" polymer membrane tape on deck seams as necessary.
28				\$917,667.97	\$14,517.36	

Solar Permit

RECORD ID	ADDR FULL LINE#	STATUS	DATE STATUS	JOB VALUE	TOTAL PAID	DESCRIPTION
BLD23-01328	11 CHARTER RD, Ellington, CT 06029	Issued	10/2/2023	\$61,847.76	\$975.24	roof mounted solar array of 39 panels @ 14.04 kW/DC
BLD23-01477	20 EAST CIDER MILL RD, Ellington, CT 06029	Issued	10/30/2023	\$34,000.00	\$541.80	Installation of 24 roof mounted solar panels.7.6 KW
BLD23-01481	16 MEADOW BROOK RD, Ellington, CT 06029	Issued	10/30/2023	\$19,440.00	\$325.08	Install 16 rooftop solar panels 6.48kW
BLD23-01416	20 STEIN RD, Ellington, CT 06029	Issued	10/18/2023	\$54,675.00	\$866.88	Install 45 rooftop solar panels 18.2kW
BLD23-01407	10 ANTHONY WAY, Ellington, CT 06029	Issued	10/16/2023	\$34,100.00	\$557.28	Installation and wiring of a roof mounted 8.200kW grid tied solar PV system consisting of (20) SunPower SPR-M410-BLK-H-AC modules and inverters.
BLD23-01357	6 OVERLOOK PASS, Ellington, CT 06029	Issued	10/4/2023	\$74,239.24	\$1,176.48	Installation of new roof mounted 9.315kw Photovoltaic System
BLD23-01337	26 SUNSET RD, Ellington, CT 06029	Issued	10/2/2023	\$45,000.00	\$712.08	Installation of 30 roof mounted solar panels, 12.150 kW with required structural upgrades: knee wall, sistering
BLD23-01378	9 GRASSY HILL RD, Ellington, CT 06029	Issued	10/11/2023	\$23,900.00	\$387.00	Installation and wiring of a roof mounted 6.090kW grid tied solar PV system consisting of (14) SunPower SPR-M435-H-AC modules and inverters. This is an add on to an existing system.
BLD23-01379	22 CEDARWOOD DR, Ellington, CT 06029	Issued	10/11/2023	\$27,845.20	\$448.92	NEW GRID-INTERACTIVE PHOTOVOLTAIC SYSTEM SYSTEM SIZE :21.7 KW DC STC (62) LG NEON R LG350Q1C-A5(350W) SOLAR MODULES (62) S440 SOLAREEDGE POWER OPTIMIZER (2) SOLAREEDGE SE7600H ENERGY HUB INVERTER
9				\$375,047.20	\$5,990.76	