

1075 Third Street East, Saint Paul, MN 55106

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
H1A Sprayed-On Structural Fireproofing Cellulose (1991)						Total Amount - 30000 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-23, 24, 25. 020110-MV-02, 03, 04, 05, 06, 15, 16	BF-23,24,25: HALLWAY 1199B. MV-02,03,04,05: BASEMENT STORAGE 0209. MV-06: ROOM 0213. MV-15: ROOM 2309. MV- 16: ROOM 1408.	30000 Sq Ft
I1A 1' x 1' Acoustical Ceiling Tile Pegboard (1924)						Total Amount - 300 Sq Ft
	37	ROOM 1215 (MEDIA CENTER)	NONE DETECTED	020110-MV-18	MV-18: ROOM 1215 (MEDIA CENTER).	300 Sq Ft
I1B 1' x 1' Acoustical Ceiling Tile Pegboard (1930)						Total Amount - 10 Sq Ft
	83	ROOM 2303	NONE DETECTED	020110-MV-27	MV-27: ROOM 2303.	10 Sq Ft
I1C 1' x 1' Acoustical Ceiling Tile Pin & Nail Holes (1991)						Total Amount - 5400 Sq Ft
	28	GYMNASIUM 1104	NONE DETECTED	072420CW-01	CW-01: GYMNASIUM 1104.	5400 Sq Ft
I2A 2' x 2' Acoustical Ceiling Tile Glacial w/Revealed Edge (1991)						Total Amount - 2400 Sq Ft
	36	ROOM 1215 (MEDIA CENTER)	NONE DETECTED	020110-MV-17	MV-17: ROOM 1215 (MEDIA CENTER).	2400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3A	2' x 4' Ceiling Tile Gouges & Pin Holes (1991)		Total Amount - 70000 Sq Ft			
6	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-4; 020110-MV-08	BF-4: 1991 MAIN OFFICE (SINCE REMOVED). MV-08: HALLWAY NEAR ROOM 1202.		70000 Sq Ft
I3B	2' x 4' Ceiling Tile Pin Holes & Craters		Total Amount - 160 Sq Ft			
125	STAFF RESTROOM 3309	NONE DETECTED				80 Sq Ft
162	STAFF RESTROOM 4308	NONE DETECTED	020110-MV-09	MV-09: STAFF RESTROOM BY ROOM 4302.		80 Sq Ft
I3D	2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes		Total Amount - 80 Sq Ft			
48	COMMUNICATIONS CLOSET 1310	NONE DETECTED	020110-MV-10	MV-10: CLOSET 1310 OFF ROOM 1309.		80 Sq Ft
J3A	Miscellaneous Cementitious Material 1" Black Window Sills (1939)		Total Amount - 186 Sq Ft			
56	ROOM 1304	NONE DETECTED				25 Sq Ft
62	ROOM 1305	NONE DETECTED				5 Sq Ft
91	ROOM 2304	NONE DETECTED				20 Sq Ft
92	ROOM 2305	NONE DETECTED				10 Sq Ft
95	ROOM 2306	NONE DETECTED	020110-MV-29	MV-29: ROOM 2306.		30 Sq Ft
137	ROOM 3304	NONE DETECTED				15 Sq Ft
138	ROOM 3305	NONE DETECTED				10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	141	ROOM 3306	NONE DETECTED			15 Sq Ft
	142	3RD FLOOR STAIRWELL 3399A & HALLWAY BY ROOM 3306	NONE DETECTED			8 Sq Ft
	143	4TH FLOOR STAIRWELL 4399A & HALLWAY BY ROOM 4306	NONE DETECTED			8 Sq Ft
	148	ROOM 4306	NONE DETECTED			15 Sq Ft
	154	ROOM 4305	NONE DETECTED			10 Sq Ft
	157	ROOM 4304	NONE DETECTED			15 Sq Ft
J3B	Miscellaneous Cementitious Material 3/4" Black Sill					Total Amount - 3 Sq Ft
	149	ROOM 4306	NONE DETECTED	020110-MV-37	MV-37: ROOM 4306.	3 Sq Ft
K1A	Sheet Vinyl Flooring & Adhesive Brown w/White Spots					Total Amount - 1000 Sq Ft
	93	ROOM 2306	NONE DETECTED	020110-MV-28	MV-28: ROOM 2306.	1000 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic White w/Blue-Green Flecks w/Black Mastic (1991)					Total Amount - 12310 Sq Ft
	24	FIRST FLOOR HALLWAYS	NONE DETECTED	020110-MV-19	MV-19: GYMNASIUM (SINCE REMOVED).	6000 Sq Ft
	32	ROOM 1206A	NONE DETECTED			70 Sq Ft
	61	ROOM 1305	NONE DETECTED	122920BV-01; 042320-BF-11	BV-01: COPY ROOM 1308 OFF OF ROOM 1307 (SINCE REMOVED). BF-11: NURSE OFFICE 1005 (SINCE REMOVED).	350 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	66	1924 ORIGINAL BUILDING 2ND FLOOR HALLWAY	NONE DETECTED			1120 Sq Ft
	75	2ND FLOOR HALLWAY 2300	NONE DETECTED			750 Sq Ft
	98	1924 ORIGINAL BUILDING 3RD FLOOR HALLWAY	NONE DETECTED	020110-MV-30	MV-30: OUTSIDE ROOM 3205.	1120 Sq Ft
	116	3RD FLOOR HALLWAY	NONE DETECTED			750 Sq Ft
	139	ROOM 3306	NONE DETECTED			280 Sq Ft
	145	4TH FLOOR HALLWAY	NONE DETECTED			750 Sq Ft
	167	1924 ORIGINAL BUILDING 4TH FLOOR HALLWAY	NONE DETECTED			1120 Sq Ft
K2B		12" x 12" Vinyl Floor Tile & Mastic White w/Multi-Colored Flecks				Total Amount - 704 Sq Ft
	33	ROOM 1208	NONE DETECTED	020110-MV-23	MV-23: ROOM 1208.	30 Sq Ft
	39	ROOM 1209	NONE DETECTED			30 Sq Ft
	43	ROOM 1301	NONE DETECTED			24 Sq Ft
	68	SOUTHWEST EXIT DOOR	NONE DETECTED			160 Sq Ft
	71	ROOM 2206	NONE DETECTED			160 Sq Ft
	77	ROOM 2301	NONE DETECTED			24 Sq Ft
	79	ROOM 2302	NONE DETECTED			24 Sq Ft
	89	ROOM 2304	NONE DETECTED			24 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	99	ROOM 3201	NONE DETECTED			24 Sq Ft
	101	ROOM 3203	NONE DETECTED			24 Sq Ft
	105	ROOM 3204	NONE DETECTED			24 Sq Ft
	108	ROOM 3205	NONE DETECTED			24 Sq Ft
	110	ROOM 3206	NONE DETECTED			24 Sq Ft
	118	ROOM 3301	NONE DETECTED			24 Sq Ft
	123	ROOM 3302	NONE DETECTED			24 Sq Ft
	135	ROOM 3304	NONE DETECTED			30 Sq Ft
	176	ROOM 4203	NONE DETECTED			30 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Yellow w/Multi-Colored Flecks (20XX)					Total Amount - 100 Sq Ft
	58	ROOM 1304	NEW			100 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic White w/Tan & Beige Marks (20xx)					Total Amount - 1025 Sq Ft
	146	ROOM 4306	NONE DETECTED	050521-BF-1	BF-1: ROOM 4306.	1025 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Light Brown Mottle (2012)					Total Amount - 24 Sq Ft
	31	ROOM 1202 SOUTH	NEW			24 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2I		12" x 12" Vinyl Floor Tile & Mastic White w/Green Flecks (20XX)				Total Amount - 200 Sq Ft
	8	THROUGHOUT BUILDING	NEW			200 Sq Ft
K2J		12" x 12" Vinyl Floor Tile & Mastic Dark Green Mottle (20XX)				Total Amount - 100 Sq Ft
	25	FIRST FLOOR HALLWAYS	NEW			100 Sq Ft
K2K		12" x 12" Vinyl Floor Tile & Mastic Light Gray Mottle (2020)				Total Amount - 5400 Sq Ft
	27	GYMNASIUM 1104	NEW			5400 Sq Ft
K3C		Miscellaneous Flooring Black Mastic				Total Amount - 3 Sq Ft
	164	HALLWAY OUTSIDE ROOM 4301	NONE DETECTED	020110-MV-38	MV-38: HALLWAY OUTSIDE ROOM 4301.	3 Sq Ft
K3E		Miscellaneous Flooring Light Green Stair Tread				Total Amount - 16 Sq Ft
	26	STORAGE 1109	NONE DETECTED	073115BV-01	BV-01: STORAGE 1109.	16 Sq Ft
K3F		Miscellaneous Flooring Tan Stair Treads				Total Amount - 120 Sq Ft
	64	STAIRWELL 1399A	NONE DETECTED	042320-BF-22	BF-22: HALLWAY 1199B (SINCE REMOVED).	120 Sq Ft
LOA		Flexible Duct Connector Black Vinyl				Total Amount - 10 Sq Ft
	54	ELEVATOR EQUIPMENT ROOM 1306	NSM			2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	85	ELECTRICAL ROOM 2307	NSM			2 Sq Ft
	126	COMMUNICATIONS ROOM 3308	NSM			2 Sq Ft
	130	MECHANICAL ROOM 3307	NSM			2 Sq Ft
	158	MECHANICAL ROOM 4307	NSM			2 Sq Ft
MOA	Plaster 1924 Original Building					Total Amount - 42000 Sq Ft
	21	THROUGHOUT 1924 ORIGINAL BUILDING BASEMENT	NONE DETECTED	020110-MV-01; 2001-1501-MP-1	MV-01: ROOM 0212 (CEILING). MP1: 0212 EAST WALL IN HALL TO CRAWL SPACE	2000 Sq Ft
	23	THROUGHOUT 1924 ORIGINAL BUILDING FIRST FLOOR	NONE DETECTED	020110-MV-11, 12	MV-11: ROOM 1215. MV-12: ROOM 1209.	10000 Sq Ft
	65	THROUGHOUT 1924 ORIGINAL BUILDING 2ND FLOOR	NONE DETECTED	020110-MV-13	MV-13: HALLWAY WALL BY ROOM 2205.	10000 Sq Ft
	97	THROUGHOUT 1924 ORIGINAL BUILDING 3RD FLOOR	NONE DETECTED	09216-BF-2; 020110-MV-14	BF-2: 2ND FLOOR SOUTH RESTROOM. MV-14: HALLWAY BY BOYS' RESTROOM.	10000 Sq Ft
	166	THROUGHOUT 1924 ORIGINAL BUILDING 4TH FLOOR	NONE DETECTED	020110-MV-22	MV-22: HALLWAY BY ROOM 4204.	10000 Sq Ft
MOB	Plaster 1930 Addition					Total Amount - 17500 Sq Ft
	30	GYMNASIUM 1104	NONE DETECTED	020110-MV-21, 41	MV-21: ROOM 1107 (SINCE REMOVED). MV-41: GYMNASIUM STORAGE 1105. (SINCE REMOVED)	3000 Sq Ft
	44	THROUGHOUT 1930 ADDITION FIRST FLOOR NORTH	NONE DETECTED	020110-MV-31, 34	MV-31: HALLWAY OUTSIDE ELEVATOR. MV-34: ROOM 1302.	4000 Sq Ft
	74	THROUGHOUT 1930 ADDITION 2ND FLOOR	NONE DETECTED			5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	115	THROUGHOUT 1930 ADDITION 3RD FLOOR	NONE DETECTED	020110-MV-33; 2001-01144-4	MV-33: 3RD FLOOR STAFF RESTROOM.	5000 Sq Ft
	159	THROUGHOUT 1930 ADDITION 4TH FLOOR	NONE DETECTED	020110-MV-35	MV-35: ROOM 4301.	500 Sq Ft
M0C	Plaster 1939 Addition					Total Amount - 11500 Sq Ft
	55	THROUGHOUT 1939 ADDITION FIRST FLOOR	NONE DETECTED			1000 Sq Ft
	86	THROUGHOUT 1939 ADDITION 2ND FLOOR	NONE DETECTED	020110-MV-27, 32	MV-27: ROOM 2303. MV-32: ROOM 2306 BEAM.	5000 Sq Ft
	132	THROUGHOUT 1939 ADDITION 3RD FLOOR	NONE DETECTED			500 Sq Ft
	144	THROUGHOUT 1939 ADDITION 4TH FLOOR	NONE DETECTED	020110-MV-36	MV-36: HALLWAY OUTSIDE ROOM 4304.	5000 Sq Ft
N0A	Drywall/Joint Compound 1991 Addition/Installation					Total Amount - 60000 Sq Ft
	5	THROUGHOUT BUILDING	NONE DETECTED	020110-MV-07	MV-07: CUSTODIAL OFFICE 0207.	60000 Sq Ft
N0B	Drywall/Joint Compound 1991 Addition					Total Amount - 600 Sq Ft
	82	ROOM 2308 (MECHANICAL)	NONE DETECTED	020110-MV-42	MV-42: ROOM 2307.	600 Sq Ft
P0A	Fire Doors Metal - 1.5 Hr Rating (Underwriters Laboratories)					Total Amount - 140 Sq Ft
	53	ELEVATOR EQUIPMENT ROOM 1306	ASSUMED			20 Sq Ft
	70	2ND FLOOR HALLWAY 2200	ASSUMED			80 Sq Ft
	127	COMMUNICATIONS ROOM 3308	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	131	MECHANICAL ROOM 3307	ASSUMED			20 Sq Ft
Q0A		Carpet Adhesive Various Berber Carpet				Total Amount - 60000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-2, 7, 18; 020110-MV-39	BF-2: CONFERENCE ROOM 1009 (SINCE REMOVED). BF-7: MAIN OFFICE 1002 (SINCE REMOVED). BF-18: ROOM 1216. MV-39: OFFICE CLOSET UP STAIRWELL ACROSS FROM ROOM 4201.	60000 Sq Ft
Q0B		Carpet Adhesive Carpet Squares (2011)				Total Amount - 100 Sq Ft
	49	ROOM 1307/1101 (COMPUTER LAB)	NEW			100 Sq Ft
Q0C		Carpet Adhesive 24" Blue, Orange, Red & Green Carpet Squares (2012)				Total Amount - 2400 Sq Ft
	35	ROOM 1215 (MEDIA CENTER)	NEW			2400 Sq Ft
ROA		Baseboard/Mopboard Adhesive Tan Baseboard (1991)				Total Amount - 2000 Sq Ft
	7	THROUGHOUT BUILDING	NONE DETECTED	020110-MV-26	MV-26: ROOM 2205.	2000 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier 1924 Original Building				Total Amount - 140 Sq Ft
	173	OFFICE 4210 UP STAIRWELL ACROSS FROM ROOM 4205	NSM			70 Sq Ft
	180	OFFICE 4212 UP STAIRWELL FROM ROOM 4201	NSM			70 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOA	Sink Undercoating Gray					Total Amount - 115 Sq Ft
	34	ROOM 1208	NONE DETECTED	020110-MV-24	MV-24: ROOM 1208.	5 Sq Ft
	40	ROOM 1209	NONE DETECTED			5 Sq Ft
	41	ROOM 1210	NONE DETECTED			5 Sq Ft
	42	ROOM 1301	NONE DETECTED			5 Sq Ft
	72	ROOM 2206	NONE DETECTED			5 Sq Ft
	73	ROOM 2207	NONE DETECTED			5 Sq Ft
	76	ROOM 2301	NONE DETECTED			5 Sq Ft
	80	ROOM 2302	NONE DETECTED			5 Sq Ft
	90	ROOM 2304	NONE DETECTED			5 Sq Ft
	94	ROOM 2306	NONE DETECTED			5 Sq Ft
	100	ROOM 3201	NONE DETECTED			5 Sq Ft
	102	ROOM 3203	NONE DETECTED			5 Sq Ft
	106	ROOM 3204	NONE DETECTED			5 Sq Ft
	109	ROOM 3205	NONE DETECTED			5 Sq Ft
	111	ROOM 3206	NONE DETECTED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	117	ROOM 3207	NONE DETECTED			5 Sq Ft
	119	ROOM 3301	NONE DETECTED			5 Sq Ft
	124	ROOM 3302	NONE DETECTED			5 Sq Ft
	136	ROOM 3304	NONE DETECTED			5 Sq Ft
	140	ROOM 3306	NONE DETECTED			5 Sq Ft
	147	ROOM 4306	NONE DETECTED			5 Sq Ft
	165	ROOM 4207	NONE DETECTED			5 Sq Ft
	177	ROOM 4203	NONE DETECTED			5 Sq Ft
VOB	Sink Undercoating Black					Total Amount - 90 Sq Ft
	45	ROOM 1302	NONE DETECTED			5 Sq Ft
	50	ROOM 1303	NONE DETECTED			5 Sq Ft
	57	ROOM 1304	NONE DETECTED	073115BV-04	BV-04: ROOM 1304.	80 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					Total Amount - 300 Sq Ft
	38	ROOM 1215 (MEDIA CENTER)	NONE DETECTED	020110-MV-18	MV-18: ROOM 1215 (MEDIA CENTER).	300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B		Total Amount - 10 Sq Ft			
84	ROOM 2303	NONE DETECTED	020110-MV-27	MV-27: ROOM 2303.	10 Sq Ft	
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C		Total Amount - 700 Sq Ft			
29	GYMNASIUM 1104	NONE DETECTED	072420CW-01	CW-01: GYMNASIUM 1104.	700 Sq Ft	
X0A	Miscellaneous Material Pipe/Valve Flange Gaskets		Total Amount - 24 Sq Ft			
22	LOWER LEVEL STORAGE ROOM 0202	ASSUMED			24 Sq Ft	
X0B	Miscellaneous Material Slate Chalkboard Adhesive (1991)		Total Amount - 400 Sq Ft			
2	THROUGHOUT BUILDING	ASSUMED			400 Sq Ft	
X0C	Miscellaneous Material Slate Chalkboard Adhesive (1930)		Total Amount - 36 Sq Ft			
81	ROOM 2302	NONE DETECTED	072910ML-01		10 Sq Ft	
121	ROOM 3302	NONE DETECTED			6 Sq Ft	
128	ROOM 3303	NONE DETECTED			10 Sq Ft	
160	ROOM 4303	NONE DETECTED			10 Sq Ft	
X0D	Miscellaneous Material Tackboard Adhesive -Brown (1930)		Total Amount - 312 Sq Ft			
78	ROOM 2301	NONE DETECTED			60 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	120	ROOM 3301	NONE DETECTED			100 Sq Ft
	122	ROOM 3302	NONE DETECTED			12 Sq Ft
	129	ROOM 3303	NONE DETECTED			20 Sq Ft
	161	ROOM 4303	NONE DETECTED			20 Sq Ft
	163	ROOM 4301	NONE DETECTED	050521-BF-3	BF-3: ROOM 4302 (SINCE REMOVED).	100 Sq Ft
XOF	Miscellaneous Material Tackboard Adhesive (1924)					Total Amount - 110 Sq Ft
	104	ROOM 3203	ASSUMED			12 Sq Ft
	113	ROOM 3206	ASSUMED			30 Sq Ft
	169	ROOM 4206	ASSUMED			32 Sq Ft
	172	ROOM 4205	ASSUMED			6 Sq Ft
	175	ROOM 4204	ASSUMED			20 Sq Ft
	179	ROOM 4203	ASSUMED			10 Sq Ft
XOG	Miscellaneous Material Slate Chalkboard Adhesive -Brown (1924)					Total Amount - 55 Sq Ft
	103	ROOM 3203	NONE DETECTED			6 Sq Ft
	107	ROOM 3204	NONE DETECTED			10 Sq Ft
	112	ROOM 3206	NONE DETECTED			8 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	168	ROOM 4206	NONE DETECTED			15 Sq Ft
	171	ROOM 4205	NONE DETECTED	050521-BF-5	BF-5: ROOM 4205.	3 Sq Ft
	174	ROOM 4204	NONE DETECTED			8 Sq Ft
	178	ROOM 4203	NONE DETECTED			5 Sq Ft
X0H	Miscellaneous Material Slate Chalkboard Adhesive					Total Amount - 5 Sq Ft
	114	ROOM 3206	ASSUMED			5 Sq Ft
X0I	Miscellaneous Material Slate Chalkboard Adhesive (1939)					Total Amount - 61 Sq Ft
	87	ROOM 2304	NONE DETECTED			15 Sq Ft
	133	ROOM 3304	NONE DETECTED	072910ML-02	ML-02: ROOM 3306 (SINCE REMOVED).	15 Sq Ft
	150	ROOM 4306	NONE DETECTED			8 Sq Ft
	152	ROOM 4305	NONE DETECTED			8 Sq Ft
	155	ROOM 4304	NONE DETECTED			15 Sq Ft
X0J	Miscellaneous Material Tackboard Adhesive -Brown (1939)					Total Amount - 188 Sq Ft
	88	ROOM 2304	NONE DETECTED			60 Sq Ft
	96	ROOM 2306	NONE DETECTED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	134	ROOM 3304	NONE DETECTED			30 Sq Ft
	151	ROOM 4306	NONE DETECTED			16 Sq Ft
	153	ROOM 4305	NONE DETECTED	050521-BF-2	BF-2: ROOM 4305.	16 Sq Ft
	156	ROOM 4304	NONE DETECTED			36 Sq Ft
XOK	Miscellaneous Material Stone Panel Adhesive					Total Amount - 170 Sq Ft
	67	BOYS' RESTROOM 128	ASSUMED			50 Sq Ft
	170	GIRLS' RESTROOM 4208	ASSUMED			70 Sq Ft
	181	BOYS' RESTROOM 4202	ASSUMED			50 Sq Ft
XOL	Miscellaneous Material Black Coating on Clay Block Wall Behind Plaster					Total Amount - 5000 Sq Ft
	18	THROUGHOUT 1924 ORIGINAL BUILDING	NONE DETECTED	073119-BF-1; 092916-BF-2	BF-1: ROOM 2201. 2: 2ND FLOOR BOYS' RESTROOM.	5000 Sq Ft
XOM	Miscellaneous Material Terrazzo Flooring					Total Amount - 1000 Sq Ft
	19	THROUGHOUT 1930 ADDITION	NONE DETECTED	042320-BF-21	BF-21: HALLWAY 1109A.	1000 Sq Ft
XON	Miscellaneous Material Brick Mortar					Total Amount - 1000 Sq Ft
	20	THROUGHOUT 1930 ADDITION	NONE DETECTED	042320-BF-32	BF-32: 1930 ADDITION EXTERIOR.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X00	Miscellaneous Material Gray Duct Caulk		Total Amount - 100 Sq Ft			
9	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-8	BF-8: MAIN OFFICE 1002.	100 Sq Ft	
X0P	Miscellaneous Material Light Gray Duct Caulk		Total Amount - 100 Sq Ft			
10	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-9	BF-9: MAIN OFFICE 1002.	100 Sq Ft	
X0Q	Miscellaneous Material Red Fire Stop		Total Amount - 100 Sq Ft			
11	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-10	BF-10: MAIN OFFICE 1002.	100 Sq Ft	
X0R	Miscellaneous Material Whiteboard Adhesive -White		Total Amount - 100 Sq Ft			
3	THROUGHOUT BUILDING	NONE DETECTED	050521-BF-4	BF-4: ROOM 4205.	100 Sq Ft	
X1A	Miscellaneous Material 1" Light Brown Ceramic Floor Tile System		Total Amount - 1400 Sq Ft			
12	THROUGHOUT BUILDING (RESTROOMS)	NONE DETECTED	073115BV-02	BV-02: BOYS' LOCKER ROOM.	1400 Sq Ft	
X1C	Miscellaneous Material 2" Light Blue Ceramic Floor Tile System (20XX)		Total Amount - 112 Sq Ft			
46	ROOM 1302 RESTROOM	NEW			36 Sq Ft	
51	ROOM 1303 RESTROOM	NEW			36 Sq Ft	
59	ROOM 1304 RESTROOM	NEW			40 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1D	Miscellaneous Material 4" Yellow Ceramic Wall Tile System (20XX)					Total Amount - 190 Sq Ft
	47	ROOM 1302 RESTROOM	NEW			80 Sq Ft
	52	ROOM 1303 RESTROOM	NEW			80 Sq Ft
	60	ROOM 1304 RESTROOM	NEW			30 Sq Ft
X1E	Miscellaneous Material 6" Red Quarry Tile (1991)					Total Amount - 1200 Sq Ft
	63	KITCHEN 1402	NEW			1200 Sq Ft
X1F	Miscellaneous Material 6" Red Quarry Tile					Total Amount - 125 Sq Ft
	69	1924 ORIGINAL BUILDING ENTRANCE 2200A	ASSUMED			125 Sq Ft
ZOA	Miscellaneous Material Roof Membrane					Total Amount - 40000 Sq Ft
	13	THROUGHOUT BUILDING ROOF	NONE DETECTED	042320-BF-35, 40, 46	BF-35: ROOF SECTION 9. BF-40: ROOF SECTION 14. BF-46: ROOF SECTION 13.	40000 Sq Ft
ZOB	Miscellaneous Material Roof Perimeter Flashing					Total Amount - 2000 Sq Ft
	14	THROUGHOUT BUILDING ROOF	NONE DETECTED	042320-BF-37, 42, 47	BF-37: ROOF SECTION 9. BF-42: ROOF SECTION 14. BF-47: ROOF SECTION 13.	2000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Z0C		Miscellaneous Material Roof Penetration Flashing				Total Amount - 300 Sq Ft
	15	THROUGHOUT BUILDING ROOF	NONE DETECTED	042320-BF-36, 41	BF-36: ROOF SECTION 9. BF-41: ROOF SECTION 14.	300 Sq Ft
Z0D		Miscellaneous Material Roof Cement Patch -Gray				Total Amount - 100 Sq Ft
	16	THROUGHOUT BUILDING ROOF	3 - 4 CH	042320-BF-38, 43, 48	BF-38: ROOF SECTION 9. BF-43: ROOF SECTION 14. BF-48: ROOF SECTION 13.	100 Sq Ft
Z0E		Miscellaneous Material Roof Flashing Caulk				Total Amount - 100 Sq Ft
	17	THROUGHOUT BUILDING ROOF	NONE DETECTED	042320-BF-39, 44, 49	BF-39: ROOF SECTION 9. BF-44: ROOF SECTION 14. BF-49: ROOF SECTION 13.	100 Sq Ft



EMSL Analytical, Inc.

3410 Winnetka Avenue North New Hope, MN 55427

Tel/Fax: (763) 449-4922 / (763) 449-4924

<http://www.EMSL.com> / minneapolislab@emsl.com

EMSL Order: 352103795
Customer ID: IFEA50
Customer PO:
Project ID:

Attention: Jennifer Theis

Inst. For Environmental Assessment

9201 West Broadway

Suite 600

Brooklyn Park, MN 55445

Project: 2001 - 202110320- American Indian Magnet

Phone: (763) 315-7900

Fax: (763) 315-7920

Received Date: 05/05/2021 9:25 AM

Analysis Date: 05/05/2021

Collected Date:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using

Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos % Type
			% Fibrous	% Non-Fibrous	
050521-BF-1-Floor Tile	Room 4306, Floor tile & mastic (12"x12"), K2G	White Non-Fibrous	100.0%	Non-fibrous (Other)	None Detected
352103795-0001		Homogeneous			
050521-BF-1-Mastic	Room 4306, Floor tile & mastic (12"x12"), K2G	Brown/Yellow Non-Fibrous	6%	Cellulose	94.0% Non-fibrous (Other)
352103795-0001A		Homogeneous			None Detected
050521-BF-2	Room 4305, Tackboard adhesive	Brown Non-Fibrous	100.0%	Non-fibrous (Other)	None Detected
352103795-0002		Homogeneous			
050521-BF-3-Adhe sive	Room 4302, Tackboard adhesive	Brown Non-Fibrous	100.0%	Non-fibrous (Other)	None Detected
352103795-0003		Homogeneous			
050521-BF-3-Backl ng	Room 4302, Tackboard adhesive	Brown/White Fibrous	15%	Cellulose	82.0% Non-fibrous (Other)
352103795-0003A		Homogeneous			3% Glass
050521-BF-4-Adhe sive	Room 4205, White board adhesive	White Non-Fibrous	100.0%	Non-fibrous (Other)	None Detected
352103795-0004		Homogeneous			
050521-BF-4-Backl ng	Room 4205, White board adhesive	Brown/White Fibrous	15%	Cellulose	82.0% Non-fibrous (Other)
352103795-0004A		Homogeneous			3% Glass
050521-BF-5	Room 4205, Chalkboard adhesive	Brown Non-Fibrous	100.0%	Non-fibrous (Other)	None Detected
352103795-0005		Homogeneous			

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/MA-82-020 "Inherm Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-fragile organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. New Hope, MN NVLAP Lab Code 200019-0; Colorado AL-24478

Initial report from: 05/05/2021 11:46:57



EMSL Analytical, Inc.

3410 Winnetka Avenue North New Hope, MN 55427

Tel/Fax: (763) 449-4922 / (763) 449-4924

<http://www.EMSL.com> / minneapolislab@emsl.com

EMSL Order: 352103795
Customer ID: IFEA50
Customer PO:
Project ID:

Attention: Jennifer Theis
Inst. For Environmental Assessment
9201 West Broadway
Suite 600
Brooklyn Park, MN 55445
Project: 2001-202110320- American Indian Magnet


Phone: (763) 315-7900
Fax: (763) 315-7920
Received Date: 05/05/2021 9:25 AM
Analysis Date: 05/05/2021
Collected Date:

The samples in this report were submitted to EMSL for analysis by Asbestos Analysis of Bulk materials via EPA/600 (0513) Method using Polarized Light Microscopy. The reference number for these samples is the EMSL Order ID above. Please use this reference number when calling about these samples.


Report Comments:

Sample Receipt Date:	05/05/2021	Sample Receipt Time:	9:25 AM
Analysis Completed Date:	05/05/2021	Analysis Completed Time:	11:40 AM

Analyst(s):



Craig Santangelo PLM (8)



Rachel Travis, Laboratory Manager
or other approved signatory

Samples Reviewed and approved by:

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and meet method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-fragile organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. New Hope, MN NVLAP Lab Code 200019-0; Colorado AL-24478

Initial report from: 05/05/2021 11:46:57



9201 West Broadway North, Suite 600
 Brooklyn Park, MN 55445
 (763) 315-7900
 1-800-233-9513

03795

CHAIN OF CUSTODY

Page 1 of 1

Client # <u>2001</u>	Project # <u>202110320</u>	Building Name <u>American Indian Magnet</u>	Shaded Areas are for Laboratory Use Only!
Client <u>Saint Paul Public Schools</u>	Project Name _____	Contact Person _____	
Address _____		Contact Person Phone _____	
Other Information _____			

Verbal results to _____	Phone, Fax No. or E-Mail _____	TAT (circle) 6 hr <u>1d</u> 2d 3d 4d Specify	
Verbal results relayed to _____	Verbal results relayed by _____	Date _____	Time _____

Analysis location: On Site Lab Regional Office Other _____

Sample #	Work Area or Phase #	Comments / Location	Sample type or Material code	Volume	Matrix type			Analysis requested				Filter type		
					Air	Bulk	Dust	PCM	PLM	TEM	Other	MCE	.8 um	.45 um
050521-BF-1	Room 4306	Floor tile + mastic (12" x 12")	K2G		<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>		<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
050521-BF-2	Room 4305	Tackboard adhesive			<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>		<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
050521-BF-3	Room 4302	Tackboard adhesive - analyze adhesive only			<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>		<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
050521-BF-4	Room 4205	White board adhesive - analyze adhesive only			<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>		<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
050521-BF-5	▼	Chalkboard adhesive			<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	<input type="radio"/>		<input type="radio"/>	<input type="radio"/>	<input type="radio"/>

The MN Department of Health Alternative Indoor Air Standard for this project is: _____ F/CC. Batch Number: _____ Samples Acceptable? Yes No

Sampled by <u>Brenda Fischer</u>	Date <u>5-5-21</u>	Time <u>7am</u>	Delivered by <u>[Signature]</u>	Date <u>5/5/21</u>	Time <u>9:25am</u>	Received by lab <u>[Signature]</u>	Date <u>5-5-21</u>	Time <u>9:25</u>	Entered by <u>[Signature]</u>	Date 	Time
Received by 	Date 	Time 	Delivered by 	Date 	Time 	Analysis by 	Date 	Time 	Delivered by 	Date 	Time

OrderID: 352103795

Page 1 of 1