

60 South Ruth Street, Saint Paul, MN 55119

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
12A 2' x 2' Acoustical Ceiling Tile Small Dents w/Pin Holes						Total Amount - 2520 Sq Ft
	22	ROOM 1103	NONE DETECTED	110508ML-20		520 Sq Ft
	205	ROOMS 1216, 1217, 1218 & 1219	NONE DETECTED			2000 Sq Ft
13A 2' x 4' Ceiling Tile Pockmarks w/Pin Holes (1996)						Total Amount - 8000 Sq Ft
	208	THROUGHOUT 1996 ADDITION	NONE DETECTED	110508ML-06; 422-8	06: HALLWAY BY ROOM 1206.	8000 Sq Ft
13B 2' x 4' Ceiling Tile Dents w/Pin Holes (2001)						Total Amount - 200 Sq Ft
	218	ROOM 1214	NONE DETECTED	110508ML-07		200 Sq Ft
13C 2' x 4' Ceiling Tile Lightly Textured w/Pin Holes						Total Amount - 1140 Sq Ft
	225	1996 ADDITION KITCHEN (1202)	NONE DETECTED	110508ML-03		900 Sq Ft
	226	KITCHEN STORAGE (1202B)	NONE DETECTED			130 Sq Ft
	227	STORAGE ROOM 1201	NONE DETECTED			110 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J2A	Transite Piping/Ducting 1964 Original Building		Total Amount - 1500 Sq Ft			
	16	1964 ORIGINAL BUILDING TUNNEL SYSTEM	30 CH	M2045-1A	SAMPLE TAKEN BY NOVA.	1500 Sq Ft
J2B	Transite Piping/Ducting 1966 Addition		Total Amount - 180 Sq Ft			
	108	1966 ADDITION WEST TUNNEL SYSTEM	ASSUMED			90 Sq Ft
	203	1966 ADDITION EAST TUNNEL SYSTEM	ASSUMED			90 Sq Ft
J3A	Miscellaneous Cementitious Material Black Window Sills (1964)		Total Amount - 204 Sq Ft			
	28	ROOM 1104	NONE DETECTED			12 Sq Ft
	33	ROOM 1105	NONE DETECTED			12 Sq Ft
	38	ROOM 1106	NONE DETECTED			12 Sq Ft
	46	ROOM 1113 (EAST IMC STORAGE)	NONE DETECTED			4 Sq Ft
	49	CONFERENCE ROOM (1111)	NONE DETECTED			5 Sq Ft
	50	MAIN OFFICE WORK ROOM (1003)	NONE DETECTED			3 Sq Ft
	53	PRINCIPAL'S OFFICE (1002)	NONE DETECTED			3 Sq Ft
	55	MAIN OFFICE RECEPTION (1001)	NONE DETECTED			6 Sq Ft
	57	MAIN OFFICE CONFERENCE ROOM (1007)	NONE DETECTED			3 Sq Ft
	61	NURSE'S OFFICE/SICK ROOM	NONE DETECTED			3 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	74	ROOM 1317	NONE DETECTED			8 Sq Ft
	80	ROOM 1316	NONE DETECTED			8 Sq Ft
	85	ROOM 1315	NONE DETECTED			8 Sq Ft
	89	ROOM 1314	NONE DETECTED			3 Sq Ft
	94	ROOM 1312	NONE DETECTED			3 Sq Ft
	102	ROOM 1310	NONE DETECTED	110508ML-24		8 Sq Ft
	105	ROOM 1311	NONE DETECTED			3 Sq Ft
	107	ROOM 1313	NONE DETECTED			4 Sq Ft
	131	ROOM 1322	NONE DETECTED			8 Sq Ft
	136	ROOM 1321	NONE DETECTED			8 Sq Ft
	141	ROOM 1324	NONE DETECTED			8 Sq Ft
	146	ROOM 1323	NONE DETECTED			8 Sq Ft
	151	ROOM 1326	NONE DETECTED			8 Sq Ft
	156	ROOM 1325	NONE DETECTED			8 Sq Ft
	168	ROOM 1330	NONE DETECTED			8 Sq Ft
	173	ROOM 1329	NONE DETECTED			12 Sq Ft
	177	ROOM 1332	NONE DETECTED			8 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	183	ROOM 1331	NONE DETECTED			12 Sq Ft
	189	ROOM 1334	NONE DETECTED			8 Sq Ft
J3B	Miscellaneous Cementitious Material Black Window Sill (1966)					Total Amount - 54 Sq Ft
	110	ROOM 1302	NONE DETECTED	110508ML-28		3 Sq Ft
	113	ROOM 1301	NONE DETECTED			8 Sq Ft
	117	ROOM 1303	NONE DETECTED			4 Sq Ft
	121	ROOM 1304	NONE DETECTED			4 Sq Ft
	123	ROOM 1306	NONE DETECTED			3 Sq Ft
	126	ROOM 1305	NONE DETECTED			8 Sq Ft
	193	ROOM 1335	NONE DETECTED			8 Sq Ft
	197	ROOM 1336	NONE DETECTED			8 Sq Ft
	201	ROOM 1337	NONE DETECTED			8 Sq Ft
J3C	Miscellaneous Cementitious Material Sliding Glass Door Sill (1964)					Total Amount - 20 Sq Ft
	44	ROOM 1112 (IMC)	NONE DETECTED	110508ML-29		20 Sq Ft
K1A	Sheet Vinyl Flooring & Adhesive White w/Gray & Tan Specks					Total Amount - 250 Sq Ft
	60	NURSE'S OFFICE/SICK ROOM (1006)	NONE DETECTED	110508ML-30		250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K1B		Sheet Vinyl Flooring & Adhesive Gray Terrazzo-Look			Total Amount - 120 Sq Ft	
91	RESTROOM 1314A	NONE DETECTED			60 Sq Ft	
96	RESTROOM 1312A	NONE DETECTED	110508ML-33; 422-4		60 Sq Ft	
K1C		Sheet Vinyl Flooring & Adhesive Pale Blue Sheet Vinyl Flooring (2020)			Total Amount - 90 Sq Ft	
59	OFFICE 1005	NEW			90 Sq Ft	
K2B		12" x 12" Vinyl Floor Tile & Mastic Gray w/Light Gray & Beige Smudges			Total Amount - 10200 Sq Ft	
2	THROUGHOUT BUILDING	NONE DETECTED	422-7	ENTRY TO ROOM 1208.	10000 Sq Ft	
69	ROOM 1320	NONE DETECTED			200 Sq Ft	
K2C		12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray Blotches (1997)			Total Amount - 4600 Sq Ft	
21	GYMNASIUM (1110)	NONE DETECTED	110508ML-19		4600 Sq Ft	
K2D		12" x 12" Vinyl Floor Tile & Mastic Gray w/Dark Gray & White Flecks			Total Amount - 4640 Sq Ft	
24	ROOM 1103	NONE DETECTED			520 Sq Ft	
26	ROOM 1104	NONE DETECTED	110508ML-23		1200 Sq Ft	
52	PRINCIPAL'S OFFICE (1002)	NONE DETECTED			90 Sq Ft	
54	MAIN OFFICE RECEPTION (1001)	NONE DETECTED			400 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	56	MAIN OFFICE CONFERENCE ROOM (1007)	NONE DETECTED			170 Sq Ft
	58	COPY ROOM 1004	NONE DETECTED			100 Sq Ft
	165	ROOM 1330	NONE DETECTED			720 Sq Ft
	175	ROOM 1332	NONE DETECTED			720 Sq Ft
	186	ROOM 1334	NONE DETECTED			720 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Gray, Tan & Beige Blotches					Total Amount - 4130 Sq Ft
	32	ROOM 1105	NONE DETECTED	110508ML-26		1200 Sq Ft
	37	ROOM 1106	NONE DETECTED			100 Sq Ft
	72	ROOM 1317	NONE DETECTED			30 Sq Ft
	77	ROOM 1316	NONE DETECTED			30 Sq Ft
	82	ROOM 1315	NONE DETECTED			30 Sq Ft
	87	ROOM 1314	NONE DETECTED			260 Sq Ft
	92	ROOM 1312	NONE DETECTED			260 Sq Ft
	97	ROOM 1309	NONE DETECTED			110 Sq Ft
	99	ROOM 1310	NONE DETECTED			260 Sq Ft
	111	ROOM 1301	NONE DETECTED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	115	ROOM 1303	NONE DETECTED			30 Sq Ft
	119	ROOM 1304	NONE DETECTED			100 Sq Ft
	124	ROOM 1305	NONE DETECTED			30 Sq Ft
	128	ROOM 1322	NONE DETECTED			30 Sq Ft
	133	ROOM 1321	NONE DETECTED			30 Sq Ft
	138	ROOM 1324	NONE DETECTED			30 Sq Ft
	143	ROOM 1323	NONE DETECTED			30 Sq Ft
	148	ROOM 1326	NONE DETECTED			30 Sq Ft
	153	ROOM 1325	NONE DETECTED			30 Sq Ft
	164	ROOM 1330	NONE DETECTED			30 Sq Ft
	174	ROOM 1332	NONE DETECTED			30 Sq Ft
	180	ROOM 1331	NONE DETECTED			1300 Sq Ft
	185	ROOM 1334	NONE DETECTED			30 Sq Ft
	191	ROOM 1335	NONE DETECTED			30 Sq Ft
	195	ROOM 1336	NONE DETECTED			30 Sq Ft
	199	ROOM 1337	NONE DETECTED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3A		Miscellaneous Flooring Black Flooring Mastic				Total Amount - 10 Sq Ft
	27	ROOM 1104	5 CH	110508ML-23		10 Sq Ft
K3B		Miscellaneous Flooring 2' x 2' Brown w/Raised Squares				Total Amount - 360 Sq Ft
	215	THROUGHOUT 1996 ADDITION ENTRIES	NONE DETECTED	110508ML-12	ENTRY NEAR CAFETERIA.	360 Sq Ft
K3C		Miscellaneous Flooring Gray & White Speckled Epoxy Flooring (2020)				Total Amount - 6000 Sq Ft
	14	1964 ORIGINAL BUILDING RAMPS	NEW			3000 Sq Ft
	216	1996 ADDITION RAMPS	NEW			3000 Sq Ft
LOA		Flexible Duct Connector Black Vinyl				Total Amount - 200 Sq Ft
	8	THROUGHOUT BUILDING	NSM			200 Sq Ft
M0A		Plaster 1964 Original Building				Total Amount - 800 Sq Ft
	11	THROUGHOUT 1964 ORIGINAL BUILDING	NONE DETECTED	511U1		800 Sq Ft
M0B		Plaster Wall Plaster Patch				Total Amount - 100 Sq Ft
	18	1964 ORIGINAL BUILDING TUNNEL SYSTEM	NONE DETECTED	M2045-2A, B, C	SAMPLE TAKEN BY NOVA.	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOC		Plaster 1996 Addition			Total Amount - 500 Sq Ft	
	209	THROUGHOUT 1996 ADDITION	NONE DETECTED	110508ML-13	EAST STAIRWELL LANDING NEAR CAFETERIA.	500 Sq Ft
NOA		Drywall/Joint Compound			Total Amount - 5000 Sq Ft	
	1	THROUGHOUT BUILDING	NONE DETECTED	422-1; 4120-422-6	422-1: OUTSIDE CAFETERIA. 4120-422-6: OUTSIDE ROOM 1314.	5000 Sq Ft
POA		Fire Doors Metal - 1.5 Hr Rating (Underwriter's Laboratories)			Total Amount - 30 Sq Ft	
	15	BOILER ROOM (1101)	ASSUMED			20 Sq Ft
	17	TUNNEL SYSTEM	ASSUMED			10 Sq Ft
POB		Fire Doors Hollow Metal - 1.5 Hr Rating (Warnock Hersey)			Total Amount - 140 Sq Ft	
	47	ROOM 1113 (EAST IMC STORAGE)	NSM			20 Sq Ft
	217	1996 ADDITION RAMPS	NSM			80 Sq Ft
	228	HALLWAY NEAR DOOR #6	NSM			40 Sq Ft
QOA		Carpet Adhesive Brown w/Multi-Colors Carpet			Total Amount - 8000 Sq Ft	
	3	THROUGHOUT BUILDING	NONE DETECTED	110508ML-18	ROOM 1315.	8000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
Q0B		Carpet Adhesive Multi-Shaded Blue Carpet (1996)				Total Amount - 520 Sq Ft	
	23	ROOM 1103	NONE DETECTED	2001-1901-3-BC	1964 ORIGINAL BUILDING RAMPS (SINCE REMOVED).	520 Sq Ft	
Q0C		Carpet Adhesive Multi-Colored Carpet				Total Amount - 8000 Sq Ft	
	4	THROUGHOUT BUILDING	NONE DETECTED	110508ML-22	ROOM 1106.	8000 Sq Ft	
Q0D		Carpet Adhesive Violet w/Multi-Colored Carpet				Total Amount - 9500 Sq Ft	
	76	ROOMS 1310, 1312, 1314 & 1316	NONE DETECTED			1500 Sq Ft	
	210	THROUGHOUT 1996 ADDITION	NONE DETECTED	110508ML-08	ROOM 1212.	8000 Sq Ft	
Q0E		Carpet Adhesive Tan w/Green Carpet				Total Amount - 1100 Sq Ft	
	171	ROOM 1329	NONE DETECTED	110508ML-35		1100 Sq Ft	
Q0F		Carpet Adhesive Purple Multi-Colored (2001)				Total Amount - 2130 Sq Ft	
	206	ROOMS 1216, 1217, 1218 & 1219	NONE DETECTED	110508ML-37	ROOM 1217.	2000 Sq Ft	
	222	STORAGE 1205	NONE DETECTED			130 Sq Ft	
ROA		Baseboard/Mopboard Adhesive 4" Gray Baseboard				Total Amount - 100 Sq Ft	
	5	THROUGHOUT BUILDING	NONE DETECTED	110508ML-14	CAFETERIA.	100 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROB		Baseboard/Mopboard Adhesive 4" Tan Baseboard				Total Amount - 200 Sq Ft
	6	THROUGHOUT BUILDING	NONE DETECTED	110508ML-15	HALLWAY OUTSIDE ROOM 1105.	200 Sq Ft
ROC		Baseboard/Mopboard Adhesive 4" Black Baseboard				Total Amount - 200 Sq Ft
	7	THROUGHOUT BUILDING	NONE DETECTED	110508ML-21	ROOM 1103.	200 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier 1964 Original Building				Total Amount - 800 Sq Ft
	42	STAGE (1108)	ASSUMED			800 Sq Ft
TOA		Light Cord Insulation				Total Amount - 500 Lin Ft
	12	THROUGHOUT 1964 ORIGINAL BUILDING	50 CH	2001-01104-5		500 Lin Ft
VOD		Sink Undercoating Gray (1996)				Total Amount - 30 Sq Ft
	214	THROUGHOUT 1996 ADDITION	NONE DETECTED	110508ML-09	ROOM 1213.	30 Sq Ft
VOF		Sink Undercoating Gray (2009)				Total Amount - 119 Sq Ft
	25	ROOM 1103	NEW			5 Sq Ft
	29	ROOM 1104	NEW			4 Sq Ft
	34	ROOM 1105	NEW			4 Sq Ft
	39	ROOM 1106	NEW			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	45	ROOM 1113 (EAST IMC STORAGE)	NEW			2 Sq Ft
	51	MAIN OFFICE WORK ROOM (1003)	NEW			4 Sq Ft
	81	ROOM 1316	NEW			4 Sq Ft
	86	ROOM 1315	NEW			4 Sq Ft
	90	ROOM 1314	NEW			4 Sq Ft
	95	ROOM 1312	NEW			4 Sq Ft
	98	ROOM 1309	NEW			4 Sq Ft
	103	ROOM 1310	NEW			4 Sq Ft
	114	ROOM 1301	NEW			4 Sq Ft
	118	ROOM 1303	NEW			4 Sq Ft
	122	ROOM 1304	NEW			4 Sq Ft
	127	ROOM 1305	NEW			4 Sq Ft
	132	ROOM 1322	NEW			4 Sq Ft
	137	ROOM 1321	NEW			4 Sq Ft
	142	ROOM 1324	NEW			4 Sq Ft
	147	ROOM 1323	NEW			4 Sq Ft
	152	ROOM 1326	NEW			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	157	ROOM 1325	NEW			4 Sq Ft
	169	ROOM 1330	NEW			4 Sq Ft
	178	ROOM 1332	NEW			4 Sq Ft
	184	ROOM 1331	NEW			8 Sq Ft
	190	ROOM 1334	NEW			4 Sq Ft
	194	ROOM 1335	NEW			4 Sq Ft
	198	ROOM 1336	NEW			4 Sq Ft
	202	ROOM 1337	NEW			4 Sq Ft
XOA	Miscellaneous Material Tan Penetration Putty					Total Amount - 50 Sq Ft
	19	1964 ORIGINAL BUILDING TUNNEL SYSTEM	25 CH	M2045-3A, B, C		50 Sq Ft
XOB	Miscellaneous Material Tan Adhesive Puck					Total Amount - 40 Sq Ft
	63	GIRLS' HAND WASHING/DRINKING FOUNTAIN CHASE EAST OF ROOM 1317	5 CH	110508ML-01		10 Sq Ft
	66	BOYS' HAND WASHING/DRINKING FOUNTAIN CHASE EAST OF ROOM 1316	5 CH			10 Sq Ft
	158	BOYS' HAND WASHING/DRINKING FOUNTAIN CHASE WEST OF ROOM 1330	5 CH			10 Sq Ft
	161	GIRLS' HAND WASHING/DRINKING FOUNTAIN CHASE WEST OF ROOM 1329	5 CH			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOC		Miscellaneous Material Black Adhesive Puck				Total Amount - 40 Sq Ft
	64	GIRLS' HAND WASHING/DRINKING FOUNTAIN CHASE EAST OF ROOM 1317	25 CH	110508ML-02		10 Sq Ft
	67	BOYS' HAND WASHING/DRINKING FOUNTAIN CHASE EAST OF ROOM 1316	25 CH			10 Sq Ft
	159	BOYS' HAND WASHING/DRINKING FOUNTAIN CHASE WEST OF ROOM 1330	25 CH			10 Sq Ft
	162	GIRLS' HAND WASHING/DRINKING FOUNTAIN CHASE WEST OF ROOM 1329	25 CH			10 Sq Ft
XOD		Miscellaneous Material Red Fire Stop				Total Amount - 100 Sq Ft
	9	THROUGHOUT BUILDING	NONE DETECTED	110508ML-17		100 Sq Ft
XOE		Miscellaneous Material Dark Gray Duct Caulk				Total Amount - 100 Sq Ft
	10	THROUGHOUT BUILDING	NONE DETECTED	110508ML-16	ROOM 1102A.	100 Sq Ft
XOF		Miscellaneous Material Mastic Associated w/Cork Ceiling Tiles				Total Amount - 600 Sq Ft
	13	THROUGHOUT 1964 ORIGINAL BUILDING HALLWAYS	NONE DETECTED	422-5		300 Sq Ft
	20	GYMNASIUM (1110)	NONE DETECTED			300 Sq Ft
XOG		Miscellaneous Material Metal Frame Chalkboard Adhesive (1964)				Total Amount - 455 Sq Ft
	30	ROOM 1104	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	35	ROOM 1105	ASSUMED			20 Sq Ft
	40	ROOM 1106	ASSUMED			20 Sq Ft
	71	ROOM 1320	ASSUMED			20 Sq Ft
	73	ROOM 1317	ASSUMED			20 Sq Ft
	78	ROOM 1316	ASSUMED			20 Sq Ft
	83	ROOM 1315	ASSUMED			20 Sq Ft
	88	ROOM 1314	ASSUMED			20 Sq Ft
	93	ROOM 1312	ASSUMED			20 Sq Ft
	100	ROOM 1310	ASSUMED			20 Sq Ft
	106	ROOM 1313	ASSUMED			15 Sq Ft
	129	ROOM 1322	ASSUMED			20 Sq Ft
	134	ROOM 1321	ASSUMED			20 Sq Ft
	139	ROOM 1324	ASSUMED			20 Sq Ft
	144	ROOM 1323	ASSUMED			20 Sq Ft
	149	ROOM 1326	ASSUMED			20 Sq Ft
	154	ROOM 1325	ASSUMED			20 Sq Ft
	166	ROOM 1330	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	170	ROOM 1329	ASSUMED			20 Sq Ft
	179	ROOM 1332	ASSUMED			20 Sq Ft
	181	ROOM 1331	ASSUMED			40 Sq Ft
	187	ROOM 1334	ASSUMED			20 Sq Ft
X0H	Miscellaneous Material Wired Window Glaze (1964)					Total Amount - 2 Sq Ft
	48	CONFERENCE ROOM (1111)	NONE DETECTED	110508ML-31		1 Sq Ft
	70	ROOM 1320	NONE DETECTED			1 Sq Ft
X0I	Miscellaneous Material Wired Side Light Window Glaze (1964)					Total Amount - 30 Sq Ft
	75	ROOM 1317	4 CH	110508ML-32		2 Sq Ft
	79	ROOM 1316	4 CH			2 Sq Ft
	84	ROOM 1315	4 CH			2 Sq Ft
	101	ROOM 1310	4 CH			2 Sq Ft
	130	ROOM 1322	4 CH			2 Sq Ft
	135	ROOM 1321	4 CH			2 Sq Ft
	140	ROOM 1324	4 CH			2 Sq Ft
	145	ROOM 1323	4 CH			2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	150	ROOM 1326	4 CH			2 Sq Ft
	155	ROOM 1325	4 CH			2 Sq Ft
	167	ROOM 1330	4 CH			2 Sq Ft
	172	ROOM 1329	4 CH			2 Sq Ft
	176	ROOM 1332	4 CH			2 Sq Ft
	182	ROOM 1331	4 CH			2 Sq Ft
	188	ROOM 1334	4 CH			2 Sq Ft
X0J	Miscellaneous Material Metal Frame Chalkboard Adhesive (1966)					Total Amount - 140 Sq Ft
	112	ROOM 1301	ASSUMED			20 Sq Ft
	116	ROOM 1303	ASSUMED			20 Sq Ft
	120	ROOM 1304	ASSUMED			20 Sq Ft
	125	ROOM 1305	ASSUMED			20 Sq Ft
	192	ROOM 1335	ASSUMED			20 Sq Ft
	196	ROOM 1336	ASSUMED			20 Sq Ft
	200	ROOM 1337	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOK		Miscellaneous Material Air Handling Seam Gasket (1966)				Total Amount - 2 Sq Ft
	109	1966 ADDITION WEST TUNNEL SYSTEM	NONE DETECTED			1 Sq Ft
	204	1966 ADDITION EAST TUNNEL SYSTEM	NONE DETECTED	110508ML-04		1 Sq Ft
XOL		Miscellaneous Material Black Window Sills (2001)				Total Amount - 40 Sq Ft
	207	ROOMS 1216, 1217, 1218 & 1219	NONE DETECTED	110508ML-38	ROOM 1218.	40 Sq Ft
XOM		Miscellaneous Material Black Window Sill (1996)				Total Amount - 80 Sq Ft
	211	THROUGHOUT 1996 ADDITION	NONE DETECTED	110508ML-10	ROOM 1208.	80 Sq Ft
XON		Miscellaneous Material Wired Window Glaze (1996)				Total Amount - 15 Sq Ft
	212	THROUGHOUT 1996 ADDITION	NONE DETECTED	110508ML-11	ROOM 1206.	15 Sq Ft
XOO		Miscellaneous Material Metal Frame Chalkboard Adhesive (1996)				Total Amount - 120 Sq Ft
	213	THROUGHOUT 1996 ADDITION	ASSUMED			120 Sq Ft
XOP		Miscellaneous Material Air Handling Unit Seam Gasket (1996)				Total Amount - 4 Sq Ft
	223	1996 ADDITION UPPER LEVEL MECHANICAL ROOM	NONE DETECTED	110508ML-05		4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1A	Miscellaneous Material 6" Brown Quarry Tile System					Total Amount - 568 Sq Ft
	31	ROOM 1104 RESTROOM	ASSUMED			15 Sq Ft
	36	ROOM 1105 RESTROOM	ASSUMED			15 Sq Ft
	41	ROOM 1106 RESTROOM	ASSUMED			15 Sq Ft
	62	NURSE'S OFFICE/SICK ROOM RESTROOM	ASSUMED			15 Sq Ft
	65	GIRLS' RESTROOM EAST OF ROOM 1317	ASSUMED			110 Sq Ft
	68	BOYS' RESTROOM EAST OF ROOM 1316	ASSUMED			110 Sq Ft
	160	BOYS' RESTROOM WEST OF ROOM 1330	ASSUMED			144 Sq Ft
	163	GIRLS' RESTROOM WEST OF ROOM 1329	ASSUMED			144 Sq Ft
X1B	Miscellaneous Material 8" Purple Quarry Tile System					Total Amount - 80 Sq Ft
	43	RESTROOM 1113 NEAR ROOM 1106	ASSUMED			40 Sq Ft
	104	RESTROOM 1310A	ASSUMED			40 Sq Ft
X1C	Miscellaneous Material 4" Cream Ceramic Wall Tile System (1996)					Total Amount - 150 Sq Ft
	219	ROOM 1215 RESTROOM (1215A)	NEW			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1D		Miscellaneous Material 2" Beige Ceramic Floor Tile System (1996)				Total Amount - 36 Sq Ft
	220	ROOM 1215 RESTROOM (1215A)	NEW			36 Sq Ft
X1E		Miscellaneous Material 6" Red Quarry Tile System (1996)				Total Amount - 1670 Sq Ft
	221	1996 ADDITION RESTROOMS 1209 & 1207	NEW			570 Sq Ft
	224	THROUGHOUT KITCHEN AREA	NEW			1100 Sq Ft