

2121 North Park Drive, Saint Paul, MN 55119

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A		Mudded Pipe Joints on Fiberglass Insulation 1971 Original Building				Total Amount - 931 Joints
	1	THROUGHOUT BUILDING	NONE DETECTED	2001-01105-5, 11; 061008ML-01, 02, 03	5: HALLWAY BY ROOM 1205. 01,02,03: ROOM 1201, ROOM 1206, ROOM 1203 (RESPECTIVELY) IN FLOOR TRENCHES (SINCE REMOVED).	420 Joints
	21	BOILER ROOM 1502 & UPPER FAN ROOM 2501	NONE DETECTED	195A1A, 509B1-P, B2; MGM-256-WI-3, S1-3, V1-3	WATER, STEAM HEADER & VALVES.	116 Joints
	26	CUSTODIAL ROOMS 1503 & 1511 OFF BOILER ROOM	NONE DETECTED			10 Joints
	28	ROOM 1508	NONE DETECTED			14 Joints
	30	ROOM 1509 (BAND)	NONE DETECTED			7 Joints
	35	AUDITORIUM STAGE 1407	NONE DETECTED			4 Joints
	38	ROOM 1407B	NONE DETECTED			1 Joints
	75	ROOM 1207	NONE DETECTED			7 Joints
	106	ROOM 1114	NONE DETECTED			25 Joints
	109	ROOM 1113	NONE DETECTED			6 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	111	ROOMS 1107-1112	NONE DETECTED			31 Joints
	113	ROOM 1109 OFF ROOM 1108	NONE DETECTED			4 Joints
	116	ROOM 1104	NONE DETECTED			7 Joints
	118	ROOM 1103	NONE DETECTED			22 Joints
	124	OFFICE MECHANICAL ROOM 1006	NONE DETECTED			25 Joints
	159	ROOM 2302 MECHANICAL	NONE DETECTED			55 Joints
	163	ABOVE AUDITORIUM CEILING (2302A)	NONE DETECTED			45 Joints
	210	2ND FLOOR MECHANICAL ROOM 2102	NONE DETECTED			110 Joints
	218	ROOM 2110 (KITCHEN LOADING DOCK)	NONE DETECTED			22 Joints
A4B		Mudded Pipe Joints on Fiberglass Insulation Roof Drains (1971)				Total Amount - 3 Joints
	22	BOILER ROOM 1502	NONE DETECTED			1 Joints
	107	ROOM 1114	NONE DETECTED	08092012MA-07	MA-07: ROOM 1114.	2 Joints
D2A		Interior Boiler Insulation Boiler Door Refractory				Total Amount - 45 Sq Ft
	23	BOILER ROOM 1502	NONE DETECTED	073115BV-01, 02, 03	BV-01,02,03: BOILER ROOM.	45 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
F2A	Exterior Duct Insulation Fiberglass (1971)		Total Amount - 2800 Sq Ft			
	20	BOILER ROOM 1502 & UPPER FAN ROOM 2501	NONE DETECTED	2001-1501-BM-2, 2001-1901-1996-3W & 4W		900 Sq Ft
	125	OFFICE MECHANICAL ROOM 1006	NONE DETECTED			200 Sq Ft
	160	ROOM 2302 MECHANICAL	NONE DETECTED			900 Sq Ft
	211	2ND FLOOR MECHANICAL ROOM 2102	NONE DETECTED			400 Sq Ft
	219	ROOM 2110 (KITCHEN LOADING DOCK)	NONE DETECTED			100 Sq Ft
	221	ROOM 2110A	NONE DETECTED			300 Sq Ft
G1A	Sprayed-On Acoustical Finish Thin, White Texture		Total Amount - 60440 Sq Ft			
	65	ROOM 1205	2-4 CH	11-03-08-MA-08		1500 Sq Ft
	69	ROOM 1206	2-4 CH			2500 Sq Ft
	76	ROOM 1207	2-4 CH	08092012MA-08	MA-08: ROOM 1207 *DEBRIS*.	1000 Sq Ft
	81	ROOM 1208	2-4 CH	11-03-08-MA-12		2500 Sq Ft
	85	1ST FLOOR HALLWAY 1004	2-4 CH			1000 Sq Ft
	87	ROOM 1201	2-4 CH			2500 Sq Ft
	92	ROOM 1202	2-4 CH			2000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	97	ROOM 1203	2-4 CH			2500 Sq Ft
	101	HALLWAY EAST OF ROOMS 1204 & 1205	2-4 CH			1080 Sq Ft
	102	ROOM 1204	2-4 CH			2500 Sq Ft
	135	ROOM 1610	2-4 CH			1400 Sq Ft
	137	ROOM 1609	2-4 CH	11-04-08-MA-09		1400 Sq Ft
	139	ROOM 1608	2-4 CH			1500 Sq Ft
	141	ROOM 1607	2-4 CH			1500 Sq Ft
	143	1ST FLOOR HALLWAY 1007	2-4 CH			1080 Sq Ft
	144	ROOM 1606	2-4 CH			2000 Sq Ft
	146	ROOM 1605	2-4 CH	11-04-08-MA-10		1100 Sq Ft
	148	ROOM 1604	2-4 CH			1500 Sq Ft
	150	ROOM 1603	2-4 CH			1500 Sq Ft
	154	ROOM 1602	2-4 CH			700 Sq Ft
	155	ROOM 1601	2-4 CH			1200 Sq Ft
	157	2ND FLOOR CENTER STAIR AREAS 2009-2010	2-4 CH			3600 Sq Ft
	166	ROOM 2204 (LIBRARY)	2-4 CH	11-04-08-MA-08		10000 Sq Ft
	170	ROOM 2601	2-4 CH			1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	172	ROOM 2602	2-4 CH			1500 Sq Ft
	174	ROOM 2603	2-4 CH			1500 Sq Ft
	176	ROOM 2605	2-4 CH			1200 Sq Ft
	185	2ND FLOOR HALLWAY 2600B	2-4 CH			1080 Sq Ft
	186	ROOM 2606	2-4 CH	11-04-08-MA-06		1600 Sq Ft
	188	ROOM 2608	2-4 CH			1300 Sq Ft
	190	ROOM 2609	2-4 CH			1600 Sq Ft
	192	ROOM 2610	2-4 CH	11-04-08-MA-02		1600 Sq Ft
H1A	Sprayed-On Structural Fireproofing Tan (1971)					Total Amount - 803 Sq Ft
	34	AUDITORIUM STAGE 1407	20 CH	2001-1901-BM-15		600 Sq Ft
	40	ROOM 1407B	20 CH	1991-2728, 2729, 2730		3 Sq Ft
	42	ROOM 1406	20 CH			80 Sq Ft
	127	ROOM 1007 (PRINCIPAL'S OFFICE)	20 CH			120 Sq Ft
H1B	Sprayed-On Structural Fireproofing Charcoal (1997)					Total Amount - 10250 Sq Ft
	31	AUDITORIUM 1403	NONE DETECTED	310-12, 13, 14, 15, 16, 17, 18		6000 Sq Ft
	37	AUDITORIUM STAGE 1407	NONE DETECTED			3450 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	39	ROOM 1407B	NONE DETECTED			400 Sq Ft
	41	ROOM 1406	NONE DETECTED			400 Sq Ft
H1C	Sprayed-On Structural Fireproofing Blue (1991)					Total Amount - 30000 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	2001-01105-2-4, 7-9; 2001-1901-BM-12, 13, 14	BM-12,13,14: BOILER ROOM.	30000 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Pin Holes & Gouges in Concentric Pattern (1997)					Total Amount - 1220 Sq Ft
	56	LOWER LEVEL HALLWAY 1300C	NONE DETECTED			500 Sq Ft
	58	1ST FLOOR HALLWAY 1300B	NONE DETECTED	11-03-08-MA-07		220 Sq Ft
	61	UPPER LEVEL GYMNASIUM HALLWAY 2300B	NONE DETECTED			500 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Rough w/Revealed Edge (2008)					Total Amount - 5470 Sq Ft
	73	ROOM 1206	NONE DETECTED			1000 Sq Ft
	74	ROOM 1207	NONE DETECTED			480 Sq Ft
	80	ROOM 1208	NONE DETECTED	11-03-08-MA-13		1000 Sq Ft
	86	ROOM 1201	NONE DETECTED			1000 Sq Ft
	91	ROOM 1202	NONE DETECTED			890 Sq Ft
	96	ROOM 1203	NONE DETECTED			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	114	ROOM 1112	NONE DETECTED			100 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Light Texture					Total Amount - 2000 Sq Ft
	112	ROOMS 1107-1112	NEW			2000 Sq Ft
I3A	2' x 4' Ceiling Tile Gouges & Pin Holes in Concentric Pattern					Total Amount - 50000 Sq Ft
	5	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-BM-5		50000 Sq Ft
I3B	2' x 4' Ceiling Tile White, Vinyl Covered					Total Amount - 1200 Sq Ft
	158	2ND FLOOR RESTROOMS 2101, 2103, 2301 & 2306	NONE DETECTED	2001-1501-BM-12; 310-3	310-3: ROOM 1306 (BOYS' LOCKER ROOM) (SINCE REMOVED).	1200 Sq Ft
I3C	2' x 4' Ceiling Tile Vinyl-Covered Gypsum					Total Amount - 1818 Sq Ft
	122	RESTROOMS 1102 & 1101	NSM			600 Sq Ft
	214	ROOM 2105 (FACULTY DINING)	NSM			378 Sq Ft
	216	ROOM 2106 (KITCHEN)	NSM			840 Sq Ft
I3D	2' x 4' Ceiling Tile Dents w/Pin Holes (1992)					Total Amount - 1800 Sq Ft
	46	ROOM 1306 (BOYS' LOCKER ROOM)	NEW			900 Sq Ft
	51	ROOM 1311 (GIRLS' LOCKER ROOM)	NEW			900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I4A	Acoustical Ceiling Tile Pin Holes in Clusters					Total Amount - 1550 Sq Ft
	66	ROOM 1205	NONE DETECTED			70 Sq Ft
	68	SCIENCE ROOMS 1201-1203 & 1206-1208	NONE DETECTED	2001-1501-BM-10	BM-10: ROOM 1207.	300 Sq Ft
	103	ROOM 1204	NONE DETECTED			70 Sq Ft
	136	ROOM 1610	NONE DETECTED			50 Sq Ft
	138	ROOM 1609	NONE DETECTED			50 Sq Ft
	140	ROOM 1608	NONE DETECTED			60 Sq Ft
	142	ROOM 1607	NONE DETECTED			60 Sq Ft
	145	ROOM 1606	NONE DETECTED			50 Sq Ft
	147	ROOM 1605	NONE DETECTED			40 Sq Ft
	149	ROOM 1604	NONE DETECTED			70 Sq Ft
	151	ROOM 1603	NONE DETECTED			70 Sq Ft
	153	ROOM 1602	NONE DETECTED			30 Sq Ft
	156	ROOM 1601	NONE DETECTED			70 Sq Ft
	171	ROOM 2601	NONE DETECTED			70 Sq Ft
	173	ROOM 2602	NONE DETECTED			70 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	175	ROOM 2603	NONE DETECTED			70 Sq Ft
	177	ROOM 2605	NONE DETECTED			60 Sq Ft
	187	ROOM 2606	NONE DETECTED			70 Sq Ft
	189	ROOM 2608	NONE DETECTED			60 Sq Ft
	191	ROOM 2609	NONE DETECTED			80 Sq Ft
	193	ROOM 2610	NONE DETECTED	11-04-08-MA-03		80 Sq Ft
I4C	Acoustical Ceiling Tile Light Fixture Heat Shields					Total Amount - 300 Sq Ft
	196	ROOM 2617	NONE DETECTED			100 Sq Ft
	200	ROOM 2614	NONE DETECTED	11-04-08-MA-05		100 Sq Ft
	207	ROOM 2611	NONE DETECTED			100 Sq Ft
J3A	Miscellaneous Cementitious Material Black Plastic Lab Tabletops					Total Amount - 2000 Sq Ft
	67	SCIENCE ROOMS 1201-1203 & 1206-1208	NSM			2000 Sq Ft
K0A	9" x 9" Vinyl Floor Tile & Mastic Dark Gray w/White Streaks					Total Amount - 30 Sq Ft
	121	ELEVATOR	3 CH (TILE)	11-03-08-MA-17		30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
KOC		9" x 9" Vinyl Floor Tile & Mastic Beige w/Tan Swirls				Total Amount - 6026 Sq Ft
	179	ROOM 2504	>1-4 CH (TILE), 10-15 CH (MASTIC)	310-11		1456 Sq Ft
	180	ROOM 2507 OFF ROOM 2504	>1-4 CH (TILE), 10-15 CH (MASTIC)			126 Sq Ft
	213	ROOM 2104 (CAFETERIA)	>1-4 CH (TILE), 10-15 CH (MASTIC)	2001-01105-26, ; 2001-1901-ZZ-32B		3986 Sq Ft
	215	ROOM 2105 (FACULTY DINING)	>1-4 CH (TILE), 10-15 CH (MASTIC)			378 Sq Ft
	217	ROOM 2106C (KITCHEN OFFICE)	>1-4 CH (TILE), 10-15 CH (MASTIC)			80 Sq Ft
KOD		9" x 9" Vinyl Floor Tile & Mastic Gray w/Brown & White Flecks				Total Amount - 9074 Sq Ft
	63	UPPER GYMNASIUM 2303 & 2304	>1-3 CH (TILE), 10-15 CH (MASTIC)	2001-1501-BM-11, ; 2001-1901-ZZ-33B		4300 Sq Ft
	128	ROOM 1010 (OFFICE STORAGE)	>1-3 CH (TILE), 10-15 CH (MASTIC)	310-8		276 Sq Ft
	131	ROOM 1003 (NURSE'S OFFICE)	>1-3 CH (TILE), 10-15 CH (MASTIC)			175 Sq Ft
	133	ROOM 1020 (BOYS' COT ROOM) OFF ROOM 1022	>1-3 CH (TILE), 10-15 CH (MASTIC)			168 Sq Ft
	134	ROOM 1021 (GIRLS' COT ROOM) OFF ROOM 1022	>1-3 CH (TILE), 10-15 CH (MASTIC)			168 Sq Ft
	194	ROOM 2617	>1-3 CH (TILE), 10-15 CH (MASTIC)			1170 Sq Ft
	197	ROOM 2619 OFF ROOM 2617	>1-3 CH (TILE), 10-15 CH (MASTIC)			145 Sq Ft
	198	ROOM 2618 OFF ROOM 2617	>1-3 CH (TILE), 10-15 CH (MASTIC)			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	199	ROOM 2614	>1-3 CH (TILE), 10-15 CH (MASTIC)			1170 Sq Ft
	202	ROOM 2616 OFF ROOM 2614	>1-3 CH (TILE), 10-15 CH (MASTIC)			200 Sq Ft
	203	ROOM 2615 OFF ROOM 2614	>1-3 CH (TILE), 10-15 CH (MASTIC)			154 Sq Ft
	205	ROOM 2611	>1-3 CH (TILE), 10-15 CH (MASTIC)			828 Sq Ft
	208	ROOM 2613 OFF ROOM 2611	>1-3 CH (TILE), 10-15 CH (MASTIC)			120 Sq Ft
	209	ROOM 2612 OFF ROOM 2611	>1-3 CH (TILE), 10-15 CH (MASTIC)			100 Sq Ft
K1A	Sheet Vinyl Flooring & Adhesive Light Blue					Total Amount - 70 Sq Ft
	104	ROOM 1114	NONE DETECTED	11-03-08-MA-14; 310-5		20 Sq Ft
	110	ROOM 1113	NONE DETECTED			50 Sq Ft
K1B	Sheet Vinyl Flooring & Adhesive Light Gray w/Gray Flecks (2020)					Total Amount - 224 Sq Ft
	130	NURSE/HEALTH AREA 1022	NEW			224 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic White w/Tan Flecks					Total Amount - 300 Sq Ft
	43	ROOM 1404	NONE DETECTED			150 Sq Ft
	44	ROOM 1402	NONE DETECTED	11-03-08-MA-02		150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2B	12" x 12" Vinyl Floor Tile & Mastic Plum w/Mauve & Gray Mottle (1997)					Total Amount - 1735 Sq Ft
	55	LOWER LEVEL HALLWAY 1300C	NONE DETECTED	11-03-08-MA-06		500 Sq Ft
	57	1ST FLOOR HALLWAY 1300B	NONE DETECTED			150 Sq Ft
	59	ELEVATOR (1997 BUILDING ADDITION)	NONE DETECTED			35 Sq Ft
	60	UPPER LEVEL GYMNASIUM HALLWAY 2300B	NONE DETECTED	310-10		700 Sq Ft
	165	2ND FLOOR HALLWAY 2300A	NONE DETECTED			350 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic Tan Mottle (2008)					Total Amount - 2660 Sq Ft
	70	ROOM 1206	NONE DETECTED			540 Sq Ft
	77	ROOM 1207	NONE DETECTED	11-03-08-MA-09		160 Sq Ft
	82	ROOM 1208	NONE DETECTED			540 Sq Ft
	88	ROOM 1201	NONE DETECTED			540 Sq Ft
	93	ROOM 1202	NONE DETECTED			340 Sq Ft
	98	ROOM 1203	NONE DETECTED			540 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Dark Brown Mottle (2008)					Total Amount - 3145 Sq Ft
	71	ROOM 1206	NONE DETECTED			600 Sq Ft
	78	ROOM 1207	NONE DETECTED	11-03-08-MA-10		270 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	83	ROOM 1208	NONE DETECTED			600 Sq Ft
	89	ROOM 1201	NONE DETECTED			600 Sq Ft
	94	ROOM 1202	NONE DETECTED			475 Sq Ft
	99	ROOM 1203	NONE DETECTED			600 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (2008)					Total Amount - 710 Sq Ft
	72	ROOM 1206	NONE DETECTED			120 Sq Ft
	79	ROOM 1207	NONE DETECTED	11-03-08-MA-11		60 Sq Ft
	84	ROOM 1208	NONE DETECTED			120 Sq Ft
	90	ROOM 1201	NONE DETECTED			120 Sq Ft
	95	ROOM 1202	NONE DETECTED			100 Sq Ft
	100	ROOM 1203	NONE DETECTED			120 Sq Ft
	115	ROOM 1111 OFF ROOM 1112	NONE DETECTED			70 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Large Light & Dark Gray Mottle					Total Amount - 1000 Sq Ft
	119	ROOM 1103	NONE DETECTED	11-03-08-MA-16; 310-6		1000 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown, White & Pink Flecks					Total Amount - 342 Sq Ft
	204	ROOM 2611	10 CH (MASTIC)	11-04-08-MA-04		342 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2H	12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan & White Flecks					Total Amount - 2080 Sq Ft
	181	ROOM 2503	NONE DETECTED			980 Sq Ft
	183	ROOM 2502	NONE DETECTED	11-04-08-MA-07		1100 Sq Ft
K3A	Miscellaneous Flooring Tan Rubber					Total Amount - 5400 Sq Ft
	50	LOWER GYMNASIUM 1304 & 1305	NONE DETECTED	2001-1901-BMS-1B	WEST SIDE.	5400 Sq Ft
K3B	Miscellaneous Flooring White w/Brown & Gray Pebbles Epoxy Flooring (2020)					Total Amount - 2000 Sq Ft
	7	THROUGHOUT BUILDING	NEW			2000 Sq Ft
LOA	Flexible Duct Connector Vinyl					Total Amount - 215 Sq Ft
	19	BOILER ROOM 1502 & UPPER FAN ROOM 2501	NONE DETECTED	2001-1501-BM-1		120 Sq Ft
	64	ELEVATOR EQUIPMENT ROOM 1301	NONE DETECTED			2 Sq Ft
	126	OFFICE MECHANICAL ROOM 1006	NONE DETECTED			20 Sq Ft
	161	ROOM 2302 MECHANICAL	NONE DETECTED			8 Sq Ft
	164	ABOVE AUDITORIUM CEILING (2302A)	NONE DETECTED			15 Sq Ft
	212	2ND FLOOR MECHANICAL ROOM 2102	NONE DETECTED			40 Sq Ft
	220	ROOM 2110 (KITCHEN LOADING DOCK)	NONE DETECTED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOA		Plaster 1971 Original Building			Total Amount - 40000 Sq Ft	
	2	THROUGHOUT BUILDING	NONE DETECTED	061808-BF-1, 2, 3, 4, 5; 206B1A, 509B3-P, B4; 110308-MA-04, 05, 15	BF-1,2,3,4,5: PLASTER OVERSPRAY. MA-04: ROOM 1402. MA-05: ROOM 1306. MA- 15: ROOM 1107 (OVERSPRAY).	40000 Sq Ft
MOB		Plaster Light Recess Areas			Total Amount - 900 Sq Ft	
	162	ABOVE AUDITORIUM CEILING (2302A)	NONE DETECTED	2001-1501-BM-3, 2001-1901-1996-1 & 2; 2001-1901-BM-20, 21, 22		900 Sq Ft
NOB		Drywall/Joint Compound Vinyl-Covered Wall Panels			Total Amount - 16000 Sq Ft	
	3	THROUGHOUT BUILDING	NONE DETECTED	2001-01105-12; 310-9	12: ROOM 1606. 9: SHOP AREA.	16000 Sq Ft
NOC		Drywall/Joint Compound 20XX Installation			Total Amount - 600 Sq Ft	
	117	ROOM 1104	NEW			600 Sq Ft
POB		Fire Doors Wood Composite - 1 Hr Rating (Warnock Hersey)			Total Amount - 1000 Sq Ft	
	16	THROUGHOUT BUILDING	NONE DETECTED	2001-01105-31	31: LOWER GYMNASIUM STORAGE.	1000 Sq Ft
POC		Fire Doors Dark Brown Vinyl Laminate w/Wood Core			Total Amount - 2000 Sq Ft	
	14	THROUGHOUT BUILDING	NSM			2000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
POD	Fire Doors Door Transom Panels (Mineral Core)					Total Amount - 30 Sq Ft
	54	LOWER LEVEL HALLWAY 1300D OUTSIDE LOCKER ROOMS	35 CH, 15 AM			12 Sq Ft
	62	UPPER LEVEL GYMNASIUM HALLWAY 2300B	35 CH, 15 AM	2001-1901-XX-45B		12 Sq Ft
	105	ROOM 1114	35 CH, 15 AM			6 Sq Ft
POE	Fire Doors Door Transom Panels (Wood Core)					Total Amount - 262 Sq Ft
	17	THROUGHOUT BUILDING	NSM			250 Sq Ft
	108	1ST FLOOR HALLWAY 1100C	NSM			12 Sq Ft
POF	Fire Doors Wood Composite - 1.5 Hr Rating (Underwriter's Laboratories)					Total Amount - 48 Sq Ft
	167	ROOM 2204 (LIBRARY)	NONE DETECTED	11-04-08-MA-01		48 Sq Ft
POG	Fire Doors Solid Wood Core (Eggers)					Total Amount - 160 Sq Ft
	15	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-BM-6	BM-6: DOOR TO CAFETERIA.	160 Sq Ft
Q0A	Carpet Adhesive Blue & Gray Berber Carpet					Total Amount - 60000 Sq Ft
	6	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-1-BCM		60000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROA		Baseboard/Mopboard Adhesive Dark Brown Baseboard				Total Amount - 6500 Sq Ft
	8	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-JLC-19B	19B: BETWEEN ROOMS 1608 & 1609.	6500 Sq Ft
ROB		Baseboard/Mopboard Adhesive 4" Gray Baseboard				Total Amount - 30 Sq Ft
	152	ROOM 1603	NEW			30 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier 1971 Original Building				Total Amount - 1500 Sq Ft
	36	AUDITORIUM STAGE 1407	ASSUMED			1500 Sq Ft
TOA		Light Cord Insulation Green, White & Black Cords				Total Amount - 50 Lin Ft
	32	AUDITORIUM CATWALK	70 CH	2001-1901-2-BCM		50 Lin Ft
TOB		Light Cord Insulation White				Total Amount - 6 Lin Ft
	33	AUDITORIUM CATWALK	ASSUMED			6 Lin Ft
VOB		Sink Undercoating White (2011)				Total Amount - 53 Sq Ft
	132	ROOM 1003 (NURSE'S OFFICE)	NEW			5 Sq Ft
	168	ROOM 2205	NEW			6 Sq Ft
	169	ROOM 2206	NEW			6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	184	ROOM 2502	NEW			6 Sq Ft
	195	ROOM 2617	NEW			10 Sq Ft
	201	ROOM 2614	NEW			10 Sq Ft
	206	ROOM 2611	NEW			10 Sq Ft
VOC	Sink Undercoating Gray (2011)					Total Amount - 95 Sq Ft
	29	ROOM 1509 (BAND)	NEW			5 Sq Ft
	123	OFFICE ROOM 1002	NEW			5 Sq Ft
	129	ROOM 1014	NEW			5 Sq Ft
	178	ROOM 2504	NEW			60 Sq Ft
	182	ROOM 2503	NEW			20 Sq Ft
XOA	Miscellaneous Material Thin, Metal-Framed Tackboard Adhesive					Total Amount - 600 Sq Ft
	9	THROUGHOUT BUILDING	NONE DETECTED	062011ML-02; 061008-ML-04	ML-02: ROOM 1501. ML-04: SCIENCE.	600 Sq Ft
XOB	Miscellaneous Material Thin, Metal-Framed Chalkboard Adhesive					Total Amount - 600 Sq Ft
	10	THROUGHOUT BUILDING	NONE DETECTED	062011ML-01; 061510-BF-1	ML-01: ROOM 1501. BF-1: ROOM 1104.	600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOC	Miscellaneous Material Black Wall Mastic		Total Amount - 8 Sq Ft			
	45	ROOM 1402	NONE DETECTED	11-03-08-MA-03		4 Sq Ft
	49	ROOM 1308	NONE DETECTED			4 Sq Ft
XOD	Miscellaneous Material Mirror Mastic		Total Amount - 50 Sq Ft			
	13	THROUGHOUT BUILDING	ASSUMED			50 Sq Ft
XOE	Miscellaneous Material Tackboard Adhesive		Total Amount - 12 Sq Ft			
	24	BOILER ROOM 1502	NONE DETECTED	073115BV-04	BV-04: BOILER ROOM.	12 Sq Ft
XOF	Miscellaneous Material Red Duct Caulk		Total Amount - 3 Sq Ft			
	25	BOILER ROOM 1502	NONE DETECTED	073115BV-05	BV-05: BOILER ROOM.	3 Sq Ft
XOG	Miscellaneous Material Acoustical Ceiling Panel Adhesive		Total Amount - 8 Sq Ft			
	120	ROOM 1103	NONE DETECTED	073115BV-06	BV-06: ROOM 1103.	8 Sq Ft
XOH	Miscellaneous Material Red Fire Stop		Total Amount - 100 Sq Ft			
	12	THROUGHOUT BUILDING	ASSUMED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1A		Miscellaneous Material 1" Brown Ceramic Floor Tile System				Total Amount - 1000 Sq Ft
	27	CUSTODIAL ROOM 1503	ASSUMED			100 Sq Ft
	47	ROOM 1306 (BOYS' LOCKER ROOM SHOWER AREA)	ASSUMED			400 Sq Ft
	48	ROOM 1307A (BOYS' LOCKER ROOM OFFICE)	ASSUMED			50 Sq Ft
	52	ROOM 1311 (GIRLS' LOCKER ROOM SHOWER AREA)	ASSUMED			400 Sq Ft
	53	ROOM 1312A (GIRLS' LOCKER ROOM OFFICE)	ASSUMED			50 Sq Ft
X1B		Miscellaneous Material 2" Brown Ceramic Floor Tile System				Total Amount - 2000 Sq Ft
	18	THROUGHOUT BUILDING RESTROOMS	ASSUMED			2000 Sq Ft
X1C		Miscellaneous Material 4" x 8" Red Quarry Tile				Total Amount - 2000 Sq Ft
	11	THROUGHOUT BUILDING	ASSUMED			2000 Sq Ft