

350 Colborne Street, Saint Paul, MN 55102

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A		Mudded Pipe Joints on Fiberglass Insulation 1973 Original Building				Total Amount - 883 Joints
	3	THROUGHOUT BUILDING	NONE DETECTED	ACB450KK-A4; 450KK-1-3, 4, 5		765 Joints
	56	STORAGE ROOM 1114	NONE DETECTED			10 Joints
	59	GYMNASIUM 1201/1202	NONE DETECTED			2 Joints
	63	NORTH GYMNASIUM MECHANICAL ROOM 1201B	NONE DETECTED			23 Joints
	66	SOUTH GYMNASIUM MECHANICAL ROOM 1202B	NONE DETECTED			23 Joints
	69	CLASSROOM POD SOUTH OF GYMNASIUM	NONE DETECTED			60 Joints
G1A		Sprayed-On Acoustical Finish White Textured				Total Amount - 1800 Sq Ft
	28	POOL 1104	<1 CH	2001-01107-1-7		1800 Sq Ft
H1B		Sprayed-On Structural Fireproofing Gray & Fluffy				Total Amount - 43500 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-AT-6-12	PENTHOUSE, STAIRS, HALLWAY & PODS 1, 2 & 3.	43500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
H1C	Sprayed-On Structural Fireproofing Tan w/Vermiculite		Total Amount - 3000 Sq Ft			
	1	THROUGHOUT BUILDING	10 CH	101408ML-34		3000 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Worms & Small Holes w/Revealed Edge		Total Amount - 200 Sq Ft			
	21	MAIN OFFICE RECEPTION AREA	NONE DETECTED	ACB450KK-A6, A8		200 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Fissured		Total Amount - 300 Sq Ft			
	39	POOL FILTER ROOM 1108	NONE DETECTED	101408ML-15		130 Sq Ft
	40	OFFICE 1111	NONE DETECTED			80 Sq Ft
	55	STORAGE ROOM 1114	NONE DETECTED			90 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Nail & Pin Holes in Concentric Circles		Total Amount - 4690 Sq Ft			
	25	RESTROOMS 1101 & 1102	NONE DETECTED			150 Sq Ft
	29	GIRLS' POOL LOCKER ROOM 1115 & HALLWAY C108	NONE DETECTED			600 Sq Ft
	37	BOYS' POOL LOCKER ROOM 1110 & HALLWAY 1107A	NONE DETECTED			600 Sq Ft
	41	HALLWAY 1200 BETWEEN GYMNASIUM & LOCKER ROOMS	NONE DETECTED	101408ML-16		500 Sq Ft
	42	ENTRY TO ROOMS 1112 & 1113	NONE DETECTED			35 Sq Ft
	44	ROOM 1112	NONE DETECTED			400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	49	RESTROOM 1113A	NONE DETECTED			70 Sq Ft
	50	ROOM 1113	NONE DETECTED			400 Sq Ft
	102	RESTROOM 1307	NONE DETECTED			70 Sq Ft
	114	STAFF RESTROOM 1313	NONE DETECTED			30 Sq Ft
	115	HALLWAY 1300B	NONE DETECTED			375 Sq Ft
	117	ROOM 1311	NONE DETECTED			700 Sq Ft
	120	BOYS' RESTROOM 1309	NONE DETECTED			130 Sq Ft
	121	GIRLS' RESTROOM 1310	NONE DETECTED			130 Sq Ft
	137	RESTROOM 1609A	NONE DETECTED			250 Sq Ft
	139	RESTROOM 1607A	NONE DETECTED			250 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Gouges & Pin Holes w/Revealed Edge					Total Amount - 31000 Sq Ft
	7	THROUGHOUT BUILDING	NONE DETECTED	101408ML-21	ML-21: ROOM 1316.	31000 Sq Ft
I2G	2' x 2' Acoustical Ceiling Tile Vinyl-Covered Sheetrock					Total Amount - 590 Sq Ft
	81	KITCHEN AREA 1501	NSM			480 Sq Ft
	85	DISHWASHING ROOM 1502	NSM			110 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3A	2' x 4' Ceiling Tile Unfinished Texture		Total Amount - 2500 Sq Ft			
	57	GYMNASIUM 1201/1202	ASSUMED			2500 Sq Ft
K1B	Sheet Vinyl Flooring & Adhesive Cream w/Blue & Red Dots		Total Amount - 1000 Sq Ft			
	93	ROOM 1321	NONE DETECTED			150 Sq Ft
	95	ROOM 1320	NONE DETECTED			160 Sq Ft
	96	ROOM 1318	NONE DETECTED			540 Sq Ft
	98	CUSTODIAL CLOSET 1304	NONE DETECTED			10 Sq Ft
	100	RESTROOM 1305	NONE DETECTED	2001-1501-AT04	AT04: STAGE ROOM.	140 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Blue w/White & Blue Smears		Total Amount - 2190 Sq Ft			
	70	CLASSROOM POD SOUTH OF GYMNASIUM	<1 CH (TILE ONLY)			1000 Sq Ft
	106	ROOM 1316	<1 CH (TILE ONLY)	2001-01107-8		90 Sq Ft
	110	ROOM 1315	<1 CH (TILE ONLY)			250 Sq Ft
	126	SOUTHEAST CLASSROOM POD	<1 CH (TILE ONLY)			850 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic White w/Grass Streaks		Total Amount - 150 Sq Ft			
	125	LAUNDRY ROOM 1601	NONE DETECTED	2001-1501-AT01		150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2D		12" x 12" Vinyl Floor Tile & Mastic Brown w/Tan Streaks			Total Amount - 6444 Sq Ft	
	31	ROOM 1105	3 CH (TILE), 10 CH (MASTIC)			850 Sq Ft
	33	ROOM 1106	3 CH (TILE), 10 CH (MASTIC)			230 Sq Ft
	35	STORAGE 1107	3 CH (TILE), 10 CH (MASTIC)			230 Sq Ft
	47	ROOM 1112	3 CH (TILE), 10 CH (MASTIC)	101408ML-19		50 Sq Ft
	53	ROOM 1113	3 CH (TILE), 10 CH (MASTIC)			50 Sq Ft
	60	GYMNASIUM 1201/1202	3 CH (TILE), 10 CH (MASTIC)			4200 Sq Ft
	88	ROOM 1301A	3 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	99	CUSTODIAL CLOSET 1304	3 CH (TILE), 10 CH (MASTIC)			4 Sq Ft
	103	ROOM 1317	3 CH (TILE), 10 CH (MASTIC)			680 Sq Ft
K2E		12" x 12" Vinyl Floor Tile & Mastic Yellow Mottle			Total Amount - 1075 Sq Ft	
	82	CAFETERIA 1500	NONE DETECTED	101408ML-25		1075 Sq Ft
K2F		12" x 12" Vinyl Floor Tile & Mastic Blue Mottle			Total Amount - 1075 Sq Ft	
	83	CAFETERIA 1500	NONE DETECTED	101408ML-26		1075 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2G		12" x 12" Vinyl Floor Tile & Mastic Light Blue Mottle				Total Amount - 70 Sq Ft
	112	ROOM 1315	NONE DETECTED	101408ML-30		70 Sq Ft
K2H		12" x 12" Vinyl Floor Tile & Mastic Olive Mottle				Total Amount - 4500 Sq Ft
	9	THROUGHOUT BUILDING	NONE DETECTED	101408ML-14		4500 Sq Ft
K2I		12" x 12" Vinyl Floor Tile & Mastic Gray w/Green & White Streaks				Total Amount - 330 Sq Ft
	24	HALLWAY 1100	NONE DETECTED	101408ML-29		260 Sq Ft
	101	RESTROOM 1307	NONE DETECTED			70 Sq Ft
K3A		Miscellaneous Flooring 2' x 2' Patterned Tile & Mastic				Total Amount - 1040 Sq Ft
	30	GIRLS' POOL LOCKER ROOM 1115 & HALLWAY C108	NONE DETECTED			520 Sq Ft
	38	BOYS' POOL LOCKER ROOM 1110 & HALLWAY 1107A	NONE DETECTED	101408ML-18		520 Sq Ft
K3B		Miscellaneous Flooring Black Flooring Mastic (1973)				Total Amount - 995 Sq Ft
	43	ENTRY TO ROOMS 1112 & 1113	10 CH			35 Sq Ft
	45	ROOM 1112	10 CH	101408ML-17		350 Sq Ft
	51	ROOM 1113	10 CH			350 Sq Ft
	84	CAFETERIA 1500	10 CH			260 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3C		Miscellaneous Flooring Black Floor Tile Mastic				Total Amount - 1000 Sq Ft
	22	MAIN OFFICE AREA & RECEPTION	NONE DETECTED	101408ML-23		1000 Sq Ft
K3D		Miscellaneous Flooring 2' x 2' White w/Gray Streaks Sheet Vinyl Flooring				Total Amount - 100 Sq Ft
	46	ROOM 1112	NONE DETECTED	101408ML-19		50 Sq Ft
	52	ROOM 1113	NONE DETECTED			50 Sq Ft
K3E		Miscellaneous Flooring Tan Sandpaper Texture (Poured Floor)				Total Amount - 200 Sq Ft
	138	RESTROOM 1609A	NONE DETECTED	101408ML-33		200 Sq Ft
L0A		Flexible Duct Connector Black Vinyl				Total Amount - 100 Sq Ft
	16	THROUGHOUT BUILDING	NSM			100 Sq Ft
L0B		Flexible Duct Connector Gray Vinyl				Total Amount - 30 Sq Ft
	17	THROUGHOUT BUILDING	NSM			30 Sq Ft
M0A		Plaster Skimcoat Over Basecoat Over Sheetrock				Total Amount - 15000 Sq Ft
	5	THROUGHOUT BUILDING	NONE DETECTED	101408ML-5, 6, 7, 8, 9, 10, 11		15000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOB	Plaster Basecoat Over Sheetrock					Total Amount - 15000 Sq Ft
	6	THROUGHOUT BUILDING	NONE DETECTED	101408ML-2, 3, 35, 36, 37, 38, 39		15000 Sq Ft
N0A	Drywall/Joint Compound					Total Amount - 30000 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	101408ML-4		30000 Sq Ft
P0A	Fire Doors Metal - 1.5 Hr Rating (Underwriter's Laboratories)					Total Amount - 80 Sq Ft
	65	NORTH GYMNASIUM MECHANICAL ROOM 1201B	ASSUMED			40 Sq Ft
	68	SOUTH GYMNASIUM MECHANICAL ROOM 1202B	ASSUMED			40 Sq Ft
Q0A	Carpet Adhesive Multiple Colored Berber Carpet					Total Amount - 30000 Sq Ft
	8	THROUGHOUT BUILDING	NONE DETECTED	101408ML-17, 23; 2001-1901-XX-9B	MAIN HALLWAY.	30000 Sq Ft
R0A	Baseboard/Mopboard Adhesive Gray Baseboard					Total Amount - 1000 Sq Ft
	10	THROUGHOUT BUILDING	NONE DETECTED	2001-01107-10; 2001-1901-XX-7B	XX-7B: HALLWAY BY MUSIC.	1000 Sq Ft
R0B	Baseboard/Mopboard Adhesive Brown Baseboard					Total Amount - 1000 Sq Ft
	11	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-XX-8B	XX-8B: EARLY CHILDHOOD ROOM.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOA	Sink Undercoating Gray					Total Amount - 150 Sq Ft
	18	THROUGHOUT BUILDING	NONE DETECTED	101408ML-20		150 Sq Ft
VOB	Sink Undercoating Pink					Total Amount - 32 Sq Ft
	23	MAIN OFFICE WORK ROOM 1007	5 CH	101408ML-22		4 Sq Ft
	73	CLASSROOM 1401	5 CH			4 Sq Ft
	97	ROOM 1318	5 CH			6 Sq Ft
	105	ROOM 1317	5 CH			6 Sq Ft
	109	ROOM 1316	5 CH			4 Sq Ft
	113	ROOM 1315	5 CH			4 Sq Ft
	119	ROOM 1311	5 CH			4 Sq Ft
VOC	Sink Undercoating Black					Total Amount - 124 Sq Ft
	72	CLASSROOM 1401	10 CH			8 Sq Ft
	74	CLASSROOM 1402	10 CH			8 Sq Ft
	75	CLASSROOM 1403	10 CH			8 Sq Ft
	76	CLASSROOM 1404	10 CH			8 Sq Ft
	77	CLASSROOM 1405	10 CH			8 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	79	CLASSROOM 1407	10 CH			8 Sq Ft
	80	CLASSROOM 1408	10 CH			8 Sq Ft
	90	ROOM 1301A	10 CH	101408ML-24		4 Sq Ft
	129	CLASSROOM 1610	10 CH			8 Sq Ft
	130	CLASSROOM 1609	10 CH			8 Sq Ft
	131	CLASSROOM 1608	10 CH			8 Sq Ft
	132	CLASSROOM 1607	10 CH			8 Sq Ft
	133	CLASSROOM 1605	10 CH			8 Sq Ft
	134	CLASSROOM 1604	10 CH			8 Sq Ft
	135	CLASSROOM 1603	10 CH			8 Sq Ft
	136	CLASSROOM 1602	10 CH			8 Sq Ft
W3A	2' x 4' Ceiling Tile Adhesive Associated w/I3A					Total Amount - 625 Sq Ft
	58	GYMNASIUM 1201/1202	ASSUMED			625 Sq Ft
X0A	Miscellaneous Material Air Handler Seam Gasket					Total Amount - 100 Sq Ft
	122	PENTHOUSE AIR HANDLER ROOM 2301	5 CH	101408ML-01		100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOB	Miscellaneous Material AHU Seam Tar					Total Amount - 45 Sq Ft
	64	NORTH GYMNASIUM MECHANICAL ROOM 1201B	5 CH			10 Sq Ft
	67	SOUTH GYMNASIUM MECHANICAL ROOM 1202B	5 CH	101408ML-13		10 Sq Ft
	123	PENTHOUSE AIR HANDLER ROOM 2301	5 CH	101408ML-12		25 Sq Ft
XOC	Miscellaneous Material Wired Window Glaze					Total Amount - 57 Sq Ft
	32	ROOM 1105	5 CH			1 Sq Ft
	34	ROOM 1106	5 CH			1 Sq Ft
	36	STORAGE 1107	5 CH			2 Sq Ft
	48	ROOM 1112	5 CH			3 Sq Ft
	54	ROOM 1113	5 CH			2 Sq Ft
	61	GYMNASIUM 1201/1202	5 CH			4 Sq Ft
	71	CLASSROOM POD SOUTH OF GYMNASIUM - SOUTH ENTRY	5 CH			2 Sq Ft
	78	ROOM 1407	5 CH			1 Sq Ft
	86	HALLWAY 1300A	5 CH			2 Sq Ft
	87	ROOM 1301	5 CH			2 Sq Ft
	89	ROOM 1301A	5 CH	101408ML-27		4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	91	ROOM 1302	5 CH			2 Sq Ft
	92	ROOM 1303	5 CH			4 Sq Ft
	107	ROOM 1316	5 CH			7 Sq Ft
	124	HALLWAY 1600	5 CH			8 Sq Ft
	127	SOUTHEAST CLASSROOM POD	5 CH			10 Sq Ft
	128	LAUNDRY ROOM 1601	5 CH			2 Sq Ft
X0D	Miscellaneous Material Brass Colored Frame Chalkboard Adhesive					Total Amount - 120 Sq Ft
	94	ROOM 1321	ASSUMED			20 Sq Ft
	104	ROOM 1317	ASSUMED			20 Sq Ft
	108	ROOM 1316	ASSUMED			20 Sq Ft
	111	ROOM 1315	ASSUMED			20 Sq Ft
	118	ROOM 1311	ASSUMED			40 Sq Ft
X0E	Miscellaneous Material Black Ceiling Tile Perimeter Grid Mastic					Total Amount - 20 Sq Ft
	116	ROOM 1311	5 CH	101408ML-31		20 Sq Ft
X0F	Miscellaneous Material Interior Acoustical Block Insulation					Total Amount - 1000 Sq Ft
	62	GYMNASIUM 1201/1202	NONE DETECTED	206AGA		1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOG		Miscellaneous Material Cream Ceiling Tile Perimeter Grid Adhesive				Total Amount - 200 Sq Ft
	14	THROUGHOUT BUILDING	3 CH	101408ML-32		200 Sq Ft
XOH		Miscellaneous Material Red Fire Stop				Total Amount - 100 Sq Ft
	13	THROUGHOUT BUILDING	NONE DETECTED	101408ML-41		100 Sq Ft
XOI		Miscellaneous Material Vermiculite				Total Amount - 10000 Sq Ft
	12	THROUGHOUT BUILDING	<1 ACT	080411-BF-1-3	BF-1-3: ROOMS 1308, 1309, & 1408.	10000 Sq Ft
XOL		Miscellaneous Material Gray Ceiling Tile Perimeter Grid Caulk				Total Amount - 200 Sq Ft
	15	THROUGHOUT BUILDING	NONE DETECTED	101408ML-40		200 Sq Ft
XOM		Miscellaneous Material Chalkboard Adhesive				Total Amount - 500 Sq Ft
	19	THROUGHOUT BUILDING	NONE DETECTED	072419-BF-3	ROOM 1610	500 Sq Ft
XON		Miscellaneous Material Tackboard Adhesive				Total Amount - 400 Sq Ft
	20	THROUGHOUT BUILDING	NONE DETECTED	072419-BF-2, 4	2: ROOM 1404; 4: ROOM 1610.	400 Sq Ft
X1A		Miscellaneous Material 6" X 6" White Ceramic Wall Tile System				Total Amount - 240 Sq Ft
	26	RESTROOMS 1101 & 1102	ASSUMED			240 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1B		Miscellaneous Material 6" X 6" Quarry Tile System Gray with Red Specks				Total Amount - 108 Sq Ft
	27	RESTROOMS 1101 & 1102	ASSUMED			108 Sq Ft