

780 West Wheelock Parkway, Saint Paul, MN 55117

**Chart C - All Materials List**

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
A4A		Mudded Pipe Joints on Fiberglass Insulation 1924 Original Building				<b>Total Amount - 55 Joints</b>	
	36	ROOM 1306C	NONE DETECTED	ACB-450W-A6		8 Joints	
	41	CAFETERIA STORAGE ROOM 1306B	NONE DETECTED			4 Joints	
	43	CAFETERIA COOLER ROOM 1306A	NONE DETECTED			4 Joints	
	61	POOL OFFICE 1210	NONE DETECTED			1 Joints	
	64	POOL MECHANICAL ROOM 1209A	NONE DETECTED			12 Joints	
	71	CUSTODIAL CLOSET 1205	NONE DETECTED			4 Joints	
	94	ROOM 1123 EAST STORAGE 1123C	NONE DETECTED			2 Joints	
	202	1924 ORIGINAL BUILDING CRAWL SPACE 0601 OFF OF WATER MAIN ROOM 0506	NONE DETECTED	2001-0701-JC-43, 44; ACB-450W-A4		20 Joints	
A4C		Mudded Pipe Joints on Fiberglass Insulation 1974 Addition				<b>Total Amount - 528 Joints</b>	
	15	1974 ADDITION BASEMENT BOILER ROOM 0200	NONE DETECTED	ACB-450W-A7	1974 BOILER ROOM.	170 Joints	
	22	1974 ADDITION BASEMENT TUNNEL 0200A OFF BOILER ROOM 0200	NONE DETECTED			32 Joints	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	23	1974 ADDITION BASEMENT FAN ROOM 0203	NONE DETECTED			62 Joints
	26	1974 ADDITION BASEMENT STAIRWELL 0199A	NONE DETECTED			6 Joints
	27	1974 ADDITION BASEMENT UNEXCAVATED AREA 0100	NONE DETECTED	ACB-450W-A4		256 Joints
	183	2ND FLOOR STAIRWELL 2399	NONE DETECTED	2001-0701-JC-45		2 Joints
A4D	Mudded Pipe Joints on Fiberglass Insulation Hard Fiberglass (1974)					<b>Total Amount - 16 Joints</b>
	17	1974 ADDITION BASEMENT BOILER ROOM 0200	NONE DETECTED	120208-MA-06, 07, 08		16 Joints
B4D	Fiberglass Thermal Pipe Insulation Hard Fiberglass (1974)					<b>Total Amount - 90 Lin Ft</b>
	16	1974 ADDITION BASEMENT BOILER ROOM 0200	NSM			90 Lin Ft
C2C	Water Tank Insulation 1974 Addition					<b>Total Amount - 100 Sq Ft</b>
	14	1974 ADDITION BASEMENT BOILER ROOM 0200	NONE DETECTED	206L-7A, 509H3, 509H4		100 Sq Ft
D1C	Boiler Gaskets Burner Gasket (Rope)					<b>Total Amount - 2 Sq Ft</b>
	8	1974 ADDITION BASEMENT BOILER ROOM 0200	85 CH	120208-MA-02		2 Sq Ft
D1E	Boiler Gaskets Fiberglass					<b>Total Amount - 2 Sq Ft</b>
	9	1974 ADDITION BASEMENT BOILER ROOM 0200	NSM			2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2C		Interior Boiler Insulation 1974 Addition			<b>Total Amount - 200 Sq Ft</b>	
	10	1974 ADDITION BASEMENT BOILER ROOM 0200	ASSUMED			200 Sq Ft
EOC		Stack Insulation 1974 Addition Breaching			<b>Total Amount - 140 Sq Ft</b>	
	11	1974 ADDITION BASEMENT BOILER ROOM 0200	NONE DETECTED	120208-MA-01; 100K1A, 100K1B, 100K1C; 509H1, H2; 2001-1501-AD-16, 18, 19	MA-01: OFF ROUND SECTION.	140 Sq Ft
G1A		Sprayed-On Acoustical Finish 1974 Installation			<b>Total Amount - 160 Sq Ft</b>	
	5	THROUGHOUT 1974 ADDITION	>1 CH	ACB-450W-A5; 2001- 01112-5		160 Sq Ft
G1B		Sprayed-On Acoustical Finish Coarse White Texture			<b>Total Amount - 100000 Sq Ft</b>	
	4	THROUGHOUT 1974 ADDITION	NONE DETECTED	120308-MA-13, 16, 18, 19, 34, 35, 36	MA-13: ROOM 2201. MA-16: ROOM 2101. MA-18: ROOM 2204. MA-19: ROOM 2303. MA- 34: HALLWAY OUTSIDE CAFETERIA. MA-35: ROOM 1311. MA-36: ROOM 1114.	100000 Sq Ft
I1A		1' x 1' Acoustical Ceiling Tile 3-Ply Rough Texture (Tacked)			<b>Total Amount - 2230 Sq Ft</b>	
	37	ROOM 1306C	NONE DETECTED	ACB-450W-A2	DISHWASHER ROOM.	80 Sq Ft
	39	CAFETERIA 1306	NONE DETECTED			700 Sq Ft
	62	POOL 1209	NONE DETECTED			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	103	SMALL GYMNASIUM 1122	NONE DETECTED			450 Sq Ft
<b>I1B</b>	<b>1' x 1' Acoustical Ceiling Tile Bumps w/Holes</b>					<b>Total Amount - 600 Sq Ft</b>
	188	ROOM 2506	NONE DETECTED	206L-6A		600 Sq Ft
<b>I2A</b>	<b>2' x 2' Acoustical Ceiling Tile Rough Texture w/Revealed Edge</b>					<b>Total Amount - 3360 Sq Ft</b>
	219	ROOMS 2609-2611 & 2509-2511	NONE DETECTED	ACB-450W-A3		3360 Sq Ft
<b>I3A</b>	<b>2' x 4' Ceiling Tile 8-Square Pattern w/Revealed Edge</b>					<b>Total Amount - 4120 Sq Ft</b>
	193	ROOM 2505	NONE DETECTED	206L-5A		850 Sq Ft
	196	ROOM 2504	NONE DETECTED			850 Sq Ft
	210	ROOM 2604	NONE DETECTED			720 Sq Ft
	216	ROOM 2605	NONE DETECTED			850 Sq Ft
	222	ROOM 2606	NONE DETECTED			850 Sq Ft
<b>I3B</b>	<b>2' x 4' Ceiling Tile Bumpy Texture Pattern</b>					<b>Total Amount - 1570 Sq Ft</b>
	190	ROOM 2506	NONE DETECTED			720 Sq Ft
	206	ROOM 2614	NONE DETECTED	2001-1501-AO-12	AO-12: ROOM 2320.	850 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3C	2' x 4' Ceiling Tile Smooth Paper w/Gray Dots		<b>Total Amount - 180 Sq Ft</b>			
223	RESTROOM 2606A	NONE DETECTED	2001-1501-AO-16	AO-16: EAST SIDE OF ROOM.	180 Sq Ft	
I3D	2' x 4' Ceiling Tile Fiberglass w/Ridged Pattern		<b>Total Amount - 1000 Sq Ft</b>			
214	1924 ORIGINAL BUILDING BOYS' & GIRLS' RESTROOMS 2513 & 2613	NONE DETECTED			500 Sq Ft	
224	HALLWAY 2500A BETWEEN 1924 ORIGINAL BUILDING & 1925 ADDITION	NONE DETECTED	2001-1501-AO-19	AO-19: SOUTHWEST END OF HALLWAY.	500 Sq Ft	
K0D	9" x 9" Vinyl Floor Tile & Mastic Tan w/Brown & Beige Streaks		<b>Total Amount - 450 Sq Ft</b>			
209	ROOM 2604	12 CH (MASTIC)	120308-MA-22		450 Sq Ft	
K1A	Sheet Vinyl Flooring & Adhesive Beige w/Subtle Tan Streaks		<b>Total Amount - 3761 Sq Ft</b>			
48	ROOM 1315	NONE DETECTED			175 Sq Ft	
55	ROOM 1313	NONE DETECTED			600 Sq Ft	
86	ROOM 1321	NONE DETECTED	2001-1501-AO-16	AO-16: SPECIAL DINING ROOM.	700 Sq Ft	
92	ROOM 1123	NONE DETECTED			20 Sq Ft	
124	ROOM 1111	NONE DETECTED			300 Sq Ft	
126	ROOM 1107	NONE DETECTED			300 Sq Ft	
129	ROOMS 1126-1127	NONE DETECTED			750 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	141	NURSE ROOMS 1132, 1133 & 1136	NONE DETECTED	313-TAN-A, B, C		900 Sq Ft
	145	ROOM 1318A	NONE DETECTED			16 Sq Ft
K1B	Sheet Vinyl Flooring & Adhesive Light Brown w/Multi-Colored Confetti					<b>Total Amount - 40 Sq Ft</b>
	123	ROOM 1112/1113 RESTROOM 1112A	NONE DETECTED	120308-MA-12		40 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan Flecks					<b>Total Amount - 6029 Sq Ft</b>
	30	STAIRWELL 1399A (DOWN) EAST OF FACULTY LOUNGE 1302	4 CH (TILE), 5 CH (MASTIC)			16 Sq Ft
	33	HALLWAY EAST OF FACULTY LOUNGE 1302	4 CH (TILE), 5 CH (MASTIC)			450 Sq Ft
	38	CAFETERIA 1306	4 CH (TILE), 5 CH (MASTIC)			1500 Sq Ft
	40	CAFETERIA STORAGE ROOM 1306B	4 CH (TILE), 5 CH (MASTIC)			200 Sq Ft
	42	CAFETERIA COOLER ROOM 1306A	4 CH (TILE), 5 CH (MASTIC)			200 Sq Ft
	45	MAINTENANCE OFFICE 1301	4 CH (TILE), 5 CH (MASTIC)			550 Sq Ft
	58	CLOSETS 1214 & 1215 OFF HALLWAY OUTSIDE POOL OFFICE	4 CH (TILE), 5 CH (MASTIC)	120308-MA-08		80 Sq Ft
	59	HALLWAY 1210A OUTSIDE POOL OFFICE	4 CH (TILE), 5 CH (MASTIC)			100 Sq Ft
	60	POOL OFFICE 1210	4 CH (TILE), 5 CH (MASTIC)			170 Sq Ft
	70	CUSTODIAL CLOSET 1205	4 CH (TILE), 5 CH (MASTIC)	310-WBSP-B	NO MASTIC PRESENT IN SAMPLE.	40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	73	STAIRWELL 1299A (DOWN) BY ROOM 1205	4 CH (TILE), 5 CH (MASTIC)			16 Sq Ft
	77	STAIRWELL 1299A (UP) BY ROOM 1206	4 CH (TILE), 5 CH (MASTIC)			45 Sq Ft
	91	CUSTODIAL CLOSET 1142	4 CH (TILE), 5 CH (MASTIC)			15 Sq Ft
	93	ROOM 1123 EAST STORAGE 1123C	4 CH (TILE), 5 CH (MASTIC)			75 Sq Ft
	95	ROOM 1123 NORTH STORAGE 1123A	4 CH (TILE), 5 CH (MASTIC)			85 Sq Ft
	99	STAIRWELL 1201C (UP) BY ROOM 1201	4 CH (TILE), 5 CH (MASTIC)			250 Sq Ft
	104	SMALL GYMNASIUM 1122 STORAGE 1122A	4 CH (TILE), 5 CH (MASTIC)			60 Sq Ft
	131	ROOM 1103	4 CH (TILE), 5 CH (MASTIC)			200 Sq Ft
	136	SCIENCE ROOM STORAGE 1102B	4 CH (TILE), 5 CH (MASTIC)			80 Sq Ft
	137	SCIENCE ROOM STORAGE 1102A	4 CH (TILE), 5 CH (MASTIC)			42 Sq Ft
	139	STAIRWELL BY PLANETARIUM	4 CH (TILE), 5 CH (MASTIC)			65 Sq Ft
	143	ROOM 1006 (CONFERENCE ROOM)	4 CH (TILE), 5 CH (MASTIC)			400 Sq Ft
	146	CUSTODIAL CLOSET 1006A	4 CH (TILE), 5 CH (MASTIC)			20 Sq Ft
	148	ELEVATOR BY ROOM 1318	4 CH (TILE), 5 CH (MASTIC)			40 Sq Ft
	149	STORAGE ROOM 1140	4 CH (TILE), 5 CH (MASTIC)			45 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	160	STORAGE ROOM 2000B	4 CH (TILE), 5 CH (MASTIC)			30 Sq Ft
	174	2ND FLOOR CUSTODIAL CLOSET 2212	4 CH (TILE), 5 CH (MASTIC)			80 Sq Ft
	175	2ND FLOOR STORAGE 2206A	4 CH (TILE), 5 CH (MASTIC)			25 Sq Ft
	177	2ND FLOOR STAIRWELL 2299B	4 CH (TILE), 5 CH (MASTIC)			30 Sq Ft
	182	2ND FLOOR STAIRWELL 2399	4 CH (TILE), 5 CH (MASTIC)			120 Sq Ft
	204	ROOM 2601	4 CH (TILE), 5 CH (MASTIC)	2001-1901-CPE-1C	1C: BOYS' RESTROOM (SINCE REMOVED).	75 Sq Ft
	205	ROOM 2602	4 CH (TILE), 5 CH (MASTIC)			75 Sq Ft
	207	ROOM 2614	4 CH (TILE), 5 CH (MASTIC)			850 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Brown w/Small Squares Pattern					<b>Total Amount - 1876 Sq Ft</b>
	34	FACULTY LOUNGE 1302	NONE DETECTED			50 Sq Ft
	44	HALLWAY 1300A OUTSIDE CUSTODIAL OFFICE 1301	NONE DETECTED			325 Sq Ft
	75	STAIRWELL 1299A (UP) BY ROOM 1206	NONE DETECTED			16 Sq Ft
	78	ENTRANCE HALLWAY 1200A	NONE DETECTED			225 Sq Ft
	114	HALLWAY 1100C OUTSIDE ROOM 1118	NONE DETECTED	310-WGS-A, B, C		80 Sq Ft
	120	HALLWAY 1100B OUTSIDE ROOM 1113	NONE DETECTED			80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	130	HALLWAY AREAS 1100 & 1104 OUTSIDE PLANETARIUM	NONE DETECTED			1000 Sq Ft
	231	1925 ADDITION HALLWAY 2400 BY SOUTH EXIT	NONE DETECTED			100 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan Streaks & Dark Pits					<b>Total Amount - 2715 Sq Ft</b>
	46	ROOM 1307	6 CH (TILE), 10 CH (MASTIC)	2001-1501-AO-15	AO-15: ROOM 1307.	130 Sq Ft
	50	ROOM 1308	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	52	ROOM 1309	6 CH (TILE), 10 CH (MASTIC)			200 Sq Ft
	57	ROOM 1310	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	83	ROOM 1204	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	88	ROOM 1203	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	89	ROOM 1202	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	96	ROOM 1201	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	105	ROOM 1121	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	107	ROOM 1120	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	109	ROOM 1119	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	111	ROOM 1116/1117 COMMON AREA	6 CH (TILE), 10 CH (MASTIC)			240 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	115	ROOM 1118	6 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
	117	ROOM 1114/1115 COMMON AREA	6 CH (TILE), 10 CH (MASTIC)			240 Sq Ft
	151	ROOM 2108	6 CH (TILE), 10 CH (MASTIC)			15 Sq Ft
	153	ROOM 2202	6 CH (TILE), 10 CH (MASTIC)			15 Sq Ft
	157	ROOM 2104	6 CH (TILE), 10 CH (MASTIC)			15 Sq Ft
	158	MEDIA CENTER STORAGE 2319 BY OFFICE	6 CH (TILE), 10 CH (MASTIC)	120308-MA-17		300 Sq Ft
	164	ROOM 2004	6 CH (TILE), 10 CH (MASTIC)			15 Sq Ft
	169	ROOM 2308	6 CH (TILE), 10 CH (MASTIC)			15 Sq Ft
	171	ROOM 2309	6 CH (TILE), 10 CH (MASTIC)			15 Sq Ft
	178	ROOM 2210	6 CH (TILE), 10 CH (MASTIC)			15 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic White w/Blue Flecks					<b>Total Amount - 494 Sq Ft</b>
	69	1ST FLOOR HALLWAY 1200 BY ROOM 1205	NONE DETECTED			6 Sq Ft
	147	HALLWAY 1000 BY ROOM 1006A	NONE DETECTED			7 Sq Ft
	161	ROOM 2101	NONE DETECTED	120308-MA-15; 310-WGRN-B		15 Sq Ft
	168	ROOM 2302	NONE DETECTED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	173	2ND FLOOR HALLWAY BY ROOM 2212	NONE DETECTED			6 Sq Ft
	208	ROOM 2604	NONE DETECTED	310-WGRN-A, C		450 Sq Ft
K2E		12" x 12" Vinyl Floor Tile & Mastic White w/Gray Flecks				<b>Total Amount - 400 Sq Ft</b>
	121	ROOM 1112/1113	NONE DETECTED	120308-MA-11; 310-WGST-A		400 Sq Ft
K2F		12" x 12" Vinyl Floor Tile & Mastic Beige w/Thin Brown Streaks				<b>Total Amount - 240 Sq Ft</b>
	81	GYMNASIUM STORAGE 1207A	8 CH (TILE), 12 CH (MASTIC)	120308-MA-10	GYMNASIUM STORAGE 1207A.	120 Sq Ft
	82	GYMNASIUM STORAGE 1207B	8 CH (TILE), 12 CH (MASTIC)			120 Sq Ft
K2H		12" x 12" Vinyl Floor Tile & Mastic Beige w/Dark Specks				<b>Total Amount - 38 Sq Ft</b>
	187	1924 ORIGINAL BUILDING HALLWAY 2600 OUTSIDE ROOM 2607	NONE DETECTED			10 Sq Ft
	198	ROOM 2504	NONE DETECTED	120308-MA-30		28 Sq Ft
K3A		Miscellaneous Flooring Brown Stair Tread Adhesive				<b>Total Amount - 225 Sq Ft</b>
	76	STAIRWELL 1299A (UP) BY ROOM 1206	NONE DETECTED	120308-MA-37	MA-37: STAIRWELL 1399A (UP) EAST OF FACULTY LOUNGE 1302 (SINCE REMOVED).	75 Sq Ft
	100	STAIRWELL 1201C (UP) BY ROOM 1201	NONE DETECTED			75 Sq Ft
	140	STAIRWELL BY PLANETARIUM	NONE DETECTED			75 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3B Miscellaneous Flooring Rubber Floor (2012)						<b>Total Amount - 5000 Sq Ft</b>
	79	GYMNASIUM 1207	NEW			5000 Sq Ft
LOA Flexible Duct Connector Beige Fabric						<b>Total Amount - 10 Sq Ft</b>
	203	1924 ORIGINAL BUILDING FAN ROOMS 0502 & 0505 OFF BOILER ROOM (UNITS 10 & 11)	NONE DETECTED	2001-1501-AO-4	AO-4: FAN ROOM.	10 Sq Ft
LOB Flexible Duct Connector Black Vinyl						<b>Total Amount - 400 Sq Ft</b>
	18	1974 ADDITION BASEMENT BOILER ROOM 0200	NONE DETECTED	2001-1501-AO-13	AO-13: BOILER ROOM.	100 Sq Ft
	25	1974 ADDITION BASEMENT FAN ROOM 0203	NONE DETECTED			200 Sq Ft
	28	1974 ADDITION BASEMENT UNEXCAVATED AREA 0100	NONE DETECTED			100 Sq Ft
MOA Plaster 1924 Original Building						<b>Total Amount - 30000 Sq Ft</b>
	184	THROUGHOUT 1924 ORIGINAL BUILDING	NONE DETECTED	120308-MA-20, 31, 32, 33; 509-H11, ; 2001-1501-AO-11, AO-17	MA-20: ATTIC STAIRWELL WALL. MA-31: ROOM 2505 CEILING. MA-32: HALLWAY OUTSIDE ROOM 2505. MA-33: ROOM 2506. H11: ROOM 2506; AO-11: ROOM 2505. AO-17: BOILER ROOM STACK.	30000 Sq Ft
MOB Plaster 1925 Addition						<b>Total Amount - 7000 Sq Ft</b>
	225	THROUGHOUT 1925 ADDITION	NONE DETECTED	120308-MA-23, 24, 25, 26, 27, 28, 29	MA-23 & 24: ROOM 2001. MA-25 & 26: ROOM 2404. MA-27 & 28: ROOM 2402. MA-29: ROOM 2403.	7000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOC	Plaster Comcast Dome Plaster					<b>Total Amount - 150 Sq Ft</b>
	135	ROOM 1102	NONE DETECTED	040215BF-3		150 Sq Ft
NOA	Drywall/Joint Compound Renovation					<b>Total Amount - 6000 Sq Ft</b>
	185	THROUGHOUT 1924 ORIGINAL BUILDING	NONE DETECTED	509-H12	OUTSIDE OLD ROOM 320.	6000 Sq Ft
NOC	Drywall/Joint Compound 1974 Addition					<b>Total Amount - 70000 Sq Ft</b>
	6	THROUGHOUT 1974 ADDITION	NONE DETECTED	2001-1501-AO-14	AO-14: ROOM 2210.	70000 Sq Ft
POA	Fire Doors Wood Composite - 1.5 Hr Rating (Weyerhaeuser)					<b>Total Amount - 180 Sq Ft</b>
	31	STAIRWELL 1399A (DOWN) EAST OF FACULTY LOUNGE 1302	ASSUMED			20 Sq Ft
	72	STAIRWELL 1299A (DOWN) BY ROOM 1205	ASSUMED			20 Sq Ft
	74	STAIRWELL 1299A (UP) BY ROOM 1206	ASSUMED			20 Sq Ft
	98	STAIRWELL 1201C (UP) BY ROOM 1201	ASSUMED			20 Sq Ft
	138	STAIRWELL BY PLANETARIUM	ASSUMED			20 Sq Ft
	150	2ND FLOOR SOUTHWEST STAIRWELL 2299A	ASSUMED			20 Sq Ft
	163	2ND FLOOR STAIRWELL 2099	ASSUMED			20 Sq Ft
	176	2ND FLOOR STAIRWELL 2299B	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
	181	2ND FLOOR STAIRWELL 2399	ASSUMED			20 Sq Ft	
POB		Fire Doors Wood Composite - 1.5 Hr Rating (Warnock Hersey)					<b>Total Amount - 20 Sq Ft</b>
	32	STAIRWELL 1399A (UP) EAST OF FACULTY LOUNGE 1302	NEW			20 Sq Ft	
Q0A		Carpet Adhesive Berber Carpet (Various)					<b>Total Amount - 50000 Sq Ft</b>
	1	THROUGHOUT BUILDING	NONE DETECTED	120308-MA-22; 2001-1901-ZZ-8C; 309-GB-A, B, C	MA-22: ROOM 2604. ZZ-3C: BY ROOM 2302. GB-A: ROOM 1114, GB-B: ROOM 1113. GB-C: OCCUPATIONAL THERAPY. 309-BLUE-A,B,C: MAIN OFFICE.	50000 Sq Ft	
Q0B		Carpet Adhesive Tan with Light and Dark Brown Stripes Carpet Squares (2020)					<b>Total Amount - 600 Sq Ft</b>
	166	ROOM 2001	NEW			600 Sq Ft	
ROB		Baseboard/Mopboard Adhesive 4" Beige Baseboard					<b>Total Amount - 1000 Sq Ft</b>
	2	THROUGHOUT BUILDING	NONE DETECTED	308-BC1-A	BC1-A: 1ST FLOOR CUSTODIAL CLOSET.	1000 Sq Ft	
ROC		Baseboard/Mopboard Adhesive 4" Brown Baseboard					<b>Total Amount - 2000 Sq Ft</b>
	3	THROUGHOUT BUILDING	NONE DETECTED	308-4B-A, B, C	1ST FLOOR HALLWAYS.	2000 Sq Ft	
ROD		Baseboard/Mopboard Adhesive 6" Black 90-Degree Angle (2012)					<b>Total Amount - 40 Sq Ft</b>
	80	GYMNASIUM 1207	NEW			40 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROE	Baseboard/Mopboard Adhesive 6" Brown 90-Degree Angle		<b>Total Amount - 30 Sq Ft</b>			
	102	SMALL GYMNASIUM 1122	NEW			30 Sq Ft
SOA	Wood Floor Felt / Vapor Barrier 1924 Original Building (Elevated)		<b>Total Amount - 20000 Sq Ft</b>			
	186	THROUGHOUT 1924 ORIGINAL BUILDING 2ND FLOOR	ASSUMED			20000 Sq Ft
SOB	Wood Floor Felt / Vapor Barrier 1925 Addition		<b>Total Amount - 3000 Sq Ft</b>			
	226	1925 ADDITION CLASSROOMS	ASSUMED			3000 Sq Ft
SOC	Wood Floor Felt / Vapor Barrier 1974 Addition		<b>Total Amount - 820 Sq Ft</b>			
	101	SMALL GYMNASIUM 1122	ASSUMED			820 Sq Ft
VOA	Sink Undercoating Black		<b>Total Amount - 50 Sq Ft</b>			
	35	FACULTY LOUNGE 1302	5 CH			5 Sq Ft
	152	ROOM 2108	5 CH			5 Sq Ft
	154	ROOM 2202	5 CH			5 Sq Ft
	156	ROOM 2104	5 CH	120308-MA-14		5 Sq Ft
	162	ROOM 2101	5 CH			5 Sq Ft
	167	ROOM 2302	5 CH			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	170	ROOM 2308	5 CH			5 Sq Ft
	172	ROOM 2309	5 CH			5 Sq Ft
	179	ROOM 2210	5 CH			5 Sq Ft
	180	ROOM 2204	5 CH			5 Sq Ft
VOB	Sink Undercoating Lavender w/Gooseneck					<b>Total Amount - 96 Sq Ft</b>
	47	ROOM 1307	5 CH			4 Sq Ft
	51	ROOM 1308	5 CH			4 Sq Ft
	53	ROOM 1309	5 CH			4 Sq Ft
	56	ROOM 1310	5 CH	120308-MA-07		4 Sq Ft
	84	ROOM 1204	5 CH			4 Sq Ft
	87	ROOM 1203	5 CH			4 Sq Ft
	90	ROOM 1202	5 CH			4 Sq Ft
	97	ROOM 1201	5 CH			4 Sq Ft
	106	ROOM 1121	5 CH			4 Sq Ft
	108	ROOM 1120	5 CH			4 Sq Ft
	110	ROOM 1119	5 CH			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	112	ROOM 1116/1117 COMMON AREA	5 CH			4 Sq Ft
	116	ROOM 1118	5 CH			4 Sq Ft
	118	ROOM 1114/1115 COMMON AREA	5 CH			4 Sq Ft
	122	ROOM 1112/1113	5 CH			8 Sq Ft
	127	ROOM 1130 (SPEECH)	5 CH			4 Sq Ft
	128	ROOM 1128	5 CH			4 Sq Ft
	142	NURSE ROOMS 1134 & 1135	5 CH			8 Sq Ft
	144	ROOM 1318	5 CH			4 Sq Ft
	155	ROOM 2313	5 CH			4 Sq Ft
	159	MEDIA CENTER STORAGE 2319 BY OFFICE	5 CH			4 Sq Ft
	165	ROOM 2004	5 CH			4 Sq Ft
VOC	Sink Undercoating Pink					<b>Total Amount - 15 Sq Ft</b>
	49	ROOM 1315	5 CH			3 Sq Ft
	54	ROOM 1313	5 CH	120308-MA-06		3 Sq Ft
	113	ROOM 1116/1117 COMMON AREA	5 CH			3 Sq Ft
	119	ROOM 1114/1115 COMMON AREA	5 CH			3 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	125	ROOM 1111	5 CH			3 Sq Ft
V0D	Sink Undercoating Lavender w/Hook Faucets					<b>Total Amount - 16 Sq Ft</b>
	85	ROOM 1321	5 CH	120308-MA-09		16 Sq Ft
V0E	Sink Undercoating Gray					<b>Total Amount - 15 Sq Ft</b>
	192	ROOM 2506	NONE DETECTED	120308-MA-21		5 Sq Ft
	211	ROOM 2604	NONE DETECTED			10 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B					<b>Total Amount - 150 Sq Ft</b>
	189	ROOM 2506	ASSUMED			150 Sq Ft
X0A	Miscellaneous Material Incinerator Refractory					<b>Total Amount - 100 Sq Ft</b>
	12	1974 ADDITION BASEMENT BOILER ROOM 0200	ASSUMED			100 Sq Ft
X0B	Miscellaneous Material Incinerator Gaskets					<b>Total Amount - 1 Sq Ft</b>
	13	1974 ADDITION BASEMENT BOILER ROOM 0200	ASSUMED			1 Sq Ft
X0C	Miscellaneous Material Pipe Flange/Valve Gaskets (1974)					<b>Total Amount - 20 Sq Ft</b>
	19	1974 ADDITION BASEMENT BOILER ROOM 0200	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0D	Miscellaneous Material Black AHU Seam Gaskets					<b>Total Amount - 80 Sq Ft</b>
	20	1974 ADDITION BASEMENT BOILER ROOM 0200	5 CH			10 Sq Ft
	24	1974 ADDITION BASEMENT FAN ROOM 0203	5 CH			50 Sq Ft
	29	1974 ADDITION BASEMENT UNEXCAVATED AREA 0100	5 CH	120208-MA-12		20 Sq Ft
X0E	Miscellaneous Material Tackboard Adhesive (1974)					<b>Total Amount - 1000 Sq Ft</b>
	7	THROUGHOUT 1974 ADDITION	ASSUMED			1000 Sq Ft
X0F	Miscellaneous Material Tan Felt Paper on Ceiling					<b>Total Amount - 50 Sq Ft</b>
	21	1974 ADDITION BASEMENT BOILER ROOM 0200	NONE DETECTED	072213-BF-1		50 Sq Ft
X0H	Miscellaneous Material Comcast Dome Black Tar Layer					<b>Total Amount - 150 Sq Ft</b>
	132	ROOM 1102	NONE DETECTED	040215BF-1		150 Sq Ft
X0I	Miscellaneous Material Comcast Dome Lip at Seams					<b>Total Amount - 20 Sq Ft</b>
	133	ROOM 1102	NONE DETECTED	040215BF-2		20 Sq Ft
X0J	Miscellaneous Material Comcast Dome Tan Adhesive					<b>Total Amount - 5 Sq Ft</b>
	134	ROOM 1102	NONE DETECTED	040215BF-4		5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1A		Miscellaneous Material Pipe/Valve Flange Gaskets				<b>Total Amount - 22 Sq Ft</b>
	200	1924 ORIGINAL BUILDING BOILER ROOM 0501	65 CH	120308-MA-02		8 Sq Ft
	201	1924 ORIGINAL BUILDING WATER MAIN ROOM 0506	65 CH			14 Sq Ft
X1E		Miscellaneous Material Slate Chalkboard Adhesive (1924)				<b>Total Amount - 120 Sq Ft</b>
	191	ROOM 2506	ASSUMED			20 Sq Ft
	194	ROOM 2505	ASSUMED			20 Sq Ft
	197	ROOM 2504	ASSUMED			20 Sq Ft
	212	ROOM 2604	ASSUMED			10 Sq Ft
	217	ROOM 2605	ASSUMED			20 Sq Ft
	220	ROOM 2606	ASSUMED			30 Sq Ft
X1F		Miscellaneous Material Tackboard Adhesive (1924)				<b>Total Amount - 360 Sq Ft</b>
	195	ROOM 2505	ASSUMED			100 Sq Ft
	199	ROOM 2504	ASSUMED			40 Sq Ft
	213	ROOM 2604	ASSUMED			40 Sq Ft
	218	ROOM 2605	ASSUMED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	221	ROOM 2606	ASSUMED			80 Sq Ft
<b>X1G</b>	<b>Miscellaneous Material Slate Chalkboard Adhesive (1925)</b>					<b>Total Amount - 70 Sq Ft</b>
	227	ROOM 2401	ASSUMED			20 Sq Ft
	229	ROOM 2402	ASSUMED			10 Sq Ft
	232	ROOM 2403	ASSUMED			20 Sq Ft
	234	ROOM 2404	ASSUMED			20 Sq Ft
<b>X1H</b>	<b>Miscellaneous Material Tackboard Adhesive (1925)</b>					<b>Total Amount - 525 Sq Ft</b>
	228	ROOM 2401	ASSUMED			150 Sq Ft
	230	ROOM 2402	ASSUMED			75 Sq Ft
	233	ROOM 2403	ASSUMED			150 Sq Ft
	235	ROOM 2404	ASSUMED			150 Sq Ft
<b>X1I</b>	<b>Miscellaneous Material 2" Blue Ceramic Floor Tile System</b>					<b>Total Amount - 4000 Sq Ft</b>
	63	POOL 1209	ASSUMED			4000 Sq Ft
<b>X1J</b>	<b>Miscellaneous Material 2" Beige Ceramic Floor Tile System</b>					<b>Total Amount - 1800 Sq Ft</b>
	65	GIRLS' LOCKER ROOM 1213	NEW			900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	67	BOYS' LOCKER ROOM 1211	NEW			900 Sq Ft
X1K	Miscellaneous Material 4" Cream Ceramic Wall Tile System					<b>Total Amount - 1000 Sq Ft</b>
	66	GIRLS' LOCKER ROOM 1213	NEW			500 Sq Ft
	68	BOYS' LOCKER ROOM 1211	NEW			500 Sq Ft
X1L	Miscellaneous Material 12" Beige Marble Ceramic Floor Tile System					<b>Total Amount - 500 Sq Ft</b>
	215	BOYS' & GIRLS' RESTROOM 2513	NEW			500 Sq Ft