

65 East Kellogg Blvd., Saint Paul, MN 55101

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A		Mudded Pipe Joints on Fiberglass Insulation Foil-Wrap				Total Amount - 12 Joints
	23	CUSTODIAL LOUNGE RESTROOM 0208A	30 CH			2 Joints
	25	PIPE CHASE 1112 BETWEEN ROOMS 0208 & 0209 (TA7)	30 CH	2001-1901-RSW-1A	1A: MEN'S RESTROOM PIPE CHASE NEAR LOWER LEVEL ELEVATOR HALLWAY (SINCE REMOVED).	1 Joints
	44	STORAGE 0105	30 CH			3 Joints
	131	ELEVATOR HALLWAY 2301	30 CH			2 Joints
	183	ROOM 6110	30 CH			4 Joints
G1A		Sprayed-On Acoustical Finish White/Tan Texture				Total Amount - 6410 Sq Ft
	118	THROUGHOUT MEZZANINE	<1 CH	062812MV-01, 02, 03; 062112MV-03	MV-01: RESTROOM 2101. MV-02: WOMEN'S LOCKER ROOM 2105. MV-03: MEN'S LOCKER ROOM 2104. 062112MV-03: VIEWING AREA.	3000 Sq Ft
	129	UPPER 2ND FLOOR HALLWAY (2300)	<1 CH	062812MV-04; 062112MV-01, 02;	MV-04: HALLWAY BY ROOM 2307. MV-01: HALLWAY BY ROOM 2306. MV-02: HALLWAY 2300 SOUTH.	1500 Sq Ft
	130	ELEVATOR HALLWAY 2301	<1 CH			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	132	MEN'S RESTROOM 2302	<1 CH	062812MV-06	MV-06: MEN'S RESTROOM 2032.	120 Sq Ft
	134	WOMEN'S RESTROOM 2303	<1 CH	062812MV-05	MV-05: WOMEN'S RESTROOM 2303.	120 Sq Ft
	136	ROOM 2313	<1 CH			250 Sq Ft
	137	ROOM 2314	<1 CH			300 Sq Ft
	138	ROOM 2306	<1 CH			900 Sq Ft
	139	ROOM 2306A	<1 CH			30 Sq Ft
	144	ROOM 2307	<1 CH			150 Sq Ft
G1B	Sprayed-On Acoustical Finish White Texture					Total Amount - 20000 Sq Ft
	168	THROUGHOUT 5TH FLOOR	NONE DETECTED	112508ML-03	ML-03: ELEVATOR LOBBY.	5000 Sq Ft
	176	THROUGHOUT 6TH FLOOR	NONE DETECTED	112508ML-04, 05	ML-04: ELEVATOR LOBBY. ML-05: OUTSIDE ROOM 6112.	5000 Sq Ft
	188	THROUGHOUT 7TH FLOOR	NONE DETECTED	110308ML-36; 112508ML-06	ML-36: OUTSIDE GYMNASIUM. ML-06: ROOM 7109.	5000 Sq Ft
	197	THROUGHOUT 8TH FLOOR	NONE DETECTED	112508ML-07, 08	ML-07: ROOM 8107. ML-08: HALLWAY OUTSIDE ROOM 8112.	5000 Sq Ft
H1A	Sprayed-On Structural Fireproofing Hard Gray (199X)					Total Amount - 300 Sq Ft
	14	THROUGHOUT GROUND FLOOR	NONE DETECTED	110308ML-09		300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
H1B	Sprayed-On Structural Fireproofing Fluffy w/Green Tint		Total Amount - 5000 Sq Ft			
42	LOADING DOCK & GARAGE 0103	NONE DETECTED	110308ML-12		5000 Sq Ft	
H1D	Sprayed-On Structural Fireproofing Gray Fluffy		Total Amount - 2000 Sq Ft			
93	THROUGHOUT 1ST FLOOR	NONE DETECTED	110308ML-37	HALLWAY OUTSIDE ROOM 1207.	2000 Sq Ft	
I1A	1' x 1' Acoustical Ceiling Tile Interlocking Fissured		Total Amount - 480 Sq Ft			
32	GROUND LEVEL ELEVATOR HALLWAY (0200)	NONE DETECTED	2001-1901-RSW-2A; W17		480 Sq Ft	
I2A	2' x 2' Acoustical Ceiling Tile Light Texture (2014)		Total Amount - 7000 Sq Ft			
94	THROUGHOUT 1ST FLOOR	NEW			7000 Sq Ft	
I2E	2' x 2' Acoustical Ceiling Tile Cloth-Covered Fiberglass		Total Amount - 4050 Sq Ft			
39	GROUND LEVEL HALLWAY 100 OUTSIDE ROOM 0106 TO EAST ENTRANCE	NSM			550 Sq Ft	
95	THROUGHOUT 1ST FLOOR	NSM			1000 Sq Ft	
124	THROUGHOUT 2ND FLOOR	NSM			2500 Sq Ft	
I2F	2' x 2' Acoustical Ceiling Tile Vinyl-Covered Sheetrock		Total Amount - 200 Sq Ft			
47	OLD KITCHEN (0106)	NSM			200 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2I	2' x 2' Acoustical Ceiling Tile Textured w/Grubs, Nail & Pin Holes					Total Amount - 2200 Sq Ft
	107	ROOM 1107 & ASSOCIATED ROOMS	NONE DETECTED	110308ML-31		700 Sq Ft
	164	ROOMS 4112, 4111 & 4109	NONE DETECTED			1500 Sq Ft
I2J	2' x 2' Acoustical Ceiling Tile Grubs w/Pin Holes					Total Amount - 2000 Sq Ft
	50	THROUGHOUT GROUND LEVEL SOUTHEAST AREA ROOMS & HALLWAYS	NONE DETECTED	110308ML-14	ROOM 0114.	2000 Sq Ft
I3A	2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes					Total Amount - 600 Sq Ft
	68	ROOM 0120	NONE DETECTED	110308ML-21		400 Sq Ft
	70	ROOM 0120A	NONE DETECTED			200 Sq Ft
I3B	2' x 4' Ceiling Tile Cloth-Covered Fiberglass (2011)					Total Amount - 12000 Sq Ft
	125	THROUGHOUT 2ND FLOOR	NSM			2000 Sq Ft
	145	THROUGHOUT 3RD FLOOR CAFETERIA	NSM			5000 Sq Ft
	158	THROUGHOUT 4TH FLOOR	NSM			5000 Sq Ft
K1A	Sheet Vinyl Flooring & Adhesive Multi-Colored w/Specks (2014)					Total Amount - 11000 Sq Ft
	100	1ST FLOOR COMMONS & HALLWAYS	NEW			4000 Sq Ft
	119	THROUGHOUT MEZZANINE	NEW			2000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	146	THROUGHOUT 3RD FLOOR CAFETERIA	NEW			5000 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Blue Mottle (2014)					Total Amount - 1282 Sq Ft
	35	STAIRWELL 0199A	NEW			75 Sq Ft
	108	ROOM 1107 & ASSOCIATED ROOMS	NEW			700 Sq Ft
	110	HALLWAY OUTSIDE OFFICE 1109	NEW			110 Sq Ft
	182	ROOM 6109	NEW			24 Sq Ft
	184	ROOM 6110	NEW			24 Sq Ft
	187	ROOM 6112	NEW			24 Sq Ft
	193	ROOMS 7112, 7110, 7109, 7106 & 7107	NEW			125 Sq Ft
	202	ROOMS 8106, 8109 8110 & 8112	NEW			200 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Gray & Blue w/Blue & White Flecks					Total Amount - 5600 Sq Ft
	41	STAIRWELL 0199C	NONE DETECTED	110308ML-11	ML-11: GROUND LEVEL HALLWAY 100 (SINCE REMOVED).	150 Sq Ft
	111	COMMUNICATIONS ROOM (1110)	NONE DETECTED			160 Sq Ft
	143	GYMNASIUM STORAGE (2309A)	NONE DETECTED			100 Sq Ft
	157	COMMUNICATIONS ROOM (3104)	NONE DETECTED			130 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	166	STORAGE ROOM 4104	NONE DETECTED			20 Sq Ft
	167	STORAGE 4111A	NONE DETECTED			20 Sq Ft
	174	CUSTODIAL CLOSET (5003)	NONE DETECTED			20 Sq Ft
	211	THROUGHOUT STAIRWELL C	NONE DETECTED			5000 Sq Ft
K2J	12" x 12" Vinyl Floor Tile & Mastic Cream w/Gray Smudges					Total Amount - 605 Sq Ft
	65	STAIRWELL 0199F	NONE DETECTED			120 Sq Ft
	66	HALLWAY 0100 OUTSIDE ROOM 0120 TO ROOM 0107	NONE DETECTED	110308ML-17		250 Sq Ft
	87	GIRLS' RESTROOM NEAR COMMUNICATIONS ROOM 0110	NONE DETECTED			25 Sq Ft
	89	COMMUNICATIONS ROOM 0110	NONE DETECTED			10 Sq Ft
	203	ROOM 8108	NONE DETECTED			200 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Pink Mottle					Total Amount - 155 Sq Ft
	64	STAIRWELL 0199F	NONE DETECTED			120 Sq Ft
	88	GIRLS' RESTROOM NEAR COMMUNICATIONS ROOM 0110	NONE DETECTED			25 Sq Ft
	90	COMMUNICATIONS ROOM 0110	NONE DETECTED	110308ML-18	ML-18: STORAGE ROOM 0116 (SINCE REMOVED).	10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2R	12" x 12" Vinyl Floor Tile & Mastic Multi-Colored Mottle (2011)					Total Amount - 10700 Sq Ft
	127	2ND FLOOR LOWER LEVEL HALLWAY (2200)	NEW			4000 Sq Ft
	128	THROUGHOUT 2ND FLOOR UPPER LEVEL	NEW			1000 Sq Ft
	156	3RD FLOOR ELEVATOR HALLWAY (3100A)	NEW			200 Sq Ft
	159	THROUGHOUT 4TH FLOOR	NEW			500 Sq Ft
	170	THROUGHOUT 5TH FLOOR	NEW			500 Sq Ft
	178	THROUGHOUT 6TH FLOOR	NEW			1500 Sq Ft
	190	THROUGHOUT 7TH FLOOR	NEW			1500 Sq Ft
	199	THROUGHOUT 8TH FLOOR	NEW			1500 Sq Ft
K2S	12" x 12" Vinyl Floor Tile & Mastic Blue Mottle (2011)					Total Amount - 700 Sq Ft
	98	THROUGHOUT 1ST FLOOR	NEW			700 Sq Ft
K2T	12" x 12" Vinyl Floor Tile & Mastic Cream w/Gray Smudges (2015)					Total Amount - 1530 Sq Ft
	34	GROUND LEVEL ELEVATOR HALLWAY (200)	NEW			480 Sq Ft
	40	GROUND LEVEL HALLWAY 100 OUTSIDE ROOM 0106 TO EAST ENTRANCE	NEW			800 Sq Ft
	67	HALLWAY 0100 OUTSIDE ROOM 0120 TO ROOM 0107	NEW			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3A	Miscellaneous Flooring Black Floor Mastic					Total Amount - 2855 Sq Ft
	57	ROOM 0118	NONE DETECTED	110308ML-19		250 Sq Ft
	60	ROOM 0116	NONE DETECTED			320 Sq Ft
	72	ROOMS 0120 & 0120A	NONE DETECTED			600 Sq Ft
	75	ROOM 0114	NONE DETECTED			390 Sq Ft
	78	ROOM 0113	NONE DETECTED			390 Sq Ft
	80	ROOM 0112	NONE DETECTED			350 Sq Ft
	82	ROOM 0107	NONE DETECTED			290 Sq Ft
	84	ROOM 0107A	NONE DETECTED	110308ML-28	ML-28: NEAR ROOM 1110 (SINCE REMOVED).	160 Sq Ft
	173	COMMUNICATIONS ROOM (5108)	NONE DETECTED			85 Sq Ft
	175	CUSTODIAL CLOSET (5003)	NONE DETECTED			20 Sq Ft
K3C	Miscellaneous Flooring 3' x 3' White w/Green, Gray & Blue					Total Amount - 50 Sq Ft
	213	ELEVATORS	NONE DETECTED	110308ML-46		50 Sq Ft
K3D	Miscellaneous Flooring Multi-Colored Epoxy (2011)					Total Amount - 3000 Sq Ft
	99	THROUGHOUT 1ST FLOOR	NSM			3000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
LOA Flexible Duct Connector Black Vinyl						Total Amount - 300 Sq Ft
	13	THROUGHOUT BUILDING	NSM			300 Sq Ft
MOA Plaster 1890 Original Building						Total Amount - 14000 Sq Ft
	1	THROUGHOUT BUILDING	<1 CH	511Q-7P; W59/60; ACB450DA-A37-43		14000 Sq Ft
MOB Plaster Columns						Total Amount - 2500 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	110308ML-49; ACB450DA-A-55	ML-49: ROOM 0105.	2500 Sq Ft
NOA Drywall/Joint Compound						Total Amount - 20000 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	110308ML-50, 51; 2001-1501-R52	50: HALLWAY OUTSIDE ROOM 0112. R2: ROOM 8105.	20000 Sq Ft
POA Fire Doors Metal - 3 Hr Rating (Mesker)						Total Amount - 320 Sq Ft
	20	MECHANICAL ROOM 0203	ASSUMED			80 Sq Ft
	21	STAIRWELL 0199B	ASSUMED			20 Sq Ft
	36	STAIRWELL 0199A	ASSUMED			20 Sq Ft
	207	THROUGHOUT STAIRWELL A	ASSUMED			160 Sq Ft
	210	THROUGHOUT STAIRWELL B	ASSUMED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
POB	Fire Doors Wood Composite - 1 Hr Rating (Roddis)					Total Amount - 60 Sq Ft
	29	ELECTRICAL/FIRE PUMP ROOM 0210A	ASSUMED			60 Sq Ft
POC	Fire Doors Metal - 1.5 Hr Rating (Underwriter's Laboratories)					Total Amount - 180 Sq Ft
	33	GROUND LEVEL ELEVATOR HALLWAY (0200)	ASSUMED			80 Sq Ft
	212	THROUGHOUT STAIRWELL D	ASSUMED			100 Sq Ft
POD	Fire Doors Metal - 3 Hr Rating (Underwriter's Laboratories)					Total Amount - 40 Sq Ft
	37	ELEVATOR EQUIPMENT ROOM (0202)	ASSUMED			20 Sq Ft
	38	ELECTRICAL ROOM (0201)	ASSUMED			20 Sq Ft
POE	Fire Doors Metal - 3/4 Hr Rating (Underwriter's Laboratories)					Total Amount - 40 Sq Ft
	208	THROUGHOUT STAIRWELL A	ASSUMED			40 Sq Ft
POF	Fire Doors Wood - 1 Hr Rating (Warnock Hersey)					Total Amount - 60 Sq Ft
	181	ROOM 6105	NEW			20 Sq Ft
	196	ROOM 7105	NEW			20 Sq Ft
	206	ROOM 8105	NEW			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0A	Carpet Adhesive Green & Tan Carpet					Total Amount - 1600 Sq Ft
	51	THROUGHOUT GROUND LEVEL SOUTHEAST AREA ROOMS & HALLWAYS	NONE DETECTED	110308ML-19	ROOM 0118.	1600 Sq Ft
Q0E	Carpet Adhesive Dark Blue Carpet					Total Amount - 200 Sq Ft
	91	ROOMS 0108 & 0109	NONE DETECTED	110308ML-27	ROOM 0108.	200 Sq Ft
Q0G	Carpet Adhesive Tan w/Multi-Colored Carpet					Total Amount - 3000 Sq Ft
	97	THROUGHOUT 1ST FLOOR	NONE DETECTED	110308ML-32		3000 Sq Ft
Q0I	Carpet Adhesive Black Squares Carpet (2011)					Total Amount - 15000 Sq Ft
	169	THROUGHOUT 5TH FLOOR	NEW			4500 Sq Ft
	177	THROUGHOUT 6TH FLOOR	NEW			3500 Sq Ft
	189	THROUGHOUT 7TH FLOOR	NEW			3500 Sq Ft
	198	THROUGHOUT 8TH FLOOR	NEW			3500 Sq Ft
Q0J	Carpet Adhesive Blue Carpet Squares (2015)					Total Amount - 13180 Sq Ft
	52	ROOM 0119	NEW			70 Sq Ft
	54	ROOM 0117	NEW			180 Sq Ft
	56	ROOM 0118	NEW			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	59	ROOM 0116	NEW			90 Sq Ft
	74	ROOM 0114	NEW			320 Sq Ft
	77	ROOM 0113	NEW			170 Sq Ft
	79	ROOM 0112	NEW			220 Sq Ft
	81	ROOM 0107	NEW			220 Sq Ft
	83	ROOM 0107A	NEW			160 Sq Ft
	96	THROUGHOUT 1ST FLOOR	NEW			5000 Sq Ft
	105	CONFERENCE OFFICE (1104)	NEW			500 Sq Ft
	120	THROUGHOUT MEZZANINE	NEW			500 Sq Ft
	126	THROUGHOUT 2ND FLOOR	NEW			4000 Sq Ft
	165	ROOMS 4108A, 4109 & 4111	NEW			1500 Sq Ft
ROA	Baseboard/Mopboard Adhesive Mauve Baseboard					Total Amount - 200 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	110308ML-47	HALLWAY 100.	200 Sq Ft
ROB	Baseboard/Mopboard Adhesive Blue Baseboard					Total Amount - 200 Sq Ft
	5	THROUGHOUT BUILDING	NONE DETECTED	110308ML-48	STAIRWELL 0199C.	200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROC		Baseboard/Mopboard Adhesive Brown Baseboard				Total Amount - 10 Sq Ft
	27	ROOM 0209	NONE DETECTED	110308ML-10		10 Sq Ft
R0D		Baseboard/Mopboard Adhesive 4" Tan Baseboard				Total Amount - 200 Sq Ft
	6	THROUGHOUT BUILDING	NONE DETECTED	110308ML-40		200 Sq Ft
R0E		Baseboard/Mopboard Adhesive 4" Red Baseboard				Total Amount - 15 Sq Ft
	73	ROOMS 0120 & 0120A	NONE DETECTED	110308ML-23		15 Sq Ft
R0F		Baseboard/Mopboard Adhesive Dark Blue Baseboard				Total Amount - 20 Sq Ft
	92	ROOMS 0108 & 0109	NONE DETECTED	110308ML-15	ROOM 0109.	20 Sq Ft
R0H		Baseboard/Mopboard Adhesive Dark Brown (2011)				Total Amount - 500 Sq Ft
	7	THROUGHOUT BUILDING	NEW			500 Sq Ft
R0I		Baseboard/Mopboard Adhesive 90 Degree Black Angled Baseboard				Total Amount - 35 Sq Ft
	141	GYMNASIUM (2309)	ASSUMED			35 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier 1890 Original Building				Total Amount - 5060 Sq Ft
	109	ROOM 1107	ASSUMED			560 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	140	GYMNASIUM (2309)	ASSUMED			4500 Sq Ft
UOA	Light Pad Insulation Light Blanket (Round Lights)					Total Amount - 8 Sq Ft
	22	CUSTODIAL LOUNGE RESTROOM 0208A	50 CH			1 Sq Ft
	26	ROOM 0209	50 CH	110308ML-05		5 Sq Ft
	209	THROUGHOUT STAIRWELL B	50 CH			2 Sq Ft
VOA	Sink Undercoating Gray					Total Amount - 100 Sq Ft
	8	THROUGHOUT BUILDING	NONE DETECTED	110308ML-20	ML-20: ROOM 0116.	100 Sq Ft
XOA	Miscellaneous Material Tar/Cork Acoustical Ceiling Coating					Total Amount - 7460 Sq Ft
	30	LOWER LEVEL WATER METER AREA (0210A)	NONE DETECTED			60 Sq Ft
	48	OLD KITCHEN (0106)	NONE DETECTED			200 Sq Ft
	53	ROOM 0119	NONE DETECTED			290 Sq Ft
	55	ROOM 0117	NONE DETECTED			180 Sq Ft
	58	ROOM 0118	NONE DETECTED			500 Sq Ft
	61	ROOM 0116	NONE DETECTED			410 Sq Ft
	86	HALLWAY 100 OUTSIDE ROOMS 0108 & 0109	NONE DETECTED			60 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	101	OFFICE RECEPTION (1102)	NONE DETECTED			60 Sq Ft
	102	NURSE'S ROOM 1102B	NONE DETECTED			320 Sq Ft
	106	CONFERENCE OFFICE (1104)	NONE DETECTED			380 Sq Ft
	147	THROUGHOUT 3RD FLOOR CAFETERIA	NONE DETECTED	2001-0157-1		5000 Sq Ft
X0C	Miscellaneous Material Tan Penetration Putty					Total Amount - 5 Sq Ft
	18	MECHANICAL ROOM 0203	NONE DETECTED	110308ML-03	ABOVE SOUTHWEST ENTRY.	5 Sq Ft
X0D	Miscellaneous Material Red Fire Stop					Total Amount - 400 Sq Ft
	9	THROUGHOUT BUILDING	NONE DETECTED	110308ML-06	ROOM 0201.	400 Sq Ft
X0E	Miscellaneous Material Black Ductwork Insulation Adhesive					Total Amount - 50 Sq Ft
	15	THROUGHOUT GROUND FLOOR	NONE DETECTED	110308ML-07	SOUTH OF AHU 4.	50 Sq Ft
X0F	Miscellaneous Material Black Pipe Sleeve Mastic					Total Amount - 3 Sq Ft
	19	MECHANICAL ROOM 0203	NONE DETECTED	110308ML-08		3 Sq Ft
X0G	Miscellaneous Material Black AHU Seam Gasket					Total Amount - 20 Sq Ft
	16	MECHANICAL ROOM 0203	NONE DETECTED	110308ML-01	AHU 4.	15 Sq Ft
	123	MECHANICAL ROOM M11	NONE DETECTED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOH		Miscellaneous Material Black Tar AHU Seam Gasket				Total Amount - 5 Sq Ft
	17	MECHANICAL ROOM 0203	10 CH	110308ML-02	AHU 1.	5 Sq Ft
XOI		Miscellaneous Material Wired Window Silicone Glaze				Total Amount - 1 Sq Ft
	43	LOADING DOCK & GARAGE 0103	NSM			1 Sq Ft
XOJ		Miscellaneous Material Old Cooler Insulation				Total Amount - 300 Sq Ft
	45	STORAGE 0105	ASSUMED			300 Sq Ft
XOK		Miscellaneous Material Gray Duct Caulk				Total Amount - 300 Sq Ft
	10	THROUGHOUT BUILDING	NONE DETECTED	110308ML-16		300 Sq Ft
XOL		Miscellaneous Material Tan Old Ceiling Tile Grid Mastic				Total Amount - 9 Sq Ft
	69	ROOM 0120	5 CH	110308ML-22		3 Sq Ft
	71	ROOM 0120A	5 CH			2 Sq Ft
	76	ROOM 0114	5 CH			3 Sq Ft
	85	HALLWAY 100 OUTSIDE ROOM 0107	5 CH			1 Sq Ft
XOM		Miscellaneous Material Wired Window Glaze				Total Amount - 130 Sq Ft
	11	THROUGHOUT BUILDING	NONE DETECTED	110308ML-41		130 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XON	Miscellaneous Material Wired Window Foam Glaze		Total Amount - 100 Sq Ft			
	12	THROUGHOUT BUILDING	NSM			100 Sq Ft
XOP	Miscellaneous Material Old Wired Window Glaze		Total Amount - 15 Sq Ft			
	142	GYMNASIUM (2309)	ASSUMED			15 Sq Ft
X1A	Miscellaneous Material 6" X 12" Gray Ceramic Wall Tile System (2014)		Total Amount - 2720 Sq Ft			
	103	NURSE'S RESTROOM 1102B	NEW			240 Sq Ft
	112	RESTROOMS 1111 AND 1112	NEW			1200 Sq Ft
	116	RESTROOM 1204	NEW			200 Sq Ft
	151	CAFETERIA BOYS' RESTROOM	NEW			80 Sq Ft
	154	THROUGHOUT 3RD FLOOR KITCHEN	NEW			1000 Sq Ft
X1B	Miscellaneous Material 12" X 18" Black Ceramic Floor Tile System (2014)		Total Amount - 1350 Sq Ft			
	104	NURSE'S RESTROOM 1102B	NEW			100 Sq Ft
	113	RESTROOMS 1111 AND 1112	NEW			300 Sq Ft
	117	RESTROOM 1204	NEW			50 Sq Ft
	150	CAFETERIA BOYS' RESTROOM	NEW			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	152	THROUGHOUT 3RD FLOOR KITCHEN	NEW			400 Sq Ft
	155	KITCHEN RESTROOM	NEW			300 Sq Ft
X1C	Miscellaneous Material 1" X 1" Multi Shaded Brown Ceramic Floor Tile System					Total Amount - 2320 Sq Ft
	24	CUSTODIAL LOUNGE RESTROOM 0208A	ASSUMED			150 Sq Ft
	28	ROOM 0209	ASSUMED			200 Sq Ft
	31	LOWER LEVEL RESTROOMS 1211 AND 1212	ASSUMED			400 Sq Ft
	121	RESTROOM 2101	ASSUMED			30 Sq Ft
	122	MECHANICAL ROOM M11 ENTRY HALLWAY	ASSUMED			100 Sq Ft
	133	MEN'S RESTROOM 2302	ASSUMED			120 Sq Ft
	135	WOMEN'S RESTROOM 2303	ASSUMED			120 Sq Ft
	148	CAFETERIA GIRLS' RESTROOM	ASSUMED			200 Sq Ft
	160	RESTROOMS 4101 AND 4102	ASSUMED			500 Sq Ft
	171	RESTROOMS 5001 AND 5002	ASSUMED			500 Sq Ft
X1D	Miscellaneous Material 6" X 6" Red Quarry Floor Tile System					Total Amount - 300 Sq Ft
	46	STORAGE 0105	ASSUMED			100 Sq Ft
	49	OLD KITCHEN (0106)	ASSUMED			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1E	Miscellaneous Material 2" X 2" Beige Ceramic Floor Tile System					Total Amount - 1620 Sq Ft
	62	RESTROOM 0115	ASSUMED			50 Sq Ft
	114	RESTROOM 1206	ASSUMED			70 Sq Ft
	179	RESTROOMS 6102 AND 6103	ASSUMED			500 Sq Ft
	191	RESTROOMS 7102 AND 7103	ASSUMED			500 Sq Ft
	200	RESTROOMS 8102 AND 8103	ASSUMED			500 Sq Ft
X1F	Miscellaneous Material 4" X 4" White Ceramic Wall Tile System					Total Amount - 4900 Sq Ft
	63	RESTROOM 0115	ASSUMED			200 Sq Ft
	115	RESTROOM 1206	ASSUMED			200 Sq Ft
	180	RESTROOMS 6102 AND 6103	ASSUMED			1500 Sq Ft
	192	RESTROOMS 7102 AND 7103	ASSUMED			1500 Sq Ft
	201	RESTROOMS 8102 AND 8103	ASSUMED			1500 Sq Ft
X1G	Miscellaneous Material 6" X 6" Light Brown Quarry Floor Tile System					Total Amount - 1000 Sq Ft
	153	THROUGHOUT 3RD FLOOR KITCHEN	ASSUMED			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1H	Miscellaneous Material 2" X 2" Beige Ceramic Wall Tile System					Total Amount - 3600 Sq Ft
	149	CAFETERIA GIRLS' RESTROOM	ASSUMED			600 Sq Ft
	161	RESTROOMS 4101 AND 4102	ASSUMED			1500 Sq Ft
	172	RESTROOMS 5001 AND 5002	ASSUMED			1500 Sq Ft
X1I	Miscellaneous Material 8" X 8" Gray Ceramic Floor Tile System					Total Amount - 400 Sq Ft
	162	UNISEX ACROSS FROM RESTROOMS 4101 AND 4102	NEW			100 Sq Ft
	185	UNISEX RESTROOM NEAR ROOM 6110	NEW			100 Sq Ft
	194	UNISEX RESTROOM NEAR ROOM 7110	NEW			100 Sq Ft
	204	UNISEX RESTROOM NEAR ROOM 8110	NEW			100 Sq Ft
X1J	Miscellaneous Material 4" X 8" Gray Ceramic Wall Tile System					Total Amount - 1600 Sq Ft
	163	UNISEX ACROSS FROM RESTROOMS 4101 AND 4102	NEW			400 Sq Ft
	186	UNISEX RESTROOM NEAR ROOM 6110	NEW			400 Sq Ft
	195	UNISEX RESTROOM NEAR ROOM 7110	NEW			400 Sq Ft
	205	UNISEX RESTROOM NEAR ROOM 8110	NEW			400 Sq Ft