

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D1A Boiler Gaskets Burner Gasket						Total Amount: 2 Sq. Ft.
	19	BOILER ROOM	NONE DETECTED	100212MV-06	MV-06: BOILER #2.	2 Sq. Ft.
D1B Boiler Gaskets Tube Access Gasket						Total Amount: 2 Sq. Ft.
	20	BOILER ROOM	NONE DETECTED	100212MV-09	MV-09: BOILER #2.	2 Sq. Ft.
G1A Sprayed-On Acoustical Finish Sand Finish (Wall)						Total Amount: 2,500 Sq. Ft.
	1	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-14,15,16,17,18	MV-14: HALLWAY BY WEST COURTYARD. MV-15: HALLWAY BY EAST COURTYARD. MV-16: HALLWAY BY ROOM 2322. MV-17: HALLWAY BY ROOM 2320. MV-18: MAIN ENTRY.	2500 Sq. Ft.
I2A 2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge						Total Amount: 5,000 Sq. Ft.
	2	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-12	MV-12: MAIN OFFICE.	5000 Sq. Ft.
I3A 2' x 4' Ceiling Tile Light Texture w/Revealed Edge						Total Amount: 50,000 Sq. Ft.
	3	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-01	MV-01: ROOM 1406.	50000 Sq. Ft.
I3B 2' x 4' Ceiling Tile Vinyl-Coated Gypsum						Total Amount: 1,500 Sq. Ft.
	24	KITCHEN AREAS	NSM			1500 Sq. Ft.
I3C 2' x 4' Ceiling Tile Lengthwise Grooves w/Revealed Edge						Total Amount: 15,000 Sq. Ft.
	4	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-10	MV-10: COMMONS BY ROOM 1302.	15000 Sq. Ft.
I4A Acoustical Ceiling Tile Tectum Panels						Total Amount: 10,000 Sq. Ft.
	5	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-08	MV-08: HALLWAY BY ROOM 1130.	10000 Sq. Ft.

Chart C - All Materials List - Crossroads Montessori (cont.)

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2A 12" x 12" Vinyl Floor Tile & Mastic Light Tan Mottle w/Multi-Colored Accents						Total Amount: 20,000 Sq. Ft.
	6	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-02	MV-02: HALLWAY BY ROOM 2020.	20000 Sq. Ft.
K2B 12" x 12" Vinyl Floor Tile & Mastic Light Gray Mottle w/Multi-Colored Accents						Total Amount: 10,000 Sq. Ft.
	7	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-21	MV-21: CAFETERIA.	10000 Sq. Ft.
L0A Flexible Duct Connector Black Vinyl						Total Amount: 150 Sq. Ft.
	8	THROUGHOUT 1999 ORIGINAL BUILDING	NSM			150 Sq. Ft.
N0A Drywall/Joint Compound 1999 Original Building						Total Amount: 50,000 Sq. Ft.
	9	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-13	MA-13: COMMONS BY ROOM 1628.	50000 Sq. Ft.
P0A Fire Door Metal - 1.5 Hr Rating (Underwriter's Laboratories)						Total Amount: 100 Sq. Ft.
	10	THROUGHOUT 1999 ORIGINAL BUILDING	NEW			100 Sq. Ft.
P0B Fire Door Wood - 1 Hr Rating (Weyerhaeuser)						Total Amount: 100 Sq. Ft.
	11	THROUGHOUT 1999 ORIGINAL BUILDING	NEW			100 Sq. Ft.
Q0A Carpet Adhesive Brown Berber Carpet						Total Amount: 40,000 Sq. Ft.
	12	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-11	MV-11: COMMONS BY ROOM 1625.	40000 Sq. Ft.
Q0B Carpet Adhesive Green & Gray Carpet Squares						Total Amount: 1,000 Sq. Ft.
	21	MAIN ENTRANCE & CORRIDORS	NEW			500 Sq. Ft.
	23	COMPUTER LAB 2016	NONE DETECTED	100212MV-20	MV-20: COMPUTER LAB 2016.	500 Sq. Ft.
Q0C Carpet Adhesive Multi-Colored Carpet						Total Amount: 4,000 Sq. Ft.
	22	LOBBY AREA 1419	NEW			4000 Sq. Ft.
R0A Baseboard/Mopboard Adhesive 4" Gray Baseboard						Total Amount: 3,000 Sq. Ft.
	13	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-03	MV-03: HEALTH OFFICE.	3000 Sq. Ft.

Chart C - All Materials List - Crossroads Montessori (cont.)

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
R0B Baseboard/Mopboard Adhesive 4" Red Baseboard						Total Amount: 500 Sq. Ft.
	14	THROUGHOUT 1999 ORIGINAL BUILDING	NEW			500 Sq. Ft.
V0A Sink Undercoating Black						Total Amount: 200 Sq. Ft.
	15	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-04	MV-04: BREAK ROOM 1526.	200 Sq. Ft.
X0A Miscellaneous Material Red Fire Stop						Total Amount: 200 Sq. Ft.
	16	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-05	MV-05: HALLWAY BY ROOM 1511.	200 Sq. Ft.
X0B Miscellaneous Material Gray Duct Caulk						Total Amount: 300 Sq. Ft.
	17	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-07	MV-07: WEST MECHANICAL ROOM 2007.	300 Sq. Ft.
X0C Miscellaneous Material Metal Flooring Transition Strip						Total Amount: 50 Sq. Ft.
	18	THROUGHOUT 1999 ORIGINAL BUILDING	NONE DETECTED	100212MV-19	MV-19: COMMONS 1419A.	50 Sq. Ft.