

540 Warwick Street, Saint Paul, MN 55116

**Chart C - All Materials List**

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A	Mudded Pipe Joints on Fiberglass Insulation 1961 Original Building					<b>Total Amount - 19 Joints</b>
	23	BASEMENT SOUTH ENTRANCE HALLWAY 0100B	30 CH, 20 AM	ACB-450BA-A17	BA-A17: MECHANICAL ROOM 2307 (SINCE REMOVED).	5 Joints
	59	CAFETERIA 0201	30 CH, 20 AM			10 Joints
	91	GYMNASIUM OFFICE RESTROOM 1205A	30 CH, 20 AM			2 Joints
	108	ROOM 1006	30 CH, 20 AM			1 Joints
	119	CUSTODIAL SLOP SINK ROOM 1205B	30 CH, 20 AM			1 Joints
D1A	Boiler Gaskets Boiler #1					<b>Total Amount - 3 Sq Ft</b>
	17	BOILER ROOM 0116	NONE DETECTED	010509ML-04		3 Sq Ft
D1B	Boiler Gaskets Compressed Mineral Wool (Boiler #2)					<b>Total Amount - 10 Sq Ft</b>
	19	BOILER ROOM 0116	NONE DETECTED	010509ML-05		10 Sq Ft
D2A	Interior Boiler Insulation Boiler #1					<b>Total Amount - 50 Sq Ft</b>
	18	BOILER ROOM 0116	ASSUMED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2B	Interior Boiler Insulation Boiler #2					<b>Total Amount - 50 Sq Ft</b>
	20	BOILER ROOM 0116	ASSUMED			50 Sq Ft
H1A	Sprayed-On Structural Fireproofing Gray w/Vermiculite					<b>Total Amount - 20000 Sq Ft</b>
	13	THROUGHOUT BASEMENT	NONE DETECTED	010509ML-46, 47, 48; 2001-1501-AM-14, 15, 16; ACB-450BA-A8	ABOVE WEST HALLWAY CEILING.	20000 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Nail & Pin Holes in Concentric Circles					<b>Total Amount - 960 Sq Ft</b>
	46	ROOM 0105	NONE DETECTED	ACB-450BA-A19		960 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Spray-On Look w/Revealed Edge (2014)					<b>Total Amount - 17700 Sq Ft</b>
	16	THROUGHOUT BASEMENT HALLWAYS	NEW			5700 Sq Ft
	69	THROUGHOUT 1ST FLOOR HALLWAYS	NEW			6000 Sq Ft
	128	THROUGHOUT 2ND FLOOR HALLWAYS	NEW			6000 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Smooth (2015)					<b>Total Amount - 1000 Sq Ft</b>
	24	KITCHEN 0202	NEW			1000 Sq Ft
I3A	2' x 4' Ceiling Tile Nail & Pin Holes in Concentric Circles					<b>Total Amount - 1500 Sq Ft</b>
	28	ROOMS 0109 & 0108	NONE DETECTED	010509ML-40; ACB- 450BA-A12	A12: ROOM 2102 (SINCE REMOVED).	1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3B	2' x 4' Ceiling Tile Vinyl-Covered w/Pin Holes		<b>Total Amount - 6920 Sq Ft</b>			
	35	ROOM 0107	NONE DETECTED			1350 Sq Ft
	65	BASEMENT RESTROOMS 0118 & 0119 & ENTRY	NONE DETECTED	010509ML-42	ML-42: CAFETERIA 0201 (SINCE REMOVED).	350 Sq Ft
	85	GYMNASIUM 1201	NONE DETECTED			4500 Sq Ft
	93	STAGE	NONE DETECTED			720 Sq Ft
I3C	2' x 4' Ceiling Tile Textured w/Pin Holes		<b>Total Amount - 4950 Sq Ft</b>			
	41	ROOM 0106	NONE DETECTED			1350 Sq Ft
	53	ROOMS 0104, 0103 & 0121	NONE DETECTED	010509ML-41	ML-41: ROOM 0104.	3600 Sq Ft
I3G	2' x 4' Ceiling Tile Textured w/Grubs, Nail & Pin Holes		<b>Total Amount - 25000 Sq Ft</b>			
	72	THROUGHOUT 1ST FLOOR ROOMS	NONE DETECTED	010509ML-32	ML-32: HALLWAY OUTSIDE ROOM 0117 (SINCE REMOVED).	12000 Sq Ft
	131	THROUGHOUT 2ND FLOOR ROOMS	NONE DETECTED			10000 Sq Ft
	157	IMC 2114 & ADJOINING ROOMS	NONE DETECTED			3000 Sq Ft
I3H	2' x 4' Ceiling Tile Smooth (20XX)		<b>Total Amount - 1890 Sq Ft</b>			
	60	CAFETERIA 0201	NEW			1890 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3A	Miscellaneous Cementitious Material Black Science Table Top					<b>Total Amount - 230 Sq Ft</b>
	139	ROOM 2206 (TEACHERS' LOUNGE)	NONE DETECTED	010509ML-07		30 Sq Ft
	142	ROOM 2119	NONE DETECTED			40 Sq Ft
	145	ROOM 2117D	NONE DETECTED			30 Sq Ft
	147	ROOM 2117A	NONE DETECTED			20 Sq Ft
	149	ROOM 2117C	NONE DETECTED			40 Sq Ft
	150	ROOM 2117B	NONE DETECTED			30 Sq Ft
	153	ROOM 2116	NONE DETECTED	435-06	435-06: STORAGE 2117 (SINCE REMOVED).	40 Sq Ft
K0A	9" x 9" Vinyl Floor Tile & Mastic Tan w/Brown & Cream Streaks					<b>Total Amount - 180 Sq Ft</b>
	98	SERVER ROOM 1201C OFF OF STAGE	3 CH (MASTIC)	010509ML-19		120 Sq Ft
	115	ART ROOM NORTHEAST STORAGE 1206A	3 CH (MASTIC)			60 Sq Ft
K0D	9" x 9" Vinyl Floor Tile & Mastic Light Gray w/Gray Streaks					<b>Total Amount - 2540 Sq Ft</b>
	158	IMC 2114	5 CH (MASTIC)	010509ML-27	ML-27: ROOM 0108 (SINCE REMOVED).	1800 Sq Ft
	159	ROOM 2113	5 CH (MASTIC)			160 Sq Ft
	160	ROOM 2112	5 CH (MASTIC)			160 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	161	ROOM 2111	5 CH (MASTIC)			420 Sq Ft
<b>K1B</b>	Sheet Vinyl Flooring & Adhesive Dark Red w/Tan Streaks					<b>Total Amount - 5 Sq Ft</b>
	111	TELEPHONE BOOTH BY MAIN OFFICE	NONE DETECTED	010509ML-22		5 Sq Ft
<b>K2C</b>	12" x 12" Vinyl Floor Tile & Mastic Gray w/Multi-Colored Smudges					<b>Total Amount - 416 Sq Ft</b>
	57	ROOM 0103	NONE DETECTED			240 Sq Ft
	82	ROOM 1202	NONE DETECTED	010509ML-24	ML-24: ROOM 0117 (SINCE REMOVED).	160 Sq Ft
	107	NURSE'S OFFICE RESTROOM 1101B	NONE DETECTED			16 Sq Ft
<b>K2D</b>	12" x 12" Vinyl Floor Tile & Mastic Brown Mottle					<b>Total Amount - 445 Sq Ft</b>
	22	ELEVATOR	NONE DETECTED	010509ML-23		25 Sq Ft
	70	THROUGHOUT 1ST FLOOR HALLWAYS	NONE DETECTED			200 Sq Ft
	120	CUSTODIAL SLOP SINK ROOM 1205B	NONE DETECTED			20 Sq Ft
	129	THROUGHOUT 2ND FLOOR HALLWAYS	NONE DETECTED			200 Sq Ft
<b>K2E</b>	12" x 12" Vinyl Floor Tile & Mastic Beige w/Multi-Colored Smudges					<b>Total Amount - 22000 Sq Ft</b>
	73	THROUGHOUT 1ST FLOOR ROOMS	NONE DETECTED			12000 Sq Ft
	132	THROUGHOUT 2ND FLOOR ROOMS	NONE DETECTED	010509ML-17	ML-17: ROOM 2102B.	10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2F	12" x 12" Vinyl Floor Tile & Mastic White w/Black & Gray Smudges					<b>Total Amount - 4750 Sq Ft</b>
	86	GYMNASIUM 1201	3 CH (MASTIC)	010509ML-18		4500 Sq Ft
	89	GYMNASIUM OFFICE 1205	3 CH (MASTIC)			150 Sq Ft
	102	STAGE ENTRANCE 1201A	3 CH (MASTIC)			100 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Tan Mottle					<b>Total Amount - 8800 Sq Ft</b>
	71	THROUGHOUT 1ST FLOOR HALLWAYS	NONE DETECTED	010509ML-37		4000 Sq Ft
	130	THROUGHOUT 2ND FLOOR HALLWAYS	NONE DETECTED			4800 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic White w/Gray Streaks					<b>Total Amount - 4500 Sq Ft</b>
	121	ROOM 1117	NONE DETECTED			900 Sq Ft
	135	ROOM 2120	NONE DETECTED	010509ML-38		900 Sq Ft
	140	ROOM 2119	NONE DETECTED			900 Sq Ft
	151	ROOM 2116	NONE DETECTED			900 Sq Ft
	181	ROOM 2121	NONE DETECTED			900 Sq Ft
K2I	12" x 12" Vinyl Floor Tile & Mastic Gray w/Light Gray & Orange Smudges (2009)					<b>Total Amount - 11760 Sq Ft</b>
	14	THROUGHOUT BASEMENT	NEW			10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	29	ROOM 0109	NEW			400 Sq Ft
	31	ROOM 0108	NEW			360 Sq Ft
	36	ROOM 0107	NEW			200 Sq Ft
	42	ROOM 0106	NEW			200 Sq Ft
	47	ROOM 0105	NEW			400 Sq Ft
	54	ROOM 0104	NEW			200 Sq Ft
LOA	Flexible Duct Connector Green Canvas					<b>Total Amount - 6 Sq Ft</b>
	116	ART ROOM NORTHEAST STORAGE 1206A	NONE DETECTED	435-01	MECHANICAL ROOM 2202 (SINCE REMOVED).	6 Sq Ft
LOB	Flexible Duct Connector Black Vinyl					<b>Total Amount - 100 Sq Ft</b>
	9	THROUGHOUT BUILDING	NSM			100 Sq Ft
MOA	Plaster 1961 Original Building w/ Skim Coat					<b>Total Amount - 40000 Sq Ft</b>
	1	THROUGHOUT BUILDING	NONE DETECTED	010509ML-09, 10, 11, 12, 13; 2001-1501-AM- 8; ACB-450-BA-A15	ML-09: CUSTODIAL STORAGE. ML-10: HALLWAY NEAR ROOM 1108. ML-11: STAIRWELL NEAR IMC. ML-12; ROOM 1108. AM-8: ROOM 0104.	40000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOB	Plaster 1961 Original Building w/o Skim Coat					<b>Total Amount - 6000 Sq Ft</b>
	12	THROUGHOUT BUILDING MECHANICAL ROOMS	NONE DETECTED	010509ML-14, 15, 16; 2001-1501-AM-1, 10, 11, 12, 13	ML-14: ROOM 2202. ML-15: BOILER ROOM. ML-16: ROOM 2209. AM12 & 13: ROOM 2101. AM10 & 11: ROOM 2203. AM1: ROOM 2202.	6000 Sq Ft
MOC	Plaster Trowelled Ceiling w/o Skim Coat					<b>Total Amount - 960 Sq Ft</b>
	81	ROOM 1202	NONE DETECTED	2001-1501-AM-9		160 Sq Ft
	92	GYMNASIUM STORAGE ROOM 1201D	NONE DETECTED			100 Sq Ft
	106	ROOM 1102	NONE DETECTED	ACB-450BA-A7		200 Sq Ft
	144	THROUGHOUT 2117 AREAS	NONE DETECTED	ACB-450BA-B3	B3: ROOM 2116 OFFICE.	500 Sq Ft
MOD	Plaster Spray-Applied Ceiling w/o Skim Coat					<b>Total Amount - 2090 Sq Ft</b>
	114	ART ROOM NORTHEAST STORAGE 1206A	NONE DETECTED			70 Sq Ft
	123	ROOM 1116	NONE DETECTED	010509ML-45		320 Sq Ft
	138	ROOM 2206 (TEACHERS' LOUNGE)	NONE DETECTED	ACB-450BA-A4, A5		240 Sq Ft
	156	IMC 2114 & ADJOINING ROOMS	NONE DETECTED	ACB-450BA-A2		960 Sq Ft
	166	MECHANICAL ROOM 2203	NONE DETECTED			220 Sq Ft
	183	ROOM 2209	NONE DETECTED	010509ML-16		280 Sq Ft



Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
NOA	Drywall/Joint Compound					<b>Total Amount - 15000 Sq Ft</b>
2	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-AM-7; 435-02; 435-03	AM-7: ROOM 0104.	15000 Sq Ft	
POA	Fire Doors Metal - 1.5 Hr Rating (Underwriter's Laboratories)					<b>Total Amount - 40 Sq Ft</b>
21	BOILER ROOM 0116	ASSUMED			20 Sq Ft	
68	CUSTODIAL OFFICE 0117	ASSUMED			20 Sq Ft	
POB	Fire Doors Wood - 1 Hr Rating (Warnock Hersey)					<b>Total Amount - 280 Sq Ft</b>
11	THROUGHOUT BUILDING	NONE DETECTED	061014BF-01	BF-01: GYMNASIUM TO STAGE DOOR.	280 Sq Ft	
POC	Fire Doors Metal - 1.5 Hr Rating (Warnock Hersey)					<b>Total Amount - 40 Sq Ft</b>
50	ROOM 0105	NEW			20 Sq Ft	
58	MECHANICAL ROOM 0102A	NEW			20 Sq Ft	
POD	Fire Doors Wood - 1 Hr Rating (Weldwood)					<b>Total Amount - 180 Sq Ft</b>
78	STORAGE ROOM 1203 ACROSS HALLWAY FROM ROOM 1109	80 CH			40 Sq Ft	
88	GYMNASIUM OFFICE 1205 & ENTRY	80 CH			40 Sq Ft	
96	SERVER ROOM 1201C OFF OF STAGE	80 CH	010509ML-43		20 Sq Ft	
101	STAGE STORAGE/OFFICE 1201B	80 CH			20 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	167	MECHANICAL ROOM 2203	80 CH			20 Sq Ft
	170	MECHANICAL ROOM 2202	80 CH			20 Sq Ft
	180	MECHANICAL ROOM 2101	80 CH			20 Sq Ft
Q0B	Carpet Adhesive Miscellaneous Berber Carpet					<b>Total Amount - 10000 Sq Ft</b>
	3	THROUGHOUT BUILDING	NONE DETECTED	010509ML-21, 27	ML-21: ROOM 0121. ML-27: ROOM 0108.	10000 Sq Ft
R0B	Baseboard/Mopboard Adhesive 6" Gray Baseboard					<b>Total Amount - 400 Sq Ft</b>
	4	THROUGHOUT BUILDING	NONE DETECTED	010509ML-25	ML-25: ROOM 0107.	400 Sq Ft
R0C	Baseboard/Mopboard Adhesive 4" Tan Baseboard					<b>Total Amount - 400 Sq Ft</b>
	5	THROUGHOUT BUILDING	NONE DETECTED	010509ML-34	ML-34: ROOM 1110.	400 Sq Ft
R0D	Baseboard/Mopboard Adhesive 4" Black Baseboard					<b>Total Amount - 200 Sq Ft</b>
	6	THROUGHOUT BUILDING	NONE DETECTED	010509ML-36	ML-36: ROOM 1117.	200 Sq Ft
R0E	Baseboard/Mopboard Adhesive 4" Brown Baseboard					<b>Total Amount - 100 Sq Ft</b>
	7	THROUGHOUT BUILDING	NONE DETECTED	010509ML-44	ML-44: SERVER ROOM OFF OF STAGE.	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROF		Baseboard/Mopboard Adhesive 6" Dark Gray Baseboard				<b>Total Amount - 20 Sq Ft</b>
	30	ROOM 0109	NEW			10 Sq Ft
	32	ROOM 0108	NEW			10 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier Elevated (1961)				<b>Total Amount - 720 Sq Ft</b>
	94	STAGE	ASSUMED			720 Sq Ft
UOA		Light Pad Insulation Round Light Pads				<b>Total Amount - 7 Sq Ft</b>
	97	SERVER ROOM 1201C OFF OF STAGE	35 CH			2 Sq Ft
	99	STAGE STORAGE/OFFICE 1201B	35 CH			2 Sq Ft
	110	MAIN OFFICE STORAGE (OLD SAFE ROOM) 1009	35 CH	010509ML-33	33: CUSTODIAL STORAGE 0120 WEST OF CAFETERIA (OLD LOCKER ROOM) (SINCE REMOVED).	1 Sq Ft
	117	ART ROOM SOUTHWEST STORAGE 1206B	35 CH			1 Sq Ft
	143	SERVER ROOM 2118	35 CH			1 Sq Ft
VOA		Sink Undercoating Gray				<b>Total Amount - 35 Sq Ft</b>
	38	ROOM 0107	NONE DETECTED	010509ML-29		5 Sq Ft
	44	ROOM 0106	NONE DETECTED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	49	ROOM 0105	NONE DETECTED			5 Sq Ft
	56	ROOM 0104	NONE DETECTED			5 Sq Ft
	62	DISCOVERY ROOM 0121	NONE DETECTED			15 Sq Ft
<b>VOB</b>	Sink Undercoating Pink					<b>Total Amount - 20 Sq Ft</b>
	109	MAIN OFFICE KITCHEN/BREAK ROOM 1005	NONE DETECTED	010509ML-35		5 Sq Ft
	155	ROOM 2116B	NONE DETECTED			5 Sq Ft
	162	ROOM 2111	NONE DETECTED			5 Sq Ft
	178	ROOM 2102B	NONE DETECTED			5 Sq Ft
<b>XOB</b>	Miscellaneous Material Off-White w/Brown Specks Countertop					<b>Total Amount - 1170 Sq Ft</b>
	15	THROUGHOUT BASEMENT	NONE DETECTED			90 Sq Ft
	74	THROUGHOUT 1ST FLOOR ROOMS	NONE DETECTED			120 Sq Ft
	133	THROUGHOUT 2ND FLOOR ROOMS	NONE DETECTED	2001-1501-AM-2	AM-2: ROOM 2110.	960 Sq Ft
<b>XOC</b>	Miscellaneous Material Metal Frame Chalkboard Adhesive					<b>Total Amount - 1560 Sq Ft</b>
	37	ROOM 0107	ASSUMED			30 Sq Ft
	43	ROOM 0106	ASSUMED			30 Sq Ft
	48	ROOM 0105	ASSUMED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	55	ROOM 0104	ASSUMED			30 Sq Ft
	61	DISCOVERY ROOM 0121	ASSUMED			30 Sq Ft
	75	ROOM 1110	ASSUMED			60 Sq Ft
	76	ROOM 1109	ASSUMED			60 Sq Ft
	79	ROOM 1108	ASSUMED			60 Sq Ft
	80	ROOM 1107	ASSUMED			60 Sq Ft
	83	ROOM 1106	ASSUMED			60 Sq Ft
	84	ROOM 1105	ASSUMED			60 Sq Ft
	122	ROOM 1117	ASSUMED			60 Sq Ft
	124	ROOM 1115	ASSUMED			30 Sq Ft
	125	ROOM 1114	ASSUMED			60 Sq Ft
	126	ROOM 1113	ASSUMED			60 Sq Ft
	127	ROOM 1111	ASSUMED			60 Sq Ft
	134	ROOM 2208	ASSUMED			30 Sq Ft
	136	ROOM 2120	ASSUMED			60 Sq Ft
	137	ROOM 2207	ASSUMED			30 Sq Ft
	141	ROOM 2119	ASSUMED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	152	ROOM 2116	ASSUMED			30 Sq Ft
	165	ROOM 2110	ASSUMED			60 Sq Ft
	168	ROOM 2109	ASSUMED			60 Sq Ft
	169	ROOM 2108	ASSUMED			60 Sq Ft
	171	ROOM 2107	ASSUMED			60 Sq Ft
	172	ROOM 2106	ASSUMED			60 Sq Ft
	173	ROOM 2105	ASSUMED			60 Sq Ft
	174	ROOM 2104	ASSUMED			60 Sq Ft
	176	ROOM 2103	ASSUMED			60 Sq Ft
	177	ROOM 2102	ASSUMED			60 Sq Ft
	182	ROOM 2121	ASSUMED			60 Sq Ft
<b>X0D</b>	<b>Miscellaneous Material Wired Window Glaze</b>					<b>Total Amount - 2 Sq Ft</b>
	90	GYMNASIUM OFFICE 1205	NONE DETECTED	010509ML-31	ML-31: DISCOVERY CLUB OFFICE 0101 (SINCE REMOVED).	2 Sq Ft
<b>X0F</b>	<b>Miscellaneous Material Red Fire Stop</b>					<b>Total Amount - 200 Sq Ft</b>
	8	THROUGHOUT BUILDING	NONE DETECTED	010509ML-49		200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOG		Miscellaneous Material Metal Frame Corkboard Adhesive				<b>Total Amount - 300 Sq Ft</b>
	10	THROUGHOUT BUILDING	ASSUMED			300 Sq Ft
XOH		Miscellaneous Material Beige & Gray Canvas-Look Countertop				<b>Total Amount - 80 Sq Ft</b>
	100	STAGE STORAGE/OFFICE 1201B	NONE DETECTED	081915BV-05	BV-05: 1201C (SINCE REMOVED).	5 Sq Ft
	154	ROOM 2116B	NONE DETECTED			25 Sq Ft
	163	ROOM 2111	NONE DETECTED			25 Sq Ft
	179	ROOM 2102B	NONE DETECTED			25 Sq Ft
XOI		Miscellaneous Material Black Wall Drying Rack				<b>Total Amount - 4 Sq Ft</b>
	148	ROOM 2117A	18 CH	081915BV-06	BV-06: ROOM 2117A.	4 Sq Ft
XOJ		Miscellaneous Material Cork Wall Tile Adhesive				<b>Total Amount - 4 Sq Ft</b>
	146	ROOM 2117D	NONE DETECTED	081915BV-07	BV-07: ROOM 2117D.	4 Sq Ft
X1A		Miscellaneous Material 6" Red Quarry Tile				<b>Total Amount - 50 Sq Ft</b>
	25	KITCHEN COOLER 0206	ASSUMED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1B	Miscellaneous Material 1" Beige w/White Ceramic Floor Tile System					<b>Total Amount - 1350 Sq Ft</b>
	34	STAFF RESTROOM 0307	NONE DETECTED			60 Sq Ft
	63	STORAGE 0120	NONE DETECTED	081915BV-04		900 Sq Ft
	103	RESTROOM 1104D	NONE DETECTED			145 Sq Ft
	104	RESTROOM 1103D	NONE DETECTED			145 Sq Ft
	113	WOMEN'S STAFF RESTROOM 1207	NONE DETECTED			100 Sq Ft
X1C	Miscellaneous Material 6" Beige Quarry Tile					<b>Total Amount - 1984 Sq Ft</b>
	33	BASEMENT STAIRWELL/ENTRANCE 0299B	ASSUMED			500 Sq Ft
	45	BASEMENT STAIRWELL/ENTRANCE 0299C	ASSUMED			500 Sq Ft
	64	STAIRWELL 0199D OFF STORAGE 0120	ASSUMED			200 Sq Ft
	87	GYMNASIUM OFFICE 1205 ENTRY	ASSUMED			24 Sq Ft
	95	STAGE	ASSUMED			60 Sq Ft
	118	MAIN ENTRY & STAIRWELL 1199A	ASSUMED			700 Sq Ft
X1D	Miscellaneous Material 2" Pink Ceramic Floor Tile System (200X)					<b>Total Amount - 90 Sq Ft</b>
	39	RESTROOM 0106A	NEW			45 Sq Ft
	51	RESTROOM 0204A	NEW			45 Sq Ft



Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1E		Miscellaneous Material 4" White Ceramic Wall Tile System (200X)				<b>Total Amount - 1000 Sq Ft</b>
	40	RESTROOM 0106A	NEW			100 Sq Ft
	52	RESTROOM 0204A	NEW			100 Sq Ft
	67	BASEMENT RESTROOMS 0118 & 0119	NEW			800 Sq Ft
X1F		Miscellaneous Material 2" Blue Ceramic Floor Tile System (20XX)				<b>Total Amount - 400 Sq Ft</b>
	66	BASEMENT RESTROOMS 0118 & 0119	NEW			400 Sq Ft
X1G		Miscellaneous Material 1" Teal w/White Ceramic Floor Tile System (20XX)				<b>Total Amount - 830 Sq Ft</b>
	77	GIRLS' RESTROOM 1204	NEW			200 Sq Ft
	105	MEN'S STAFF RESTROOM 1208A	NEW			45 Sq Ft
	112	BOYS' RESTROOM 1208	NEW			225 Sq Ft
	164	GIRLS' RESTROOM 2204	NEW			180 Sq Ft
	175	BOYS' RESTROOM 2201	NEW			180 Sq Ft
X1H		Miscellaneous Material 6" x 6" Gray Quarry Tile System (2015)				<b>Total Amount - 152 Sq Ft</b>
	26	KITCHEN DISH ROOM 0207	NEW			140 Sq Ft
	27	SMALL KITCHEN STORAGE 0207B	NEW			12 Sq Ft