

1290 Arcade Street North, Saint Paul, MN 55106

**Chart C - All Materials List**

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2A		Mudded Pipe Joints on Millboard Insulation 1924 Addition				<b>Total Amount - 8 Joints</b>
	59	THROUGHOUT 1924 ADDITION	ASSUMED			8 Joints
B2A		Millboard Pipe Insulation 1924 Addition				<b>Total Amount - 40 Lin Ft</b>
	58	THROUGHOUT 1924 ADDITION	ASSUMED			40 Lin Ft
D1A		Boiler Gaskets White, Shiny				<b>Total Amount - 4 Sq Ft</b>
	90	BOILER ROOM 1303	NONE DETECTED	020810ML-11		4 Sq Ft
D2A		Interior Boiler Insulation Interior Refractory				<b>Total Amount - 60 Sq Ft</b>
	91	BOILER ROOM 1303	ASSUMED			60 Sq Ft
H1A		Sprayed-On Structural Fireproofing Light Blue, Fluffy (2004)				<b>Total Amount - 600 Sq Ft</b>
	160	HALLWAY 3200B BETWEEN ROOMS 3204 & 3207	NONE DETECTED	020810ML-35, 36		50 Sq Ft
	164	ROOM 3207	NONE DETECTED			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	169	ROOM 3206	NONE DETECTED	020810ML-35, 36		100 Sq Ft
	172	ROOM 3205	NONE DETECTED			50 Sq Ft
	176	ROOM 3204	NONE DETECTED	020810ML-34		200 Sq Ft
I3A	2' x 4' Ceiling Tile Widthwise Slits & Pin Holes (1992)					<b>Total Amount - 13669 Sq Ft</b>
	10	HALLWAY OUTSIDE ROOMS 1201 & 1202	NONE DETECTED			200 Sq Ft
	11	ROOM 1202	NONE DETECTED			145 Sq Ft
	13	GYMNASIUM OFFICE 1203A	NONE DETECTED			85 Sq Ft
	17	ROOM 1201	NONE DETECTED			200 Sq Ft
	43	MAIN OFFICE 1001	NONE DETECTED			720 Sq Ft
	46	OFFICE 1002	NONE DETECTED			120 Sq Ft
	48	OFFICE 1003	NONE DETECTED			190 Sq Ft
	50	NURSE'S OFFICE 1004	NONE DETECTED			135 Sq Ft
	54	SICK ROOM 1005	NONE DETECTED			130 Sq Ft
	60	ROOM 1204	NONE DETECTED			350 Sq Ft
	70	ROOM 1205	NONE DETECTED			240 Sq Ft
	75	HALLWAY 1200B BETWEEN ROOMS 1206 & 1207	NONE DETECTED			170 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	79	ROOM 1207	NONE DETECTED			1050 Sq Ft
	82	ROOM 1206	NONE DETECTED			1050 Sq Ft
	85	NORTH ENTRY 1300D NEAR CUSTODIAL OFFICE	NONE DETECTED			200 Sq Ft
	88	CUSTODIAL OFFICE 1302	NONE DETECTED			110 Sq Ft
	89	HALLWAY OUTSIDE BOILER ROOM 1303	NONE DETECTED	020810ML-02		80 Sq Ft
	95	SOUTH ENTRY 1300B TO GYMNASIUM 1301B	NONE DETECTED			190 Sq Ft
	96	HALLWAY 1300	NONE DETECTED			360 Sq Ft
	126	ROOM 2201	NONE DETECTED			640 Sq Ft
	133	MEDIA CENTER 2208	NONE DETECTED			1950 Sq Ft
	137	MEDIA CENTER OFFICE 2209	NONE DETECTED	020810ML-03		320 Sq Ft
	145	HALLWAY 2200B BETWEEN ROOMS 2204 & 2206	NONE DETECTED			170 Sq Ft
	147	ROOM 2206	NONE DETECTED			820 Sq Ft
	149	ROOM 2205	NONE DETECTED			240 Sq Ft
	151	ROOM 2204	NONE DETECTED			820 Sq Ft
	173	ROOM 3205	NONE DETECTED			190 Sq Ft
	181	ROOM 3203	NONE DETECTED			750 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	184	ROOM 3208	NONE DETECTED			750 Sq Ft
	187	ROOM 3209	NONE DETECTED			250 Sq Ft
	190	ROOM 3201	NONE DETECTED			680 Sq Ft
	196	ROOM 3211	NONE DETECTED			364 Sq Ft
I3B	2' x 4' Ceiling Tile Vinyl-Covered Sheetrock					<b>Total Amount - 1120 Sq Ft</b>
	93	KITCHEN AREA 1304	NSM			1120 Sq Ft
I3C	2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes					<b>Total Amount - 2110 Sq Ft</b>
	155	THROUGHOUT 3RD FLOOR HALLWAY	NONE DETECTED	020810ML-29		330 Sq Ft
	161	HALLWAY 3200B BETWEEN ROOMS 3204 & 3207	NONE DETECTED			140 Sq Ft
	165	ROOM 3207	NONE DETECTED			820 Sq Ft
	177	ROOM 3204	NONE DETECTED			820 Sq Ft
I3D	2' x 4' Ceiling Tile Dents w/Pin Holes					<b>Total Amount - 330 Sq Ft</b>
	170	ROOM 3206	NONE DETECTED	020810ML-33		330 Sq Ft
J3A	Miscellaneous Cementitious Material Black Window Sills (2004)					<b>Total Amount - 15 Sq Ft</b>
	167	ROOM 3207	NONE DETECTED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	179	ROOM 3204	NONE DETECTED	020810ML-32		10 Sq Ft
<b>K1A</b>	Sheet Vinyl Flooring & Adhesive Purple Terrazzo-Look					<b>Total Amount - 130 Sq Ft</b>
	55	SICK ROOM 1005	NONE DETECTED	020810ML-09		130 Sq Ft
<b>K2A</b>	12" x 12" Vinyl Floor Tile & Mastic Gray w/Black Specks					<b>Total Amount - 4775 Sq Ft</b>
	14	GYMNASIUM OFFICE 1203A	NONE DETECTED	020810ML-04		85 Sq Ft
	92	GYMNASIUM 1301A & 1301B	NONE DETECTED			4500 Sq Ft
	174	ROOM 3205	NONE DETECTED			190 Sq Ft
<b>K2B</b>	12" x 12" Vinyl Floor Tile & Mastic Tan Mottle					<b>Total Amount - 139 Sq Ft</b>
	51	NURSE'S OFFICE 1004	NONE DETECTED	020810ML-08		135 Sq Ft
	109	ROOM 2105	NONE DETECTED			4 Sq Ft
<b>K2C</b>	12" x 12" Vinyl Floor Tile & Mastic Pink Mottle					<b>Total Amount - 820 Sq Ft</b>
	152	ROOM 2204	NONE DETECTED	020810ML-28		820 Sq Ft
<b>K3A</b>	Miscellaneous Flooring Black Floor Tile Mastic					<b>Total Amount - 2850 Sq Ft</b>
	7	THROUGHOUT 1ST FLOOR HALLWAY	NONE DETECTED			950 Sq Ft
	98	THROUGHOUT 2ND FLOOR HALLWAY	NONE DETECTED	020810ML-06	ML-06: HALLWAY NEAR ROOM 2203.	950 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	157	THROUGHOUT 3RD FLOOR HALLWAY	NONE DETECTED			950 Sq Ft
<b>K3B</b>	Miscellaneous Flooring 2' x 2' Blue Raised Circles Stair Treads					<b>Total Amount - 500 Sq Ft</b>
	78	NORTH STAIRWELL 1399D	NONE DETECTED	020810ML-26		500 Sq Ft
<b>K3C</b>	Miscellaneous Flooring 2' X 2' Red, White & Blue Rubber Floor Tile (2012)					<b>Total Amount - 2990 Sq Ft</b>
	6	THROUGHOUT 1ST FLOOR HALLWAY	NEW			950 Sq Ft
	97	THROUGHOUT 2ND FLOOR HALLWAY	NEW			950 Sq Ft
	156	THROUGHOUT 3RD FLOOR HALLWAY	NEW			950 Sq Ft
	162	HALLWAY 3200B BETWEEN ROOMS 3204 & 3207	NEW			140 Sq Ft
<b>K3D</b>	Miscellaneous Flooring Mottled Green Epoxy Flooring					<b>Total Amount - 1140 Sq Ft</b>
	94	KITCHEN AREA 1304	NEW			1120 Sq Ft
	129	ROOM 2201 RESTROOM (2201A)	NEW			20 Sq Ft
<b>K3E</b>	Miscellaneous Flooring White w/Red, Black, & Gray Pebbles Epoxy Flooring (2019)					<b>Total Amount - 1315 Sq Ft</b>
	118	GIRLS' RESTROOM 2106	NEW			315 Sq Ft
	124	BOYS' RESTROOM 2107	NEW			300 Sq Ft
	199	BOYS' RESTROOM 3107	NEW			300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	205	GIRLS' RESTROOM 3106	NEW			400 Sq Ft
<b>LOA</b>						<b>Total Amount - 15 Sq Ft</b>
	131	1991 MECHANICAL ROOM 2201B	NSM			15 Sq Ft
<b>MOA</b>						<b>Total Amount - 20000 Sq Ft</b>
	9	THROUGHOUT 1922 ORIGINAL BUILDING	NONE DETECTED	020810ML-12, 13, 14, 15, 16, 17; 458-1	ML-12: CUSTODIAL CLOSET NEAR ROOM 3101. ML-13: MEDIA CENTER. ML-14: MAIN OFFICE. ML-15: ROOM 2105. ML-16: ROOM 3210. ML-17: ROOM 3105. 458-1: ROOM 1103.	20000 Sq Ft
<b>MOB</b>						<b>Total Amount - 3000 Sq Ft</b>
	57	THROUGHOUT 1924 ADDITION	NONE DETECTED	020810ML-18, 19, 20, 21, 22;458-2	ML-18: ROOM 3208. ML-19: 3RD FLOOR HALLWAY. ML-20: SERVER ROOM. ML-21: MEDIA OFFICE. ML-22: ROOM 1205. 458-2: ROOM 1208.	3000 Sq Ft
<b>NOA</b>						<b>Total Amount - 10000 Sq Ft</b>
	1	THROUGHOUT BUILDING	NONE DETECTED	020810ML-23; 509N7	ML-23: BOILER ROOM. N7: ROOM 1202.	10000 Sq Ft
<b>POA</b>						<b>Total Amount - 360 Sq Ft</b>
	8	THROUGHOUT 1ST FLOOR HALLWAY	ASSUMED			160 Sq Ft
	16	ELEVATOR MECHANICAL ROOM 1203	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	86	NORTH ENTRY 1300D NEAR CUSTODIAL OFFICE	ASSUMED			20 Sq Ft
	100	THROUGHOUT 2ND FLOOR HALLWAY	ASSUMED			80 Sq Ft
	159	THROUGHOUT 3RD FLOOR HALLWAY	ASSUMED			80 Sq Ft
<b>POB</b>	Fire Doors Metal - 1.5 Hr Rating (Underwriter's Laboratories) (1991)					<b>Total Amount - 20 Sq Ft</b>
	130	1991 MECHANICAL ROOM 2201B	NEW			20 Sq Ft
<b>POC</b>	Fire Doors Metal - 1.5 Hr Rating (Warnock Hersey)					<b>Total Amount - 20 Sq Ft</b>
	87	NORTH ENTRY 1300D NEAR CUSTODIAL OFFICE	ASSUMED			20 Sq Ft
<b>POD</b>	Fire Doors Pieced Metal					<b>Total Amount - 40 Sq Ft</b>
	223	LOWER LEVEL	ASSUMED			40 Sq Ft
<b>Q0A</b>	Carpet Adhesive Purple Carpet					<b>Total Amount - 18589 Sq Ft</b>
	12	ROOM 1202	NONE DETECTED			145 Sq Ft
	18	ROOM 1201	NONE DETECTED			200 Sq Ft
	23	ROOM 1105	NONE DETECTED			750 Sq Ft
	27	ROOM 1104	NONE DETECTED			750 Sq Ft
	44	MAIN OFFICE 1001	NONE DETECTED			720 Sq Ft



Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	47	OFFICE 1002	NONE DETECTED			120 Sq Ft
	49	OFFICE 1003	NONE DETECTED			190 Sq Ft
	61	ROOM 1204	NONE DETECTED			350 Sq Ft
	71	ROOM 1205	NONE DETECTED			240 Sq Ft
	80	ROOM 1207	NONE DETECTED			1050 Sq Ft
	83	ROOM 1206	NONE DETECTED			1050 Sq Ft
	104	ROOM 2103	NONE DETECTED	020810ML-01		750 Sq Ft
	110	ROOM 2105	NONE DETECTED			500 Sq Ft
	114	ROOM 2102	NONE DETECTED			750 Sq Ft
	120	ROOM 2101	NONE DETECTED			750 Sq Ft
	127	ROOM 2201	NONE DETECTED			640 Sq Ft
	134	MEDIA CENTER 2208	NONE DETECTED			1950 Sq Ft
	138	MEDIA CENTER OFFICE 2209	NONE DETECTED			320 Sq Ft
	142	ROOM 2203	NONE DETECTED			750 Sq Ft
	148	ROOM 2206	NONE DETECTED			820 Sq Ft
	182	ROOM 3203	NONE DETECTED			750 Sq Ft
	185	ROOM 3208	NONE DETECTED			750 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	188	ROOM 3209	NONE DETECTED			250 Sq Ft
	191	ROOM 3201	NONE DETECTED			680 Sq Ft
	192	ROOM 3210	NONE DETECTED			750 Sq Ft
	197	ROOM 3211	NONE DETECTED			364 Sq Ft
	201	ROOM 3101	NONE DETECTED			750 Sq Ft
	207	ROOM 3102	NONE DETECTED			750 Sq Ft
	215	ROOM 3103	NONE DETECTED			750 Sq Ft
<b>Q0B</b>	<b>Carpet Adhesive Brown Carpet</b>					<b>Total Amount - 750 Sq Ft</b>
	34	ROOM 1102	NONE DETECTED	2001-1901-XX-26B		750 Sq Ft
<b>Q0C</b>	<b>Carpet Adhesive Blue Carpet</b>					<b>Total Amount - 1500 Sq Ft</b>
	38	ROOM 1101	NONE DETECTED	020810ML-25		750 Sq Ft
	219	ROOM 3104	NONE DETECTED			750 Sq Ft
<b>Q0D</b>	<b>Carpet Adhesive Multi-Colored Berber Carpet</b>					<b>Total Amount - 1970 Sq Ft</b>
	166	ROOM 3207	NONE DETECTED			820 Sq Ft
	171	ROOM 3206	NONE DETECTED			330 Sq Ft
	178	ROOM 3204	NONE DETECTED	020810ML-31		820 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0E		Carpet Adhesive Blue & Gray w/Red Accents (2017)			<b>Total Amount - 2250 Sq Ft</b>	
	30	ROOM 1103	NEW			750 Sq Ft
	65	ROOM 1208	NEW			750 Sq Ft
	211	ROOM 3105	NEW			750 Sq Ft
ROA		Baseboard/Mopboard Adhesive 4" Maroon Baseboard			<b>Total Amount - 30 Sq Ft</b>	
	52	NURSE'S OFFICE 1004	NONE DETECTED	2001-1901-XX-28B		20 Sq Ft
	56	SICK ROOM 1005	NONE DETECTED			5 Sq Ft
	153	ROOM 2204	NONE DETECTED			5 Sq Ft
ROB		Baseboard/Mopboard Adhesive 4" Blue (2012)			<b>Total Amount - 35 Sq Ft</b>	
	76	HALLWAY 1200B BETWEEN ROOMS 1206 & 1207	NEW			5 Sq Ft
	146	HALLWAY 2200B BETWEEN ROOMS 2204 & 2206	NEW			5 Sq Ft
	158	THROUGHOUT 3RD FLOOR HALLWAY	NEW			20 Sq Ft
	163	HALLWAY 3200B BETWEEN ROOMS 3204 & 3207	NEW			5 Sq Ft
ROC		Baseboard/Mopboard Adhesive 4" Dark Brown Baseboard			<b>Total Amount - 15 Sq Ft</b>	
	77	HALLWAY 1200B BETWEEN ROOMS 1206 & 1207	ASSUMED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	175	ROOM 3205	ASSUMED			10 Sq Ft
SOA	Wood Floor Felt / Vapor Barrier 1922 Original Building				<b>Total Amount - 14114 Sq Ft</b>	
	24	ROOM 1105	ASSUMED			750 Sq Ft
	28	ROOM 1104	ASSUMED			750 Sq Ft
	31	ROOM 1103	ASSUMED			750 Sq Ft
	35	ROOM 1102	ASSUMED			750 Sq Ft
	39	ROOM 1101	ASSUMED			750 Sq Ft
	103	ROOM 2104	ASSUMED			300 Sq Ft
	105	ROOM 2103	ASSUMED			750 Sq Ft
	108	ROOM 2105	ASSUMED			1200 Sq Ft
	115	ROOM 2102	ASSUMED			750 Sq Ft
	121	ROOM 2101	ASSUMED			750 Sq Ft
	135	MEDIA CENTER 2208	ASSUMED			1500 Sq Ft
	189	ROOM 3209	ASSUMED			250 Sq Ft
	193	ROOM 3210	ASSUMED			750 Sq Ft
	198	ROOM 3211	ASSUMED			364 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	202	ROOM 3101	ASSUMED			750 Sq Ft
	208	ROOM 3102	ASSUMED			750 Sq Ft
	212	ROOM 3105	ASSUMED			750 Sq Ft
	216	ROOM 3103	ASSUMED			750 Sq Ft
	220	ROOM 3104	ASSUMED			750 Sq Ft
<b>SOB</b>	<b>Wood Floor Felt / Vapor Barrier 1924 Addition</b>					<b>Total Amount - 4130 Sq Ft</b>
	64	ROOM 1204	ASSUMED			350 Sq Ft
	66	ROOM 1208	ASSUMED			750 Sq Ft
	72	ROOM 1205	ASSUMED			240 Sq Ft
	136	MEDIA CENTER 2208	ASSUMED			450 Sq Ft
	143	ROOM 2203	ASSUMED			750 Sq Ft
	144	SERVER ROOM 2207	ASSUMED			90 Sq Ft
	183	ROOM 3203	ASSUMED			750 Sq Ft
	186	ROOM 3208	ASSUMED			750 Sq Ft
<b>VOA</b>	<b>Sink Undercoating Gray</b>					<b>Total Amount - 112 Sq Ft</b>
	26	ROOM 1105	NONE DETECTED			6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	29	ROOM 1104	NONE DETECTED			6 Sq Ft
	32	ROOM 1103	NONE DETECTED			6 Sq Ft
	36	ROOM 1102	NONE DETECTED			6 Sq Ft
	42	ROOM 1101	NONE DETECTED			6 Sq Ft
	45	MAIN OFFICE 1001	NONE DETECTED			4 Sq Ft
	53	NURSE'S OFFICE 1004	NONE DETECTED			6 Sq Ft
	69	ROOM 1208	NONE DETECTED	020810ML-07		6 Sq Ft
	81	ROOM 1207	NONE DETECTED			6 Sq Ft
	84	ROOM 1206	NONE DETECTED			6 Sq Ft
	113	ROOM 2105	NONE DETECTED			16 Sq Ft
	128	ROOM 2201	NONE DETECTED			8 Sq Ft
	139	MEDIA CENTER OFFICE 2209	NONE DETECTED			4 Sq Ft
	150	ROOM 2205	NONE DETECTED			4 Sq Ft
	154	ROOM 2204	NONE DETECTED			10 Sq Ft
	168	ROOM 3207	NONE DETECTED			6 Sq Ft
	180	ROOM 3204	NONE DETECTED			6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOA	Miscellaneous Material Black Damp Proofing					<b>Total Amount - 2 Sq Ft</b>
	15	ELEVATOR MECHANICAL ROOM 1203	15 CH	020810ML-05		2 Sq Ft
XOB	Miscellaneous Material Wood Frame Chalkboard Adhesive (1922)					<b>Total Amount - 190 Sq Ft</b>
	40	ROOM 1101	ASSUMED			10 Sq Ft
	101	ROOM 2104	ASSUMED			10 Sq Ft
	106	ROOM 2103	ASSUMED			20 Sq Ft
	111	ROOM 2105	ASSUMED			15 Sq Ft
	116	ROOM 2102	ASSUMED			20 Sq Ft
	122	ROOM 2101	ASSUMED			20 Sq Ft
	194	ROOM 3210	ASSUMED			20 Sq Ft
	203	ROOM 3101	ASSUMED			20 Sq Ft
	209	ROOM 3102	ASSUMED			20 Sq Ft
	213	ROOM 3105	ASSUMED			5 Sq Ft
	217	ROOM 3103	ASSUMED			20 Sq Ft
	221	ROOM 3104	ASSUMED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0C	Miscellaneous Material Wood Frame Corkboard Adhesive (1922)					<b>Total Amount - 2072 Sq Ft</b>
	25	ROOM 1105	ASSUMED			60 Sq Ft
	33	ROOM 1103	ASSUMED			5 Sq Ft
	37	ROOM 1102	ASSUMED			2 Sq Ft
	41	ROOM 1101	ASSUMED			50 Sq Ft
	99	THROUGHOUT 2ND FLOOR HALLWAY	ASSUMED			5 Sq Ft
	102	ROOM 2104	ASSUMED			60 Sq Ft
	107	ROOM 2103	ASSUMED			230 Sq Ft
	112	ROOM 2105	ASSUMED			60 Sq Ft
	117	ROOM 2102	ASSUMED			230 Sq Ft
	123	ROOM 2101	ASSUMED			230 Sq Ft
	195	ROOM 3210	ASSUMED			230 Sq Ft
	204	ROOM 3101	ASSUMED			230 Sq Ft
	210	ROOM 3102	ASSUMED			230 Sq Ft
	214	ROOM 3105	ASSUMED			180 Sq Ft
	218	ROOM 3103	ASSUMED			230 Sq Ft



Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	222	ROOM 3104	ASSUMED			40 Sq Ft
<b>X0D</b>	<b>Miscellaneous Material Brown Ductwork Seam Caulk</b>					<b>Total Amount - 200 Sq Ft</b>
	2	THROUGHOUT BUILDING	NONE DETECTED	020810ML-10	ML-10: MEDIA CENTER.	200 Sq Ft
<b>X0E</b>	<b>Miscellaneous Material Wood Frame Corkboard Adhesive (1924)</b>					<b>Total Amount - 400 Sq Ft</b>
	63	ROOM 1204	ASSUMED			60 Sq Ft
	68	ROOM 1208	ASSUMED			230 Sq Ft
	74	ROOM 1205	ASSUMED			30 Sq Ft
	141	ROOM 2203	ASSUMED			80 Sq Ft
<b>X0F</b>	<b>Miscellaneous Material Red Fire Stop</b>					<b>Total Amount - 100 Sq Ft</b>
	4	THROUGHOUT BUILDING	NONE DETECTED	020810ML-24	ML-24: ROOM 1205.	100 Sq Ft
<b>X0G</b>	<b>Miscellaneous Material AHU Seam Tar (1991)</b>					<b>Total Amount - 10 Sq Ft</b>
	132	1991 MECHANICAL ROOM 2201B	NONE DETECTED	020810ML-27		10 Sq Ft
<b>X0H</b>	<b>Miscellaneous Material Gray Duct Caulk</b>					<b>Total Amount - 100 Sq Ft</b>
	3	THROUGHOUT BUILDING	NONE DETECTED	020810ML-30	ML-30: 3RD FLOOR HALLWAY.	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOI	Miscellaneous Material Wood Frame Chalkboard Adhesive (1924)					<b>Total Amount - 60 Sq Ft</b>
	62	ROOM 1204	ASSUMED			15 Sq Ft
	67	ROOM 1208	ASSUMED			20 Sq Ft
	73	ROOM 1205	ASSUMED			5 Sq Ft
	140	ROOM 2203	ASSUMED			20 Sq Ft
XOJ	Miscellaneous Material Wired Window Glaze					<b>Total Amount - 50 Sq Ft</b>
	5	THROUGHOUT BUILDING	3 CH	081012ML-02	ROOM 3203	50 Sq Ft
XOK	Miscellaneous Material Stone Panel Adhesive					<b>Total Amount - 280 Sq Ft</b>
	119	GIRLS' RESTROOM 2106	ASSUMED			80 Sq Ft
	125	BOYS' RESTROOM 2107	ASSUMED			60 Sq Ft
	200	BOYS' RESTROOM 3107	ASSUMED			60 Sq Ft
	206	GIRLS' RESTROOM 3106	ASSUMED			80 Sq Ft
X1A	Miscellaneous Material 6" X 6" Beige Ceramic Wall Tile System					<b>Total Amount - 1080 Sq Ft</b>
	19	BOYS' RESTROOM 1107	ASSUMED			540 Sq Ft
	21	GIRLS' RESTROOM 1106	ASSUMED			540 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1B	Miscellaneous Material	2" X 2" Tan Ceramic Floor Tile System				<b>Total Amount - 336 Sq Ft</b>
	20	BOYS' RESTROOM 1107	ASSUMED			168 Sq Ft
	22	GIRLS' RESTROOM 1106	ASSUMED			168 Sq Ft