

1000 Walsh Street, Saint Paul, MN 55106

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2B Mudded Pipe Joints on Millboard Insulation 1937 Addition						Total Amount - 20 Joints
	170	AUDITORIUM 2104	ASSUMED			20 Joints
A4A Mudded Pipe Joints on Fiberglass Insulation Unknown Installation						Total Amount - 2 Joints
	52	1925 ORIGINAL BUILDING NORTHEAST STAIRWELL 1299A	NONE DETECTED	081012ML-01	ON LANDINGS FEEDING RADIATOR BETWEEN FLOORS.	2 Joints
A4C Mudded Pipe Joints on Fiberglass Insulation 1965 Addition						Total Amount - 23 Joints
	225	CHASE WALLS FOR BOYS' & GIRLS' SHOWERS	ASSUMED			20 Joints
	226	BOYS' LOCKER ROOM TOILET/URINAL PIPE CHASE	ASSUMED			3 Joints
B2B Millboard Pipe Insulation 1937 Addition						Total Amount - 160 Lin Ft
	169	AUDITORIUM 2104	ASSUMED			160 Lin Ft
C2A Water Tank Insulation Fiberglass						Total Amount - 40 Sq Ft
	23	MECHANICAL ROOM 0304	NSM			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D1A	Boiler Gaskets White					Total Amount - 8 Sq Ft
	10	BOILER ROOM 0300	NONE DETECTED	121708ML-01		8 Sq Ft
D2A	Interior Boiler Insulation Burner Refractory					Total Amount - 4 Sq Ft
	11	BOILER ROOM 0300	ASSUMED			4 Sq Ft
F2A	Exterior Duct Insulation Hard Seams					Total Amount - 2000 Sq Ft
	241	1965 ADDITION FAN ROOM (1401A) NORTH OF GYMNASIUM	NONE DETECTED	2001-1501 AP 11-13	11: MIDDLE OF ROOM. 12: WEST END. 13: EAST END.	2000 Sq Ft
F2B	Exterior Duct Insulation Brown Duct Insulation w/Silver Seam Tape					Total Amount - 1000 Sq Ft
	213	THROUGHOUT 1965 ADDITION	NONE DETECTED	315-1, 2, 3		1000 Sq Ft
H1A	Sprayed-On Structural Fireproofing Blue/Green Spray					Total Amount - 500 Sq Ft
	206	THROUGHOUT 1996 ADDITION	NONE DETECTED	314-4, 5, 6	STORAGE ROOM 1314A.	500 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Pockmarks & Gouges					Total Amount - 6825 Sq Ft
	94	CAFETERIA 1102	NONE DETECTED	121708ML-10; 010209ML-01		3600 Sq Ft
	171	AUDITORIUM 2104	NONE DETECTED	121708ML-71		2400 Sq Ft
	195	ROOM 3312	NONE DETECTED	121708ML-56		825 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I1C	1' x 1' Acoustical Ceiling Tile Fissured (1925)					Total Amount - 4330 Sq Ft
	40	STAFF LOUNGE 1205	NONE DETECTED	121708ML-18		530 Sq Ft
	44	MEDIA CENTER 1204	NONE DETECTED	211-A6A		1200 Sq Ft
	48	MEDIA CENTER STORAGE 1203	NONE DETECTED			500 Sq Ft
	59	ROOM 2205	NONE DETECTED			1050 Sq Ft
	66	ROOM 2206	NONE DETECTED			1050 Sq Ft
I1D	1' x 1' Acoustical Ceiling Tile Vinyl-Paper Coated w/Gray Flecks					Total Amount - 50 Sq Ft
	46	MEDIA CENTER 1204	NONE DETECTED	121708ML-19		50 Sq Ft
I1E	1' x 1' Acoustical Ceiling Tile Large & Medium Random Hole Pattern					Total Amount - 950 Sq Ft
	34	THROUGHOUT MAIN OFFICE 1000	NONE DETECTED	211-A9A		950 Sq Ft
I1F	1' x 1' Acoustical Ceiling Tile Nail & Pin Holes in Concentric Circles					Total Amount - 200 Sq Ft
	56	2ND FLOOR HALLWAY BETWEEN ROOMS 2205 & 2206	NONE DETECTED	121708ML-34		200 Sq Ft
I1G	1' x 1' Acoustical Ceiling Tile Fissured (1965)					Total Amount - 400 Sq Ft
	211	HALLWAY LINK FROM 1937 ADDITION TO 1965 ADDITION	NONE DETECTED	121708ML-58		400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2A	2' x 2' Acoustical Ceiling Tile Rough Texture w/Revealed Edge					Total Amount - 8360 Sq Ft
	82	ROOM 3202	NONE DETECTED			920 Sq Ft
	86	PREP ROOM 3102 BETWEEN ROOMS 3202 & 3104	NONE DETECTED			240 Sq Ft
	218	1965 ADDITION GYMNASIUM 0401	NONE DETECTED	211-A10A; 315-7	315-7: MAINTENANCE OFFICE (0303) (SINCE REMOVED).	7200 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Light Texture					Total Amount - 100 Sq Ft
	205	THROUGHOUT 1996 ADDITION	NONE DETECTED	121708ML-41	ML-41: 3RD FLOOR ELEVATOR LOBBY.	100 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Nail & Pin Holes in Clusters					Total Amount - 14000 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED			4000 Sq Ft
	103	NURSE'S OFFICE AREA	NONE DETECTED	2001-0701-BF-1	BF-1: OLD LIBRARY.	600 Sq Ft
	217	THROUGHOUT 1965 ADDITION GROUND FLOOR & 1ST FLOOR HALLWAYS	NONE DETECTED	211-A11A		5000 Sq Ft
	249	ROOM 1403	NONE DETECTED			1100 Sq Ft
	252	ROOM 1405	NONE DETECTED	121708ML-46		1100 Sq Ft
	257	ROOM 1407	NONE DETECTED			1100 Sq Ft
	261	ROOM 1409	NONE DETECTED			1100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2D	2' x 2' Acoustical Ceiling Tile Grubs, Dents & Pin Holes					Total Amount - 3340 Sq Ft
	25	MAINTENANCE OFFICE 0303	NONE DETECTED			400 Sq Ft
	243	AUXILIARY GYMNASIUM (1402)	NONE DETECTED	121708ML-50		1440 Sq Ft
	245	AUXILIARY GYMNASIUM (1420)	NONE DETECTED			1000 Sq Ft
	247	CLASSROOM 1422	NONE DETECTED			500 Sq Ft
I3B	2' x 4' Ceiling Tile 2' x 2'-Look Grubs w/Pin Holes w/Revealed Edge					Total Amount - 20000 Sq Ft
	91	THROUGHOUT 1937 ADDITION	NONE DETECTED	121708ML-28		20000 Sq Ft
I3C	2' x 4' Ceiling Tile Textured w/Pin Holes					Total Amount - 10000 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	121708ML-15		10000 Sq Ft
J3A	Miscellaneous Cementitious Material Black Science Table Top					Total Amount - 730 Sq Ft
	84	ROOM 3202	NONE DETECTED	121708ML-40		300 Sq Ft
	88	PREP ROOM 3102	NONE DETECTED			80 Sq Ft
	165	ROOM 2102	NONE DETECTED			50 Sq Ft
	178	ROOM 3104	NONE DETECTED			300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3B		Miscellaneous Cementitious Material Black Fume Hood Base				Total Amount - 6 Sq Ft
	85	ROOM 3202	ASSUMED			6 Sq Ft
K0A		9" x 9" Vinyl Floor Tile & Mastic Cream w/White Streaks				Total Amount - 3020 Sq Ft
	58	2ND FLOOR HALLWAY BETWEEN ROOMS 2205 & 2206	8 CH (TILE), 3 CH (MASTIC)			200 Sq Ft
	61	ROOM 2205	8 CH (TILE), 3 CH (MASTIC)	121708ML-57		1050 Sq Ft
	65	ROOMS 2207 & 2208	8 CH (TILE), 3 CH (MASTIC)			720 Sq Ft
	68	ROOM 2206	8 CH (TILE), 3 CH (MASTIC)			1050 Sq Ft
K0F		9" x 9" Vinyl Floor Tile & Mastic White w/Gray Streaks				Total Amount - 8000 Sq Ft
	244	AUXILIARY GYMNASIUM (1402)	8 CH (TILE), 15 CH (MASTIC)	315-16		1500 Sq Ft
	246	AUXILIARY GYMNASIUM (1420)	8 CH (TILE), 15 CH (MASTIC)			1000 Sq Ft
	248	CLASSROOM 1422	8 CH (TILE), 15 CH (MASTIC)			500 Sq Ft
	250	ROOM 1403	8 CH (TILE), 15 CH (MASTIC)	2001-1501 AP15		1100 Sq Ft
	251	STORAGE ROOM 1403A	8 CH (TILE), 15 CH (MASTIC)			150 Sq Ft
	253	ROOM 1405	8 CH (TILE), 15 CH (MASTIC)			1100 Sq Ft
	256	STORAGE ROOM 1405A	8 CH (TILE), 15 CH (MASTIC)			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	258	ROOM 1407	8 CH (TILE), 15 CH (MASTIC)			1100 Sq Ft
	260	STORAGE 1407A	8 CH (TILE), 15 CH (MASTIC)			150 Sq Ft
	262	ROOM 1409	8 CH (TILE), 15 CH (MASTIC)			1100 Sq Ft
	264	ROOM 1409A	8 CH (TILE), 15 CH (MASTIC)			150 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Cream w/Brown Streaks					Total Amount - 820 Sq Ft
	20	MECHANICAL ROOM 0301	3 CH (MASTIC)			20 Sq Ft
	32	1925 ORIGINAL BUILDING 1ST FLOOR HALLWAY	3 CH (MASTIC)	310-TB5-A, B, C		800 Sq Ft
K2I	12" x 12" Vinyl Floor Tile & Mastic Light Blue Mottle					Total Amount - 4310 Sq Ft
	96	CAFETERIA 1102	NONE DETECTED	121708ML-11		4100 Sq Ft
	97	OFFICE 1103	NONE DETECTED			105 Sq Ft
	98	STORAGE 1105	NONE DETECTED			105 Sq Ft
K2J	12" x 12" Vinyl Floor Tile & Mastic Blue w/Dark & Light Blue					Total Amount - 2730 Sq Ft
	17	MECHANICAL ROOM 0301	NONE DETECTED			20 Sq Ft
	33	1925 ORIGINAL BUILDING 1ST FLOOR HALLWAY OUTSIDE MEDIA CENTER	NONE DETECTED			150 Sq Ft
	42	STAFF LOUNGE 1205	NONE DETECTED			700 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	50	MEDIA CENTER STORAGE 1203	NONE DETECTED	121708ML-20		500 Sq Ft
	100	ROOM 1006A	NONE DETECTED			100 Sq Ft
	164	ROOM 2102	NONE DETECTED			1000 Sq Ft
	167	ROOM 2102A	NONE DETECTED			260 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Gray w/Brown Specks					Total Amount - 20 Sq Ft
	21	MECHANICAL ROOM 0301	NONE DETECTED			20 Sq Ft
K2L	12" x 12" Vinyl Floor Tile & Mastic Cream w/Brown Smudges					Total Amount - 1420 Sq Ft
	22	MECHANICAL ROOM 0301	NONE DETECTED			20 Sq Ft
	55	1925 ORIGINAL BUILDING 2ND FLOOR HALLWAY	NONE DETECTED			800 Sq Ft
	78	1925 ORIGINAL BUILDING 3RD FLOOR HALLWAY	NONE DETECTED	072015JP-01	JP-01: 3RD FLOOR HALLWAY OUTSIDE STAFF RESTROOM.	600 Sq Ft
K2M	12" x 12" Vinyl Floor Tile & Mastic White w/Black Streaks					Total Amount - 250 Sq Ft
	53	1925 ORIGINAL BUILDING NORTHEAST STAIRWELL 1299A	NONE DETECTED	315-20		250 Sq Ft
K2N	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray & White Streaks					Total Amount - 570 Sq Ft
	16	MECHANICAL ROOM 0301	NONE DETECTED			20 Sq Ft
	79	CUSTODIAL STORAGE 3204	NONE DETECTED	121708ML-38		250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	80	STORAGE ROOMS 3205 & 3205B	NONE DETECTED			300 Sq Ft
K2O	12" x 12" Vinyl Floor Tile & Mastic Blue w/Dark Blue Specks					Total Amount - 2120 Sq Ft
	19	MECHANICAL ROOM 0301	NONE DETECTED			40 Sq Ft
	83	ROOM 3202	NONE DETECTED	121708ML-39		920 Sq Ft
	87	PREP ROOM 3102	NONE DETECTED			240 Sq Ft
	177	ROOM 3104	NONE DETECTED			920 Sq Ft
K2P	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray & White Blotches					Total Amount - 616 Sq Ft
	18	MECHANICAL ROOM 0301	NONE DETECTED			20 Sq Ft
	133	ELEVATOR LOBBY 2399B	NONE DETECTED			48 Sq Ft
	201	ROOM 3399B ELEVATOR LOBBY	NONE DETECTED			48 Sq Ft
	207	THROUGHOUT 1996 ADDITION	NONE DETECTED	121708ML-42		400 Sq Ft
	239	1996 ADDITION GROUND FLOOR HALLWAY TO ELEVATOR	NONE DETECTED			100 Sq Ft
K2Q	12" x 12" Vinyl Floor Tile & Mastic Black w/White Smudges					Total Amount - 216 Sq Ft
	134	ELEVATOR LOBBY 2399B	NONE DETECTED			48 Sq Ft
	202	ROOM 3399B ELEVATOR LOBBY	NONE DETECTED			48 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	208	THROUGHOUT 1996 ADDITION	NONE DETECTED	315-25		100 Sq Ft
	240	1996 ADDITION GROUND FLOOR HALLWAY TO ELEVATOR	NONE DETECTED			20 Sq Ft
K2R	12" x 12" Vinyl Floor Tile & Mastic Green Mottle					Total Amount - 360 Sq Ft
	232	ROOM 0406	NONE DETECTED			70 Sq Ft
	236	ROOM 0406A	NONE DETECTED			120 Sq Ft
	237	ROOM 0406B	NONE DETECTED			70 Sq Ft
	238	ROOM 0406C	NONE DETECTED	121708ML-48		100 Sq Ft
K2S	12" x 12" Vinyl Floor Tile & Mastic Gray w/Multi-Colored					Total Amount - 80 Sq Ft
	15	MECHANICAL ROOM 0301	NONE DETECTED			20 Sq Ft
	210	ELEVATOR	NONE DETECTED	513-8		60 Sq Ft
K3A	Miscellaneous Flooring Brown Stair Treads					Total Amount - 30 Sq Ft
	54	1925 ORIGINAL BUILDING NORTHEAST STAIRWELL 1299A	3 CH (TREAD ONLY)	121708ML-37		30 Sq Ft
K3B	Miscellaneous Flooring 2' X 2' Blue with Beige Flecks Rubber (2020)					Total Amount - 1726 Sq Ft
	72	ROOM 2202 (NORTH)	NEW			400 Sq Ft
	74	ROOM 2202A (SOUTH)	NEW			726 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	105	NURSE'S OFFICE AREA	NEW			600 Sq Ft
K3C		Miscellaneous Flooring Gray with Red & White Flakes Epoxy Flooring				Total Amount - 400 Sq Ft
	26	MAINTENANCE OFFICE 0303	NSM			400 Sq Ft
K3D		Miscellaneous Flooring Cream w/Black & Blue Flakes Epoxy Flooring				Total Amount - 200 Sq Ft
	129	ROOM 1314	NEW			200 Sq Ft
L0A		Flexible Duct Connector White Fabric				Total Amount - 10 Sq Ft
	175	STAGE FAN ROOMS	NONE DETECTED	121708ML-70		10 Sq Ft
L0B		Flexible Duct Connector Gray Cloth				Total Amount - 13 Sq Ft
	228	FLIGHT SIMULATOR ROOM 0408	NONE DETECTED			2 Sq Ft
	234	ROOM 0406	NONE DETECTED			3 Sq Ft
	242	1965 ADDITION FAN ROOM (1401A) NORTH OF GYMNASIUM	NONE DETECTED	2001-01111-5		8 Sq Ft
L0C		Flexible Duct Connector Green Canvas				Total Amount - 2 Sq Ft
	14	MECHANICAL ROOM 0301	NONE DETECTED	2001-1901-BF-4		2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
LOD	Flexible Duct Connector Black Vinyl					Total Amount - 8 Sq Ft
	12	BOILER ROOM 0300	NSM			4 Sq Ft
	37	ROOM 1304A	NSM			2 Sq Ft
	77	SERVER ROOM 2304A	NSM			2 Sq Ft
M0A	Plaster 1925 Original Building					Total Amount - 10000 Sq Ft
	29	THROUGHOUT 1925 ORIGINAL BUILDING	NONE DETECTED	121708ML-60, 61, 62, 63, 64; 511P2; 315-9		10000 Sq Ft
M0B	Plaster 1937 Addition					Total Amount - 10000 Sq Ft
	90	THROUGHOUT 1937 ADDITION	NONE DETECTED	121708ML-51, 65, 66, 67, 68, 69; 315-10		10000 Sq Ft
M0C	Plaster 1965 Addition					Total Amount - 4000 Sq Ft
	212	THROUGHOUT 1965 ADDITION	NONE DETECTED	121708ML-52, 53, 54, 55; 2001-1501-AP-10	AP-10: NORTH WALL BOYS' LOCKER ROOM.	4000 Sq Ft
M0D	Plaster Textured Skim Coat					Total Amount - 200 Sq Ft
	28	STAIRWELL OUTSIDE CUSTODIAL OFFICE	NONE DETECTED	121708ML-02, 03, 04		200 Sq Ft
M0E	Plaster Decorative Plaster Soffit (1937 Addition)					Total Amount - 1000 Sq Ft
	168	AUDITORIUM 2104	NONE DETECTED	111915ML-04, 05, 06	ML-04,05,06: AUDITORIUM.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
NOA	Drywall/Joint Compound					Total Amount - 10000 Sq Ft
1	THROUGHOUT BUILDING	NONE DETECTED	315-23; 511-P3, P4	315-23: MAIN OFFICE AREA.	10000 Sq Ft	
POC	Fire Doors Fiberglass					Total Amount - 20 Sq Ft
13	MECHANICAL ROOM 0301	NSM			20 Sq Ft	
POD	Fire Doors Pieced Metal -Wood Core					Total Amount - 20 Sq Ft
24	MECHANICAL ROOM 0304	NSM			20 Sq Ft	
POE	Fire Doors Hollow Metal -Unrated (Mesker)					Total Amount - 20 Sq Ft
132	MECHANICAL ROOM 1314A	NSM			20 Sq Ft	
Q0B	Carpet Adhesive Blue w/Multi-Colored Streaks Carpet					Total Amount - 8000 Sq Ft
4	THROUGHOUT BUILDING	NONE DETECTED	121708ML-13		8000 Sq Ft	
Q0C	Carpet Adhesive Blue, Gray & Tan Berber Carpet					Total Amount - 2525 Sq Ft
62	ROOM 2205	NONE DETECTED			1050 Sq Ft	
107	ROOM 1306	NONE DETECTED	121708ML-25		575 Sq Ft	
180	ROOM 3303	NONE DETECTED			900 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0D	Carpet Adhesive Red Berber Carpet					Total Amount - 1050 Sq Ft
69	ROOM 2206	NONE DETECTED	121708ML-36		1050 Sq Ft	
Q0E	Carpet Adhesive Green Berber Carpet					Total Amount - 400 Sq Ft
233	ROOM 0406	NONE DETECTED	121708ML-49		400 Sq Ft	
Q0G	Carpet Adhesive Blue Berber Carpet					Total Amount - 960 Sq Ft
135	ROOM 2312	NONE DETECTED	121708ML-32		960 Sq Ft	
ROA	Baseboard/Mopboard Adhesive 4" Gray Baseboard					Total Amount - 300 Sq Ft
5	THROUGHOUT BUILDING	NONE DETECTED	121708ML-12		300 Sq Ft	
ROB	Baseboard/Mopboard Adhesive 4" Brown Baseboard					Total Amount - 200 Sq Ft
6	THROUGHOUT BUILDING	NONE DETECTED	121708ML-14		200 Sq Ft	
ROC	Baseboard/Mopboard Adhesive 4" Dark Blue Baseboard					Total Amount - 100 Sq Ft
7	THROUGHOUT BUILDING	NONE DETECTED	121708ML-22		100 Sq Ft	
ROE	Baseboard/Mopboard Adhesive 6" Tan Baseboard					Total Amount - 20 Sq Ft
111	ROOM 1307	NONE DETECTED	121708ML-26		20 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROF		Baseboard/Mopboard Adhesive 6" Black Baseboard			Total Amount - 60 Sq Ft	
117	ROOM 1311	NONE DETECTED	121708ML-29		20 Sq Ft	
136	ROOM 2312	NONE DETECTED	121708ML-31		40 Sq Ft	
ROH		Baseboard/Mopboard Adhesive 4" Tan Baseboard			Total Amount - 20 Sq Ft	
63	ROOM 2205	NONE DETECTED	121708ML-35		20 Sq Ft	
ROI		Baseboard/Mopboard Adhesive 4" Black Baseboard (1996)			Total Amount - 100 Sq Ft	
209	THROUGHOUT 1996 ADDITION	NONE DETECTED	121708ML-43	ML-43: 3RD FLOOR ELEVATOR LOBBY.	100 Sq Ft	
ROJ		Baseboard/Mopboard Adhesive 6" Gray (2017)			Total Amount - 330 Sq Ft	
73	ROOM 2202 (NORTH)	NEW			40 Sq Ft	
75	ROOM 2202A (SOUTH)	NEW			70 Sq Ft	
216	THROUGHOUT 1965 ADDITION HALLWAYS	NEW			100 Sq Ft	
221	1965 ADDITION GYMNASIUM ENTRANCES	NEW			20 Sq Ft	
223	THROUGHOUT 1965 LOCKER ROOM AREAS	NEW			100 Sq Ft	
ROK		Baseboard/Mopboard Adhesive 4" Black Baseboard			Total Amount - 50 Sq Ft	
108	ROOM 1306	ASSUMED			50 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROL		Baseboard/Mopboard Adhesive 4" Black Angled Baseboard				Total Amount - 600 Sq Ft
	220	1965 ADDITION GYMNASIUM 0401	ASSUMED			600 Sq Ft
ROM		Baseboard/Mopboard Adhesive 6" Gray (2020)				Total Amount - 60 Sq Ft
	106	NURSE'S OFFICE AREA	NEW			60 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier 1925 Original Building				Total Amount - 5480 Sq Ft
	30	THROUGHOUT 1925 ORIGINAL BUILDING	ASSUMED			5000 Sq Ft
	64	ROOM 2205A	ASSUMED			240 Sq Ft
	70	ROOM 2206A	ASSUMED			240 Sq Ft
SOB		Wood Floor Felt / Vapor Barrier 1937 Addition				Total Amount - 5000 Sq Ft
	92	THROUGHOUT 1937 ADDITION	ASSUMED			5000 Sq Ft
SOC		Wood Floor Felt / Vapor Barrier On Grade (1965)				Total Amount - 6000 Sq Ft
	219	1965 ADDITION GYMNASIUM 0401	ASSUMED			6000 Sq Ft
VOA		Sink Undercoating Gray (Old)				Total Amount - 5 Sq Ft
	27	MAINTENANCE OFFICE 0303	NONE DETECTED	121708ML-08		5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOB	Sink Undercoating Gray (New)					Total Amount - 20 Sq Ft
	43	STAFF LOUNGE 1205	NONE DETECTED	121708ML-21		5 Sq Ft
	51	MEDIA CENTER STORAGE 1203	NONE DETECTED			5 Sq Ft
	104	NURSE'S OFFICE AREA	NONE DETECTED			5 Sq Ft
	166	ROOM 2102	NONE DETECTED			5 Sq Ft
VOC	Sink Undercoating Cream					Total Amount - 10 Sq Ft
	71	ROOM 2202 (NORTH)	NONE DETECTED			5 Sq Ft
	76	ROOM 2202A (SOUTH)	NONE DETECTED	121708ML-33		5 Sq Ft
VOD	Sink Undercoating Gray (1965)					Total Amount - 60 Sq Ft
	215	THROUGHOUT 1965 ADDITION	NONE DETECTED	121708ML-47		60 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A					Total Amount - 1830 Sq Ft
	95	CAFETERIA 1102	10 CH	121708ML-10		1025 Sq Ft
	172	AUDITORIUM 2104	10 CH	121708ML-71		600 Sq Ft
	196	ROOM 3312	10 CH	121708ML-56		205 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C					Total Amount - 1165 Sq Ft
	41	STAFF LOUNGE 1205	NONE DETECTED	121708ML-18		130 Sq Ft
	45	MEDIA CENTER 1204	NONE DETECTED			400 Sq Ft
	49	MEDIA CENTER STORAGE 1203	NONE DETECTED			125 Sq Ft
	60	ROOM 2205	NONE DETECTED			250 Sq Ft
	67	ROOM 2206	NONE DETECTED			260 Sq Ft
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1D					Total Amount - 12 Sq Ft
	47	MEDIA CENTER 1204	NONE DETECTED	121708ML-19		12 Sq Ft
W1E	1' x 1' Ceiling Tile Adhesive Associated w/I1E					Total Amount - 240 Sq Ft
	35	THROUGHOUT MAIN OFFICE 1000	NONE DETECTED	121708ML-16		240 Sq Ft
W1F	1' x 1' Ceiling Tile Adhesive Associated w/I1F					Total Amount - 50 Sq Ft
	57	2ND FLOOR HALLWAY BETWEEN ROOMS 2205 & 2206	NONE DETECTED	121708ML-34		50 Sq Ft
X0A	Miscellaneous Material Black Window Sill					Total Amount - 500 Sq Ft
	93	THROUGHOUT 1937 ADDITION	NONE DETECTED	121708ML-05		500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOB	Miscellaneous Material Red Fire Stop					Total Amount - 300 Sq Ft
	8	THROUGHOUT BUILDING	NONE DETECTED	121708ML-17		300 Sq Ft
XOC	Miscellaneous Material Wood Frame Chalkboard Mastic (1937)					Total Amount - 485 Sq Ft
	109	ROOM 1307	NONE DETECTED			10 Sq Ft
	112	ROOM 1309	NONE DETECTED			5 Sq Ft
	118	ROOM 1313	NONE DETECTED			30 Sq Ft
	121	ROOM 1310	NONE DETECTED			15 Sq Ft
	123	ROOM 1315	NONE DETECTED			30 Sq Ft
	126	ROOM 1312	NONE DETECTED	121708ML-07		15 Sq Ft
	137	ROOM 2312	NONE DETECTED			20 Sq Ft
	140	ROOM 2313	NONE DETECTED			15 Sq Ft
	143	ROOM 2310	NONE DETECTED			30 Sq Ft
	146	ROOM 2311	NONE DETECTED			30 Sq Ft
	149	ROOM 2308	NONE DETECTED			10 Sq Ft
	152	ROOM 2309	NONE DETECTED			30 Sq Ft
	155	ROOM 2306	NONE DETECTED			15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	158	ROOM 2307	NONE DETECTED			30 Sq Ft
	181	ROOM 3303	NONE DETECTED			30 Sq Ft
	184	ROOM 3306	NONE DETECTED			10 Sq Ft
	187	ROOM 3305	NONE DETECTED			30 Sq Ft
	189	ROOM 3308	NONE DETECTED			30 Sq Ft
	191	ROOM 3307	NONE DETECTED			30 Sq Ft
	193	ROOM 3310	NONE DETECTED			30 Sq Ft
	197	ROOM 3312	NONE DETECTED			10 Sq Ft
	199	ROOM 3309	NONE DETECTED			30 Sq Ft
XOE	Miscellaneous Material Gray Duct Caulk					Total Amount - 100 Sq Ft
	9	THROUGHOUT BUILDING	NONE DETECTED	121708ML-30	ML-30: ROOM 1311.	100 Sq Ft
XOF	Miscellaneous Material Black Window Sill (1965)					Total Amount - 200 Sq Ft
	214	THROUGHOUT 1965 ADDITION	NONE DETECTED	121708ML-06		200 Sq Ft
XOG	Miscellaneous Material Tectum Panels					Total Amount - 1000 Sq Ft
	229	FLIGHT SIMULATOR ROOM 0408	NONE DETECTED	121708ML-59		1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOH	Miscellaneous Material Corkboard Adhesive (1937)					Total Amount - 1976 Sq Ft
	110	ROOM 1307	ASSUMED			18 Sq Ft
	113	ROOM 1309	ASSUMED			8 Sq Ft
	115	ROOM 1308	ASSUMED			10 Sq Ft
	119	ROOM 1313	ASSUMED			110 Sq Ft
	122	ROOM 1310	ASSUMED			50 Sq Ft
	124	ROOM 1315	ASSUMED			110 Sq Ft
	127	ROOM 1312	ASSUMED			110 Sq Ft
	138	ROOM 2312	ASSUMED			50 Sq Ft
	141	ROOM 2313	ASSUMED			110 Sq Ft
	144	ROOM 2310	ASSUMED			110 Sq Ft
	147	ROOM 2311	ASSUMED			110 Sq Ft
	150	ROOM 2308	ASSUMED			80 Sq Ft
	153	ROOM 2309	ASSUMED			110 Sq Ft
	156	ROOM 2306	ASSUMED			60 Sq Ft
	159	ROOM 2307	ASSUMED			110 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	173	AUDITORIUM STORAGE 2105	ASSUMED			30 Sq Ft
	174	AUDITORIUM STORAGE 2107	ASSUMED			30 Sq Ft
	182	ROOM 3303	ASSUMED			110 Sq Ft
	185	ROOM 3306	ASSUMED			40 Sq Ft
	188	ROOM 3305	ASSUMED			110 Sq Ft
	190	ROOM 3308	ASSUMED			110 Sq Ft
	192	ROOM 3307	ASSUMED			110 Sq Ft
	194	ROOM 3310	ASSUMED			110 Sq Ft
	198	ROOM 3312	ASSUMED			60 Sq Ft
	200	ROOM 3309	ASSUMED			110 Sq Ft
X0I	Miscellaneous Material Metal Frame Chalkboard Adhesive (1965)					Total Amount - 15 Sq Ft
	230	FLIGHT SIMULATOR ROOM 0408	ASSUMED			5 Sq Ft
	235	ROOM 0406	ASSUMED			5 Sq Ft
	254	ROOM 1405	ASSUMED			5 Sq Ft
X0J	Miscellaneous Material Metal Frame Corkboard Adhesive (1965)					Total Amount - 215 Sq Ft
	222	1965 ADDITION GYMNASIUM ENTRANCES	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	231	FLIGHT SIMULATOR ROOM 0408	ASSUMED			25 Sq Ft
	255	ROOM 1405	ASSUMED			80 Sq Ft
	259	ROOM 1407	ASSUMED			60 Sq Ft
	263	ROOM 1409	ASSUMED			30 Sq Ft
XOK	Miscellaneous Material Thin Metal Frame Corkboard Adhesive					Total Amount - 105 Sq Ft
	114	ROOM 1308	ASSUMED			100 Sq Ft
	204	OFFICE 3399	ASSUMED			5 Sq Ft
XOL	Miscellaneous Material Wood Frame Corkboard Adhesive (1937)					Total Amount - 113 Sq Ft
	99	ROOM 1006	ASSUMED			2 Sq Ft
	116	ROOM 1308	ASSUMED			5 Sq Ft
	120	ROOM 1313	ASSUMED			3 Sq Ft
	125	ROOM 1315	ASSUMED			5 Sq Ft
	128	ROOM 1312	ASSUMED			5 Sq Ft
	139	ROOM 2312	ASSUMED			5 Sq Ft
	142	ROOM 2313	ASSUMED			5 Sq Ft
	145	ROOM 2310	ASSUMED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	148	ROOM 2311	ASSUMED			5 Sq Ft
	151	ROOM 2308	ASSUMED			5 Sq Ft
	154	ROOM 2309	ASSUMED			5 Sq Ft
	157	ROOM 2306	ASSUMED			5 Sq Ft
	160	ROOM 2307	ASSUMED			5 Sq Ft
	161	ROOM 2303	ASSUMED			20 Sq Ft
	162	ROOM 2305	ASSUMED			5 Sq Ft
	176	ROOM 3103	ASSUMED			3 Sq Ft
	183	ROOM 3303	ASSUMED			5 Sq Ft
	186	ROOM 3306	ASSUMED			10 Sq Ft
	203	STAIRWELL 1399A	ASSUMED			10 Sq Ft
X0M	Miscellaneous Material Stone Panel Adhesive (1925)					Total Amount - 60 Sq Ft
	36	BOYS' RESTROOM 1302	ASSUMED			20 Sq Ft
	81	STAFF RESTROOM 3203 SOUTH OF 1925 ORIGINAL BUILDING STAIRWELL	ASSUMED			20 Sq Ft
	89	BOYS' RESTROOM 3302	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0N	Miscellaneous Material Stone Panel Adhesive (1937)					Total Amount - 80 Sq Ft
	163	GIRLS' RESTROOM 2102	ASSUMED			40 Sq Ft
	179	GIRLS' RESTROOM 3101	ASSUMED			40 Sq Ft
X1A	Miscellaneous Material 2" X 2" Gray with White Specks Ceramic Floor Tile System (2020)					Total Amount - 60 Sq Ft
	101	NURSE'S OFFICE RESTROOM 1303A	NEW			60 Sq Ft
X1B	Miscellaneous Material 1" Beige & Blue Ceramic Floor Tile System					Total Amount - 80 Sq Ft
	39	STAFF RESTROOM 1202 ACROSS FROM MAIN OFFICE 1001	ASSUMED			80 Sq Ft
X1C	Miscellaneous Material 6" X 6" Red Quarry Tile System					Total Amount - 500 Sq Ft
	31	1925 ORIGINAL BUILDING ENTRANCES	ASSUMED			500 Sq Ft
X1D	Miscellaneous Material 2" X 2" Taupe Ceramic Floor Tile System					Total Amount - 40 Sq Ft
	131	RESTROOM 1314B	ASSUMED			40 Sq Ft
X1E	Miscellaneous Material 1" X 1" Light Gray Ceramic Floor Tile System (1965)					Total Amount - 1500 Sq Ft
	224	THROUGHOUT 1965 LOCKER ROOM AREAS	ASSUMED			1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1F		Miscellaneous Material 1" X 1" Beige Ceramic Floor Tile System (1965)				Total Amount - 1000 Sq Ft
	227	RESTROOMS 0407 & 0410	ASSUMED			500 Sq Ft
	265	1965 ADDITION RESTROOMS 1404 & 1408	ASSUMED			500 Sq Ft
X2A		Miscellaneous Material 4" X 4" Gray Ceramic Wall Tile System (2020)				Total Amount - 100 Sq Ft
	102	NURSE'S OFFICE RESTROOM 1303A	NEW			100 Sq Ft
X2B		Miscellaneous Material 4" X 4" Beige Ceramic Wall Tile System				Total Amount - 200 Sq Ft
	38	STAFF RESTROOM 1202 ACROSS FROM MAIN OFFICE 1001	ASSUMED			100 Sq Ft
	130	RESTROOM 1314B	ASSUMED			100 Sq Ft