

1023 Osceola Avenue, Saint Paul, MN 55105

**Chart C - All Materials List**

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B1A	Air Cell Pipe Insulation 1922 Original Building					<b>Total Amount - 12 Lin Ft</b>
15	MAINTENANCE OFFICE (0101)	30 CH	206G1A, 207G1A		12 Lin Ft	
B2A	Millboard Pipe Insulation 1922 Original Building					<b>Total Amount - 6 Lin Ft</b>
16	MAINTENANCE OFFICE (0101)	ASSUMED			6 Lin Ft	
I2A	2' x 2' Acoustical Ceiling Tile Dents w/Pin Holes (2018)					<b>Total Amount - 26000 Sq Ft</b>
2	THROUGHOUT BUILDING	NEW			26000 Sq Ft	
I2B	2' x 2' Acoustical Ceiling Tile Lightly Textured w/Revealed Edge (2018)					<b>Total Amount - 10000 Sq Ft</b>
3	THROUGHOUT BUILDING	NEW			10000 Sq Ft	
K1D	Sheet Vinyl Flooring & Adhesive Brown w/Dark & Light Brown Specks (2012)					<b>Total Amount - 2500 Sq Ft</b>
26	2ND FLOOR HALLWAY 2100 & 2200 FROM ROOM 2109 TO ELEVATOR	NEW			1500 Sq Ft	
33	3RD FLOOR HALLWAYS 3100 & 3200 FROM ROOMS 3109-3206	NEW			1000 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2A	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (1996)					<b>Total Amount - 30 Sq Ft</b>
	24	ELEVATOR	NONE DETECTED	122717-BF-6; 030309-MA-35	BF-6: SOUTHWEST STAIRWELL. MA-35: STORAGE ROOM 1206 (SINCE REMOVED)	30 Sq Ft
K3A	Miscellaneous Flooring 2' X 2' Rubber (2018)					<b>Total Amount - 15000 Sq Ft</b>
	5	THROUGHOUT BUILDING	NEW			15000 Sq Ft
M0A	Plaster 1922 Original Building					<b>Total Amount - 10000 Sq Ft</b>
	13	THROUGHOUT 1922 ORIGINAL BUILDING	NONE DETECTED	122717-BF-7, 22; 030309-MA-18, 19, 20, 21; 510N-4, 5, 6	BF-7: ROOM 1109. BF-22: ROOM 3204. N4,5: LIBRARY OFFICE. N6: 1ST FLOOR EAST ENTRANCE. MA-18: ROOM 3106A. MA-19: ROOM 3106C. MA-20: ROOM 2107. MA-21: MAIN OFFICES.	10000 Sq Ft
M0B	Plaster 1924 Addition					<b>Total Amount - 4000 Sq Ft</b>
	22	THROUGHOUT 1924 ADDITION	NONE DETECTED	122717-BF-21; 030309-MA-28, 29, 30, 31, 32	BF-21: HALLWAY NEAR ROOM 3201. MA-28: ROOM 1204. MA-29: ROOM 2204. MA-30: ROOM 2201. MA-31: ROOM 3201. MA-32: ROOM 3206.	4000 Sq Ft
N0A	Drywall/Joint Compound					<b>Total Amount - 2000 Sq Ft</b>
	1	THROUGHOUT BUILDING	NONE DETECTED	510N1, 510N2, 510N3		2000 Sq Ft
P0A	Fire Doors Pieced Metal					<b>Total Amount - 20 Sq Ft</b>
	17	MECHANICAL ROOM (0102)	NSM			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0A	Carpet Adhesive Striped Carpet Squares (2018)					<b>Total Amount - 15000 Sq Ft</b>
	4	THROUGHOUT BUILDING	NEW			15000 Sq Ft
R0A	Baseboard/Mopboard Adhesive 4" Gray (2018)					<b>Total Amount - 1000 Sq Ft</b>
	6	THROUGHOUT BUILDING	NEW			1000 Sq Ft
S0A	Wood Floor Felt / Vapor Barrier 1922 Original Building (On-Grade)					<b>Total Amount - 3000 Sq Ft</b>
	18	THROUGHOUT 1922 ORIGINAL BUILDING 1ST FLOOR	NONE DETECTED	101617-BF-1	BF-1: ROOM 1109A.	3000 Sq Ft
S0AA	Wood Floor Felt / Vapor Barrier 1922 Original Building (Elevated)					<b>Total Amount - 6000 Sq Ft</b>
	25	THROUGHOUT 1922 ORIGINAL BUILDING 2ND FLOOR ROOMS	NONE DETECTED	101617-BF-2	BF-2: ROOM 2107.	3000 Sq Ft
	34	THROUGHOUT 1922 ORIGINAL BUILDING 3RD FLOOR ROOMS	NONE DETECTED			3000 Sq Ft
S0B	Wood Floor Felt / Vapor Barrier 1924 Addition (On-Grade)					<b>Total Amount - 1500 Sq Ft</b>
	23	THROUGHOUT 1924 ADDITION 1ST FLOOR ROOMS	NONE DETECTED	101617-BF-3	BF-3: ROOM 1204.	1500 Sq Ft
S0BB	Wood Floor Felt / Vapor Barrier 1924 Addition (Elevated)					<b>Total Amount - 3000 Sq Ft</b>
	32	THROUGHOUT 1924 ADDITION 2ND FLOOR ROOMS	NONE DETECTED	101617-BF-4	BF-4: ROOM 2204.	1500 Sq Ft
	35	THROUGHOUT 1924 ADDITION 3RD FLOOR ROOMS	NONE DETECTED			1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0D		Miscellaneous Material Wood Frame Chalkboard Adhesive (1922)			<b>Total Amount - 60 Sq Ft</b>	
	28	MEDIA CENTER 2108	ASSUMED			20 Sq Ft
	30	ROOM 2104	ASSUMED			20 Sq Ft
	36	ROOM 3106	ASSUMED			20 Sq Ft
X0F		Miscellaneous Material Wired Window Glaze			<b>Total Amount - 6 Sq Ft</b>	
	19	NORTH STAIRWELL	NONE DETECTED	030309-MA-37	MA-37: HALLWAY 2200 OUTSIDE ROOM 2204 (SINCE REMOVED).	6 Sq Ft
X0H		Miscellaneous Material Wood Frame Brown Corkboard Adhesive (1922)			<b>Total Amount - 145 Sq Ft</b>	
	27	ROOM 2109	NONE DETECTED	122717-BF-8, 12, 17	BF-8: HALLWAY NEAR ROOM 1107 (SINCE REMOVED). BF-12: HALLWAY NEAR ROOM 2202 (SINCE REMOVED). BF-17: ROOM 2107.	10 Sq Ft
	29	MEDIA CENTER 2108	NONE DETECTED	122717-BF-28	BF-28: ROOM 3110 (SINCE REMOVED).	90 Sq Ft
	31	ROOM 2104	NONE DETECTED			15 Sq Ft
	37	ROOM 3106	NONE DETECTED	122717-BF-28	BF-28: ROOM 3110 (SINCE REMOVED).	30 Sq Ft
X0K		Miscellaneous Material Vermiculite			<b>Total Amount - 5000 Sq Ft</b>	
	20	THROUGHOUT 1966 ADDITION	<1 ACT	070617BV-01, 02, 03	BV-01,02,03: GYMNASIUM.	5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0L	Miscellaneous Material Black Wall Dampproofing					<b>Total Amount - 800 Sq Ft</b>
14	THROUGHOUT 1922 ORIGINAL BUILDING	NONE DETECTED	061318-ID-01	ID-01: 2ND FLOOR RESTROOM 2103.	800 Sq Ft	
X1A	Miscellaneous Material 6" Light Brown Quarry Tile					<b>Total Amount - 800 Sq Ft</b>
21	ROOM 1201	NONE DETECTED	122717-BF-5	BF-5: KITCHEN.	800 Sq Ft	
X1B	Miscellaneous Material 1' X 2' Marble Look Ceramic Wall Tile System (2018)					<b>Total Amount - 10000 Sq Ft</b>
7	THROUGHOUT BUILDING	NEW			10000 Sq Ft	
X1C	Miscellaneous Material 1" X 2" Gray Ceramic Wall Tile System (2018)					<b>Total Amount - 1000 Sq Ft</b>
8	THROUGHOUT BUILDING	NEW			1000 Sq Ft	
X1D	Miscellaneous Material 2" X 2" Gray w/White Specks Ceramic Floor Tile System (2018)					<b>Total Amount - 5000 Sq Ft</b>
9	THROUGHOUT BUILDING	NEW			5000 Sq Ft	
X1E	Miscellaneous Material 6" X 6" Light Blue Ceramic Wall Tile System (2018)					<b>Total Amount - 600 Sq Ft</b>
10	THROUGHOUT BUILDING	NEW			600 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1F	Miscellaneous Material 6" X 12" Lime Green Ceramic Wall Tile System (2018)					<b>Total Amount - 3000 Sq Ft</b>
	11	THROUGHOUT BUILDING	NEW			3000 Sq Ft
X1G	Miscellaneous Material 1/2" X 1/2" Orange Wall Tile System (2018)					<b>Total Amount - 500 Sq Ft</b>
	12	THROUGHOUT BUILDING	NEW			500 Sq Ft