

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2A 2' x 2' Acoustical Ceiling Tile Light Texture						Total Amount: 20,000 Sq. Ft.
	1	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-01	MV-01: ROOM 2112.	20000 Sq. Ft.
I2B 2' x 2' Acoustical Ceiling Tile Vinyl-Coated Gypsum						Total Amount: 1,000 Sq. Ft.
	15	KITCHEN AREA	NEW			1000 Sq. Ft.
J3A Miscellaneous Cementitious Material Black Science Tabletops						Total Amount: 300 Sq. Ft.
	14	ROOMS 2011 & 2013	NONE DETECTED	092512MV-14	MV-14: ROOM 2011.	300 Sq. Ft.
K1A Sheet Vinyl Flooring & Adhesive Gray/Tan Marble-Look						Total Amount: 2,000 Sq. Ft.
	11	LOBBY HALLWAY & COMMONS	NONE DETECTED	092512MV-11	MV-11: HALLWAY BY ROOM 1302.	2000 Sq. Ft.
K1B Sheet Vinyl Flooring & Adhesive Tan w/Gray Specks						Total Amount: 500 Sq. Ft.
	13	ROOMS 2011 & 2013	NONE DETECTED	092512MV-13	MV-13: ROOM 2011.	500 Sq. Ft.
K2A 12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown & White Streaks						Total Amount: 15,000 Sq. Ft.
	2	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-02	MV-02: HALLWAY BY EAST ENTRY.	15000 Sq. Ft.
K3A Miscellaneous Flooring Black Rubber Floor & Adhesive						Total Amount: 400 Sq. Ft.
	12	ROOMS 1306 & 1306A	NONE DETECTED	092512MV-12	MV-12: ROOM 1306A.	400 Sq. Ft.
N0A Drywall/Joint Compound 2007 Original Building						Total Amount: 20,000 Sq. Ft.
	3	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-03	MV-03: HALLWAY BY STAFF RESTROOM 1113.	20000 Sq. Ft.

Chart C - All Materials List - Gordon Parks High School (cont.)

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0A Carpet Adhesive Brown Berber Carpet						Total Amount: 8,000 Sq. Ft.
	4	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-04	MV-04: ROOM 1115.	8000 Sq. Ft.
R0A Baseboard/Mopboard Adhesive 4" Blue Baseboard						Total Amount: 500 Sq. Ft.
	5	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-05	MV-05: ROOM 1214.	500 Sq. Ft.
R0B Baseboard/Mopboard Adhesive 4" Gray Baseboard						Total Amount: 1,000 Sq. Ft.
	6	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-06	MV-06: ROOM 1306A.	1000 Sq. Ft.
V0A Sink Undercoating Black						Total Amount: 30 Sq. Ft.
	7	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-07	MV-07: ROOM 1109.	30 Sq. Ft.
X0A Miscellaneous Material Gray Duct Caulk						Total Amount: 200 Sq. Ft.
	8	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-08	MV-08: ROOM 1212.	200 Sq. Ft.
X0B Miscellaneous Material Red Fire Stop						Total Amount: 100 Sq. Ft.
	9	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-09	MV-09: ROOM 1212.	100 Sq. Ft.
X0C Miscellaneous Material Gray Duct Seam Putty						Total Amount: 50 Sq. Ft.
	10	THROUGHOUT 2007 ORIGINAL BUILDING	NONE DETECTED	092512MV-10	MV-10: ROOM 2112.	50 Sq. Ft.