

2045 St. Clair Avenue, Saint Paul, MN 55105

**Chart C - All Materials List**

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A1C		Mudded Pipe Joints on Air Cell Insulation 1931 Addition				<b>Total Amount - 15 Joints</b>
	26	CAFETERIA (1101)	ASSUMED			15 Joints
A4D		Mudded Pipe Joints on Fiberglass Insulation 1978 Addition				<b>Total Amount - 64 Joints</b>
	80	MEDIA CENTER UPPER FAN ROOM	NONE DETECTED			3 Joints
	86	THROUGHOUT 1978 ADDITION REC CENTER	NONE DETECTED	476-08	08: LOUNGE AREA.	32 Joints
	99	1978 ADDITION REC CENTER FAN ROOM	NONE DETECTED	476-07	07: MAIN STEAM LINE.	26 Joints
	103	1978 ADDITION REC CENTER GYMNASIUM STORAGE	NONE DETECTED	2001-1501-AG19	AG19: ON SMALL STEAM LINE.	3 Joints
B1C		Air Cell Pipe Insulation 1931 Addition				<b>Total Amount - 180 Lin Ft</b>
	25	CAFETERIA (1101)	ASSUMED			180 Lin Ft
B4A		Fiberglass Thermal Pipe Insulation Hard White Pipe Wrap Over Cellulose Insulation				<b>Total Amount - 9 Lin Ft</b>
	135	1924 ADDITION 2ND FLOOR HALLWAY	NONE DETECTED			2 Lin Ft
	140	ROOM 2139	NONE DETECTED			2 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	143	1924 ADDITION 3RD FLOOR HALLWAY	NONE DETECTED			1 Lin Ft
	146	ROOM 3142	NONE DETECTED	012109ML-34		2 Lin Ft
	149	ROOM 3139	NONE DETECTED			2 Lin Ft
D1A	Boiler Gaskets Shiny White Cellulose					<b>Total Amount - 5 Sq Ft</b>
	10	BOILER ROOM (1114)	NONE DETECTED	012109ML-03		5 Sq Ft
D1B	Boiler Gaskets Stack Box Access Panel Gasket					<b>Total Amount - 1 Sq Ft</b>
	11	BOILER ROOM (1114)	NONE DETECTED	012109ML-06		1 Sq Ft
D2A	Interior Boiler Insulation Firebox Insulation					<b>Total Amount - 100 Sq Ft</b>
	12	BOILER ROOM (1114)	ASSUMED			100 Sq Ft
D2B	Interior Boiler Insulation Door Refractory (Mineral Wool)					<b>Total Amount - 28 Sq Ft</b>
	13	BOILER ROOM (1114)	NSM			28 Sq Ft
D2C	Interior Boiler Insulation Hatch Refractory					<b>Total Amount - 4 Sq Ft</b>
	14	BOILER ROOM (1114)	NONE DETECTED	070918BV-01, 02, 03	BV-01,02,03: BOILER ROOM.	4 Sq Ft
E1A	Stack Gasket Shiny White					<b>Total Amount - 5 Sq Ft</b>
	15	BOILER ROOM (1114)	NONE DETECTED	012109ML-04		5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I1A	1' x 1' Acoustical Ceiling Tile Pegboard (1931)		<b>Total Amount - 1500 Sq Ft</b>			
27	CAFETERIA (1101)	NONE DETECTED	W450-RA4	RA4: CAFETERIA.	1500 Sq Ft	
I1B	1' x 1' Acoustical Ceiling Tile Pegboard (1924)		<b>Total Amount - 1500 Sq Ft</b>			
69	IMC (1200)	NONE DETECTED	012109ML-41		1500 Sq Ft	
I1C	1' x 1' Acoustical Ceiling Tile Random Nail & Pin Holes		<b>Total Amount - 50 Sq Ft</b>			
71	IMC (1200)	NONE DETECTED	012109ML-44; 476-12		50 Sq Ft	
I2A	2' x 2' Acoustical Ceiling Tile Dents w/Pin Holes		<b>Total Amount - 15000 Sq Ft</b>			
2	THROUGHOUT BUILDING	NONE DETECTED	012109ML-07	ML-07: HALLWAY NEAR ROOM 1123.	15000 Sq Ft	
I2B	2' x 2' Acoustical Ceiling Tile Vinyl-Covered Sheetrock		<b>Total Amount - 800 Sq Ft</b>			
47	THROUGHOUT KITCHEN AREA (1120)	NSM			800 Sq Ft	
I2C	2' x 2' Acoustical Ceiling Tile Fissures w/Pin Holes		<b>Total Amount - 40 Sq Ft</b>			
81	1ST FLOOR ELEVATOR ENTRY (1131)	NONE DETECTED	012109ML-46		40 Sq Ft	
I2D	2' x 2' Acoustical Ceiling Tile Grubs w/Dents & Pin Holes		<b>Total Amount - 1000 Sq Ft</b>			
124	THROUGHOUT MAIN OFFICE AREA	NONE DETECTED	012109ML-33		1000 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3A	2' x 4' Ceiling Tile Textured w/Nail & Pin Holes					<b>Total Amount - 2510 Sq Ft</b>
	84	1978 ADDITION HALLWAY RAMP TO NORTH EXIT	NONE DETECTED			130 Sq Ft
	88	THROUGHOUT 1978 ADDITION REC CENTER	NONE DETECTED			1600 Sq Ft
	89	HALLWAY RAMP TO REC CENTER & REC CENTER COMMONS AREA	NONE DETECTED	012109ML-47	ML-47: REC CENTER RAMP.	780 Sq Ft
I3C	2' x 4' Ceiling Tile 2' x 2'-Look Dents w/Pin Holes & Revealed Edge					<b>Total Amount - 2200 Sq Ft</b>
	73	IMC (1200)	NONE DETECTED	012109ML-15		2200 Sq Ft
I3D	2' x 4' Ceiling Tile Grubs w/Nail & Pin Holes					<b>Total Amount - 4000 Sq Ft</b>
	105	THROUGHOUT 1997 ADDITION (REC CENTER)	NONE DETECTED	012109ML-24		4000 Sq Ft
I3E	2' x 4' Ceiling Tile Chicken Scratch					<b>Total Amount - 2170 Sq Ft</b>
	114	ROOM 2102	NONE DETECTED	012109ML-30		550 Sq Ft
	117	ROOM 2104	NONE DETECTED			540 Sq Ft
	166	ROOM 3104	NONE DETECTED			540 Sq Ft
	171	ROOM 3102	NONE DETECTED			540 Sq Ft
I3F	2' x 4' Ceiling Tile Light Texture w/Pin Holes (2015)					<b>Total Amount - 1500 Sq Ft</b>
	29	CAFETERIA (1101)	NEW			1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3A	Miscellaneous Cementitious Material Black Window Sills (1931)		<b>Total Amount - 120 Sq Ft</b>			
	24	THROUGHOUT 1931 ADDITION	NONE DETECTED	012109ML-02; 0301-JC1	ML-02: RESTROOM OFF OF CAFETERIA.	120 Sq Ft
K0A	9" x 9" Vinyl Floor Tile & Mastic Dark Brown		<b>Total Amount - 50 Sq Ft</b>			
	111	ROOM 2101	NONE DETECTED	012109ML-37		25 Sq Ft
	173	STORAGE ROOM (3101) NEAR ROOM 3102	NONE DETECTED	2001-1501-AG8	AG8: BY ROOM 300.	25 Sq Ft
K0B	9" x 9" Vinyl Floor Tile & Mastic Light Brown		<b>Total Amount - 50 Sq Ft</b>			
	112	ROOM 2101	NONE DETECTED			25 Sq Ft
	174	STORAGE ROOM (3101) NEAR ROOM 3102	NONE DETECTED	2001-1501-AG9	AG9: BY ROOM 300.	25 Sq Ft
K0C	9" x 9" Vinyl Floor Tile & Mastic Tan w/Brown & White Streaks		<b>Total Amount - 2 Sq Ft</b>			
	77	IMC SOUTHEAST ENTRY (1299B)	5 CH (TILE & MASTIC)	2001-1501-AG20		2 Sq Ft
K0J	9" x 9" Vinyl Floor Tile & Mastic Maroon w/Red & White Streaks		<b>Total Amount - 8 Sq Ft</b>			
	68	IMC SOUTHWEST ENTRY (1299A)	ASSUMED			8 Sq Ft
K1A	Sheet Vinyl Flooring & Adhesive Cream w/Blue & Brown Specks		<b>Total Amount - 18 Sq Ft</b>			
	41	ROOM 1113	NONE DETECTED	072215BV-01	BV-01: ROOM 1113.	18 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2B		12" x 12" Vinyl Floor Tile & Mastic Off-White w/Black Streaks				<b>Total Amount - 830 Sq Ft</b>
	136	1924 ADDITION 2ND FLOOR HALLWAY	<1 CH (TILE), 10 CH (MASTIC)	012109ML-36		430 Sq Ft
	144	1924 ADDITION 3RD FLOOR HALLWAY	<1 CH (TILE), 10 CH (MASTIC)	2001-1501-AG10	AG10: BY ROOM 311.	400 Sq Ft
K2C		12" x 12" Vinyl Floor Tile & Mastic Off-White w/Tan Smudges				<b>Total Amount - 90 Sq Ft</b>
	75	IMC SOUTHEAST ENTRY (1299B)	<1 CH (TILE), 10 CH (MASTIC)	012109ML-42; 2001-0301-JC3		90 Sq Ft
K2D		12" x 12" Vinyl Floor Tile & Mastic White w/Gray Smudges				<b>Total Amount - 25 Sq Ft</b>
	154	3RD FLOOR STAFF LOUNGE RESTROOM	NONE DETECTED	012109ML-35		25 Sq Ft
K2G		12" x 12" Vinyl Floor Tile & Mastic Light Brown w/Brown & White Smudges				<b>Total Amount - 300 Sq Ft</b>
	78	IMC OFFICE (1201)	10 CH (MASTIC)	012109ML-40; 2001-1501-AG14	AG14: NORTHWEST CORNER OF OFFICE.	300 Sq Ft
K2H		12" x 12" Vinyl Floor Tile & Mastic Off-White w/Brown Streaks				<b>Total Amount - 1760 Sq Ft</b>
	21	SUB-BASEMENT OFF OF BOILER ROOM	<1 CH (TILE), 5 CH (MASTIC)			25 Sq Ft
	90	HALLWAY RAMP TO REC CENTER & REC CENTER COMMONS AREA	<1 CH (TILE), 5 CH (MASTIC)	2001-1501-AG15	AG15: NORTH EXIT DOOR.	780 Sq Ft
	92	REC CENTER KITCHEN	<1 CH (TILE), 5 CH (MASTIC)	012109ML-48		130 Sq Ft
	94	ACTIVITY ROOM (1321) NEXT TO KITCHEN	<1 CH (TILE), 5 CH (MASTIC)			420 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	98	STORAGE ROOM (1321A) OFF ACTIVITY ROOM	<1 CH (TILE), 5 CH (MASTIC)			225 Sq Ft
	104	STORAGE ROOM EAST OF KITCHEN	<1 CH (TILE), 5 CH (MASTIC)			180 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Off-White w/Black Specks					<b>Total Amount - 1500 Sq Ft</b>
	30	CAFETERIA (1101)	NONE DETECTED	012109ML-09		1500 Sq Ft
K2L	12" x 12" Vinyl Floor Tile & Mastic Brown w/Black Specks					<b>Total Amount - 720 Sq Ft</b>
	31	CAFETERIA (1101)	NONE DETECTED	012109ML-10		600 Sq Ft
	33	CAFETERIA STORAGE (1101B)	NONE DETECTED			60 Sq Ft
	34	CAFETERIA OFFICE (1101A)	NONE DETECTED			60 Sq Ft
K2N	12" x 12" Vinyl Floor Tile & Mastic Cream w/White & Beige Smudges					<b>Total Amount - 445 Sq Ft</b>
	82	1ST FLOOR ELEVATOR LOBBY (1131)	NONE DETECTED	012109ML-22		40 Sq Ft
	83	ELEVATOR	NONE DETECTED			35 Sq Ft
	85	1978 ADDITION HALLWAY RAMP TO NORTH EXIT	NONE DETECTED			130 Sq Ft
	133	2ND FLOOR ELEVATOR LOBBY (2131)	NONE DETECTED			120 Sq Ft
	155	3RD FLOOR ELEVATOR LOBBY (3131)	NONE DETECTED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2O		12" x 12" Vinyl Floor Tile & Mastic Beige & Green (1997)				<b>Total Amount - 800 Sq Ft</b>
	106	THROUGHOUT 1997 ADDITION (REC CENTER EAST)	NONE DETECTED	012109ML-25		800 Sq Ft
K2P		12" x 12" Vinyl Floor Tile & Mastic Green Mottle				<b>Total Amount - 25 Sq Ft</b>
	45	1ST FLOOR STAFF RESTROOM ACROSS FROM ROOM 1119	NONE DETECTED	012109ML-38		25 Sq Ft
K2Q		12" x 12" Vinyl Floor Tile & Mastic Tan w/Black Specks				<b>Total Amount - 1150 Sq Ft</b>
	32	CAFETERIA (1101)	NONE DETECTED			50 Sq Ft
	110	1931 ADDITION 2ND FLOOR HALLWAY	NONE DETECTED			300 Sq Ft
	118	ROOM 2104	NONE DETECTED	012109ML-32		50 Sq Ft
	130	NURSE'S OFFICE AREA	NONE DETECTED			400 Sq Ft
	164	1931 ADDITION 3RD FLOOR HALLWAY	NONE DETECTED			300 Sq Ft
	167	ROOM 3104	NONE DETECTED			50 Sq Ft
K2R		12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray Smudges				<b>Total Amount - 40 Sq Ft</b>
	145	1924 ADDITION 3RD FLOOR HALLWAY	5 CH (MASTIC ONLY)	476-05	05: 3RD FLOOR EAST HALLWAY.	40 Sq Ft
K2S		12" x 12" Vinyl Floor Tile & Mastic Light Blue Mottle (2012)				<b>Total Amount - 84 Sq Ft</b>
	63	STORAGE 1135B/C	NEW			84 Sq Ft



Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2T		12" x 12" Vinyl Floor Tile & Mastic White w/Black & Gray Specks (2012)				<b>Total Amount - 228 Sq Ft</b>
	43	ROOM 1113 (STORAGE & RESTROOM ENTRY)	NEW			228 Sq Ft
K3A		Miscellaneous Flooring Maroon w/Tan Swirls Stair Treads				<b>Total Amount - 50 Sq Ft</b>
	67	IMC SOUTHWEST ENTRY (1299A)	NONE DETECTED	012109ML-45		50 Sq Ft
K3B		Miscellaneous Flooring Tan w/White Swirls Stair Treads				<b>Total Amount - 50 Sq Ft</b>
	76	IMC SOUTHEAST ENTRY (1299B)	2 CH (TREAD)	012109ML-43		50 Sq Ft
K3D		Miscellaneous Flooring 1' X 2' Brown Stair Treads				<b>Total Amount - 50 Sq Ft</b>
	79	STAIRS (1200A) TO UPPER FAN ROOM	5 CH (TREAD), NONE DETECTED (MASTIC)	012109ML-17	ML-17: IMC FAN ROOM.	50 Sq Ft
K3E		Miscellaneous Flooring 2' x 2' Tan w/Multi-Colored Specks (2015)				<b>Total Amount - 210 Sq Ft</b>
	57	ENTRY TO ROOM 1135	NEW			70 Sq Ft
	58	ROOM 1135	NEW			140 Sq Ft
LOA		Flexible Duct Connector 1924 Addition				<b>Total Amount - 24 Sq Ft</b>
	137	2ND FLOOR MECHANICAL ROOM (ROOM 2136)	NONE DETECTED	0301-JC2		24 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
LOB Flexible Duct Connector Vinyl (1978)						<b>Total Amount - 50 Sq Ft</b>
100	1978 ADDITION REC CENTER FAN ROOM	NONE DETECTED	476-09			50 Sq Ft
LOC Flexible Duct Connector White Fabric (1921)						<b>Total Amount - 8 Sq Ft</b>
16	FAN ROOM (1114C) OFF OF BOILER ROOM	NONE DETECTED	2001-1504-J1; 2001-1901-BF6			8 Sq Ft
MOA Plaster 1921 Original Building						<b>Total Amount - 20000 Sq Ft</b>
8	THROUGHOUT 1921 ORIGINAL BUILDING	NONE DETECTED	012109ML-51, 52, 53, 54, 55; 2001-1501-AG5; 511-R3	ML-51: HALLWAY NEAR ROOM 1123. ML-52: HALLWAY NEAR ROOM 1113. ML-53: ROOM 3118. ML-54: ROOM 2123. ML-55: HALLWAY NEAR MAIN OFFICE. AG5: KITCHEN.		20000 Sq Ft
MOB Plaster 1924 Addition						<b>Total Amount - 10000 Sq Ft</b>
55	THROUGHOUT 1924 ADDITION	NONE DETECTED	012109ML-56, 57, 58, 59, 60, 61, 62	ML-56: IMC FAN ROOM. ML-57: ROOM 3138. ML-58: ROOM 1135. ML-59: ROOM 3142. ML-60: ROOM 3139. ML-61: ROOM 2137. ML-62: ROOM 2142.		10000 Sq Ft
MOC Plaster 1931 Addition						<b>Total Amount - 10000 Sq Ft</b>
22	THROUGHOUT 1931 ADDITION	NONE DETECTED	012109ML-63, 64, 65, 66, 67, 68, 69; 476-3, 4	ML-63: ROOM 3103. ML-64: ROOM 3109. ML-65: ROOM 1105. ML-66: HALLWAY NEAR ROOM 2104. ML-67: HALLWAY NEAR ROOM 2101. ML-68: ROOM 2103. ML-69: HALLWAY NEAR ROOM 3104. 476-3: 3RD FLOOR HALLWAY. 476-4: ROOM 2137.		10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOD		Plaster 1978 Addition			<b>Total Amount - 300 Sq Ft</b>	
	87	THROUGHOUT 1978 ADDITION REC CENTER	NONE DETECTED	012109ML-49, 50; 2001-1501-AG6	ML-49: GIRLS' RESTROOM ENTRY. ML-50: BOYS' RESTROOM ENTRY. AG6: HATCH IN WOMEN'S LOCKER ROOM.	300 Sq Ft
NOA		Drywall/Joint Compound			<b>Total Amount - 8000 Sq Ft</b>	
	1	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-AG4, AG5, AG7	AG4: BY ROOM 210 HALLWAY DOOR. AG-5: REC CENTER KITCHEN. AG7: HALLWAY BY ROOM 3102.	8000 Sq Ft
NOB		Drywall/Joint Compound 2012 Installation			<b>Total Amount - 160 Sq Ft</b>	
	52	RESTROOM 1123B	NEW			80 Sq Ft
	64	RESTROOM 1135A	NEW			80 Sq Ft
POA		Fire Doors Pieced Metal			<b>Total Amount - 60 Sq Ft</b>	
	18	FAN ROOM (1114C) OFF OF BOILER ROOM	NSM			20 Sq Ft
	19	CUSTODIAL STORAGE (1114A) OFF OF BOILER ROOM	NSM			20 Sq Ft
	20	STAIRS TO SUBBASEMENT OFF OF BOILER ROOM	NSM			20 Sq Ft
Q0B		Carpet Adhesive Green & Pink Berber Carpet			<b>Total Amount - 3200 Sq Ft</b>	
	107	THROUGHOUT 1997 ADDITION (REC CENTER EAST)	NONE DETECTED	012109ML-26		3200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0C	Carpet Adhesive Blue & Tan Berber Carpet					<b>Total Amount - 10000 Sq Ft</b>
3	THROUGHOUT BUILDING	NONE DETECTED	012109ML-29		10000 Sq Ft	
Q0D	Carpet Adhesive Gray w/Blue Swirls (2010)					<b>Total Amount - 2200 Sq Ft</b>
74	IMC (1200)	NEW			2200 Sq Ft	
Q0E	Carpet Adhesive Gray Carpet (2015)					<b>Total Amount - 970 Sq Ft</b>
59	ROOM 1135	NEW			970 Sq Ft	
Q0G	Carpet Adhesive Tan Carpet					<b>Total Amount - 280 Sq Ft</b>
161	CUSTODIAL OFFICE 3118/3120	NONE DETECTED	070918BV-05	BV-05: ROOM 3120.	280 Sq Ft	
Q0H	Carpet Adhesive Gray Striped Carpet Squares (2018)					<b>Total Amount - 350 Sq Ft</b>
95	ACTIVITY ROOM (1321) NEXT TO KITCHEN	NEW			350 Sq Ft	
ROA	Baseboard/Mopboard Adhesive 4" Light Brown Baseboard					<b>Total Amount - 20 Sq Ft</b>
4	THROUGHOUT BUILDING	NONE DETECTED	012109ML-12		20 Sq Ft	
ROB	Baseboard/Mopboard Adhesive 4" Black Baseboard					<b>Total Amount - 100 Sq Ft</b>
5	THROUGHOUT BUILDING	NONE DETECTED	012109ML-19		100 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROC		Baseboard/Mopboard Adhesive 4" Green Baseboard (1997)				<b>Total Amount - 50 Sq Ft</b>
	108	THROUGHOUT 1997 ADDITION (REC CENTER EAST)	NONE DETECTED	012109ML-27		50 Sq Ft
ROD		Baseboard/Mopboard Adhesive Black 90-Degree Angled Baseboard (2012)				<b>Total Amount - 50 Sq Ft</b>
	102	1978 ADDITION REC CENTER GYMNASIUM	NEW			50 Sq Ft
ROE		Baseboard/Mopboard Adhesive 4" Gray Baseboard				<b>Total Amount - 10 Sq Ft</b>
	44	ROOM 1113 (STORAGE & RESTROOM ENTRY)	NEW			10 Sq Ft
ROG		Baseboard/Mopboard Adhesive 4" Brown (2018)				<b>Total Amount - 10 Sq Ft</b>
	96	ACTIVITY ROOM (1321) NEXT TO KITCHEN	NEW			10 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier 1921 Original Building				<b>Total Amount - 10000 Sq Ft</b>
	9	THROUGHOUT 1921 ORIGINAL BUILDING	ASSUMED			10000 Sq Ft
SOB		Wood Floor Felt / Vapor Barrier 1924 Addition				<b>Total Amount - 5000 Sq Ft</b>
	56	THROUGHOUT 1924 ADDITION	ASSUMED			5000 Sq Ft
SOC		Wood Floor Felt / Vapor Barrier 1931 Addition				<b>Total Amount - 5000 Sq Ft</b>
	23	THROUGHOUT 1931 ADDITION	ASSUMED			5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOA	Sink Undercoating Gray					<b>Total Amount - 34 Sq Ft</b>
	51	ROOM 1123	NONE DETECTED			5 Sq Ft
	60	ROOM 1135	NONE DETECTED	012109ML-20		5 Sq Ft
	120	ROOM 2104	NONE DETECTED			4 Sq Ft
	125	MAIN OFFICE CONFERENCE ROOM (2015)	NONE DETECTED			5 Sq Ft
	131	NURSE'S OFFICE AREA	NONE DETECTED			5 Sq Ft
	153	3RD FLOOR STAFF LOUNGE (3136)	NONE DETECTED			5 Sq Ft
	169	ROOM 3104	NONE DETECTED			5 Sq Ft
VOB	Sink Undercoating Black					<b>Total Amount - 10 Sq Ft</b>
	93	REC CENTER KITCHEN	NONE DETECTED	012109ML-23		5 Sq Ft
	97	ACTIVITY ROOM (1321) NEXT TO KITCHEN	NONE DETECTED			5 Sq Ft
VOC	Sink Undercoating Gray (1997)					<b>Total Amount - 10 Sq Ft</b>
	109	THROUGHOUT 1997 ADDITION (REC CENTER EAST)	NONE DETECTED	012109ML-28		10 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A					<b>Total Amount - 375 Sq Ft</b>
	28	CAFETERIA (1101)	NONE DETECTED	012109ML-13		375 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B		<b>Total Amount - 325 Sq Ft</b>			
	70	IMC (1200)	NONE DETECTED	012109ML-41		325 Sq Ft
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C		<b>Total Amount - 15 Sq Ft</b>			
	72	IMC (1200)	NONE DETECTED	012109ML-44		15 Sq Ft
X0A	Miscellaneous Material Red Fire Stop		<b>Total Amount - 100 Sq Ft</b>			
	6	THROUGHOUT BUILDING	NONE DETECTED	012109ML-05	ML-5: IMC FAN ROOM.	100 Sq Ft
X0B	Miscellaneous Material Green AHU Flange Putty		<b>Total Amount - 3 Sq Ft</b>			
	17	FAN ROOM (1114C) OFF OF BOILER ROOM	NONE DETECTED	012109ML-01		3 Sq Ft
X0C	Miscellaneous Material Wood Frame Chalkboard Adhesive (1921)		<b>Total Amount - 165 Sq Ft</b>			
	42	ROOM 1113	ASSUMED			10 Sq Ft
	50	ROOM 1123	ASSUMED			10 Sq Ft
	122	ROOM 2113	ASSUMED			20 Sq Ft
	132	ROOM 2123	ASSUMED			15 Sq Ft
	156	1921 ORIGINAL BUILDING 3RD FLOOR HALLWAY	ASSUMED			30 Sq Ft
	157	ROOM 3124	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	158	ROOM 3123	ASSUMED			20 Sq Ft
	162	ROOM 3114	ASSUMED			20 Sq Ft
	163	ROOM 3113	ASSUMED			20 Sq Ft
X0D	Miscellaneous Material Light Gray Duct Caulk					<b>Total Amount - 5 Sq Ft</b>
	49	THROUGHOUT KITCHEN AREA (1120)	NONE DETECTED	012109ML-14		5 Sq Ft
X0E	Miscellaneous Material Gray Smeared Duct Caulk					<b>Total Amount - 100 Sq Ft</b>
	7	THROUGHOUT BUILDING	NONE DETECTED	012109ML-18	ML-18: IMC FAN ROOM.	100 Sq Ft
X0F	Miscellaneous Material Wired Window Glaze (1997)					<b>Total Amount - 8 Sq Ft</b>
	91	THROUGHOUT COMMONS	NONE DETECTED			2 Sq Ft
	113	ROOM 2101	NONE DETECTED	012109ML-31		1 Sq Ft
	115	ROOM 2102	NONE DETECTED			1 Sq Ft
	119	ROOM 2104	NONE DETECTED			1 Sq Ft
	168	ROOM 3104	NONE DETECTED			1 Sq Ft
	172	ROOM 3102	NONE DETECTED			1 Sq Ft
	175	STORAGE ROOM (3101) NEAR ROOM 3102	NONE DETECTED			1 Sq Ft



Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOG	Miscellaneous Material Wood Frame Chalkboard Adhesive (1931)					<b>Total Amount - 65 Sq Ft</b>
	116	ROOM 2103	ASSUMED			15 Sq Ft
	121	ROOM 2109	ASSUMED			20 Sq Ft
	165	ROOM 3109	ASSUMED			10 Sq Ft
	170	ROOM 3103	ASSUMED			20 Sq Ft
XOH	Miscellaneous Material Wood Frame Chalkboard Adhesive (1924)					<b>Total Amount - 160 Sq Ft</b>
	138	ROOM 2137	ASSUMED			20 Sq Ft
	139	ROOM 2138	ASSUMED			20 Sq Ft
	141	ROOM 2139	ASSUMED			20 Sq Ft
	142	ROOM 2142	ASSUMED			20 Sq Ft
	147	ROOM 3142	ASSUMED			20 Sq Ft
	150	ROOM 3139	ASSUMED			20 Sq Ft
	151	ROOM 3138	ASSUMED			20 Sq Ft
	152	ROOM 3137	ASSUMED			20 Sq Ft
XOI	Miscellaneous Material Corkboard Adhesive (1931)					<b>Total Amount - 31 Sq Ft</b>
	36	ROOM 1105	3 CH	062911BF-1		16 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	37	ROOM 1105	3 CH			10 Sq Ft
	40	STAIRWELL 1199A	3 CH			5 Sq Ft
<b>X0J</b>	Miscellaneous Material Corkboard Adhesive (1924)					<b>Total Amount - 40 Sq Ft</b>
	61	ROOM 1135	ASSUMED			40 Sq Ft
<b>X0K</b>	Miscellaneous Material White Adhesive on Chalkboard					<b>Total Amount - 2 Sq Ft</b>
	148	ROOM 3142	NONE DETECTED	08152012MA-10		2 Sq Ft
<b>X0L</b>	Miscellaneous Material Corkboard Adhesive (1931)					<b>Total Amount - 100 Sq Ft</b>
	35	ROOM 1105	ASSUMED			100 Sq Ft
<b>X0M</b>	Miscellaneous Material Tackboard Adhesive (1924)					<b>Total Amount - 140 Sq Ft</b>
	62	ROOM 1135	NONE DETECTED			40 Sq Ft
	134	THROUGHOUT 1924 ADDITION CLASSROOMS	NONE DETECTED	0702141-BF-1	BF-1: ROOM 3142.	100 Sq Ft
<b>X0N</b>	Miscellaneous Material Rubber Flooring (2012)					<b>Total Amount - 4000 Sq Ft</b>
	101	1978 ADDITION REC CENTER GYMNASIUM	NEW			4000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X00		Miscellaneous Material Wood Frame Corkboard Adhesive (1921)				<b>Total Amount - 60 Sq Ft</b>
	46	1921 ORIGINAL BUILDING 1ST FLOOR HALLWAY NEAR KITCHEN	ASSUMED			15 Sq Ft
	123	1921 ORIGINAL BUILDING 2ND FLOOR HALLWAY	ASSUMED			45 Sq Ft
X0P		Miscellaneous Material Black Wall Coating				<b>Total Amount - 375 Sq Ft</b>
	38	STORAGE 1109	ASSUMED			125 Sq Ft
	39	MECHANICAL 1110	ASSUMED			250 Sq Ft
X1A		Miscellaneous Material 6" Red Quarry Tile (20XX)				<b>Total Amount - 800 Sq Ft</b>
	48	THROUGHOUT KITCHEN AREA (1120)	NEW			800 Sq Ft
X1B		Miscellaneous Material 2" White w/Gray Specks Ceramic Floor Tile (2012)				<b>Total Amount - 134 Sq Ft</b>
	53	RESTROOM 1123B	NEW			50 Sq Ft
	65	RESTROOM 1135A	NEW			84 Sq Ft
X1C		Miscellaneous Material 4" White Ceramic Wall Tile System (2012)				<b>Total Amount - 280 Sq Ft</b>
	54	RESTROOM 1123B	NEW			100 Sq Ft
	66	RESTROOM 1135A	NEW			180 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1D	Miscellaneous Material 2" Beige Ceramic Floor Tile System (20XX)					<b>Total Amount - 140 Sq Ft</b>
	126	MAIN OFFICE RESTROOM 2013	NEW			45 Sq Ft
	128	MAIN OFFICE RESTROOM 2025	NEW			45 Sq Ft
	159	RESTROOM 3119A	NEW			50 Sq Ft
X1E	Miscellaneous Material 4" Beige Ceramic Wall Tile System (20XX)					<b>Total Amount - 250 Sq Ft</b>
	127	MAIN OFFICE RESTROOM 2013	NEW			80 Sq Ft
	129	MAIN OFFICE RESTROOM 2025	NEW			80 Sq Ft
	160	RESTROOM 3119A	NEW			90 Sq Ft