

1140 White Bear Avenue, Saint Paul, MN 55106

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2A		Mudded Pipe Joints on Millboard Insulation 1956 Original Building				Total Amount - 158 Joints
	39	ROOM 1006	15-20 CH	112113MA-01		1 Joints
	67	NURSE 1011	15-20 CH			6 Joints
	101	GIRLS' LOCKER ROOM 1105	15-20 CH			10 Joints
	115	BOYS' LOCKER ROOM 1109	15-20 CH			10 Joints
	123	KITCHEN 1111	15-20 CH			8 Joints
	129	KITCHEN RESTROOM 1111B	15-20 CH			5 Joints
	145	OFFICE 1201	15-20 CH			5 Joints
	153	UNISEX RESTROOM NEAR ROOM 1202	15-20 CH			4 Joints
	168	HALLWAY FROM ROOMS 1205-1321	15-20 CH			50 Joints
	173	MAINTENANCE ROOM 1206	15-20 CH			4 Joints
	190	ROOM 1302	15-20 CH			6 Joints
	205	ROOM 1306	15-20 CH	031909BF-02		3 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	213	ROOM 1308	15-20 CH			3 Joints
	234	ROOM 1310	15-20 CH			2 Joints
	244	ROOM 1312	15-20 CH			3 Joints
	265	ROOM 1314	15-20 CH			4 Joints
	323	ROOM 2322	15-20 CH			2 Joints
	331	ROOM 2321	15-20 CH			2 Joints
	339	ROOM 2319	15-20 CH			4 Joints
	347	ROOM 2320	15-20 CH			4 Joints
	355	ROOM 2318	15-20 CH			2 Joints
	363	ROOM 2317	15-20 CH			2 Joints
	377	ROOM 2314	15-20 CH			2 Joints
	385	ROOM 2315	15-20 CH			2 Joints
	403	ROOM 2313	15-20 CH			2 Joints
	415	ROOM 2311	15-20 CH			2 Joints
	427	ROOM 2309	15-20 CH			2 Joints
	435	ROOM 2307	15-20 CH			2 Joints
	453	ROOM 2305	15-20 CH			2 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	466	ROOM 2303	15-20 CH			4 Joints
A3A	Mudded Pipe Joints on Pre-formed Insulation 1956 Original Building					Total Amount - 2 Joints
	37	ROOM 1006	30 CH	207J-3A	3A: MAIN GYMNASIUM FAN ROOM (SINCE REMOVED).	2 Joints
B2A	Millboard Pipe Insulation 1956 Original Building					Total Amount - 1112 Lin Ft
	28	HALLWAY FROM MAIN OFFICE TO CAFETERIA	3-60 CH			50 Lin Ft
	38	ROOM 1006	3-60 CH	112113MA-02		4 Lin Ft
	47	COPY ROOM 1007	3-60 CH			12 Lin Ft
	49	OFFICE 1008	3-60 CH			12 Lin Ft
	66	NURSE 1011	3-60 CH			60 Lin Ft
	72	NURSE'S OFFICE 1014	3-60 CH			24 Lin Ft
	77	NURSE'S RESTROOM 1011A	3-60 CH			6 Lin Ft
	100	GIRLS' LOCKER ROOM 1105	3-60 CH			60 Lin Ft
	104	GIRLS' LOCKER ROOM OFFICE 1106	3-60 CH			25 Lin Ft
	111	BOYS' LOCKER ROOM OFFICE 1108	3-60 CH			15 Lin Ft
	114	BOYS' LOCKER ROOM 1109	3-60 CH			20 Lin Ft
	122	KITCHEN 1111	3-60 CH			20 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	128	KITCHEN RESTROOM 1111B	3-60 CH			15 Lin Ft
	144	OFFICE 1201	3-60 CH			40 Lin Ft
	152	UNISEX RESTROOM NEAR ROOM 1202	3-60 CH			20 Lin Ft
	160	STAFF WOMEN'S RESTROOM 1304	3-60 CH			40 Lin Ft
	167	HALLWAY FROM ROOMS 1205-1321	3-60 CH			240 Lin Ft
	172	MAINTENANCE ROOM 1206	3-60 CH			16 Lin Ft
	185	ENTRANCE TO ROOM 1302	3-60 CH	031909BF-01	BF-01: ROOM 1302 (SINCE REMOVED).	2 Lin Ft
	189	ROOM 1302	3-60 CH			40 Lin Ft
	204	ROOM 1306	3-60 CH			90 Lin Ft
	212	ROOM 1308	3-60 CH			50 Lin Ft
	233	ROOM 1310	3-60 CH			60 Lin Ft
	243	ROOM 1312	3-60 CH			40 Lin Ft
	264	ROOM 1314	3-60 CH			30 Lin Ft
	292	STORAGE ROOM 1316B	3-60 CH			2 Lin Ft
	322	ROOM 2322	3-60 CH			4 Lin Ft
	330	ROOM 2321	3-60 CH			4 Lin Ft
	338	ROOM 2319	3-60 CH			25 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	346	ROOM 2320	3-60 CH			25 Lin Ft
	354	ROOM 2318	3-60 CH			4 Lin Ft
	362	ROOM 2317	3-60 CH			4 Lin Ft
	376	ROOM 2314	3-60 CH			4 Lin Ft
	384	ROOM 2315	3-60 CH			4 Lin Ft
	402	ROOM 2313	3-60 CH			4 Lin Ft
	414	ROOM 2311	3-60 CH			4 Lin Ft
	426	ROOM 2309	3-60 CH			4 Lin Ft
	434	ROOM 2307	3-60 CH			4 Lin Ft
	452	ROOM 2305	3-60 CH			4 Lin Ft
	465	ROOM 2303	3-60 CH			25 Lin Ft
B3A	Pre-Formed Pipe Insulation 1956 Original Building					Total Amount - 30 Lin Ft
	36	ROOM 1006	15 CH, 15 AM	2071-2A	2A: MAIN GYMNASIUM FAN ROOM (SINCE REMOVED).	10 Lin Ft
	169	HALLWAY FROM ROOMS 1205-1321	15 CH, 15 AM			20 Lin Ft
D1A	Boiler Gaskets Fiberglass					Total Amount - 4 Sq Ft
	22	BOILER ROOM	NONE DETECTED	121609ML-2		4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2A	Interior Boiler Insulation Burner Refractory					Total Amount - 20 Sq Ft
23	BOILER ROOM	ASSUMED				20 Sq Ft
D2B	Interior Boiler Insulation Mineral Wool Access Panel Insulation					Total Amount - 20 Sq Ft
24	BOILER ROOM	ASSUMED				20 Sq Ft
G1A	Sprayed-On Acoustical Finish Light Texture					Total Amount - 5500 Sq Ft
86	AUDITORIUM	NONE DETECTED	ACB4500-A1, A2, A3, A4, A5; 2001-1901- HPJH-1B, 2B			5500 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Rough Crevices					Total Amount - 27368 Sq Ft
30	HALLWAY FROM MAIN OFFICE TO CAFETERIA	NONE DETECTED				1400 Sq Ft
34	MAIN OFFICE 1002	NONE DETECTED				1200 Sq Ft
41	OFFICE 1005	NONE DETECTED				170 Sq Ft
44	OFFICE 1004	NONE DETECTED				180 Sq Ft
50	OFFICE 1008	NONE DETECTED				110 Sq Ft
53	OFFICE 1003	NONE DETECTED				150 Sq Ft
56	TECHNOLOGY ROOM 1009	NONE DETECTED				100 Sq Ft
58	OFFICE 1016	NONE DETECTED				80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	61	OFFICE 1015	NONE DETECTED			180 Sq Ft
	64	COUNSELOR'S WORK ROOM 1010	NONE DETECTED			160 Sq Ft
	68	NURSE 1011	NONE DETECTED			240 Sq Ft
	73	NURSE'S OFFICE 1014	NONE DETECTED			150 Sq Ft
	80	COT ROOM 1013	NONE DETECTED			120 Sq Ft
	83	OFFICE 1012	NONE DETECTED			100 Sq Ft
	87	AUDITORIUM	NONE DETECTED			600 Sq Ft
	94	AUDITORIUM LIGHT BOOTH 2102	NONE DETECTED			200 Sq Ft
	98	HALLWAY EAST OF AUDITORIUM	NONE DETECTED			960 Sq Ft
	118	HALLWAY WEST OF CAFETERIA	NONE DETECTED	121609ML-12		960 Sq Ft
	124	KITCHEN 1111	NONE DETECTED			35 Sq Ft
	133	KITCHEN SERVING AREA	NONE DETECTED			400 Sq Ft
	136	CAFETERIA 1114	NONE DETECTED			3200 Sq Ft
	141	CAFETERIA STORAGE ROOMS 1115/1116	NONE DETECTED			360 Sq Ft
	146	OFFICE 1201	NONE DETECTED			280 Sq Ft
	155	OFFICE 1202	NONE DETECTED			250 Sq Ft
	163	OFFICE 1205	NONE DETECTED			240 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	170	HALLWAY FROM ROOMS 1205-1321	NONE DETECTED			5100 Sq Ft
	178	STORAGE ROOM 1207	NONE DETECTED	20719A		450 Sq Ft
	181	STAIRWELL NEAR ROOM 1207	NONE DETECTED			50 Sq Ft
	186	ENTRANCE TO ROOM 1302	NONE DETECTED			120 Sq Ft
	246	ROOM 1312	NONE DETECTED			750 Sq Ft
	251	STAIRWELL NEAR ROOM 1312	NONE DETECTED			28 Sq Ft
	260	ROOM 1312A	NONE DETECTED			750 Sq Ft
	287	ROOM 1316	NONE DETECTED			900 Sq Ft
	294	ROOM 1318	NONE DETECTED			430 Sq Ft
	311	STAIRWELL OUTSIDE ROOM 1320	NONE DETECTED			65 Sq Ft
	314	ROOM 1320	NONE DETECTED			440 Sq Ft
	319	HALLWAY FROM ROOMS 2301-2322	NONE DETECTED			5100 Sq Ft
	371	STORAGE ROOM 2316	NONE DETECTED			150 Sq Ft
	392	HALLWAY TO ROOMS 2310 & 2312	NONE DETECTED			100 Sq Ft
	395	ROOM 2312	NONE DETECTED			350 Sq Ft
	410	STORAGE ROOM 2308A	NONE DETECTED			260 Sq Ft
	461	ROOM 2304	NONE DETECTED			500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I1B	1' x 1' Acoustical Ceiling Tile Fissured					Total Amount - 2000 Sq Ft
	14	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	121609ML-26; 2001-1901-JB1	ML-26: HALLWAY BY ROOM 1104. JB1: 2ND FLOOR HALLWAY.	2000 Sq Ft
I1C	1' x 1' Acoustical Ceiling Tile Various Sized Holes					Total Amount - 5400 Sq Ft
	107	MAIN GYMNASIUM	NONE DETECTED	207I-10A	10A: MAIN GYMNASIUM.	5400 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Textured w/Pin Holes					Total Amount - 33545 Sq Ft
	29	HALLWAY FROM MAIN OFFICE TO CAFETERIA	NONE DETECTED	121609ML-9		2300 Sq Ft
	197	ROOM 1305	NONE DETECTED			900 Sq Ft
	206	ROOM 1306	NONE DETECTED			620 Sq Ft
	214	ROOM 1308	NONE DETECTED			780 Sq Ft
	220	ROOM 1307	NONE DETECTED			800 Sq Ft
	227	ROOM 1309	NONE DETECTED			860 Sq Ft
	235	ROOM 1310	NONE DETECTED			860 Sq Ft
	245	ROOM 1312	NONE DETECTED			1000 Sq Ft
	253	ROOM 1311	NONE DETECTED			860 Sq Ft
	259	ROOM 1312A	NONE DETECTED			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	267	ROOM 1313	NONE DETECTED			860 Sq Ft
	272	ROOM 1315	NONE DETECTED			860 Sq Ft
	277	ROOM 1314A	NONE DETECTED			1000 Sq Ft
	281	ROOM 1317/1317A	NONE DETECTED			900 Sq Ft
	286	ROOM 1316	NONE DETECTED			1950 Sq Ft
	293	ROOM 1318	NONE DETECTED			860 Sq Ft
	300	ROOM 1319/1319A	NONE DETECTED			900 Sq Ft
	305	ROOM 1321	NONE DETECTED			860 Sq Ft
	313	ROOM 1320	NONE DETECTED			880 Sq Ft
	324	ROOM 2322	NONE DETECTED			980 Sq Ft
	332	ROOM 2321	NONE DETECTED			860 Sq Ft
	340	ROOM 2319	NONE DETECTED			860 Sq Ft
	348	ROOM 2320	NONE DETECTED			980 Sq Ft
	356	ROOM 2318	NONE DETECTED			980 Sq Ft
	364	ROOM 2317	NONE DETECTED			860 Sq Ft
	378	ROOM 2314	NONE DETECTED			980 Sq Ft
	386	ROOM 2315	NONE DETECTED			860 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	399	ROOM 2310	NONE DETECTED			815 Sq Ft
	404	ROOM 2313	NONE DETECTED			860 Sq Ft
	416	ROOM 2311	NONE DETECTED			860 Sq Ft
	428	ROOM 2309	NONE DETECTED			980 Sq Ft
	436	ROOM 2307	NONE DETECTED			900 Sq Ft
	454	ROOM 2305	NONE DETECTED			860 Sq Ft
	467	ROOM 2303	NONE DETECTED			860 Sq Ft
	476	ROOM 2302	NONE DETECTED			1000 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Bumpy Texture w/Nail Holes					Total Amount - 4500 Sq Ft
	175	THROUGHOUT MEDIA CENTER	NONE DETECTED			3000 Sq Ft
	183	ROOM 1301	NONE DETECTED	121609ML-19		1500 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Light Texture					Total Amount - 7740 Sq Ft
	191	ROOM 1302	NONE DETECTED	121609ML-14		2100 Sq Ft
	196	ENTRANCE HALLWAY BETWEEN ROOMS 1301 & 1305	NONE DETECTED			360 Sq Ft
	422	ROOM 2308	NONE DETECTED			980 Sq Ft
	441	HALLWAY 2306 BETWEEN 2306E AND 2306A	NONE DETECTED			230 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	443	ROOM 2306A	NONE DETECTED			400 Sq Ft
	445	ROOM 2306B	NONE DETECTED			440 Sq Ft
	448	ROOM 2304E	NONE DETECTED			150 Sq Ft
	450	ROOM 2304D	NONE DETECTED			220 Sq Ft
	460	ROOM 2304	NONE DETECTED			1000 Sq Ft
	474	ROOM 2302 AREAS	NONE DETECTED			1000 Sq Ft
	482	ROOM 2301	NONE DETECTED			860 Sq Ft
J3A	Miscellaneous Cementitious Material Black Window Sills (1956)					Total Amount - 1378 Sq Ft
	32	HALLWAY FROM MAIN OFFICE TO CAFETERIA	NONE DETECTED			32 Sq Ft
	43	OFFICE 1005	NONE DETECTED			12 Sq Ft
	46	OFFICE 1004	NONE DETECTED			16 Sq Ft
	55	OFFICE 1003	NONE DETECTED			12 Sq Ft
	60	OFFICE 1016	NONE DETECTED			8 Sq Ft
	63	OFFICE 1015	NONE DETECTED			16 Sq Ft
	71	NURSE 1011	NONE DETECTED			12 Sq Ft
	76	NURSE'S OFFICE 1014	NONE DETECTED			12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	126	KITCHEN 1111	NONE DETECTED			8 Sq Ft
	140	CAFETERIA 1114	NONE DETECTED	121609ML-10	ML-10: CAFETERIA.	64 Sq Ft
	149	OFFICE 1201	NONE DETECTED			12 Sq Ft
	157	OFFICE 1202	NONE DETECTED			12 Sq Ft
	166	OFFICE 1205	NONE DETECTED			12 Sq Ft
	194	ROOM 1302	NONE DETECTED			70 Sq Ft
	201	ROOM 1305	NONE DETECTED			28 Sq Ft
	210	ROOM 1306	NONE DETECTED			28 Sq Ft
	218	ROOM 1308	NONE DETECTED			28 Sq Ft
	224	ROOM 1307	NONE DETECTED			28 Sq Ft
	231	ROOM 1309	NONE DETECTED			28 Sq Ft
	240	ROOM 1310	NONE DETECTED			28 Sq Ft
	250	ROOM 1312	NONE DETECTED			28 Sq Ft
	257	ROOM 1311	NONE DETECTED			28 Sq Ft
	262	ROOM 1312A	NONE DETECTED			28 Sq Ft
	271	ROOM 1313	NONE DETECTED			28 Sq Ft
	276	ROOM 1315	NONE DETECTED			28 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	280	ROOM 1314A	NONE DETECTED			28 Sq Ft
	284	ROOM 1317/1317A	NONE DETECTED			24 Sq Ft
	291	ROOM 1316	NONE DETECTED			56 Sq Ft
	298	ROOM 1318	NONE DETECTED			28 Sq Ft
	304	ROOM 1319/1319A	NONE DETECTED			40 Sq Ft
	309	ROOM 1321	NONE DETECTED			28 Sq Ft
	318	ROOM 1320	NONE DETECTED			24 Sq Ft
	328	ROOM 2322	NONE DETECTED			28 Sq Ft
	336	ROOM 2321	NONE DETECTED			28 Sq Ft
	344	ROOM 2319	NONE DETECTED			28 Sq Ft
	352	ROOM 2320	NONE DETECTED			28 Sq Ft
	360	ROOM 2318	NONE DETECTED			28 Sq Ft
	368	ROOM 2317	NONE DETECTED			28 Sq Ft
	382	ROOM 2314	NONE DETECTED			28 Sq Ft
	390	ROOM 2315	NONE DETECTED			28 Sq Ft
	398	ROOM 2312	NONE DETECTED			12 Sq Ft
	401	ROOM 2310	NONE DETECTED			24 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	408	ROOM 2313	NONE DETECTED			28 Sq Ft
	420	ROOM 2311	NONE DETECTED			28 Sq Ft
	424	ROOM 2308	NONE DETECTED			28 Sq Ft
	432	ROOM 2309	NONE DETECTED			28 Sq Ft
	440	ROOM 2307	NONE DETECTED			28 Sq Ft
	447	ROOM 2306B	NONE DETECTED			24 Sq Ft
	458	ROOM 2305	NONE DETECTED			28 Sq Ft
	463	ROOM 2304	NONE DETECTED			44 Sq Ft
	471	ROOM 2303	NONE DETECTED			20 Sq Ft
	477	ROOM 2302	NONE DETECTED			28 Sq Ft
J3B	Miscellaneous Cementitious Material Epoxy Resin Black Science Tabletops (2008)				Total Amount - 1070 Sq Ft	
	369	ROOM 2317	NSM			180 Sq Ft
	391	ROOM 2315	NSM			180 Sq Ft
	409	ROOM 2313	NSM			250 Sq Ft
	413	STORAGE ROOM 2308A	NSM			30 Sq Ft
	421	ROOM 2311	NSM			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	433	ROOM 2309	NSM			180 Sq Ft
K0B	9" x 9" Vinyl Floor Tile & Mastic Gray w/White & Black Streaks		Total Amount - 120 Sq Ft			
	425	ROOM 2306C	3-4 CH (TILE ONLY)	032014MV-01; 121609ML-3; 2001-1501-H2-04	MV-01: AUDITORIUM (SINCE REMOVED). ML-3: GIRLS' LOCKER ROOM 1105 (SINCE REMOVED). HS-04: COPY ROOM 1007 (SINCE REMOVED).	120 Sq Ft
K0E	9" x 9" Vinyl Floor Tile & Mastic Cream w/Brown Streaks		Total Amount - 475 Sq Ft			
	180	STORAGE ROOM 1207	NONE DETECTED	121609ML-13; 325-1	325-1: MIDDLE OF ROOM 1207.	475 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic White w/Black & White Swirls		Total Amount - 60 Sq Ft			
	242	STORAGE ROOM 1310A BY ROOM 1310	NONE DETECTED	2001-1504-Q5	Q5: STORAGE ROOM BY ELEVATOR.	60 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray & White Smudges (2008)		Total Amount - 4980 Sq Ft			
	258	ENTRANCE TO ROOM 1312A	NEW			100 Sq Ft
	266	ROOM 1314	NEW			200 Sq Ft
	365	ROOM 2317	NEW			860 Sq Ft
	387	ROOM 2315	NEW			860 Sq Ft
	405	ROOM 2313	NEW			860 Sq Ft
	412	STORAGE ROOM 2308A	NEW			260 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	417	ROOM 2311	NEW			860 Sq Ft
	429	ROOM 2309	NEW			980 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Off-White w/Black Specks (2009)					Total Amount - 6480 Sq Ft
	188	ENTRANCE TO ROOM 1302	NEW			120 Sq Ft
	321	HALLWAY FROM ROOMS 2301-2322	NEW			6100 Sq Ft
	370	STORAGE ROOM 2316A	NEW			40 Sq Ft
	373	STORAGE ROOM 2316	NEW			150 Sq Ft
	473	HALLWAY OUTSIDE ROOM 2302	NEW			70 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Gray w/Dark Gray & White Specks (2009)					Total Amount - 11950 Sq Ft
	148	OFFICE 1201	NEW			280 Sq Ft
	192	ROOM 1302	NEW			2100 Sq Ft
	325	ROOM 2322	NEW			980 Sq Ft
	333	ROOM 2321	NEW			860 Sq Ft
	341	ROOM 2319	NEW			860 Sq Ft
	349	ROOM 2320	NEW			980 Sq Ft
	357	ROOM 2318	NEW			980 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	379	ROOM 2314	NEW			980 Sq Ft
	394	HALLWAY TO ROOMS 2310 & 2312	NEW			100 Sq Ft
	397	ROOM 2312	NEW			350 Sq Ft
	437	ROOM 2307	NEW			900 Sq Ft
	455	ROOM 2305	NEW			860 Sq Ft
	468	ROOM 2303	NEW			860 Sq Ft
	483	ROOM 2301	NEW			860 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Tan w/Black Specks (2009)					Total Amount - 600 Sq Ft
	442	HALLWAY 2306 BETWEEN 2306E AND 2306A	NEW			230 Sq Ft
	449	ROOM 2304E	NEW			150 Sq Ft
	451	ROOM 2304D	NEW			220 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Gray w/Black Specks (2009)					Total Amount - 840 Sq Ft
	444	ROOM 2306A	NEW			400 Sq Ft
	446	ROOM 2306B	NEW			440 Sq Ft
K2J	12" x 12" Vinyl Floor Tile & Mastic Beige Mottle (2010)					Total Amount - 4860 Sq Ft
	198	ROOM 1305	NEW			900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	215	ROOM 1308	NEW			400 Sq Ft
	219	STORAGE 1308A	NEW			70 Sq Ft
	221	ROOM 1307	NEW			500 Sq Ft
	225	ROOM 1307 RESTROOM	NEW			30 Sq Ft
	228	ROOM 1309	NEW			500 Sq Ft
	232	ROOM 1309 RESTROOM	NEW			30 Sq Ft
	236	ROOM 1310	NEW			600 Sq Ft
	241	ROOM 1310 RESTROOM	NEW			30 Sq Ft
	282	ROOM 1317/1317A	NEW			900 Sq Ft
	301	ROOM 1319/1319A	NEW			900 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (2011)					Total Amount - 50 Sq Ft
	131	KITCHEN RESTROOM 1111B	NEW			50 Sq Ft
K2L	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (2012)					Total Amount - 40 Sq Ft
	226	ELEVATOR	NEW			40 Sq Ft
K2M	12" x 12" Vinyl Floor Tile & Mastic Gray/Tan Marble-Look (2012)					Total Amount - 2000 Sq Ft
	464	ROOM 2304	NEW			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	475	ROOM 2302 AREAS	NEW			1000 Sq Ft
K3A	Miscellaneous Flooring Cork Flooring/Adhesive					Total Amount - 500 Sq Ft
	478	ROOM 2302	NONE DETECTED (BROWN MASTIC)	073012-BF-1	BF-1: BAND ROOM.	500 Sq Ft
K3B	Miscellaneous Flooring 2' x 2' Gray w/Gray & White Specks (2014)					Total Amount - 1710 Sq Ft
	40	ROOM 1006	NEW			180 Sq Ft
	48	COPY ROOM 1007	NEW			100 Sq Ft
	70	NURSE 1011	NEW			240 Sq Ft
	75	NURSE'S OFFICE 1014	NEW			150 Sq Ft
	82	COT ROOM 1013	NEW			120 Sq Ft
	85	OFFICE 1012	NEW			120 Sq Ft
	105	GIRLS' LOCKER ROOM OFFICE 1106	NEW			70 Sq Ft
	112	BOYS' LOCKER ROOM OFFICE 1108	NEW			80 Sq Ft
	132	KITCHEN OFFICE 1113	NEW			50 Sq Ft
	143	CAFETERIA STORAGE ROOMS 1115/1116	NEW			360 Sq Ft
	151	ROOM 1202 & ENTRY	NEW			240 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3C	Miscellaneous Flooring Tan w/Gray & White (2014)					Total Amount - 100 Sq Ft
	89	AUDITORIUM	NEW			100 Sq Ft
K3D	Miscellaneous Flooring Blue w/Multi-Colored Specks (2014)					Total Amount - 4445 Sq Ft
	203	ENTRANCE TO ROOM 1306	NEW			75 Sq Ft
	207	ROOM 1306	NEW			930 Sq Ft
	254	ROOM 1311	NEW			860 Sq Ft
	268	ROOM 1313	NEW			860 Sq Ft
	273	ROOM 1315	NEW			860 Sq Ft
	306	ROOM 1321	NEW			860 Sq Ft
L0A	Flexible Duct Connector Green Canvas					Total Amount - 42 Sq Ft
	25	BOILER ROOM	NONE DETECTED	121609ML-1		6 Sq Ft
	27	MECHANICAL ROOM 1209	NONE DETECTED			6 Sq Ft
	110	GYMNASIUM FAN ROOM 240	NONE DETECTED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOA		Plaster 1956 Original Building			Total Amount - 82000 Sq Ft	
	12	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	121609ML-4, 11, 16, 21, 22, 23; 207I-4A	ML-4: GIRLS' LOCKER ROOM STORAGE 1105A. ML-11: CAFETERIA. ML-16: ROOM 1006. ML-21: ROOM 1308. ML-22: ROOM 2311. ML-23: ROOM 2304E.	82000 Sq Ft
NOA		Drywall/Joint Compound			Total Amount - 5000 Sq Ft	
	13	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	121609ML-18; 2001-1504-Q1	ML-18: ROOM 1302. Q1: CUSTODIAL OFFICE IN BOILER ROOM.	5000 Sq Ft
NOB		Drywall/Joint Compound Media Center Addition			Total Amount - 200 Sq Ft	
	174	THROUGHOUT MEDIA CENTER	NEW			200 Sq Ft
POA		Fire Doors Pieced Metal			Total Amount - 34 Sq Ft	
	26	BOILER ROOM	NSM			30 Sq Ft
	96	AUDITORIUM LIGHT BOOTH 2102	NSM			4 Sq Ft
QOA		Carpet Adhesive Blue/Gray Berber Carpet			Total Amount - 8000 Sq Ft	
	17	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	073012-BF-01; 121609ML-15	BF-01: ROOM 2300. ML-15: ROOM 1005.	8000 Sq Ft
QOC		Carpet Adhesive Red, Gray & Tan Berber Carpet			Total Amount - 4175 Sq Ft	
	184	ROOM 1301	NONE DETECTED	121609ML-20	ML-20: ROOM 1301.	1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	317	ROOM 1320	NONE DETECTED			880 Sq Ft
	400	ROOM 2310	NONE DETECTED			815 Sq Ft
	423	ROOM 2308	NONE DETECTED			980 Sq Ft
Q0E	Carpet Adhesive Blue Carpet (2014)					Total Amount - 110 Sq Ft
	52	OFFICE 1008	NEW			110 Sq Ft
Q0F	Carpet Adhesive Brown Carpet (2014)					Total Amount - 400 Sq Ft
	90	AUDITORIUM	NEW			400 Sq Ft
Q0G	Carpet Adhesive Blue Carpet Squares (2014)					Total Amount - 3300 Sq Ft
	33	THROUGHOUT MAIN OFFICE AREA	NEW			2200 Sq Ft
	165	OFFICE 1205	NEW			240 Sq Ft
	296	ROOM 1318	NEW			860 Sq Ft
Q0H	Carpet Adhesive Multi-Colored Berber Carpet (2010)					Total Amount - 2000 Sq Ft
	211	ROOMS 1307-1310	NEW			2000 Sq Ft
Q0I	Carpet Adhesive Black and Navy Blue Carpet Squares					Total Amount - 3000 Sq Ft
	176	THROUGHOUT MEDIA CENTER	NEW			3000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROA		Baseboard/Mopboard Adhesive 4" Gray Baseboard				Total Amount - 400 Sq Ft
	18	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	325-2	325-2: 1100B.	400 Sq Ft
ROB		Baseboard/Mopboard Adhesive 4" Brown Baseboard (2009)				Total Amount - 200 Sq Ft
	2	THROUGHOUT BUILDING	NEW			200 Sq Ft
ROC		Baseboard/Mopboard Adhesive 4" Black Baseboard (2009)				Total Amount - 200 Sq Ft
	3	THROUGHOUT BUILDING	NEW			200 Sq Ft
ROD		Baseboard/Mopboard Adhesive 6" Blue Baseboard				Total Amount - 200 Sq Ft
	4	THROUGHOUT BUILDING	NEW			200 Sq Ft
ROE		Baseboard/Mopboard Adhesive 6" Gray Baseboard				Total Amount - 200 Sq Ft
	5	THROUGHOUT BUILDING	NEW			200 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier On-Grade (1956)				Total Amount - 4340 Sq Ft
	120	EAST AUXILIARY GYMNASIUM 1110	3-8 CH	SN97-77892	77892: MAIN GYMNASIUM (SINCE REMOVED).	1300 Sq Ft
	121	WEST AUXILIARY GYMNASIUM 1104	3-8 CH			1300 Sq Ft
	297	ROOM 1318	3-8 CH	325-5	325-5: MIDDLE OF INNER WALL.	860 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	316	ROOM 1320	3-8 CH			880 Sq Ft
SOC		Wood Floor Felt / Vapor Barrier Elevated (1956)				Total Amount - 1500 Sq Ft
	92	AUDITORIUM STAGE	12 CH	121609ML-8	ML-08: STAGE.	1500 Sq Ft
SOD		Wood Floor Felt / Vapor Barrier On-Grade (199X)				Total Amount - 5400 Sq Ft
	109	MAIN GYMNASIUM	NEW			5400 Sq Ft
TOA		Light Cord Insulation White				Total Amount - 55 Lin Ft
	91	AUDITORIUM	50 CH			25 Lin Ft
	93	AUDITORIUM STAGE	50 CH	121609ML-7		30 Lin Ft
UOA		Light Pad Insulation Round				Total Amount - 2 Sq Ft
	97	HALLWAY SOUTHEAST OF AUDITORIUM OUTSIDE SPRINKLER SHUT-OFF ROOM	70 CH	121609ML-5		1 Sq Ft
	130	KITCHEN RESTROOM 1111B	70 CH			1 Sq Ft
VOA		Sink Undercoating Gray				Total Amount - 36 Sq Ft
	193	ROOM 1302	NONE DETECTED	121609ML-25		24 Sq Ft
	361	ROOM 2318	NONE DETECTED			12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOB		Sink Undercoating Black			Total Amount - 52 Sq Ft	
	239	ROOM 1310	3 CH			6 Sq Ft
	263	ROOM 1312A	3 CH	121609ML-28	ML-28: ROOM 2322; SINCE REMOVED.	6 Sq Ft
	353	ROOM 2320	3 CH			20 Sq Ft
	383	ROOM 2314	3 CH			20 Sq Ft
VOC		Sink Undercoating Gray (201X)			Total Amount - 6 Sq Ft	
	329	ROOM 2322	NEW			6 Sq Ft
W1A		1' x 1' Ceiling Tile Adhesive Associated w/11A			Total Amount - 7129 Sq Ft	
	31	HALLWAY FROM MAIN OFFICE TO CAFETERIA	2 CH			350 Sq Ft
	35	MAIN OFFICE 1002	2 CH			240 Sq Ft
	42	OFFICE 1005	2 CH			40 Sq Ft
	45	OFFICE 1004	2 CH			45 Sq Ft
	51	OFFICE 1008	2 CH			25 Sq Ft
	54	OFFICE 1003	2 CH			35 Sq Ft
	57	TECHNOLOGY ROOM 1009	2 CH			25 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	59	OFFICE 1016	2 CH			20 Sq Ft
	62	OFFICE 1015	2 CH			45 Sq Ft
	65	COUNSELOR'S WORK ROOM 1010	2 CH			160 Sq Ft
	69	NURSE 1011	2 CH	071212MV-01	MV-01: ROOM 1011.	60 Sq Ft
	74	NURSE'S OFFICE 1014	2 CH			35 Sq Ft
	81	COT ROOM 1013	2 CH			30 Sq Ft
	84	OFFICE 1012	2 CH			25 Sq Ft
	88	AUDITORIUM	2 CH			200 Sq Ft
	95	AUDITORIUM LIGHT BOOTH 2102	2 CH			50 Sq Ft
	99	HALLWAY EAST OF AUDITORIUM	2 CH			240 Sq Ft
	119	HALLWAY WEST OF CAFETERIA	2 CH	121609ML-12		240 Sq Ft
	125	KITCHEN 1111	2 CH			9 Sq Ft
	134	KITCHEN SERVING AREA	2 CH			100 Sq Ft
	137	CAFETERIA 1114	2 CH			800 Sq Ft
	142	CAFETERIA STORAGE ROOMS 1115/1116	2 CH			90 Sq Ft
	147	OFFICE 1201	2 CH			70 Sq Ft
	156	OFFICE 1202	2 CH			70 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	164	OFFICE 1205	2 CH			60 Sq Ft
	171	HALLWAY FROM ROOMS 1205-1321	2 CH	071212MV-02	MV-02: HALLWAY BY ROOM 1307.	1275 Sq Ft
	179	STORAGE ROOM 1207	2 CH	325-7		110 Sq Ft
	182	STAIRWELL NEAR ROOM 1207	2 CH			12 Sq Ft
	187	ENTRANCE TO ROOM 1302	2 CH			30 Sq Ft
	247	ROOM 1312	2 CH	071212MV-03	MV-03: ROOM 1312.	200 Sq Ft
	252	STAIRWELL NEAR ROOM 1312	2 CH			7 Sq Ft
	261	ROOM 1312A	2 CH			175 Sq Ft
	288	ROOM 1316	2 CH			225 Sq Ft
	295	ROOM 1318	2 CH	071212MV-04	MV-04: ROOM 1318.	215 Sq Ft
	312	STAIRWELL OUTSIDE ROOM 1320	2 CH			16 Sq Ft
	315	ROOM 1320	2 CH			110 Sq Ft
	320	HALLWAY FROM ROOMS 2301-2322	2 CH	071212MV-05	MV-05: HALLWAY BY ROOM 2322.	1275 Sq Ft
	372	STORAGE ROOM 2316	2 CH			35 Sq Ft
	393	HALLWAY TO ROOMS 2310 & 2312	2 CH			25 Sq Ft
	396	ROOM 2312	2 CH	071212MV-06	MV-06: ROOM 2312.	90 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	411	STORAGE ROOM 2308A	2 CH			65 Sq Ft
	462	ROOM 2304	2 CH			200 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B (Light Brown)					Total Amount - 500 Sq Ft
	15	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	071212MV-07, 08; 121609ML-26; 301- MPA	MV-07,08: HALLWAY BY CAFETERIA. ML-26: HALLWAY BY ROOM 1104. 301-MPA: STORAGE ROOM 1000A.	500 Sq Ft
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C					Total Amount - 1350 Sq Ft
	108	MAIN GYMNASIUM	NONE DETECTED	071212MV-11	MV-11: GYMNASIUM.	1350 Sq Ft
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1B (Dark Brown Patch)					Total Amount - 30 Sq Ft
	16	THROUGHOUT 1956 ORIGINAL BUILDING	2 CH	071212MV-09, 10; 121609ML-27	MV-09: BY ROOM 1313. MV-10: BY ROOM 2307. ML-27: HALLWAY BY ROOM 1205.	30 Sq Ft
X0A	Miscellaneous Material Tar Coated Fiberglass Inside Perimeter Radiators					Total Amount - 3000 Sq Ft
	19	THROUGHOUT 1956 ORIGINAL BUILDING CLASSROOMS	NONE DETECTED	ACB4350-O-A009	A009: ROOM 2300.	3000 Sq Ft
X0B	Miscellaneous Material Wood Frame Chalkboard Adhesive (1956)					Total Amount - 473 Sq Ft
	138	CAFETERIA 1114	NONE DETECTED			30 Sq Ft
	199	ROOM 1305	NONE DETECTED	073108BF-2	BF-2: ROOM 1301 (SINCE REMOVED).	15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	208	ROOM 1306	NONE DETECTED			15 Sq Ft
	216	ROOM 1308	NONE DETECTED			10 Sq Ft
	222	ROOM 1307	NONE DETECTED			15 Sq Ft
	229	ROOM 1309	NONE DETECTED			15 Sq Ft
	237	ROOM 1310	NONE DETECTED			15 Sq Ft
	248	ROOM 1312	NONE DETECTED			15 Sq Ft
	255	ROOM 1311	NONE DETECTED			15 Sq Ft
	269	ROOM 1313	NONE DETECTED			15 Sq Ft
	274	ROOM 1315	NONE DETECTED			15 Sq Ft
	278	ROOM 1314A	NONE DETECTED			15 Sq Ft
	285	ROOM 1317/1317A	NONE DETECTED			15 Sq Ft
	289	ROOM 1316	NONE DETECTED			10 Sq Ft
	302	ROOM 1319/1319A	NONE DETECTED			23 Sq Ft
	307	ROOM 1321	NONE DETECTED			15 Sq Ft
	326	ROOM 2322	NONE DETECTED			10 Sq Ft
	334	ROOM 2321	NONE DETECTED			15 Sq Ft
	342	ROOM 2319	NONE DETECTED			15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	350	ROOM 2320	NONE DETECTED			10 Sq Ft
	358	ROOM 2318	NONE DETECTED			10 Sq Ft
	366	ROOM 2317	NONE DETECTED			15 Sq Ft
	374	STORAGE ROOM 2316	NONE DETECTED			10 Sq Ft
	380	ROOM 2314	NONE DETECTED			10 Sq Ft
	388	ROOM 2315	NONE DETECTED			15 Sq Ft
	406	ROOM 2313	NONE DETECTED			20 Sq Ft
	418	ROOM 2311	NONE DETECTED			20 Sq Ft
	430	ROOM 2309	NONE DETECTED			15 Sq Ft
	438	ROOM 2307	NONE DETECTED			15 Sq Ft
	456	ROOM 2305	NONE DETECTED			15 Sq Ft
	469	ROOM 2303	NONE DETECTED			15 Sq Ft
	480	ROOM 2302	NONE DETECTED			10 Sq Ft
X0C	Miscellaneous Material Wood Frame Corkboard Adhesive (1956)					Total Amount - 2354 Sq Ft
	139	CAFETERIA 1114	NONE DETECTED			60 Sq Ft
	200	ROOM 1305	NONE DETECTED			180 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	209	ROOM 1306	NONE DETECTED			100 Sq Ft
	217	ROOM 1308	NONE DETECTED			60 Sq Ft
	223	ROOM 1307	NONE DETECTED			80 Sq Ft
	230	ROOM 1309	NONE DETECTED			100 Sq Ft
	238	ROOM 1310	NONE DETECTED			100 Sq Ft
	249	ROOM 1312	NONE DETECTED			50 Sq Ft
	256	ROOM 1311	NONE DETECTED			100 Sq Ft
	270	ROOM 1313	NONE DETECTED			100 Sq Ft
	275	ROOM 1315	NONE DETECTED			100 Sq Ft
	279	ROOM 1314A	NONE DETECTED			20 Sq Ft
	283	ROOM 1317/1317A	NONE DETECTED			80 Sq Ft
	290	ROOM 1316	NONE DETECTED			30 Sq Ft
	303	ROOM 1319/1319A	NONE DETECTED			28 Sq Ft
	308	ROOM 1321	NONE DETECTED			100 Sq Ft
	327	ROOM 2322	NONE DETECTED			70 Sq Ft
	335	ROOM 2321	NONE DETECTED			100 Sq Ft
	343	ROOM 2319	NONE DETECTED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	351	ROOM 2320	NONE DETECTED			70 Sq Ft
	359	ROOM 2318	NONE DETECTED			70 Sq Ft
	367	ROOM 2317	NONE DETECTED			100 Sq Ft
	375	STORAGE ROOM 2316	NONE DETECTED			16 Sq Ft
	381	ROOM 2314	NONE DETECTED			70 Sq Ft
	389	ROOM 2315	NONE DETECTED			20 Sq Ft
	407	ROOM 2313	NONE DETECTED			20 Sq Ft
	419	ROOM 2311	NONE DETECTED			20 Sq Ft
	431	ROOM 2309	NONE DETECTED			100 Sq Ft
	439	ROOM 2307	NONE DETECTED			100 Sq Ft
	457	ROOM 2305	NONE DETECTED			100 Sq Ft
	470	ROOM 2303	NONE DETECTED	073108BF-1	BF-01: ROOM 2301 (SINCE REMOVED).	100 Sq Ft
	481	ROOM 2302	NONE DETECTED			10 Sq Ft
XOE	Miscellaneous Material Red Fire Stop					Total Amount - 100 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	121609ML-17	ML-17: ROOM 1302.	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOF	Miscellaneous Material Interior Window Caulk					Total Amount - 200 Sq Ft
6	THROUGHOUT BUILDING	NONE DETECTED	060712BF-1		200 Sq Ft	
XOG	Miscellaneous Material Interior Window Glaze					Total Amount - 200 Sq Ft
7	THROUGHOUT BUILDING	NONE DETECTED	060712BF-2		200 Sq Ft	
XOH	Miscellaneous Material Exterior Window Caulk					Total Amount - 200 Sq Ft
8	THROUGHOUT BUILDING	NONE DETECTED	060712BF-3		200 Sq Ft	
XOI	Miscellaneous Material Exterior Window Glaze					Total Amount - 200 Sq Ft
9	THROUGHOUT BUILDING	NONE DETECTED	060712BF-4		200 Sq Ft	
XOJ	Miscellaneous Material Exterior Black Dampproofing					Total Amount - 5000 Sq Ft
10	THROUGHOUT BUILDING	12 CH	021712-MA-1	MA-1:	5000 Sq Ft	
XOK	Miscellaneous Material Cork Wall Adhesive					Total Amount - 300 Sq Ft
479	ROOM 2302	5 CH	073012-BF-2	BF-2: BAND ROOM.	300 Sq Ft	
XOM	Miscellaneous Material Dark Gray Marble Look Vinyl Countertop & Associated Adhesive					Total Amount - 250 Sq Ft
20	THROUGHOUT 1956 ORIGINAL BUILDING CLASSROOMS	NONE DETECTED	082119RR-01; 101717-BF-2	RR-01: ROOM 1307. BF-2: ROOM 1307.	250 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0N	Miscellaneous Material Yellow w/Brown Streaks		Total Amount - 250 Sq Ft			
	21	THROUGHOUT 1956 ORIGINAL BUILDING CLASSROOMS	NONE DETECTED	082119RR-02	RR-02: ROOM 1307.	250 Sq Ft
X1A	Miscellaneous Material Quarry Tile System (2014)		Total Amount - 1400 Sq Ft			
	127	KITCHEN 1111	NEW			1000 Sq Ft
	135	KITCHEN SERVING AREA	NEW			400 Sq Ft
X1B	Miscellaneous Material 2" X 2" Gray Ceramic Floor Tile System		Total Amount - 340 Sq Ft			
	78	NURSE'S RESTROOM 1011A	ASSUMED			40 Sq Ft
	158	STAFF MEN'S RESTROOM 1203	ASSUMED			150 Sq Ft
	161	STAFF WOMEN'S RESTROOM 1304	ASSUMED			150 Sq Ft
X1C	Miscellaneous Material 4" X 4" Gray Ceramic Wall Tile System		Total Amount - 40 Sq Ft			
	79	NURSE'S RESTROOM 1011A	ASSUMED			40 Sq Ft
X1D	Miscellaneous Material 2" X 2" Blue Ceramic Floor Tile System		Total Amount - 1770 Sq Ft			
	102	GIRLS' LOCKER ROOM 1105	ASSUMED			150 Sq Ft
	106	GIRLS' LOCKER ROOM OFFICE 1106 RESTROOM	ASSUMED			30 Sq Ft
	113	BOYS' LOCKER ROOM OFFICE 1108 RESTROOM	ASSUMED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	116	BOYS' LOCKER ROOM 1109	ASSUMED			300 Sq Ft
	150	OFFICE 1201 RESTROOM	ASSUMED			30 Sq Ft
	154	UNISEX RESTROOM NEAR ROOM 1202	ASSUMED			30 Sq Ft
	195	RESTROOM 1304A	ASSUMED			150 Sq Ft
	202	RESTROOM 1304B	ASSUMED			150 Sq Ft
	299	RESTROOM 1322	ASSUMED			150 Sq Ft
	310	RESTROOM 1324	ASSUMED			150 Sq Ft
	337	RESTROOM 2320B	ASSUMED			150 Sq Ft
	345	RESTROOM 2320A	ASSUMED			150 Sq Ft
	459	RESTROOM 2302D	ASSUMED			150 Sq Ft
	472	RESTROOM 2302C	ASSUMED			150 Sq Ft
X1E	Miscellaneous Material 2" X 2" Light Yellow Ceramic Floor Tile System					Total Amount - 200 Sq Ft
	103	GIRLS' LOCKER ROOM 1105	ASSUMED			100 Sq Ft
	117	BOYS' LOCKER ROOM 1109	ASSUMED			100 Sq Ft
X1F	Miscellaneous Material 4" X 4" Yellow Ceramic Wall Tile System					Total Amount - 450 Sq Ft
	159	STAFF MEN'S RESTROOM 1203	ASSUMED			450 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1G		Miscellaneous Material 4" X 4" Pink Ceramic Wall Tile System				Total Amount - 450 Sq Ft
	162	STAFF WOMEN'S RESTROOM 1304	ASSUMED			450 Sq Ft
X1H		Miscellaneous Material 1' X 1' Beige Quarry Floor Tile System				Total Amount - 200 Sq Ft
	177	MEDIA CENTER EAST ENTRY	NEW			200 Sq Ft
X1I		Miscellaneous Material 6" X 6" Brown Quarry Floor Tile System				Total Amount - 500 Sq Ft
	11	THROUGHOUT BUILDING STAIRWELLS	ASSUMED			500 Sq Ft