

1015 South Snelling Avenue, Saint Paul, MN 55116

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A		Mudded Pipe Joints on Fiberglass Insulation 1957 Original Building				Total Amount - 27 Joints
	26	MIDDLE SCHOOL - GIRLS' LOCKER ROOM SHOWER ROOM 0107C	20 CH, 35 AM	010709-MA-04	MA-04: JUNIOR HIGH - ROOM 0106A (SINCE REMOVED).	10 Joints
	38	MIDDLE SCHOOL - BOYS' LOCKER ROOM SHOWER ROOM 0105A	20 CH, 35 AM			6 Joints
	39	MIDDLE SCHOOL - BOYS' LOCKER ROOM SHOWER ROOM 0104B	20 CH, 35 AM			10 Joints
	63	MIDDLE SCHOOL - KITCHEN LOCKER ROOM 1103	20 CH, 35 AM			1 Joints
A4B		Mudded Pipe Joints on Fiberglass Insulation 1963 Addition				Total Amount - 36 Joints
	309	SENIOR HIGH - 1ST FLOOR GYMNASIUM 0401 WEST STORAGE	35 CH, 20 AM			7 Joints
	482	SENIOR HIGH - ROOM 3312	35 CH, 20 AM			2 Joints
	487	SENIOR HIGH - ROOM 3201	35 CH, 20 AM			2 Joints
	496	SENIOR HIGH - ROOM 3202	35 CH, 20 AM			4 Joints
	500	SENIOR HIGH - ROOM 3203	35 CH, 20 AM			4 Joints
	503	SENIOR HIGH - ROOM 3204	35 CH, 20 AM			3 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	510	SENIOR HIGH - ROOM 3205	35 CH, 20 AM			4 Joints
	511	SENIOR HIGH - ROOM 3206	35 CH, 20 AM			2 Joints
	515	SENIOR HIGH - ROOM 3207	35 CH, 20 AM			3 Joints
	523	SENIOR HIGH - ROOM 3210	35 CH, 20 AM			3 Joints
	526	SENIOR HIGH - ROOM 3211	35 CH, 20 AM	450-FC-8	FC-8: TUNNEL (SINCE REMOVED).	2 Joints
A4C	Mudded Pipe Joints on Fiberglass Insulation 1970 Addition					Total Amount - 374 Joints
	321	SENIOR HIGH - STORAGE ROOM 1405A	NONE DETECTED			6 Joints
	356	SENIOR HIGH - AUDITORIUM ADDITION	NONE DETECTED			88 Joints
	360	SENIOR HIGH - AUDITORIUM 3RD FLOOR MECHANICAL ROOM 2506	NONE DETECTED			67 Joints
	361	SENIOR HIGH - AUDITORIUM EAST HALLWAY	NONE DETECTED			7 Joints
	362	SENIOR HIGH - AUDITORIUM PIPE CHASES	NONE DETECTED			48 Joints
	363	SENIOR HIGH - AUDITORIUM STAGE 1102	NONE DETECTED	1382-B-1, 2, 3		38 Joints
	368	SENIOR HIGH - AUDITORIUM STAGE STORAGE ROOM 1102A	NONE DETECTED			19 Joints
	369	SENIOR HIGH - AUDITORIUM BOILER ROOM 1110	NONE DETECTED	102814MV-01, 02, 03; 409-X-4P, 5, 6; 2001-1501-AA14, 15, 16	MV-01,02,03: AUDITORIUM BOILER ROOM. AA14: BY WATER HEATER. 15: BACK OF BOILER. 16: AT REHEAT PUMP.	101 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
G1A		Sprayed-On Acoustical Finish Textured Paint				Total Amount - 1280 Sq Ft
	70	MIDDLE SCHOOL - LOBBY OUTSIDE MAIN OFFICE	NONE DETECTED	511P-5, 6, 7; 220-2, 3		1280 Sq Ft
H1B		Sprayed-On Structural Fireproofing Fluffy Cellulose				Total Amount - 575 Sq Ft
	376	SENIOR HIGH - ROOM 1119 (GIRLS' VARSITY LOCKER ROOM)	NONE DETECTED	409X-15P, 16, 17		575 Sq Ft
H1C		Sprayed-On Structural Fireproofing White Cellulose				Total Amount - 180 Sq Ft
	401	SENIOR HIGH - 1988 ELEVATOR ADDITION	NONE DETECTED	2001-0101-183; 2001-1901-HPSH-1D, 2D		180 Sq Ft
I1A		1' x 1' Acoustical Ceiling Tile Pegboard (1957)				Total Amount - 65440 Sq Ft
	10	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE WEST GYMNASIUM	NONE DETECTED			90 Sq Ft
	40	MIDDLE SCHOOL - 1ST FLOOR HALLWAY 0100 OUTSIDE EAST GYMNASIUM	NONE DETECTED			75 Sq Ft
	46	MIDDLE SCHOOL - GYMNASIUM STORAGE 0101A	NONE DETECTED			65 Sq Ft
	48	MIDDLE SCHOOL - GYMNASIUM STORAGE 0101B	NONE DETECTED			65 Sq Ft
	56	MIDDLE SCHOOL - CAFETERIA 1101	NONE DETECTED			6000 Sq Ft
	59	MIDDLE SCHOOL - KITCHEN	NONE DETECTED			1200 Sq Ft
	73	MIDDLE SCHOOL - MAIN OFFICE	NONE DETECTED			4200 Sq Ft
	82	MIDDLE SCHOOL - ROOM 1208	NONE DETECTED			520 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	84	MIDDLE SCHOOL - ROOM 1209	NONE DETECTED			1000 Sq Ft
	89	MIDDLE SCHOOL - ROOM 1210	NONE DETECTED			80 Sq Ft
	91	MIDDLE SCHOOL - ROOM 1211	NONE DETECTED			40 Sq Ft
	93	MIDDLE SCHOOL - ROOM 1212	NONE DETECTED			40 Sq Ft
	95	MIDDLE SCHOOL - ROOM 1214 (CHOIR)	NONE DETECTED			520 Sq Ft
	99	MIDDLE SCHOOL - ROOM 1215	NONE DETECTED			400 Sq Ft
	106	MIDDLE SCHOOL - ROOM 1307	NONE DETECTED			710 Sq Ft
	108	MIDDLE SCHOOL - ROOM 1308	NONE DETECTED			1070 Sq Ft
	114	MIDDLE SCHOOL - ROOM 1306	NONE DETECTED			1070 Sq Ft
	117	MIDDLE SCHOOL - ROOM 1305	NONE DETECTED			1070 Sq Ft
	120	MIDDLE SCHOOL - ROOM 1305 STORAGE 1305B	NONE DETECTED			320 Sq Ft
	122	MIDDLE SCHOOL - ROOM 1304	NONE DETECTED			1070 Sq Ft
	127	MIDDLE SCHOOL - ROOM 1302	NONE DETECTED			1070 Sq Ft
	131	MIDDLE SCHOOL - ROOM 1301	NONE DETECTED			1640 Sq Ft
	135	MIDDLE SCHOOL - ROOM 1301 STORAGE ROOM 1301A	NONE DETECTED			60 Sq Ft
	138	MIDDLE SCHOOL - ROOM 1325	NONE DETECTED			900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	143	MIDDLE SCHOOL - ROOM 1323	NONE DETECTED			1000 Sq Ft
	148	MIDDLE SCHOOL - ROOM 1406	NONE DETECTED			200 Sq Ft
	151	MIDDLE SCHOOL - ROOM 1405	NONE DETECTED			400 Sq Ft
	155	MIDDLE SCHOOL - ROOM 1403	NONE DETECTED			900 Sq Ft
	159	MIDDLE SCHOOL - ROOM 1401	NONE DETECTED			900 Sq Ft
	176	MIDDLE SCHOOL - ROOM 1309	NONE DETECTED			530 Sq Ft
	179	MIDDLE SCHOOL - ROOM 1311	NONE DETECTED			1000 Sq Ft
	183	MIDDLE SCHOOL - ROOM 1317	NONE DETECTED			1100 Sq Ft
	189	MIDDLE SCHOOL - ROOM 1313	NONE DETECTED			530 Sq Ft
	194	MIDDLE SCHOOL - ROOM 1315	NONE DETECTED			530 Sq Ft
	198	MIDDLE SCHOOL - ROOM 1319	NONE DETECTED			500 Sq Ft
	200	MIDDLE SCHOOL - HALLWAY 1300C	NONE DETECTED			120 Sq Ft
	203	MIDDLE SCHOOL - ROOM 1319B	NONE DETECTED			150 Sq Ft
	207	MIDDLE SCHOOL - IMC 1407	NONE DETECTED			5300 Sq Ft
	211	MIDDLE SCHOOL - IMC 1407A	NONE DETECTED			105 Sq Ft
	223	MIDDLE SCHOOL - ROOM 1415	NONE DETECTED			800 Sq Ft
	226	MIDDLE SCHOOL - ROOM 1416	NONE DETECTED			800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	233	MIDDLE SCHOOL - THROUGHOUT 1957 ORIGINAL BUILDING 3RD FLOOR	NONE DETECTED			13500 Sq Ft
	248	MIDDLE SCHOOL - ROOM 2409	NONE DETECTED			300 Sq Ft
	262	MIDDLE SCHOOL - THROUGHOUT 4TH FLOOR	NONE DETECTED	511P-1	511P-1: ROOM 320.	13500 Sq Ft
11B	1' x 1' Acoustical Ceiling Tile Grubs & Pin Holes					Total Amount - 4374 Sq Ft
	24	MIDDLE SCHOOL - GIRLS' LOCKER ROOM OFFICE 0108	NONE DETECTED			200 Sq Ft
	27	MIDDLE SCHOOL - ROOM 0106 (LOWER GYM)	NONE DETECTED	511P-11	511P-11: GIRLS' RESTROOM 0110 (SINCE REMOVED).	2860 Sq Ft
	33	MIDDLE SCHOOL - BOYS' LOCKER ROOM 0104	NONE DETECTED	220-5		1100 Sq Ft
	35	MIDDLE SCHOOL - BOYS' LOCKER ROOM OFFICE 0105	NONE DETECTED			214 Sq Ft
11C	1' x 1' Acoustical Ceiling Tile Random Pin & Nail Holes (Spline)					Total Amount - 180 Sq Ft
	162	MIDDLE SCHOOL - 2ND FLOOR HALLWAY BY NORTHEAST ELEVATOR	NONE DETECTED	511P-8		90 Sq Ft
	237	MIDDLE SCHOOL - 3RD FLOOR HALLWAY OUTSIDE NORTHEAST ELEVATOR	NONE DETECTED			90 Sq Ft
11D	1' x 1' Acoustical Ceiling Tile Uniform Diagonal Holes					Total Amount - 805 Sq Ft
	13	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE WEST GYMNASIUM	NONE DETECTED	511P-9		75 Sq Ft
	16	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE LOCKER ROOMS	NONE DETECTED	010709-MA-05; 220-6		730 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
11E		1' x 1' Acoustical Ceiling Tile Nail & Pin Holes in Clusters (Spline)				Total Amount - 3490 Sq Ft	
	267	MIDDLE SCHOOL - 4TH FLOOR HALLWAY OUTSIDE NORTHEAST ELEVATOR	NONE DETECTED	010609-MA-24		90 Sq Ft	
	310	SENIOR HIGH - BOYS' LOCKER ROOM OFFICES (NORTH & SOUTH)	NONE DETECTED	2001-01382-2B		400 Sq Ft	
	327	SENIOR HIGH - OFFICE AREAS 1303-1311	NONE DETECTED	052616-BF-2, 3, 4; 2001-0301-JC-10	BF-2: BASEMENT WEST RAMP. BF-3: 3RD FLOOR WEST RAMP. BF-4: 4TH FLOOR WEST RAMP. JC-10: WEST RAMP.	3000 Sq Ft	
11F		1' x 1' Acoustical Ceiling Tile Nail & Pin Holes in Clusters (Glued)				Total Amount - 3155 Sq Ft	
	337	SENIOR HIGH - MUSIC HALLWAY 1327	NONE DETECTED	011209-MA-06		135 Sq Ft	
	339	SENIOR HIGH - ROOM 1328	NONE DETECTED			1000 Sq Ft	
	341	SENIOR HIGH - ROOM 1328B (UNIFORMS)	NONE DETECTED			115 Sq Ft	
	343	SENIOR HIGH - ROOM 1328A & HALLWAY OUTSIDE	NONE DETECTED	2001-0301-JC-9		75 Sq Ft	
	345	SENIOR HIGH - ROOM 1330 (MUSIC OFFICE/LIBRARY)	NONE DETECTED			240 Sq Ft	
	347	SENIOR HIGH - ROOM 1329 (CHOIR)	NONE DETECTED			1000 Sq Ft	
	349	SENIOR HIGH - ROOM 1329B	NONE DETECTED			115 Sq Ft	
	351	SENIOR HIGH - ROOM 1329A & HALLWAY OUTSIDE	NONE DETECTED			75 Sq Ft	
	449	SENIOR HIGH - ROOM 2218	NONE DETECTED			400 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2A	2' x 2' Acoustical Ceiling Tile Small Gouges & Pin Holes (200X)		Total Amount - 4232 Sq Ft			
	75	MIDDLE SCHOOL - MAIN OFFICE	NONE DETECTED	010509-MA-11		4200 Sq Ft
	384	SENIOR HIGH - ROOM 1401 STORAGE 1401B	NONE DETECTED			32 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Bumps w/Pin Holes		Total Amount - 14800 Sq Ft			
	297	SENIOR HIGH - CAFETERIA 1112	NONE DETECTED	010709-MA-12	MA-12: ALA CARTE AREA.	10000 Sq Ft
	302	SENIOR HIGH - ROOM 0159	NONE DETECTED			2400 Sq Ft
	304	SENIOR HIGH - OFFICE 0158	NONE DETECTED			400 Sq Ft
	306	SENIOR HIGH - ROOM 0154	NONE DETECTED			2000 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Tectum		Total Amount - 6840 Sq Ft			
	299	SENIOR HIGH - 2ND FLOOR HALLWAY UNDER CAFETERIA	NONE DETECTED			800 Sq Ft
	316	SENIOR HIGH - 2ND FLOOR HALLWAYS	NONE DETECTED	220-12		2840 Sq Ft
	373	SENIOR HIGH - 2000 ADDITION HALLWAYS & ROOMS	NONE DETECTED			2000 Sq Ft
	377	SENIOR HIGH - ROOM 1119 (GIRLS' VARSITY LOCKER ROOM)	NONE DETECTED			1200 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Patterned Pin Holes		Total Amount - 10000 Sq Ft			
	308	SENIOR HIGH - 1ST FLOOR GYMNASIUM 0401	NONE DETECTED	ACB450F-C2		10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2E	2' x 2' Acoustical Ceiling Tile Textured w/Pin Holes & Revealed Edge (20XX)					Total Amount - 10100 Sq Ft
	50	MIDDLE SCHOOL - 1ST & 2ND FLOOR ELEVATOR LOBBIES BY OFFICE	NEW			100 Sq Ft
	51	MIDDLE SCHOOL - 2ND FLOOR HALLWAYS	NEW			10000 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Knock Down Look w/Revealed Edge (201x)					Total Amount - 2200 Sq Ft
	71	MIDDLE SCHOOL - LOBBY OUTSIDE MAIN OFFICE	NEW			2200 Sq Ft
I3A	2' x 4' Ceiling Tile Large Random Fissures					Total Amount - 3136 Sq Ft
	44	MIDDLE SCHOOL - ROOM 0101 (GYMNASIUM)	NONE DETECTED	2001-1901-HPJW-1A		3136 Sq Ft
I3B	2' x 4' Ceiling Tile Small Gouges & Pin Holes (200X)					Total Amount - 6035 Sq Ft
	21	MIDDLE SCHOOL - GIRLS' LOCKER ROOM 0107	NEW			1000 Sq Ft
	187	MIDDLE SCHOOL - ROOM 1317B	NEW			130 Sq Ft
	319	SENIOR HIGH - ROOM 1405 (FITNESS CENTER)	NEW			3000 Sq Ft
	322	SENIOR HIGH - STORAGE ROOM 1405A	NEW			400 Sq Ft
	324	SENIOR HIGH - ROOM 1402	NEW			225 Sq Ft
	326	SENIOR HIGH - STAIRWELL OFF OF ROOM 1402	NEW			150 Sq Ft
	433	SENIOR HIGH - 1970 ADDITION ROOM 2401	NEW			770 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	436	SENIOR HIGH - 1970 ADDITION 3RD FLOOR MECHANICAL ROOM 2402	NEW			360 Sq Ft
I3C	2' x 4' Ceiling Tile Bumps & Pin Holes					Total Amount - 9149 Sq Ft
	165	MIDDLE SCHOOL - ROOMS 1310-1320	NONE DETECTED	010609-MA-01	MA-01: ROOM 164.	5000 Sq Ft
	329	SENIOR HIGH - ROOM 1314	NONE DETECTED			565 Sq Ft
	409	SENIOR HIGH - ROOM 2306	NONE DETECTED			675 Sq Ft
	411	SENIOR HIGH - ROOM 2307	NONE DETECTED			675 Sq Ft
	461	SENIOR HIGH - ROOM 3303	NONE DETECTED			1000 Sq Ft
	463	SENIOR HIGH - ROOM 3304	NONE DETECTED			1000 Sq Ft
	465	SENIOR HIGH - ROOM 3305	NONE DETECTED			144 Sq Ft
	519	SENIOR HIGH - ROOM 3208	NONE DETECTED	2001-1501-AA-6	AA-6: ROOM 322.	90 Sq Ft
I3D	2' x 4' Ceiling Tile Gouges & Pin Holes in Concentric Pattern					Total Amount - 810 Sq Ft
	105	MIDDLE SCHOOL - ROOM 1307	NONE DETECTED	010609-MA-03		710 Sq Ft
	157	MIDDLE SCHOOL - ROOM 1403	NONE DETECTED			100 Sq Ft
I3E	2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes					Total Amount - 4520 Sq Ft
	113	MIDDLE SCHOOL - ROOM 1306	NONE DETECTED	010609-MA-05		1070 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	418	SENIOR HIGH - ROOM 2312	NONE DETECTED			675 Sq Ft
	420	SENIOR HIGH - ROOM 2313	NONE DETECTED			675 Sq Ft
	454	SENIOR HIGH - ROOM 2222	NONE DETECTED			1000 Sq Ft
	472	SENIOR HIGH - ROOM 3308	NONE DETECTED			1000 Sq Ft
	491	SENIOR HIGH - ROOM 3201	NONE DETECTED	2001-1501-AA3	AA3: ROOM 312 ABOVE LAB STATION BY DOOR.	100 Sq Ft
I3F	2' x 4' Ceiling Tile Craters & Pin Holes					Total Amount - 2100 Sq Ft
	178	MIDDLE SCHOOL - ROOM 1311	NONE DETECTED	010609-MA-11		1000 Sq Ft
	182	MIDDLE SCHOOL - ROOM 1317	NONE DETECTED			1100 Sq Ft
I3G	2' x 4' Ceiling Tile Small Holes, Gouges & Dents					Total Amount - 7346 Sq Ft
	188	MIDDLE SCHOOL - ROOM 1313	NONE DETECTED			530 Sq Ft
	193	MIDDLE SCHOOL - ROOM 1315	NONE DETECTED			530 Sq Ft
	206	MIDDLE SCHOOL - IMC 1407	NONE DETECTED			4000 Sq Ft
	242	MIDDLE SCHOOL - ROOM 2411	NONE DETECTED			1170 Sq Ft
	247	MIDDLE SCHOOL - ROOM 2409	NONE DETECTED	220-13		300 Sq Ft
	251	MIDDLE SCHOOL - ROOM 2407	NONE DETECTED			816 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3H	2' x 4' Ceiling Tile Random Fissures w/Pin Holes		Total Amount - 215 Sq Ft			
218	MIDDLE SCHOOL - ROOMS 1413 & 1413A	NONE DETECTED	010609-MA-14		215 Sq Ft	
I3I	2' x 4' Ceiling Tile Bumpy w/Small Holes & Gouges		Total Amount - 3800 Sq Ft			
357	SENIOR HIGH - AUDITORIUM ADDITION	NONE DETECTED	207-M2A		3000 Sq Ft	
381	SENIOR HIGH - ROOM 1401	NONE DETECTED			800 Sq Ft	
I3K	2' x 4' Ceiling Tile Pin & Nail Holes in Clusters		Total Amount - 80000 Sq Ft			
290	SENIOR HIGH - THROUGHOUT	NONE DETECTED	011209-MA-08; ACB450F-C6; 207M4A, 207M6A; 409X-2P; 220- 10	MA-08: ROOM 203 BACK ENTRANCE. C6: ROOM 311. 409X-2P: ROOM 302. 220-10: 4TH FLOOR HALLWAY.	80000 Sq Ft	
I3L	2' x 4' Ceiling Tile Tectum		Total Amount - 130 Sq Ft			
518	SENIOR HIGH - ROOM 3208	NSM			130 Sq Ft	
I3M	2' x 4' Ceiling Tile Vinyl Coated Gypsum		Total Amount - 1000 Sq Ft			
145	MIDDLE SCHOOL - ROOM 1323	NEW			1000 Sq Ft	
J1B	Cementitious Panels Gray Table Tops		Total Amount - 80 Sq Ft			
303	SENIOR HIGH - ROOM 0159	ASSUMED			80 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J1C	Cementitious Panels Sandwich Panels					Total Amount - 1560 Sq Ft
	318	SENIOR HIGH - 2ND FLOOR NORTH HALLWAY 1300	25 CH			360 Sq Ft
	385	SENIOR HIGH - 2ND FLOOR SOUTH HALLWAY OUTSIDE ROOM 1401	25 CH			160 Sq Ft
	405	SENIOR HIGH - 3RD FLOOR NORTH HALLWAY	25 CH			360 Sq Ft
	438	SENIOR HIGH - 3RD FLOOR SOUTH HALLWAY OUTSIDE ROOM 2401 & MECHANICAL ROOM 2402	25 CH	220-14		160 Sq Ft
	459	SENIOR HIGH - 4TH FLOOR NORTH HALLWAY	25 CH			360 Sq Ft
	502	SENIOR HIGH - 4TH FLOOR SOUTH HALLWAY OUTSIDE ROOMS 3203 & 3204	25 CH			160 Sq Ft
J1F	Cementitious Panels Pegboard					Total Amount - 100 Sq Ft
	478	SENIOR HIGH - ROOM 3311 STORAGE ROOMS A & B	ASSUMED			100 Sq Ft
J3A	Miscellaneous Cementitious Material Slate Window Ledges					Total Amount - 1500 Sq Ft
	4	MIDDLE SCHOOL - THROUGHOUT 1957 ORIGINAL BUILDING	NONE DETECTED	220-20	20: EAST HALLWAY BY MAIN OFFICE.	1500 Sq Ft
J3B	Miscellaneous Cementitious Material Black Epoxy Lab Table Tops					Total Amount - 925 Sq Ft
	168	MIDDLE SCHOOL - ROOM 1316	NONE DETECTED			320 Sq Ft
	171	MIDDLE SCHOOL - ROOM 1316A	NONE DETECTED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	174	MIDDLE SCHOOL - ROOM 1320	NONE DETECTED			320 Sq Ft
	246	MIDDLE SCHOOL - ROOM 2411	NONE DETECTED	220-19		20 Sq Ft
	253	MIDDLE SCHOOL - ROOM 2407	NONE DETECTED			20 Sq Ft
	277	MIDDLE SCHOOL - ROOM 3411	NONE DETECTED			20 Sq Ft
	480	SENIOR HIGH - ROOM 3312 & STORAGE ROOM 3312A	NONE DETECTED			75 Sq Ft
	488	SENIOR HIGH - ROOM 3201	NONE DETECTED			20 Sq Ft
	494	SENIOR HIGH - ROOM 3202 & STORAGE ROOMS	NONE DETECTED			40 Sq Ft
	501	SENIOR HIGH - ROOM 3203	NONE DETECTED			20 Sq Ft
	505	SENIOR HIGH - ROOM 3204	NONE DETECTED	220-17		20 Sq Ft
J3C	Miscellaneous Cementitious Material Black Fume Hood Base					Total Amount - 30 Sq Ft
	244	MIDDLE SCHOOL - ROOM 2411	NONE DETECTED	010609-MA-18		15 Sq Ft
	278	MIDDLE SCHOOL - ROOM 3411	NONE DETECTED			15 Sq Ft
J3D	Miscellaneous Cementitious Material Gray Fume Hood Panels					Total Amount - 80 Sq Ft
	245	MIDDLE SCHOOL - ROOM 2411	NONE DETECTED	010609-MA-19		40 Sq Ft
	279	MIDDLE SCHOOL - ROOM 3411	NONE DETECTED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3E		Miscellaneous Cementitious Material Black Lab Table Tops				Total Amount - 925 Sq Ft
	484	SENIOR HIGH - ROOM 3312	NONE DETECTED			300 Sq Ft
	486	SENIOR HIGH - ROOM 3201 & STORAGE ROOMS	NONE DETECTED			300 Sq Ft
	495	SENIOR HIGH - ROOM 3202 & STORAGE ROOMS	NONE DETECTED	220-18		300 Sq Ft
	528	SENIOR HIGH - ROOM 3211	NONE DETECTED			25 Sq Ft
J3F		Miscellaneous Cementitious Material Black Drying Rack				Total Amount - 10 Sq Ft
	489	SENIOR HIGH - ROOM 3201	25 CH	011209-MA-10		5 Sq Ft
	497	SENIOR HIGH - ROOM 3202	25 CH			5 Sq Ft
J3G		Miscellaneous Cementitious Material Black Masonite Lab Table Tops				Total Amount - 1000 Sq Ft
	499	SENIOR HIGH - ROOM 3203 & STORAGE ROOMS	NONE DETECTED	220-15	220-15: ROOM 320.	300 Sq Ft
	506	SENIOR HIGH - ROOM 3204	NONE DETECTED			300 Sq Ft
	507	SENIOR HIGH - ROOM 3205 & STORAGE ROOMS	NONE DETECTED			300 Sq Ft
	513	SENIOR HIGH - ROOM 3206	NONE DETECTED			70 Sq Ft
	517	SENIOR HIGH - ROOM 3207 BACK STORAGE	NONE DETECTED			10 Sq Ft
	525	SENIOR HIGH - ROOM 3210B	NONE DETECTED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3H		Miscellaneous Cementitious Material Tan Panels on Cart				Total Amount - 18 Sq Ft
	524	SENIOR HIGH - ROOM 3210	NONE DETECTED	011209-MA-15		18 Sq Ft
J3I		Miscellaneous Cementitious Material Small Black Plastic Sinks				Total Amount - 150 Sq Ft
	479	SENIOR HIGH - THROUGHOUT SCIENCE ROOMS	NONE DETECTED	220-16	220-16: ROOM 316.	150 Sq Ft
J3J		Miscellaneous Cementitious Material White Ceramic Fume Hood Panels				Total Amount - 280 Sq Ft
	169	MIDDLE SCHOOL - ROOM 1316	NSM			40 Sq Ft
	175	MIDDLE SCHOOL - ROOM 1320	NSM			40 Sq Ft
	481	SENIOR HIGH - ROOM 3312 & STORAGE ROOM 3312A	NSM			80 Sq Ft
	490	SENIOR HIGH - ROOM 3201	NSM			40 Sq Ft
	492	SENIOR HIGH - ROOM 3202 & STORAGE ROOMS	NSM			80 Sq Ft
KOA		9" x 9" Vinyl Floor Tile & Mastic Gray/Green w/Black & White Streaks (1957)				Total Amount - 300 Sq Ft
	104	MIDDLE SCHOOL - ROOM 1216	5-10 CH (TILE & MASTIC)	010509-MA-12B; 2001-01128-1; 2001-1901-HPJS-4C	MA-12B: MAIN OFFICE (SINCE REMOVED). 1: MIDDLE SCHOOL - ROOM 2411 (SINCE REMOVED).	300 Sq Ft
KOD		9" x 9" Vinyl Floor Tile & Mastic Multi-Shaded Gray Marble				Total Amount - 310 Sq Ft
	391	SENIOR HIGH - ROOM 1215	8 CH			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	395	SENIOR HIGH - ROOM 1217	8 CH			10 Sq Ft
	468	SENIOR HIGH - ROOM 3306A	8 CH	220-21	220-21: 2ND FLOOR HALLWAY (SINCE REMOVED).	290 Sq Ft
KOE	9" x 9" Vinyl Floor Tile & Mastic Gray w/Black & White Streaks (1963)					Total Amount - 3265 Sq Ft
	328	SENIOR HIGH - OFFICE AREAS 1303-1311	3-5 CH (TILE), 10 CH (MASTIC)	2001-1501-AA5	AA5: ROOM 318 (SINCE REMOVED).	3000 Sq Ft
	331	SENIOR HIGH - ROOM 1314	3-5 CH (TILE), 10 CH (MASTIC)			215 Sq Ft
	380	SENIOR HIGH - ROOM 1206 OFF ROOM 1208 (MEDIA CENTER)	3-5 CH (TILE), 10 CH (MASTIC)	011209-MA-03	MA-03: SENIOR HIGH - ROOM 1217A (SINCE REMOVED).	50 Sq Ft
K1A	Sheet Vinyl Flooring & Adhesive Tan w/Gray & Brown Specks					Total Amount - 20 Sq Ft
	77	MIDDLE SCHOOL - MAIN OFFICE SMALL RESTROOM	NONE DETECTED	010509-MA-10		20 Sq Ft
K1C	Sheet Vinyl Flooring & Adhesive Small Gray, Beige & Pink Swirls					Total Amount - 1360 Sq Ft
	78	MIDDLE SCHOOL - MAIN OFFICE LARGE RESTROOM	NONE DETECTED	220-68		40 Sq Ft
	80	MIDDLE SCHOOL - MAIN OFFICE NURSE'S RESTROOM	NONE DETECTED			20 Sq Ft
	333	SENIOR HIGH - ROOM 1315 (NURSE'S OFFICE)	NONE DETECTED	220-11		1300 Sq Ft
K1D	Sheet Vinyl Flooring & Adhesive Tan w/Brown & Beige Terrazzo-look					Total Amount - 75 Sq Ft
	383	SENIOR HIGH - ROOM 1401 RESTROOM 1401A	NONE DETECTED	010709-MA-21		75 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K1E	Sheet Vinyl Flooring & Adhesive Brown, Tan & Gray (2012)					Total Amount - 15217 Sq Ft
	268	MIDDLE SCHOOL - ROOM 3401	NEW			816 Sq Ft
	271	MIDDLE SCHOOL - ROOM 3403	NEW			816 Sq Ft
	272	MIDDLE SCHOOL - ROOM 3406	NEW			270 Sq Ft
	273	MIDDLE SCHOOL - ROOM 3405	NEW			816 Sq Ft
	274	MIDDLE SCHOOL - ROOM 3407	NEW			816 Sq Ft
	275	MIDDLE SCHOOL - ROOM 3409	NEW			300 Sq Ft
	276	MIDDLE SCHOOL - ROOM 3411	NEW			1170 Sq Ft
	280	MIDDLE SCHOOL - ROOM 3413	NEW			816 Sq Ft
	282	MIDDLE SCHOOL - ROOM 3410	NEW			270 Sq Ft
	283	MIDDLE SCHOOL - ROOM 3415	NEW			816 Sq Ft
	288	MIDDLE SCHOOL - ROOM 3417	NEW			816 Sq Ft
	406	SENIOR HIGH - ROOM 2303	NEW			750 Sq Ft
	408	SENIOR HIGH - ROOM 2305	NEW			675 Sq Ft
	412	SENIOR HIGH - ROOM 2307	NEW			675 Sq Ft
	413	SENIOR HIGH - ROOM 2308	NEW			675 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	415	SENIOR HIGH - ROOM 2309A	NEW			220 Sq Ft
	434	SENIOR HIGH - 1970 ADDITION ROOM 2401	NEW			700 Sq Ft
	444	SENIOR HIGH - ROOM 2213	NEW			675 Sq Ft
	445	SENIOR HIGH - ROOM 2213A	NEW			125 Sq Ft
	446	SENIOR HIGH - ROOM 2214	NEW			675 Sq Ft
	447	SENIOR HIGH - ROOM 2216	NEW			675 Sq Ft
	450	SENIOR HIGH - ROOM 2218	NEW			400 Sq Ft
	453	SENIOR HIGH - STORAGE 2221	NEW			50 Sq Ft
	455	SENIOR HIGH - ROOM 2222	NEW			1000 Sq Ft
	456	SENIOR HIGH - ROOM 2222A	NEW			125 Sq Ft
	457	SENIOR HIGH - SCHOOL STORE 2223	NEW			75 Sq Ft
K1F	Sheet Vinyl Flooring & Adhesive Gray (2012)					Total Amount - 3000 Sq Ft
	265	MIDDLE SCHOOL - 4TH FLOOR HALLWAY	NEW			3000 Sq Ft
K1G	Sheet Vinyl Flooring & Adhesive Gold (2012)					Total Amount - 800 Sq Ft
	266	MIDDLE SCHOOL - 4TH FLOOR HALLWAY	NEW			800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2B	12" x 12" Vinyl Floor Tile & Mastic Tan, Brown & Beige Mottle (200X)					Total Amount - 6000 Sq Ft
58	MIDDLE SCHOOL - CAFETERIA 1101	NONE DETECTED	010509-MA-08		6000 Sq Ft	
K2D	12" x 12" Vinyl Floor Tile & Mastic White w/Black Marbling					Total Amount - 3000 Sq Ft
54	MIDDLE SCHOOL - 2ND FLOOR HALLWAYS	NONE DETECTED	010709-MA-07		3000 Sq Ft	
K2E	12" x 12" Vinyl Floor Tile & Mastic Solid Gray w/Dark Gray & White Streaking					Total Amount - 3250 Sq Ft
55	MIDDLE SCHOOL - 2ND FLOOR HALLWAYS	NONE DETECTED	010709-MA-08		500 Sq Ft	
374	SENIOR HIGH - 2000 ADDITION HALLWAYS & ROOMS	NONE DETECTED			2750 Sq Ft	
K2F	12" x 12" Vinyl Floor Tile & Mastic White w/Black Flecks					Total Amount - 120 Sq Ft
116	MIDDLE SCHOOL - ROOM 1306 STORAGE ROOMS 1306A & 1306B	NONE DETECTED	010609-MA-06		120 Sq Ft	
K2H	12" x 12" Vinyl Floor Tile & Mastic Caramel, Brown & Beige Mottle (2002)					Total Amount - 2550 Sq Ft
167	MIDDLE SCHOOL - ROOM 1316	NONE DETECTED	010609-MA-09		1200 Sq Ft	
170	MIDDLE SCHOOL - ROOM 1316A	NONE DETECTED			150 Sq Ft	
173	MIDDLE SCHOOL - ROOM 1320	NONE DETECTED			1200 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2I	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Dark Gray & Black Streaks					Total Amount - 700 Sq Ft
53	MIDDLE SCHOOL - 2ND FLOOR HALLWAYS	NONE DETECTED	220-34		700 Sq Ft	
K2J	12" x 12" Vinyl Floor Tile & Mastic Beige w/Black Specks					Total Amount - 2100 Sq Ft
181	MIDDLE SCHOOL - ROOM 1311	NONE DETECTED	010609-MA-12		1000 Sq Ft	
185	MIDDLE SCHOOL - ROOM 1317	NONE DETECTED			1100 Sq Ft	
K2K	12" x 12" Vinyl Floor Tile & Mastic Gray w/Black Specks (200X)					Total Amount - 385 Sq Ft
186	MIDDLE SCHOOL - ROOMS 1317B, 1317C, & 1317D	NONE DETECTED	010609-MA-13		200 Sq Ft	
219	MIDDLE SCHOOL - ROOMS 1413 & 1413A	NONE DETECTED			185 Sq Ft	
K2M	12" x 12" Vinyl Floor Tile & Mastic Blue Mottle					Total Amount - 400 Sq Ft
191	MIDDLE SCHOOL - ROOM 1313	NONE DETECTED	010709-MA-11		200 Sq Ft	
196	MIDDLE SCHOOL - ROOM 1315	NONE DETECTED			200 Sq Ft	
K2N	12" x 12" Vinyl Floor Tile & Mastic Bright Gray Mottle					Total Amount - 11798 Sq Ft
298	SENIOR HIGH - CAFETERIA 1112	NONE DETECTED	010709-MA-13	MA-13: ALA CARTE AREA.	10000 Sq Ft	
300	SENIOR HIGH - 2ND FLOOR HALLWAY UNDER CAFETERIA	NONE DETECTED			660 Sq Ft	
428	SENIOR HIGH - ROOM 2206	NONE DETECTED			144 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	430	SENIOR HIGH - ROOM 2207	NONE DETECTED			144 Sq Ft
	439	SENIOR HIGH - ROOM 2208 & STORAGE 2208A	NONE DETECTED			850 Sq Ft
K2O		12" x 12" Vinyl Floor Tile & Mastic Dirty Gray Mottle				Total Amount - 180 Sq Ft
	301	SENIOR HIGH - 2ND FLOOR HALLWAY UNDER CAFETERIA	NONE DETECTED	010709-MA-14		180 Sq Ft
K2P		12" x 12" Vinyl Floor Tile & Mastic Small Brown Squares Pattern				Total Amount - 1430 Sq Ft
	307	SENIOR HIGH - LINK (1150) BETWEEN JUNIOR & SENIOR HIGH BUILDINGS	NONE DETECTED	011209-MA-16		1430 Sq Ft
K2R		12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan/Olive Flecks				Total Amount - 10 Sq Ft
	334	SENIOR HIGH - ROOM 1315 (NURSE'S OFFICE)	NONE DETECTED	220-33		10 Sq Ft
K2S		12" x 12" Vinyl Floor Tile & Mastic White w/Light Brown Flecks				Total Amount - 24465 Sq Ft
	399	SENIOR HIGH - ROOM 1218	NONE DETECTED	011209-MA-04		120 Sq Ft
	400	SENIOR HIGH - ROOM 1219	NONE DETECTED			75 Sq Ft
	458	SENIOR HIGH - 4TH FLOOR HALLWAYS	NONE DETECTED			6400 Sq Ft
	460	SENIOR HIGH - ROOM 3302	NONE DETECTED			330 Sq Ft
	467	SENIOR HIGH - ROOM 3306	NONE DETECTED			730 Sq Ft
	470	SENIOR HIGH - ROOM 3307	NONE DETECTED			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	473	SENIOR HIGH - ROOM 3308	NONE DETECTED			1000 Sq Ft
	475	SENIOR HIGH - ROOM 3309	NONE DETECTED			675 Sq Ft
	476	SENIOR HIGH - ROOM 3310	NONE DETECTED			675 Sq Ft
	477	SENIOR HIGH - ROOM 3311 & STORAGE ROOMS A, B & C	NONE DETECTED			1000 Sq Ft
	483	SENIOR HIGH - ROOM 3312	NONE DETECTED			1100 Sq Ft
	485	SENIOR HIGH - ROOM 3201 & STORAGE ROOMS	NONE DETECTED			1350 Sq Ft
	493	SENIOR HIGH - ROOM 3202 & STORAGE ROOMS	NONE DETECTED	011209-MA-12	MA-12: BY FUME HOOD.	1350 Sq Ft
	498	SENIOR HIGH - ROOM 3203 & STORAGE ROOMS	NONE DETECTED			1350 Sq Ft
	504	SENIOR HIGH - ROOM 3204	NONE DETECTED			1100 Sq Ft
	508	SENIOR HIGH - ROOM 3205 & STORAGE ROOMS	NONE DETECTED			1500 Sq Ft
	512	SENIOR HIGH - ROOM 3206	NONE DETECTED			1200 Sq Ft
	514	SENIOR HIGH - ROOM 3207 & STORAGE ROOMS	NONE DETECTED			1350 Sq Ft
	520	SENIOR HIGH - ROOM 3208	NONE DETECTED			220 Sq Ft
	522	SENIOR HIGH - ROOM 3210 & STORAGE ROOMS	NONE DETECTED			1500 Sq Ft
	527	SENIOR HIGH - ROOM 3211	NONE DETECTED			1100 Sq Ft
	529	SENIOR HIGH - ROOM 3212	NONE DETECTED			90 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2T	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Red, White & Blue Streaks					Total Amount - 390 Sq Ft
	353	SENIOR HIGH - ROOM 1332 LIFT ACCESS OFF HALLWAY	NONE DETECTED	011209-MA-07		110 Sq Ft
	354	SENIOR HIGH - ROOM 1332 LIFT ACCESS STORAGE 1332A	NONE DETECTED			80 Sq Ft
	521	SENIOR HIGH - ROOM 3209	NONE DETECTED	220-30		200 Sq Ft
K2U	12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown Flecks & Black Non-Skid Dots					Total Amount - 2000 Sq Ft
	336	SENIOR HIGH - WEST RAMP - ALL FLOORS	NONE DETECTED	2001-0301-JC-11; 2001-01129-3		2000 Sq Ft
K2V	12" x 12" Vinyl Floor Tile & Mastic White w/Blue & Gray Streaks					Total Amount - 18450 Sq Ft
	52	MIDDLE SCHOOL - 2ND FLOOR HALLWAYS	NONE DETECTED	010709-MA-06	MA-06: UNDER EAST STAIRS BY ROOM 122.	5000 Sq Ft
	404	SENIOR HIGH - 3RD FLOOR HALLWAYS	NONE DETECTED			3000 Sq Ft
	414	SENIOR HIGH - ROOMS 2309 & 2309B	NONE DETECTED			800 Sq Ft
	416	SENIOR HIGH - ROOM 2310	NONE DETECTED			675 Sq Ft
	417	SENIOR HIGH - ROOM 2311	NONE DETECTED			675 Sq Ft
	419	SENIOR HIGH - ROOM 2312	NONE DETECTED			675 Sq Ft
	421	SENIOR HIGH - ROOM 2313	NONE DETECTED			675 Sq Ft
	422	SENIOR HIGH - ROOM 2314 & STORAGE 2314A	NONE DETECTED			885 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	423	SENIOR HIGH - ROOM 2201 & STORAGE 2201A	NONE DETECTED			885 Sq Ft
	424	SENIOR HIGH - ROOM 2202	NONE DETECTED			675 Sq Ft
	425	SENIOR HIGH - ROOM 2203	NONE DETECTED			675 Sq Ft
	426	SENIOR HIGH - ROOM 2204	NONE DETECTED			675 Sq Ft
	427	SENIOR HIGH - ROOM 2205 & STORAGE 2205A	NONE DETECTED			835 Sq Ft
	440	SENIOR HIGH - ROOM 2209	NONE DETECTED			675 Sq Ft
	441	SENIOR HIGH - ROOM 2210	NONE DETECTED			675 Sq Ft
	442	SENIOR HIGH - ROOM 2211 & STORAGE 2211A	NONE DETECTED			900 Sq Ft
	443	SENIOR HIGH - STORAGE 2212	NONE DETECTED			70 Sq Ft
K2W	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (2011)				Total Amount - 3700 Sq Ft	
	146	MIDDLE SCHOOL - ROOM 1323	NEW			1000 Sq Ft
	407	SENIOR HIGH - ROOM 2304	NEW			675 Sq Ft
	410	SENIOR HIGH - ROOM 2306	NEW			675 Sq Ft
	448	SENIOR HIGH - ROOM 2217	NEW			675 Sq Ft
	452	SENIOR HIGH - ROOM 2220	NEW			675 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2X	12" x 12" Vinyl Floor Tile & Mastic White w/Olive Flecks (2012)		Total Amount - 3400 Sq Ft			
	403	SENIOR HIGH - 3RD FLOOR HALLWAYS	NEW			3400 Sq Ft
K3A	Miscellaneous Flooring Black Stair Tread Mastic		Total Amount - 180 Sq Ft			
	12	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE WEST GYMNASIUM	NONE DETECTED	010509-MA-05	MA-05: MIDDLE SCHOOL - ROOM 0106 (LOWER GYM) (SINCE REMOVED).	90 Sq Ft
	42	MIDDLE SCHOOL - 1ST FLOOR HALLWAY 0100 OUTSIDE EAST GYMNASIUM	NONE DETECTED			90 Sq Ft
K3B	Miscellaneous Flooring Gray w/Beige Marbling Stair Treads		Total Amount - 400 Sq Ft			
	232	MIDDLE SCHOOL - WEST STAIRWELL	NONE DETECTED	2001-1501-AB10		200 Sq Ft
	257	MIDDLE SCHOOL - EAST STAIRWELL 2499B	NONE DETECTED			200 Sq Ft
K3C	Miscellaneous Flooring Black Flooring Mastic		Total Amount - 80 Sq Ft			
	102	MIDDLE SCHOOL - ROOM 1215	5-10 CH	2001-1901-HPJH-4C		80 Sq Ft
K3D	Miscellaneous Flooring 2' x 2' Gray w/Tan & Beige Flecks (2014)		Total Amount - 21956 Sq Ft			
	29	MIDDLE SCHOOL - ROOM 0106 (LOWER GYM)	NEW			3100 Sq Ft
	64	MIDDLE SCHOOL - KITCHEN LOCKER ROOM 1103	NEW			70 Sq Ft
	86	MIDDLE SCHOOL - ROOM 1209	NEW			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	101	MIDDLE SCHOOL - ROOM 1215	NEW			780 Sq Ft
	110	MIDDLE SCHOOL - ROOM 1308	NEW			1070 Sq Ft
	112	MIDDLE SCHOOL - ROOM 1308 STORAGE ROOMS 1308A & 1308B	NEW			120 Sq Ft
	124	MIDDLE SCHOOL - ROOM 1304	NEW			1070 Sq Ft
	125	MIDDLE SCHOOL - ROOM 1304 STORAGE ROOMS 1304A & 1304B	NEW			120 Sq Ft
	129	MIDDLE SCHOOL - ROOM 1302	NEW			1070 Sq Ft
	130	MIDDLE SCHOOL - ROOM 1302 STORAGE ROOMS 1302A & 1302B	NEW			120 Sq Ft
	133	MIDDLE SCHOOL - ROOM 1301	NEW			1640 Sq Ft
	137	MIDDLE SCHOOL - ROOM 1301 STORAGE ROOM 1301A	NEW			60 Sq Ft
	140	MIDDLE SCHOOL - ROOM 1325	NEW			900 Sq Ft
	142	MIDDLE SCHOOL - ROOM 1325 RESTROOM 1325A & STORAGE ROOM 1325B	NEW			110 Sq Ft
	153	MIDDLE SCHOOL - ROOM 1405	NEW			320 Sq Ft
	158	MIDDLE SCHOOL - ROOM 1403	NEW			900 Sq Ft
	161	MIDDLE SCHOOL - ROOM 1401	NEW			900 Sq Ft
	205	MIDDLE SCHOOL - ROOM 1319B	NEW			150 Sq Ft
	216	MIDDLE SCHOOL - IMC ROOM 1410	NEW			330 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	217	MIDDLE SCHOOL - ROOM 1410A	NEW			70 Sq Ft
	222	MIDDLE SCHOOL - IMC ROOM 1411	NEW			450 Sq Ft
	225	MIDDLE SCHOOL - ROOM 1415	NEW			800 Sq Ft
	228	MIDDLE SCHOOL - ROOM 1416	NEW			800 Sq Ft
	231	MIDDLE SCHOOL - WEST STAIRWELL	NEW			204 Sq Ft
	236	MIDDLE SCHOOL - 3RD FLOOR HALLWAY	NEW			3900 Sq Ft
	252	MIDDLE SCHOOL - ROOM 2407	NEW			816 Sq Ft
	254	MIDDLE SCHOOL - ROOM 2405	NEW			816 Sq Ft
	255	MIDDLE SCHOOL - ROOM 2406	NEW			270 Sq Ft
K3E	Miscellaneous Flooring 2' x 2' Gray w/Tan & Beige Flecks (2015)					Total Amount - 17929 Sq Ft
	15	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE WEST GYMNASIUM	NEW			150 Sq Ft
	18	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE LOCKER ROOMS	NEW			730 Sq Ft
	43	MIDDLE SCHOOL - 1ST FLOOR HALLWAY 0100 OUTSIDE EAST GYMNASIUM	NEW			150 Sq Ft
	79	MIDDLE SCHOOL - ROOM 1013 - MAIN NURSE'S OFFICE	NEW			150 Sq Ft
	202	MIDDLE SCHOOL - HALLWAY 1300C	NEW			600 Sq Ft
	238	MIDDLE SCHOOL - ROOM 2417	NEW			816 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	239	MIDDLE SCHOOL - ROOM 2415	NEW			816 Sq Ft
	240	MIDDLE SCHOOL - ROOM 2410	NEW			270 Sq Ft
	241	MIDDLE SCHOOL - ROOM 2413	NEW			816 Sq Ft
	243	MIDDLE SCHOOL - ROOM 2411	NEW			1170 Sq Ft
	250	MIDDLE SCHOOL - ROOM 2409	NEW			300 Sq Ft
	256	MIDDLE SCHOOL - EAST STAIRWELL 2499B	NEW			194 Sq Ft
	258	MIDDLE SCHOOL - ROOM 2403	NEW			816 Sq Ft
	259	MIDDLE SCHOOL - ROOM 2401	NEW			816 Sq Ft
	317	SENIOR HIGH - 2ND FLOOR HALLWAYS	NEW			6400 Sq Ft
	332	SENIOR HIGH - 2ND FLOOR NORTHWEST ENTRY 1300A	NEW			120 Sq Ft
	386	SENIOR HIGH - 2ND FLOOR SOUTHEAST ENTRANCE	NEW			120 Sq Ft
	387	SENIOR HIGH - ROOM 1211	NEW			1120 Sq Ft
	388	SENIOR HIGH - ROOM 1211A	NEW			120 Sq Ft
	389	SENIOR HIGH - ROOM 1212	NEW			200 Sq Ft
	390	SENIOR HIGH - ROOM 1213	NEW			1000 Sq Ft
	392	SENIOR HIGH - ROOM 1215	NEW			75 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	394	SENIOR HIGH - ROOM 1216	NEW			100 Sq Ft
	396	SENIOR HIGH - ROOM 1217	NEW			700 Sq Ft
	398	SENIOR HIGH - ROOM 1217A	NEW			120 Sq Ft
	402	SENIOR HIGH - 1988 ELEVATOR ADDITION BY ROOM 1219	NEW			60 Sq Ft
LOA	Flexible Duct Connector Dark Canvas					Total Amount - 355 Sq Ft
	7	MIDDLE SCHOOL - ROOM 0112 OFF ROOM 0113	NONE DETECTED			12 Sq Ft
	8	MIDDLE SCHOOL - TUNNELS OFF ROOM 0113	NONE DETECTED	2001-1504-F3		12 Sq Ft
	30	MIDDLE SCHOOL - ROOM 0106A	NONE DETECTED			1 Sq Ft
	31	MIDDLE SCHOOL - ROOM 0106B	NONE DETECTED			1 Sq Ft
	69	MIDDLE SCHOOL - AUDITORIUM MECHANICAL ROOM SOUTH	NONE DETECTED			30 Sq Ft
	97	MIDDLE SCHOOL - AUDITORIUM MECHANICAL ROOM NORTH 1207	NONE DETECTED			45 Sq Ft
	311	SENIOR HIGH - 1ST FLOOR MECHANICAL ROOM 0302	NONE DETECTED			10 Sq Ft
	312	SENIOR HIGH - 1ST FLOOR MECHANICAL ROOM 0301 BY LAUNDRY	NONE DETECTED			5 Sq Ft
	313	SENIOR HIGH - 1ST FLOOR POOL MECHANICAL ROOM - NORTH 0307	NONE DETECTED	2001-1504-C1	C1: 3RD FLOOR FAN ROOM (1ST UNIT) (SINCE REMOVED).	30 Sq Ft
	530	SENIOR HIGH - 4TH FLOOR BOYS' & GIRLS' RESTROOMS	NONE DETECTED			9 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	531	SENIOR HIGH - EAST PENTHOUSE 4201	NONE DETECTED	220-37		100 Sq Ft
	533	SENIOR HIGH - WEST PENTHOUSE 4301	NONE DETECTED			100 Sq Ft
LOB	Flexible Duct Connector Black Vinyl					Total Amount - 54 Sq Ft
	314	SENIOR HIGH - 1ST FLOOR POOL MECHANICAL ROOM - NORTH 0307	NSM			10 Sq Ft
	315	SENIOR HIGH - 1ST FLOOR POOL MECHANICAL ROOM - SOUTH 0307A	NSM			4 Sq Ft
	532	SENIOR HIGH - EAST PENTHOUSE 4201	NSM			20 Sq Ft
	534	SENIOR HIGH - WEST PENTHOUSE 4301	NSM			20 Sq Ft
M0A	Plaster 1957 Original Building					Total Amount - 100000 Sq Ft
	2	MIDDLE SCHOOL - THROUGHOUT 1957 ORIGINAL BUILDING	NONE DETECTED	010609-MA-04, 22; 010709-MA-02, 09, 10; 2001-1501-AB11, AB15	MA-02: 1ST FLOOR ELEVATOR LOBBY BY OFFICE (WALL). MA-04: ROOM 105 CEILING. MA-09: AUDITORIUM CATWALK WALL. MA-10: AUDITORIUM CEILING AT SPRINKLER PENETRATIONS. MA-22: ROOM 320 CEILING. AB11: BEHIND OUTLET PLATE. AB15: 1ST SHOWER ROOM (BOYS') ABOVE DOOR.	100000 Sq Ft
M0AA	Plaster Associated with Ahu (1957)					Total Amount - 1 Sq Ft
	32	MIDDLE SCHOOL - ROOM 0106B	NONE DETECTED			1 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOB		Plaster 1963 Addition			Total Amount - 40000 Sq Ft	
	293	SENIOR HIGH - THROUGHOUT 1963 ADDITION	NONE DETECTED	011209-MA-05; 2001-1501-AA2, AA8; 2001-01382-1B	MA-05: MUSIC HALLWAY. AA2: ROOM 311 NORTH OF DOOR TO HALLWAY. AA8: 4TH FLOOR BOYS' RESTROOM. 1B: 4TH FLOOR ENTRY.	40000 Sq Ft
MOC		Plaster 1970 Addition			Total Amount - 5600 Sq Ft	
	355	SENIOR HIGH - AUDITORIUM ADDITION	NONE DETECTED	2001-1501-AA17; 220-38; 511P-22	AA17: OUTSIDE AUDITORIUM UPSTAIRS. 220-38: WEST HALLWAY. 511P-22: HALLWAY BY BOILER ROOM.	5600 Sq Ft
MOF		Plaster 2000 Addition			Total Amount - 130 Sq Ft	
	378	SENIOR HIGH - ROOM 1119 (GIRLS' VARSITY LOCKER ROOM) SHOWER AREA	NONE DETECTED	011209-MA-18, 19, 20		130 Sq Ft
MOG		Plaster 2015 Installation			Total Amount - 50 Sq Ft	
	23	MIDDLE SCHOOL - GIRLS' LOCKER ROOM RESTROOM 0107A	NEW			50 Sq Ft
NOA		Drywall/Joint Compound 1957 Original Building			Total Amount - 20000 Sq Ft	
	3	MIDDLE SCHOOL - THROUGHOUT 1957 ORIGINAL BUILDING	NONE DETECTED	2001-0301-JC-1; 2001-1504-F2; ACB450F-C7	JC-1: EAST HALLWAY BY ROOM 211. 511-P4: EAST BAND ROOM. F2: IMC (130).	20000 Sq Ft
NOC		Drywall/Joint Compound 1970 Addition			Total Amount - 1400 Sq Ft	
	432	SENIOR HIGH - 1970 ADDITION ROOM 2401 & MECHANICAL ROOM 2402	NONE DETECTED	ACB450F-C7		1400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
NOF		Drywall/Joint Compound 2000 Addition				Total Amount - 1000 Sq Ft	
	372	SENIOR HIGH - 2000 ADDITION HALLWAYS & ROOMS	NONE DETECTED	011209-MA-17	MA-17: ROOM 105 RESTROOM.	1000 Sq Ft	
NOG		Drywall/Joint Compound 2002 Addition				Total Amount - 3500 Sq Ft	
	166	MIDDLE SCHOOL - ROOMS 1310-1320 & HALLWAY	NONE DETECTED	010609-MA-02	MA-02: ROOM 164.	3500 Sq Ft	
POA		Fire Doors Wood Composite - 1.5 Hr Rating (Weyerhaeuser)				Total Amount - 144 Sq Ft	
	367	SENIOR HIGH - AUDITORIUM STAGE 1102	10 CH, 25 AM	010709-MA-01	MA-01: LATCH ON DOOR TO STORAGE ROOM.	80 Sq Ft	
	370	SENIOR HIGH - AUDITORIUM BOILER ROOM 1110	10 CH, 25 AM			20 Sq Ft	
	371	SENIOR HIGH - AUDITORIUM ELECTRICAL ROOM (1105)	10 CH, 25 AM			20 Sq Ft	
	435	SENIOR HIGH - 1970 ADDITION 3RD FLOOR MECHANICAL ROOM 2402	10 CH, 25 AM			24 Sq Ft	
Q0B		Carpet Adhesive Red Berber Carpet				Total Amount - 840 Sq Ft	
	65	MIDDLE SCHOOL - AUDITORIUM	NONE DETECTED	2001-1910-HPJH-2C	SOUTHWEST ENTRANCE.	840 Sq Ft	
Q0C		Carpet Adhesive Multi-Colored Berber Carpet				Total Amount - 30500 Sq Ft	
	81	MIDDLE SCHOOL - ROOMS 1208-1216	NONE DETECTED	2001-1901-HPJH-4C; (LAYERS C & D)	ROOM 104 ADJACENT STAIRS.	4500 Sq Ft	
	291	SENIOR HIGH - THROUGHOUT	NONE DETECTED	2001-1901-HPSH-1C, 3C	1C: ROOM 102. 3C: OUTSIDE TEACHERS' LOUNGE.	20000 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	358	SENIOR HIGH - AUDITORIUM ADDITION	NONE DETECTED	2001-1901-HPSH-2C	2C: NORTHWEST CORNER OF AUDITORIUM LOBBY.	6000 Sq Ft
Q0D	Carpet Adhesive Dark Gray w/Red, Blue & Light Gray Carpet Squares (2014)					Total Amount - 9255 Sq Ft
	76	MIDDLE SCHOOL - MAIN OFFICE	NEW			4200 Sq Ft
	88	MIDDLE SCHOOL - ROOMS 1210-1212	NEW			200 Sq Ft
	150	MIDDLE SCHOOL - ROOM 1406	NEW			200 Sq Ft
	209	MIDDLE SCHOOL - IMC 1407	NEW			4000 Sq Ft
	213	MIDDLE SCHOOL - IMC 1407A	NEW			105 Sq Ft
	214	MIDDLE SCHOOL - IMC ROOM 1408	NEW			150 Sq Ft
	215	MIDDLE SCHOOL - IMC ROOM 1409	NEW			200 Sq Ft
	220	MIDDLE SCHOOL - ROOM 1410B	NEW			200 Sq Ft
ROA	Baseboard/Mopboard Adhesive Gray Baseboard					Total Amount - 3500 Sq Ft
	1	MIDDLE SCHOOL - THROUGHOUT	NONE DETECTED	2001-1901-HPJH-5C	ROOM 104 ADJACENT STAIRS.	500 Sq Ft
	292	SENIOR HIGH - THROUGHOUT	NONE DETECTED	2001-1901-HPSH-4C	OUTSIDE TEACHERS' LOUNGE.	3000 Sq Ft
ROC	Baseboard/Mopboard Adhesive Black Baseboard					Total Amount - 800 Sq Ft
	235	MIDDLE SCHOOL - THROUGHOUT 1957 ORIGINAL BUILDING 3RD FLOOR	NONE DETECTED	010609-MA-23	MA-23: ROOM 320 CLOSET.	600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	359	SENIOR HIGH - AUDITORIUM ADDITION	NONE DETECTED	2001-1901-HPSH-5C	NORTHWEST CORNER OF AUDITORIUM LOBBY.	200 Sq Ft
SOA	Wood Floor Felt / Vapor Barrier 1957 Original Building (On-Grade)					Total Amount - 7200 Sq Ft
	45	MIDDLE SCHOOL - ROOM 0101 (GYMNASIUM)	10 CH	010509-MA-06		7200 Sq Ft
SOAA	Wood Floor Felt / Vapor Barrier 1957 Original Building (Elevated)					Total Amount - 2700 Sq Ft
	68	MIDDLE SCHOOL - AUDITORIUM STAGE	ASSUMED			2400 Sq Ft
	103	MIDDLE SCHOOL - ROOM 1216	ASSUMED			300 Sq Ft
SOC	Wood Floor Felt / Vapor Barrier Elevated (1970)					Total Amount - 5625 Sq Ft
	320	SENIOR HIGH - ROOM 1405 (FITNESS CENTER)	NSM			3000 Sq Ft
	323	SENIOR HIGH - STORAGE ROOM 1405A	NSM			400 Sq Ft
	325	SENIOR HIGH - ROOM 1402	NSM			225 Sq Ft
	364	SENIOR HIGH - AUDITORIUM STAGE 1102	NSM			2000 Sq Ft
SOD	Wood Floor Felt / Vapor Barrier 2009 Installation (Raised Floor)					Total Amount - 1500 Sq Ft
	330	SENIOR HIGH - ROOM 1314	NSM			1500 Sq Ft
TOA	Light Cord Insulation Fuzzy, White					Total Amount - 38 Lin Ft
	66	MIDDLE SCHOOL - AUDITORIUM CATWALK	ASSUMED			6 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	67	MIDDLE SCHOOL - AUDITORIUM STAGE	ASSUMED			32 Lin Ft
TOB						Total Amount - 90 Lin Ft
		Light Cord Insulation Fuzzy, White (1970)				
	365	SENIOR HIGH - AUDITORIUM STAGE 1102	ASSUMED			90 Lin Ft
VOB						Total Amount - 20 Sq Ft
		Sink Undercoating Cream				
	192	MIDDLE SCHOOL - ROOM 1313	NONE DETECTED	010609-MA-08	MA-08: JUNIOR HIGH - ROOM 1323 (SINCE REMOVED).	10 Sq Ft
	197	MIDDLE SCHOOL - ROOM 1315	NONE DETECTED			10 Sq Ft
VOC						Total Amount - 5 Sq Ft
		Sink Undercoating Gray (2002)				
	172	MIDDLE SCHOOL - ROOM 1316A	NONE DETECTED	010609-MA-10		5 Sq Ft
VOD						Total Amount - 10 Sq Ft
		Sink Undercoating Cream w/Hook Faucet				
	335	SENIOR HIGH - ROOM 1315 (NURSE'S OFFICE)	NONE DETECTED	010609-MA-16	MA-16: MIDDLE SCHOOL - ROOM 2411 (SINCE REMOVED).	10 Sq Ft
VOF						Total Amount - 39 Sq Ft
		Sink Undercoating Pink				
	375	SENIOR HIGH - CONCESSIONS AREA	NONE DETECTED	010709-MA-16	MA-16: SENIOR HIGH - OFFICE WORK ROOM 1311 (SINCE REMOVED).	5 Sq Ft
	393	SENIOR HIGH - ROOM 1215	NONE DETECTED			4 Sq Ft
	429	SENIOR HIGH - ROOM 2206	NONE DETECTED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	431	SENIOR HIGH - ROOM 2207	NONE DETECTED			5 Sq Ft
	451	SENIOR HIGH - ROOM 2218	NONE DETECTED			5 Sq Ft
	462	SENIOR HIGH - ROOM 3303	NONE DETECTED			5 Sq Ft
	464	SENIOR HIGH - ROOM 3304	NONE DETECTED			5 Sq Ft
	466	SENIOR HIGH - ROOM 3305	NONE DETECTED			5 Sq Ft
VOG	Sink Undercoating Light Green					Total Amount - 9 Sq Ft
	469	SENIOR HIGH - ROOM 3306A	NONE DETECTED	011209-MA-09		3 Sq Ft
	471	SENIOR HIGH - ROOM 3307	NONE DETECTED			3 Sq Ft
	474	SENIOR HIGH - ROOM 3308	NONE DETECTED			3 Sq Ft
VOH	Sink Undercoating Black w/Gooseneck Faucet					Total Amount - 12 Sq Ft
	509	SENIOR HIGH - ROOM 3205 & STORAGE ROOMS	NONE DETECTED	011209-MA-13	MA-13: ROOM 306.	12 Sq Ft
VOI	Sink Undercoating Rough Gray w/Pump Faucet					Total Amount - 5 Sq Ft
	516	SENIOR HIGH - ROOM 3207	NONE DETECTED	011209-MA-14		5 Sq Ft
VOJ	Sink Undercoating Pink w/Hook Faucet					Total Amount - 8 Sq Ft
	397	SENIOR HIGH - ROOM 1217	NONE DETECTED	011209-MA-01	MA-01: SENIOR HIGH - ROOM 1211 (SINCE REMOVED).	8 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOK	Sink Undercoating Gray					Total Amount - 32 Sq Ft
	147	MIDDLE SCHOOL - ROOM 1323	NEW			32 Sq Ft
VOL	Sink Undercoating White					Total Amount - 10 Sq Ft
	62	MIDDLE SCHOOL - KITCHEN	ASSUMED			5 Sq Ft
	87	MIDDLE SCHOOL - ROOM 1209	ASSUMED			5 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A					Total Amount - 15022 Sq Ft
	11	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE WEST GYMNASIUM	NONE DETECTED			20 Sq Ft
	41	MIDDLE SCHOOL - 1ST FLOOR HALLWAY 0100 OUTSIDE EAST GYMNASIUM	NONE DETECTED			15 Sq Ft
	47	MIDDLE SCHOOL - GYMNASIUM STORAGE 0101A	NONE DETECTED			15 Sq Ft
	49	MIDDLE SCHOOL - GYMNASIUM STORAGE 0101B	NONE DETECTED			15 Sq Ft
	57	MIDDLE SCHOOL - CAFETERIA 1101	NONE DETECTED	301-MP-C (NOVA)	2ND FLOOR HALLWAYS (SINCE REMOVED).	1500 Sq Ft
	60	MIDDLE SCHOOL - KITCHEN	NONE DETECTED			250 Sq Ft
	74	MIDDLE SCHOOL - MAIN OFFICE	NONE DETECTED	010509-MA-09	MA-09: NEAR SOUTH ENTRY.	1000 Sq Ft
	83	MIDDLE SCHOOL - ROOM 1208	NONE DETECTED			130 Sq Ft
	85	MIDDLE SCHOOL - ROOM 1209	NONE DETECTED			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	90	MIDDLE SCHOOL - ROOM 1210	NONE DETECTED			20 Sq Ft
	92	MIDDLE SCHOOL - ROOM 1211	NONE DETECTED			10 Sq Ft
	94	MIDDLE SCHOOL - ROOM 1212	NONE DETECTED			10 Sq Ft
	96	MIDDLE SCHOOL - ROOM 1214 (CHOIR)	NONE DETECTED			130 Sq Ft
	100	MIDDLE SCHOOL - ROOM 1215	NONE DETECTED			100 Sq Ft
	107	MIDDLE SCHOOL - ROOM 1307	NONE DETECTED			170 Sq Ft
	109	MIDDLE SCHOOL - ROOM 1308	NONE DETECTED			250 Sq Ft
	115	MIDDLE SCHOOL - ROOM 1306	NONE DETECTED			250 Sq Ft
	118	MIDDLE SCHOOL - ROOM 1305	NONE DETECTED			250 Sq Ft
	121	MIDDLE SCHOOL - ROOM 1305 STORAGE 1305B	NONE DETECTED			75 Sq Ft
	123	MIDDLE SCHOOL - ROOM 1304	NONE DETECTED			250 Sq Ft
	128	MIDDLE SCHOOL - ROOM 1302	NONE DETECTED			250 Sq Ft
	132	MIDDLE SCHOOL - ROOM 1301	NONE DETECTED			325 Sq Ft
	136	MIDDLE SCHOOL - ROOM 1301 STORAGE ROOM 1301A	NONE DETECTED			12 Sq Ft
	139	MIDDLE SCHOOL - ROOM 1325	NONE DETECTED			200 Sq Ft
	144	MIDDLE SCHOOL - ROOM 1323	NONE DETECTED			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	149	MIDDLE SCHOOL - ROOM 1406	NONE DETECTED			50 Sq Ft
	152	MIDDLE SCHOOL - ROOM 1405	NONE DETECTED			80 Sq Ft
	156	MIDDLE SCHOOL - ROOM 1403	NONE DETECTED			200 Sq Ft
	160	MIDDLE SCHOOL - ROOM 1401	NONE DETECTED			200 Sq Ft
	177	MIDDLE SCHOOL - ROOM 1309	NONE DETECTED	110320-BF-1	BF-1: ROOM 1309.	120 Sq Ft
	180	MIDDLE SCHOOL - ROOM 1311	NONE DETECTED			250 Sq Ft
	184	MIDDLE SCHOOL - ROOM 1317	NONE DETECTED			250 Sq Ft
	190	MIDDLE SCHOOL - ROOM 1313	NONE DETECTED			120 Sq Ft
	195	MIDDLE SCHOOL - ROOM 1315	NONE DETECTED			120 Sq Ft
	199	MIDDLE SCHOOL - ROOM 1319	NONE DETECTED			125 Sq Ft
	201	MIDDLE SCHOOL - HALLWAY 1300C	NONE DETECTED			30 Sq Ft
	204	MIDDLE SCHOOL - ROOM 1319B	NONE DETECTED			35 Sq Ft
	208	MIDDLE SCHOOL - IMC 1407	NONE DETECTED			1200 Sq Ft
	212	MIDDLE SCHOOL - IMC 1407A	NONE DETECTED			20 Sq Ft
	224	MIDDLE SCHOOL - ROOM 1415	NONE DETECTED			200 Sq Ft
	227	MIDDLE SCHOOL - ROOM 1416	NONE DETECTED			200 Sq Ft
	234	MIDDLE SCHOOL - THROUGHOUT 1957 ORIGINAL BUILDING 3RD FLOOR	NONE DETECTED			3000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	249	MIDDLE SCHOOL - ROOM 2409	NONE DETECTED			75 Sq Ft
	263	MIDDLE SCHOOL - THROUGHOUT 4TH FLOOR	NONE DETECTED	010609-MA-21	MA-21; ROOM 320.	3000 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B					Total Amount - 1040 Sq Ft
	25	MIDDLE SCHOOL - GIRLS' LOCKER ROOM OFFICE 0108	<1 ANT	010509-MA-04	MA-04: 1ST FLOOR GIRLS' RESTROOM 0110 (SINCE REMOVED).	50 Sq Ft
	28	MIDDLE SCHOOL - ROOM 0106 (LOWER GYM)	<1 ANT			700 Sq Ft
	34	MIDDLE SCHOOL - BOYS' LOCKER ROOM 0104	<1 ANT			250 Sq Ft
	36	MIDDLE SCHOOL - BOYS' LOCKER ROOM OFFICE 0105	<1 ANT	301-MP-B (NOVA)		40 Sq Ft
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1D					Total Amount - 165 Sq Ft
	14	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE WEST GYMNASIUM	<1 ANT			15 Sq Ft
	17	MIDDLE SCHOOL - 1ST FLOOR HALLWAY OUTSIDE LOCKER ROOMS	<1 ANT	010709-MA-05		150 Sq Ft
W1F	1' x 1' Ceiling Tile Adhesive Associated w/I1F					Total Amount - 576 Sq Ft
	338	SENIOR HIGH - MUSIC HALLWAY 1327	NONE DETECTED	011209-MA-06		30 Sq Ft
	340	SENIOR HIGH - ROOM 1328	NONE DETECTED	301-MP-A (NOVA)		200 Sq Ft
	342	SENIOR HIGH - ROOM 1328B (UNIFORMS)	NONE DETECTED			25 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	344	SENIOR HIGH - ROOM 1328A & HALLWAY OUTSIDE	NONE DETECTED			18 Sq Ft
	346	SENIOR HIGH - ROOM 1330 (MUSIC OFFICE/LIBRARY)	NONE DETECTED			60 Sq Ft
	348	SENIOR HIGH - ROOM 1329 (CHOIR)	NONE DETECTED			200 Sq Ft
	350	SENIOR HIGH - ROOM 1329B	NONE DETECTED			25 Sq Ft
	352	SENIOR HIGH - ROOM 1329A & HALLWAY OUTSIDE	NONE DETECTED			18 Sq Ft
XOA	Miscellaneous Material Gray Laminate Countertops					Total Amount - 466 Sq Ft
	111	MIDDLE SCHOOL - ROOM 1308	NONE DETECTED	220-27		130 Sq Ft
	134	MIDDLE SCHOOL - ROOM 1301	NONE DETECTED			190 Sq Ft
	141	MIDDLE SCHOOL - ROOM 1325	NONE DETECTED			18 Sq Ft
	210	MIDDLE SCHOOL - IMC 1407	NONE DETECTED			50 Sq Ft
	221	MIDDLE SCHOOL - ROOM 1410B	NONE DETECTED			30 Sq Ft
	264	MIDDLE SCHOOL - THROUGHOUT 4TH FLOOR	NONE DETECTED			48 Sq Ft
XOC	Miscellaneous Material Black Laminate Countertops					Total Amount - 90 Sq Ft
	281	MIDDLE SCHOOL - ROOM 3413	NONE DETECTED	220-29		30 Sq Ft
	285	MIDDLE SCHOOL - ROOM 3415	NONE DETECTED			30 Sq Ft
	289	MIDDLE SCHOOL - ROOM 3417	NONE DETECTED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0D		Miscellaneous Material Coarse White Proscenium Curtains				Total Amount - 1100 Sq Ft
	366	SENIOR HIGH - AUDITORIUM STAGE 1102	ASSUMED			1100 Sq Ft
X0E		Miscellaneous Material Wood Paneling Adhesive				Total Amount - 20 Sq Ft
	305	SENIOR HIGH - OFFICE 0158	5 CH	010709-MA-15		20 Sq Ft
X0G		Miscellaneous Material Chalkboard Adhesive (1970)				Total Amount - 10 Sq Ft
	382	SENIOR HIGH - ROOM 1401	ASSUMED			10 Sq Ft
X0H		Miscellaneous Material Slate Chalkboard Adhesive (1963)				Total Amount - 800 Sq Ft
	294	SENIOR HIGH - THROUGHOUT 1963 ADDITION	ASSUMED			800 Sq Ft
X0I		Miscellaneous Material Tackboard Adhesive (1963)				Total Amount - 3200 Sq Ft
	295	SENIOR HIGH - THROUGHOUT 1963 ADDITION	ASSUMED			3200 Sq Ft
X0J		Miscellaneous Material McQuay AHU Tar Gaskets				Total Amount - 10 Sq Ft
	437	SENIOR HIGH - 1970 ADDITION 3RD FLOOR MECHANICAL ROOM 2402	5 CH	080111-JC-01	JC-01: MECHANICAL ROOM 2402.	10 Sq Ft
X0K		Miscellaneous Material Dampproofing				Total Amount - 10000 Sq Ft
	5	MIDDLE SCHOOL - THROUGHOUT 1957 ORIGINAL BUILDING	NONE DETECTED	061112MV-01	BOILER ROOM	10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOL		Miscellaneous Material Vermiculite Insulation				Total Amount - 1070 Sq Ft
	72	THROUGHOUT MIDDLE SCHOOL OFFICE AREA	<1 ACT	062515-BF-1	BF-1: MAIN OFFICE SOUTH EXTERIOR WALL.	1070 Sq Ft
XOM		Miscellaneous Material Old Electrical Wire Insulation & Jacket				Total Amount - 100 Sq Ft
	296	THROUGHOUT SENIOR HIGH 1963 ADDITION	NONE DETECTED	071315-BF-1, 2	BF-1,2: ROOM 0301A.	100 Sq Ft
XON		Miscellaneous Material Tan/Beige Insulation Below Floor				Total Amount - 1100 Sq Ft
	19	MIDDLE SCHOOL - LOCKER ROOM AREAS	NONE DETECTED	101515BF-1	BF-1: BOYS' LOCKER ROOM.	1100 Sq Ft
XOO		Miscellaneous Material Black Tar Below Floor				Total Amount - 1100 Sq Ft
	20	MIDDLE SCHOOL - LOCKER ROOM AREAS	NONE DETECTED	101515BF-2	BF-2: BOYS' LOCKER ROOM.	1100 Sq Ft
X1A		Miscellaneous Material Pipe/Valve Flange Gaskets				Total Amount - 18 Sq Ft
	6	MIDDLE SCHOOL - BOILER ROOM 0114	ASSUMED			4 Sq Ft
	9	MIDDLE SCHOOL - TUNNELS OFF ROOM 0113	ASSUMED			14 Sq Ft
X1B		Miscellaneous Material 6" x 6" Red Quarry Tile System				Total Amount - 4435 Sq Ft
	22	MIDDLE SCHOOL - GIRLS' LOCKER ROOM SHOWER & RESTROOM	ASSUMED			500 Sq Ft
	37	MIDDLE SCHOOL - BOYS' LOCKER ROOM SHOWER & RESTROOM	ASSUMED			500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	61	MIDDLE SCHOOL - KITCHEN	ASSUMED			1000 Sq Ft
	98	MIDDLE SCHOOL - AUDITORIUM MECHANICAL ROOM NORTH 1207	ASSUMED			50 Sq Ft
	119	MIDDLE SCHOOL - ROOM 1305	ASSUMED			35 Sq Ft
	126	MIDDLE SCHOOL - ROOM 1303	ASSUMED			85 Sq Ft
	154	MIDDLE SCHOOL - ROOM 1405 RESTROOM	ASSUMED			120 Sq Ft
	163	MIDDLE SCHOOL - MAINTENANCE ROOM 1404	ASSUMED			60 Sq Ft
	164	MIDDLE SCHOOL - GIRLS' RESTROOM NEAR ROOM 1404	ASSUMED			400 Sq Ft
	229	MIDDLE SCHOOL - BOYS' RESTROOM BY ROOM 1416	ASSUMED			200 Sq Ft
	230	MIDDLE SCHOOL - ROOM 1412	ASSUMED			85 Sq Ft
	260	MIDDLE SCHOOL - ROOM 2404	ASSUMED			200 Sq Ft
	261	MIDDLE SCHOOL -GIRLS' RESTROOM NEXT TO ROOM 2404	ASSUMED			200 Sq Ft
	269	MIDDLE SCHOOL - ROOM 3404	ASSUMED			200 Sq Ft
	270	MIDDLE SCHOOL - GIRLS' RESTROOM NEAR ROOM 3404	ASSUMED			200 Sq Ft
	284	MIDDLE SCHOOL - ROOM 3415	ASSUMED			200 Sq Ft
	286	MIDDLE SCHOOL - ROOM 3412	ASSUMED			200 Sq Ft
	287	MIDDLE SCHOOL - BOYS' RESTROOM NEAR ROOM 3412	ASSUMED			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X2A	Miscellaneous Material Tectum Wall Panels				Total Amount - 3000 Sq Ft	
	379	SENIOR HIGH - FIELDHOUSE	NSM			3000 Sq Ft



EMSL Analytical, Inc.

3410 Winnetka Avenue North New Hope, MN 55427

Tel/Fax: (763) 449-4922 / (763) 449-4924

<http://www.EMSL.com> / minneapolislab@emsl.com

EMSL Order: 352101409
Customer ID: IFEA50
Customer PO:
Project ID:

Attention: Jennifer Theis
Inst. For Environmental Assessment
9201 West Broadway
Suite 600
Brooklyn Park, MN 55445
Project: 2001-202110015- Highland Park Middle School

Phone: (763) 315-7900
Fax: (763) 315-7920
Received Date: 02/22/2021 4:00 PM
Analysis Date: 02/23/2021
Collected Date:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
022221-BF--1	Room 0106B, Plaster	White		100.0%	None Detected
352101409-0001	Associated with AHU	Non-Fibrous Homogeneous			

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Inherm Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-fragile organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. New Hope, MN NVLAP Lab Code 200019-0; Colorado AL-24478

Initial report from: 02/23/2021 12:06:52



EMSL Analytical, Inc.

3410 Winnetka Avenue North New Hope, MN 55427

Tel/Fax: (763) 449-4922 / (763) 449-4924

<http://www.EMSL.com> / minneapolislab@emsl.com

EMSL Order: 352101409
Customer ID: IFEA50
Customer PO:
Project ID:

Attention: Jennifer Theis
Inst. For Environmental Assessment
9201 West Broadway
Suite 600
Brooklyn Park, MN 55445
Project: 2001-202110015- Highland Park Middle School

Phone: (763) 315-7900
Fax: (763) 315-7920
Received Date: 02/22/2021 4:00 PM
Analysis Date: 02/23/2021
Collected Date:

The samples in this report were submitted to EMSL for analysis by Asbestos Analysis of Bulk materials via EPA/600 (0513) Method using Polarized Light Microscopy. The reference number for these samples is the EMSL Order ID above. Please use this reference number when calling about these samples.

Report Comments:

Sample Receipt Date:	02/22/2021	Sample Receipt Time:	4:00 PM
Analysis Completed Date:	02/23/2021	Analysis Completed Time:	10:27 AM

Analyst(s):

Lynn Scott PLM (1)

Rachel Travis, Laboratory Manager
or other approved signatory

Samples Reviewed and approved by:

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-fragile organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. New Hope, MN NVLAP Lab Code 200019-0, Colorado AL-24478

Initial report from: 02/23/2021 12:06:52

