

2001 Eleanor Avenue, Saint Paul, MN 55116

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|---------------|--------------------------------------|------------|-------------------|----------------------------|-----------------------------------|
| B1A Air Cell Pipe Insulation 1930 Original Building | | | | | | Total Amount - 10 Lin Ft |
| | 14 | 1930 ORIGINAL BUILDING TUNNEL | ASSUMED | | | 10 Lin Ft |
| B2C Millboard Pipe Insulation 1954 Addition | | | | | | Total Amount - 1 Lin Ft |
| | 41 | 1954 ADDITION 2ND FLOOR HALLWAY 2100 | 5 CH | 2001-1501-MN-4, 5 | ROOM 1301 (SINCE REMOVED). | 1 Lin Ft |
| I2D 2' x 2' Acoustical Ceiling Tile Textured w/Revealed Edge (2018) | | | | | | Total Amount - 20000 Sq Ft |
| | 2 | THROUGHOUT BUILDING | NEW | | | 20000 Sq Ft |
| I2E 2' x 2' Acoustical Ceiling Tile Pock Marks w/Pin Holes (2018) | | | | | | Total Amount - 40000 Sq Ft |
| | 3 | THROUGHOUT BUILDING | NEW | | | 40000 Sq Ft |
| K1B Sheet Vinyl Flooring & Adhesive Gray (2018) | | | | | | Total Amount - 2000 Sq Ft |
| | 8 | THROUGHOUT BUILDING RESTROOMS | NEW | | | 2000 Sq Ft |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|---------------|-----------------------------------|---------------|--|--|-----------------------------------|
| K3A Miscellaneous Flooring 2' X 2' Gray Rubber (2018) | | | | | | Total Amount - 30000 Sq Ft |
| | 4 | THROUGHOUT BUILDING | NEW | | | 30000 Sq Ft |
| M0A Plaster 1930 Original Building | | | | | | Total Amount - 15000 Sq Ft |
| | 11 | THROUGHOUT 1930 ORIGINAL BUILDING | NONE DETECTED | 050218-BF-9; 022509-MA-11; 2001-01364-01, 02; 510-H1, H2, H3; 1140-8 | BF-9: HALLWAY BY ROOM 1203. MA-11: 1ST FLOOR HALLWAY. H1: EAST STAIRWELL. H2: SOUTHWEST STAIRWELL. H3: STAIRWELL TO BOILER ROOM. | 15000 Sq Ft |
| M0B Plaster 1939 Addition | | | | | | Total Amount - 15000 Sq Ft |
| | 15 | THROUGHOUT 1939 ADDITION | NONE DETECTED | 022509-MA-24, 26, 27, 28, 29; 518-8 | MA-24: ROOM 2211. MA-26: ROOM 1202. MA-27: ROOM 1209. MA-28: ROOM 0210. MA-29: ROOM 0205. | 15000 Sq Ft |
| M0C Plaster 1954 Addition | | | | | | Total Amount - 20000 Sq Ft |
| | 21 | THROUGHOUT 1954 ADDITION | NONE DETECTED | 022509-MA-25, 32, 33, 34; 518-2, 3; 1140-3, 9 | MA-25: ROOM 1301. MA-32: ROOM 1002. MA-33: WEST STAIRWELL CLOSET. MA-34: 2ND FLOOR BOYS' RESTROOM FAN ROOM. | 20000 Sq Ft |
| N0A Drywall/Joint Compound | | | | | | Total Amount - 10000 Sq Ft |
| | 1 | THROUGHOUT BUILDING | NONE DETECTED | 510-H4; 518-13, 15 | 510-H4: ROOM 1205C. | 10000 Sq Ft |
| N0B Drywall/Joint Compound 1995 Addition | | | | | | Total Amount - 10000 Sq Ft |
| | 45 | THROUGHOUT 1954 ADDITION | NONE DETECTED | 061917BF-13 | BF-13: CORRIDOR 1400. | 10000 Sq Ft |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|---|---------------|---|---------------|-------------|------------------|-----------------------------------|
| Q0C Carpet Adhesive Black, Gray w/Multi-Colored Stripes Carpet Squares (2018) | | | | | | Total Amount - 30000 Sq Ft |
| | 5 | THROUGHOUT BUILDING | NEW | | | 30000 Sq Ft |
| Q0D Carpet Adhesive Black & Gray Carpet Squares | | | | | | Total Amount - 500 Sq Ft |
| | 7 | THROUGHOUT BUILDING ENTRANCES | NEW | | | 500 Sq Ft |
| R0F Baseboard/Mopboard Adhesive 4" Black (2018) | | | | | | Total Amount - 500 Sq Ft |
| | 6 | THROUGHOUT BUILDING | NEW | | | 500 Sq Ft |
| R0G Baseboard/Mopboard Adhesive Black 90 Degree (2018) | | | | | | Total Amount - 50 Sq Ft |
| | 47 | 1954 ADDITION GYMNASIUM | NEW | | | 50 Sq Ft |
| SOA Wood Floor Felt / Vapor Barrier 1930 Original Building | | | | | | Total Amount - 5000 Sq Ft |
| | 23 | THROUGHOUT 1930 ORIGINAL BUILDING 1ST FLOOR | NONE DETECTED | 040518-BF-1 | BF-1: ROOM 1204. | 2500 Sq Ft |
| | 30 | THROUGHOUT 1930 ORIGINAL BUILDING 2ND FLOOR | NONE DETECTED | 040518-BF-2 | BF-2: ROOM 2206. | 2500 Sq Ft |
| SOB Wood Floor Felt / Vapor Barrier 1939 Addition (On-Grade) | | | | | | Total Amount - 1740 Sq Ft |
| | 16 | ROOM 0210A | NONE DETECTED | | | 140 Sq Ft |
| | 17 | ROOM 0210 | NONE DETECTED | | | 860 Sq Ft |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|--|------------------------------------|---------------|---------------------------|------------------|----------------------------------|
| | 18 | ROOM 0206 | NONE DETECTED | | | 220 Sq Ft |
| | 19 | ROOM 0204 | NONE DETECTED | 040518-BF-3 | BF-3: ROOM 0204. | 520 Sq Ft |
| S0BB | Wood Floor Felt / Vapor Barrier 1939 Addition (Elevated) | | | | | Total Amount - 2000 Sq Ft |
| | 27 | THROUGHOUT 1939 ADDITION 1ST FLOOR | NONE DETECTED | 040518-BF-4 | BF-4: ROOM 1209. | 2000 Sq Ft |
| VOA | Sink Undercoating Gray | | | | | Total Amount - 9 Sq Ft |
| | 29 | ROOM 1202 | NONE DETECTED | | | 5 Sq Ft |
| | 48 | 1995 ADDITION NURSE'S OFFICE AREA | NONE DETECTED | 061917-BF-3; 022509-MA-13 | BF-3: ROOM 1401. | 4 Sq Ft |
| XOA | Miscellaneous Material Wood Frame Chalkboard Adhesive (1930) | | | | | Total Amount - 40 Sq Ft |
| | 24 | ROOM 1204 | NONE DETECTED | | | 5 Sq Ft |
| | 32 | ROOM 2205 | NONE DETECTED | 052318-BF-1 | BF-1: ROOM 2205. | 15 Sq Ft |
| | 34 | ROOM 2206 | NONE DETECTED | | | 20 Sq Ft |
| XOB | Miscellaneous Material Wood Frame Chalkboard Adhesive (1939) | | | | | Total Amount - 20 Sq Ft |
| | 36 | ROOM 2202 | ASSUMED | | | 20 Sq Ft |
| XOC | Miscellaneous Material Metal Frame Chalkboard Adhesive (1954) | | | | | Total Amount - 5 Sq Ft |
| | 25 | ROOM 1204 | ASSUMED | | | 5 Sq Ft |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|--|---------------|--------------|----------------------------------|-----------------|---------------------------------|
| X0D | Miscellaneous Material White Material Between Metal Window Panels | | | | | Total Amount - 600 Sq Ft |
| 10 | THROUGHOUT BUILDING | NONE DETECTED | 022509-MA-10 | MA-10: BOILER ROOM. | 600 Sq Ft | |
| X0E | Miscellaneous Material Wood Frame Corkboard Adhesive (1930) | | | | | Total Amount - 340 Sq Ft |
| 26 | ROOM 1205 | NONE DETECTED | | | 140 Sq Ft | |
| 33 | ROOM 2205 | NONE DETECTED | 052318-BF-2 | BF-2: ROOM 2204 (SINCE REMOVED). | 80 Sq Ft | |
| 35 | ROOM 2206 | NONE DETECTED | | | 120 Sq Ft | |
| X0F | Miscellaneous Material Wood Frame Corkboard Adhesive (1939) | | | | | Total Amount - 120 Sq Ft |
| 28 | ROOM 1202 | NONE DETECTED | | | 40 Sq Ft | |
| 37 | ROOM 2202 | NONE DETECTED | 052318-BF-3 | BF-3: ROOM 2202. | 80 Sq Ft | |
| X0G | Miscellaneous Material Metal Frame Corkboard Adhesive (1954) | | | | | Total Amount - 480 Sq Ft |
| 38 | ROOM 1101 | ASSUMED | | | 80 Sq Ft | |
| 39 | ROOM 1102 | ASSUMED | | | 80 Sq Ft | |
| 40 | ROOM 1103 | ASSUMED | | | 80 Sq Ft | |
| 42 | ROOM 2103 | ASSUMED | | | 80 Sq Ft | |
| 43 | ROOM 2104 | ASSUMED | | | 80 Sq Ft | |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|---|--|---------------|-------------|-----------------|----------------------------------|
| | 44 | ROOM 2105 | ASSUMED | | | 80 Sq Ft |
| X0H | Miscellaneous Material Black Wall Coating | | | | | Total Amount - 125 Sq Ft |
| | 12 | COAL STORAGE 0208B | NONE DETECTED | 061917BF-19 | | 125 Sq Ft |
| X0I | Miscellaneous Material Poured Rubber Flooring (2018) | | | | | Total Amount - 5000 Sq Ft |
| | 46 | 1954 ADDITION GYMNASIUM | NEW | | | 5000 Sq Ft |
| X1C | Miscellaneous Material 6" X 6" White Ceramic Wall Tile System (2018) | | | | | Total Amount - 5000 Sq Ft |
| | 9 | THROUGHOUT BUILDING RESTROOMS | NEW | | | 5000 Sq Ft |
| X1D | Miscellaneous Material 3" X 3" Gray Ceramic Floor Tile System | | | | | Total Amount - 240 Sq Ft |
| | 20 | RESTROOM 0209 | NEW | | | 80 Sq Ft |
| | 31 | RESTROOM 2106 | NEW | | | 160 Sq Ft |
| X1E | Miscellaneous Material 2" X 2" Brown Ceramic Floor Tile System | | | | | Total Amount - 35 Sq Ft |
| | 13 | CUSTODIAL RESTROOM 0208B | NEW | | | 35 Sq Ft |
| X1H | Miscellaneous Material 6" X 6" Brownish Red Quarry Tile System | | | | | Total Amount - 120 Sq Ft |
| | 22 | THROUGHOUT 1954 ADDITION STAIRWELLS | ASSUMED | | | 120 Sq Ft |