

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D1A Boiler Gaskets Shiny Total Amount: 5 Sq. Ft.						
	9	MECHANICAL ROOM 1111	NONE DETECTED	091112MV-01	MV-01: ROOM 1111 BOILER #1.	5 Sq. Ft.
D2A Interior Boiler Insulation Refractory Total Amount: 200 Sq. Ft.						
	10	MECHANICAL ROOM 1111	NONE DETECTED	091112MV-02	MV-02: ROOM 1111 BOILER #1.	200 Sq. Ft.
D2B Interior Boiler Insulation Boiler Brick Total Amount: 50 Sq. Ft.						
	11	MECHANICAL ROOM 1111	NONE DETECTED	091112MV-03	MV-03: ROOM 1111 BOILER #1.	50 Sq. Ft.
G1A Sprayed-On Acoustical Finish Texture on Walls Total Amount: 5,000 Sq. Ft.						
	1	THROUGHOUT BUILDING	NONE DETECTED	091112MV-04,05,06,07,08,09,10	MV-04: HALLWAY BY ROOM 1512. MV-05: HALLWAY BY ROOM 1201. MV-06: HALLWAY BY ROOM 1308. MV-07: HALLWAY BY ROOM 1409. MV-08: LOBBY 1000. MV-09: LOUNGE 1201. MV-10: HALLWAY BY ROOM 1402.	5000 Sq. Ft.
I2A 2' x 2' Acoustical Ceiling Tile Grubs & Pin Holes w/Revealed Edge Total Amount: 3,000 Sq. Ft.						
	2	THROUGHOUT BUILDING	NONE DETECTED	091112MV-11	MV-11: HALLWAY BY ROOM 1108.	3000 Sq. Ft.
I3A 2' x 4' Ceiling Tile Grubs & Pin Holes Total Amount: 35,000 Sq. Ft.						
	3	THROUGHOUT BUILDING	NONE DETECTED	091112MV-12	MV-12: ROOM 1101.	35000 Sq. Ft.
I3B 2' x 4' Ceiling Tile Vinyl-Coated Gypsum Total Amount: 100 Sq. Ft.						
	28	ROOM 1216	NSM			100 Sq. Ft.
K2A 12" x 12" Vinyl Floor Tile & Mastic Gray w/Multi-Colored Smears Total Amount: 978 Sq. Ft.						
	13	LOUNGE 1201	NONE DETECTED	091112MV-14	MV-14: LOUNGE 1201.	210 Sq. Ft.
	20	ROOM 1315	NONE DETECTED			580 Sq. Ft.
	22	ROOM 1203 (STAFF LOUNGE)	NONE DETECTED			180 Sq. Ft.
	27	ROOM 1212A	NONE DETECTED			8 Sq. Ft.

Chart C - All Materials List - Hubbs Lifelong Learning (cont.)

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2B 12" x 12" Vinyl Floor Tile & Mastic Green Mottle						Total Amount: 300 Sq. Ft.
	14	HALLWAY OUTSIDE WEST RESTROOMS	NONE DETECTED	091112MV-15	MV-15: HALLWAY BY ROOM 1202B.	60 Sq. Ft.
	16	ROOM 1508	NONE DETECTED			240 Sq. Ft.
K2C 12" x 12" Vinyl Floor Tile & Mastic Beige w/Multi-Colored Smears						Total Amount: 2,000 Sq. Ft.
	24	THROUGHOUT CHILD CARE AREAS	NONE DETECTED	091112MV-16	MV-16: ROOM 1214.	2000 Sq. Ft.
L0A Flexible Duct Connector Black Vinyl						Total Amount: 20 Sq. Ft.
	19	PENTHOUSE MECHANICAL	NSM			20 Sq. Ft.
N0A Drywall/Joint Compound 1993 Addition/Installation						Total Amount: 20,000 Sq. Ft.
	4	THROUGHOUT BUILDING	NONE DETECTED	091112MV-17	MV-17: CONFERENCE ROOM 1005.	20000 Sq. Ft.
P0A Fire Door 1 Hr Rating (Weyerhaeuser)						Total Amount: 30 Sq. Ft.
	18	STAIRS TO PENTHOUSE	NEW			30 Sq. Ft.
P0B Fire Door Metal - 1.5 Hr Rating (Pioneer)						Total Amount: 30 Sq. Ft.
	12	MECHANICAL ROOM 1111	NEW			30 Sq. Ft.
Q0A Carpet Adhesive Blue Berber Carpet						Total Amount: 30,000 Sq. Ft.
	5	THROUGHOUT BUILDING	NONE DETECTED	091112MV-18	MV-18: LOUNGE 1201.	30000 Sq. Ft.
Q0B Carpet Adhesive Blue & Gray Carpet Squares						Total Amount: 2,000 Sq. Ft.
	25	THROUGHOUT CHILD CARE AREAS	NEW			2000 Sq. Ft.
R0A Baseboard/Mopboard Adhesive 4" Gray Baseboard						Total Amount: 1,000 Sq. Ft.
	6	THROUGHOUT BUILDING	NONE DETECTED	091112MV-19	MV-19: ROOM 1402.	1000 Sq. Ft.
R0B Baseboard/Mopboard Adhesive 4" Green Baseboard						Total Amount: 25 Sq. Ft.
	15	HALLWAY OUTSIDE WEST RESTROOMS	NONE DETECTED	091112MV-20	MV-20: HALLWAY BY ROOM 1202B.	10 Sq. Ft.
	17	ROOM 1508	NONE DETECTED			15 Sq. Ft.

Chart C - All Materials List - Hubbs Lifelong Learning (cont.)

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
R0C Baseboard/Mopboard Adhesive 4" Tan Baseboard						Total Amount: 200 Sq. Ft.
	26	THROUGHOUT CHILD CARE AREAS	NONE DETECTED	091112MV-21	MV-21: ROOM 1214.	200 Sq. Ft.
V0A Sink Undercoating Gray						Total Amount: 25 Sq. Ft.
	21	ROOM 1315	NONE DETECTED	091112MV-22	MV-22: ROOM 1315.	5 Sq. Ft.
	23	ROOM 1203 (STAFF LOUNGE)	NONE DETECTED			5 Sq. Ft.
	29	ROOM 1214	NONE DETECTED			5 Sq. Ft.
	30	ROOM 1213	NONE DETECTED			5 Sq. Ft.
	31	ROOM 1210	NONE DETECTED			5 Sq. Ft.
X0A Miscellaneous Material Cream Duct Seam Caulk						Total Amount: 200 Sq. Ft.
	7	THROUGHOUT BUILDING	NONE DETECTED	091112MV-23	MV-23: PENTHOUSE.	200 Sq. Ft.
X0C Miscellaneous Material Gray Duct Caulk						Total Amount: 200 Sq. Ft.
	8	THROUGHOUT BUILDING	NONE DETECTED	091112MV-24	MV-24: PENTHOUSE.	200 Sq. Ft.